

## ATTACHEMENT B



- Milling and resurfacing. Preping of sub-base before resurfacing to obtain proper drainage.
- Remove and dispose of existing asphalt paving. Remove and regrade to achieve proper drainage in the area. Rework base material and add as needed to obtain 6" of base material compacted to 95% density per ASTM. Install 2" of compacted Type D Mix asphalt paving.