

SECTION 01 5000
TEMPORARY FACILITIES AND CONTROLS

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Temporary utilities.
- B. Temporary sanitary facilities.
- C. Waste removal facilities and services.

1.02 RELATED REQUIREMENTS

- A. Section 01 5100 - Temporary Utilities.
- B. Section 01 5500 - Vehicular Access and Parking.

1.03 TEMPORARY UTILITIES - SEE SECTION 01 5100

- A. Owner will provide the following:
 - ~~1. Electrical power and metering, consisting of connection to existing facilities.~~
 - ~~2. Water supply, consisting of connection to existing facilities.~~
- B. Use trigger-operated nozzles for water hoses, to avoid waste of water.

1.04 TEMPORARY SANITARY FACILITIES

- A. Provide and maintain required facilities and enclosures. Provide at time of project mobilization.
- B. Use of existing facilities is not permitted.
- C. Maintain daily in clean and sanitary condition.
- D. At end of construction, return project site to same or better condition as originally found.

1.05 EXTERIOR ENCLOSURES

- A. Contractor may, at Contractor's option provide and supply a mobile storage container for the intended purpose of storing and securing materials and tools. The container may be placed on site, however, the location must be pre-approved by the Owner through the assigned Construction Manager. Failure to secure prior approval may expose Contractor to fines and/or penalties.

1.06 VEHICULAR ACCESS AND PARKING - SEE SECTION 01 5500

- A. Comply with regulations relating to use of streets and sidewalks, access to emergency facilities, and access for emergency vehicles.
- B. Coordinate access and haul routes with governing authorities and Owner.
- C. Provide and maintain access to fire hydrants, free of obstructions.
- D. Provide temporary parking areas to accommodate construction personnel. When site space is not adequate, provide additional off-site parking.

1.07 WASTE REMOVAL

- A. Provide waste removal facilities and services as required to maintain the site in clean and orderly condition.
- B. Provide containers. Remove trash from site periodically.
- C. If materials to be recycled or re-used on the project must be stored on-site, provide suitable non-combustible containers; locate containers holding flammable material outside the structure unless otherwise approved by the authorities having jurisdiction.
- D. Open free-fall chutes are not permitted. Terminate closed chutes into appropriate containers with lids.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION - NOT USED

END OF SECTION

