

TECHNICAL SPECIFICATIONS
FOR
Cayce Utility Phase 1B Project
Metropolitan Development and Housing Agency
Nashville, Tennessee
June 2022

Prepared by:

Kimley-Horn and Associates, Inc.
10 Lea Avenue, Suite 400
Nashville, TN 37210

©2022
Kimley-Horn and Associates, Inc.

GENERAL

Recipients of bidding instruments must consult the Index to determine the full scope of the work involved and to ensure that all pages of the project manual and drawings have been included.

Neither the Owner nor the Owner’s Representative will be responsible for bids submitted that are based on incomplete bidding instruments.

DOCUMENTS

Technical Specifications

	<u>Date</u>
011000 – Summary	March 2022
012200 – Unit Prices	March 2022
012500 – Substitution Procedures	March 2022
012600 – Contract Modification Procedures.....	March 2022
012664 – Weather Delays	March 2022
012900 – Payment Procedures.....	March 2022
013100 – Project Management and Coordination.....	March 2022
013200 – Construction Progress Documentation	March 2022
013300 – Submittal Procedures.....	March 2022
014000 – Quality Requirements.....	March 2022
014200 – References	March 2022
015639 – Temporary Tree and Plant Protection.....	March 2022
017700 – Closeout Procedures.....	March 2022
017839 – Project Record Documents.....	March 2022
330130 – Post-rehabilitation Sanitary Sewer CCTV Inspection.....	March 2022
330140 – Cured-in-place Pipe Lining	March 2022
330151 – Pre-rehabilitation Sanitary Sewer CCTV Inspection.....	March 2022
333520 – Sewer Cleaning for Preparation of Sewer Rehabilitation	March 2022

The following additional Technical Specifications are incorporated by Reference. The referenced specifications are available to download through MDHA or through the agency responsible for the specifications.

Metro Water Services Specifications	<u>Revision Date</u>
Metro Water Services Specifications – MWS Water and Sewer Standard Specifications	05/08/2019

Metro Nashville Public Works Specifications	
02225 – Earthwork for Structures and Pipelines.....	11/13/00
02520 – Cement Concrete Curb, Gutter, and Combined Curb and Gutter	09/06/00
02522 – Cement Concrete Sidewalks, Driveways, and Median Pavement.....	09/06/00
02523 – Detectable Warnings.....	05/07/14
02575 – Pavement Repair Specification.....	08/22/14
02500 – Paving and Resurfacing	02/14/13
02720 – Storm Sewers and Drain Systems.....	N/A

TENNESSEE DEPARTMENT OF TRANSPORTATION (TDOT) STANDARD SPECIFICATIONS, SUPPLEMENTAL SPECIFICAIONS, AND SPECIAL PROVISIONS

	<u>Revision Date</u>
Supplemental Specifications to The Standard Specifications	
Supplemental Specification to Section 100.....	12/15/21
Supplemental Specification to Section 400.....	12/15/21
Supplemental Specification to Section 600.....	12/15/21
Supplemental Specification to Section 700.....	12/15/21
Supplemental Specification to Section 900.....	12/15/21

Project Documents

Cayce Utility Phase 1 Bid Set, by Kimley-Horn and Associates, Inc., dated **March 15, 2022**

Geotechnical Engineering Report, by Terracon Consultants, dated February 6, 2020

CCTV files of Stormwater pipes

The above Standard Specifications, Supplemental Specifications, and Special Provisions revised as noted, are incorporated by reference for bidding and contract purposes. These documents may be obtained from the Department at Suite 700, James K. Polk Bldg., Nashville, Tennessee or viewed on the Department's website at <http://www.tdot.state.tn.us/construction>.

SECTION 011000 - SUMMARY

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Project information.
2. Work covered by Contract Documents.
3. Access to site.
4. Coordination with occupants.
5. Work restrictions.
6. Specification and drawing conventions.
7. Miscellaneous provisions.

B. Related Requirements:

1. Section 015000 "Temporary Facilities and Controls" for limitations and procedures governing temporary use of Owner's facilities.

1.2 PROJECT INFORMATION

A. Project Identification: Cayce Utility Phase 1B

1. Project Location: South 7th Street, Crutcher Street, and Glenview Drive in Nashville, TN 37206.

B. Owner: Metropolitan Development and Housing Agency (MDHA)

1. Owner's Representative: Mike Wegerson and Brad Muckel

C. Engineer: Kimley-Horn and Associates, Inc.

D. Contractor: To be determined.

1.3 WORK COVERED BY CONTRACT DOCUMENTS

A. The Work of Project is defined by the Contract Documents and consists of the following:

1. This project consists of installation of new storm sewer lines, new water lines and new sanitary sewer lines. Associated sanitary and storm structures are included. Removal of old lines is also part of the contract. Roadway backfill, asphalt replacement, curb and gutter replacement and sidewalk replacement will be required as necessary. Refer to construction plans for more detailed information.

B. Type of Contract.

1. Project will be constructed under a single prime contract.

1.4 ACCESS TO SITE

- A. General: Contractor shall have full use of Project site for construction operations during construction period. Contractor's use of Project site is limited only by Owner's right to perform work or to retain other contractors on portions of Project.
- B. Use of Site: Limit use of Project site to areas within the Contract limits of disturbance as indicated on the construction plans. Do not disturb portions of Project site beyond areas in which the Work is indicated.
 1. Limits: Confine construction operations to limits of disturbance. If additional areas are required for staging and storage of materials the contractor shall request that as soon as possible.
 2. Driveways, Walkways and Entrances: Keep driveways and entrances serving premises clear and available to Owner, Owner's employees, and emergency vehicles at all times. Do not use these areas for parking or storage of materials.
 - a. Schedule deliveries to minimize use of driveways and entrances by construction operations.
 - b. Schedule deliveries to minimize space and time requirements for storage of materials and equipment on-site.
- C. Phasing Plan: Refer to the construction plans for general phasing plan and approved road closures at one time. All road and lane closures must be submitted to Metro Public Works and contractor is responsible for obtaining road and lane closure permits.

1.5 COORDINATION WITH OCCUPANTS

- A. Full Owner Occupancy: Owner will occupy site and adjacent building(s) during entire construction period. Cooperate with Owner during construction operations to minimize conflicts and facilitate Owner usage. Perform the Work so as not to interfere with Owner's day-to-day operations. Maintain existing exits unless otherwise indicated.
 1. Maintain access to existing walkways, corridors, and other adjacent occupied or used facilities. Do not close or obstruct walkways, corridors, or other occupied or used facilities without written permission from Owner and approval of authorities having jurisdiction.
 2. Notify Owner not less than 72 hours in advance of activities that will affect Owner's operations.

1.6 WORK RESTRICTIONS

- A. Work Restrictions, General: Comply with restrictions on construction operations.
 1. Comply with limitations on use of public streets and with other requirements of authorities having jurisdiction.

- B. On-Site Work Hours: approved work hours are based on Metro Public Works regulations and conditions of road or lane closure permits.
- C. Existing Utility Interruptions: Do not interrupt utilities serving facilities occupied by Owner or others unless permitted under the following conditions and then only after providing temporary utility services according to requirements indicated:
 - 1. Notify Engineer and Owner not less than 72 hours in advance of proposed utility interruptions.
 - 2. Obtain Owner's written permission before proceeding with utility interruptions.
- D. Noise, Vibration, and Odors: Coordinate operations that may result in high levels of noise and vibration, odors, or other disruption to Owner occupancy with Owner.
 - 1. Notify Owner not less than two days in advance of proposed disruptive operations.

1.7 SPECIFICATION AND DRAWING CONVENTIONS

- A. Specification Content: The Specifications use certain conventions for the style of language and the intended meaning of certain terms, words, and phrases when used in particular situations. These conventions are as follows:
 - 1. Imperative mood and streamlined language are generally used in the Specifications. The words "shall," "shall be," or "shall comply with," depending on the context, are implied where a colon (:) is used within a sentence or phrase.
 - 2. Specification requirements are to be performed by Contractor unless specifically stated otherwise.
 - 3. Any reference to "Architect" in these contract specifications, plans or agreement shall refer to "Engineer."
- B. Division 01 General Requirements: Requirements of Sections in Division 01 apply to the Work of all Sections in the Specifications.
- C. Drawing Coordination: Requirements for materials and products identified on Drawings are described in detail in the Specifications. One or more of the following are used on Drawings to identify materials and products:
 - 1. Terminology: Materials and products are identified by the typical generic terms used in the individual Specifications Sections.
 - 2. Abbreviations: Materials and products are identified by abbreviations published as part of the U.S. National CAD Standard.
 - 3. Keynoting: Materials and products are identified by reference keynotes referencing Specification Section numbers found in this Project Manual.

1.8 MISCELLANEOUS PROVISIONS

END OF SECTION 011000

SECTION 012200 - UNIT PRICES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for unit prices.
- B. Related Requirements:
 - 1. Section 012600 "Contract Modification Procedures" for procedures for submitting and handling Change Orders.

1.2 DEFINITIONS

- A. Unit price is an amount incorporated in the Agreement, applicable during the duration of the Work as a price per unit of measurement for materials, equipment, or services, or a portion of the Work, added to or deducted from the Contract Sum by appropriate modification, if the scope of Work or estimated quantities of Work required by the Contract Documents are increased or decreased.

1.3 PROCEDURES

- A. Unit prices include all necessary material, plus cost for delivery, installation, insurance, applicable taxes, overhead, and profit.
- B. Measurement and Payment: See individual Specification Sections for work that requires establishment of unit prices. Methods of measurement and payment for unit prices are specified in those Sections.
- C. Owner reserves the right to reject Contractor's measurement of work-in-place that involves use of established unit prices and to have this work measured, at Owner's expense, by an independent surveyor acceptable to Contractor.
- D. List of Unit Prices: A schedule of unit prices is included in Part 3. Specification Sections referenced in the schedule contain requirements for materials described under each unit price.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION

3.1 SCHEDULE OF UNIT PRICES

BASE BID				
Note	TDOT Item No.	Item Description	Unit	Quantity
1	105-01	CONSTRUCTION STAKES, LINES, GRADES	LS	1
2	202-02.01	REMOVAL OF PIPE (42" STORM)	L.F.	1073
2	202-02.02	REMOVAL OF PIPE (12" STORM)	L.F.	125
2	202-02.02	REMOVAL OF PIPE (18" STORM)	L.F.	537
2	202-02.21	REMOVAL OF PIPE (6" WATER)	L.F.	1580
2	202-02.21	REMOVAL OF PIPE (8" WATER)	L.F.	46
3	202-03	REMOVAL OF RIGID PAVEMENT, SIDEWALK, ETC.	S.Y.	770
3	202-03.01	REMOVAL OF ASPHALT PAVEMENT FULL DEPTH	S.Y.	5550
4	202-04.01	REMOVAL OF STRUCTURES (STORM)	EA	16
5	202-08.15	REMOVAL OF CURB AND GUTTER	LF	1800
6	203-01.29	ROCK EXCAVATION	C.Y.	100
7	203-02.01	BORROW EXCAVATION (GRADED SOLID ROCK)	TON	150
8	203-05	UNDERCUTTING	C.Y.	100
	209-03.21	FILTER SOCK (12 INCH)	L.F.	292
	209-08.02	TEMPORARY SILT FENCE (WITH BACKING)	L.F.	1350
	209-40.33	CATCH BASIN PROTECTION (TYPE D)	E.A.	22
9	303-01	MINERAL AGGREGATE, TYPE A BASE, GRADING D	TON	2500
	307-01.08	ASPHALT CONCRETE MIX (PG64-22) (BPMB-HM) GRADING B-M2	TON	700
	402-01	BITUMINOUS MATERIAL FOR PRIME COAT (PC)	TON	9
	403-01	BITUMINOUS MATERIAL FOR TACK COAT (TC)	TON	2
10	407-20.05	SAWCUTTING ASPHALT PAVEMENT	L.F.	700
	411-01.10	ACS MIX (PG64-22) GRADING D	TON	550
	415-01.01	COLD PLANING BITUMINOUS PAVEMENT	TON	50
11	607-02.02	15" RCP CLASS III	LF	260
11	607-03.02	18" RCP CLASS III	LF	74

11	607-07.02	24" RCP CLASS III	LF	227
11	607-09.02	36" RCP CLASS III	LF	347
11	607-10.02	54" RCP CLASS III	LF	700
11	607-11.03	60" RCP CLASS III	LF	360
12	611-01.10	MANHOLES, (60" DIAMETER, 6'-12' DEPTH)	EA	2
12	611-01.11	MANHOLES (96" DIAMETER, 12'-16' DEPTH)	EA	2
12	611-01.12	MANHOLES (108" DIAMETER, 13' DEPTH)	EA	1
12	611-42.02	CATCH BASINS, TYPE 42, > 4' - 8' DEPTH	EA	1
12	611-90.01	CATCH BASINS, (SINGLE INLET (METRO NASHVILLE DR-105), 5' - 9' DEPTH)	EA	5
12	611-90.02	CATCH BASINS, (DOUBLE INLET (METRO NASHVILLE DR-110), 5'-9' DEPTH)	EA	3
12	611-90.03	CATCH BASINS TYPE 12, 4'-8' DEPTH - SINGLE	EA	4
12	611-90.04	CATCH BASINS TYPE 12, 8'-12' DEPTH - SINGLE	EA	2
12	611-90.05	CATCH BASINS TYPE 12, 8'-12' DEPTH - DOUBLE	EA	3
12	611-90.06	CATCH BASINS TYPE 12, 12'-16' DEPTH - SINGLE	EA	2
12	611-90.07	CATCH BASINS TYPE 12, 12'-16' DEPTH - DOUBLE	EA	2
20	607-25.02	CIPP PIPE LINING (for 36" pipe)	LF	539
13	701-01.01	CONCRETE SIDEWALK (4")	SF	9000
14	701-02	RESIDENTIAL CONCRETE DRIVEWAY (METRO ST-322)	SF	360
15	701-02.03	CONCRETE CURB RAMP	SF	400
16	702-03	CONCRETE COMBINED CURB AND GUTTER	CY	100
17	712-01.50	MAINTENANCE OF TRAFFIC	LS	1
	713-16.20	SIGNS (REGULATORY SIGNS WITH POST AND FOOTER)	EA	5
	716-02.05	PLASTIC PAVEMENT MARKING (STOP LINE)	LF	250
	716-13.01	SPRAY THERMO PAVEMENT MARKING (60 MIL) (4 IN LINE)	LF	1300
	717-01	MOBILIZATION	LS	1
11	795-03.02	FURNISH AND INSTALL 8" DIP RESTRAINED JOINT WATER LINE	LF	1630
	795-06.04	2 IN PVC WATER LINE	L.F.	100

	795-06.05	RECONNECT TO 6" WATER LINE	EA	1
	795-08.04	RECONNECT TO 8" WATER LINE	EA	2
	795-08.05	6" GATE VALVE ASSEMBLY	EA	2
	795-10.11	8" GATE VALVE ASSEMBLY	EA	4
	795-11.02	REMOVE WATER VALVE	E.A.	8
18	795-12.01	FIRE HYDRANT ASSEMBLY	EA	1
	795-13.01	REMOVE FIRE HYDRANT	E.A.	1
	795-16.22	DI FITTINGS	LB	750
		RECONNECT WATER SERVICE LINES	EA	7
		8" X 6" WATERLINE REDUCER	E.A.	1
		APCO 400 AIR RELEASE VALVE	E.A.	1
	797-05.01	CONNECT TO EXISTING FIRE HYDRANT	EA	1
11	797-05.51	8" DI GRAVITY SEWER PIPE	LF	35
11	797-07.02	8" PVC GRAVITY SEWER PIPE	LF	400
12	797-07.05	48" SANITARY SEWER MANHOLES 4'-6' DEPTH	EA	1
12	797-07.80	48" SANITARY SEWER MANHOLES 10'-12' DEPTH	EA	2
4	797-11.35	REMOVE SEWER STRUCTURES	E.A.	2
3		REMOVE EXISTING SEWER 8IN - 14IN	L.F.	330
		CUT, CAP, AND ABANDON SANITARY SEWER LINE IN PLACE	L.F.	137
	801-01	REPLACE MANHOLE IN PLACE	E.A.	1
	802-05.01	SEEDING (WITH MULCH)	UNIT	5
	920-10.01	TEMPORARY TREE PROTECTION	L.F.	74
19	105-01	CONCRETE TURN DOWN SLAB (0.5' WIDTH)	LF	140

NOTE: Any item, material, equipment, labor, or operation required to complete the work outlined in the Construction Plans that is not listed as a bid item above shall be considered incidental and shall be incorporated into other bid items.

FOOTNOTES	
1	Includes all construction staking and layout necessary for the project. Also includes Metro Water Services required As-built and project close out information.
2	Removal of pipe line items include the excavation to dig down to the pipe and the removal and disposal of the pipes.
3	Includes full depth removal of asphalt or concrete and base stone down to subgrade
4	Removal of structures shall include required excavation, removal and disposal of the structures.
5	Includes full depth removal of existing curb or curb and gutter and base stone down to subgrade.
6	This unit price shall apply to any solid rock excavation that is deemed necessary for installation of utility lines associated with this project. Based on the Geotechnical Report we do not anticipate any large-scale rock formations within the existing roadways. Should we encounter rock that needs to be removed to achieve a depth as indicated on the plans this unit price would apply. Owner and Engineer shall be consulted prior to any rock excavation taking place. Written approval shall be provided before excavation of any solid bedrock.
7	This unit price shall apply when undercutting (203-05) is approved. Borrow Excavation (Graded Solid Rock) will be used to fill back in where poor soils were removed through undercutting. Graded Solid Rock will be used to bring the grade back up to subgrade or bedding grade for utility lines.
8	This unit price shall apply to any excavation below the necessary depth required for pipe bedding or standard excavation required to preform the construction as indicated on the plans. Construction Materials representatives will be on site during excavation and shall be consulted if the contractor believes undercutting is required. This item would consist of additional excavation to remove poor soils and haul off site to an approved and permitted fill site. Owner, Engineer and Material Testing representative shall be consulted prior to any undercutting taking place. Written approval shall be provided before any undercutting occurs.
9	This item shall be used for 8" base stone where full depth asphalt replacement is noted on the plans. All other required stone backfill shall be incidental to pipe installation or other items
10	Includes saw cutting of asphalt and concrete.
11	Pipe installation shall consist of required excavation, bedding material, pipe installation and backfill material up to subgrade. It shall also consist of any trenching, trench boxes or other safety measures required for the installation of the pipe. This item shall also consist of all required testing.
12	Structures shall consist of required excavation, bedding material, structure installation, and backfill material up to subgrade. It shall also consist of any trenching, trench boxes or other safety measures required for the installation of the structure.

13	Concrete sidewalk pay item includes 4" base stone, 4" concrete, expansion and control joints, all prep, labor, materials, formwork, finished associated with the construction of the sidewalk. Refer to Metro Detail No. ST-209 and ST-210 on Sheet C8-02A.
14	Concrete driveway pay items includes 4" base stone, welded wire mesh, concrete, expansion and control joints, all prep, labor, materials, formwork, finished associated with the construction of the sidewalk. Refer to Metro Detail No. ST-322 and ST-323 on Sheet C8-02B.
15	Concrete curb ramp pay item includes 4" base stone, 6" concrete, tactile warning system, expansion and control joints, all prep, labor, materials, formwork, finished associated with the construction of the sidewalk. Refer to Metro Detail No. ST-320, ST-321, ST-329 and ST-330 on Sheet C8-02B and C8-02C.
16	Concrete curb and gutter pay item includes 4" base stone, concrete, expansion and control joints, all prep, labor, materials, formwork, finished associated with the construction of the sidewalk. Refer to Metro Detail No. ST-200 on Sheet C8-02A.
17	Bid item includes all necessary Maintenance of Traffic for the project including but not limited to road closures, lane closures, sidewalk closures, detours, and the lane shifts at Crutcher Street, Glenview Drive, and South 7th Street as shown on Sheet C9-00, C9-01, and C9-02.
18	Fire hydrant assembly shall consist of hydrant, valve, concrete blocks and 6" line from water main. See Metro Detail WDET005 on Sheet C8-01A.
19	See detail on Sheet C8-02C, Sheet C5-03 for locations and cross sections for heights of turn down.
20	Bid item for cured-in-place pipe liner shall include cleaning of pipe before and after pipe lining. It shall also include cleaning of joints and grouting joints as necessary per specifications. Refer to specification sections 33 01 40 and 33 35 20. Also refer to video of pipe provided with bid documents.

END OF SECTION 012200

SECTION 012500 - SUBSTITUTION PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for substitutions.
- B. Related Requirements:
 - 1. Section 016000 "Product Requirements" for requirements for submitting comparable product submittals for products by listed manufacturers.

1.2 DEFINITIONS

- A. Substitutions: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents and proposed by Contractor.

1.3 ACTION SUBMITTALS

- A. Substitution Requests: Submit three copies of each request for consideration. Identify product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
 - 1. Substitution Request Form: Request form shall be provided by the contractor at the beginning of the project for approval by the Engineer and Owner. Once this form is approved, it shall be used for all substitution requests for the duration of the project.
 - 2. Documentation: Show compliance with requirements for substitutions and the following, as applicable:
 - a. Statement indicating why specified product or fabrication or installation cannot be provided, if applicable.
 - b. Coordination information, including a list of changes or revisions needed to other parts of the Work and to construction performed by Owner and separate contractors, that will be necessary to accommodate proposed substitution.
 - c. Detailed comparison of significant qualities of proposed substitution with those of the Work specified. Include annotated copy of applicable Specification Section. Significant qualities may include attributes such as performance, weight, size, durability, visual effect, sustainable design characteristics, warranties, and specific features and requirements indicated. Indicate deviations, if any, from the Work specified.
 - d. Product Data, including drawings and descriptions of products and fabrication and installation procedures.
 - e. Samples, where applicable or requested.
 - f. Certificates and qualification data, where applicable or requested.
 - g. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners.

- h. Material test reports from a qualified testing agency indicating and interpreting test results for compliance with requirements indicated.
 - i. Detailed comparison of Contractor's construction schedule using proposed substitution with products specified for the Work, including effect on the overall Contract Time. If specified product or method of construction cannot be provided within the Contract Time, include letter from manufacturer, on manufacturer's letterhead, stating date of receipt of purchase order, lack of availability, or delays in delivery.
 - j. Cost information, including a proposal of change, if any, in the Contract Sum.
 - k. Contractor's certification that proposed substitution complies with requirements in the Contract Documents except as indicated in substitution request, is compatible with related materials, and is appropriate for applications indicated.
 - l. Contractor's waiver of rights to additional payment or time that may subsequently become necessary because of failure of proposed substitution to produce indicated results.
3. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within seven days of receipt of a request for substitution. Architect will notify Contractor of acceptance or rejection of proposed substitution within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.
 - a. Forms of Acceptance: Change Order, Construction Change Directive, or Architect's Supplemental Instructions for minor changes in the Work.
 - b. Use product specified if Architect does not issue a decision on use of a proposed substitution within time allocated.

1.4 QUALITY ASSURANCE

- A. Compatibility of Substitutions: Investigate and document compatibility of proposed substitution with related products and materials. Engage a qualified testing agency to perform compatibility tests recommended by manufacturers.

PART 2 - PRODUCTS

2.1 SUBSTITUTIONS

- A. Substitutions for Cause: Submit requests for substitution immediately on discovery of need for change, but not later than 15 days prior to time required for preparation and review of related submittals.
 1. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied:
 - a. Requested substitution is consistent with the Contract Documents and will produce indicated results.
 - b. Requested substitution will not adversely affect Contractor's construction schedule.

- c. Requested substitution has received necessary approvals of authorities having jurisdiction.
 - d. Requested substitution is compatible with other portions of the Work.
 - e. Requested substitution has been coordinated with other portions of the Work.
 - f. Requested substitution provides specified warranty.
 - g. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.
- B. Substitutions for Convenience: Architect will consider requests for substitution if received within 90 days after the Notice to Proceed.
1. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied:
 - a. Requested substitution offers Owner a substantial advantage in cost, time, energy conservation, or other considerations, after deducting additional responsibilities Owner must assume. Owner's additional responsibilities may include compensation to Architect for redesign and evaluation services, increased cost of other construction by Owner, and similar considerations.
 - b. Requested substitution does not require extensive revisions to the Contract Documents.
 - c. Requested substitution is consistent with the Contract Documents and will produce indicated results.
 - d. Requested substitution will not adversely affect Contractor's construction schedule.
 - e. Requested substitution has received necessary approvals of authorities having jurisdiction.
 - f. Requested substitution is compatible with other portions of the Work.
 - g. Requested substitution has been coordinated with other portions of the Work.
 - h. Requested substitution provides specified warranty.
 - i. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.

PART 3 - EXECUTION (Not Used)

END OF SECTION 012500

SECTION 012600 - CONTRACT MODIFICATION PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for handling and processing Contract modifications.

1.2 MINOR CHANGES IN THE WORK

- A. Architect will issue supplemental instructions authorizing minor changes in the Work, not involving adjustment to the Contract Sum or the Contract Time, on AIA Document G710, "Architect's Supplemental Instructions."

1.3 PROPOSAL REQUESTS

- A. Owner-Initiated Proposal Requests: Architect will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or the Contract Time. If necessary, the description will include supplemental or revised Drawings and Specifications.
 - 1. Work Change Proposal Requests issued by Architect are not instructions either to stop work in progress or to execute the proposed change.
 - 2. Within time specified in Proposal Request or 20 days, when not otherwise specified after receipt of Proposal Request, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time necessary to execute the change.
 - a. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
 - b. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
 - c. Include costs of labor and supervision directly attributable to the change.
 - d. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
 - e. Quotation Form: Use forms acceptable to Architect.
- B. Contractor-Initiated Work Change Proposals: If latent or changed conditions require modifications to the Contract, Contractor may initiate a claim by submitting a request for a change to Architect.
 - 1. Include a statement outlining reasons for the change and the effect of the change on the Work. Provide a complete description of the proposed change. Indicate the effect of the proposed change on the Contract Sum and the Contract Time.

2. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
3. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
4. Include costs of labor and supervision directly attributable to the change.
5. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
6. Comply with requirements in Section 012500 "Substitution Procedures" if the proposed change requires substitution of one product or system for product or system specified.
7. Work Change Proposal Request Form: Use form acceptable to Architect.

1.4 ADMINISTRATIVE CHANGE ORDERS

- A. Unit-Price Adjustment: See Section 012200 "Unit Prices" for administrative procedures for preparation of Change Order Proposal for adjusting the Contract Sum to reflect measured scope of unit-price work.

1.5 CHANGE ORDER PROCEDURES

- A. On Owner's approval of a Work Changes Proposal Request, Architect will issue a Change Order for signatures of Owner and Contractor on AIA Document G701.

1.6 CONSTRUCTION CHANGE DIRECTIVE

- A. Construction Change Directive: Architect may issue a Construction Change Directive on AIA Document G714. Construction Change Directive instructs Contractor to proceed with a change in the Work, for subsequent inclusion in a Change Order.
 1. Construction Change Directive contains a complete description of change in the Work. It also designates method to be followed to determine change in the Contract Sum or the Contract Time.
- B. Documentation: Maintain detailed records on a time and material basis of work required by the Construction Change Directive.
 1. After completion of change, submit an itemized account and supporting data necessary to substantiate cost and time adjustments to the Contract.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012600

SECTION 012664 – WEATHER DELAYS

PART 1 - GENERAL

1.1 EXTENSIONS OF CONTRACT TIME

- A. If the basis exists for an extension of time in accordance with Article 8.3 of the General Conditions, an extension of time on the basis of weather may be granted only for the number of Weather Delay Days in excess of the number of days listed as the Standard Baseline for that month.
- B. Weather Delay Days are defined as days of Adverse Weather (see 1.3 A, below) exceeding the Standard Baseline (see 1.2 B, below) of Adverse Weather Days.

1.2 STANDARD BASELINE FOR AVERAGE CLIMATIC RANGE

- A. The Owner has reviewed weather data available from the National Oceanic and Atmospheric Administration (NOAA) and determined a Standard Baseline of average climatic range for the State of Tennessee
- B. Standard Baseline is defined as the normal and anticipatable number of calendar days for each month during which construction activity exposed to weather conditions is expected to be prevented and suspended by cause of Adverse Weather. The Contractor’s schedule shall include this Standard Baseline in all weather dependent activities. Suspension of construction activity for the number of days each month as listed in the Standard Baseline is included in the Contractor’s schedule and is not eligible for extension of Contract Time.
- C. Standard Baseline is as follows:

JAN	FEB	MAR	APR	MAY	JUNE	JULY	AUG	SEPT	OCT	NOV	DEC
12	11	8	7	7	6	7	5	4	5	6	11

1.3 ADVERSE WEATHER AND WEATHER DELAY DAYS

- A. An Adverse Weather Day may be counted if Adverse Weather prevents fifty percent (50%) or more of the Contractor's scheduled critical path construction activity on the Project for that day, including a weekend day or holiday. Adverse Weather must actually cause a delay to the completion of the Project. The delay must be beyond the control and without the fault or negligence of the Contractor.
 - 1. Adverse Weather is defined as the occurrence of one or more of the following conditions within a Twenty-four (24) hour day that prevents construction activity exposed to weather conditions or access to the site:
 - a. Precipitation (rain, snow, or Ice) in excess of one-tenth inch (0.10”) liquid measure;
 - b. Temperatures that do not rise above 32 degrees F by 10:00a.m.

- c. Temperatures which do not rise above that specified for the day's construction activity by 10:00a.m., if any is specified
- d. Sustained wind in excess of twenty-five (25) m.p.h.
- e. Standing snow in excess of one inch (1.00")
- 2. Adverse Weather may include, if appropriate, "dry-out" or "mud" days:
 - a. Resulting from precipitation days that occur beyond the Standard Baseline;
 - b. Only if there is a hindrance to site access or sitework and Contractor has taken all reasonable accommodations to avoid such hindrance; and,
 - c. At a rate no greater than one (1) make-up day for each day or consecutive days of precipitation beyond the Standard Baseline that total one inch (1.00") or more, liquid measure, unless specifically recommended otherwise by the Designer.
 - d. Contractor shall take into account that certain construction activities are more affected by Adverse Weather and seasonal conditions than other activities, and that "dry-out" or "mud" days are not eligible to be counted as a Adverse Weather Day until the Standard Baseline is exceeded. Hence, Contractor should allow for an appropriate number of additional days associated with the Standard Baseline days in which such applicable construction activities are expected to be prevented and suspended.

1.4 DOCUMENTATION AND SUBMITTALS

- A. Submit to the Architect and Owner within twenty-four (24) hours of occurrence daily jobsite work logs showing which and to what extent critical path construction activities have been affected by adverse weather. In addition, if the Contractor fails to contact the Owner's representative within twenty-four (24) hours the day will not be considered an adverse weather day. Monthly Weather Day Summary Reports shall be compiled and submitted with the monthly reports. Both the daily jobsite work log and the Weather Day Summary Report shall describe the construction activity on the critical path that was affected by the Adverse Weather and the respective measurement of precipitation, temperature, or wind causing the Adverse Weather. Additionally, the Weather Day Summary Report shall calculate the claimable Weather Delay Days by subtracting the number of Standard Baseline days for the respective month as shown in section 1.2.C from the number of approved Adverse Weather Days in that month.
 - B. Submit actual weather data to support claim for time extension obtained from nearest NOAA weather station or other independently verified source approved by Designer at beginning of project.
 - C. Use Standard Baseline data provided in this Section when documenting Weather Delay Days due to weather in excess of the average climatic range.
 - D. Organize claim and its documentation to facilitate evaluation on a basis of calendar month periods, and submit to the Architect and the Owner in accordance with the procedures for Claims established in Article 15 of the General Conditions, and the applicable general requirements.
 - E. If an extension of the Contract Time is appropriate, such extension shall be made in accordance with the provisions of Article 7 of the General Conditions, and the applicable requirements.
- END OF SECTION 012600

SECTION 012900 - PAYMENT PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements necessary to prepare and process Applications for Payment.
- B. Related Requirements:
 - 1. Section 012200 "Unit Prices" for administrative requirements governing the use of unit prices.
 - 2. Section 012600 "Contract Modification Procedures" for administrative procedures for handling changes to the Contract.
 - 3. Section 013200 "Construction Progress Documentation" for administrative requirements governing the preparation and submittal of the Contractor's construction schedule.

1.2 SCHEDULE OF VALUES

- A. Coordination: Coordinate preparation of the schedule of values with preparation of Contractor's construction schedule.
 - 1. Coordinate line items in the schedule of values with other required administrative forms and schedules, including the following:
 - a. Application for Payment forms with continuation sheets.
 - b. Submittal schedule.
 - c. Items required to be indicated as separate activities in Contractor's construction schedule.
 - 2. Submit the schedule of values to Architect at earliest possible date but no later than seven days before the date scheduled for submittal of initial Applications for Payment.
- B. Format and Content: Use Project Manual table of contents as a guide to establish line items for the schedule of values. Provide at least one line item for each Specification Section.
 - 1. Identification: Include the following Project identification on the schedule of values:
 - a. Project name and location.
 - b. Name of Architect.
 - c. Architect's project number.
 - d. Contractor's name and address.
 - e. Date of submittal.
 - 2. Arrange schedule of values consistent with format of AIA Document G703 or EJCDC Document C-620.

3. Retain option in first subparagraph below where Contractor's ongoing activities related to Project closeout will be a line item subject to Application for Payment approval.
4. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Coordinate with Project Manual table of contents. Provide multiple line items for principal subcontract amounts in excess of five percent of the Contract Sum.
5. Round amounts to nearest whole dollar; total shall equal the Contract Sum.
6. Provide a separate line item in the schedule of values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.
7. Provide separate line items in the schedule of values for initial cost of materials, for each subsequent stage of completion, and for total installed value of that part of the Work.
8. Allowances: Provide a separate line item in the schedule of values for each allowance. Show line-item value of unit-cost allowances, as a product of the unit cost, multiplied by measured quantity. Use information indicated in the Contract Documents to determine quantities.
9. Each item in the schedule of values and Applications for Payment shall be complete. Include total cost and proportionate share of general overhead and profit for each item.
 - a. Temporary facilities and other major cost items that are not direct cost of actual work-in-place may be shown either as separate line items in the schedule of values or distributed as general overhead expense, at Contractor's option.
10. Schedule Updating: Update and resubmit the schedule of values before the next Applications for Payment when Change Orders or Construction Change Directives result in a change in the Contract Sum.

1.3 APPLICATIONS FOR PAYMENT

- A. Each Application for Payment shall be consistent with previous applications and payments as certified by Architect and paid for by Owner.
 1. Initial Application for Payment, Application for Payment at time of Substantial Completion, and final Application for Payment involve additional requirements.
- B. Payment Application Times: The date for each progress payment is indicated in the Agreement between Owner and Contractor. The period of construction work covered by each Application for Payment is the period indicated in the Agreement.
- C. Payment Application Times: Submit Application for Payment to Architect by the 10th of the month. The period covered by each Application for Payment is one month, ending on the last day of the previous month.
- D. Application for Payment Forms: Use AIA Document G702 and AIA Document G703 as form for Applications for Payment.
- E. Application Preparation: Complete every entry on form. Notarize and execute by a person authorized to sign legal documents on behalf of Contractor. Architect will return incomplete applications without action.

1. Entries shall match data on the schedule of values and Contractor's construction schedule. Use updated schedules if revisions were made.
 2. Include amounts of Change Orders and Construction Change Directives issued before last day of construction period covered by application.
- F. Transmittal: Submit three signed and notarized original copies of each Application for Payment to Architect by a method ensuring receipt. One copy shall include waivers of lien and similar attachments if required.
1. Transmit each copy with a transmittal form listing attachments and recording appropriate information about application.
- G. Waivers of Mechanic's Lien: With each Application for Payment, submit waivers of mechanic's lien from entities lawfully entitled to file a mechanic's lien arising out of the Contract and related to the Work covered by the payment.
1. Submit partial waivers on each item for amount requested in previous application, after deduction for retainage, on each item.
 2. When an application shows completion of an item, submit conditional final or full waivers.
 3. Owner reserves the right to designate which entities involved in the Work must submit waivers.
 4. Waiver Forms: Submit executed waivers of lien on forms acceptable to Owner.
- H. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:
1. List of subcontractors.
 2. Schedule of values.
 3. Contractor's construction schedule (preliminary if not final).
 4. Schedule of unit prices.
 5. Submittal schedule (preliminary if not final).
 6. List of Contractor's staff assignments.
 7. List of Contractor's principal consultants.
 8. Copies of building permits.
 9. Copies of authorizations and licenses from authorities having jurisdiction for performance of the Work.
 10. Initial progress report.
 11. Report of preconstruction conference.
 12. Certificates of insurance and insurance policies.
- I. Application for Payment at Substantial Completion: After Architect issues the Certificate of Substantial Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.
1. Include documentation supporting claim that the Work is substantially complete and a statement showing an accounting of changes to the Contract Sum.
 2. This application shall reflect Certificates of Partial Substantial Completion issued previously for Owner occupancy of designated portions of the Work.

- J. Final Payment Application: After completing Project closeout requirements, submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:
1. Evidence of completion of Project closeout requirements.
 2. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
 3. Updated final statement, accounting for final changes to the Contract Sum.
 4. AIA Document G706-1994, "Contractor's Affidavit of Payment of Debts and Claims."
 5. AIA Document G706A-1994, "Contractor's Affidavit of Release of Liens."
 6. AIA Document G707-1994, "Consent of Surety to Final Payment."
 7. Evidence that claims have been settled.
 8. Final meter readings for utilities, a measured record of stored fuel, and similar data as of date of Substantial Completion or when Owner took possession of and assumed responsibility for corresponding elements of the Work.
 9. Final liquidated damages settlement statement.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 012900

SECTION 013100 - PROJECT MANAGEMENT AND COORDINATION

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative provisions for coordinating construction operations on Project including, but not limited to, the following:
 - 1. Coordination drawings.
 - 2. Requests for Information (RFIs).
 - 3. Project Web site.
 - 4. Project meetings.
- B. Related Requirements:

1.2 DEFINITIONS

- A. RFI: Request from Owner, Architect, or Contractor seeking information required by or clarifications of the Contract Documents.

1.3 INFORMATIONAL SUBMITTALS

- A. Subcontract List: Prepare a written summary identifying individuals or firms proposed for each portion of the Work, including those who are to furnish products or equipment fabricated to a special design. Include the following information in tabular form:
 - 1. Name, address, and telephone number of entity performing subcontract or supplying products.
 - 2. Number and title of related Specification Section(s) covered by subcontract.
 - 3. Drawing number and detail references, as appropriate, covered by subcontract.

1.4 GENERAL COORDINATION PROCEDURES

- A. Coordination: Coordinate construction operations included in different Sections of the Specifications to ensure efficient and orderly installation of each part of the Work. Coordinate construction operations, included in different Sections, that depend on each other for proper installation, connection, and operation.
 - 1. Schedule construction operations in sequence required to obtain the best results where installation of one part of the Work depends on installation of other components, before or after its own installation.
 - 2. Coordinate installation of different components to ensure maximum performance and accessibility for required maintenance, service, and repair.
 - 3. Make adequate provisions to accommodate items scheduled for later installation.

- B. Prepare memoranda for distribution to each party involved, outlining special procedures required for coordination. Include such items as required notices, reports, and list of attendees at meetings.
 - 1. Prepare similar memoranda for Owner and separate contractors if coordination of their Work is required.
- C. Administrative Procedures: Coordinate scheduling and timing of required administrative procedures with other construction activities to avoid conflicts and to ensure orderly progress of the Work. Such administrative activities include, but are not limited to, the following:
 - 1. Preparation of Contractor's construction schedule.
 - 2. Preparation of the schedule of values.
 - 3. Installation and removal of temporary facilities and controls.
 - 4. Delivery and processing of submittals.
 - 5. Progress meetings.
 - 6. Preinstallation conferences.
 - 7. Project closeout activities.
 - 8. Startup and adjustment of systems.

1.5 REQUESTS FOR INFORMATION (RFIs)

- A. General: Immediately on discovery of the need for additional information or interpretation of the Contract Documents, Contractor shall prepare and submit an RFI in the form specified.
 - 1. Architect will return RFIs submitted to Architect by other entities controlled by Contractor with no response.
 - 2. Coordinate and submit RFIs in a prompt manner so as to avoid delays in Contractor's work or work of subcontractors.
- B. Content of the RFI: Include a detailed, legible description of item needing information or interpretation and the following:
 - 1. Project name.
 - 2. Project number.
 - 3. Date.
 - 4. Name of Contractor.
 - 5. Name of Architect.
 - 6. RFI number, numbered sequentially.
 - 7. RFI subject.
 - 8. Specification Section number and title and related paragraphs, as appropriate.
 - 9. Drawing number and detail references, as appropriate.
 - 10. Field dimensions and conditions, as appropriate.
 - 11. Contractor's suggested resolution. If Contractor's solution(s) impacts the Contract Time or the Contract Sum, Contractor shall state impact in the RFI.
 - 12. Contractor's signature.
 - 13. Attachments: Include sketches, descriptions, measurements, photos, Product Data, Shop Drawings, coordination drawings, and other information necessary to fully describe items needing interpretation.

- C. RFI Forms: AIA Document G716 or Software-generated form with substantially the same content as indicated above, acceptable to Architect.
- D. Architect's Action: Architect will review each RFI, determine action required, and respond. Allow seven working days for Architect's response for each RFI. RFIs received by Architect after 1:00 p.m. local time will be considered as received the following working day.
1. The following RFIs will be returned without action:
 - a. Requests for approval of submittals.
 - b. Requests for approval of substitutions.
 - c. Requests for coordination information already indicated in the Contract Documents.
 - d. Requests for adjustments in the Contract Time or the Contract Sum.
 - e. Requests for interpretation of Architect's actions on submittals.
 - f. Incomplete RFIs or inaccurately prepared RFIs.
 2. Architect's action may include a request for additional information, in which case Architect's time for response will date from time of receipt of additional information.
 3. Architect's action on RFIs that may result in a change to the Contract Time or the Contract Sum may be eligible for Contractor to submit Change Proposal according to Section 012600 "Contract Modification Procedures."
 - a. If Contractor believes the RFI response warrants change in the Contract Time or the Contract Sum, notify Architect in writing within 10 days of receipt of the RFI response.
- E. RFI Log: Prepare, maintain, and submit a tabular log of RFIs organized by the RFI number. Submit log monthly. Include the following:
1. Project name.
 2. Name and address of Contractor.
 3. Name and address of Architect.
 4. RFI number including RFIs that were dropped and not submitted.
 5. RFI description.
 6. Date the RFI was submitted.
 7. Date Architect's response was received.
- F. On receipt of Architect's action, update the RFI log and immediately distribute the RFI response to affected parties. Review response and notify Architect within seven days if Contractor disagrees with response.
1. Identification of related Minor Change in the Work, Construction Change Directive, and Proposal Request, as appropriate.
 2. Identification of related Field Order, Work Change Directive, and Proposal Request, as appropriate.

1.6 PROJECT MEETINGS

- A. General: Schedule and conduct meetings and conferences at Project site unless otherwise indicated.
1. Attendees: Inform participants and others involved, and individuals whose presence is required, of date and time of each meeting. Notify Owner and Architect of scheduled meeting dates and times.
 2. Agenda: Prepare the meeting agenda. Distribute the agenda to all invited attendees.
 3. Minutes: Entity responsible for conducting meeting will record significant discussions and agreements achieved. Distribute the meeting minutes to everyone concerned, including Owner, and Architect, within seven days of the meeting.
- B. Preconstruction Conference: Architect will schedule and conduct a preconstruction conference before starting construction, at a time convenient to Owner and Architect, but no later than 15 days after execution of the Agreement.
1. Attendees: Authorized representatives of Owner, Architect, and their consultants; Contractor and its superintendent; major subcontractors; suppliers; and other concerned parties shall attend the conference. Participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work.
 2. Agenda: Discuss items of significance that could affect progress, including the following:
 - a. Tentative construction schedule.
 - b. Phasing.
 - c. Critical work sequencing and long-lead items.
 - d. Designation of key personnel and their duties.
 - e. Procedures for processing field decisions and Change Orders.
 - f. Procedures for RFIs.
 - g. Procedures for testing and inspecting.
 - h. Procedures for processing Applications for Payment.
 - i. Distribution of the Contract Documents.
 - j. Submittal procedures.
 - k. Preparation of record documents.
 - l. Use of the premises.
 - m. Work restrictions.
 - n. Working hours.
 - o. Owner's occupancy requirements.
 - p. Responsibility for temporary facilities and controls.
 - q. Procedures for disruptions and shutdowns.
 - r. Construction waste management and recycling.
 - s. Parking availability.
 - t. Office, work, and storage areas.
 - u. Equipment deliveries and priorities.
 - v. First aid.
 - w. Security.
 - x. Progress cleaning.
 3. Minutes: Entity responsible for conducting meeting will record and distribute meeting minutes.

- C. Progress Meetings: Conduct biweekly intervals.
1. Attendees: In addition to representatives of Owner and Architect, each contractor, subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the meeting shall be familiar with Project and authorized to conclude matters relating to the Work.
 2. Agenda: Review and correct or approve minutes of previous progress meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.
 - a. Contractor's Construction Schedule: Review progress since the last meeting. Determine whether each activity is on time, ahead of schedule, or behind schedule, in relation to Contractor's construction schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.
 - 1) Review schedule for next period.
 - b. Review present and future needs of each entity present, including the following:
 - 1) Interface requirements.
 - 2) Sequence of operations.
 - 3) Status of submittals.
 - 4) Deliveries.
 - 5) Off-site fabrication.
 - 6) Access.
 - 7) Site utilization.
 - 8) Temporary facilities and controls.
 - 9) Progress cleaning.
 - 10) Quality and work standards.
 - 11) Status of correction of deficient items.
 - 12) Field observations.
 - 13) Status of RFIs.
 - 14) Status of proposal requests.
 - 15) Pending changes.
 - 16) Status of Change Orders.
 - 17) Pending claims and disputes.
 - 18) Documentation of information for payment requests.
 3. Minutes: Entity responsible for conducting the meeting will record and distribute the meeting minutes to each party present and to parties requiring information.
 - a. Schedule Updating: Revise Contractor's construction schedule after each progress meeting where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with the report of each meeting.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 013100

SECTION 013200 - CONSTRUCTION PROGRESS DOCUMENTATION

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for documenting the progress of construction during performance of the Work, including the following:
 - 1. Contractor's construction schedule.
 - 2. Construction schedule updating reports.
 - 3. Daily construction reports.
 - 4. Site condition reports.
- B. Related Requirements:

1.2 DEFINITIONS

- A. Activity: A discrete part of a project that can be identified for planning, scheduling, monitoring, and controlling the construction project. Activities included in a construction schedule consume time and resources.
 - 1. Critical Activity: An activity on the critical path that must start and finish on the planned early start and finish times.
 - 2. Predecessor Activity: An activity that precedes another activity in the network.
 - 3. Successor Activity: An activity that follows another activity in the network.
- B. CPM: Critical path method, which is a method of planning and scheduling a construction project where activities are arranged based on activity relationships. Network calculations determine when activities can be performed and the critical path of Project.
- C. Critical Path: The longest connected chain of interdependent activities through the network schedule that establishes the minimum overall Project duration and contains no float.
- D. Float: The measure of leeway in starting and completing an activity.
 - 1. Float time is not for the exclusive use or benefit of either Owner or Contractor, but is a jointly owned, expiring Project resource available to both parties as needed to meet schedule milestones and Contract completion date.

1.3 INFORMATIONAL SUBMITTALS

- A. Format for Submittals: Submit required submittals in the following format:
 - 1. Working electronic copy of schedule file, where indicated.
 - 2. PDF electronic file.

- B. Startup Network Diagram: Of size required to display entire network for entire construction period. Show logic ties for activities.
- C. Contractor's Construction Schedule: Initial schedule, of size required to display entire schedule for entire construction period.
 - 1. Submit a working electronic copy of schedule, using software indicated, and labeled to comply with requirements for submittals. Include type of schedule (initial or updated) and date on label.
- D. Construction Schedule Updating Reports: Submit with Applications for Payment.
- E. Daily Construction Reports: Contractor to keep in their possession and submit any daily work report upon request from the Architect or Owner.
- F. Site Condition Reports: Submit at time of discovery of differing conditions.

1.4 COORDINATION

- A. Coordinate Contractor's construction schedule with the schedule of values, schedule, progress reports, payment requests, and other required schedules and reports.
 - 1. Secure time commitments for performing critical elements of the Work from entities involved.
 - 2. Coordinate each construction activity in the network with other activities and schedule them in proper sequence.

PART 2 - PRODUCTS

2.1 CONTRACTOR'S CONSTRUCTION SCHEDULE, GENERAL

- A. Time Frame: Extend schedule from date established for the Notice to Proceed to date of final completion.
 - 1. Contract completion date shall not be changed by submission of a schedule that shows an early completion date, unless specifically authorized by Change Order.
- B. Activities: Treat each story or separate area as a separate numbered activity for each main element of the Work. Comply with the following:
 - 1. Activity Duration: Define activities so no activity is longer than 20 days, unless specifically allowed by Architect.
 - 2. Procurement Activities: Include procurement process activities for the following long lead items and major items, requiring a cycle of more than 60 days, as separate activities in schedule. Procurement cycle activities include, but are not limited to, submittals, approvals, purchasing, fabrication, and delivery.

3. Submittal Review Time: Include review and resubmittal times indicated in Section 013300 "Submittal Procedures" in schedule. Coordinate submittal review times in Contractor's construction schedule with submittal schedule.
 4. Startup and Testing Time: Include no fewer than 15 days for startup and testing.
 5. Substantial Completion: Indicate completion in advance of date established for Substantial Completion and allow time for Architect's administrative procedures necessary for certification of Substantial Completion.
 6. Punch List and Final Completion: Include not more than 30 days for completion of punch list items and final completion.
- C. Constraints: Include constraints and work restrictions indicated in the Contract Documents and as follows in schedule and show how the sequence of the Work is affected.
1. Phasing: Arrange list of activities on schedule by phase.
 2. Work by Owner: Include a separate activity for each portion of the Work performed by Owner.
 3. Work Restrictions: Show the effect of the following items on the schedule:
 - a. Coordination with existing construction.
 - b. Limitations of continued occupancies.
 - c. Uninterruptible services.
 - d. Partial occupancy before Substantial Completion.
 - e. Use of premises restrictions.
 - f. Provisions for future construction.
 - g. Seasonal variations.
 - h. Environmental control.
 4. Work Stages: Indicate important stages of construction for each major portion of the Work.
- D. Milestones: Include milestones indicated in the Contract Documents in schedule, including, but not limited to, the Notice to Proceed, Substantial Completion, and final completion.
- E. Upcoming Work Summary: Prepare summary report indicating activities scheduled to occur or commence prior to submittal of next schedule update. Summarize the following issues:
1. Unresolved issues.
 2. Unanswered Requests for Information.
 3. Rejected or unreturned submittals.
 4. Notations on returned submittals.
 5. Pending modifications affecting the Work and Contract Time.
- F. Recovery Schedule: When periodic update indicates the Work is 14 or more calendar days behind the current approved schedule, submit a separate recovery schedule indicating means by which Contractor intends to regain compliance with the schedule.
- G. Computer Scheduling Software: Prepare schedules using current version of a program that has been developed specifically to manage construction schedules.
1. Use Microsoft Project, Primavera, Prolog, or other approved software operating system.

2.2 CONTRACTOR'S CONSTRUCTION SCHEDULE (CPM SCHEDULE)

- A. General: Prepare network diagrams using AON (activity-on-node) format.
- B. Startup Network Diagram: Submit diagram within 14 days of date established for the Notice of Award. Outline significant construction activities for the first 90 days of construction. Include skeleton diagram for the remainder of the Work and a cash requirement prediction based on indicated activities.
- C. CPM Schedule: Prepare Contractor's construction schedule using a time-scaled CPM network analysis diagram for the Work.
 - 1. Develop network diagram in sufficient time to submit CPM schedule so it can be accepted for use no later than 60 days after date established for the Notice of Award.
 - a. Failure to include any work item required for performance of this Contract shall not excuse Contractor from completing all work within applicable completion dates, regardless of Architect's approval of the schedule.
 - 2. Establish procedures for monitoring and updating CPM schedule and for reporting progress. Coordinate procedures with progress meeting and payment request dates.
 - 3. Use "one workday" as the unit of time for individual activities. Indicate nonworking days and holidays incorporated into the schedule in order to coordinate with the Contract Time.
- D. CPM Schedule Preparation: Prepare a list of all activities required to complete the Work. Using the startup network diagram, prepare a skeleton network to identify probable critical paths.
 - 1. Activities: Indicate the estimated time duration, sequence requirements, and relationship of each activity in relation to other activities. Include estimated time frames for the following activities:
 - a. Preparation and processing of submittals.
 - b. Mobilization and demobilization.
 - c. Purchase of materials.
 - d. Delivery.
 - e. Fabrication.
 - f. Utility interruptions.
 - g. Installation.
 - h. Work by Owner that may affect or be affected by Contractor's activities.
 - i. Testing.
 - j. Punch list and final completion.
 - k. Activities occurring following final completion.
 - 2. Critical Path Activities: Identify critical path activities, including those for interim completion dates. Scheduled start and completion dates shall be consistent with Contract milestone dates.
 - 3. Processing: Process data to produce output data on a computer-drawn, time-scaled network. Revise data, reorganize activity sequences, and reproduce as often as necessary to produce the CPM schedule within the limitations of the Contract Time.

4. Format: Mark the critical path. Locate the critical path near center of network; locate paths with most float near the edges.
 - a. Subnetworks on separate sheets are permissible for activities clearly off the critical path.
- E. Contract Modifications: For each proposed contract modification and concurrent with its submission, prepare a time-impact analysis using a network fragment to demonstrate the effect of the proposed change on the overall project schedule.
- F. Initial Issue of Schedule: Prepare initial network diagram from a sorted activity list indicating straight "early start-total float." Identify critical activities. Prepare tabulated reports showing the following:
 1. Contractor or subcontractor and the Work or activity.
 2. Description of activity.
 3. Main events of activity.
 4. Immediate preceding and succeeding activities.
 5. Early and late start dates.
 6. Early and late finish dates.
 7. Activity duration in workdays.
 8. Total float or slack time.
 9. Average size of workforce.
 10. Dollar value of activity (coordinated with the schedule of values).
- G. Schedule Updating: Concurrent with making revisions to schedule, prepare tabulated reports showing the following:
 1. Identification of activities that have changed.
 2. Changes in early and late start dates.
 3. Changes in early and late finish dates.
 4. Changes in activity durations in workdays.
 5. Changes in the critical path.
 6. Changes in total float or slack time.
 7. Changes in the Contract Time.

2.3 REPORTS

- A. Daily Construction Reports: Prepare a daily construction report recording the following information concerning events at Project site:
 1. List of subcontractors at Project site.
 2. List of separate contractors at Project site.
 3. Approximate count of personnel at Project site.
 4. Equipment at Project site.
 5. Material deliveries.
 6. High and low temperatures and general weather conditions, including presence of rain or snow.
 7. Accidents.
 8. Meetings and significant decisions.

9. Unusual events.
 10. Stoppages, delays, shortages, and losses.
 11. Meter readings and similar recordings.
 12. Emergency procedures.
 13. Orders and requests of authorities having jurisdiction.
 14. Change Orders received and implemented.
 15. Construction Change Directives received and implemented.
 16. Services connected and disconnected.
 17. Equipment or system tests and startups.
 18. Partial completions and occupancies.
 19. Substantial Completions authorized.
- B. Site Condition Reports: Immediately on discovery of a difference between site conditions and the Contract Documents, prepare and submit a detailed report. Submit with a Request for Information. Include a detailed description of the differing conditions, together with recommendations for changing the Contract Documents.

PART 3 - EXECUTION

3.1 CONTRACTOR'S CONSTRUCTION SCHEDULE

- A. Contractor's Construction Schedule Updating: At monthly intervals, update schedule to reflect actual construction progress and activities. Issue schedule at least two days before the next scheduled progress meeting.
1. Revise schedule immediately after each meeting or other activity where revisions have been recognized or made. Issue updated schedule concurrently with the report of each such meeting.
 2. Include a report with updated schedule that indicates every change, including, but not limited to, changes in logic, durations, actual starts and finishes, and activity durations.
 3. As the Work progresses, indicate final completion percentage for each activity.
- B. Distribution: Distribute copies of approved schedule to Architect, Owner, separate contractors, testing and inspecting agencies, and other parties identified by Contractor with a need-to-know schedule responsibility.
1. Post copies in Project meeting rooms and temporary field offices.
 2. When revisions are made, distribute updated schedules to the same parties and post in the same locations. Delete parties from distribution when they have completed their assigned portion of the Work and are no longer involved in performance of construction activities.

END OF SECTION 013200

SECTION 013300 - SUBMITTAL PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes requirements for the submittal schedule and administrative and procedural requirements for submitting Shop Drawings, Product Data, Samples, and other submittals.
- B. Related Requirements:
 - 1. Section 013200 "Construction Progress Documentation" for submitting schedules and reports, including Contractor's construction schedule.
 - 2. Section 017839 "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.

1.2 DEFINITIONS

- A. Action Submittals: Written and graphic information and physical samples that require Architect's responsive action.
- B. Informational Submittals: Written and graphic information and physical samples that do not require Architect's responsive action. Submittals may be rejected for not complying with requirements.

1.3 ACTION SUBMITTALS

- A. Submittal Schedule: Submit a schedule of submittals, arranged in chronological order by dates required by construction schedule. Include time required for review, ordering, manufacturing, fabrication, and delivery when establishing dates. Include additional time required for making corrections or revisions to submittals noted by Architect and additional time for handling and reviewing submittals required by those corrections.

1.4 SUBMITTAL ADMINISTRATIVE REQUIREMENTS

- A. Architect's Digital Data Files: Electronic copies of digital data files of the Contract Drawings will be provided by Architect for Contractor's use in preparing submittals.
 - 1. Architect will furnish Contractor one set of digital data drawing files of the Contract Drawings for use in preparing Shop Drawings and Project record drawings.
 - a. Architect makes no representations as to the accuracy or completeness of digital data drawing files as they relate to the Contract Drawings.
 - b. Contractor shall execute a data licensing agreement in the form of Agreement form acceptable to Owner and Architect.

- B. Coordination: Coordinate preparation and processing of submittals with performance of construction activities.
1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.
 2. Coordinate transmittal of different types of submittals for related parts of the Work so processing will not be delayed because of need to review submittals concurrently for coordination.
 - a. Architect reserves the right to withhold action on a submittal requiring coordination with other submittals until related submittals are received.
- C. Processing Time: Allow time for submittal review, including time for resubmittals, as follows. Time for review shall commence on Architect's receipt of submittal. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing, including resubmittals.
1. Initial Review: Allow 7 days for initial review of each submittal. Allow additional time if coordination with subsequent submittals is required. Architect will advise Contractor when a submittal being processed must be delayed for coordination.
 2. Intermediate Review: If intermediate submittal is necessary, process it in same manner as initial submittal.
 3. Resubmittal Review: Allow 7 days for review of each resubmittal.
- D. Electronic Submittals: Identify and incorporate information in each electronic submittal file as follows:
1. Assemble complete submittal package into a single indexed file incorporating submittal requirements of a single Specification Section and transmittal form with links enabling navigation to each item.
 2. Name file with submittal number or other unique identifier, including revision identifier.
 - a. File name shall use project identifier and Specification Section number followed by a decimal point and then a sequential number (e.g., LNHS-061000.01). Resubmittals shall include an alphabetic suffix after another decimal point (e.g., LNHS-061000.01.A).
 3. Provide means for insertion to permanently record Contractor's review and approval markings and action taken by Architect.
 4. Transmittal Form for Electronic Submittals: Use electronic form acceptable to Owner, containing the following information:
 - a. Project name.
 - b. Date.
 - c. Name and address of Architect.
 - d. Name of Construction Manager.
 - e. Name of Contractor.
 - f. Name of firm or entity that prepared submittal.
 - g. Names of subcontractor, manufacturer, and supplier.
 - h. Category and type of submittal.
 - i. Submittal purpose and description.

- j. Specification Section number and title.
 - k. Specification paragraph number or drawing designation and generic name for each of multiple items.
 - l. Drawing number and detail references, as appropriate.
 - m. Location(s) where product is to be installed, as appropriate.
 - n. Related physical samples submitted directly.
 - o. Indication of full or partial submittal.
 - p. Transmittal number.
 - q. Submittal and transmittal distribution record.
 - r. Other necessary identification.
 - s. Remarks.
- E. Options: Identify options requiring selection by Architect.
- F. Deviations: Identify deviations from the Contract Documents on submittals.
- G. Resubmittals: Make resubmittals in same form and number of copies as initial submittal.
- 1. Note date and content of previous submittal.
 - 2. Note date and content of revision in label or title block and clearly indicate extent of revision.
 - 3. Resubmit submittals until they are marked with approval notation from Architect's action stamp.
- H. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, authorities having jurisdiction, and others as necessary for performance of construction activities. Show distribution on transmittal forms.
- I. Use for Construction: Retain complete copies of submittals on Project site. Use only final action submittals that are marked with approval notation from Architect's action stamp.

PART 2 - PRODUCTS

2.1 SUBMITTAL PROCEDURES

- A. General Submittal Procedure Requirements:
- 1. Submit electronic submittals via email as PDF electronic files.
 - a. Architect will return annotated file. Annotate and retain one copy of file as an electronic Project record document file.
 - 2. Certificates and Certifications Submittals: Provide a statement that includes signature of entity responsible for preparing certification. Certificates and certifications shall be signed by an officer or other individual authorized to sign documents on behalf of that entity.
 - a. Provide a digital signature with digital certificate on electronically-submitted certificates and certifications where indicated.

- b. Provide a notarized statement on original paper copy certificates and certifications where indicated.
- B. Product Data: Collect information into a single submittal for each element of construction and type of product or equipment.
 1. If information must be specially prepared for submittal because standard published data are not suitable for use, submit as Shop Drawings, not as Product Data.
 2. Mark each copy of each submittal to show which products and options are applicable.
 3. Include the following information, as applicable:
 - a. Manufacturer's catalog cuts.
 - b. Manufacturer's product specifications.
 - c. Standard color charts.
 - d. Statement of compliance with specified referenced standards.
 - e. Testing by recognized testing agency.
 - f. Application of testing agency labels and seals.
 - g. Notation of coordination requirements.
 - h. Availability and delivery time information.
 4. For equipment, include the following in addition to the above, as applicable:
 - a. Wiring diagrams showing factory-installed wiring.
 - b. Printed performance curves.
 - c. Operational range diagrams.
 - d. Clearances required to other construction, if not indicated on accompanying Shop Drawings.
 5. Submit Product Data before or concurrent with Samples.
 6. Submit Product Data in the following format:
 - a. PDF electronic file.
- C. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data.
 1. Preparation: Fully illustrate requirements in the Contract Documents. Include the following information, as applicable:
 - a. Identification of products.
 - b. Schedules.
 - c. Compliance with specified standards.
 - d. Notation of coordination requirements.
 - e. Notation of dimensions established by field measurement.
 - f. Relationship and attachment to adjoining construction clearly indicated.
 - g. Seal and signature of professional engineer if specified.
 2. Submit Shop Drawings in the following format:
 - a. PDF electronic file.

- D. Product Schedule: As required in individual Specification Sections, prepare a written summary indicating types of products required for the Work and their intended location. Include the following information in tabular form:
 - 1. Submit product schedule in the following format:
 - a. PDF electronic file.
- E. Contractor's Construction Schedule: Comply with requirements specified in Section 013200 "Construction Progress Documentation."
- F. Application for Payment and Schedule of Values: Comply with requirements specified in Section 012900 "Payment Procedures."
- G. Test and Inspection Reports and Schedule of Tests and Inspections Submittals: Comply with requirements specified in Section 014000 "Quality Requirements."
- H. Closeout Submittals and Maintenance Material Submittals: Comply with requirements specified in Section 017700 "Closeout Procedures."
- I. Qualification Data: Prepare written information that demonstrates capabilities and experience of firm or person. Include lists of completed projects with project names and addresses, contact information of architects and owners, and other information specified.
- J. Manufacturer Certificates: Submit written statements on manufacturer's letterhead certifying that manufacturer complies with requirements in the Contract Documents. Include evidence of manufacturing experience where required.
- K. Product Certificates: Submit written statements on manufacturer's letterhead certifying that product complies with requirements in the Contract Documents.
- L. Material Certificates: Submit written statements on manufacturer's letterhead certifying that material complies with requirements in the Contract Documents.
- M. Material Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting test results of material for compliance with requirements in the Contract Documents.
- N. Product Test Reports: Submit written reports indicating that current product produced by manufacturer complies with requirements in the Contract Documents. Base reports on evaluation of tests performed by manufacturer and witnessed by a qualified testing agency, or on comprehensive tests performed by a qualified testing agency.
- O. Research Reports: Submit written evidence, from a model code organization acceptable to authorities having jurisdiction, that product complies with building code in effect for Project.
- P. Schedule of Tests and Inspections: Comply with requirements specified in Section 014000 "Quality Requirements."

- Q. Preconstruction Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of tests performed before installation of product, for compliance with performance requirements in the Contract Documents.
- R. Compatibility Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of compatibility tests performed before installation of product. Include written recommendations for primers and substrate preparation needed for adhesion.
- S. Field Test Reports: Submit written reports indicating and interpreting results of field tests performed either during installation of product or after product is installed in its final location, for compliance with requirements in the Contract Documents.
- T. Design Data: Prepare and submit written and graphic information, including, but not limited to, performance and design criteria, list of applicable codes and regulations, and calculations. Include list of assumptions and other performance and design criteria and a summary of loads. Include load diagrams if applicable. Provide name and version of software, if any, used for calculations. Include page numbers.

PART 3 - EXECUTION

3.1 CONTRACTOR'S REVIEW

- A. Action and Informational Submittals: Review each submittal and check for coordination with other Work of the Contract and for compliance with the Contract Documents. Note corrections and field dimensions. Mark with approval stamp before submitting to Architect.
- B. Project Closeout and Maintenance Material Submittals: See requirements in Section 017700 "Closeout Procedures."
- C. Approval Stamp: Stamp each submittal with a uniform, approval stamp. Include Project name and location, submittal number, Specification Section title and number, name of reviewer, date of Contractor's approval, and statement certifying that submittal has been reviewed, checked, and approved for compliance with the Contract Documents.

3.2 ARCHITECT'S ACTION

- A. General: Architect will not review submittals that do not bear Contractor's approval stamp and will return them without action.
- B. Action Submittals: Architect will review each submittal, make marks to indicate corrections or revisions required, and return it. Architect will stamp each submittal with an action stamp and will mark stamp appropriately to indicate action.
- C. Informational Submittals: Architect will review each submittal and will not return it or will return it if it does not comply with requirements. Architect will forward each submittal to appropriate party.

- D. Incomplete submittals are unacceptable, will be considered nonresponsive, and will be returned for resubmittal without review.
- E. Submittals not required by the Contract Documents may not be reviewed and may be discarded.

END OF SECTION 013300

SECTION 014000 - QUALITY REQUIREMENTS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for quality assurance and quality control.
- B. Testing and inspecting services are required to verify compliance with requirements specified or indicated. These services do not relieve Contractor of responsibility for compliance with the Contract Document requirements.
 - 1. Specified tests, inspections, and related actions do not limit Contractor's other quality-assurance and -control procedures that facilitate compliance with the Contract Document requirements.
 - 2. Requirements for Contractor to provide quality-assurance and -control services required by Architect, Owner, or authorities having jurisdiction are not limited by provisions of this Section.
 - 3. Specific test and inspection requirements are not specified in this Section.

1.2 DEFINITIONS

- A. Quality-Assurance Services: Activities, actions, and procedures performed before and during execution of the Work to guard against defects and deficiencies and substantiate that proposed construction will comply with requirements.
- B. Quality-Control Services: Tests, inspections, procedures, and related actions during and after execution of the Work to evaluate that actual products incorporated into the Work and completed construction comply with requirements. Services do not include contract enforcement activities performed by the Construction Materials Testing Company (to be hired by the Owner).
- C. Preconstruction Testing: Tests and inspections performed specifically for Project before products and materials are incorporated into the Work, to verify performance or compliance with specified criteria.
- D. Product Testing: Tests and inspections that are performed by an NRTL, an NVLAP, or a testing agency qualified to conduct product testing and acceptable to authorities having jurisdiction, to establish product performance and compliance with specified requirements.
- E. Source Quality-Control Testing: Tests and inspections that are performed at the source, e.g., plant, mill, factory, or shop.
- F. Field Quality-Control Testing: Tests and inspections that are performed on-site for installation of the Work and for completed Work.

- G. Testing Agency: An entity engaged to perform specific tests, inspections, or both. Testing laboratory shall mean the same as testing agency.
- H. Installer/Applicator/Erector: Contractor or another entity engaged by Contractor as an employee, Subcontractor, or Sub-subcontractor, to perform a particular construction operation, including installation, erection, application, and similar operations.
 - 1. Use of trade-specific terminology in referring to a trade or entity does not require that certain construction activities be performed by accredited or unionized individuals, or that requirements specified apply exclusively to specific trade(s).
- I. Experienced: When used with an entity or individual, "experienced" means having successfully completed a minimum of ten previous projects similar in nature, size, and extent to this Project; being familiar with special requirements indicated; and having complied with requirements of authorities having jurisdiction.

1.3 CONFLICTING REQUIREMENTS

- A. Referenced Standards: If compliance with two or more standards is specified and the standards establish different or conflicting requirements for minimum quantities or quality levels, comply with the most stringent requirement. Refer conflicting requirements that are different, but apparently equal, to Architect for a decision before proceeding.
- B. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified shall be the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of requirements. Refer uncertainties to Architect for a decision before proceeding.

1.4 INFORMATIONAL SUBMITTALS

- A. Contractor's Statement of Responsibility: When required by authorities having jurisdiction, submit copy of written statement of responsibility sent to authorities having jurisdiction before starting work on the following systems:
- B. Testing Agency Qualifications: For testing agencies specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include proof of qualifications in the form of a recent report on the inspection of the testing agency by a recognized authority.

1.5 REPORTS AND DOCUMENTS

- A. Test and Inspection Reports: Prepare and submit certified written reports specified in other Sections. Include the following:
 - 1. Date of issue.
 - 2. Project title and number.
 - 3. Name, address, and telephone number of testing agency.

4. Dates and locations of samples and tests or inspections.
5. Names of individuals making tests and inspections.
6. Description of the Work and test and inspection method.
7. Identification of product and Specification Section.
8. Complete test or inspection data.
9. Test and inspection results and an interpretation of test results.
10. Record of temperature and weather conditions at time of sample taking and testing and inspecting.
11. Comments or professional opinion on whether tested or inspected Work complies with the Contract Document requirements.
12. Name and signature of laboratory inspector.
13. Recommendations on retesting and reinspecting.

B. **Manufacturer's Field Reports:** Prepare written information documenting tests and inspections specified in other Sections. Include the following:

1. Name, address, and telephone number of representative making report.
2. Statement on condition of substrates and their acceptability for installation of product.
3. Summary of installation procedures being followed, whether they comply with requirements and, if not, what corrective action was taken.
4. Results of operational and other tests and a statement of whether observed performance complies with requirements.
5. Other required items indicated in individual Specification Sections.

C. **Permits, Licenses, and Certificates:** For Owner's records, submit copies of permits, licenses, certifications, inspection reports, releases, jurisdictional settlements, notices, receipts for fee payments, judgments, correspondence, records, and similar documents, established for compliance with standards and regulations bearing on performance of the Work.

1.6 QUALITY ASSURANCE

A. **General:** Qualifications paragraphs in this article establish the minimum qualification levels required; individual Specification Sections specify additional requirements.

B. **Manufacturer Qualifications:** A firm experienced in manufacturing products or systems similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.

C. **Fabricator Qualifications:** A firm experienced in producing products similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.

D. **Installer Qualifications:** A firm or individual experienced in installing, erecting, or assembling work similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction with a record of successful in-service performance.

E. **Professional Engineer Qualifications:** A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed

for installations of the system, assembly, or product that are similar in material, design, and extent to those indicated for this Project.

- F. Specialists: Certain Specification Sections require that specific construction activities shall be performed by entities who are recognized experts in those operations. Specialists shall satisfy qualification requirements indicated and shall be engaged for the activities indicated.
1. Requirements of authorities having jurisdiction shall supersede requirements for specialists.
- G. Testing Agency Qualifications: An NRTL, an NVLAP, or an independent agency with the experience and capability to conduct testing and inspecting indicated, as documented according to ASTM E 329; and with additional qualifications specified in individual Sections; and, where required by authorities having jurisdiction, that is acceptable to authorities.
1. NRTL: A nationally recognized testing laboratory according to 29 CFR 1910.7.
 2. NVLAP: A testing agency accredited according to NIST's National Voluntary Laboratory Accreditation Program.
- H. Manufacturer's Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to observe and inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.
- I. Preconstruction Testing: Where testing agency is indicated to perform preconstruction testing for compliance with specified requirements for performance and test methods, comply with the following:
1. Contractor responsibilities include the following:
 - a. Provide test specimens representative of proposed products and construction.
 - b. Submit specimens in a timely manner with sufficient time for testing and analyzing results to prevent delaying the Work.
 - c. When testing is complete, remove test specimens, assemblies, do not reuse products on Project.
 2. Testing Agency Responsibilities: Submit a certified written report of each test, inspection, and similar quality-assurance service to Architect, with copy to Contractor. Interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from the Contract Documents.

1.7 QUALITY CONTROL

- A. Owner Responsibilities: Where quality-control services are indicated as Owner's responsibility, Owner will engage a qualified testing agency to perform these services.
1. Owner will furnish Contractor with names, addresses, and telephone numbers of testing agencies engaged and a description of types of testing and inspecting they are engaged to perform.

2. Costs for retesting and reinspecting construction that replaces or is necessitated by work that failed to comply with the Contract Documents will be charged to Contractor.
- B. Contractor Responsibilities: Tests and inspections not explicitly assigned to Owner are Contractor's responsibility. Perform additional quality-control activities required to verify that the Work complies with requirements, whether specified or not.
1. Where services are indicated as Contractor's responsibility, engage a qualified testing agency to perform these quality-control services.
 - a. Contractor shall not employ same entity engaged by Owner, unless agreed to in writing by Owner.
 2. Notify testing agencies at least 24 hours in advance of time when Work that requires testing or inspecting will be performed.
 3. Where quality-control services are indicated as Contractor's responsibility, submit a certified written report, in duplicate, of each quality-control service.
 4. Testing and inspecting requested by Contractor and not required by the Contract Documents are Contractor's responsibility.
 5. Submit additional copies of each written report directly to authorities having jurisdiction, when they so direct.
- C. Manufacturer's Field Services: Where indicated, engage a manufacturer's representative to observe and inspect the Work. Manufacturer's representative's services include examination of substrates and conditions, verification of materials, inspection of completed portions of the Work, and submittal of written reports.
- D. Retesting/Reinspecting: Regardless of whether original tests or inspections were Contractor's responsibility, provide quality-control services, including retesting and reinspecting, for construction that replaced Work that failed to comply with the Contract Documents.
- E. Testing Agency Responsibilities: Cooperate with Architect and Contractor in performance of duties. Provide qualified personnel to perform required tests and inspections.
1. Notify Architect and Contractor promptly of irregularities or deficiencies observed in the Work during performance of its services.
 2. Determine the location from which test samples will be taken and in which in-situ tests are conducted.
 3. Conduct and interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from requirements.
 4. Submit a certified written report, in duplicate, of each test, inspection, and similar quality-control service through Contractor.
 5. Do not release, revoke, alter, or increase the Contract Document requirements or approve or accept any portion of the Work.
 6. Do not perform any duties of Contractor.
- F. Associated Services: Cooperate with agencies performing required tests, inspections, and similar quality-control services, and provide reasonable auxiliary services as requested. Notify agency sufficiently in advance of operations to permit assignment of personnel. Provide the following:

1. Access to the Work.
 2. Incidental labor and facilities necessary to facilitate tests and inspections.
 3. Adequate quantities of representative samples of materials that require testing and inspecting. Assist agency in obtaining samples.
 4. Facilities for storage and field curing of test samples.
 5. Delivery of samples to testing agencies.
 6. Preliminary design mix proposed for use for material mixes that require control by testing agency.
 7. Security and protection for samples and for testing and inspecting equipment at Project site.
- G. Coordination: Coordinate sequence of activities to accommodate required quality-assurance and -control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspecting.
1. Schedule times for tests, inspections, obtaining samples, and similar activities.

PART 2 - EXECUTION

2.1 TEST AND INSPECTION LOG

- A. Test and Inspection Log: Prepare a record of tests and inspections. Include the following:
1. Date test or inspection was conducted.
 2. Description of the Work tested or inspected.
 3. Date test or inspection results were transmitted to Architect.
 4. Identification of testing agency or special inspector conducting test or inspection.
- B. Maintain log at Project site. Post changes and revisions as they occur. Provide access to test and inspection log for Architect's reference during normal working hours.

2.2 REPAIR AND PROTECTION

- A. General: On completion of testing, inspecting, sample taking, and similar services, repair damaged construction and restore substrates and finishes.
1. Provide materials and comply with installation requirements specified in other Specification Sections or matching existing substrates and finishes. Restore patched areas and extend restoration into adjoining areas with durable seams that are as invisible as possible. Comply with the Contract Document requirements for cutting and patching in Section 017300 "Execution."
- B. Protect construction exposed by or for quality-control service activities.
- C. Repair and protection are Contractor's responsibility, regardless of the assignment of responsibility for quality-control services.

END OF SECTION 014000

SECTION 014200 - REFERENCES

PART 1 - GENERAL

1.1 DEFINITIONS

- A. General: Basic Contract definitions are included in the Conditions of the Contract.
- B. "Approved": When used to convey Architect's action on Contractor's submittals, applications, and requests, "approved" is limited to Architect's duties and responsibilities as stated in the Conditions of the Contract.
- C. "Directed": A command or instruction by Architect. Other terms including "requested," "authorized," "selected," "required," and "permitted" have the same meaning as "directed."
- D. "Indicated": Requirements expressed by graphic representations or in written form on Drawings, in Specifications, and in other Contract Documents. Other terms including "shown," "noted," "scheduled," and "specified" have the same meaning as "indicated."
- E. "Regulations": Laws, ordinances, statutes, and lawful orders issued by authorities having jurisdiction, and rules, conventions, and agreements within the construction industry that control performance of the Work.
- F. "Furnish": Supply and deliver to Project site, ready for unloading, unpacking, assembly, installation, and similar operations.
- G. "Install": Unload, temporarily store, unpack, assemble, erect, place, anchor, apply, work to dimension, finish, cure, protect, clean, and similar operations at Project site.
- H. "Provide": Furnish and install, complete and ready for the intended use.
- I. "Project Site": Space available for performing construction activities. The extent of Project site is shown on Drawings and may or may not be identical with the description of the land on which Project is to be built.

1.2 INDUSTRY STANDARDS

- A. Applicability of Standards: Unless the Contract Documents include more stringent requirements, applicable construction industry standards have the same force and effect as if bound or copied directly into the Contract Documents to the extent referenced. Such standards are made a part of the Contract Documents by reference.
- B. Publication Dates: Comply with standards in effect as of date of the Contract Documents unless otherwise indicated.
- C. Copies of Standards: Each entity engaged in construction on Project should be familiar with industry standards applicable to its construction activity. Copies of applicable standards are not bound with the Contract Documents.

1. Where copies of standards are needed to perform a required construction activity, obtain copies directly from publication source.

1.3 ABBREVIATIONS AND ACRONYMS

- A. Industry Organizations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities indicated in Gale's "Encyclopedia of Associations: National Organizations of the U.S." or in Columbia Books' "National Trade & Professional Associations of the United States."
- B. Industry Organizations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list.
 1. AABC - Associated Air Balance Council; www.aabc.com.
 2. AAMA - American Architectural Manufacturers Association; www.aamanet.org.
 3. AAPFCO - Association of American Plant Food Control Officials; www.aapfco.org.
 4. AASHTO - American Association of State Highway and Transportation Officials; www.transportation.org.
 5. AATCC - American Association of Textile Chemists and Colorists; www.aatcc.org.
 6. ABMA - American Bearing Manufacturers Association; www.americanbearings.org.
 7. ACI - American Concrete Institute; (Formerly: ACI International); www.concrete.org.
 8. ACPA - American Concrete Pipe Association; www.concrete-pipe.org.
 9. AEIC - Association of Edison Illuminating Companies, Inc. (The); www.aeic.org.
 10. AF&PA - American Forest & Paper Association; www.afandpa.org.
 11. AGA - American Gas Association; www.aga.org.
 12. AHAM - Association of Home Appliance Manufacturers; www.aham.org.
 13. AHRI - Air-Conditioning, Heating, and Refrigeration Institute (The); www.ahrinet.org.
 14. AI - Asphalt Institute; www.asphaltinstitute.org.
 15. AIA - American Institute of Architects (The); www.aia.org.
 16. AISC - American Institute of Steel Construction; www.aisc.org.
 17. AISI - American Iron and Steel Institute; www.steel.org.
 18. AITC - American Institute of Timber Construction; www.aitc-glulam.org.
 19. AMCA - Air Movement and Control Association International, Inc.; www.amca.org.
 20. ANSI - American National Standards Institute; www.ansi.org.
 21. AOSA - Association of Official Seed Analysts, Inc.; www.aosaseed.com.
 22. APA - APA - The Engineered Wood Association; www.apawood.org.
 23. APA - Architectural Precast Association; www.archprecast.org.
 24. API - American Petroleum Institute; www.api.org.
 25. ARI - Air-Conditioning & Refrigeration Institute; (See AHRI).
 26. ARI - American Refrigeration Institute; (See AHRI).
 27. ARMA - Asphalt Roofing Manufacturers Association; www.asphaltroofing.org.
 28. ASCE - American Society of Civil Engineers; www.asce.org.
 29. ASCE/SEI - American Society of Civil Engineers/Structural Engineering Institute; (See ASCE).
 30. ASHRAE - American Society of Heating, Refrigerating and Air-Conditioning Engineers; www.ashrae.org.
 31. ASME - ASME International; (American Society of Mechanical Engineers); www.asme.org.
 32. ASSE - American Society of Safety Engineers (The); www.asse.org.
 33. ASSE - American Society of Sanitary Engineering; www.asse-plumbing.org.

34. ASTM - ASTM International; (American Society for Testing and Materials International); www.astm.org.
35. ATIS - Alliance for Telecommunications Industry Solutions; www.atis.org.
36. AWEA - American Wind Energy Association; www.awea.org.
37. AWI - Architectural Woodwork Institute; www.awinet.org.
38. AWMAC - Architectural Woodwork Manufacturers Association of Canada; www.awmac.com.
39. AWPA - American Wood Protection Association; (Formerly: American Wood-Preservers' Association); www.awpa.com.
40. AWS - American Welding Society; www.aws.org.
41. AWWA - American Water Works Association; www.awwa.org.
42. BHMA - Builders Hardware Manufacturers Association; www.buildershardware.com.
43. BIA - Brick Industry Association (The); www.gobrick.com.
44. BICSI - BICSI, Inc.; www.bicsi.org.
45. BIFMA - BIFMA International; (Business and Institutional Furniture Manufacturer's Association); www.bifma.com.
46. BISSC - Baking Industry Sanitation Standards Committee; www.bissc.org.
47. BWF - Badminton World Federation; (Formerly: International Badminton Federation); www.bwfbadminton.org.
48. CDA - Copper Development Association; www.copper.org.
49. CEA - Canadian Electricity Association; www.electricity.ca.
50. CEA - Consumer Electronics Association; www.ce.org.
51. CFFA - Chemical Fabrics & Film Association, Inc.; www.chemicalfabricsandfilm.com.
52. CFSEI - Cold-Formed Steel Engineers Institute; www.cfsei.org.
53. CGA - Compressed Gas Association; www.cganet.com.
54. CIMA - Cellulose Insulation Manufacturers Association; www.cellulose.org.
55. CISCA - Ceilings & Interior Systems Construction Association; www.cisca.org.
56. CISPI - Cast Iron Soil Pipe Institute; www.cispi.org.
57. CLFMI - Chain Link Fence Manufacturers Institute; www.chainlinkinfo.org.
58. CPA - Composite Panel Association; www.pbmdf.com.
59. CRI - Carpet and Rug Institute (The); www.carpet-rug.org.
60. CRRC - Cool Roof Rating Council; www.coolroofs.org.
61. CRSI - Concrete Reinforcing Steel Institute; www.crsi.org.
62. CSA - Canadian Standards Association; www.csa.ca.
63. CSA - CSA International; (Formerly: IAS - International Approval Services); www.csa-international.org.
64. CSI - Construction Specifications Institute (The); www.csinet.org.
65. CSSB - Cedar Shake & Shingle Bureau; www.cedarbureau.org.
66. CTI - Cooling Technology Institute; (Formerly: Cooling Tower Institute); www.cti.org.
67. CWC - Composite Wood Council; (See CPA).
68. DASMA - Door and Access Systems Manufacturers Association; www.dasma.com.
69. DHI - Door and Hardware Institute; www.dhi.org.
70. ECA - Electronic Components Association; (See ECIA).
71. ECAMA - Electronic Components Assemblies & Materials Association; (See ECIA).
72. ECIA ? Electronic Components Industry Association; www.eciaonline.org.
73. EIA - Electronic Industries Alliance; (See TIA).
74. EIMA - EIFS Industry Members Association; www.eima.com.
75. EJMA - Expansion Joint Manufacturers Association, Inc.; www.ejma.org.
76. ESD - ESD Association; (Electrostatic Discharge Association); www.esda.org.
77. ESTA - Entertainment Services and Technology Association; (See PLASA).
78. EVO - Efficiency Valuation Organization; www.evo-world.org.

79. FIBA - Fédration Internationale de Basketball; (The International Basketball Federation); www.fiba.com.
80. FIVB - Fédration Internationale de Volleyball; (The International Volleyball Federation); www.fivb.org.
81. FM Approvals - FM Approvals LLC; www.fmglobal.com.
82. FM Global - FM Global; (Formerly: FMG - FM Global); www.fmglobal.com.
83. FRSA - Florida Roofing, Sheet Metal & Air Conditioning Contractors Association, Inc.; www.floridarroof.com.
84. FSA - Fluid Sealing Association; www.fluidsealing.com.
85. FSC - Forest Stewardship Council U.S.; www.fscus.org.
86. GA - Gypsum Association; www.gypsum.org.
87. GANA - Glass Association of North America; www.glasswebsite.com.
88. GS - Green Seal; www.greenseal.org.
89. HI - Hydraulic Institute; www.pumps.org.
90. HI/GAMA - Hydronics Institute/Gas Appliance Manufacturers Association; (See AHRI).
91. HMMA - Hollow Metal Manufacturers Association; (See NAAMM).
92. HPVA - Hardwood Plywood & Veneer Association; www.hpva.org.
93. HPW - H. P. White Laboratory, Inc.; www.hpwhite.com.
94. IAPSC - International Association of Professional Security Consultants; www.iapsc.org.
95. IAS - International Accreditation Service; www.iasonline.org.
96. IAS - International Approval Services; (See CSA).
97. ICBO - International Conference of Building Officials; (See ICC).
98. ICC - International Code Council; www.iccsafe.org.
99. ICEA - Insulated Cable Engineers Association, Inc.; www.icea.net.
100. ICPA - International Cast Polymer Alliance; www.icpa-hq.org.
101. ICRI - International Concrete Repair Institute, Inc.; www.icri.org.
102. IEC - International Electrotechnical Commission; www.iec.ch.
103. IEEE - Institute of Electrical and Electronics Engineers, Inc. (The); www.ieee.org.
104. IES - Illuminating Engineering Society; (Formerly: Illuminating Engineering Society of North America); www.ies.org.
105. IESNA - Illuminating Engineering Society of North America; (See IES).
106. IEST - Institute of Environmental Sciences and Technology; www.iest.org.
107. IGMA - Insulating Glass Manufacturers Alliance; www.igmaonline.org.
108. IGSHPA - International Ground Source Heat Pump Association; www.igshpa.okstate.edu.
109. ILI - Indiana Limestone Institute of America, Inc.; www.iliai.com.
110. Intertek - Intertek Group; (Formerly: ETL SEMCO; Intertek Testing Service NA); www.intertek.com.
111. ISA - International Society of Automation (The); (Formerly: Instrumentation, Systems, and Automation Society); www.isa.org.
112. ISAS - Instrumentation, Systems, and Automation Society (The); (See ISA).
113. ISFA - International Surface Fabricators Association; (Formerly: International Solid Surface Fabricators Association); www.isfanow.org.
114. ISO - International Organization for Standardization; www.iso.org.
115. ISSFA - International Solid Surface Fabricators Association; (See ISFA).
116. ITU - International Telecommunication Union; www.itu.int/home.
117. KCMA - Kitchen Cabinet Manufacturers Association; www.kcma.org.
118. LMA - Laminating Materials Association; (See CPA).
119. LPI - Lightning Protection Institute; www.lightning.org.
120. MBMA - Metal Building Manufacturers Association; www.mbma.com.
121. MCA - Metal Construction Association; www.metalconstruction.org.

122. MFMA - Maple Flooring Manufacturers Association, Inc.; www.maplefloor.org.
123. MFMA - Metal Framing Manufacturers Association, Inc.; www.metalframingmfg.org.
124. MHIA - Material Handling Industry of America; www.mhia.org.
125. MIA - Marble Institute of America; www.marble-institute.com.
126. MMPA - Moulding & Millwork Producers Association; (Formerly: Wood Moulding & Millwork Producers Association); www.wmmpa.com.
127. MPI - Master Painters Institute; www.paintinfo.com.
128. MSS - Manufacturers Standardization Society of The Valve and Fittings Industry Inc.; www.mss-hq.org.
129. NAAMM - National Association of Architectural Metal Manufacturers; www.naamm.org.
130. NACE - NACE International; (National Association of Corrosion Engineers International); www.nace.org.
131. NADCA - National Air Duct Cleaners Association; www.nadca.com.
132. NAIMA - North American Insulation Manufacturers Association; www.naima.org.
133. NBGQA - National Building Granite Quarries Association, Inc.; www.nbgqa.com.
134. NCAA - National Collegiate Athletic Association (The); www.ncaa.org.
135. NCMA - National Concrete Masonry Association; www.ncma.org.
136. NEBB - National Environmental Balancing Bureau; www.nebb.org.
137. NECA - National Electrical Contractors Association; www.necanet.org.
138. NeLMA - Northeastern Lumber Manufacturers Association; www.nelma.org.
139. NEMA - National Electrical Manufacturers Association; www.nema.org.
140. NETA - InterNational Electrical Testing Association; www.netaworld.org.
141. NFHS - National Federation of State High School Associations; www.nfhs.org.
142. NFPA - NFPA; (National Fire Protection Association); www.nfpa.org.
143. NFPA - NFPA International; (See NFPA).
144. NFRC - National Fenestration Rating Council; www.nfrc.org.
145. NHLA - National Hardwood Lumber Association; www.nhla.com.
146. NLGA - National Lumber Grades Authority; www.nlga.org.
147. NOFMA - National Oak Flooring Manufacturers Association; (See NWFA).
148. NOMMA - National Ornamental & Miscellaneous Metals Association; www.nomma.org.
149. NRCA - National Roofing Contractors Association; www.nrca.net.
150. NRMCA - National Ready Mixed Concrete Association; www.nrmca.org.
151. NSF - NSF International; (National Sanitation Foundation International); www.nsf.org.
152. NSPE - National Society of Professional Engineers; www.nspe.org.
153. NSSGA - National Stone, Sand & Gravel Association; www.nssga.org.
154. NTMA - National Terrazzo & Mosaic Association, Inc. (The); www.ntma.com.
155. NWFA - National Wood Flooring Association; www.nwfa.org.
156. PCI - Precast/Prestressed Concrete Institute; www.pci.org.
157. PDI - Plumbing & Drainage Institute; www.pdionline.org.
158. PLASA - PLASA; (Formerly: ESTA - Entertainment Services and Technology Association); www.plasa.org.
159. RCSC - Research Council on Structural Connections; www.boltcouncil.org.
160. RFCI - Resilient Floor Covering Institute; www.rfci.com.
161. RIS - Redwood Inspection Service; www.redwoodinspection.com.
162. SAE - SAE International; (Society of Automotive Engineers); www.sae.org.
163. SCTE - Society of Cable Telecommunications Engineers; www.scte.org.
164. SDI - Steel Deck Institute; www.sdi.org.
165. SDI - Steel Door Institute; www.steeldoor.org.
166. SEFA - Scientific Equipment and Furniture Association; www.sefalabs.com.

167. SEI/ASCE - Structural Engineering Institute/American Society of Civil Engineers; (See ASCE).
168. SIA - Security Industry Association; www.siaonline.org.
169. SJI - Steel Joist Institute; www.steeljoist.org.
170. SMA - Screen Manufacturers Association; www.smainfo.org.
171. SMACNA - Sheet Metal and Air Conditioning Contractors' National Association; www.smacna.org.
172. SMPTE - Society of Motion Picture and Television Engineers; www.smpte.org.
173. SPFA - Spray Polyurethane Foam Alliance; www.sprayfoam.org.
174. SPIB - Southern Pine Inspection Bureau; www.spib.org.
175. SPRI - Single Ply Roofing Industry; www.spri.org.
176. SRCC - Solar Rating and Certification Corporation; www.solar-rating.org.
177. SSINA - Specialty Steel Industry of North America; www.ssina.com.
178. SSPC - SSPC: The Society for Protective Coatings; www.sspc.org.
179. STI - Steel Tank Institute; www.steeltank.com.
180. SWI - Steel Window Institute; www.steelwindows.com.
181. SWPA - Submersible Wastewater Pump Association; www.swpa.org.
182. TCA - Tilt-Up Concrete Association; www.tilt-up.org.
183. TCNA - Tile Council of North America, Inc.; (Formerly: Tile Council of America); www.tileusa.com.
184. TEMA - Tubular Exchanger Manufacturers Association, Inc.; www.tema.org.
185. TIA - Telecommunications Industry Association; (Formerly: TIA/EIA - Telecommunications Industry Association/Electronic Industries Alliance); www.tiaonline.org.
186. TIA/EIA - Telecommunications Industry Association/Electronic Industries Alliance; (See TIA).
187. TMS - The Masonry Society; www.masonrysociety.org.
188. TPI - Truss Plate Institute; www.tpinst.org.
189. TPI - Turfgrass Producers International; www.turfgrasssod.org.
190. TRI - Tile Roofing Institute; (Formerly: National Tile Roofing Manufacturing Association); www.tilerroofing.org.
191. UBC - Uniform Building Code; (See ICC).
192. UL - Underwriters Laboratories Inc.; www.ul.com.
193. UNI - Uni-Bell PVC Pipe Association; www.uni-bell.org.
194. USAV - USA Volleyball; www.usavolleyball.org.
195. USGBC - U.S. Green Building Council; www.usgbc.org.
196. USITT - United States Institute for Theatre Technology, Inc.; www.usitt.org.
197. WASTEC - Waste Equipment Technology Association; www.wastec.org.
198. WCLIB - West Coast Lumber Inspection Bureau; www.wclib.org.
199. WCMA - Window Covering Manufacturers Association; www.wcmanet.org.
200. WDMA - Window & Door Manufacturers Association; www.wdma.com.
201. WI - Woodwork Institute; (Formerly: WIC - Woodwork Institute of California); www.wicnet.org.
202. WMMPA - Wood Moulding & Millwork Producers Association; (See MMPA).
203. WSRCA - Western States Roofing Contractors Association; www.wsrca.com.
204. WPA - Western Wood Products Association; www.wwpa.org.

C. Code Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list.

1. DIN - Deutsches Institut f?r Normung e.V.; www.din.de.

2. IAPMO - International Association of Plumbing and Mechanical Officials; www.iapmo.org.
 3. ICC - International Code Council; www.iccsafe.org.
 4. ICC-ES - ICC Evaluation Service, LLC; www.icc-es.org.
- D. Federal Government Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list.
1. COE - Army Corps of Engineers; www.usace.army.mil.
 2. CPSC - Consumer Product Safety Commission; www.cpsc.gov.
 3. DOC - Department of Commerce; National Institute of Standards and Technology; www.nist.gov.
 4. DOD - Department of Defense; <http://dodssp.daps.dla.mil>.
 5. DOE - Department of Energy; www.energy.gov.
 6. EPA - Environmental Protection Agency; www.epa.gov.
 7. FAA - Federal Aviation Administration; www.faa.gov.
 8. FG - Federal Government Publications; www.gpo.gov.
 9. GSA - General Services Administration; www.gsa.gov.
 10. HUD - Department of Housing and Urban Development; www.hud.gov.
 11. LBL - Lawrence Berkeley National Laboratory; Environmental Energy Technologies Division; <http://eetd.lbl.gov>.
 12. OSHA - Occupational Safety & Health Administration; www.osha.gov.
 13. SD - Department of State; www.state.gov.
 14. TRB - Transportation Research Board; National Cooperative Highway Research Program; www.trb.org.
 15. USDA - Department of Agriculture; Agriculture Research Service; U.S. Salinity Laboratory; www.ars.usda.gov.
 16. USDA - Department of Agriculture; Rural Utilities Service; www.usda.gov.
 17. USDJ - Department of Justice; Office of Justice Programs; National Institute of Justice; www.ojp.usdoj.gov.
 18. USP - U.S. Pharmacopeia; www.usp.org.
 19. USPS - United States Postal Service; www.usps.com.
- E. Standards and Regulations: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the standards and regulations in the following list.
1. CFR - Code of Federal Regulations; Available from Government Printing Office; www.gpo.gov/fdsys.
 2. DOD - Department of Defense; Military Specifications and Standards; Available from Department of Defense Single Stock Point; <http://dodssp.daps.dla.mil>.
 3. DSCC - Defense Supply Center Columbus; (See FS).
 4. FED-STD - Federal Standard; (See FS).
 5. FS - Federal Specification; Available from Department of Defense Single Stock Point; <http://dodssp.daps.dla.mil>.
 - a. Available from Defense Standardization Program; www.dsp.dla.mil.
 - b. Available from General Services Administration; www.gsa.gov.
 - c. Available from National Institute of Building Sciences/Whole Building Design Guide; www.wbdg.org/ccb.

6. MILSPEC - Military Specification and Standards; (See DOD).
 7. USAB - United States Access Board; www.access-board.gov.
 8. USATBCB - U.S. Architectural & Transportation Barriers Compliance Board; (See USAB).
- F. State Government Agencies: Where abbreviations and acronyms are used in Specifications or other Contract Documents, they shall mean the recognized name of the entities in the following list.
1. CBHF; State of California; Department of Consumer Affairs; Bureau of Electronic Appliance and Repair, Home Furnishings and Thermal Insulation; www.bearhfti.ca.gov.
 2. CCR; California Code of Regulations; Office of Administrative Law; California Title 24 Energy Code; www.calregs.com.
 3. CDHS; California Department of Health Services; (See CDPH).
 4. CDPH; California Department of Public Health; Indoor Air Quality Program; www.cal-iaq.org.
 5. CPUC; California Public Utilities Commission; www.cpuc.ca.gov.
 6. SCAQMD; South Coast Air Quality Management District; www.aqmd.gov.
 7. TFS; Texas Forest Service; Forest Resource Development and Sustainable Forestry; <http://txforestservation.tamu.edu>.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 014200

SECTION 015639 - TEMPORARY TREE AND PLANT PROTECTION

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes general protection and pruning of existing trees and plants that are affected by execution of the Work, whether temporary or permanent construction.

1.2 DEFINITIONS

- A. Plant-Protection Zone: Area surrounding individual trees, groups of trees, shrubs, or other vegetation to be protected during construction and indicated on Drawings.
- B. Tree-Protection Zone: Area surrounding individual trees or groups of trees to be protected during construction and indicated on Drawings or defined by a circle concentric with each tree with a radius 1.5 times the diameter of the drip line unless otherwise indicated.

1.3 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings:
 - 1. Include plans, elevations, sections, and locations of protection-zone fencing and signage, showing relation of equipment-movement routes and material storage locations with protection zones.
- C. Tree Pruning Schedule: Written schedule detailing scope and extent of pruning of trees to remain that interfere with or are affected by construction.

1.5 INFORMATIONAL SUBMITTALS

- A. Certification: From arborist, certifying that trees indicated to remain have been protected during construction according to recognized standards and that trees were promptly and properly treated and repaired when damaged.
- B. Maintenance Recommendations: From arborist, for care and protection of trees affected by construction during and after completing the Work.

- C. Existing Conditions: Documentation of existing trees and plantings indicated to remain, which establishes preconstruction conditions that might be misconstrued as damage caused by construction activities.

1.6 QUALITY ASSURANCE

- A. Arborist Qualifications: Certified Arborist as certified by ISA, licensed arborist in jurisdiction where Project is located, current member of ASCA, or registered Consulting Arborist as designated by ASCA.

1.7 FIELD CONDITIONS

- A. The following practices are prohibited within protection zones:
 - 1. Storage of construction materials, debris, or excavated material.
 - 2. Moving or parking vehicles or equipment.
 - 3. Foot traffic.
 - 4. Erection of sheds or structures.
 - 5. Impoundment of water.
 - 6. Excavation or other digging unless otherwise indicated.
 - 7. Attachment of signs to or wrapping materials around trees or plants unless otherwise indicated.
- B. Do not direct vehicle or equipment exhaust toward protection zones.
- C. Prohibit heat sources, flames, ignition sources, and smoking within or near protection zones and organic mulch.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Backfill Soil: Planting soil of suitable moisture content and granular texture for placing around tree; free of stones, roots, plants, sod, clods, clay lumps, pockets of coarse sand, concrete slurry, concrete layers or chunks, cement, plaster, building debris, and other extraneous materials harmful to plant growth.
 - 1. Planting Soil: Planting soil as approved by Architect.
- B. Organic Mulch: Free from deleterious materials and suitable as a top dressing for trees and shrubs, consisting of one of the following:
 - 1. Type: Shredded hardwood
- C. Protection-Zone Fencing: Fencing fixed in position and meeting one of the following requirements: Previously used materials may be used when approved by Architect.
 - 1. Chain-Link Protection-Zone Fencing: Galvanized-steel fencing fabricated from minimum 2-inch (50-mm) opening, 0.148-inch- (3.76-mm-) diameter wire chain-link fabric; with

pipe posts, minimum 2-inch OD line posts (minimum of every 5'), and 2-7/8-inch OD corner and pull posts; with 1-5/8-inch OD top rails and 0.177-inch diameter bottom tension wire; with tie wires, hog ring ties, and other accessories for a complete fence system. Orange high-visibility construction fencing shall be tied to outside of chain link fence.

- a. Height: 48 inches
- D. Protection-Zone Signage: Shop-fabricated, rigid plastic or metal sheet with attachment holes prepunched and reinforced; legibly printed with nonfading lettering, placed every 50' along tree protection fencing.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Erosion and Sedimentation Control: Examine the site to verify that temporary erosion- and sedimentation-control measures are in place. Verify that flows of water redirected from construction areas or generated by construction activity do not enter or cross protection zones.

3.2 PREPARATION

- A. Protect tree root systems from damage caused by runoff or spillage of noxious materials while mixing, placing, or storing construction materials. Protect root systems from ponding, eroding, or excessive wetting caused by dewatering operations.
- B. Tree-Protection Zones: Mulch areas inside tree-protection zones and other areas indicated. Do not exceed indicated thickness of mulch.
1. Apply 5-inch uniform thickness of organic mulch unless otherwise indicated. Do not place mulch within 12 inches of tree trunks.

3.3 PROTECTION ZONES

- A. Protection-Zone Fencing: Install protection-zone fencing along edges of protection zones in a manner that will prevent people from easily entering protected areas except by entrance gates.
1. Chain-Link Fencing: Install to comply with ASTM F 567 and with manufacturer's written instructions.
 2. Posts: Set or drive posts into ground one-third the total height of the fence without concrete footings. Where a post is located on existing paving or concrete to remain, provide appropriate means of post support acceptable to Architect.
- B. Protection-Zone Signage: Install protection-zone signage in visibly prominent locations in a manner approved by Architect.
- C. Maintain protection zones free of weeds and trash.

- D. Maintain protection-zone fencing and signage in good condition as acceptable to Architect and remove when construction operations are complete and equipment has been removed from the site.

3.4 EXCAVATION

- A. General: Excavate at edge of protection zones and for trenches indicated within protection zones according to requirements in Section 312000 "Earth Moving" unless otherwise indicated.
- B. Trenching within Protection Zones: Where utility trenches are required within protection zones, excavate under or around tree roots by hand or with air spade, or tunnel under the roots by drilling, auger boring, or pipe jacking. Do not cut main lateral tree roots or taproots; cut only smaller roots that interfere with installation of utilities. Cut roots as required for root pruning. Any work within tree protection zone shall be approved by the Owner after consultation with a Certified Arborist.
- C. Do not allow exposed roots to dry out before placing permanent backfill.

3.5 ROOT PRUNING

- A. Prune tree roots that are affected by temporary and permanent construction. Prune roots only as approved by the Owner and after consultant with a Certified Arborist as follows:
 - 1. Cut roots manually by digging a trench and cutting exposed roots with sharp pruning instruments; do not break, tear, chop, or slant the cuts. Do not use a backhoe or other equipment that rips, tears, or pulls roots.
 - 2. Temporarily support and protect roots from damage until they are permanently redirected and covered with soil.
 - 3. Cover exposed roots with burlap and water regularly.
 - 4. Backfill as soon as possible according to requirements in Section 312000 "Earth Moving."
- B. Root Pruning at Edge of Protection Zone: Prune tree roots by cleanly cutting all roots to the depth of the required excavation.
- C. Root Pruning within Protection Zone: Clear and excavate by hand or with air spade to the depth of the required excavation to minimize damage to tree root systems. If excavating by hand, use narrow-tine spading forks to comb soil to expose roots. Cleanly cut roots as close to excavation as possible.

3.6 CROWN PRUNING

- A. Prune branches that are affected by temporary and permanent construction. Prune branches only as approved by the owner and as directed by a certified arborist.
 - 1. Prune to remove only injured, broken, dying, or dead branches unless otherwise indicated. Do not prune for shape unless otherwise indicated.

2. Do not remove or reduce living branches to compensate for root loss caused by damaging or cutting root system.
 3. Pruning Standards: Prune trees according to ANSI A300 (Part 1)
- B. Cut branches with sharp pruning instruments; do not break or chop.
 - C. Do not paint or apply sealants to wounds.
 - D. Chip removed branches and dispose of off-site.

3.7 REGRADING

- A. Lowering Grade: Where new finish grade is indicated below existing grade around trees, slope grade beyond the protection zone. Maintain existing grades within the protection zone.
- B. Raising Grade: Where new finish grade is indicated above existing grade around trees, slope grade beyond the protection zone. Maintain existing grades within the protection zone.
- C. Minor Fill within Protection Zone: Where existing grade is 2 inches or less below elevation of finish grade, fill with backfill soil. Place backfill soil in a single uncompacted layer and hand grade to required finish elevations.

3.8 FIELD QUALITY CONTROL

- A. Inspections: Engage a qualified arborist to direct plant-protection measures in the vicinity of trees, shrubs, and other vegetation indicated to remain and to prepare inspection reports.

3.9 REPAIR AND REPLACEMENT

- A. General: Repair or replace trees, shrubs, and other vegetation indicated to remain or to be relocated that are damaged by construction operations, in a manner approved by Architect.
 1. Perform repairs of damaged trunks, branches, and roots within 24 hours according to arborist's written instructions.
 2. Replace trees and other plants that cannot be repaired and restored to full-growth status, as determined by Architect.
- B. Excess Mulch: Rake mulched area within protection zones, being careful not to injure roots. Rake to loosen and remove mulch that exceeds a 2-inch uniform thickness to remain.

3.10 DISPOSAL OF SURPLUS AND WASTE MATERIALS

- A. Disposal: Remove excess excavated material, displaced trees, trash, and debris and legally dispose of them off Owner's property.

END OF SECTION 015639

SECTION 017700 - CLOSEOUT PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for contract closeout, including, but not limited to, the following:
 - 1. Substantial Completion procedures.
 - 2. Final completion procedures.
 - 3. Warranties.
 - 4. Final cleaning.
 - 5. Repair of the Work.
- B. Related Requirements:
 - 1. Section 013233 "Photographic Documentation" for submitting final completion construction photographic documentation.
 - 2. Section 017839 "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.

1.2 ACTION SUBMITTALS

- A. Contractor's List of Incomplete Items: Initial submittal at Substantial Completion.
- B. Certified List of Incomplete Items: Final submittal at Final Completion.

1.3 CLOSEOUT SUBMITTALS

- A. Certificates of Release: From authorities having jurisdiction.
- B. Certificate of Insurance: For continuing coverage.
- C. Field Report: For pest control inspection.

1.4 MAINTENANCE MATERIAL SUBMITTALS

- A. Schedule of Maintenance Material Items: For maintenance material submittal items specified in other Sections.

1.5 SUBSTANTIAL COMPLETION PROCEDURES

- A. Contractor's List of Incomplete Items: Prepare and submit a list of items to be completed and corrected (Contractor's punch list), indicating the value of each item on the list and reasons why the Work is incomplete.
- B. Submittals Prior to Substantial Completion: Complete the following a minimum of 10 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.
1. Certificates of Release: Obtain and submit releases from authorities having jurisdiction permitting Owner unrestricted use of the Work and access to services and utilities. Include occupancy permits, operating certificates, and similar releases.
 2. Submit closeout submittals specified in other Division 01 Sections, including project record documents, operation and maintenance manuals, final completion construction photographic documentation, damage or settlement surveys, property surveys, and similar final record information.
 3. Submit closeout submittals specified in individual Sections, including specific warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
 4. Submit maintenance material submittals specified in individual Sections, including tools, spare parts, extra materials, and similar items, and deliver to location designated by Architect. Label with manufacturer's name and model number where applicable.
 - a. Schedule of Maintenance Material Items: Prepare and submit schedule of maintenance material submittal items, including name and quantity of each item and name and number of related Specification Section. Obtain Architect's signature for receipt of submittals.
 5. Submit test/adjust/balance records.
 6. Submit changeover information related to Owner's occupancy, use, operation, and maintenance.
- C. Procedures Prior to Substantial Completion: Complete the following a minimum of 10 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.
1. Advise Owner of pending insurance changeover requirements.
 2. Complete startup and testing of systems and equipment.
 3. Perform preventive maintenance on equipment used prior to Substantial Completion.
 4. Advise Owner of changeover in heat and other utilities.
 5. Participate with Owner in conducting inspection and walkthrough with local emergency responders.
 6. Terminate and remove temporary facilities from Project site, along with mockups, construction tools, and similar elements.
 7. Complete final cleaning requirements, including touchup painting.
 8. Touch up and otherwise repair and restore marred exposed finishes to eliminate visual defects.
- D. Inspection: Submit a written request for inspection to determine Substantial Completion a minimum of 10 days prior to date the work will be completed and ready for final inspection and

tests. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare the Certificate of Substantial Completion after inspection or will notify Contractor of items, either on Contractor's list or additional items identified by Architect, that must be completed or corrected before certificate will be issued.

1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.
2. Results of completed inspection will form the basis of requirements for final completion.

1.6 FINAL COMPLETION PROCEDURES

- A. Preliminary Procedures: Before requesting final inspection for determining final completion, complete the following:
1. Submit a final Application for Payment according to Section 012900 "Payment Procedures."
 2. Certified List of Incomplete Items: Submit certified copy of Architect's Substantial Completion inspection list of items to be completed or corrected (punch list), endorsed and dated by Architect. Certified copy of the list shall state that each item has been completed or otherwise resolved for acceptance.
 3. Certificate of Insurance: Submit evidence of final, continuing insurance coverage complying with insurance requirements.
 4. Instruct Owner's personnel in operation, adjustment, and maintenance of products, equipment, and systems.
- B. Inspection: Submit a written request for final inspection to determine acceptance. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued.
1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.

1.7 LIST OF INCOMPLETE ITEMS (PUNCH LIST)

- A. Organization of List: Include name and identification of each space and area affected by construction operations for incomplete items and items needing correction including, if necessary, areas disturbed by Contractor that are outside the limits of construction.
1. Submit list of incomplete items in the following format:
 - a. PDF electronic file. Architect will return annotated copy.

1.8 SUBMITTAL OF PROJECT WARRANTIES

- A. Time of Submittal: Submit written warranties on request of Architect for designated portions of the Work where commencement of warranties other than date of Substantial Completion is indicated, or when delay in submittal of warranties might limit Owner's rights under warranty.

- B. Organize warranty documents into an orderly sequence based on the table of contents of the Project Manual.
 - 1. Warranty Electronic File: Scan warranties and bonds and assemble complete warranty and bond submittal package into a single indexed electronic PDF file with links enabling navigation to each item. Provide bookmarked table of contents at beginning of document.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 FINAL CLEANING

- A. General: Perform final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations.
- B. Cleaning:
 - 1. Complete the following cleaning operations before requesting inspection for certification of Substantial Completion for entire Project or for a designated portion of Project:
 - a. Clean Project site, yard, and grounds, in areas disturbed by construction activities, including landscape development areas, of rubbish, waste material, litter, and other foreign substances.
 - b. Sweep paved areas broom clean. Remove petrochemical spills, stains, and other foreign deposits.
 - c. Rake grounds that are neither planted nor paved to a smooth, even-textured surface.
 - d. Remove tools, construction equipment, machinery, and surplus material from Project site.
 - e. Clean exposed exterior and interior hard-surfaced finishes to a dirt-free condition, free of stains, films, and similar foreign substances. Avoid disturbing natural weathering of exterior surfaces. Restore reflective surfaces to their original condition.

3.2 REPAIR OF THE WORK

- A. Complete repair and restoration operations before requesting inspection for determination of Substantial Completion.
- B. Repair or remove and replace defective construction. Repairing includes replacing defective parts, refinishing damaged surfaces, touching up with matching materials, and properly adjusting operating equipment. Where damaged or worn items cannot be repaired or restored, provide replacements. Remove and replace operating components that cannot be repaired. Restore damaged construction and permanent facilities used during construction to specified condition.

1. Remove and replace chipped, scratched, and broken glass, reflective surfaces, and other damaged transparent materials.
2. Touch up and otherwise repair and restore marred or exposed finishes and surfaces. Replace finishes and surfaces that that already show evidence of repair or restoration.
 - a. Do not paint over "UL" and other required labels and identification, including mechanical and electrical nameplates. Remove paint applied to required labels and identification.
3. Replace parts subject to operating conditions during construction that may impede operation or reduce longevity.
4. Replace burned-out bulbs, bulbs noticeably dimmed by hours of use, and defective and noisy starters in fluorescent and mercury vapor fixtures to comply with requirements for new fixtures.

END OF SECTION 017700

SECTION 017839 - PROJECT RECORD DOCUMENTS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes administrative and procedural requirements for project record documents, including the following:
 - 1. Record Drawings.
 - 2. Record Product Data.
- B. Related Requirements:

1.2 CLOSEOUT SUBMITTALS

- A. Record Drawings: Comply with the following:
 - 1. Number of Copies: Submit one set(s) of marked-up record prints.
 - 2. Number of Copies: Submit copies of record Drawings as follows:
 - a. Initial Submittal:
 - 1) Submit PDF electronic files of scanned record prints and one set(s) of file prints.
 - 2) Architect will indicate whether general scope of changes, additional information recorded, and quality of drafting are acceptable.
 - b. Final Submittal:
 - 1) Submit PDF electronic files of scanned record prints and set(s) of prints.
 - 2) Print each drawing, whether or not changes and additional information were recorded.
- B. Record Product Data: Submit annotated PDF electronic files and directories of each submittal.

PART 2 - PRODUCTS

2.1 RECORD DRAWINGS

- A. Record Prints: Maintain one set of marked-up paper copies of the Contract Drawings and Shop Drawings, incorporating new and revised Drawings as modifications are issued.
 - 1. Preparation: Mark record prints to show the actual installation where installation varies from that shown originally. Require individual or entity who obtained record data, whether individual or entity is Installer, subcontractor, or similar entity, to provide information for preparation of corresponding marked-up record prints.

- a. Give particular attention to information on concealed elements that would be difficult to identify or measure and record later.
 - b. Record data as soon as possible after obtaining it.
 - c. Record and check the markup before enclosing concealed installations.
2. Mark the Contract Drawings and Shop Drawings completely and accurately. Use personnel proficient at recording graphic information in production of marked-up record prints.
 3. Mark record sets with erasable, red-colored pencil. Use other colors to distinguish between changes for different categories of the Work at same location.
 4. Note Construction Change Directive numbers, alternate numbers, Change Order numbers, and similar identification, where applicable.
- B. Record Digital Data Files: Immediately before inspection for Certificate of Substantial Completion, review marked-up record prints with Architect. When authorized, prepare a full set of corrected digital data files of the Contract Drawings, as follows:
1. Format: DWG operating system.
 2. Incorporate changes and additional information previously marked on record prints. Delete, redraw, and add details and notations where applicable.
 3. Refer instances of uncertainty to Architect for resolution.
 4. Architect will furnish Contractor one set of digital data files of the Contract Drawings for use in recording information.
- C. Format: Identify and date each record Drawing; include the designation "PROJECT RECORD DRAWING" in a prominent location.
1. Record Prints: Organize record prints and newly prepared record Drawings into manageable sets. Bind each set with durable paper cover sheets. Include identification on cover sheets.
 2. Format: Annotated PDF electronic file
 3. Record Digital Data Files: Organize digital data information into separate electronic files that correspond to each sheet of the Contract Drawings. Name each file with the sheet identification. Include identification in each digital data file.
 4. Identification: As follows:
 - a. Project name.
 - b. Date.
 - c. Designation "PROJECT RECORD DRAWINGS."
 - d. Name of Architect.
 - e. Name of Contractor.

2.2 RECORD PRODUCT DATA

- A. Preparation: Mark Product Data to indicate the actual product installation where installation varies substantially from that indicated in Product Data submittal.
1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
 2. Include significant changes in the product delivered to Project site and changes in manufacturer's written instructions for installation.

3. Note related Change Orders and record Drawings where applicable.
- B. Format: Submit record Product Data as annotated PDF electronic file.

PART 3 - EXECUTION

3.1 RECORDING AND MAINTENANCE

- A. Recording: Maintain one copy of each submittal during the construction period for project record document purposes. Post changes and revisions to project record documents as they occur; do not wait until end of Project.
- B. Maintenance of Record Documents and Samples: Store record documents and Samples in the field office apart from the Contract Documents used for construction. Do not use project record documents for construction purposes. Maintain record documents in good order and in a clean, dry, legible condition, protected from deterioration and loss. Provide access to project record documents for Architect's reference during normal working hours.

END OF SECTION 017839

SECTION 33 01 30 - POST-REHABILITATION SANITARY SEWER CCTV INSPECTION

PART 1 - GENERAL

1.01 DESCRIPTION

- A. Perform all sewer line closed circuit television (CCTV) inspection work after the CIPP rehabilitation has been performed.

1.02 REFERENCES

- A. National Association of Sewer Service Companies (NASSCO)
 - 1. Pipeline Assessment and Certification Program (PACP) Reference Manual
 - 2. Recommended Specifications for Sewer Collection System Rehabilitation Standard (2006)

1.03 RELATED WORK

- A. Sewer line cleaning is included in Section 33 35 20.
- B. Pre-rehabilitation CCTV Sewer Inspection is included in Section 33 01 51.

1.04 DEFINITIONS

- A. Television Inspection: A necessary operation to complete a true-color audio-visual inspection to verify existing internal sewer line conditions. Furnish labor, materials, equipment, tools, and other incidental services for CCTV inspection.
- B. MPEG: MPEG is an acronym for Moving Pictures Expert Group, which is a family of international standards used for coding audio-visual information in a digital compressed format. For this Section, digital audio-visual coding has a 352 pixels (x) by 240 pixels (y) resolution and a 30 frames per second interlaced frame rate. MPEG coding shall be named using “.mpg” as the file extension.
- C. Acceptable media for the video recordings are external hard drive electronic media for data transfer.

1.05 SUBMITTALS

- A. Submit the following shop drawings in accordance with these specifications.
- B. Submit a written description for procedures to be used.
- C. Submit the product literature for all digital video equipment, including, but not limited to, cabling, camera, monitor, footage counter, digital video titling device, and recorder.
- D. Submit a written/printed copy of television inspection logs to the Construction Manager. Logs shall record defects according to NASSCO’s Pipeline Assessment and Certification Program (PACP) or/and Manhole Assessment and Certification Program (MACP).

- E. Submit 2 copies of visual and audio recording to the Construction Manager in electronic format.
 - 1. The Construction Manager will review the inspections to ensure that the required information is provided and the recording quality is acceptable, but they will not review the inspections for content accuracy.
 - 2. If the Construction Manager determines the recording is defective or not adequate quality, the Contractor shall perform the CCTV inspection again at the Contractor's expense.

1.06 QUALITY ASSURANCE

- A. Comply with all codes, laws, ordinances, and regulations of governmental authorities having jurisdiction over this part of the work.
- B. The television inspection shall be performed one section of line at a time. An individual digital video file and data file shall be developed for each manhole-to-manhole section.
- C. The inspection shall be performed in accordance with NASSCO's Pipeline Assessment and Certification Program (PACP) and/or Manhole Assessment and Certification Program (MACP).
- D. Review all videos and data before they are submitted to the Construction Manager for compliance with the requirements of the Contract.

PART 2 - PRODUCTS

2.01 GENERAL

- A. Furnish the television inspection studio, television camera, audio-visual digital encoding equipment/software, and other necessary equipment, materials, electricity, labor, technicians, as may be needed to perform the television inspection.

2.02 TELEVISION INSPECTION EQUIPMENT

- A. The television inspection equipment shall be able to inspect 1,000 feet minimum sewer line when entry into the sewer can be accessed from the upstream and downstream manholes. When entry is at one end only, the inspection equipment shall be able to inspect 750 feet by a self-propelled unit. The inspection equipment shall be able to clearly televise the interior of 6-inch and larger diameter sewers.
- B. Transport the television equipment in a stable condition through the sewer line to be inspected. Throughout the inspection, position the camera equipment with the camera directed along the sewer's longitudinal axis.

2.03 TELEVISION CAMERA

- A. Use a television camera specifically designed and constructed for sewer pipeline inspection.
 - 1. The camera shall be waterproof and able to operate in any conditions encountered in the inspection environment.

2. Provide a color pan, tilt, and zoom camera to facilitate inspecting service laterals and sewer line to clearly view manhole defects and construction features.
 3. The television camera shall be capable of 360-degree rotational scan indicating salient defects.
 4. The tilt arc shall not be less than 225 degrees unless otherwise approved by the Construction Manager.
 5. The focus and iris adjustment shall provide a minimum 3-inch focal range in front of the camera's lens.
- B. The distance along the sewer in focus from the initial observation point shall be a minimum of twice the sewer's vertical height.
- C. The illumination shall allow an even light shadowing distribution.
1. The view seen by the television camera shall be transmitted to an 11-inch or larger color monitor.
 2. The television camera shall be able to receive and transmit a picture having not less than a 352(x) by 240(y) resolution.
 3. The television inspection camera travel speed through the sewer shall be uniform and shall not exceed 30 feet per minute maximum speed.
- D. The television inspection equipment shall be a quality to achieve the following:
1. The CCTV monitor display shall incorporate an automatically updated record in feet and tenths of a foot for the distance along the line from the cable calibration point to the camera's or transducer's center point, whichever unit is being used.
 2. The relative positions for the two center points should also be noted.
 3. Use a metering device that enables the cable length to be accurately measured; this shall be accurate to 6-inches.
 4. Demonstrate the tolerance is being achieved by tape measurement between manholes on the surface. This taped measurement must be included on each written and digital television log.
 5. The CCTV camera shall be calibrated for accurate length measurements at least once per week with above ground markings every 25 feet for up to 100 feet. The accuracy should be within 0.2 foot for every 100 feet.
 6. If the Contractor fails to meet the required accuracy standard, the Construction Manager will instruct the Contractor to provide a new device to measure the footage. The Construction Manager may instruct the Contractor to resurvey those sewer lengths first inspected with the original measuring device using the new measuring device.
 7. Audio-visual recordings and collected data made during the television inspection shall become MWS property. Submit the digital data to the Construction Manager within two weeks from completing the television inspection.

2.04 TELEVISION STUDIO

- A. The television studio shall be large enough to accommodate four people for viewing the television monitor while the inspection is in progress.
- B. The television studio shall be insulated against noise and temperature extremes and shall have the means to control external and internal light sources to ensure the monitor screen display is in accordance with this Section's requirements.
- C. The Construction Manager shall have access at all times to view the television screen.

PART 3 - EXECUTION

3.01 TELEVISION INSPECTION

- A. Inspect sewer pipelines with pan, tilt and zoom conventional television imagery to record relevant pipeline features and defects. Pipeline inspection shall be carried out in a format reviewed by the Construction Manager. Perform cleaning in accordance with contract document requirements.
- B. CCTV operators shall be NASSCO PACP certified and have a current certification.
- C. If television inspection for an entire section cannot be successfully performed from one manhole, perform a reverse setup to obtain a complete television inspection.
- D. Perform sewer televising work as necessary, using NASSCO PACP coding to thoroughly document the condition for all sewers, service lateral connections, manhole corbel, barrel, and cone-sections in the study area. To achieve this, the CCTV camera operator shall stop the camera in each manhole invert and shall pan and zoom up the manhole to obtain the best possible image of the manhole, including the cone and corbel section(s).
- E. The quality and coding for all work specified in this Section shall meet or exceed the National Association of Sewer Service Companies (NASSCO) Recommended Specifications for Sewer Collection System Rehabilitation (latest edition) requirements. Applicable Section portions which inadvertently fall below those standards shall be corrected and maintained at the NASSCO standards as a minimum requirement, at no additional cost to MWS.
- F. Document all internal sewer inspections via digital video recordings, television logs, digital photos, and a database compatible with the NASSCO PACP coded.
 - 1. If the video is poor quality due to the chosen media, Metro reserves the right to require re-submittal on a different media.
 - 2. Create separate MPEG 4 H264 files for each sewer line segment.
 - 3. In a reverse setup, store such inspection in a separate MPEG 4 H264 file.
 - 4. MPEG 4 H264 files shall be written to an external media for delivery to the Construction Manager.
 - 5. Each media shall be labeled, at a minimum, with the following information: Metro Water Services, MWS project name, MWS project number, CWNOAP project number, creation date, Prime Contractor's firm name, and TV inspection contractor's firm name.

- G. Digital video shall be defined as ISO-MPEG Level 4 (MPEG 4) --coding with a 352-pixel (x) by 240-pixel (y) (minimum) resolution and a 30 frames per second encoded frame rate.
1. The digital recording shall include audio and video information which accurately reproduces the original video inspection picture and sound.
 2. The digital recording's video portion shall be free from electrical interference and shall produce a clear and stable image.
 3. The audio portion shall produce a clear and discernible oral report, sufficiently free from background and electrical noise.
- H. Separate digital video recordings shall be made for each sewer section and shall be properly identified via continuous on-screen display and voice-over recording with the following:
1. MWS Project number
 2. Upstream MH ID and downstream MH ID
 3. Sewer segment being inspected
 4. Inspection date
 5. Project name
 6. Distance along the reach from the entering manhole
- I. Contractor shall coordinate with Construction Manager prior to commencing work to ensure identification is accomplished in a manner acceptable to MWS. If the video and/or audio recording is poor quality, the Metro has the right to require a re-submittal of the affected sewer sections. No payment will be made until an acceptable video and audio recording is made and submitted to and accepted by the Construction Manager.
- J. The CCTV equipment/software shall be able to produce digitized images for all sewer line defects, manhole defects, and sewer line service connections in .jpeg format. Plan to take digital still images of each defect, construction features, and service connection to clearly depict it. More images may be necessary depending on the lined pipe condition.
- K. Provide CCTV inspection data via external media. Data shall be recorded and provided in a current version of the NASSCO PACP Exchange format. The data shall specifically include video indexing for all observations. Data to be submitted shall include:
1. NASSCO PACP exchange database file
 2. .jpeg files (still photos)
 3. MPG 4 H264 files format -(video) for each pipe segment
- L. Provide a complete television inspection for the upstream and downstream manholes. The CCTV operator shall pan and zoom up the manhole from the invert for each manhole and obtain the best possible image of the manhole, including cone and corbel sections. In addition, 3 still digital photos shall be taken for each pipe connection within each manhole. The CCTV operator shall zoom in on each pipe connection so the photos capture each pipe connection's size, location, and approximate elevation.

- M. Whenever prevailing conditions allow, position the camera head to reduce the risk of picture distortion. In circular sewers, position the camera lens centrally (i.e., in prime position) within the sewer. In noncircular sewers, picture orientation shall be taken at mid-height, unless otherwise agreed, and centered horizontally. Direct the camera lens along the sewer's longitudinal axis when in prime position. A +/- 10 percent positioning tolerance of the vertical sewer dimension shall be allowed when the camera is in prime position.
- N. Perform television inspections during low flow conditions. The Construction Manager will reject any television inspection that does not produce an effective sewer pipe survey due to flow conditions or for any other reason. Sewer flow shall be controlled so that the invert of rehabilitated pipe is fully visible.
- O. Do not pull a cleaning device in front of the television inspection camera while taping the sewer line.

3.02 DIGITAL AUDIO/VISUAL RECORDING

- A. Take continuous digital video recordings of the inspection view as it appears on the television monitor. A digital video recording shall be made for the complete television inspection of the sewer lines constructed as part of this project. The recording shall also be used as a permanent record for defects. The recording shall be MPG 4 H264 file format. The digital video encoding shall include sound and video information that can be reproduced with a video image equal or very close to the original picture quality on the television monitor. The recorded video information replay, when reviewed by Windows Media Player™, shall be free from electrical interference and shall produce a clear, stable image. The composite digital coding's audio portion shall be sufficiently free from electrical interference/background noise to produce an oral report that is clear and completely and easily discernible.
- B. The inspection report's audio portion shall include the section's location or identification, the manhole-to-manhole travel direction, and the distance traveled on the specific run encountered. The inspection camera equipment shall be on the specific run encountered. Continuously connect the inspection camera equipment to the television inspection or monitoring equipment. The recording and monitoring equipment shall have the built-in capability to allow the Construction Manager to instantly review the recording's audio and video quality during the television survey. Playback speed shall be continuously adjustable from 1/3 normal speed for slow-motion viewing to normal playback speed.
- C. Name the MPG 4 H264 files according to the following file specification: Upstream Manhole Number_Downstream Manhole Number_Month_Day_Year.mpg
- D. One final video record shall be submitted for each rehabilitated line segment.

3.03 TELEVISION INSPECTION REPORTS

- A. Prepare a television inspection report covering the television inspection work and the information acquired. Prior to beginning work, submit a sample hardcopy television inspection report to the Construction Manager for review.
- B. Report sewer defects in accordance with the National Association of Sewer Service Companies (NASSCO) program known as Pipeline Assessment and Certification Program (PACP). The Construction Manager reserves the right to refuse any inspection report that does not comply with the PACP program.

3.04 QUALITY CONTROL

- A. Operate a quality control system that will effectively gauge the accuracy of inspection reports produced by the operator.
- B. The Construction Manager shall be entitled to audit the control system and be present when sewer integrity assessments are being determined for rehabilitated or upgraded pipe. When requested, provide sufficient details and information for such audit assessment. Should any report fail to achieve a margin the Construction Manager deems satisfactory, the Contractor, without any additional compensation, shall recode and resubmit any data or reports.

END OF SECTION

SECTION 33 01 40 - CURED-IN-PLACE PIPE LINING

PART 1 - GENERAL

1.01 DESCRIPTION

- A. This Section includes furnishing all labor, materials, equipment, and incidentals required to install and test the cured-in-place pipe (CIPP) lining and appurtenances complete as shown on the Drawings, including, but not limited to, all services necessary as specified herein for the following:
 - 1. Traffic control
 - 2. Bypass pumping and/or diverting flows
 - 3. Cleaning and television inspection of sewers to be lined
 - 4. Lining installation
 - 5. Quality control
 - 6. Samples for performing required material tests
 - 7. Final television inspection
 - 8. Testing the lined pipe system
 - 9. Warranty work
- B. Sewer cleaning, pre-rehabilitation closed-circuit television (CCTV) inspection, and post-rehabilitation CCTV inspection are required for all pipes to be rehabilitated by CIPP lining methods.
- C. The Contractor shall remove all pipeline obstructions as required to complete the CIPP rehabilitation.
- D. Neither the CIPP system nor its installation shall cause adverse effects to any Metro processes, facilities, the environment, or the Cumberland River. Product use shall not result in forming or producing any detrimental compounds or by-products that are released into the Cumberland River. The Contractor shall notify the Construction Manager and identify any by-products produced due to the installation operations and shall test and monitor the levels and comply with any and all local waste discharge requirements.
- E. The Contractor shall cleanup, restore existing surface conditions and structures, and repair any CIPP system determined to be defective. The Contractor shall conduct installation operations and schedule cleanup in a manner to cause the least possible obstruction and inconvenience to traffic, pedestrians, businesses, and property owners or tenants.

1.02 RELATED WORK

- A. Pre-CCTV and post-CCTV inspections are included in Section 33 01 51 and Section 33 01 30, respectively.
- B. Sewer line cleaning is included in Section 33 35 20.

1.03 SUBMITTALS

- A. Submit product data, design calculations, installation details, and shop drawings to the Construction Manager. The Contractor shall provide this information without delay or claim to any confidentiality. Submittals shall include the following:
1. CIPP lining supplier's name and a materials list
 2. Required CIPP lining schedule, including field-verified lengths and diameters for all CIPP linings and appurtenances. Plans should include map(s) showing insertion points for all CIPP installations for pipes 18 inches in diameter and larger.
 3. Shop drawings and product data to demonstrate compliance with these specifications and identify construction materials, including resins, catalysts, felt, etc., felt manufacturer and facility location, wet-out facility location, etc.
 4. Manufacturers' shipping, storage, and handling recommendations for all CIPP system components
 5. MSDS sheets for all materials to be furnished for the project
 6. Detailed installation procedures, including CIPP lining production schedule, acceptable inversion heads and pressures, inversion procedures, curing and cool-down procedures and temperatures, and times for each process stage
 7. Prior to each CIPP lining shipment, certified test reports showing that the CIPP lining for this Contract was manufactured and tested in accordance with all ASTM Standards specified and referenced herein.
 8. An odor control plan that ensures project specific odors will be minimized at the project site and surrounding area. The plan shall address the monitoring of ambient odors such as styrene concentrations, the creation and distribution/availability of public information materials, preventative measures, and methods and means of responses to issues that arise. The plan shall include the furnishing of an on-site, functioning calibrated metering capability to the nearest 0.1 ppm in the event of styrene odor complaints or when requested by the Construction Manager.
 9. A detailed public notification plan shall be prepared and submitted, including detailed staged notification to businesses affected by the CIPP installation
 10. Pre-rehabilitation CCTV main-line inspection data as further defined herein
 11. A complete description for the proposed wet-out procedure for the proposed technology
 12. Wet-out forms with detailed information, including, but not limited to resin volumes and/or weights, CIPP liner length, roller gap settings, start times, finish times, gel times, resin injection locations, and any other pertinent data documenting the wet-out for each CIPP liner section manufactured.
 13. Design data and specification data sheets listing all parameters used in the CIPP liner design and thickness calculations based on ASTM F1216. All calculations shall be prepared under and stamped by a Tennessee registered professional engineer.

14. Manufacturer's recommended cure method for each CIPP liner diameter and thickness to be installed, including detailed curing procedures describing the curing medium and the application method.
 15. CIPP lining curing reports documenting the liner installation for all sewer segments. The CIPP lining reports shall document all lining installation details, including manhole numbers, street names/sewer location, project number, date, time, temperature, curing temperature, curing time, CIPP liner thickness, etc.
 16. Post-rehabilitation CCTV mainline inspection data as further defined herein.
 17. Installed liner(s) samples for testing to be performed by an ASTM-certified independent testing laboratory, as described further herein
 18. Data on the maximum allowable stresses and elongation of the tube during installation and the means the Contractor will use to monitor stress and elongation
 19. A detailed summary about the proposed quality controls to be performed by the Contractor, including:
 - a. Proposed procedures for quality control
 - b. Product sampling and testing method and frequency for product sampling and testing in raw material form and cured product form
 - c. Inspection forms and guidelines for quality control inspections
- B. Submit the name and experience for lead personnel, including verifiable references, as described in the Qualifications subsection below.

1.04 REFERENCE STANDARDS

- A. American Society for Testing and Materials (ASTM)
1. ASTM D543 – Standard and Practice for Evaluating the Resistance of Plastics to Chemical Reagents
 2. ASTM D638 – Standard Test Method for Tensile Properties of Plastics
 3. ASTM D790 – Standard Test Method for Flexural Properties of Unreinforced and Reinforced Plastics and Electrical Insulating Materials
 4. ASTM D792 – Standard Test Methods for Density and Specific Gravity of Plastics by Displacement
 5. ASTM D2412 – Standard Test Method for Determination of External Loading Characteristics of Plastic Pipe by Parallel-Plate Loading
 6. ASTM F1216 – Standard Practice for Rehabilitation of Existing Pipelines and Conduits by the Inversion and Curing of a Resin-Impregnated Tube
 7. ASTM F1743 – Standard Practice for Rehabilitation of Existing Pipelines and Conduits by Pulled-in-Place Installation of Cured-in-Place Thermosetting Resin Pipe (CIPP)
 8. ASTM D638 – Standard Test Method for Tensile Properties of Plastics

9. ASTM D5813 – Standard Specification for Cured-in-Place Thermosetting Resin Sewer Piping Systems
 10. ASTM D2990 – Standard Test Methods for Tensile, Compressive, and Flexural Creep and Creep-Rupture of Plastics
- B. National Association of Sewer Service Companies (NASSCO)
1. Recommended Specifications for Sewer Collection System Rehabilitation
- C. Where reference is made to one of the above standards, the revision in effect at the time of bid opening shall apply.

1.05 EXPERIENCE AND CERTIFICATIONS

- A. The Contractor performing the CIPP lining work shall be experienced and equipped to complete this work expeditiously and in a satisfactory manner and shall be certified and/or licensed as an installer by the CIPP lining manufacturer.
- B. The lead personnel, including the supervisor, the foreman, and the lead crew personnel for the CCTV inspection, factory resin wet-out, the CIPP lining installation, lining curing and the robotic service reconnections each must have a 3-year and/or 250,000 feet minimum total continuous experience with the CIPP technology proposed for this Contract and must have demonstrated competency and experience to perform the scope of work contained in this Contract.

1.06 GUARANTEE

- A. All placed CIPP linings shall be guaranteed by the Contractor and manufacturer for a 3-year period from the final acceptance date. During this period, the Contractor shall remove and replace any and all serious defects discovered in the CIPP lining, as determined by Metro, which may materially affect the pipe's integrity, strength, function, and/or operation in a satisfactory manner to Metro at no cost to Metro. Defects replaced during this 3-year period shall be fully warranted by the Contractor and manufacturer for a period of two years from date the defect was repaired. At Metro's own expense, Metro may conduct an independent CCTV inspection of the CIPP lining work prior to completing the guarantee period.
- B. CIPP tube manufacturer shall warrant the tube and resin materials to be free from any defects for a 10-year minimum from the manufacture date.

1.07 QUALITY ASSURANCE

- A. All CIPP linings shall be from a single manufacturer. The suppliers shall be responsible for providing all test requirements specified herein as applicable. In addition, all CIPP linings to be installed under this Contract may be inspected at the plant for compliance with these specifications by an independent testing laboratory provided by Metro or Construction Manager. The Contractor shall require the manufacturer's cooperation with these inspections. The cost for CIPP lining plant inspection approved for this Contract will be MWS or the Construction Manager's responsibility.
- B. The Construction Manager or Metro may inspect CIPP lining after delivery. The CIPP lining shall be subject to rejection at any time if it fails to meet any requirements specified, even though sample CIPP lining may have been accepted as satisfactory at the manufacturer. CIPP lining rejected after delivery shall be marked for identification and removed from the job site.

- C. In the event that an installation is rejected based on a review of the post-rehabilitation CCTV inspection data, the Contractor shall repair the sewer segment to the satisfaction of Metro at no additional cost to Metro.

1.08 DELIVERY, STORAGE, AND HANDLING

- A. Care shall be taken in shipping, handling, and laying to avoid damaging the CIPP liner. Any CIPP liner damaged in shipment shall be replaced as directed by the Construction Manager.
- B. Any CIPP lining showing a split or tear or which has received a blow that may have caused damage, even though no such damage can be seen, shall be marked as rejected and removed at once from the work.
- C. While stored, CIPP shall be adequately supported and protected in the manner recommended by the manufacturer.
- D. The CIPP lining shall be maintained at a proper temperature in refrigerated facilities at all times prior to installation to prevent premature curing. The CIPP lining shall be protected from UV light. Any CIPP lining showing evidence of premature curing shall be rejected for use and immediately removed from the site.

1.09 WATER

- A. Water for all construction operations shall be available from identified Metro fire hydrants at normal commercial rates. Water usage shall be in accordance with Metro backflow and metering policies.

1.10 AVAILABLE SEWER VIDEOS

- A. The existing sewer lines scheduled for rehabilitation were inspected to the degree possible for pipe conditions by a cleaning and CCTV services contractor. Electronic files with the video inspections only of the main may be provided to the Contractor FOR INFORMATION ONLY upon written request with liability of use release.

PART 2 - PRODUCTS

2.01 CIPP FELT LINER AND RESIN

- A. CIPP lining shall be Granite Inliner Technologies by Granite Inliner, Inc.; Insituform by Insituform Technologies, Inc.; MooreLiner by Moore Construction Co.; Pipenology Liner by SAK Construction, LLC; CIPP Corporation liner by American Infrastructures Technologies; Inverta A Pipe Liner by Inland Pipe Rehabilitation (IPR Southeast); or pre-bid approved equal.
- B. The CIPP liner shall have tubing material with layers of a flexible non-woven polyester felt with or without additives such as woven fiberglass or other fibers and shall meet ASTM F1216, ASTM F1743, ASTM D5813, and ASTM D2990 requirements. The CIPP liner's felt content shall be determined by the Contractor, but shall not exceed 15 percent of the total impregnated liner volume. The fabric tube shall be able to absorb and carry resins, be constructed to withstand installation pressures and curing temperatures, and have sufficient strength to bridge missing pipe segments and stretch to fit irregular pipe sections.
- C. The CIPP liner tube will be multiple layer construction with any layer not less than 1.5 mm thick. The wet-out fabric tube shall have a uniform thickness and excess resin distribution

which, when compressed at installation pressures, will meet or exceed the design thickness after cure.

- D. Prior to being inverted, the tube's outside layer shall be coated with an impermeable material compatible with the resin and fabric.
- E. The manufactured tube's exterior shall have distance markings along its length at regular intervals not to exceed 5 feet. Use these marks as a gauge to measure elongation during insertion. Should a reach's overall elongation exceed 5 percent, the liner tube shall be rejected and replaced.
- F. The tube shall be homogenous across the entire wall thickness, containing no intermediate or encapsulated layers. No material shall be included in the tube that may cause delamination in the cured CIPP. No dry or unsaturated layers shown by the color contrast between the felt fabric and the activated resin containing a colorant shall be visible upon inspection.
- G. Seams in the tube shall be stronger than the non-seamed felt material and shall meet the requirements of ASTM D5813.
- H. The CIPP's interior wall color after installation shall be a relatively light reflective color so that a clear detailed examination with CCTV equipment may be made. The hue of the color shall be dark enough to distinguish between fully resin saturated felt fabric and dry or resin lean areas.
- I. Resin: The resin shall be a corrosion resistant polyester or vinyl ester resin and catalyst system or epoxy and hardener system that, when properly cured within the tube composite, meets the requirements of ASTM F 1216, ASTM F 1743 or ASTM F 2019, the physical properties herein, and those which are to be utilized in the design of CIPP for this project. Resin shall produce CIPP which will comply with or exceed structural and chemical resistance requirements. Liner material and resin shall be completely compatible. Generally, resin shall not contain fillers, except those required for viscosity control, fire retardance, or increased strength, or with applications for which inert fillers would facilitate better heat transfer and retention during installation. The liner contractor may add up to 5 percent by mass of a thixotropic agent for viscosity control, which will not interfere with visual inspection.
- J. The felt tubing shall be vacuum impregnated with a thermosetting polyester resin and catalyst; vinyl ester resin and catalyst; or epoxy resin, inhibitors and hardener.
- K. The resins may contain pigments, dyes, or colorants which shall not interfere with visually inspecting cured lining. The resin quantity used for tube impregnation shall be sufficient to fill the volume of air voids in the tube with additional allowances for polymerization shrinkage and the resin loss through cracks and irregularities in the original pipe wall. Use a serial vacuum impregnation process (or equal) to provide maximum resin impregnation throughout the tube.
- L. The Contractor shall identify the wet-out facility where all CIPP linings under this Contract will be manufactured. All CIPP linings shall be manufactured from this designated wet-out facility throughout the entire Contract, unless specifically approved otherwise in writing by the Construction Manager.
- M. Metro or its representatives may inspect the CIPP lining during manufacturing and wet-out. The Metro and its representatives must be given an opportunity to witness the manufacturing for all CIPP linings for this project. If the Metro decides to inspect the CIPP lining manufacturing, the Contractor shall provide full access to witness the wet-out process and any and all information related to the manufacturing as requested without delay and without claims

about confidentiality or product privacy. Metro is responsible for costs associated with witnessing the CIPP lining manufacturing.

- N. Applying resin to the felt tubing (wet-out) shall be conducted under factory conditions using vacuum impregnation, and the materials shall be fully protected against UV light, excessive heat, and contamination at all times.
- O. Liners that are impregnated at the factory and transported to the project site in refrigerated trucks shall be installed as soon as possible and within no more than ten calendar (10) days after the date of impregnation at the factory.
- P. When cured, the CIPP lining shall form a continuous, hard, impermeable lining which is chemically resistant to any chemicals normally found in domestic sewage per Table x2.1 in ASTM F1216. The CIPP lining shall be chemically resistant to trace amounts of gasoline and other oil products commonly found in municipal storm sewers and soils adjacent to the sewer pipe to be lined. The CIPP lining shall provide the maximum available abrasion resistance.
- Q. The Contractor shall measure the existing pipelines in the field prior to ordering lining. The CIPP lining's length shall be as deemed necessary by the Contractor to effectively carry out inserting and sealing the CIPP lining at the outlet and inlet manholes.
 - 1. The CIPP lining tube shall be manufactured or fabricated to a size that will tightly fit the internal circumference of the sewer being rehabilitated after being installed and cured.
 - 2. The CIPP lining shall be able to fit into irregularly shaped pipe sections, through bends (up to 45 degrees), displaced host pipe joints and dips within the pipeline.
 - 3. Allowance for longitudinal and circumferential expansion shall be taken into account when sizing and installing the CIPP lining.
 - 4. The tube shall be properly sized to the existing pipe's diameter and the length to be rehabilitated and be able to stretch to fit irregular pipe sections or joints and negotiate bends.
 - 5. The Contractor shall verify the lengths in the field prior to ordering and prior to the impregnation of tube with resin to ensure that the tube will have sufficient length to extend entire length of the run, which is defined as the length of the existing host pipe measured from the interior walls of the manholes and/or from the ends of the pipe when/if the pipe extends into the manholes. The Contractor shall also measure the inside diameter and circumference of the existing pipelines at the face of each manhole in the field prior to ordering the liner so that liner can be installed in a tight-fitted condition with little or no wrinkling.
- R. The Contractor shall verify the proposed CIPP lining thicknesses and submit the associated calculations. The CIPP lining may be designed in accordance with the applicable ASTM F1216 provisions for "partially deteriorated gravity pipe conditions". The CIPP lining shall meet the following minimum design conditions, unless Metro agrees to their change or as noted on the Drawings:
 - 1. AASHTO H-20 Live Load with two trucks passing
 - 2. Constrained soil modulus of native soil in the pipe zone = 1,000 psi
 - 3. Soil weight with 120 pounds per cubic foot and a coefficient of friction of $Ku' = 0.130r$ shall be used for the installed depths.

4. The long-term flexural modulus used in the design calculations shall be estimated by multiplying the lowest short-term flexural modulus specified in the ASTM standards by a long-term retention of mechanical properties factor equal to 50 percent.
 5. Design safety factor = 2.0
 6. The groundwater depth used in the calculations should be the maximum depth from the ground surface to the pipe crown.
 7. Service temperature range shall be 40 °F to 100 °F.
 8. Maximum long-term deflection shall be 5 percent.
 9. Minimum pipe ovality shall be 2 percent.
 10. The CIPP lining thickness to be used shall be the largest thickness as determined by calculations for deflection, bending, buckling, and minimum stiffness.
 11. The CIPP shall be designed to withstand all imposed loads, including live loads and, if applicable, hydrostatic pressure. The liner shall have sufficient wall thickness to withstand all anticipated external pressures and loads that may be imposed after installation.
 12. Submit to the Construction Manager for approval the structural design.
- S. The CIPP lining shall be watertight.
- T. The CIPP lining shall provide a 50-year service life and shall have the following minimum initial and long-term properties:

Property	Test Method	Initial (psi)	Long-term (psi)
Flexural Strength	ASTM D790	4,500	2,250
Flexural Modulus of Elasticity	ASTM D790	300,000	150,000

Enhanced strength resins and composite CIPP systems may be used for sewers greater than 33 inches in diameter to reduce wall thickness and be more cost-effective. These systems must be submitted to the Construction Manager for specific approval.

2.02 END SEALS

- A. End seals shall be composed of hydrophilic rubber and molded or formed as a one-piece cylinder which, when installed, will form a 360 degree seal between the host pipe and the newly installed liner. Use of caulking in lieu of an end seal will not be allowed. Acceptable end seals are Insignia™ End Seals by LMK Enterprises, Hydrotite by Greenstreak, or approved equal.

PART 3 - EXECUTION

3.01 PRE-INSTALLATION

- A. The Contractor shall notify individual property owners at least 72 hours in advance, giving the date, start time, and estimated completion time for the work being conducted

- B. The Contractor shall clean each pipe length to be lined and shall dispose of any resulting material offsite.
- C. The Contractor shall conduct a pre-rehabilitation CCTV inspection for all sewers to be rehabilitated by CIPP lining methods in accordance with Section 33 01 51. The inspection shall be to verify the segment for rehabilitation, identify pipe defects, and to confirm additional needed point repair locations other than those indicated on the Drawings. The Contractor's project manager and/or superintendent shall review the pre-rehabilitation inspection videos to confirm the quality of the videos, and locations of point repairs to be performed. Only after the contractor has confirmed that the quality of the videos is adequate for a clear review of the pipeline, shall they be submitted to Metro. The Construction Manager will review pre-rehabilitation inspection videos to verify the segment for rehabilitation and confirm point repair locations to be performed by the Contractor. The Contractor may not proceed with CIPP lining installation until the Construction Manager has reviewed and approved the Contractor's pre-rehabilitation CCTV inspection data. A minimum of 5 working days shall be provided to review each pre-rehabilitation CCTV inspection data submittal.
- D. During the pre-rehabilitation CCTV inspection and prior to installing the CIPP lining, all protrusions greater than or equal to $\frac{3}{4}$ inch for 18-inch and larger diameter pipe shall be internally cut or ground down flush with the pipe wall using a robotic cutter specifically designed for this purpose. The internal cutter shall be able to cut cast iron, PVC, vitrified clay pipe, concrete pipe, ductile iron pipe, and Orangeburg pipe. All materials/cuttings shall be removed from the sewer and properly disposed.
- E. The Contractor shall provide flow bypass pumping. Lining installation shall not begin until the Contractor has installed the required plugs or a flow by-pass system and until all pumping facilities have been installed and tested under full operating conditions, including bypassing mainline and side sewer flows addressed. Once the lining process has begun, existing flows shall be maintained until the resin/felt tube composite has been fully cured, cooled down, fully televised, and the CIPP ends finished.
- F. The Contractor shall furnish and install the CIPP lining in the sewer's full length as shown on the Drawings. The CIPP lining installation shall be in complete accordance with applicable ASTM F1216 provisions and the manufacturer's recommendations.
- G. If the CIPP lining manufacturer believes the infiltration rate in the sewer segment is high enough to risk washing out the resin, the Contractor shall perform required measures to minimize infiltration prior to installation. If any infiltration runners or gushers as defined by NASSCO PACP are observed during the pre-CCTV inspection, the Contractor shall submit in writing for approval by the Construction Manager the methods and materials for mitigating any adverse impacts from the infiltration. Infiltration runners or gushers that are observed may be stopped by injecting a chemical hydrophilic grouting using a remote packer as an acceptable and preferred method or short cured-in-place internal repairs. If the pipe is larger than 33 inches in diameter, man-entry with hand-applied epoxy application can be performed to stop the infiltration.
- H. The Contractor shall for 33-inch and larger pipe with displaced and open host pipe joints greater than 2-inches shall hand-apply epoxy fillers under man-entry to smoothly transition the CIPP liner across the joint displacement areas for a distance equal to the displacement.
- I. The Contractor shall evaluate CIPP liner installations for the potential of adverse odor issues such as from styrene and implement measures, including, but not limited to, supplemental ventilation, service plugging, and monitoring in accordance with the *Odor Control Plan* and pertinent state and federal rules and regulations. The evaluations shall include issues that may occur from long duration installations, extended curing times, close proximity to buildings,

and/or resident's sensitivities, impairments, or known health conditions relative to respiratory issues.

- J. Throughout the construction and installation, the Construction Manager may elect to conduct independent odor monitorings, such as styrene concentration readings. The Contractor shall cooperate with the Construction Manager and the Construction Manager's representatives and allow full access to the project lining site and equipment.

3.02 INSTALLATION

- A. The CIPP shall be installed in appropriate dry weather conditions, low groundwater conditions and extended weather forecast with no precipitation to fully accomplish the CIPP installation without requiring major flow diversion equipment for the storm sewer system. The Construction Manager shall approve the tentative schedule 1 week prior to the installation and confirm 24 hours before CIPP inversion commencement. No CIPP installation shall be commenced with a chance of rain/snow or thunderstorms potential in the 3 day forecast.
- B. The CIPP lining may be installed via inversion using hydrostatic head or air pressure or pull-in methods in accordance with ASTM F1216 and manufacturer's recommendations. Pull-in methods shall use a thin film "preliner" to protect the CIPP liner from insertion damage.
- C. The Contractor shall install a hydrophilic seal at each manhole face prior to inverting or pulling in the uncured CIPP lining.
- D. If the CIPP lining does not fit tightly against the original pipe at its termination points, at no additional cost to Metro, the full circumference of the CIPP lining exiting the host pipe shall be filled with a resin mixture compatible with the CIPP and approved by the CIPP manufacturer. There shall be no groundwater leakage between the existing pipe and the CIPP lining at the manhole connection. Any leakage found shall be eliminated by the Contractor at no additional cost to Metro.
- E. The installed CIPP lining shall be cured using circulating heated water or steam in accordance with ASTM F1216 and manufacturer's recommendations with temperature monitoring at manholes and service openings if available.
- F. The resin-impregnated flexible felt tube lining shall be processed to affect the desired cure throughout the tube's length, extending full length from manhole to manhole(s). The resin shall be cured into a hard impermeable pipe of the minimum specified thickness, providing a structurally sound, uniformly smooth interior and tight-fitting lining within the existing pipe.
- G. Cool-down procedures shall be in accordance with ASTM F1216 and manufacturer's recommendations.
- H. UV cured CIPP will not be permitted without written approval from Metro and after reviewing the documentation to ensure the lining is compatible with all specifications and other related work, including any lateral lining systems.
- I. Temperature monitoring systems shall be required. This system shall be installed at the pipe invert per the manufacturer's recommended procedures. The temperature sensors shall be placed at intervals as recommended by the sensor manufacturer. Additional sensors shall be placed where significant heat sinks are likely or anticipated. The sensors, if installed, shall be monitored by a computer using a tamper proof database which can record temperatures at the lining interface and the host pipe. The Contractor shall provide the Construction Manager with access to the longitudinal temperature monitoring system data during the installation via

digital data, web-based or other approved methodology, and printed reports. Temperature monitoring systems shall be Zia Systems or Vericure by Pipeline Renewal Technologies.

- J. If cool-down is to be accomplished by introducing cool water into an inversion standpipe to replace the water being drained from a small hole made in the downstream end, cool the hardened pipe to a temperature below 100 °F (38 °C) before relieving static head in the inversion standpipe. When releasing static head, ensure a vacuum will not be produced that could damage the newly installed CIPP lining. When releasing static head, ensure the rate of heated water flow shall not be detrimental to the receiving system, water course or Cumberland River.
- K. Vent and/or exhaust noxious fumes or odors generated during and remaining after the curing process has been completed. This process shall remain in place at all manholes, laterals, etc., until noxious odors have dissipated to an acceptable level in accordance with OSHA requirements for the materials used and there is no potential health hazard left to the general public or the construction workers.
- L. Provide piping, pumps, valves, and other equipment to discharge curing water.
- M. All cutting and sealing of CIPP liner at manhole connections and/or walls shall provide watertight pipe and manhole seals. All cut edges of cured liner shall be thoroughly sealed with the same resin used in the liner. If a catalyst or hardener is used, it shall be compatible with the resin/catalyst used in liner previously. However, it shall not require an external heat source to begin exothermic reaction (curing). There shall be no leakage of groundwater into the manhole between the CIPP liner and the existing sewer pipe or between the existing sewer pipe and the manhole wall.
- N. The installed CIPP lining shall be continuous over the sewer line section's entire length and be free from visual defects such as foreign inclusions, dry spots, pinholes, fins, major wrinkles, and delamination. The lined invert and lower third of the pipe in normal flow depth shall be of particular concern to defect avoidance. The CIPP lining shall be impervious and free from any pipe leakage to the surrounding ground or from the ground to inside the lined pipe.

3.03 FIELD TESTING AND ACCEPTANCE

- A. Larger diameter sewers will be visually inspected only by CCTV for leaks during a period of high groundwater with a required outcome of no visible leaks. Any lining not able to meet this testing requirement shall be repaired and retested at no additional cost to Metro.
- B. Field acceptance for the CIPP lining shall be based on the Construction Manager's evaluation of the installation, including reviewing the CIPP lining curing data, the post-rehabilitation CCTV inspection data, the certified test data for the installed CIPP lining, and CIPP air testing results. All CIPP sample testing and repairs to the installed CIPP as applicable shall be completed and documented in written form before final acceptance.
- C. For every 1,000 linear feet of CIPP lining installed, the Contractor shall perform sampling and testing to determine the installed CIPP lining's flexural properties and thickness
- D. Tests shall be performed by an independent testing laboratory certified by the American Association for Laboratory Accreditation (A2LA). The Contractor shall submit to the Construction Manager the name and location for the independent testing laboratory, a certified statement from the laboratory indicating they are independent from and not associated with the Contractor in any way, and the ASTM certification for the independent testing laboratory.

- E. All expenses for sampling and testing the installed lining shall be paid by the Contractor. The cost for all manufacturers' testing to qualify products furnished to the project site shall be the Contractor's responsibility.
- F. Sampling and testing for the installed CIPP lining shall conform to the following requirements.
1. For sewers 18 inches in diameter and larger, a minimum of two plate samples formulated out of the same felt blend and resin mixture as the installed liner shall be prepared and cured in the downtube of the installation column.
 2. The CIPP lining thickness shall be measured in accordance with *ASTM D5813*. *Flexural properties shall be determined in accordance with ASTM D790*. The Contractor shall label and date all samples for shipping to the independent testing laboratory. The Construction Manager shall be copied on all transmittals to the independent testing laboratory. Testing results shall be submitted to the Construction Manager within 30 days after installing the CIPP lining or payment will be withheld.
1. Any CIPP lining not meeting the specified installed strength and/or thickness requirements, regardless of the amount below the specified requirements, shall not be approved for payment until the deficiency has been corrected by the Contractor in a manner approved by the Construction Manager at no additional cost to Metro. Options considered for correcting deficient CIPP lining installations include the following.
- a. Remove the existing CIPP lining and re-line the sewer.
 - b. Provide open-cut sewer replacement from manhole to manhole.
 - c. Re-line the sewer with the existing CIPP lining in place. Note that this will not be accepted if Metro determines that the sewer section has capacity concerns.
 - d. Accept the following penalties depending on the structural and thickness test results.
 - 1) If the tests are within 90 percent of the specification, the payment reduction shall be 10 percent of the bid price per item.
 - 2) If the tests are between 75 percent and 89 percent of the specification, then 75 percent of the bid price shall be paid.
 - 3) If the tests are below 75 percent, the Contractor must reline or replace the segment.
- G. The Contractor shall perform a post-rehabilitation CCTV inspection for all sewers rehabilitated using CIPP lining methods in accordance with Section 33 01 30. The post-rehabilitation CCTV inspection shall be performed following the CIPP lining installation. The Contractor's project manager and/or superintendent shall review the post-rehabilitation inspection videos to confirm the quality of the videos and of the installed CIPP. Only after the Contractor has confirmed that the video is of good quality shall the videos be submitted to the Construction Manager. If it is determined that any repairs are needed at any segment, a new CCTV inspection of the entire segment(s) shall be performed after the repairs have been completed.
1. The Construction Manager shall review and approve payment based on the Contractor having satisfactorily completed a lining free from significant defects. The finished lining shall be continuous between manholes and shall be free from visual defects such as

foreign inclusions, reverse curvatures, splits, flats, cracks, lifts, kinks, wrinkles, flats, dry spots, pinholes, shrinkage, crazing, leaks, and delamination. The maximum allowable size for wrinkle or bulge as shown in the inspection shall not exceed 3 percent of equivalent pipe diameter or 1 inch by visual measurement, whichever is smaller. No wrinkles will be allowed in the invert of the pipe between the 4:00 and 8:00 o'clock positions.

- a. The Contractor will be responsible for removing and repairing, at Contractor's expense, all such defects in a manner that is satisfactory to the Construction Manager.
- b. Shrinkage of the CIPP liner's length of more than one (1) inch for pipe diameters less than 18 inches and of more than two (2) inches for pipe diameters greater than or equal to 18 inches from the face of the manhole shall be repaired with a fiberglass reinforced CIPP spot repair at no cost to Metro.

H. The cured CIPP lining and all pipe-to-manhole connections shall be watertight and free from infiltration.

3.04 MEASUREMENT AND PAYMENT

A. Payment

1. Payment for CIPP lining shall be made at the contract unit price per linear foot for each size as stated in the Bid, complete in place in accordance with the Drawings and specifications. Payment will be based on the actual number of feet installed, as measured by the Construction Manager. The pipe will be measured horizontally on the surface from center-to-center of manholes or face of headwall structures to the nearest 0.1 foot.
2. The price paid per linear foot for pipe lining shall include full compensation for furnishing labor, materials, tools, equipment, and incidentals necessary to furnish, install, and test the CIPP lining plus traffic control, flow bypassing, water control, manhole connections, cleaning, sewer cleaning materials disposal, final inspection, protecting existing utilities and adjacent property, and all required surface restoration work and traffic control, complete in place, as shown on the Drawings and specified herein.

3.05 CLEANUP

- A. Upon the installation work and testing acceptance, restore the project area affected by the operations to a condition at least equal to what existed prior to the work.

END OF SECTION

SECTION 33 01 51 - PRE-REHABILITATION SANITARY SEWER CCTV INSPECTION

PART 1 - GENERAL

1.01 DESCRIPTION

- A. When preparing each sewer segment to be relined or replaced, furnish all necessary labor, materials, equipment, services, and incidentals required to visually inspect designated sewer line sections, including, but not limited to, recording and playback equipment, materials and supplies required for closed-circuit television (CCTV).
- B. Perform the inspection on one sewer line section at a time (i.e., manhole-to-manhole) to complete the following:
 - 1. Document the sewer's general condition
 - 2. Confirm the cleaning is sufficient for relining
 - 3. Determine accurate service lateral locations
 - 4. Determine any other significant pipe conditions that may be necessary to repair to properly and successfully install the cured-in-place pipe (CIPP) liner and other lining materials
- C. Make digital CCTV video recordings of the inspections. Supply recordings and printed inspection log copies to the Construction Manager. Pre-rehabilitation CCTV inspection for all sewer segments and service laterals is required.
- D. Contractor may have to perform cleaning, point repairs, and obstruction removal or remove protruding service connections to complete pre-rehabilitation CCTV inspection.

1.02 RELATED WORK

- A. Sewer line cleaning is included in Section 33 35 20.
- B. CIPP lining is specified in Section 33 01 40.

PART 2 - PRODUCTS

2.01 EQUIPMENT

- A. The television camera(s) used for the inspection shall be specifically designed and constructed for such inspections.
- B. Camera lighting shall be suitable to allow a clear picture for the pipe's entire periphery.
- C. The camera shall be operative in 100 percent humidity conditions.
- D. The camera, television monitor, and other video system components shall be able to produce a minimum 500-line resolution video picture.

- E. Picture quality and definition shall be to the Construction Manager's satisfaction. If the quality is unsatisfactory, the inspection shall be performed again with the appropriate Construction Manager designated changes made at no additional cost to Metro.
- F. The television inspection equipment shall have an accurate footage counter that shall display on the monitor the camera's exact distance from the starting manhole's centerline or the connection with sewer main.

PART 3 - EXECUTION

3.01 TELEVISION INSPECTION

- A. Inspect sewer pipelines with pan, tilt, and zoom conventional television imagery to record relevant pipeline features and defects. Pipeline inspection shall be carried out in a format reviewed by the Construction Manager prior to the commencement of the inspection. Perform cleaning in accordance with Contract Document requirements.
- B. CCTV operators shall be NASSCO PACP certified and have a current certification.
- C. If television inspection for an entire section cannot be successfully performed from one manhole, perform a reverse setup to obtain a complete television inspection.
- D. Perform sewer televising work as necessary using NASSCO PACP coding to thoroughly document the condition for all sewers, service lateral connections, service lateral conditions, manhole corbel, barrel, and cone-sections in the study area. To achieve this, the CCTV camera operator shall stop the camera in each manhole invert and shall pan and zoom up the manhole to obtain the best possible image of the manhole, including the cone and corbel section(s).
- E. The quality and coding for all work specified in this Section shall meet or exceed the National Association of Sewer Service Companies (NASSCO) Recommended Specifications for Sewer Collection System Rehabilitation (latest edition) requirements. Applicable Section portions which inadvertently fall below those standards shall be corrected and maintained at the NASSCO standards as a minimum requirement, at no additional cost to MWS.
- F. Document all internal sewer via digital video recordings, television logs, digital photos.
 - 1. If the video is poor quality due to the chosen media, Metro reserves the right to require re-submittal on a different media.
 - 2. Create separate MPEG 4 H264 files for each sewer line segment.
 - 3. In a reverse setup, store such inspection in a separate MPEG 4 H264 file.
 - 4. MPEG 4 H264 files shall be written to an external media for delivery to the Construction Manager.
 - 5. Each media shall be labeled, at a minimum, with the following information: owner's name, project name, MWS project number, creation date, prime contractor's firm name, and TV inspection contractor's firm name.

- G. Digital video shall be defined as ISO-MPEG Level 4 (MPEG-4) coding with a 352-pixel (x) by 240-pixel (y) (minimum) resolution and a 30 frames per second encoded frame rate.
 - 1. The digital recording shall include audio and video information which accurately reproduces the original video inspection picture and sound.
 - 2. The digital recording's video portion shall be free from electrical interference and shall produce a clear and stable image.
 - 3. The audio portion shall produce a clear and discernible oral report, sufficiently free from background and electrical noise.
- H. Separate digital video recordings shall be made for each sewer section and shall be properly identified via continuous on-screen display and voice-over recording with the following:
 - 1. MWS Project number
 - 2. Upstream MH ID and downstream MH ID
 - 3. Sewer segment being inspected
 - 4. Inspection date
 - 5. Project name
 - 6. Distance along the reach from the entering manhole
- I. Contractor shall coordinate with Construction Manager prior to commencing work to ensure identification is accomplished in a manner acceptable to MWS. If the video and/or audio recording is poor quality, the Metro has the right to require a re-submittal of the affected sewer sections and service laterals. No payment will be made until an acceptable video and audio recording is made and submitted to and accepted by the Construction Manager.
- J. Inspection software to be used shall be Cues GraniteNet in the most current MWS version.
- K. The CCTV equipment/software shall be able to produce digitized images for all sewer line defects, manhole defects, sewer line service connections in .jpeg format. Plan to take digital still images of each defect, construction features, and service connection to clearly depict it. More images may be necessary depending on the lined pipe condition.
- L. Provide CCTV inspection data via external media. Data shall be recorded and provided in a current version of the NASSCO PACP Exchange format. The data shall specifically include video indexing for all observations. Data to be submitted shall include:
 - 1. NASSCO PACP exchange database file
 - 2. .jpeg files (still photos)
 - 3. MPG 4 H264 -files (video) for each pipe segment
- M. Provide a complete television inspection for the upstream and downstream manholes. The CCTV operator shall pan and zoom up the manhole from the invert for each manhole and obtain the best possible image of the manhole, including cone and corbel sections. In addition, 3 still digital photos shall be taken for each pipe connection within each manhole.

The CCTV operator shall zoom in on each pipe connection so the photos capture each pipe connection's size, location, and approximate elevation.

- N. Whenever prevailing conditions allow, position the camera head to reduce the risk of picture distortion. In circular sewers, position the camera lens centrally (i.e., in prime position) within the sewer. In noncircular sewers, picture orientation shall be taken at mid-height, unless otherwise agreed, and centered horizontally. Direct the camera lens along the sewer's longitudinal axis when in prime position. A +/- 10 percent positioning tolerance of the vertical sewer dimension shall be allowed when the camera is in prime position.
- O. Perform television inspections during low flow conditions. The Construction Manager will reject any television inspection that does not produce an effective sewer pipe survey due to flow conditions or for any other reason. Sewer flow shall be controlled so that the invert of pipe is fully visible.

3.02 PROCEDURE

- A. The camera shall be moved through the line in either direction at a uniform rate, stopping when necessary to ensure it properly documents the sewer's or service lateral's condition.
 - 1. At no time shall the television camera travel at a speed greater than 30 feet per minute.
 - 2. To move the camera through the sewer line, use manual winches, power winches, TV cable, and powered rewinds or other devices that do not obstruct the camera's view or interfere with proper sewer condition documentation.
 - 3. If, the television camera will not pass through the entire main sewer line section during the inspection operation, the equipment shall be removed and repositioned so the inspection can be performed from the opposite manhole.
 - 4. All set-up costs for the inspection shall be included in the unit prices bid.
- B. The measurement must be accurate to within 0.2 foot for the length of the sewer line section being inspected.
 - 1. Significant defect locations that may require internal remediation or excavation or that may prohibit the use of CIPP lining shall be measured and marked above ground using an appropriate measurement device. These defects and markings must be noted on the drawings as they are being marked in the field. The Construction Manager must be notified about the drawings, and a copy of these drawings must be submitted to the Construction Manager within 5 working days after the notes are added to the drawings. The Construction Manager may choose to accompany the Contractor during the marking activity.
 - 2. Marking on cable or the like, which would require interpolation for manhole depth, shall not be allowed.
 - 3. Accuracy for the measurement meters shall be checked daily using a walking meter, roll-a-tape, or other suitable device. The accuracy shall be satisfactory to the Construction Manager.
- C. The camera height shall be adjusted so the camera lens is always centered (12-inch inside diameter or larger) in the pipe being televised. Control flow so the flow depth shall not exceed 20 percent of pipe's diameter.

- D. Lighting system shall be adequate for quality video.
- E. At the direction of the Construction Manager, the Contractor shall inspect segments by push camera CCTV inspection from existing cleanouts to the service lateral if a lateral launch from the main is unsuccessful or if the main is excessive in length and requires both views.

3.03 RECORDING FIELD OBSERVATIONS

A. Television Inspection logs

1. Electronic location records shall be kept which shall clearly show the location, in relation to adjacent manholes, for each discovered infiltration source.
2. Keep other significant data, including building and house service connection locations, estimated infiltration from such services, transitions, bends, and any significant structural defects or construction features that could pose an issue for the installation or cause any lining defects. A copy of such records in a summary spreadsheet format shall be supplied to the Construction Manager prior to initiating work on each segment.

B. Digital CCTV Video

1. Digital CCTV video shall supply a visual and audio record of the sewer service connections, an estimate for infiltration from such services, and any significant structural defects or construction features that could be an issue for the installation or cause any lining defects.
2. The Contractor shall provide a digital copy of this video for each pipe segment.
3. These videos are essential for payment.
4. The Contractor shall keep a copy of the video for 30 days minimum after completing the project.

END OF SECTION

SECTION 33 35 20 – SEWER LINE CLEANING FOR PREPARATION OF SEWER REHABILITATION

PART 1 - GENERAL

1.01 DESCRIPTION

- A. Clean all sewer pipe for proposed CIPP lining rehabilitation.
- B. Cleaning shall include properly high-pressure water jetting and flushing sewers and manholes prior to inspection by closed circuit television (CCTV), pipeline rehabilitation, and testing operations.
- C. The goal is to remove all debris, roots, intruding services, deposits, and other blockages to a 95 percent minimum open area so the CIPP can be successfully installed without any significant installation issues or post lining defects. On all sewers, perform sewer cleaning work to an acceptable level as necessary to perform a thorough television inspection of the sewer and to install a CIPP liner. If the pipe condition is such that cleaning may cause a potential collapse, the pipe shall be televised without attempting to clean it to the 95 percent condition, pending Construction Manager's approval.
- D. Cleaning may involve preparatory or light sewer cleaning (small amounts of debris and/or light root growth existing within the sewer line) or heavy sewer cleaning (large amounts of debris, grease, large size stones, and bricks existing within the sewer line).
 - 1. The bid price for pipeline rehabilitation shall include preparatory cleaning for all sewers completely. Preparatory or light cleaning is defined as all cleaning up to and including 3 high-pressure water-jetting passes.
 - 2. If the sewer is still not clean after 3 high-pressure water-jetting passes, inform the Construction Manager about the condition and the reason(s) for the failure to fully clear the line. The Construction Manager may direct heavy cleaning of the problem sewer section.
- E. Cleaning shall dislodge, transport, and remove all sludge, mud, sand, gravel, rocks, bricks, grease, roots, sticks, and all other debris from inside the sewer pipe and manholes.

1.02 RELATED WORK

- A. Pre-rehabilitation sewer television inspection is specified in Section 33 01 51.
- B. Cured-in-place pipe lining (CIPP) is specified in Section 33 01 40.

PART 2 - PRODUCTS

2.01 MATERIALS

- A. High Velocity Hydro-Cleaning Equipment shall have the following:
 - 1. A minimum 750-foot high pressure hose
 - 2. Two or more high velocity nozzles able to produce a scouring action from 15 to 45 degrees in all size lines to be cleaned

3. A high velocity gun for washing and scouring manhole walls and floor
4. Ability to produce flows from a fine spray to a long distance solid stream
5. A water tank, auxiliary engines and pumps and a hydraulically driven hose reel
6. Equipment operating controls located above ground

PART 3 - EXECUTION

3.01 PERFORMANCE

- A. Cleaning Precautions: During sewer cleaning operations, satisfactory precautions shall be taken when using cleaning equipment.
 1. When hydraulically propelled cleaning tools (which depend on water pressure to provide their cleaning force) or tools which retard the flow in the sewer line are used, precautions shall be taken to ensure the water pressure created does not damage or cause flooding of public or private property being served by the sewer.
 2. When it is necessary to use water from fire hydrants in order to avoid delays in normal work procedures, the water shall be conserved and not used unnecessarily. No fire hydrant shall be obstructed. Access to the fire hydrant shall be available at all times.
- B. Sewer Cleaning
 1. The designated sewer manhole sections shall be cleaned using hydraulically propelled, high velocity jet equipment.
 2. Cleaning equipment selection shall be based on the conditions of lines at the time the work commences.
 3. The equipment and methods selected shall be satisfactory to the Construction Manager.
 4. The equipment shall be able to remove dirt, grease, rocks, sand, and other materials and obstructions from the sewer lines and manholes.
 5. If cleaning of an entire section cannot be successfully performed from one manhole, the equipment shall be set up on the other manhole and cleaning again attempted. If successful cleaning still cannot be performed or the equipment fails to traverse the entire manhole section, it will be assumed a major blockage exists, and the cleaning effort shall be repeated.
- C. Cleaning equipment selection shall be based on the conditions of the manholes and sewer lines at the time the work commences based on the pre-construction CCTV inspection to be conducted.
 1. Light cleaning (small amounts of debris existing within the sewer line)
 - a. Use high-pressure water jetting equipment (3 passes), brushes, and swabs.

b. "Light Cleaning" will be defined and managed as follows:

- 1) Sewer reaches that do not require heavy cleaning, as defined below, and produce little or no debris shall be categorized as "light cleaning."
- 2) Costs related to light cleaning such sewers shall be included in bid unit prices for CCTV and CIPP Lining.

D. Use properly selected equipment to remove all dirt, grease, rock, and other deleterious materials and obstructions.

E. Protect existing sewer lines from damage caused by improper using cleaning equipment.

F. Take precautions to avoid damage or flooding to public or private property being served by the line being cleaned.

G. Material Removal

1. Remove all solids and semi-solids at the downstream manhole in the section being cleaned.

H. Material Disposal

1. Remove from the site and properly dispose of all solids or semi-solids recovered during the cleaning operation.
2. The Contractor shall be responsible for properly disposing of all collected material.

3.02 WATER

A. Water for all construction operations shall be available from identified Metro fire hydrants at normal commercial rates.

B. Water usage shall be in accordance with Metro backflow and metering polices.

3.03 FIELD QUALITY CONTROL

A. Acceptance for this work portion shall depend on the results from the pre-rehabilitation television inspection.

B. The cleaning goal is to remove all necessary debris, roots intruding services, deposits, and other blockages to a 95 percent minimum open area so the CIPP can be successfully installed without any significant installation issues or post lining defects due to cleaning quality.

C. Lines not acceptably clean as to permit television inspection shall be re-cleaned and re-inspected at no additional cost to Metro.

3.04 CLEANUP

A. Upon cleaning acceptance, restore the project area affected by the operations to a condition at least equal to that existing prior to the work.

END OF SECTION



STATE OF TENNESSEE
DEPARTMENT OF ENVIRONMENT AND CONSERVATION
DIVISION OF WATER RESOURCES

William R. Snodgrass Tennessee Tower
312 Rosa L. Parks Avenue, 11th Floor
Nashville, Tennessee 37243
PHONE: 615-532-0191 FAX: 615-532-0686

May 8, 2019

Mr. Michael Morris, PE
Metro Water Services
1600 Second Avenue North
Nashville TN 37208-2206

RE: Metro Water Services (PWSID# 0000494)
Davidson County
Project Number DW 19-0535
Standard Specifications for Water Lines

Dear Mr. Morris:

This letter acknowledges receipt of one set of standard construction specifications for the Metro Water Services. We have reviewed the specifications and found them satisfactory. The specifications have been stamped to indicate our approval. This approval is valid for three years and will expire on May 8, 2022. You must then either resubmit the standard specifications or request in writing for extension of approval.

The approved standard specifications may be referenced on any plans submitted for approval before the expiration date. We are retaining one copy of the specifications for our records, and are returning the remaining copies to you. All addenda, revisions or correspondence concerning these specifications should contain the DW Project Number as referenced. If you have any questions contact us at (615) 532-0191.

Very truly yours,

R. William Hench, P.E.
Drinking Water Engineering
Division of Water Resources

RWH/ DWS-35

cc: Nashville Field Office – Water Resources

METRO WATER SERVICES SPECIFICATIONS

MWS Water and Sewer Standard Specifications

DW 19 0535

APPROVAL EXPIRES
MAY 08 2012
TENN. DEPT. OF ENVIRONMENT & CONSERVATION
DIVISION OF WATER RESOURCES

APPROVED FOR CONSTRUCTION
THE DOCUMENT BEARING THIS STAMP HAS BEEN PREPARED AND REVIEWED BY THE
TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION
DIVISION OF WATER RESOURCES
AND IS HEREBY APPROVED FOR CONSTRUCTION BY THE COMMISSIONER

MAY 08 2019

THIS APPROVAL IS VALID FOR ONE YEAR
THE APPROVAL SHALL NOT BE CONSIDERED AS CREATING A PROHIBITION OF CORRECT
OPERATION OR AS WARRANTING BY THE COMMISSIONER THAT THE APPROVED FACILITIES
WILL REACH THE DESIGN GOAL FOR THE SUBMITTALS

BY _____ TITLE _____





STATE OF TENNESSEE
DEPARTMENT OF ENVIRONMENT AND CONSERVATION
DIVISION OF WATER RESOURCES

William R. Snodgrass - Tennessee Tower
312 Rosa L. Parks Avenue, 11th Floor
Nashville, Tennessee 37243-1102

June 6, 2019

Mr. Michael D. Morris, P. E.
Metro Water Services Nashville
e-copy: mike.morris@nashville.gov
1600 Second Avenue, North
Nashville, TN 37208

Subject: **Nashville**
County: Davidson
Wastewater Project Number: 19.0269
Job Number:
Project: MWS Standard Specification

Dear Mr. Morris:

The Tennessee Department of Environment and Conservation, Division of Water Resources, acknowledges the receipt of your engineering documents on May 7, 2019.

Review of these standard sanitary sewer specifications shows that they are in conformance with our guidelines. Therefore, they have been stamped "APPROVED". This approval will remain in effect until June 6, 2024.

To expedite matters, please reference the assigned wastewater project number 19.0269 on any future correspondence. If we may be of any assistance, please feel free to contact Mr. Mahendra Upadhyaya at (615) 253-3399 or by E-mail at Mahendra.Upadhyaya@tn.gov.

Sincerely,

Vojin Janjić
Manager, Water-Based Systems

cc: Water-Based Systems File
Mr. Tim Jennette, Multi-Program Coordinator, TDEC Division of Water Resources, tim.jennette@tn.gov

METRO WATER SERVICES SPECIFICATIONS

MWS Water and Sewer Standard Specifications

APPROVED

TN Dept. of Env. & Conservation

MAY 07 2019

Division of Water Resources

APPROVED FOR CONSTRUCTION
THE DOCUMENT BEARING THIS STAMP HAS BEEN RECEIVED AND REVIEWED BY THE
TENNESSEE DEPARTMENT OF ENVIRONMENT AND CONSERVATION
DIVISION OF WATER RESOURCES
AND IS HEREBY APPROVED FOR CONSTRUCTION BY THE COMMISSIONER

JUN 06 2019

THIS APPROVAL IS VALID FOR ONE YEAR
THE APPROVAL SHALL NOT BE CONSTRUED AS CREATING A PRESUMPTION OF CORRECT
OPERATION OR AS WARRANTING BY THE COMMISSIONER THAT THE APPROVED FACILITIES
WILL REACH THE DESIGN GOAL FOR THE COMMISSIONER

BY *[Signature]* TITLE *EAS*

TN Dept. of Env. & Conservation
MAY 07 2019
Division of Water Resources

APPROVAL EXPIRES
JUN 06 2024
TENN DEPT OF ENVIRONMENT & CONSERVATION
DIVISION OF WATER RESOURCES

WPN19-0269

MICHAEL D. MORRIS
REGISTERED ENGINEER
OF AGRICULTURE
AND COMMERCE
No. 101315
STATE OF TENNESSEE



METRO WATER SERVICES SPECIFICATIONS

MWS Water and Sewer Standard Specifications




TABLE OF CONTENTS

Section	Section Pages	Page Number	Applies To	
Title Page	i	i	Water	Sewer
Table of Contents	ii	ii	Water	Sewer
01 12 00 Contractor's Use of Premises	3	1	Water	Sewer
01 20 00 Measurement and Payment	3	4	Water	Sewer
01 31 00 Coordination and Meetings	2	7	Water	Sewer
01 32 16 Construction Progress Schedule	2	9	Water	Sewer
01 32 33 Photographic Documentation	2	11	Water	Sewer
01 33 00 Submittal Procedures	2	13	Water	Sewer
01 35 23 Health and Safety	3	15	Water	Sewer
01 41 00 Regulatory Requirements	2	18	Water	Sewer
01 45 00 Quality Assurance and Quality Control	3	20	Water	Sewer
01 51 00 Temporary Utilities	2	23	Water	Sewer
01 52 00 Temporary Facilities	2	25	Water	Sewer
01 55 26 Traffic Control	2	27	Water	Sewer
01 57 19 Environmental Controls	5	29	Water	Sewer
01 58 00 Temporary Project Identification	3	34	Water	Sewer
01 66 00 Product Storage and Handling	2	37	Water	Sewer
01 77 00 Closeout Procedures	2	39	Water	Sewer
01 78 39 Project Record Documents	1	41	Water	Sewer
03 30 00 Cast In Place Concrete	11	42	Water	Sewer
31 50 00 Trench Safety Systems	2	53	Water	Sewer
32 10 00 Paving and Roadway Restoration	2	55	Water	Sewer
32 16 13 Concrete Curb and Gutter	1	57	Water	Sewer
32 16 23 Concrete Sidewalk, Driveway, and Median	1	58	Water	Sewer
32 17 26 Detectable Warnings	1	59	Water	Sewer
32 90 00 Landscaping	3	60	Water	Sewer
33 00 01 Water Mains	10	63	Water	
33 05 16.17 Valve Boxes, Meter Boxes, and Vaults	2	73	Water	Sewer
33 11 00.11 Polyvinyl Chloride (PVC) Pipe and Fittings	3	75	Water	Sewer
33 11 13.13 Ductile Iron Pipe and Fittings	5	78	Water	Sewer
33 12 13 Water Service Lines and Connections	3	83	Water	
33 12 16.07 Blow Off Valves	2	86	Water	
33 12 16.09 Pressure Reducing Valves	2	88	Water	
33 12 16.11 Gate Valves	3	90	Water	
33 12 16.17 Tapping Sleeve and Valve	2	93	Water	
33 12 16.19 Air Release and Vacuum Relief Valves	2	95	Water	Sewer
33 12 16.21 Altitude Valves	2	97	Water	
33 12 16.23 Corporation Stops	1	99	Water	
33 12 16.25 Check Valves	2	100	Water	
33 12 19 Fire Hydrant Assembly	5	102	Water	
33 12 33 Water Meters	5	107	Water	
33 13 10 Disinfection of Water Mains	1	112	Water	
33 14 13 Acceptance Testing for Water	3	113	Water	
33 31 00 Gravity Sewer Mains	9	116		Sewer
33 31 13.17 Reinforced Concrete Pipe and Fittings	3	125		Sewer
33 31 51 Bypass Pumping	6	128		Sewer
33 31 61 Acceptance Testing for Sanitary Sewers	11	134		Sewer
33 33 00 Low Pressure Sanitary Sewers	10	145		Sewer
33 33 13 Grinder Pumps	3	155		Sewer
33 34 00 Sewer Force Mains	8	158		Sewer
33 39 13 Manholes	9	166	Water	Sewer

SECTION 01 12 00
CONTRACTOR'S USE OF PREMISES

PART 1: GENERAL

1.01 SCOPE

- A. Contractor's Use of Premises

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit agreements with private property owners to access or use property related to the project.

1.03 MEASUREMENT AND PAYMENT

- A. Consider expenses for contractor's use of premises incidental to the Work with no separate payment allowed.
- B. If damages occur, restore to pre-construction condition or an approved betterment at no cost to MWS.

1.04 GENERAL

- A. Before beginning Work coordinate working hours with the proper agencies.
- B. At least forty-eight hours but not longer than two weeks prior to construction in any approved right of entries, notify in writing MWS and the affected properties.
- C. Dispose of waste materials at Metro approved sites.
- D. Do not burn waste materials on the project site.

1.05 RIGHT-OF-WAYS

- A. Confine access, operations, and storage areas to properly approved right of entries; trespassing on abutting property or other areas is not allowed.
- B. Maintain access for emergency vehicles including access to fire hydrants.
- C. Avoid obstructing drainage ditches or inlets; when obstruction is unavoidable due to requirements of the Work, provide regulatory approved grading and temporary drainage structures to maintain unimpeded flow.
- D. Locate and protect private lawn sprinkler systems that may exist on right of entries within the site. Repair or replace damaged systems to condition equal to or better than pre-construction condition.
- E. Perform daily cleanup of all disturbed areas. Keep streets, driveways, and sidewalks clean of dirt, debris, and scrap materials. Do not leave buildings, roads, streets, or other construction areas unclean overnight.

1.06 PRIVATE PROPERTY NECESSARY FOR THE WORK

- A. Where the Work encroaches upon private property, MWS will obtain necessary permits, approvals, contracts, right of entries, and/or easements.
 - B. Comply with all stipulations outlined in agreements between the property owner and MWS and the limits shown on the Drawings and/or conditions described.
 - C. Repair or replace any damages to preconstruction condition or better.
- 1.07 PRIVATE PROPERTY CONVENIENT FOR THE WORK
- A. Obtain written agreements from private property owners for additional areas deemed convenient but not necessary for the Work and submit a copy of the agreement to MWS. Such written agreements shall comply with all Metro ordinances and restrictions.
 - B. Make arrangements for temporary use of private properties and indemnify and hold harmless MWS against claims or demands arising from use of properties outside of rights-of-way.
 - C. Repair or replace any damages to preconstruction condition or better.
- 1.08 LOCAL STREETS AND ALLEYS
- A. Secure permits and obtain operation procedures from the Metropolitan Department of Public Works before closing or starting construction within the right-of-way of any street or alley.
 - B. Construct and maintain temporary detours, ramps, and roads to provide traffic flow when use of local roads or streets is closed by necessities of the Work.
 - C. Provide mats or other means to prevent overloading or damage to existing roadways from tracked or heavy equipment.
 - D. Maintain ingress/egress to driveways or entrances at all times.
- 1.09 STATE AND FEDERAL RIGHT OF WAY
- A. Where the Work encroaches upon the right of way under the jurisdiction of Tennessee Department of Transportation (TDOT), MWS will obtain necessary permits, approvals, contracts, and/or easements.
 - B. Comply with stipulations outlined in agreements between TDOT and MWS and permit conditions.
- 1.10 RAILROAD RIGHT OF WAY
- A. Where the Work encroaches upon the right-of-way of a railroad company, MWS will obtain necessary permits, approvals, contracts, and/or easements.
 - B. Comply with stipulations outlined in agreements between the railroad company and MWS.

- C. Furnish insurance documentation and satisfy requirements of the railroad company prior to entering the railroad right-of-way.
- D. Pay expenses and/or charges for the monitoring, flagging, inspection, and/or other services assessed by the railroad company unless specifically indicated as a pay item in the Bid Schedule.

1.11 OTHER UTILITIES AND OTHER ENTITIES

- A. Where the Work encroaches upon the right-of-way and/or jurisdictional authorities of other utilities or entities, MWS will obtain necessary permits, approvals, contracts, and/or easements.
- B. Comply with stipulations outlined in agreements between other utilities or entities and MWS.
- C. Satisfy requirements of other utilities or entities prior to entering the right-of-way.
- D. Pay expenses and/or charges for the monitoring, flagging, inspection, and/or other services assessed by other utilities or entities unless specifically indicated as a pay item in the Bid Schedule.

PART 2: PRODUCTS

2.01 NOT USED

PART 3: EXECUTION

3.01 NOT USED

END OF SECTION

SECTION 01 20 00
MEASUREMENT AND PAYMENT

PART 1: GENERAL

1.01 SCOPE

- A. Measurement and payment including conditions for nonconformance and nonpayment for rejected products or workmanship.

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit items as described in individual specification sections.

1.03 MEASUREMENT AND PAYMENT

- A. Submit actual quantities and measurements installed or performed, verified by MWS, for payment only.
- B. Consider quantities on the Bid Schedule estimates; actual quantities may vary.
- C. If the actual Work requires more or less quantity indicated on the Bid Schedule, provide the required quantities at the unit prices contracted.
- D. Obtain MWS written approval before installing or performing Work that exceeds quantities on the Bid Schedule.

1.04 MEASUREMENT OF THE WORK

- A. Measure the Work according to the units indicated on the Bid Schedule and individual specification sections.
- B. Use a method to measure the Work that is an accepted standard practice when not specifically outlined in individual specification sections.
- C. Supply access to the Work for MWS to verify measurements.
- D. Verify measurements of the Work with MWS on a daily basis.

1.05 PAYMENT FOR THE WORK

- A. Consider full compensation for the Work the unit price multiplied by the number of items installed complete in place and ready for use including all incidentals as described in individual specification sections.
- B. Make claims for compensation only for items specifically included in the Bid Schedule. Claims for compensation of Work not covered in the list of item with unit prices contained in the Bid Schedule will not be accepted.
- C. Recognize that a retainage percentage of payments may be withheld by other provisions of the Contract Documents.

1.06 NONCONFORMING OR REJECTED WORK

- A. Remove and replace the Work, or portions of the Work, rejected or not, conforming to the Contract Documents at no cost.
- B. Generally nonconforming work will not be accepted.
- C. If MWS decides it is not practical to remove and replace the nonconforming Work, lower the unit price, provide an extended warranty, and/or modify the nonconforming Work to MWS satisfaction. MWS will provide written official documentation to accept nonconforming work and/or adjustments of payment of nonconforming work. Verbal acceptance of nonconforming or rejected work will not be binding.

1.07 ALLOWANCES AND CONTINGENCIES

- A. Consider allowances and contingencies specified in the Bid Schedule a method to pay the cost of items that MWS could not establish accurate quantities, a detailed scope of work, and/or items that may or may not be needed for completion of a project.
- B. Submit a written proposal with a cost quote for the need to use an allowance and/or contingencies to MWS and obtain written approval from MWS prior to performing the Work. Fractional use of an allowance and/or contingencies may be utilized.
- C. Utilize the following paragraphs for clarification for allowances and/or contingencies appearing in the Bid Schedule and disregard the following paragraphs for allowances and/or contingencies not found in the Bid Schedule. Understand that payment for allowances and/or contingencies not appearing in the Bid Schedule will not be allowed.
 - 1. Contingency for Unforeseen Work Elements: This contingency, not shown or specified on the Drawings and Specifications bid and not included by another item in the Bid Schedule, may be required in the event the MWS approves the need for additional work deemed to be necessary for the successful completion of the Work.
 - 2. Allowance for Additional Traffic Control: This allowance has been established as a means of payment for traffic control or special flagging that is required by a regulatory agency and approved by MWS that is above and beyond the baseline traffic control that is specified in the Special Provisions and/or Bid Schedule. If this allowance is specified in

the bid schedule but a baseline traffic control has not been specified, the allowance may only be utilized with MWS written approval.

3. Allowance for Permits: This allowance has been established as a means of payment for permits fee cost that are required for the completion of the Work. This allowance will be directly reimbursed with presentation of an invoice from the regulatory agency. Regulatory fines will not be paid by this allowance.
4. Allowance for Water Usage to Test and Disinfect Water Mains: This allowance has been established as a means to reimburse for water usage necessary to test and disinfect water mains. This allowance will not be permitted when re-disinfection and refilling is required due to a noncompliant sample. This allowance will not be permitted when refilling is necessary due to a failed hydrostatic pressure test or other retest done for acceptance testing for water mains. This allowance will directly reimburse, with no markup, for metered water utilizing a Water Services issued water meter and backflow prevention device directly associated with this project upon the presentation of an invoice from Water Services.
 - A. Submit evidence of payment for services resulting from the use of an allowance and/or contingency to MWS prior to its inclusion in the invoice for the progress payments.
 - B. When using allowances and/or contingencies, only receive payment for completed work authorized by MWS.

PART 2: PRODUCTS

2.01 NOT USED

PART 3: EXECUTION

3.01 NOT USED

END OF SECTION

SECTION 01 31 00
COORDINATION AND MEETINGS

PART 1: GENERAL

1.01 SCOPE

- A. Coordination and Meetings

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit items related to this Section as found described in the other sections of the Specifications.

1.03 MEASUREMENT AND PAYMENT

- A. Consider expenses for coordination and meetings incidental to the Work with no separate payment allowed.

1.04 COORDINATION

- A. Coordinate with other utilities in a manner that promotes an efficient and orderly sequence of construction.
- B. Perform a TN One Call in accordance with TCA 65-31-101 through TCA 65-31-113 before starting construction.
- C. Contact other entities identified at the Preconstruction Meeting before starting construction including, but not limited to: Satellite Cities, other Metro Departments, property owners, residents, etc.

1.05 MEETINGS

A. Preconstruction Meeting

1. Attend a MWS held Preconstruction Meeting after a purchase order is issued and before any portion of the Work is started.
2. Route correspondence related to the project through the MWS Representative(s) identified at the preconstruction meeting.
3. Discuss and coordinate the Work with other entities involved with the project.
4. Provide contact information, general approach to the work, schedule information, submittals, proposed Construction Start Date, Quality Control Plan, Safety and Health Plan.
5. Identify availability for Construction Kickoff Meeting attendance.

B. Construction Kickoff Meeting

1. After MWS issues the Notice to Proceed, attend a MWS administered

- Construction Kickoff Meeting.
- 2. Make preparations to attend the Construction Kickoff Meeting either offsite, onsite, or both.
- C. Progress Meetings
 - 1. Attend progress meetings as scheduled and administered by MWS.
- D. Special Meetings
 - 1. MWS reserves the right to require other project meetings, including but not limited to, pre-installation meetings for specific components of the work.
 - 2. Be prepared to attend, during the course of the Work, additional meetings to discuss specific elements of the Work.
- E. Substantial Completion Review / Final Walkthrough Reviews
 - 1. Near the end of the project attend the substantial completion meeting for MWS to generate the punch list for remaining contract items to be completed.
 - 2. Upon completion of all punch list items, attend a MWS scheduled Final Walkthrough Review to ensure project completion.

PART 2: PRODUCTS

2.01 NOT USED

PART 3: EXECUTION

3.01 NOT USED

END OF SECTION

SECTION 01 32 16
CONSTRUCTION PROGRESS SCHEDULE

PART 1: GENERAL

1.01 SCOPE

- A. Construction Progress Schedule and Recovery Schedule if warranted

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 – Submittal Procedures.
- B. Submit one digital initial Construction Progress Schedule in PDF format for review by MWS before beginning the work.
- C. After review by MWS, and if edits are requested, submit revised Construction Progress Schedule.
- D. Submit an updated Construction Progress Schedule with every Application of Payment of the same number of copies.
- E. If requested by MWS, or if a critical path milestone has not been achieved, submit a Recovery Schedule.

1.03 MEASUREMENT AND PAYMENT

- A. Consider expenses for creating and/or revising Construction Progress/Recovery Schedules incidental to the Work with no separate payment allowed.

1.04 GENERAL

- A. Plan, schedule, execute, and report the Work with a Construction Progress Schedule using a critical path method format with a work breakdown structure.
- B. Identify work in separate stages and other logically grouped activities.
- C. Show sequence of construction by activity with dates for beginning and completion of each element of construction.
- D. Provide sub-schedules if applicable to define critical portions of the Work.
- E. Show accumulated percentage of completion for each construction activity.
- F. Consider and include typical seasonal weather conditions in the planning and scheduling of the Work.
- G. Include the date approved submittals are needed in the Construction Progress Schedule. Allow ten MWS business days for review of all submittals.
- H. Identify modifications or changes for updated Construction Progress Schedules.
- I. Provide a narrative report to define problem areas, anticipated delays, and impact on schedule including corrective actions taken or recommendations.
- J. If an updated Construction Progress Schedule indicates the project or a required

milestone is ten or more workdays behind schedule and there is no change to support a time extension or when requested by MWS, prepare and submit a Recovery Schedule within five calendar days.

- K. Include in the Recovery Schedule proposed revisions to the Construction Progress Schedule demonstrating intentions to achieve all contractual milestones (including contract completion dates) within the remaining Contract Time including a narrative describing the cause for the problems and the actions planned to recover lost time.
- L. Recovery Schedule shall include all activities required to complete the contract.
- M. Recovery Schedule will become the Construction Progress Schedule when approved by MWS.
- N. Promptly undertake appropriate action to recover lost time at no additional cost to MWS.
- O. MWS may consider the refusal or failure to take appropriate recovery action, and/or submit a Recovery Schedule a lack of due diligence of the work and withhold some or all of any payment due and terminate the contract.

PART 2: PRODUCTS

2.01 NOT USED

PART 3: EXECUTION

3.01 NOT USED

END OF SECTION

SECTION 01 32 33
PHOTOGRAPHIC DOCUMENTATION

PART 1: GENERAL

1.01 SCOPE

- A. Photographic Documentation

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit digital color pictures and/or videos to MWS by email and/or two copies on a MWS approved media within 5 days taken with the Project Name, Project Number, date taken, and brief description including, if applicable, house number and street name.
- C. Submit pictures in an approved MWS format and resolution.

1.03 MEASUREMENT AND PAYMENT

- A. Consider expenses for photographic documentation incidental to the Work with no separate payment allowed.

PART 2: PRODUCTS

2.01 PRECONSTRUCTION

- A. Prior to starting construction, take digital color photographs and/or video of the entire route of the project or project site.
- B. Provide photographs and/or videos showing the preconstruction condition of the following:
 - 1. Streets and Roads;
 - 2. Sidewalks, Curbs and Gutters, and Driveways;
 - 3. Surface features (lights, fences, manholes, valve boxes, sprinkler heads, mail boxes, utilities, etc.);
 - 4. Landscaping (lawns, trees, shrubs, grass, flower gardens, etc.);
 - 5. Preexisting damage within or near the Work;
 - 6. Any other item deemed important to document.

2.02 POST CONSTRUCTION

- A. After completion of construction, provide photographs and/or videos of public or private property that has been repaired, restored, or were the subject of complaints during construction.
- B. Submit post construction photographic documentation in the same format as preconstruction photographic documentation.

PART 3: EXECUTION

3.01 NOT USED

END OF SECTION

SECTION 01 33 00
SUBMITTAL PROCEDURES

PART 1: GENERAL

1.01 SCOPE

- A. Submittal Procedures

1.02 SUBMITTALS

- A. Find specific submittals required in each individual specification section.

1.03 MEASUREMENT AND PAYMENT

- A. Consider expenses for submittals incidental to the Work with no separate payment allowed including, but not limited to, samples.

1.04 GENERAL

- A. Within a minimum of ten calendar days after the date of the Notice to Proceed letter, submit a Submittal Log and submittals for approval.
- B. Submittals shall be numbered sequentially as outlined on the Submittal Log.
- C. Present submittals to MWS in advance of when they are needed and allow ten MWS business days for review.
- D. Submit a construction schedule in the critical path method format.
- E. Identify project name and number, Contractor, Subcontractor or Supplier, and specification section number on each submittal including identification of variations from Contract Documents, products, and/or systems.
- F. Submit the number of copies indicated in each individual specification section, and if the number of copies is not listed, submit five paper copies.
- G. Submit a digital copy in a MWS approved format.
- H. Sequentially number initial submittals and include a letter suffix for resubmittals following the original initial submittal number; also, identify all changes made from the previous submittal.
- I. Apply a project manager or company official signed and dated stamp certifying that submittals are in accordance with the requirements of the Contract Documents and clearly denote item intended for use.
- J. After MWS approval of submittals, distribute copies of approved submittals for construction.
- K. MWS reserves the right to reject a supplier from submitting future products if multiple submittals have not conformed to project requirements.
- L. MWS approvals shall not relieve requirements to meet project specifications.

- M. Furnish submittals in accordance with MWS published Approved Materials.
- N. MWS reserves the right to approve and/or disapprove product substitutions.
- O. Rejected submittals do not warrant additional contract time or damage claims.
- P. Submit Record Drawings upon completion of the Work. MWS reserves the right to request additional information on the Record Drawings.

PART 2: PRODUCTS

(Not Used)

PART 3: EXECUTION

(Not Used)

END OF SECTION 01 33 00

SECTION 01 35 23
HEALTH AND SAFETY

PART 1: GENERAL

1.01 SCOPE

- A. Health and Safety

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit a Safety Program as an informational submittal. MWS will not issue an approval of the Safety Program.
- C. Submit an Emergency Response Plan, Accident Notification, and Claim Notifications.
- D. Submit the proper report for any incident that results in damage, injury, or loss.

1.03 MEASUREMENT AND PAYMENT

- A. Consider expenses for health and safety incidental to the Work with no separate payment allowed.

1.04 GENERAL

- A. Familiarize and comply with the provisions and requirements of the Occupational Safety and Health Act (OSHA) and TOSHA and other applicable federal, state, county, local laws, ordinances, codes, relating to the safety of persons, property, and protection of persons or property from damage, injury, or loss. Ignorance of any provision or requirement shall not relieve responsibilities of compliance, fines, or penalties.
- B. Address provision or requirement conflicts related to safety by contacting the conflicting agencies for resolution. If resolution cannot be achieved, follow the more stringent requirement.
- C. Supply, erect, and maintain all necessary safeguards for health, safety, and protection.
- D. Initiate, maintain, and supervise all safety precautions and programs in connection with the Work with sole responsibility. Such responsibility does not relieve Subcontractors of their responsibility for the safety of persons or property in the performance of their work, nor for compliance with applicable safety Laws and Regulations.
- E. Take all necessary precautions for health and safety and provide the necessary protection to prevent damage, injury, or loss to the following:

1. All persons inside or outside the project limits who may be affected by the Work;
 2. All the materials, and equipment to be incorporated inside or outside the project limits;
 3. Other property inside or outside the project limits including, but not limited to: trees, shrubs, lawns, walks, pavements, roadways, structures, utilities, and underground facilities not designated for removal, relocation, or replacement in the course of construction.
- F. Anticipate and meet the specific health and safety requirements of the project.
- G. Require workers to use personal protective equipment (PPE) and observe proper hygienic precautions in accordance with the Construction Safety Program.
- H. Take measures to ensure that workers observe proper safety precautions when working in hazardous areas including, but not limited to: confined spaces, detrimental gases, oxygen deficiencies, flowing fluid with high velocities, and soil instability.
- I. Notify owners of adjacent property and facilities prior to starting activities that may have adverse effects.
- J. Provide at all times proper facilities for safe access to the work by MWS and their authorized representatives including testing personnel and authorized government officials.
- K. MWS reserves the right to suspend any activity or situation it deems unsafe without compensation.

1.05 Construction Safety Program

- A. Before starting the Work, develop and implement a Construction Safety Program with a plan indicating an understanding of the specific safety and health dangers of the project and demonstrate the experience and qualifications to perform the work in a safe manner. Include within the plan, but not limited to:
1. Safety organization and representatives
 2. Employee training and orientation
 3. Blood-borne pathogen exposure prevention
 4. PPE requirements including OSHA and TOSHA compliant serviceable hardhats with company logos required for employees and subconsultants
 5. Procedure for mandatory initial and refresher confined space training for all Contractor and subcontractor onsite personnel and develop and

- maintain a program for confined space entry
- 6. Procedures for electrical and mechanical Lock-Out/Tag-Out
- 7. Procedures for Hot Works in hazardous areas
- 8. General site safety regulations
- 9. Record keeping and reporting requirements
- 10. Safety promotion programs or incentive goals
- 11. Documentation incorporated into the Contractor's safety manual whereby its personnel have been informed about and know what health precautions should be taken when working with water or wastewater systems
- 12. List with emergency phone numbers that allows MWS to obtain responses to an emergency at any time day or night
- B. Emergency Response Plan including, but not limited to:
 - 1. Emergency evacuation procedures
 - 2. Emergency notification plan
 - 3. Emergency supplies
 - 4. Disaster supply kit
- C. Accident Notification Procedures including, but not limit to:
 - 1. Report all accidents causing death, serious injuries, or serious damage to MWS immediately by telephone. No later than 24 hours after the occurrence of the accident, meet with MWS.
 - 2. Submit a written report to MWS providing full details and witness statements no later than 7 days after the accident.
 - 3. Follow this procedure for all accidents resulting from or in conjunction with performing the Work, whether on or off project site.
- D. For claim notification procedures, report the facts giving full details in writing to MWS and if anyone makes any claims including subcontractors due to an accident, notify MWS within 24 hours after receiving notice of the claim.

PART 2: PRODUCTS

2.01 NOT USED

PART 3: EXECUTION

3.01 NOT USED

END OF SECTION

SECTION 01 41 00
REGULATORY REQUIREMENTS

PART 1: GENERAL

1.01 SCOPE

- A. Regulatory requirements.

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 – Submittal Procedures.
- B. Submit agreements, permits, or other documents for regulatory requirements pertaining to the project.

1.03 MEASUREMENT AND PAYMENT

- A. Consider expenses for regulatory requirements incidental to the Work with no separate payment allowed.
- B. Violations resulting in regulatory fines / penalties will not be paid by MWS.

1.04 GENERAL

- A. Comply with private, local, state, and federal regulatory requirements.
- B. Immediately notify MWS where conflict exists between regulatory requirements and/or specifications.
- C. Take full responsibility for actions that violate project regulatory permits or Federal, State or local environmental regulations including, but not limited to: U.S. Army Corps of Engineers 404 Permits; TDEC Aquatic Resource Alteration Permits; TDEC Construction General Permits; any State or Federal permits/approvals related to Threatened and Endangered Species; Metro Individual NPDES permits; Stormwater Management Manual, Volume 1, Section 6.9, and/or Metro Code 15.64.205 Non-stormwater Discharges.
- D. Take responsibility for, but not limited to, payment of all fines, assessments, and/or civil penalties, actions, design, and/or installation and payment of mitigation measures required due to the violation and cleanup associated with any violation.
- E. Upon discovery of archeological artifacts within the project limits, immediately stop the Work and notify MWS. MWS shall have and retain all right, title, and interest to such artifacts and shall have the further right, during the course of the contract to examine, or cause to have examined, the site of the Work for any artifacts and perform or have performed archeological excavations and all other related work to explore, discover, recover, and remove artifacts from the work

site. In the event an archeological examination delays the Work, a time extension may be granted.

- F. Obtain from MWS and keep onsite during construction original Tennessee Department of Environment and Conservation (TDEC) Division of Water Supply and/or Water Pollution Control approved construction drawings and letter.
- G. Obtain and comply with Metro Public Works Excavation, Sidewalk, and/or Street Closure Permits requirements.
- H. Obtain building permits from Metro Codes when required.
- I. Obtain from MWS and comply with the conditions of the Tennessee Department of Transportation (TDOT) Right of Way Permit when working within state routes.
- J. Obtain from MWS and comply with conditions of the Tennessee Department of Transportation (TDOT) Bridge Approval when working near or on bridges of the state.
- K. Comply with requirements and/or permit conditions of other private or public entities having jurisdiction such as but not limited to: railroads, gas companies, and power companies.
- L. Comply with the Safe Drinking Water Act.
- M. Comply with the Clean Water Act and Metro Stormwater Management Regulations.
- N. Comply with the American with Disabilities Act (ADA).

PART 2: PRODUCTS

2.01 NOT USED

PART 3: EXECUTION

3.01 NOT USED

END OF SECTION

SECTION 01 45 00
QUALITY ASSURANCE AND CONTROL

PART 1: GENERAL

1.01 SCOPE

- A. Quality assurance and quality control

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 – Submittal Procedures.
- B. Submit a Quality Assurance/Quality Control Plan (QA / QC Plan) including at a minimum the following:
 - 1. Quality management and responsibilities;
 - 2. Qualifications of Employees;
 - 3. Project quality plan;
 - 4. Inspections and testing;
 - 5. Control and prevention of nonconformance;
 - 6. Training required for the Work;
 - 7. Project documentation;
 - 8. Closeout of the Project.

1.03 MEASUREMENT AND PAYMENT

- A. Consider expenses for quality assurance and quality control incidental to the Work with no separate payment allowed.

1.04 GENERAL

- A. Perform Work in accordance with Drawings, Specifications, and manufacturer's instructions.
- B. Request clarification in writing from MWS if a conflict is discovered between the Drawings, Specifications, and/or manufacturer's instructions.
- C. Immediately notify MWS of irregularities or deficiencies of the Work.
- D. Cooperate with MWS and provide access to the Work.
- E. Furnish copies of test reports and certificates of materials to MWS.
- F. Furnish material and labor to provide MWS access to the Work for observations, handling samples, and testing.
- G. Sign and acknowledge reports and quantities sheets from MWS.
- H. Notify MWS Field Representative 48-hours prior to expected time for operations requiring services or observations with a 24-hour notice of change-of-time or cancellation.

- I. Pay for a third party firm's observation services for the following:
 - 1. Re-observation of nonconforming Work.
 - 2. Observation of additional work caused by errors, faulty equipment, or incompetence.
 - 3. Insufficient notification of cancellation of Work.
- J. Provide the services of a manufacturer's representative on-site during installation, testing, and startup for portions of the Work as recommended by the manufacturer or requested by MWS.

1.05 OBSERVATION SERVICES

- A. MWS may perform testing of the Work or observe tests of any portion of the Work to ascertain compliance with the Drawings, Specifications, and manufacturer's instructions.
- B. MWS reserves the right to employ and pay for a third party firm to provide supplemental observational services.
- C. MWS and/or a third party firm may produce reports indicating observations and compliance or non-compliance with the Drawings, Specifications, and the manufacturer's instructions.
- D. MWS observations, commentaries, or refraining from testing or observing the Work shall not relieve obligations to perform the Work in full compliance with the Drawings, Specifications, and manufacturers' instructions including all safety requirements.
- E. MWS may compare actual materials used for the Work with test reports and certifications and report conflicts.
- F. MWS Field Representative is not authorized, without written approval of MWS, to:
 - 1. Revoke, alter, enlarge, or waive requirements of the Drawings, Specifications, or manufacturer's instructions.
 - 2. Approve or accept any portion of work beyond the approved Work detailed in the Drawings and Specifications.
 - 3. Perform any duties of Contractor.
- G. MWS has the authority to stop the Work at any time.

1.06 TESTING

- A. Perform testing of the Work and/or materials in conformation with the Drawings, Specifications, and manufacturer's instructions.

- B. Pay for testing the portions of the Work required to be tested by an independent third party materials testing firm.
- C. Pay for testing by an independent third party materials testing firm for portions of the Work that MWS considers deficient and is found to be deficient.
- D. Increase testing frequencies beyond industry standards if requested by MWS.
- E. MWS reserves the right to retest samples, specimens, or portions of the Work previously tested by the Contractor or an independent third party materials testing firm.
- F. Reports and/or observations by a testing laboratory do not relieve obligations to perform work in full compliance with the Drawings, Specifications, and manufacturer's instructions.
- G. Comply with recognized industry standards for testing when none are specified in the Drawings, Specifications, or manufacturer's instructions.
- H. Provide copies of testing results and reports to MWS.

PART 2: PRODUCTS

2.01 NOT USED

PART 3: EXECUTION

3.01 NOT USED

END OF SECTION

SECTION 01 51 00
TEMPORARY UTILITIES

PART 1: GENERAL

1.01 SCOPE

- A. Temporary Utilities for Temporary Facilities not including by-pass pumping, temporary water mains, or any other temporary utilities used for public services.

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit sketch indicating temporary utility connections.

1.03 MEASUREMENT AND PAYMENT

- A. Consider expenses for temporary utilities incidental to the Work with no separate payment allowed.

1.04 GENERAL

- A. Arrange for authorities having jurisdiction to test and examine each temporary utility before use. Obtain required certifications and permits.
- B. Protect, operate, and maintain existing utilities regardless of previously assigned responsibilities. Do not disrupt or interfere with services of existing permanent utilities or violate regulatory codes.
- C. Temporary Water Service - Make arrangements with MWS to obtain metering and backflow devices. Connections to MWS water supply require a meter and backflow device. Supply necessary pipe or hose extensions to convey the water to the use points. Comply with applicable regulations and code requirements including metering and backflow prevention. If outside MWS water service area, coordinate with the appropriate water utility. MWS reserves the right to limit, suspend, or terminate supplying water at any time should it consider such action to be necessary due to distribution system damage, the need to conserve water, or other emergency. In this event, no additional payment shall be made for delays or added expenses to the Contractor.
- D. Temporary Sewer Service – Provide and maintain adequate number of temporary prefabricated chemical type toilets with proper enclosures secluded if possible from public observation for use of workers during construction. Comply with local and state health requirements and sanitary regulations. Maintain the sanitary facilities in a satisfactory and sanitary condition at all times and enforce their use. If using MWS existing sewer service, provide service connection

appurtenances as required. Make arrangements and pay costs associated with tying sanitary system into an approved disposal system or alternative sanitary service.

- E. Temporary Electricity Service - Make necessary arrangements and pay for temporary electric service and lighting required during construction. Install necessary temporary wiring, panel boards, outlets, switches, lamps, fuses, controls and accessories. Comply with NECA, NEMA, NFPA 70, and UL standards and regulations for temporary electric service.
- F. Temporary Heating / Air Conditioning - Provide temporary heating, including costs of equipment and installation, fuel, and attendance, whenever and for such periods as heating may be required. Observe and take precautions against general weather conditions to prevent freezing and retarding of curing of concrete. Maintain suitable working conditions for workers.
- G. Restore site when removing Temporary Utilities to equal or better condition.

PART 2: PRODUCTS

2.01 NOT USED

PART 3: EXECUTION

3.01 NOT USED

END OF SECTION

SECTION 01 52 00
TEMPORARY FACILITIES

PART 1: GENERAL

1.01 SCOPE

- A. Temporary Facilities

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit site plan indicating temporary facility size, locations, staging areas, and parking areas for construction personnel.

1.03 MEASUREMENT AND PAYMENT

- A. Consider expenses for temporary facilities incidental to the Work with no separate payment allowed.

1.04 GENERAL

- A. Provide temporary facilities to properly complete the Work as required and as specified.
- B. Provide temporary facilities in compliance with all regulatory agencies.
- C. Provide temporary facilities to cause least inconvenience possible to the public.
- D. Protect all temporary facilities from adverse weather.
- E. Obtain MWS approval before transporting or locating temporary facilities within construction site.
- F. Temporary Contractor Field Office - At the discretion of MWS, provide, equip, and maintain a temporary field office at a suitable location near the Work.
 - 1. Maintain copies of all contract documents in the contractor field office.
 - 2. Maintain support facilities until MWS schedules substantial completion review. Remove before final completion review unless otherwise directed by MWS.
 - 3. Allow other entities to use temporary services and facilities without cost including personnel related to the project and/or having jurisdiction.
- G. Temporary MWS Field Office – If required in the Special Provisions, provide, equip, and maintain a temporary field office at a suitable location near the Work for exclusive use by MWS Project Representative.
- H. Emergency Contact List - at each telephone, office exit doors and Emergency Response station, post a list with important telephone numbers.
 - 1. Police and fire departments.

2. Ambulance service.
 3. Contractor's home office.
 4. Contractor's emergency after-hours telephone number.
 5. MWS Field Representative offices.
 6. Metro office – Public Information Officer.
 7. Principal subcontractors' field and home offices.
 8. Others as required.
- I. Site Security - take positive measures to prevent entry of unauthorized persons to work site and storage areas at all times.

PART 2: PRODUCTS

2.01 NOT USED

PART 3: EXECUTION

3.01 NOT USED

END OF SECTION

SECTION 01 55 26
TRAFFIC CONTROL

PART 1: GENERAL

1.01 SCOPE

- A. Traffic Control

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit a vehicular and pedestrian traffic control plan for review to the appropriate agencies including but not limited to MWS, MPW, ADA, and/or TDOT. MWS will not issue an approval of a traffic control plan.

1.03 MEASUREMENT AND PAYMENT

- A. Consider expenses for traffic control incidental to the Work with no payment allowed unless a traffic control bid item is specifically indicated on the Bid Schedule.

1.04 GENERAL

- A. Assume sole responsibility of traffic control operations and associated vehicular and pedestrian safety.
- B. Provide traffic control processes needed to create a safe work zone and maintain the safety of vehicular and pedestrian traffic.
- C. Provide traffic control for Work within local roads in accordance with MPW latest standards and permit provisions.
- D. Provide traffic control for Work within state route and interstate right of ways in accordance with TDOT latest standards and permit provisions.
- E. Provide certified flaggers, temporary signage, traffic control devices, and other incidentals necessary for the traffic control operations.
- F. Ensure roadways are fully accessible to traffic during non-working hours.
- G. Provide temporary ingress and egress to properties during working hours.
- H. Coordinate and receive permit approval from MPW prior to roadway or lane closures for local roadways.
- I. Coordinate and conform to the stipulations of TDOT permit requirements for Work within state route and/or interstate right of ways.
- J. Utilize traffic control in accordance with of latest revision of Metropolitan Code of Laws including but not limited to Sections 13.20.030 and 13.20.090.

PART 2: PRODUCTS

2.01 TRAFFIC CONTROL

- A. Provide traffic control devices in conformance with the latest revision of the Manual on Uniform Traffic Control Devices (MUTCD).

PART 3: EXECUTION

3.01 NOT USED

END OF SECTION

SECTION 01 57 19
ENVIRONMENTAL CONTROLS

PART 1: GENERAL

1.01 SCOPE

- A. Environmental Controls: Air Pollution, Noise Pollution, Construction and Site Waste, and Erosion/Sediment and Storm Water Pollution.

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Air Pollution - Submit dust plan consisting of a sketch and narrative indicating the dust control measures proposed for use, proposed locations, and proposed timeframe for their operation.
- C. Noise Pollution - Submit noise plan consisting of a sketch and narrative indicating the noise control measures proposed for use, proposed locations, and proposed timeframe for their operation and Identify further options if proposed measures are later determined to be inadequate.
- D. Construction and Site Waste - Submit plans, permits, and certifications.
- E. Erosion/Sediment and Storm Water Pollution - Submit plans, permits, and certifications. At a minimum, prepare, submit, and comply with: Notice of Intent (NOI) and Storm Water Pollution Prevention Plan (SWPPP).

1.03 MEASUREMENT AND PAYMENT

- A. Consider expenses for environmental controls incidental to the Work with no separate payment allowed.
- B. Consider additional environmental controls required by MWS or other agencies having jurisdiction during the course of the Work incidental with no separate payment allowed.

1.04 GENERAL

- A. Maintain onsite and offsite work areas free from environmental pollution that violates federal, state, local regulations and/or generates complaints from the Public.
- B. Provide methods, means, and facilities to prevent contamination of soil, water, and atmosphere from discharge of noxious, toxic substances, and pollutants produced by construction operations.
- C. Notify MWS immediately of any violations of noncompliant or complaints concerning environmental controls.

- D. MWS reserves the right to stop construction activities that cause or are likely to cause harm to the environment. Time extensions and payments for non-compliant acts will not be granted.
- E. Dispose of waste materials at Metro approved sites
- F. Do not burn waste materials on the project site.

1.05 AIR POLLUTION CONTROL

- A. Comply with air pollution control requirements that conform with rules, regulations, laws and/or ordinances of all regulatory agencies.
- B. Maintain dust control using standard practices acceptable to MWS.
- C. Minimize air pollution by requiring properly operating combustion emission control devices be used on construction vehicles and equipment and encourage shutting down motorized equipment when not in use.
- D. Do not burn material on the construction site.
- E. Minimize air pollution from fumigate chemicals used in construction processes by requiring ventilation devices and equipment be used.

1.06 NOISE POLLUTION CONTROLS

- A. Minimize noise pollution from vehicles, equipment, and activities to conform to latest TOSHA standards and abide by local codes, ordinances, regulations, rules, and laws.
- B. Schedule and conduct the work in a manner which minimizes the noise level escaping the site, especially at night and on weekends to cause the least annoyance to residents and businesses.
- C. Equip construction equipment with mechanical devices necessary to minimize noise.
- D. If pile driving is required, use only pile driver hammers with mufflers able to significantly reduce noise and use noise barriers or shielding techniques to comply with applicable federal, state and local ordinances.
- E. MWS reserves the right to determine when excessive noise is being generated and require additional noise control measures at no additional cost.

1.07 CONSTRUCTION AND SITE WASTE

- A. Use chemicals such as herbicides, pesticides, disinfectants, polymers, reactants or other chemicals needed for the Work that are approved by USEPA, U.S. Department of Agriculture or any other applicable regulatory agency.
- B. Use and dispose of chemicals per the manufacturer's instructions.

- C. Comply with local, state, and federal regulations concerning transporting and storing chemicals and/or site waste.
- D. Keep motorized equipment in good working order and remove damaged or leaking equipment from project site.
- E. Identify and use appropriate areas for fuel storage, fuel equipment, and containment provisions.
- F. Do not change oil on equipment or store or dispose solvents, lubricants, or other potentially hazardous materials onsite.
- G. Do not store more than a weekly usage volume for fuels or dispose fuels onsite.
- H. Report spills or leaks from fueling equipment or construction equipment to MWS and proper authorities. Clean up and mitigate spills as required by local, state or federal regulations.
- I. Remove and properly dispose of trash and debris resulting from construction activities.
- J. Properly dispose of excess excavated material not required or not suitable for backfill and other waste material in accordance with regulatory requirements at regulated disposal sites.
- K. Provide watertight container for liquid, semiliquid or saturated solids which tend to bleed during transport.
- L. Properly dispose of concrete waste material at regulated disposal sites.

1.08 EROSION/SEDIMENT AND STORM WATER POLLUTION

- A. Comply with the following statement:

“All activities performed in under this solicitation and resulting contract/PO shall be conducted in full compliance with Metro Code of Law §§ 15.64 et al (Storm water Management) including §§ 15.64.205 (<http://www.nashville.gov/Water-Services/Pollution-Prevention/Illicit-Discharge-Ordinance.aspx>). This requirement pertains to Unlawful/Prohibited Discharges to the Metro Storm Sewer System/Community Waters. It prohibits the discharge of "wastewater" and "non-stormwater" discharges such as wash water, process wastewater, etc. into the Municipal Storm Sewer System (MS4) or into Community Waters. Any questions relating these provisions should be routed to the Metro Water Services NPDES Office at (615) 880-2420. This requirement shall apply to all Metro construction projects in the service area, including areas outside Davidson County. Contractor shall bear responsibility for all of Contractor's actions that cause MWS to violate project regulatory permits or Federal,

State or local environmental regulations. Such permits and regulations may include, but are not limited to: U.S. Army Corps of Engineers 404 Permits; TDEC Aquatic Resource Alteration Permits; TDEC Construction General Permits; Any State or Federal permits/approvals related to Threatened and Endangered Species; Metro Individual NPDES permits; Metro Code §15.64.205 - Metro Illicit Discharge Ordinance; Metro Stormwater Management Manual. Contractor's responsibility shall include, but not be limited to, payment of all fines, assessments and/or civil penalties incurred due to Contractor's work, actions, design or installation and payment for any mitigation measures required due to the violation and cleanup associated with any violation."

- B. Reference and comply with procedures outlined in the latest revisions of the following:
 - 1. United States Environmental Protection Agency (USEPA): USEPA-72-015: Guidelines for Erosion and Sedimentation Control Planning and Implementation;
 - 2. USEPA 43019-73-007: Processes, Procedures, and Methods to Control Pollution Resulting from All Construction Activity for Environmental Controls;
 - 3. Tennessee Department of Environment and Conservation (TDEC): TDEC General NPDES permit for Storm Water Discharged Associated with Construction Activities;
 - 4. TDEC Erosion & Sediment Control Handbook; and
 - 5. Metropolitan Government of Nashville and Davidson County, Department of Water and Sewerage Services (MWS) - Stormwater Management Manual for environmental controls.
- C. Comply with provisions of Metro Water Services Stormwater Management guidance documents with Best Management Practices and TDEC regulations.
- D. Notify MWS and take immediate corrective action for notifications of noncompliance of stormwater pollution control or any environmentally objectionable acts from federal, state, or local regulatory agencies. Failure to promptly address notifications of noncompliance may result in a stop work order until satisfactory corrective actions have been completed with no claims for time, expense, or damage considered.
- E. Comply with rules, regulations and permit requirements from local, state, and federal government agencies prohibiting pollution in lakes, streams, rivers,

wetlands, sewers, or storm sewers by dumping refuse, rubbish, spoils, chemicals, wastewater, stormwater, dredge material, or debris.

- F. Keep SWPPP and related documents onsite during construction available for review by regulatory authorities.
- G. Make corrections or repairs to erosion control devices when non-functional or at the request of MWS or other agencies having jurisdiction.

PART 2: PRODUCTS

2.01 NOT USED

PART 3: EXECUTION

3.01 NOT USED

END OF SECTION

SECTION 01 58 00
TEMPORARY PROJECT IDENTIFICATION

PART 1: GENERAL

1.01 SCOPE

- A. Temporary Project Identification: Project Sign

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit information to be placed on the project sign and proposed location for review and approval before fabrication.
- C. Identify and submit deviations from the detail for review and approval.

1.03 MEASUREMENT AND PAYMENT

- A. Consider expenses for project signs incidental to the Work with no separate payment allowed.

1.04 PROJECT SIGN


- A. Furnish, erect, and maintain near the work limits a project sign(s) sized and lettered as shown on the details found at the end of this section.
- B. Provide project sign(s) at a minimum of 72 hours prior to starting the Work.
- C. Do not erect other commercial or advertising signs on the work site or on public property in the vicinity of the work.
- D. Provide signs as indicated on the following details.
- E. Maintain quality sign appearance throughout the life of the project. Replace signs as warranted or as directed by MWS.
- F. Provide a number of signs to adequately identify all work zones. MWS reserves the right to require multiply signs.


PART 2: PRODUCTS

2.01 NOT USED

PART 3: EXECUTION

3.01 NOT USED





END OF SECTION

SECTION 01 66 00
PRODUCT STORAGE AND HANDLING

PART 1: GENERAL

1.01 SCOPE

- A. Product storage and handling

1.02 MEASUREMENT AND PAYMENT

- A. Consider expenses for product storage and handling incidental to the Work with no separate payment allowed.

1.03 PACKING, TRANSPORTATION, AND HANDLING

- A. Require supplier/vendor to package products in manufacturer's recommended shipping, handling, and/or storage containers.
- B. Transport, store, and handle products in accordance with the manufacturer's instructions.
- C. Protect sensitive products against exposure to the elements and moisture.
- D. Protect equipment and finishes against impact, abrasion, and other damages.
- E. Provide the proper equipment and personnel to handle products, including any products furnished by MWS, to prevent damages.

1.04 DELIVERY

- A. Schedule the delivery of products in accordance with the Construction Progress Schedule allowing sufficient time for MWS examination prior to installation.
- B. Deliver products to designated MWS approved and accessible locations.
- C. Clearly mark product deliveries for installation and MWS examination and inventory.
- D. Promptly examine delivered products in the presence of MWS to ensure items comply with project requirements.
- E. Reject damaged or incorrect products at no cost to MWS.

1.05 STORAGE

- A. Properly store products immediately upon delivery in accordance with the manufacturer's instructions.
- B. Arrange products to provide reasonable access for examinations.
- C. Provide platforms or other means to prevent soiling, staining, or corrosion of stored product.
- D. Provide adequate ventilation to avoid condensation when storing items vulnerable to moisture.

- E. Maintain stored products in accordance with the manufacturer's instructions.
- F. Do not store PVC products in sunlight.
- G. Store loose granular materials in a well-drained area on solid surfaces to prevent mixing with foreign materials.

PART 2: PRODUCTS

2.01 NOT USED

PART 3: EXECUTION

3.01 NOT USED

END OF SECTION

SECTION 01 77 00
CLOSEOUT PROCEDURES

PART 1: GENERAL

1.01 SCOPE

- A. Closeout procedures including final submittals such as operation and maintenance data, warranties, spare parts, and maintenance materials.

1.02 MEASUREMENT AND PAYMENT

- A. Consider expenses for closeout procedures incidental to the Work with no separate payment allowed.

1.03 CLOSEOUT PROCEDURES

- A. Start closeout procedures after substantial completion of the Work.
- B. Remove all paint markings from the project area that were originated for this Work, regardless of who applied the markings.
- C. Accompany MWS for an initial walkthrough to generate a punch list.
- D. Complete or correct punch list items.
- E. Accompany MWS for a final walkthrough and correct any deficient items.
- F. Comply with the Contract Documents General Conditions as it relates to final completion and final payment when the Work is complete.
- G. Discovery of new items not on the original punch list or arise after the punch list and final review have been completed are considered warranty items and must be addressed within less than 30 calendar days of notification by MWS during the warranty period.
- H. Provide Project Record Documents prior to project closeout.
- I. MWS reserves the right to initiate close out procedures for portions of the Work.
- J. Submit operation and maintenance information.
- K. Provide required contract documents prior to final closeout.

1.04 WARRANTIES

- A. Provide the originals of each warranty from subcontractors, suppliers, and/or manufacturers.
- B. Provide warranties prior to final application for payment.
- C. Guarantee all Work for a 1-year warranty period unless a longer warranty period is specified for the entire Work or portions of the Work.

PART 2: PRODUCTS

2.01 NOT USED

PART 3: EXECUTION

3.01 NOT USED

END OF SECTION

SECTION 01 78 39
PROJECT RECORD DOCUMENTS

PART 1: GENERAL

1.01 SCOPE

- A. Project Record Documents

1.02 MEASUREMENT AND PAYMENT

- A. Consider expenses for project record documents incidental to the Work with no separate payment allowed.

1.03 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit clean, legible, red line, Record Drawings signed by a responsible party of the actual work installed varying from the Drawings, standards, and/or Specifications.
- C. Submit Change Authorizations, Field Authorizations, and/or Change Orders modifying the original documents.
- D. Submit field testing records, video tapes, and project-related testing documents.
- E. Submit third party, independent laboratory, and/or inspection certificates.
- F. Submit operation and maintenance manuals in labeled three-ring binders and a digital copy.

PART 2: PRODUCTS

2.01 NOT USED

PART 3: EXECUTION

3.01 NOT USED

END OF SECTION

SECTION 03 30 00
CAST IN PLACE CONCRETE

PART 1: GENERAL

1.01 SCOPE

- A. Cast in place concrete for structures requiring reinforcement.
- B. This Section does not include Metro Public Works and TDOT above grade concrete elements within the right of way, flowable fill, precast concrete, and standard thrust blocking.

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit a certification from the concrete producer that the concrete is suitable for the application and conforms to the compressive strength needed for the proposed component of the Work.
- C. Submit manufacturer's product data with application and installation instructions for proprietary materials and items.
- D. Submit actual design mix including admixtures with test cylinder breaks for 7 and 28 days.
- E. Submit reinforcing schedule and drawings including fabrication, bending, and placement with a minimum scale of 3/8" = 1' 0".
- F. Submit affidavit indicating the heat numbers and origin of reinforcement.
- G. Do not submit reproduction of structural drawings for shop drawings.
- H. Submit laboratory test reports for concrete materials to MWS on same day that tests are made.
- I. Submit Manufacturer's letter of certification that curing compound will not adversely affect the adhesion of subsequent materials to be applied to concrete.
- J. Submit concrete truck tickets upon delivery.

1.03 MEASUREMENT AND PAYMENT

- A. MWS will compensate for furnishing and installing cast in place concrete at the contract unit price on the Bid Schedule.
- B. Include all cost in the unit price for cast in place concrete for reinforcement, form work installation and removal, finishing, third party testing, and all incidentals necessary for a complete and operable installation.

1.04 GENERAL

- A. Perform the Work in accordance and comply with the latest revision of American

Concrete Institute (ACI), Concrete Reinforcing Steel Institute (CRSI), and American Society of Testing Materials (ASTM) standards.

- B. Obtain materials from same source throughout Work.
- C. Notify MWS not less than 24 hours after reinforcement has been placed for examination and 24 hours prior to pouring concrete.

PART 2: PRODUCTS

2.01 CONCRETE MIXES

- A. Use ready-mixed concrete in conformance with the latest requirements of ASTM C 94.
- B. Provide a concrete mix with a minimum 28-day compressive strength of 4,000 psi.

2.02 CONCRETE MATERIALS

- A. Provide Type II Portland Cement in conformance with the latest requirements of ASTM C 150, unless otherwise approved in writing by MWS.
- B. Provide American manufactured Type II Portland Cement with an equivalent alkali content of less than 0.60 percent that has been shipped from a single manufacturer throughout the Work milled not more than three months prior to incorporation.
- C. Provide Portland cement in complete unbroken sacks for job site mixing.
- D. Add air entraining agent to entrain 4½ percent air \pm 1 percent with all other ingredients as recommended by approved manufacturers in conformance with the latest requirements of ASTM C 260.
- E. Use aggregates from a single source in conformance with the latest requirements of ASTM C 33.
- F. Use fine aggregates with clean, hard, durable, uncoated particles, free of lumps of clay, soft or flaky material, loam, and organic matter, frozen material of any type, appreciable quantities of mica, shale, slate, or other soft grains.
- G. Use fine aggregate that will not contain more than two percent by weight of material that may be removed by elutriation testing.
- H. Use sands that pass the color metric tests unless the failure to pass is caused by lignite or coal particles.
- I. Provide sand that limits alkali reactivity as defined in the latest requirements of ASTM Designations C 33, Appendix IX and C 289.
- J. Use natural river sand or specially approved manufactured sand. Use of

mountain sand will not be permitted.

- K. Use fine aggregates with 95 to 100 percent passing a No .4 screen size and a minimum of 2 to 10 percent passing a No. 100 screen size.
- L. Use coarse aggregates with 100 percent passing a 1½-inch sieve and a minimum of 0 to 5 percent passing No. 4 screen size.
- M. Use ¼ to ½ inch pea gravel for sections less than 3-inches in thickness.
- N. Use potable water clean and free from injurious amounts of oils, acids, alkalis, organic materials, or other deleterious substances in conformance with the latest requirements of ASTM C 94.
- O. Do not use water containing more than 500 mg/L of chlorides or sulfates.
- P. Use chemical admixtures and Class F fly ash in conformance with the latest requirements of ASTM C 494 and ASTM C 618.
- Q. If fly ash is acceptable for the application as an admixture, only use Class F in conformance with ASTM C 618.

2.03 CONCRETE REINFORCEMENT

- A. Use uncoated deformed reinforcing bars of billet steel grade with 60,000 psi minimum yield strength in conformance with the latest requirement of ASTM A 615, Grade 60.
- B. Use new reinforcing bars of new stock, free from rust, scale, or other coatings that could reduce bonding.
- C. Use welded wire mesh, plain type in flat sheets or coiled rolls with uncoated finish, in conformance with the latest requirement of ASTM A 185.
- D. Provide steel tie wire, minimum 16 gage annealed type, in conformance with the latest requirements of ASTM A 82, plain, cold drawn steel.
- E. Use supports for reinforcement wire bar type supports complying with CRSI recommendations, unless otherwise approved.
- F. Use supports with sand plates or horizontal runners where base material will not support chair legs for slabs on grade.
- G. Provide supports with plastic protected legs, (CRSI, Class I) or stainless steel protected legs (CRSI, Class II) for exposed to view concrete surfaces where legs of supports are in contact with forms.
- H. Use concrete masonry units to support reinforcement to obtain proper clearance from earth.

2.04 CONCRETE JOINTS

- A. Provide watertight expansion joints.
- B. For watertight joints utilizing steel plates, provide:
 - a. a steel slide recess clip;
 - b. expansion joint filler and sealant;
 - c. uncoated steel bar stock in conformance with the latest requirements of ASTM A36;
 - d. fabricated slide recess clip of 20 gauge steel with a hot dipped galvanized coating; and
 - e. an asphalt type expansion joint filler in conformance with the latest requirements of ASTM D994.
- C. For watertight expansion joints utilizing rubber, provide a two part polysulfide rubber joint sealant in conformance with the latest requirements of ASTM C920.
- D. Where indicated on the Drawings or directed by MWS, use pre-molded expansion joint material in conformance with the latest requirements of ASTM D1751.
- E. Provide joint filler for exposed control joints in slabs on ground with a semi-flexible, 100% solids epoxy designed for nonmoving control joints, with a minimum shored hardness of 50.

2.05 MISCELLANEOUS

- A. Provide non-shrink grout for pipe penetrations, field repairs, and other applications as directed by MWS to insure water tightness.
- B. Fill-in holes and openings left in concrete structures for passage of work by other trades, unless otherwise shown or directed, after work of other trades is in place. Mix, place, and cure concrete as specified, to blend with in-place construction. Provide other miscellaneous concrete filling shown or required to complete work.
- C. Provide on the leading edge of stairs, steps, and landings non-skid cast aluminum nosing.

PART 3: EXECUTION

3.01 INSTALLATION

- A. Provide concrete truck tickets with each truck or load of concrete delivered to the project site for placement with the following information listed on each ticket:
 - 1. Project name,
 - 2. Classification of concrete,
 - 3. Time of the batching of material,

4. Batch weights of each material including water,
 5. Additional materials added to concrete mix,
 6. Initials of the concrete supplier's weight man or independent third party inspection service representative, and
 7. Signature of a responsible party of the vendor certifying the truck conforms to the approved design mix for the Work.
- B. Understand failure of supplying truck ticket is grounds for rejection of the load.
 - C. Protect concrete from the drying action of the sun; freezing weather; wash from rain or flowing water; muddy conditions; and other damaging conditions.
 - D. When concrete is mixed or delivered by truck mixer, place concrete within the time recommended by the manufacturer or 90 minutes, whichever is less.
 - E. Consider weather, including temperature, when placing concrete in accordance with the latest requirements of ACI 305 and ACI 306.
 - F. Mix and place concrete when the temperature is 40 degrees Fahrenheit and rising or not to exceed 85 degrees Fahrenheit, unless MWS approved means are employed.
 - G. Prevent segregation and loss of ingredients when conveying concrete from the mixer to the forms by controlling the speed and drop height of placement.
 - H. Do not drop concrete into forms from a height greater than 5 feet.
 - I. Avoid coating of reinforcement or form surfaces with concrete paste that could dry before coverage of concrete.
 - J. Deposit concrete continuously or in layers of such thickness that no concrete will be placed on concrete which has hardened sufficiently to cause the formation of seams or planes of weakness.
 - K. Deposit concrete in forms in horizontal layers not deeper than 24 inches and in a manner to avoid inclined construction joints.
 - L. Pour each layer of concrete while the preceding layer is still plastic to avoid cold joints.
 - M. Consolidate placed concrete by mechanical vibrating equipment supplemented by hand-spading, rodding, or tamping.
 - N. Avoid the use of vibrators to transport concrete inside forms or into lower layers of concrete that have begun to set.
 - O. Consolidate concrete during placement operations so that concrete is thoroughly worked around reinforcement and other embedded items and into corners.

- P. Pour concrete to the grades and slopes as indicated on the Drawings.
- Q. Check and level surface plane to a tolerance not exceeding 5/16-inch in 10 feet when tested with a 10 feet straight edge.

3.02 REINFORCEMENT

- A. Comply with CRSI recommended practice for placing reinforcing bars, for details and methods of reinforcement placement and supports.
- B. Position, support, and secure reinforcement against displacement by formwork, construction or concrete placement operations.
- C. Provide a minimum of four extra diagonal bars in each face of the wall or slab of the same size of the largest bar in the wall or slab for openings 12 inches and larger.
- D. Provide a minimum area of steel reinforcing equivalent to 0.0018 times the cross sectional area of the concrete work performed for Class A concrete walls, slabs and other concrete work if through an omission no reinforcement.
- E. Lap all bars a minimum of 40 diameters at splices unless a greater lap is indicated on the Drawings.
- F. Locate and support reinforcing by metal chairs, runners, bolsters, spacers, and hangers, as required.
- G. Place reinforcement to obtain at least 2-inch coverage.
- H. Arrange, space, and securely tie bars and bar supports to hold reinforcement in position during concrete placement operations.
- I. Set wire ties so ends are directed into concrete, not toward exposed concrete surfaces.
- J. Bend reinforcing bars cold and do not heat bars with a torch.
- K. Install welded wire fabric in as long of lengths as practicable.
- L. Lap adjoining welded wire pieces at least one full mesh opening and lace splices with wire.
- M. Offset end laps of welded wire pieces in adjacent widths to prevent continuous laps in either direction.
- N. Place wire mesh in the top third of the slab thickness.

3.03 FORMWORK AND ACCESSORIES

- A. Construct and erect concrete formwork in accordance with the latest requirements of ACI 301 and ACI 347.
- B. Remove forms when concrete has attained strength sufficient for support of the

superimposed loads.

- C. Removal of cold weather forms will not be permitted when the danger of freezing or damaging of the concrete surface exists.
- D. Provide openings in concrete formwork to accommodate work of other trades.
- E. Coat contact surfaces of forms in compliance with manufacturer's instructions with a form coating compound before reinforcement is placed.
- F. Furnish form material in largest practicable sizes to minimize number of joints and to conform to joint system as required.
- G. Provide ties that leave no metal within 1-1/2-inch of the surface and exhibit a cone shaped depression at least 1-1/2-inch deep to allow filling and patching.
- H. Use form coatings inside clearwells that are approved by the waterproofing manufacturer and MWS.

3.04 JOINTS

- A. Provide construction joints as indicated on the Drawings but no more than 30 feet in each direction or more than 900 square feet.
- B. Provide vertical construction joints at 30 feet intervals or less from corners or above grade water holding basin walls and below grade dry spaces.
- C. Provide horizontal construction joints at 30 feet intervals or less in walls enclosing dry spaces below grade.
- D. Provide for all joints, except expansion joints, reinforcing steel extending into subsequent sections of construction to make the work a monolith.
- E. Provide keyways at least 1-1/2" deep in construction joints in walls, slabs and between walls and footings; accepted bulkheads designed for this purpose may be used for slabs.
- F. Place construction joints perpendicular to the main reinforcement.
- G. Continue reinforcement across construction joints.
- H. Locate construction joints in footings and walls across areas of low shearing stress and provide keyways, water stops, and/or expansions joints as indicated on the Drawings.
- I. Locate construction joints near the middle of spans of slabs, beams, or girders unless a beam intersects a girder at this location, in which case offset the joints in the girder a distance equal to twice the beam width. Make a provision for shear with the use of inclined reinforcement.
- J. Construct isolation joints in slabs on grade at points of contact between slabs on

ground and vertical surfaces, such as columns, foundation walls, grade beams and elsewhere as indicated.

- K. Construct control joints in slabs on ground to form panels of patterns as indicated on the Drawings.
- L. Use control joint inserts of ¼ inch wide by ¼ of the slab depth or saw cuts to ¼ of slab depth, unless otherwise indicated.
- M. Provide spacing of control joints in slabs on grade at distances not exceeding 15 feet.

3.05 CONCRETE CURING AND PROTECTION

- A. Protect freshly placed concrete from premature drying and temperatures harmful to the concrete in accordance with ACI 308 procedures and avoid rapid drying at end of final curing period.
- B. Interior Floor Slabs
 - 1. Apply by means of a roller or spray gun a membrane curing compound designed to cure, seal, harden, and is dustproof within 30 minutes of the completion of finishing operations and/or immediately after the disappearance of the surface moisture sheen.
 - 2. Apply the coating to slab surfaces uniformly at the manufacturer's recommended rate.
 - 3. Cover with curing sheets meeting the latest requirements of ASTM C171 if the floor slab is completed prior to the building envelope.
 - 4. Secure, maintain, and anchor in place for a minimum of seven days.
- C. Exterior Slabs and Water Holding Basin Floor Slabs
 - 1. Apply and seal with a hydrocarbon, resin-based compound meeting the latest requirements of ASTM C309 within 30 minutes of the completion of finishing operations in accordance with the manufacturer's instructions.
 - 2. Apply coatings uniformly at the manufacturer's recommended rate.
 - 3. Use as an alternate means of curing, a burlap covering system to completely cover the exterior slab and continuously soak with a potable water sprinkler system for four days only with MWS approval.

3.06 CONCRETE SURFACE REPAIRS

- A. Conform to applicable requirements of ACI 301 for concrete repair.
- B. Repair and patch defective areas with cement mortar immediately after removal of forms to match color, shape, grade, slope, and texture of surrounding repaired

areas for exposed to view surfaces when dry.

- C. Cut out, perpendicular to the concrete surface and expose reinforcing steel with at least 3/4-inch clearance all around: honeycomb, rock pockets, voids over 1/4-inch in any dimension, down to solid concrete but, in no case to a depth of less than 1-inch.
- D. Thoroughly clean, dampen with water, brush-coat the area to be patched with the appropriate bonding compound, and place patching mortar after bonding compound has dried.
- E. Flush out form tie holes and fill with dry pack mortar or precast cement cone plugs secured in place with bonding agent.
- F. Repair concealed formed surfaces, where possible, that contain defects that affect the durability of concrete.
- G. Correct high areas in unformed surfaces by grinding, after concrete has cured at least 14 days.
- H. Use epoxy-based adhesive and/or mortar for structural repairs where directed by MWS.
- I. Remove and replace concrete having defective surfaces if defects cannot be repaired to the satisfaction of MWS.

3.07 CONCRETE FINISHING OF FORMED SURFACES

- A. Conform to applicable requirements of ACI 301 for concrete finishing.
- B. Coordinate final finish with MWS before application.
- C. Provide concrete finish as indicated on the Drawings or as directed below:
 - 1. Smooth form finished for concrete to receive membrane waterproofing;
 - 2. Scratch finish to monolithic slab surfaces that are to receive concrete floor topping or mortar setting beds for tile;
 - 3. Float finish to monolithic slab surfaces to receive trowel finish and slab surfaces which are to be covered with membrane or elastic waterproofing, membrane or elastic roofing;
 - 4. Trowel finish to monolithic slab surfaces to be exposed to view, and slab surfaces to be covered with resilient flooring, paint or other thin film finish coating system;
 - 5. Monolithic finish to interior curbs by stripping forms while concrete is still green and steel-troweling surfaces to a hard, dense finish with corners, intersections and terminations slightly rounded;

6. Float finish of all water holding basin floor slabs;
 7. Non-slip broom finish to exterior concrete platforms, steps and ramps;
 8. Hand trowelled at the edges of floor slabs, around building columns, and other surface interruptions.
 9. Provide a smooth trowel finish for slab recesses intended to receive equipment or furnishings.
 10. Provide a minimum of three trowellings of interior floor slabs.
- D. Refloat surface after cutting down high spots and filling low spots and uniformly slope surfaces to drains.

3.08 QUALITY CONTROL AND TESTING

- A. Obtain third party material testing firm, approved by and at no cost to MWS.
- B. Assume responsibility for ensuring that all concrete and concrete placements meet the project requirements. Failure of MWS or third party testing laboratory to detect defective work, workmanship, or materials will in no way prevent rejection.
- C. Perform material testing meeting the latest requirements of ACI 301, ASTM E 329 and ASTM C 172 or C 94; for the following:
 1. Slump – ASTM C 143; one test for each concrete load at point of discharge and one test for each set of compressive strength test specimens;
 2. Air Content – ASTM C 173, volumetric method for lightweight concrete; ASTM C 231, pressure for normal weight concrete; one for each set of compressive strength test specimens;
 3. Concrete Temperature - Test hourly when air temperature is below 40 degrees Fahrenheit or greater than 80 degrees Fahrenheit; and each time a set of compression test specimens is made. Take and test one additional test cylinder during cold and hot weather cured onsite.
 4. Compression Strength Test – Sample, store, and cure specimens in accordance with ASTM C 31. Mold and store cylinders for laboratory cured test specimens except when field-cure test specimens are required. Test specimens in accordance with ASTM C 39. Test one set, five specimens, for each concrete class of 25 cubic yards placed in any one day or for each 5,000 square feet of surface area placed. Test two specimens at 7 days, two specimens at 28 days, and one specimen retained in reserve for later testing if required.

- D. Materials, including cement and aggregates, and operations shall be tested and examined as work progresses. Failure to detect defective work will not prevent rejection when defective concrete is discovered, nor will it obligate MWS for final acceptance.
- E. Remove and replace concrete not meeting specified strengths and/or parameters at no cost to MWS. MWS may elect to allow the following tests to demonstrate in place concrete meets specifications instead of removal and replacement:
 - 1. Cored cylinders in conformance with the latest requirements of ASTM C 42 when test results indicate specified concrete strengths and other characteristics have not been attained in the structure.
 - 2. Load testing in conformance with the latest requirements of ACI 318 when after additional testing evidence indicates low strength concrete still exists.
- F. Take approved corrective action when such defects are discovered. MWS or the third party testing laboratory will not be obligated to make a final acceptance until corrective action is completed.
- G. Testing and/or retesting of materials and installed work, as directed by MWS, may occur at any time during work progress. Allow free access to material stockpiles and facilities.
- H. Pay for testing, not specifically indicated to be done at MWS expense, including retesting of rejected materials and installed work.

3.09 MISCELLANEOUS CONCRETE ITEMS

- A. Provide machine and equipment bases and foundations, as indicated on Drawings. Set anchor bolts and imbeds for machines and equipment to template at correct elevations, complying with certified diagrams or templates of manufacturer furnishing machines and equipment.
- B. Grout all column base plates, equipment bases, and other locations noted on the Structural Drawings with specified non-shrink grout.
- C. Provide concrete fill for steel pan stair treads and landings and associated items. Cast-in safety inserts and accessories as indicated on Drawings. Install all joint types, keyways, and expansion anchors as indicated on the Drawings.

END OF SECTION

SECTION 31 50 00
TRENCH SAFETY SYSTEMS

PART 1: GENERAL

1.01 SCOPE

- A. Trench Safety Systems

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 - Submittal Procedures.
- B. Submit a trench safety systems program and identify the TOSHA and OSHA competent person for the program. MWS will not issue an approval of the Trench Safety System Program.
- C. Understand MWS does not assume any responsibility for acceptance and/or review of a submitted trench safety systems program.
- D. Submit the design drawings and calculations for special shoring sealed by a registered TN Professional Engineer when required per TOSHA and OSHA standards.

1.03 MEASUREMENT AND PAYMENT

- A. Consider expenses for trench safety systems, operations, and designs incidental to the Work and no separate payment allowed.

1.04 GENERAL

- A. Provide trench safety systems necessary to complete the Work in accordance with TOSHA and OSHA standards.
- B. Assume sole responsibility for the implementation of the trench safety systems.
- C. Provide maintenance and daily examinations of trench safety systems for the duration of the Work. Maintain records of daily examinations of the trench safety systems program.
- D. Protect existing structures, streets, walkways, utilities, and other improvements against damages during excavation.
- E. Take responsibility for damages and assume expenses for direct or indirect injury caused by the trench safety system activities to above ground facilities or below ground facilities.
- F. Install and operate necessary dewatering and surface water control measures.
- G. Cease Work immediately if evidence of potential cave-ins or slides are observed and move personnel to safe locations until the necessary precautions have been taken to safeguard personnel.

- H. Indemnify and hold harmless MWS concerning trench safety systems including but not limited to failure to issue a stop work order for unsafe conditions.

PART 2: PRODUCTS

2.01 GENERAL

- A. Provide suitable trench safety systems materials.

PART 3: EXECUTION

3.01 INSTALLATION

- A. Install and maintain trench safety systems in conformance with TOSHA and OSHA standards.
- B. Verify the field conditions encountered during the Work are compatible with the trench safety systems program.
- C. Verify trench safety program components are certified for conditions present.
- D. Coordinate and provide safe access at all times within excavation for MWS to access the Work.

END OF SECTION

SECTION 32 10 00
PAVING AND ROADWAY RESTORATION

PART 1: GENERAL

1.01 SCOPE

- A. Paving and Roadway Restoration

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit data confirming materials that meet specified requirements.

1.03 MEASUREMENT AND PAYMENT

- A. MWS will compensate for paving and roadway restoration at the contract unit price on the Bid Schedule for the following items:
 - 1. Asphalt milling measured in square yards - MWS will compensate for asphalt milling calculated by the specified milling thickness and limits indicated on the Drawings.
 - 2. Asphalt paving measured in square yards - MWS will compensate for asphalt paving calculated by the specified paving thickness and limits indicated on the Drawings.
- B. Consider expenses for temporary and permanent pavement markings, traffic detection loop repairs, water box adjustments, manhole casting adjustments, catch basin adjustments, other casting adjustments, and all other items necessary for a complete paving and roadway restoration incidental to the Work with no separate payment allowed.

1.04 GENERAL

- A. Before performing any Work, secure required permits from Metro Public Works and/or TDOT. MWS will obtain TDOT permits.
- B. For pavement and roadway restoration within local roads, conform to permit conditions and current Metro Public Works specifications.
- C. For pavement repairs within state routes, refer to TDOT Standard Specifications for Road and Bridge Construction and TDOT permit conditions.
- D. Provide temporary and permanent pavement markings to preconstruction alignments unless otherwise indicated on the drawings or directed by MWS.
- E. Remove and replace at no extra cost nonconforming pavement materials.

PART 2: PRODUCTS

2.01 NOT USED

PART 3: EXECUTION

3.01 NOT USED

END OF SECTION

SECTION 32 16 13
CONCRETE CURB AND GUTTER

PART 1: GENERAL

1.01 SCOPE

- A. Concrete Curb and Gutter

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit data confirming materials meet specified requirements.

1.03 MEASUREMENT AND PAYMENT

- A. MWS will compensate for installing concrete curb and gutters at the contract unit price on the Bid Schedule.
- B. Include all cost in the unit price for concrete curb and gutters for form work, labor, equipment, material, and all incidentals necessary for a complete and operable installation.

1.04 GENERAL

- A. Before performing any Work in the right-of-way, secure required permits from Metro Public Works and/or TDOT. MWS will obtain TDOT permits.
- B. For construction of concrete curb and/or gutter within local roads, conform to permit conditions and current Metro Public Works specifications and standard details.
- C. For construction of concrete curb and/or gutter within state routes, refer to TDOT Standard Specifications for Road and Bridge Construction and TDOT permit conditions.
- D. Remove and replace at no extra cost nonconforming materials.

PART 2: PRODUCTS

2.01 NOT USED

PART 3: EXECUTION

3.01 NOT USED

END OF SECTION

SECTION 32 16 23
CONCRETE SIDEWALK, DRIVEWAY, AND MEDIAN

PART 1: GENERAL

1.01 SCOPE

- A. Concrete Sidewalk, Curb Ramp, Driveway, Driveway Ramp, and Median

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit data confirming materials used meet specified requirements.

1.03 MEASUREMENT AND PAYMENT

- A. MWS will compensate for installing sidewalks, driveways, and ramps at the contract unit price on the Bid Schedule.
- B. Include all cost in the unit price for sidewalks, driveways, and driveway ramps for form work, labor, equipment, material, and all incidentals necessary for a complete and operable installation.

1.04 GENERAL

- A. Before performing any Work, secure required permits from Metro Public Works and/or TDOT. MWS will obtain TDOT permits.
- B. For concrete sidewalks, driveways, ramps, and medians within local roads, conform to permit conditions and current Metro Public Works specifications and standard details.
- C. For concrete sidewalks, driveways, ramps, and medians within state routes, refer to TDOT Standard Specifications for Road and Bridge Construction and TDOT permit conditions.
- D. Remove and replace at no extra cost nonconforming materials.

PART 2: PRODUCTS

2.01 NOT USED

PART 3: EXECUTION

3.01 NOT USED

END OF SECTION

SECTION 32 17 26
DETECTABLE WARNINGS

PART 1: GENERAL

1.01 SCOPE

- A. Detectable Warnings

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit data confirming materials meet specified requirements.

1.03 MEASUREMENT AND PAYMENT

- A. MWS will compensate for furnishing and installing detectable warnings at the contract unit price per square foot for the unit installed complete and ready for operation.
- B. Include all cost in the unit price for detectable warnings for preparing the surface to receive the detectable warnings and all incidentals necessary for a complete and operable installation.

PART 2: PRODUCTS

2.01 GENERAL

- A. Conform to current Metro Public Works guidelines, standards and specification for detectable warnings.
- B. Conform to the latest ADA requirements.

PART 3: EXECUTION

3.01 NOT USED

END OF SECTION

SECTION 32 90 00
LANDSCAPING

PART 1: GENERAL

1.01 SCOPE

- A. Topsoil, topsoil modifiers, sod, seeds, plants, trees, irrigation, miscellaneous, and warranty

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. If requested by MWS, provide samples and/or tags of the landscape components to be used for approval prior to installation.

1.03 MEASUREMENT AND PAYMENT

- A. Consider expenses for landscaping incidental to the Work with no separate payment allowed unless specifically included as a bid item on the Bid Schedule.
- B. Furnish all landscaping components, labor, material, tools, appliances, and equipment required as part of landscaping with no separate payment allowed.
- C. Perform rough and finish grading a part of landscaping with no separate payment allowed.

1.04 GENERAL

- A. Comply with all local, state, and federal regulatory requirements concerning landscaping.
- B. Plant or install materials during normal planting seasons for each type of landscape work required.
- C. Match existing terrain contours by uniformly grading topsoil with a sufficient thickness (typically minimum of 4 inches thick) to promote vegetation growth and long term sustainability.
- D. Protect topsoil from wind and water erosion until suitable growth has been established.
- E. Protect existing landscaping components and grasses from damage during construction.
- F. Obtain appropriate permits and receive written approval from MWS before removing any trees or shrubs.
- G. Protect trees and shrubs designated to remain.

1.05 WARRANTY

- A. Provide one year warranty, starting after final completion, on landscaping

components and grasses.

- B. Replace dead and/or damaged landscaping components and grasses during the warranty period.
- C. Periodically examine landscaping components and grasses for proper watering and spraying during the warranty period.
- D. Consider damage caused by natural hazards such as hail, high winds, or storms included in the warranty.
- E. Consider plants, trees, and grasses which die due to insects or diseases included in the warranty.

1.01 FINAL ACCEPTANCE

- A. Request a final acceptance review from MWS at the end of the 1-year warranty period.
- B. Request approval of grasses when the following conditions are met: no bare spots larger than 1 square foot and the total area of bare spots does not exceed 5 percent of the entire grass area.
- C. Expect no partial acceptance of grasses.

PART 2: PRODUCTS

2.01 LANDSCAPING

- A. Restore disturbed areas with similar components unless otherwise specified.
- B. Supply topsoil that is fertile, friable, natural sandy loam surface soil and reasonably free of clay lumps, brush, weeds, non-soil materials, contamination, roots, stumps, and/or stones.
- C. Obtain topsoil from local sources having similar characteristics found at the project site; do not obtain topsoil from bogs, marshes, or wetlands.
- D. Provide an inorganic commercial fertilizer which is uniform in composition, dry and free flowing, in original unopened containers, each bearing the manufacturer's guaranteed analysis. Do not use caked, damaged or otherwise unsuitable fertilizer. Use the proper fertilizer mixes based on the manufacturer's recommendations for the type of application.
- E. Identify and provide soil modifiers as needed to topsoil to promote healthy growth and satisfy warranty conditions.
- F. Provide grass seed, sod, trees, shrubs, hydro seeding, grass mats, etc. to match the existing vegetation of the surrounding area unless type is specified elsewhere.

PART 3: EXECUTION

3.01 NOT USED

END OF SECTION

SECTION 33 00 01

WATER MAINS

PART 1: GENERAL

1.01 SCOPE

- A. Water Mains, Temporary Water Mains, Water Main Taps and Connections, Abandonment of Water Mains, and Excavation and Backfill for Water Mains.

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit manufacturer's product data for proposed water main pipe, joints, joint materials, specials, coatings, paint for exterior piping, and fittings for approval.
- C. Submit crushed stone bedding and envelope material sieve analysis and compaction methods.
- D. Submit asphaltic binder information certifying material is in conformance with the latest revision of Metro Public Works standard specification Section 02575 if the water main is to be installed within a Metro Public Works roadway or the latest revision of the applicable TDOT asphaltic binder specification if water main is to be installed within a TDOT roadway
- E. Submit flowable fill information certifying material is in conformance with the latest revision of Metro Public Works standard specification Section 02225 if the water main is to be installed within a Metro Public Works roadway or the latest revision of the applicable TDOT flowable specification if water main is to be installed within a TDOT roadway.
- F. Submit outside roadway backfill material source, quality information, and compaction methods.
- G. Submit Proctor Density Test results in accordance with the latest revision of ASTM D698 or ASTM D1557 when required by MWS.
- H. Submit compaction field testing results in accordance with the latest revision of ASTM D6938 or other approved method when required by MWS.
- I. Submit manufacturer's product data for proposed temporary water mains if utilized.

1.03 MEASUREMENT AND PAYMENT

- A. MWS will compensate for furnishing and installing water mains at the contract unit price per linear foot for the water main installed complete and ready for operation. Measure the water main horizontally along the centerline of the pipe in

place including valves, bends, reducers, and offsets.

1. Include cost in the unit price for water mains for labor, equipment, material, cutting, laying, joints, lowering, raising, other offsets necessary to avoid obstructions, field adjustments of alignment, rodding, temporary sampling/filling/flushing caps, standby time and delay in MWS isolation of existing water mains, hydrostatic testing and other testing required, disinfection and all incidentals necessary for a complete and operable installation.
 2. Include cost in the unit price for water mains for fittings whether fittings and/or offsets are indicated on the Drawings or not.
 3. Include cost in the unit price for water mains for excavation. Excavation is unclassified with no distinction made between rock and/or dirt excavation. Rock excavation beyond anticipated or indicated in a provided geotechnical report will not be considered basis for additional payment.
 4. Include cost in the unit price for water mains for crushed stone bedding, crushed stone envelope, and additional crushed stone used as backfill material when water main exceeds minimum depths.
 5. Include cost in the unit price for water mains for outside of roadway backfill material.
 6. Include cost in the unit price for water mains for dewatering operations including but not limited to water filtration systems for groundwater, obtaining permits with appropriate agencies on dewatering activities, and appropriately filtering and properly disposing of groundwater in accordance with permits.
 7. Undercutting of undesirable material at the trench base and approved refill material to be paid with Unforeseen Work Elements allowance bid item.
- B. MWS will compensate for furnishing and installing taps and connections at the contract unit price per each for each taps and connection complete and ready for operation.
1. Include all cost in the unit price for taps and connections for labor, equipment, excavation, material, rodding, backfilling, and all incidentals necessary for a complete and operable installation.
- C. MWS will compensate for cutting and capping in order to abandon a water main at the contract unit price of each for each cutting and capping operation.
1. Include all cost in the unit price for cutting and capping for labor, equipment,

materials, permanent solid water main cap, removing valve boxes over valves on abandoned water mains, and all incidentals necessary for a complete water main abandonment operation.

- D. MWS will compensate for furnishing and installing flowable fill at the contract unit price per theoretical cubic yard calculated utilizing the specified trench width per water main size, the length of water main installed, and the specified flowable fill depth; not the actual amount of flowable fill if more material is installed.
 - 1. Include all cost in the unit price for flowable fill for excavation, material, labor, and all incidentals necessary for a complete installation.
- E. MWS will compensate for furnishing and installing asphalt binder at the contract unit price per theoretical cubic yard calculated utilizing the specified trench width per water main size, the length of water main installed, and the specified asphalt binder depth; not the actual amount of asphalt binder if more material is installed.
 - 1. Include all cost in the unit price for asphalt binder for excavation, material, labor, and all incidentals necessary for a complete installation.
- F. MWS will compensate for furnishing and installing miscellaneous concrete at the contract unit price per cubic yard for concrete installed between a proposed water main traversing perpendicular and below an existing sewer main.
 - 1. Include all cost in the unit price for miscellaneous concrete for excavation, materials, labor, and all incidentals necessary for a complete installation.
- G. MWS will compensate for furnishing and installing temporary water mains at the contract unit price per linear foot for the temporary water main installed complete and ready for operation if indicated on the Bid Schedule. MWS will not compensate for furnishing and installing temporary water mains if being installed for contractor's ease of construction and convenience, or being installed due to contractor's negligence. Measure the temporary water main horizontally along the centerline of the pipe in place including valves, bends, reducers, and offsets.
 - 1. Include all cost in the unit price for temporary water mains for labor, equipment, excavation, material, cutting, laying, temporary fittings, temporary valves, backfill, testing, disinfection, temporary connections to water system, temporary service connections, and all incidentals necessary for a complete and operable installation.

1.04 GENERAL

- A. Calculate Bid Schedule payment items of flowable fill and asphalt binder by the

following table. If a wider than indicated trench width is utilized during construction, payment will only be compensated based on the trench width limits detailed in the following table.

Nominal Pipe Diameter (inches)	Trench Width (feet)
12 and smaller	2.5
14	3.0
16	3.0
18	3.0
20	3.5
24	4.0
30	4.5
36	5.0
42	6.0
48	6.5
54	7.0
60	8.0
64	8.5

B. Bury water main and backfill trench in roadways in accordance with the following table. Bury pipe at minimum depths unless additional depth is required to avoid an obstruction. Utilize crushed stone material compacted in maximum 8-inch lifts at the proper moisture content as the supplementary trench backfill material when water main must be installed below the minimum depths.

Nominal Pipe Size	MPW Roadway		TDOT Roadway
	Smaller than 12"	12" and Larger	All Pipe Sizes
Asphalt Binder above Flowable Fill to Grade	8"	8"	11"
Flowable Fill above Crushed Stone Envelope	14"	20"	24"
Crushed Stone Envelope above Top of Pipe	8"	8"	8"
Total Cover (Min Depths)	30"	36"	43"
Crushed Stone Bedding Below Bottom of Pipe	6"	6"	6"

C. Bury water main and backfill trench outside of roadways in accordance with the following table. Bury pipe at minimum depths unless additional depth is required to avoid an obstruction. Utilized native backfill material compacted in 12 inch lifts

as the supplementary trench backfill material when water main must be installed below the minimum depths.

Nominal Water Main Size	Total Cover (Minimum Depth)	Crushed Stone Bedding below Bottom of Pipe	Crushed Stone Envelope above Top of Pipe	Native Soil above Crushed Stone Envelope to Finished Grade
Smaller than 12"	30"	6"	8"	22"
12" and Larger	36"	6"	8"	28"

- D. Maintain existing water services throughout construction.
- E. Request shut down isolation times and durations in writing to MWS 48 hours in advance for approval.
- F. Provide water customers at least 24 hour notice prior to an interruption of water service.
- G. Do not operate valves on the existing system and/or new water mains placed in service.
- H. MWS will make every reasonable effort to isolate and shut off the flow of water when required for the Work. Circumstances may prevent timely water shut offs such as but not limited to faulty valves, water main breaks, and lack of forces due to higher priority situations. Consider standby time due to these types of delays incidental to the Work will no separate payment allowed.
- I. Do not make connections to the existing water system until applicable tests including; disinfection and hydrostatic testing have been performed and reported to MWS and found to be in compliance.
- J. Install temporary caps on new water mains and tap sampling caps with a pluggable outlet of adequate size to be utilized as a sampling, filling and/or flushing location.
- K. Install a solid permanent water main cap on the end of an existing water main when performing a cutting and capping operation for abandonment of a water main.
- L. Remove valve boxes over valves on abandoned water mains.
- M. Perform Proctor Density Test in accordance with the latest revision of ASTM D698 or ASTM D1557 when required by MWS. Test to be performed by an independent MWS approved materials testing firm. Pay for test if Work is found to be noncompliance.
- N. Perform compaction field testing results in accordance with the latest revision of

ASTM D6938 or other approved method when required by MWS. Compaction tests to be performed by an independent MWS approved materials testing firm. Pay for test if Work is found to be noncompliance.

PART 2: PRODUCTS

2.01 GENERAL

- A. Provide water main products and accessories from manufacturers in accordance with MWS published Approved Materials List.
- B. Provide pipe, pipe fittings, plumbing fittings, and fixtures, including but not limited to, coated or uncoated brass or bronze materials that could come in contact with drinking water in accordance with the 2011 Reduction of Lead in Drinking Water Act that amends the Safe Drinking Water Act Section 1417 effective January 4, 2014. The following link provides further clarification and direction on the requirement: <http://nepis.epa.gov/Adobe/PDF/P100GRDZ.pdf>.
- C. Provide ductile iron restrained joint pipe for water mains unless otherwise indicated on the Drawings.
- D. Provide No. 57 or No. 67 crushed stone for pipe bedding, pipe envelope, and additional backfill material when water main exceeds minimum buried depths.
- E. Provide asphaltic binder in conformance with the latest revision of Metro Public Works standard specification Section 02575 when the water main is to be installed within a Metro Public Works roadway and provide asphaltic binder in conformance with the latest revisions of the applicable TDOT specification when the water main is to be installed within a TDOT roadway.
- F. Provide excavatable flowable fill in conformance the latest revision of Metro Public Works standard specification Section 02225 when a water main is to be installed within a Metro Public Works roadway and provide excavatable flowable fill in conformance with the latest revisions of the applicable TDOT specification when the water main is to be installed within a TDOT roadway.
- G. Provide Certa-Lok Yelomine restraint joint pipe and fittings or approved equal for temporary water mains. Provide a temporary water main and fittings with a pressure rating equal to 1.5 times the working pressure and adequately sized to maintain the existing level of water service to the customers.

PART 3: EXECUTION

3.01 GENERAL

- A. Deliver water main products and accessories to job site free of damages and/or

defects. If damages or defects are discovered, provide new material at no cost to MWS.

- B. Store materials on site in enclosures or under protective above ground coverings.
- C. Keep interiors of water main products free of dirt and debris.
- D. Install water main, joints, and fittings per manufacturer's recommendations.
- E. Install water main to maintain minimum cover as specified.
- F. Install water main pipe in crushed stone gravel bedding in the dry.
- G. Install dewatering systems, if necessary, for excavation and water main installation. Provide water filtration systems for groundwater, obtain permits with appropriate agencies for dewatering activities and appropriately filter and properly dispose of groundwater in accordance with permits.
- H. Do not deflect water mains in excess of the manufacturer's recommendations.
- I. Clean the inside of the bell and the outside of the plain end of the pipe with a wire brush wipe clean prior to joint assembly.
- J. Clean all gaskets prior to joints and/or fittings assembly.
- K. Grind all rough edges of the plain end of a field cut pipe.
- L. Maintain a minimum of 10 feet horizontal separation when installing a water main sharing a parallel alignment with a sewer main or sewer service line.
- M. If sufficient cover is available, install the water main over existing sewer mains or sewer service lines when sharing perpendicular alignments. Maintain a minimum vertical separation of 18 inches from the bottom of the water main to the top of the existing sewer mains or sewer service lines.
- N. If sufficient cover is not available, install the water main under the existing sewer mains or sewer service lines when sharing perpendicular alignments. Maintain a minimum vertical separation of 24 inches from the bottom of the sewer main or sewer service to the top of the water main. Center the water main pipe at the point of the crossing to keep the joints at equal distances and as far as possible from the sewer main or sewer service line. Install concrete material between the water and sewer crossing for the entire width of the distance between the utilities and for a length of at least 6 feet centered at the point of crossing.
- O. Disinfect water mains, valves, fittings, temporary water mains, and appurtenances in accordance with Section 33 13 10 Disinfection of Water Mains.

3.02 EXCAVATION

- A. No blasting will be permitted.

- B. MWS may limit the method of excavation if conditions warrant such as trenching within areas of high concentration of utilities.
- C. Contact Tennessee One Call Center (1-800-351-1111) the location of buried facilities pursuant to TCA 65-31-101 through TCA 65-31-133; however, take sole responsibility for the location of all affected underground utilities.
- D. Locate and preserve existing utilities. The types and locations of known existing utilities as indicated on the Drawings are approximate. Repair or replace damaged utilities, whether shown on the Drawings or not, at no cost to MWS.
- E. Notify MWS immediately, stop the Work, and wait for MWS direction before resuming the Work if solvents, petroleum products, or any unknown chemical substance is discovered during excavation.
- F. Do not remove any structures unless the structure is indicated to be removed on the Drawings or written approval is received by MWS.
- G. Consider all excavation material unclassified, whether a geotechnical report is provided or not.
- H. Saw cut pavement to trench width limits when excavation is within a roadway.
- I. Excavate trench width to permit a minimum of 6 inches between the edge of the trench and the outside of the water main.
- J. Excavate to allow for a minimum of 6 inches of crushed stone bedding below the bottom of the water main.
- K. Remove unstable soil at the trench bottom if discovered and refill area with appropriate material. Notify and receive approval from MWS prior to undercutting and removing undesirable material at the trench base and utilizing approved refill material.
- L. Remove all loose material from the trench bottom. Do not lay water mains and accessories directly on rock.
- M. Excavate to allow minimum water main cover per water main size and roadway conditions as indicated.
- N. Excavate in accordance with Trench Safety Systems, TOSHA and OSHA regulations, and permits.
- O. Dispose of surplus excavated material at a Metro approved permitted site. Do not place excavated material on private property.

3.02 BACKFILL WITHIN ROADWAY

- A. Take precautions not to damage the water main and water main accessories

- during backfill operations. Replace damaged items at no cost to MWS.
- B. Install specified backfill material for the full width of the excavated trench and to specified depths.
 - C. Install No. 57 or No. 67 crushed stone compacted to 95% Standard Proctor Density in 8-inch lifts for pipe bedding and pipe envelope. Place crushed stone bedding 6 inches below the bottom of the water main. Place crushed stone envelope to a height of 8 inches above the top of the water main. Utilize crushed stone material compacted in maximum 8-inch lifts at the proper moisture content as the supplementary trench backfill material when water main must be installed below the minimum depths.
 - D. Install flowable fill above crushed stone envelope at indicated depths.
 - E. Install asphalt binder above flowable fill at the indicated depths compacted flush with the roadway surface elevation. Maintain smooth driving surface until final paving is complete.
 - F. Remove the indicated thickness of asphalt binder as part of the milling operations when preparing to pave the roadway.
 - G. Install the indicated thickness of asphaltic surface mix as part of the paving operations in accordance with Metro Public Works or TDOT specifications.
 - H. Remediate any settlement of backfill material for a period of one year after final completion and final acceptance of the Work by MWS.

3.03 BACKFILL OUTSIDE OF ROADWAY

- A. Take precautions not to damage the water main and water main accessories during backfill operations. Replace damaged items at no cost to MWS.
- B. Install specified backfill material for the full width of the excavated trench.
- C. Install No. 57 or No. 67 crushed stone compacted to 95% Standard Proctor Density in 8-inch lifts for pipe bedding and pipe envelope. Place crushed stone bedding 6 inches below the bottom of the water main. Place crushed stone envelope to a height of 8 inches above the top of the water main.
- D. Install native soil compacted to 90% maximum Proctor Density in 12-inch lifts above the crushed stone envelope to finished grade. Utilize native soil material as the supplementary trench backfill material when water main must be installed below the minimum depths. Do not utilize rock greater than 8 inches as backfill.
- E. Remediate any settlement of backfill material for a period of one year after final completion and final acceptance of the Work by MWS.

- F. Seed and straw disturbed area to reestablish growth. Replace trees and vegetation removed during clearing and excavation with trees and vegetation of equal size or larger.

END OF SECTION

SECTION 33 05 16.17

VALVE BOXES, METER BOXES, AND VAULTS

PART 1: GENERAL

1.01 SCOPE

- A. Precast valve boxes, meter boxes, and vaults.
- B. This Section does not include Metro Public Works and TDOT structures.

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit manufacturer's product data for proposed valve boxes, meter boxes, and vaults for approval.
- C. Furnish five sets of notarized shop drawings and certificates of inspection, stating that the valve boxes, meter boxes, and/or vaults were constructed and satisfactorily tested for the conditions present on-site as to loadings in full compliance with these Specifications.

1.03 MEASUREMENT AND PAYMENT

- A. Consider expenses for furnishing, installing, and/or adjustment of boxes and vaults incidental to the Work with no separate payment allowed unless specifically included as a bid item on the Bid Schedule.
- B. Include in the installation and/or adjustment of boxes and vaults the labor, equipment, materials, box or vault, footing blocks, box casting including lid, excavation, bedding, backfill, and incidentals necessary for a complete installation.
- C. For vaults, if undesirable base material is discovered, undercutting undesirable material at the base and approved refill material to be paid with Unforeseen Work Elements allowance bid item.

PART 2: PRODUCTS

2.01 GENERAL

- A. Furnish valve boxes and meter boxes in accordance with MWS published Approved Materials List.
- B. Provide a minimum 4000 psi, 28-day compressive strength precast concrete sections of the sizes and configurations indicated on the Drawings, complete with reinforcement to support an AASHTO H-20 vehicle loading for valve boxes, meter boxes, and vaults.

- C. For valve boxes and meter boxes, provide precast concrete footing blocks of the size, configuration and quantity indicated on the Drawings and provide Portland cement in conformance with the latest revision of ASTM C-150 Type 1 for use in establishing a full mortar bed to set the casting..
- D. Provide sound, smooth, blemish free cast iron castings in conformance with the latest revision of ASTM A48, Class 30 with support of an AASHTO H-20 loading for vehicles and of the sizes and configurations indicated on the Drawings.
- E. Provide hand ground contact surfaces for the covers and frames so that the cover rests securely on the frame without movement and is in contact with the frame for the entire perimeter of the contact surface.
- F. Provide casting covers with the required identification indicated on the Drawings.
- G. Provide vaults and vault lids indicated on the Drawings.

PART 3: EXECUTION

3.01 INSTALLATION

- A. Install valve boxes, meter boxes, and vaults plumb and flush with existing ground surface unless otherwise indicated on the Drawings.
- B. For vaults, remove unstable soil at the base if discovered and refill area with appropriate material. Notify and receive approval from MWS prior to undercutting and removing undesirable material at the base and utilizing approved refill material.

END OF SECTION

SECTION 33 11 00.11

POLYVINYL CHLORIDE (PVC) PIPE AND FITTINGS

PART 1: GENERAL

1.01 SCOPE

- A. Polyvinyl chloride (PVC) pipe and fittings
- B. PVC pipe, joints, and fittings for low pressure sanitary sewers and gravity sewer mains.

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittals Procedures.
- B. Submit manufacturer's product data for proposed PVC pipe, joints, and fittings for approval.
- C. Furnish five sets of shop drawings and a statement from the factory inspector, stating that the pipe was constructed and satisfactorily tested in full compliance with these specifications.
- D. When required by MWS, furnish five sets of shop drawings and a statement from the factory inspector, stating that the joints, joint materials, specials, and fittings were constructed and satisfactorily tested in full compliance with these specifications.
- E. Submit a certificate of inspection, sworn to by the factory inspector stating the number of and lengths of pieces of pipe making up the shipment.
- F. Provide MWS with the access to observe all testing, if requested, and submit certified copies of all test results prior to pipe and fitting shipment.
- G. Submit certification from the manufacturer verifying conformance with the latest revision of the applicable ASTM Standards.

1.03 MEASUREMENT AND PAYMENT

- A. Compensation for PVC pipe and fittings is not addressed in this section; refer to gravity sewer mains and/or low pressure sanitary sewers specification sections.
- B. Consider all requirements in this section incidental to the Work with no separate payment allowed.

PART 2: PRODUCTS

2.01 GENERAL

- A. Provide PVC pipe laying nominal lengths of 14 or 20 feet for gravity sewer mains and 20 feet for low pressure sanitary sewers.

- B. Provide PVC pipe with Styrene Butadiene Rubber (SBR) gaskets in conformance with the latest revision of ASTM F477.
- C. Provide Cell Classification 12454 A or 12454 B PVC manufactured in conformance with the latest revision of ASTM D1784.
- D. Provide piping marked with diameter, manufacture's name or trademark, pressure pipe type, grade and class to be clearly visible.
- E. Provide Green Type P solvent cement conforming to the latest revision of ASTM D2564.

2.02 GRAVITY SEWER MAINS

- A. Furnish PVC pipe, fittings, and accessory materials for gravity sewer mains in accordance with MWS published Approved Materials List.
- B. Provide SDR 35 or SDR 26 PVC pipe and fittings as indicated on the Drawings.
- C. For pipe 15 inches and smaller, provide pipe and fittings in conformance with the latest revision of ASTM D3034, with a pipe stiffness in conformance with the latest revision of ASTM D 3412 and a pipe joint in conformance with the latest revision of ASTM D3212.
- D. For pipe 18 inches and larger, provide pipe and fittings in conformance with the latest revision of ASTM F679, with a pipe stiffness in conformance with the latest revision of ASTM D3412 and a pipe joint in conformance with the latest revision of ASTM D3212 for 18-inch and larger.
- E. Provide SDR 35 or SDR 26 PVC full body injection molded or factory fabricated fittings and cleanout assemblies.

2.03 LOW PRESSURE SANITARY SEWERS FOR SIZES EQUAL TO OR LESS THAN 1 ¼"

- A. Provide PVC Solvent Weld Pressure SDR 21 pipe manufactured in strict accordance with the latest revision of ASTM D2241 for physical dimensions and tolerances.
- B. Provide fittings with the same pressure rating required for the pipe.
- C. Provide each production run of pipe manufactured exceeding the test requirements for materials, workmanship, burst pressure, impact resistance, flattening, and extrusion quality conforming to the latest revision of ASTM D2241.
- D. Provide belled end pipe with tapered sockets to create an interference type fit meeting dimensional requirements and the minimum socket length for pressure-type belled sockets conforming to the latest revision of ASTM D2672.
- E. Provide pipe in nominal lengths of 20 feet.

- F. Provide piping with a #12 AWG, high strength copper clad steel conductor with HDPE insulation rated for direct burial. Provide wire to be brought up into the valve box at 1,000 feet maximum intervals and taped to the top of the force main at minimum 10-foot intervals.

2.04 LOW PRESSURE SANITARY SEWER FOR SIZES GREATER THAN 1 ¼"

- A. Provide Type 1, Grade 1 or 2 PVC SDR 21 pipe manufactured in strict accordance with the latest revision of ASTM D2241 for physical dimensions and tolerances and joints in accordance with the latest revision of ASTM-D3139.
- B. Provide fittings with the same pressure rating required for the pipe.
- C. Provide each production run of pipe manufactured exceeding the test requirements for materials, workmanship, burst pressure, impact resistance, flattening, and extrusion quality conforming to the latest revision of ASTM D2241.
- D. Provide pipe in nominal lengths of 20 feet.
- E. Provide single rubber gasket push-on (bell and spigot) joints designed so that the pipe and fittings may be connected without the use of solvent cement or any special equipment.
- F. Provide solvent welded type joints for clean out assemblies.
- G. Provide piping with a #12 AWG, high strength copper clad steel conductor with HDPE insulation rated for direct burial. Provide wire to be brought up into the valve box at 1,000 feet maximum intervals and taped to the top of the force main at minimum 10-foot intervals.

PART 3: EXECUTION

3.01 NOT USED

END OF SECTION

SECTION 33 11 13.13
DUCTILE IRON PIPE AND FITTINGS

PART 1: GENERAL

1.01 SCOPE

- A. Ductile Iron Pipe (DIP), Joints, and Fittings
- B. Ductile iron pipe, joints, and fittings for water mains, sewer force mains, and gravity sewer mains.

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit manufacturer's product data for proposed pipe, joints, joint materials, specials, coatings, paint for exterior piping, and fittings for approval.
- C. Furnish five sets of shop drawings and a statement from the factory inspector, stating that the pipe was constructed and satisfactorily tested in full compliance with these specifications.
- D. When required by MWS, furnish five sets of shop drawings and a statement from the factory inspector, stating that the joints, joint materials, specials, and fittings were constructed and satisfactorily tested in full compliance with these specifications.
- E. Submit a certificate of inspection, sworn to by the factory inspector stating the number of and lengths of pieces of pipe making up the shipment.
- F. Provide MWS with the access to observe all testing, if requested, and submit certified copies of all test results prior to pipe and fitting shipment.
- G. Submit a certificate of inspection stating the pipes were hydrostatically tested to a minimum of 500 psi for a minimum of 5 seconds in conformance with the latest revision of AWWA Standard C151.
- H. For pipes 30 inches and larger submit a certificate of inspection stating the pipes were subjected to a pressure equal to 75% of the 42,000 psi minimum yield strength for ductile iron pipe.
- I. Submit certification from the manufacturer verifying conformance with the latest revision of the applicable AWWA Standards.

1.03 MEASUREMENT AND PAYMENT

- A. Compensation for ductile iron pipe and fittings is not addressed in this section; refer to water mains, gravity sewer mains, and/or sewer force mains specification sections.

- B. Consider all requirements in this section incidental to the Work with no separate payment allowed.

PART 2: PRODUCTS

2.01 GENERAL

- A. Provide ductile iron pipe, fittings, and accessory materials that meet the requirements of NSF 61, Drinking Water System Components – Health Effects.
- B. Provide ductile iron pipe laying nominal lengths of 18 or 20 feet.
- C. Furnish ductile iron pipe and fittings from manufacturers in accordance with MWS published Approved Materials List.
- D. Provide gasket lubricant in accordance with the manufacturer's instructions, NSF 61, and in conformance with the latest revision of AWWA Standard C111.
- E. Gray iron fittings are not allowed.

2.02 DUCTILE IRON PIPE AND FITTINGS FOR WATER MAINS

- A. Provide Pressure Class 350 ductile iron pipe for all pipe sizes in conformance with the latest revision of AWWA Standard C151.
- B. Provide an interior cement mortar lining with asphaltic seal coating for all pipe, joints, and fittings in conformance with the latest revision of AWWA Standard C104.
- C. For buried pipe, provide an exterior asphaltic coated surface, joints, and fittings in accordance with the latest revision of AWWA Standard C151.
- D. For non-buried pipe, provide an exterior protective coating in accordance with the latest revisions of AWWA Standard C151 with the following:
 - 1. Clean, dry, remove all existing paint and black coating, and sandblast with non-silica media for surface preparation in accordance with NAPF 500-3 Standard.
 - 2. Apply TNEMEC N69(F) - Hi-Build Epoxoline II or approved equal at 4.0-6.0 mils for 1st coat.
 - 3. Apply TNEMEC N69 - Color Hi-Build Epoxoline II or approved equal at 4.0-6.0 mils for intermediate coat.
 - 4. Apply TNEMEC 1074/1075 Endura Shield Dark Blue or approved equal at 2.0-3.0 mils for finished coat.
 - 5. Do not coat nameplates, brass, or stainless steel surfaces.
- E. For sizes 24" and below, provide restrained joints and fittings with a minimum pressure rating of 350 psi in conformance with the latest revisions of AWWA

Standard C110, AWWA Standard C111, and AWWA Standard C153.

1. Provide Fast-Grip® joints, Field Flex-Ring® joints, Field LOK 350® joints, or approved equal for buried pipe in sizes 4" to 24".
 2. Provide Fast-Grip® fittings, Field Flex-Ring® fittings, Field LOK 350® fittings or mechanical joint fittings with Mega-Lug® or approved equal restraint for buried pipe in sizes 4" to 24".
 3. For fittings at fire hydrants and valves provide mechanical joint fittings with Mega-Lug® or approved equal restraint.
 4. Provide flanged joints and fittings in above ground or vault applications.
- F. For sizes above 24", provide restrained joints and fittings with a minimum pressure rating of 250 psi in conformance with the latest revisions of AWWA Standard C110, AWWA Standard C111 and AWWA Standard C153.
1. Provide HP LOK® joints, TR Flex® joints, Flex-ring® joints, LOK-Ring® joints or approved equal for buried pipe in sizes greater than 24".
 2. Provide HP LOK® fittings, TR Flex® fittings, Flex-ring® fittings, LOK-Ring® fittings or mechanical joint fittings with Mega-Lug® or approved equal restraint for buried pipe in sizes greater than 24".
 3. For fittings at fire hydrants and valves, provide mechanical joint fittings with Mega-Lug® or approved equal restraint.
 4. Provide flanged joints and fittings in above ground or vault applications.

2.03 DUCTILE IRON PIPE AND FITTINGS FOR GRAVITY SEWERS

- A. Provide Pressure Class 350 ductile iron pipe for all pipe sizes in conformance with the latest revision of AWWA Standard C150 and AWWA Standard C151.
- B. Provide interior 40 mil dry film thickness Protecto 401 Ceramic Epoxy or approved equal for all pipe and fitting sizes in conformance with the latest revision of ASTM E 96 Method A; ASTM B 117; ASTM G 95; ASTM G 22; ASTM D 714; An abrasion resistance test using European Standard EN 598:1994, Section 7.8; and a thickness test using SSPC-PA2.
- C. Provide an exterior asphaltic coated surface on all buried pipe and fittings in accordance with the latest revision of AWWA Standard C151.
- D. For sizes 24" and below, provide push-on type single joints with styrene butadiene rubber (SBR) gaskets with a minimum pressure rating of 350 psi in conformance with the latest revision of AWWA Standard C110, AWWA Standard C111, AWWA Standard C150, AWWA Standard C151, and AWWA Standard

C153.

- E. For sizes above 24", provide push-on type single joints with styrene butadiene rubber (SBR) gaskets with a minimum pressure rating of 250 psi in conformance with the latest revision of AWWA Standard C110, AWWA Standard C111, AWWA Standard C150, AWWA Standard C151, and AWWA Standard C153.
- F. Within casing pipe, for sizes 24" and below, provide Fast-Grip® joints, Field Flex-Ring® joints, Field LOK 350® joints, or approved equal restrained joints with a minimum pressure rating of 350 psi in conformance with the latest revisions of AWWA Standard C110, AWWA Standard C111, and AWWA Standard C153.
- G. Within casing pipe, for sizes above 24", provide HP LOK® joints, TR Flex® joints, Flex-ring® joints, LOK-Ring® joints or approved equal restrained joint with a minimum pressure rating of 250 psi in conformance with the latest revisions of AWWA Standard C110, AWWA Standard C111, and AWWA Standard C153.

2.04 DUCTILE IRON PIPE FOR WASTEWATER FORCE MAINS

- A. Provide Pressure Class 350 ductile iron pipe for all pipe sizes in conformance with the latest revision of AWWA Standard C151.
- B. Provide interior 40 mil dry film thickness Protecto 401 Ceramic Epoxy or approved equal for all pipe and fitting sizes in conformance with the latest revision of ASTM E 96 Method A; ASTM B 117; ASTM G 95; ASTM G 22; ASTM D 714; An abrasion resistance test using European Standard EN 598:1994, Section 7.8; and a thickness test using SSPC-PA2.
- C. For buried pipe, provide an exterior asphaltic coated surface, joints, and fittings in accordance with the latest revision of AWWA Standard C151.
- D. For non-buried pipe, provide an exterior protective coating in accordance with the latest revisions of AWWA Standard C151 with the following:
 - 1. Clean, dry, remove all existing paint and black coating, and sandblast with non-silica media for surface preparation in accordance with NAPF 500-3 Standard.
 - 2. Apply TNEMEC N69(F) Hi-Build Epoxoline II or approved equal at 4.0-6.0 mils for 1st coat.
 - 3. Apply TNEMEC N69 Color Hi-Build Epoxoline II or approved equal at 4.0-6.0 mils for intermediate coat.
 - 4. Apply TNEMEC 1074/1075 Endura Shield Dark Blue or approved equal at 2.0-3.0 mils for finished coat.

5. Do not coat nameplates, brass, or stainless steel surfaces.
- E. For sizes 24" and below, provide restrained joints and fittings with a minimum pressure rating of 350 psi in conformance with the latest revisions of AWWA Standard C110, AWWA Standard C111, and AWWA Standard C153
1. Provide Fast-Grip® Joints, Field Flex-Ring® Joints, Field LOK 350® Joints, or approved equal for buried pipe in sizes 4" to 24".
 2. Provide Fast-Grip® Fittings, Field Flex-Ring® Fittings, Field LOK 350® Fittings or Mechanical Joint Fittings with Mega-Lug® or approved equal restraint for buried pipe in sizes 4" to 24".
 3. Provide flanged joints and fittings in above ground or vault applications.
- F. For sizes above 24", provide restrained joints and fittings with a minimum pressure rating of 250 psi in conformance with the latest revisions of AWWA Standard C110, AWWA Standard C111 and AWWA Standard C153.
1. Provide HP LOK® Joints, TR Flex® Joints, Flex-ring® Joints, Lok-Ring® Joints or approved equal for buried pipe in sizes greater than 24".
 2. Provide HP LOK® Fittings, TR Flex® Fittings, Flex-ring® Fittings, Lok-Ring® Fittings or Mechanical Joint Fittings with Mega-Lug® or approved equal restraint for buried pipe in sizes greater than 24".
 3. Provide flanged joints and fittings in above ground or vault applications.

PART 3: EXECUTION

3.01 NOT USED

END OF SECTION

SECTION 33 12 13
WATER SERVICE LINES AND CONNECTIONS

PART 1: GENERAL

1.01 SCOPE

- A. Water Service Lines and Service Connections

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit manufacturer's product data for proposed pipe, joints, joint materials, specials, valves, and fittings for approval.
- C. Furnish five sets of notarized shop drawings, stating that the piping, joints, joint materials, specials, valves, and fittings were constructed and satisfactorily tested in full compliance with these specifications.

1.03 MEASUREMENT AND PAYMENT

- A. For service connections, MWS will compensate for furnishing and installing the connections or taps with the corporation stop and required fittings to the proposed or existing water main per each for the unit installed complete and ready for operation. Include all costs in the unit price for furnishing, installing, and testing the connection including but not limited to labor, materials, equipment, service, excavation, bedding, backfill, tapping the water main, corporation stop, fittings, and all incidentals necessary for a complete and operable installation.
- B. For service lines, MWS will compensate for furnishing and installing water service line inside and outside of roadways horizontally along the centerline of the pipe in place from the water service connection location to the water main to the water meter box location and/or where construction ends per linear foot installed with no deductions in length for fittings, valves, corporation stops, and/or boxes. Include all costs in the unit price for furnishing, installing, and testing water service line, including but not limited to: labor, materials, equipment, excavation, backfill, pipeline, fittings, corporation stops, curb stops, and all incidentals necessary for a complete and operable installation. Consider the requirement of bored/jacked services lines to be incidental to the service line bid item with no separate payment allowed.
- C. Compensate MWS for wet tap of service lines connections.
- D. MWS will compensate, in addition to the contract unit price per linear feet of

copper water service line, a lump sum value of \$250.00 for all lead service line replacements for the additional coordination efforts, proper disposal, and delays that may occur. The Contingency for Unforeseen Work Elements will be utilized to compensate for the additional lump sum amount of \$250.00 for each lead service line replacement. There will be no other compensation for this effort.

1.04 GENERAL

- A. Reconnect all existing service lines to the new water main, whether shown on the Drawings or not.
- B. Jack and/or bore water service lines under existing pavement.
- C. For water service lines 2-1/2 inches in diameter and smaller, the contractor shall replace galvanized and/or damaged water service lines from the water main to the meter with copper. Connections to include flared fittings at the water main with a minimum 12 inch long flexible gooseneck and with either compression or flanged fittings for connections at the meter.
- D. Contact MWS if lead services are discovered. Replace lead service lines from the water main to the meter with copper only after timing of replacement has been coordinated with MWS and the customer. This may cause some delays and additional coordination. Replacement of lead service lines requires an additional sampling protocol that will delay the replacement of the service line until the protocol can be coordinated with the customer. Replacement of lead service lines also requires proper disposal of the lead material.
- E. Replace all water service lines sizes less than ¾ inches in size.
- F. Perform dry taps only.
- G. Only MWS will perform wet taps on their schedule.
- H. Prepare the site for wet taps including excavation; cleaning pipe; and backfill after completion of the tap.

PART 2: PRODUCTS

2.01 WATER SERVICE LINES AND CONNECTIONS

- A. Provide Type K, annealed, copper pipe, conforming to the latest revision of ASTM B-88 for ¾-inch through 2-inch diameter service lines.
- B. Provide either flared or compression water service line components such as corporation stops, couplings, and curb stops in conformance with the latest revision of AWWA Standard C800.
- C. Furnish service line and connection materials in accordance with MWS published

Approved Materials List.

- D. Provide water service line and connection materials in conformance with the Safe Drinking Water Act, ANSI/NSF 61 Drinking Water System Components-Health Effects.
- E. For service lines larger than 2 inches, use ductile iron pipe and fittings.

PART 3: EXECUTION

3.01 INSTALLATION

- A. Install the water service line and connection a minimum of 24 inches below the finished ground surface or roadway elevation.
- B. Provide a 12-inch minimum gooseneck supported by a brick for each water service line 2 inches and smaller.
- C. If work is to be performed beyond the water meter box, a licensed and bonded plumber is required.
- D. Disinfect all service lines.

END OF SECTION

SECTION 33 12 16.07

BLOW OFF VALVES

PART 1: GENERAL

1.01 SCOPE

- A. Blow Off Valves

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit manufacturer's product data for proposed valves and components for approval.
- C. Furnish five sets of notarized shop drawings and certificates of inspection, stating that the valves and components were constructed and satisfactorily tested in full compliance with these specifications.

1.03 MEASUREMENT AND PAYMENT

- A. MWS will compensate for furnishing and installing blow off valves and boxes or manholes at the contract unit price per each for the unit installed complete and ready for operation.
- B. Include all costs in the unit price for piping, connections to main, materials, valve, equipment, labor, excavation, backfill, manhole or valve box, casting, piping, fittings, rodding, testing, service, and incidentals, necessary for a complete installation.

PART 2: PRODUCTS

2.01 BLOW OFF VALVE ASSEMBLY

- A. Furnish blow off valves and components in accordance with MWS published Approved Materials List.
- B. For 2-inch blow-off valve assemblies, provide red brass blow-off ball valves in conformance with the latest revision of ASTM B283, UNS Number C83800, threaded ends, lever handle, blowout proof stem and minimum working pressure of 150 psi.
- C. Provide Type K copper piping in conformance with the latest revision of ASTM B88 for blow-off valve assemblies 2-inch and smaller.
- D. Provide copper fittings in conformance with the latest revision of ANSI Standard B16.22 for solder joints and ANSI Standard B16.26 for flared joints.
- E. Provide gate valves for blow-off valve assemblies larger than 2-inch.

PART 3: EXECUTION

3.01 INSTALLATION

- A. Install the type and size blow-off valves and components as indicated on the Drawings with the actual location subject to field verification and adjustment.
- B. Operate blow-off valve assembly to ensure proper operation before placing the water main into service.

END OF SECTION

SECTION 33 12 16.09
PRESSURE REDUCING VALVES

PART 1: GENERAL

1.01 SCOPE

- A. Pressure reducing valves for water

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit manufacturer's product data for proposed valves for approval.
- C. Furnish five sets of notarized shop drawings and certificates of inspection, stating the valves were constructed and satisfactorily tested in full compliance with these specifications.
- D. Submit a start-up report after installation including actual set pressures, testing results, and other items concerning valve installation.

1.03 MEASUREMENT AND PAYMENT

- A. MWS will compensate for furnishing and installing pressure reducing valves at the contract unit price per each valve installed complete and ready for operation.
- B. Include all cost in the unit price for pressure reducing valves for items and incidentals necessary for a complete and operable installation unless a component is specifically included as separate item on the Bid Schedule.

PART 2: PRODUCTS

3.01 PRESSURE REDUCING VALVES

- A. Provide pressure reducing valves in conformance with the latest revision of AWWA Standard C530.
- B. Provide valves in conformance with the Safe Water Drinking Act, ANSI/NSF 61 Drinking Water System Components – Health Effects.
- C. Furnish pressure reducing valves from manufacturers in accordance with MWS published Approved Materials List.
- D. Provide pressure reducing valves of the size, type, pressure class, and quantity as indicated on the Drawings.
- E. Provide pressure reducing valves with anti-cavitation option.
- F. Provide internal and external coatings per manufacturers recommendations.

PART 3: EXECUTION

3.01 INSTALLATION

- A. Verify initial pressure reducing valve set pressures from MWS and adjust

pressure settings for actual field conditions at the direction of MWS.

- B. Maintain constant valve outlet pressure during start up.
- C. Provide the services of manufacturer's representative on-site during installation to ensure the valve is installed, tested, and started properly.

END OF SECTION

SECTION 33 12 16.11

GATE VALVES

PART 1: GENERAL

1.01 SCOPE

- A. Gate valves

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittals Procedures.
- B. Submit manufacturer's product data for proposed valves for approval.
- C. Furnish five sets of notarized shop drawings and certificates of inspection, stating that the valves were constructed and satisfactorily tested in full compliance with these Specifications.
- D. Submit engineered foundations for valves larger than 36-inch.
- E. Provide MWS with the access to observe all testing, if requested and submit certified copies of all test results prior to valve shipment.

1.03 MEASUREMENT AND PAYMENT

- A. MWS will compensate for furnishing and installing gate valves at the contract unit price per each for the unit installed complete and ready for operation.
- B. Include all costs in the unit price for furnishing, installing, and testing valves including but not limited to: labor, materials, equipment, service, excavation, bedding, backfill, valve, valve box, valve box footing blocks, valve box casting, flush port valve, flush port box, accessories, engineered foundations if required, and all incidentals necessary for a complete and operable installation.

PART 2: PRODUCTS

2.01 SMALL VALVES – SMALLER THAN 2-INCH

- A. Provide differential pressure rated 125 psi, red brass, rising stem, single-wedge, disc type with screwed ends for valves smaller than 2-inch.
- B. Utilize smaller than 2-inch valves only with MWS written approval.

2.02 GENERAL VALVE REQUIREMENTS- 2-INCH THROUGH 60-INCH

- A. Provide differential pressure rated 250 psi, ductile iron, resilient seated gate valves in conformance with the latest revisions of AWWA Standard C509 or AWWA Standard C515.
- B. Provide valves in conformance with the Safe Water Drinking Act, ANSI/NSF 61 Drinking Water System Components – Health Effects.
- C. Furnish valves from manufacturers in accordance with MWS published Approved

Materials List.

- D. Provide vertical mounted valves unless otherwise specified.
- E. Provide valves with non-rising stems that open clockwise with operating nut painted red to indicate gate valve opens right.
- F. Provide valve ends with restrained mechanical joints in conformance with the latest revision of AWWA Standard C111 for non-exposed piping installations and for exposed piping installations, provide valves with flanged joints.
- G. Provide hand wheels for valves located in vaults, pits, and/or exposed piping.
- H. Where indicated on the Drawings, provide outside screw and yoke (OS&Y) flanged end valves with the Underwriters' Laboratory (UL) label for Factory Mutual (Fire Service) type meter installations.
- I. Provide valve stems manufactured of a low zinc alloy.
- J. Provide valve stem seals with O-rings capable of replacement under pressure when the valve is fully open.
- K. Provide valves with a resilient seat that will be bonded or mechanically attached to either the gate or valve body.
- L. Provide valves with a rubber material for the resilient seat bonded or vulcanized in accordance with the latest revision of ASTM D429.
- M. Provide protective fusion bonded epoxy interior and exterior coating, including bolt holes, in conformance with the latest revision of AWWA Standard C550.
- N. Provide locking type valve extensions on any gate valve where operating nut is 5 feet below finished grade with the extension 2 feet below finished grade.

2.03 HORIZONTAL VALVES

- A. Provide vertical valves for sizes 24 inch and smaller where adequate cover is available and if adequate cover is not available; provide horizontal, resilient-seated, beveled geared actuator valves.
- B. Provide horizontal, resilient-seated, beveled geared actuator valves for valves greater than 24 inch.
- C. Provide flush ports, piping, fittings, and accessories, sized as recommended by the manufacturer to permit removal of foreign material from the valve internal cavity upon opening of the valve.

PART 3: EXECUTION

3.01 INSTALLATION

- A. Install valves in accordance with the latest revision of AWWA Standard C600.

- B. Install valves plumb and operate to verify valve parts are functioning properly.
- C. Disinfect through newly installed gate valve utilizing temporary water cap with pluggable outlet.

END OF SECTION

SECTION 33 12 16.17
TAPPING SLEEVES AND VALVES

PART 1: GENERAL

1.01 SCOPE

- A. Tapping sleeves and valves

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit manufacturer's product data for proposed tapping sleeves and valves for approval.
- C. Furnish notarized shop drawings and certificates of inspection, stating the tapping sleeves and valves were constructed and satisfactorily tested in full compliance with these Specifications.

1.03 MEASUREMENT AND PAYMENT

- A. MWS will compensate for furnishing, installing, and testing tapping sleeves and valves at the contract unit price per each for the unit installed complete and ready for operation.
- B. Include all costs in the unit price for labor, equipment, materials, excavation, bedding, backfill, tapping sleeve and valve, valve box, valve box footing blocks, valve box casting, incidentals, flush port if required, and all incidentals necessary for a complete and operable installation.

PART 2: PRODUCTS

2.01 GENERAL

- A. Refer to Section 33 12 16.11 Gate Valves for tapping valve requirements.
- B. Provide sleeves in conformance with the Safe Water Drinking Act, ANSI/NSF 61 Drinking Water System Components – Health Effects.
- C. Furnish tapping sleeves in accordance with MWS Approved Material List.
- D. Provide a ductile iron outlet in conformance with the latest revision of AWWA Standard C110 with outlet end compatible with a mechanical restrained joint connection.
- E. Provide bolts and nuts in conformance with the latest revision of AWWA Standard C111.
- F. Provide ductile iron sleeves in conformance with the latest revision of ASTM A536 with rubber gaskets held together by bolts with the valve bolted to the sleeve.

- G. Provide oval flange cross sectional shaped seals.
- H. Determine the outside diameter and type of material of the existing water main to be tapped prior to ordering the tapping sleeve.
- I. Provide a ¾-inch nominal pipe thread test tap on the top of the tapping sleeve.
- J. Furnish rubber gaskets for use between the flanges of the sleeve and valve.
- K. Provide only tapping sleeves for tapping existing water mains and do not use tapping saddles.

PART 3: EXECUTION

3.01 INSTALLATION

- A. Provide MWS approved excavation dimensions in order to perform the tap.
- B. Perform tightening of sleeve bolts in the proper sequence to prevent undue stress on the existing water main.
- C. Align valve properly and attach to the sleeve.
- D. Insure the tapping sleeve and valve is plumb through the use of a bubble self-leveling type device.
- E. Install tapping sleeve and valve without removing the existing water main from service.
- F. Perform pressure test on tapping sleeve and valve after installation on the existing water main to insure watertightness with no leakage permitted and perform testing in the presence of MWS.
- G. Contact MWS personnel to schedule tapping of existing water main by MWS.

END OF SECTION

SECTION 33 12 16.19

AIR RELEASE AND VACUUM RELIEF VALVES

PART 1: GENERAL

1.01 SCOPE

- A. Air release valves, vacuum relief valves, and combination air valves for water and wastewater.

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit manufacturer's product data for proposed valves for approval.
- C. Furnish five sets of notarized shop drawings and certificates of inspection, stating the valves were constructed and satisfactorily tested in full compliance with these specifications.
- D. Submit valve start up report after installation.
- E. Submit a detailed schedule of valves for more complex installations.

1.03 MEASUREMENT AND PAYMENT

- A. MWS will compensate for furnishing and installing air release, vacuum relief valves, or combination air valves, and vaults at the contract unit price per each for the unit installed complete and ready for operation.
- B. Include costs in the unit price for piping, connections to main, materials, equipment, labor, excavation, backfill, manhole or valve box, casting, fittings, rodding, testing, service, and all incidentals necessary for a complete and operable installation.

PART 2: PRODUCTS

2.01 AIR RELEASE AND VACUUM RELIEF VALVES

- A. Provide air release and vacuum relief valves in conformance with the latest revision of AWWA Standard C512.
- B. Provide valves in conformance with the Safe Water Drinking Act, ANSI/NSF 61 Drinking Water System Components – Health Effects.
- C. Furnish air release and vacuum relief valves from manufacturers in accordance with MWS published Approved Materials List.
- D. Provide bodies and covers of ductile iron meeting the latest requirements of ASTM A536, Grade 65-45-12 or cast iron meeting the latest requirements of ASTM A126, Class B, or ASTM A48, Class 35.
- E. Use Pressure Class 300 for ductile iron body valves and Pressure Class 250 for

cast iron bodied valves.

- F. For valve sizes 2 inches and smaller, provide connections to the valve conforming to the requirements for tapered pipe threads for general use, per ASME B1.20.1.
- G. For valve sizes greater than 2 inches, provide connections to the valve per ASME B16.42.
- H. Furnish 316 stainless steel cover bolts, nuts, float balls, and guides.
- I. Provide properly sized orifices for the service condition required.
- J. Provide air release valves with a port to allow reverse direction capability.
- K. Provide internal and external coatings per MWS or manufacturers recommendations.
- L. For sewage force main applications, provide special long-body sewage air release valves, complete with top and bottom flushing connections and hoses.

PART 3: EXECUTION

3.01 INSTALLATION

- A. Install the type and size air release, vacuum relief, and/or combination valves as indicated on the Drawings with the actual location subject to field verification and adjustment.
- B. Provide the services of the manufacturer's field representative during installation to ensure the valve is installed, tested, and brought into operation properly.

END OF SECTION

SECTION 33 12 16.21

ALTITUDE VALVES

PART 1: GENERAL

1.01 SCOPE

- A. Altitude valves

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit manufacturer's product data for proposed valves for approval.
- C. Furnish five sets of notarized shop drawings and certificates of inspection, stating that the valves were constructed and satisfactorily tested in full compliance with these Specifications.
- D. Submit valve start up report after installation.
- E. Submit a detailed schedule and/or operational schematic of valves for more complex installations.

1.03 MEASUREMENT AND PAYMENT

- A. MWS will compensate for furnishing and installing altitude valves at the contract unit price per each for the unit installed complete and ready for operation.
- B. Include all costs in the unit price for testing and startup of the altitude valve.
- C. Include all cost in the unit price for altitude valves for items and incidentals necessary for a complete and operable installation unless a component is specifically included as separate item on the Bid Schedule.

PART 2: PRODUCTS

2.01 ALTITUDE VALVES

- A. Provide altitude valves in conformance with latest revision of AWWA Standard C530.
- B. Provide altitude valve materials in conformance with the Safe Water Drinking Act, NSF / ANSI 61 Drinking Water System Components – Health Effects.
- C. Furnish altitude valves from manufacturers in accordance with MWS published Approved Materials List.
- D. Furnish altitude valves with an approved wireless remote telemetry unit (RTU) meeting the requirements of MWS existing SCADA system and associated instrumentation for remote monitoring of the status and remote open/close control where indicated on the Drawings. MWS shall be responsible for programming the new unit into the master control station.

- E. Provide a position indicator rod on the altitude valve for the purpose of continuous visual indication of the status of the valve.

PART 3: EXECUTION

3.01 INSTALLATION

- A. Verify initial valve control parameters from MWS and adjust for actual field conditions at the direction of MWS.
- B. Provide the services of the manufacturer's field representative during installation to ensure the valve is installed, tested, and brought into operation properly.

END OF SECTION

SECTION 33 12 16.23
CORPORATION STOPS

PART 1: GENERAL

1.01 SCOPE

- A. Corporation stops

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit manufacturer's product data for proposed valves for approval.

1.03 MEASUREMENT AND PAYMENT

- A. Consider expenses for furnishing and installing corporation stops incidental to the Work with no separate payment allowed.

PART 2: PRODUCTS

2.01 CORPORATION STOPS

- A. Provide corporation stops in conformance with the latest revision of AWWA Standard C800.
- B. Provide corporation stops in conformance with the Safe Water Drinking Act, NSF / ANSI 61 Drinking Water System Components – Health Effects.
- C. Furnish corporation stops from manufacturers in accordance with MWS published Approved Materials List.
- D. Provide brass corporation stops of the type, size, and threads for inlet and outlet as indicated on the Drawings.

PART 3: EXECUTION

3.01 NOT USED

END OF SECTION

SECTION 33 12 16.25

CHECK VALVES

PART 1: GENERAL

1.01 SCOPE

- A. Check valves within the water distribution system not including privately owned and maintained backflow prevention devices.

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittals Procedures.
- B. Submit manufacturer's product data for proposed valves for approval.
- C. Furnish five sets of notarized shop drawings and certificates of inspection, stating that the valves were constructed and satisfactorily tested in full compliance with these Specifications.
- D. Submit engineered foundations for 12-inch and larger check valves.
- E. If requested, submit certified copies of all test results prior to valve shipment.

1.03 MEASUREMENT AND PAYMENT

- A. MWS will compensate for furnishing and installing check valves at the contract unit price per each for the unit installed complete and ready for operation.
- B. Include all costs in the unit price for testing and startup of the check valve.
- C. Include all cost in the unit price for check valves for items and incidentals necessary for a complete and operable installation unless a component is specifically included as separate item on the Bid Schedule.

PART 2: PRODUCTS

3.01 CHECK VALVES

- A. Provide full opening, swing type check valves in conformance with the latest revision of AWWA Standard C508.
- B. Provide check valve materials in conformance with the Safe Water Drinking Act, NSF / ANSI 61 Drinking Water System Components – Health Effects.
- C. Furnish check valves from manufacturers in accordance with MWS published Approved Materials List.
- D. Provide check valve body material of ductile iron in conformance with the latest revision of ASTM A395 or A536, Grade 65-45-12, Grade 70-50-05, or Grade 80-55-06.
- E. Provide a stainless steel hinge pin with bronze support bearings; stainless steel/steel bolts, nuts, and studs; and mechanical or flanged ends in

conformance with latest revision AWWA Standard C111 with ANSI B16.2.

- F. Provide check valves that can be mounted horizontal or vertical positioned for repair/maintenance without removal.
- G. Provide protective fusion bonded epoxy interior and exterior coating, including bolt holes, in conformance with the latest revision of AWWA Standard C550.
- H. Provide check valve rated at a minimum working pressure of 250 psi.

PART 3: EXECUTION

3.01 INSTALLATION

- A. Install valves in accordance with the latest revision of AWWA Standard C508.
- B. Install valves plumb and operate to verify valve parts are functioning properly.

END OF SECTION

SECTION 33 12 19
FIRE HYDRANT ASSEMBLY

PART 1: GENERAL

1.01 SCOPE

- A. Fire Hydrant Assembly

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit name of fire hydrant manufacturer, type of bonnet paint, shop drawings and detailed data outlined in AWWA C502.
- C. Furnish five sets of certified drawings, certificates of inspection, sworn to by the factory inspector in the presence of a Notary Public, stating that the hydrant and material used in fabrication conform to the applicable requirements of AWWA C502, and the tests specified have been performed and all tests requirements have been meet.

1.03 MEASUREMENT AND PAYMENT

- A. MWS will compensate for furnishing and installing fire hydrant assemblies at the contract unit price per each for the unit installed complete and ready for operation.
- B. Include all cost in the unit price for fire hydrant assemblies for materials, equipment, labor, excavation, backfill, concrete or stone blocking, mechanical joints, restrained joints, and rodding (if required), riser pipe/extension, testing, ductile iron fittings, appurtenances, and removal and stockpile of existing fire hydrant (if applicable), and all incidentals necessary for a complete and operable installation.
- C. Do not include in the unit price for fire hydrant assemblies the linear feet of 6-inch fire hydrant leads, tapping sleeves and valves, valves, valve boxes, pavement replacement, and/or other units of work if specifically included on the Bid Schedule.

PART 2: PRODUCTS

2.01 FIRE HYDRANTS

- A. Provide fire hydrant in conformance with AWWA Standard C502, Dry Barrel Fire Hydrants, of latest edition.
- B. Provide fire hydrant in conformance with the Safe Water Drinking Act, NSF / ANSI 61 Drinking Water System Components – Health Effects. Note: Section

1417 Reduction of Lead 2011 by HR3588, the Community Fire Safety Act excludes fire hydrants.

- C. Furnish fire hydrants from manufacturers in accordance with MWS published Approved Materials.
- D. Provide fire hydrant with compression post type opening to the left (counterclockwise) against the pressure.
- E. Provide fire hydrant outlets consisting of one main valve with a 4½-inch pumper nozzle outlet and two 2½-inch hose nozzle outlets with nozzles and caps meeting National Fire Protection Association (NFPA) 1963 - Standard for Screw Threads and Gaskets for Hose Connections.
- F. Provide nozzle caps that are chained or cabled to the barrel of the fire hydrant with a chain or cable constructed of material not less than ⅛-inch in diameter.
- G. Provide fire hydrant with a lower hydrant barrel fabricated from ductile iron pipe as single piece connected to upper hydrant barrel by means of joint coupling that will provide three hundred sixty degree rotation of upper barrel.
- H. Provide fire hydrant with a mechanical joint inlet.
- I. Lubrication shall be accessible without removing stem nut.
- J. Provide fire hydrant with a 1-inch square operating nut on top of stem and on nozzle caps.
- K. Protect the opening between the stem nut and the top of bonnet by a weather shield cap.
- L. Provide fire hydrant with an arrow 1¼-inch long and the word "open" in ½-inch high letters casted with ⅛-inch relief on or near the top of the fire hydrant bonnet to indicate the direction of operation clearly visible when viewed from the top.
- M. Use O-rings or other approved seals of equal ease of operation. Do not use stuffing boxes or glands.
- N. Provide fire hydrant edges and corners with sufficient radius in accordance with standard foundry practices.

PART 3: EXECUTION

3.01 INSTALLATION

- A. Install fire hydrants in conformance with AWWA Manual M17 - Installations, Field Testing, and Maintenance of Fire Hydrants.
- B. Set fire hydrant plumb at locations as shown.
- C. Connect fire hydrants to 6-inch water mains or larger with sufficient pressures.

- D. Protect the casting containing fire hydrant outlets and the stem from damage with a method approved by MWS.
- E. Use a minimum of 2 cubic feet of clean TDOT No. 57 or No. 67 stone for drainage around fire hydrant.
- F. Do not cover drain ports, bolts, or fittings when placing concrete thrust blocks.
- G. Locate the upper flange connection 6 inches above the finished grade to easily remove bolts and revolve the top part of hydrant.
- H. Install fire hydrant at proper height where hydrant wrench can turn 360 degrees on 4½-inch pumper nozzle outlet and 2½-inch hose nozzles without ground surface obstruction.
- I. Do not install fire hydrant at an excessive height with final height approved by MWS.
- J. Locate fire hydrant measuring a minimum of 18 inches from the face of curb or edge of pavement if no curb exist to the 4½-inch pumper nozzle nut.
- K. Use a bury depth of 3 ½ feet. Use an offset bend instead of extensions if the water main or lead has a depth greater than 3 ½ feet. Obtain MWS approval in writing prior to installation of fire hydrants that require changes in bury depth due to obstructions not shown.
- L. Use concrete blocks, 12-inch x 12-inch x 4-inch minimum underneath the hydrant base and around the hydrant to undisturbed earth, or use the equivalent of poured concrete without clogging the drain hole.
- M. Use concrete blocks, 20-inch x 20-inch x 4-inch minimum, between hydrant base and back of trench to undisturbed earth or use the equivalent of poured concrete without clogging the drain hole.
- N. Connect fire hydrants to a new water main with a tee connection with Class 350 ductile iron mechanical restraint joints (Mega Lugs and Field-Lok gaskets or rodding) including connections from the fire hydrant tee to the fire hydrant valve and from the fire hydrant valve to the fire hydrant base.
- O. Connect fire hydrants with tapping sleeve and valve with Class 350 ductile iron restraint mechanical joints for connections to existing water mains.
- P. Place out of service indicators approved by MWS on fire hydrants that are not in service. Remove indicators after water line is tested and approved by MWS.

3.02 TESTING

- A. MWS may, at any time prior to or during installation of hydrants, randomly select

a furnished hydrant for disassembly and laboratory inspection at MWS expense, to verify compliance with Specifications. When a hydrant is found to be non-compliant, replace with a compliant hydrant.

- B. Fire hydrant assemblies shall be visually examined for leaks by MWS under pressure for a 10-minute period. Repair all visible leaks regardless of the amount of leakage.

3.03 HYDRANT COATING REQUIREMENTS

- A. Obtain test data from MWS including static and residual pressure; provide material and labor to properly paint hydrants per MWS Fire Hydrant Painting Colors Policy and provide labor to attach tags provided by MWS for each fire hydrant installed.
- B. Apply coatings in strict accordance with recommendations from the manufacturer.
- C. Use the following table for a summary of the current fire hydrant color policy:

Table 1 - MWS FIRE HYDRANT PAINTING COLORS					
	HYDRANT RESIDUAL PRESSURE (2-1/2" NOZZLE - psi)	FLOW (gpm)	BARREL	CAPS	DOME
ALL HYDRANTS	0	0	SHROUD WITH BLACK BAG AND TURN IN FOR REPAIR - OUT OF SERVICE EXCEPTION: EMERGENCY CALL IN IF HYDRANT IS ADJACENT TO ESSENTIAL SERVICES (HOSPITAL, NURSING HOMES, ETC)		
PUBLIC HYDRANT	0.1 - 8.9	1-500	RED	BLACK	RED
PUBLIC HYDRANT	9 - 35.9	501-1000	RED	GREEN	GREEN
PUBLIC HYDRANT	>= 36	>1000	RED	ORANGE	ORANGE
END OF LINE PUBLIC HYDRANT	0.1 - 8.9	1-500	WHITE	BLACK	RED
END OF LINE PUBLIC HYDRANT	9 - 35.9	501-1000	WHITE	GREEN	GREEN
END OF LINE PUBLIC HYDRANT	>= 36	>1000	WHITE	ORANGE	ORANGE
<u>Notes:</u>					
<p>1. White "cap color" is the de facto indicator of the fire hydrant flow capacity; barrel color can sometimes also provide useful information. For example, fire hydrants with white barrels signify those which are last on a dead end main.</p> <p>2. Typically, silver fire hydrants (caps and barrels) signify private hydrants while red hydrants (caps and barrels) signify hydrant not yet in service.</p> <p>3. Cap color is determined by field tests performed by Metro Water Services or their designee and is representative of the latest residual pressure testing performed. Records of testing are available at the office of MWS.</p> <p>4. Regulations of the Tennessee Department of Environment and Conservation (Rules of TDEC Public Water System Chapter 1200-5-1-.17, paragraph 18) require that fire hydrant be capable of providing at least 500 gallons per minute with a minimum residual pressure of 20 pounds per square inch (psi). There are some hydrants in MWS' system that are not capable of this requirement and are color coded accordingly (black caps). Therefore, the MFD agrees not to connect a pumper truck to any black cap hydrants.</p> <p>5. In order to assure consistency, it is imperative that all water companies having jurisdiction within Davidson County identify their hydrant using this same cap color code.</p>					

END OF SECTION

SECTION 33 12 33

WATER METERS

PART 1: GENERAL

1.01 SCOPE

- A. Water meters and fire service meters

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit manufacturer's product data for proposed valves for approval.
- C. Furnish five sets of notarized shop drawings and certificates of inspection, stating that the water meters were constructed and satisfactorily tested in full compliance with these specifications.

1.03 MEASUREMENT AND PAYMENT

- A. MWS will compensate for relocating, furnishing, and/or installing water meters at the contract unit price per each for the unit installed complete and ready for operation.
- B. Include all cost in the unit price for materials, equipment, labor, excavation, backfill, appurtenances, and concrete box with lid, and all incidentals necessary for a complete and operable installation.

1.04 GENERAL

- A. Adjust and/or relocate existing water meters and boxes as necessary.
- B. Install the meter at a depth in which the top of the meter is 18 to 24 inches below the top of the meter box.

PART 2: PRODUCTS

2.01 GENERAL

- A. Furnish water meters from manufacturers in accordance with MWS published Approved Materials List.
- B. Provide water meters in conformance with the Safe Water Drinking Act, NSF / ANSI 61 Drinking Water System Components – Health Effects.
- C. Provide water meters in the MWS system equipped with an encoded register wired to a meter interface unit (MXU) with 6 feet of wire for residential accounts and 25 feet of wire for commercial accounts.
- D. Provide an affidavit of compliance and a certificate of testing for accuracy in conformance with the latest revision of the AWWA Standard applicable for the meter type utilized.

- E. Provide serial numbers, meter size, and direction of water flow on meters in raised characters. Provide the manufacturer's serial number imprinted permanently on the outer case and the register box lid.
- F. Furnish metal mutilated pinions and white number wheels with black figures. The number wheels may be made of plastic, but wheel gears must be made of metal.

2.02 RESIDENTIAL COLD WATER MAGNETIC DRIVE METERS

- A. Provide residential cold water oscillating–piston magnetic drive meters (size 5/8 - inch through 1 - inch) in conformance with the latest revision of AWWA Standard C700.
- B. Supply registers operating by permanent drive magnets with straight reading with 6 numeral wheels measuring in cubic feet including a low flow indicator on the face dial.
- C. Provide register secured to the main case by means of a tamper resistant locking screw seal pin so the register cannot be removed by nonutility personnel. Seal wiring or a frangible head screw is not acceptable.
- D. Provide registers and casings with a guarantee from the manufacturer to be free from defective material and workmanship for a period of 25 years.
- E. Provide all reduction gearing contained in a permanently hermetically sealed, tamper proof enclosure made from a stainless steel or copper material, covered with a heat tempered glass lens.
- F. Provide registers with convertibility to AMR applications.
- G. Provide registers with two permanently potted wire connections.
- H. Provide outer casing of noncorrosive water corks bronze with a separate measuring chamber that can be easily removed from the case.
- I. Equip meters with breakable frost proof bottoms or equivalent frost protection safeguards.
- J. Equip meters with plastic liners or corrosion resistant material on bottom plates.
- K. Provide external bolts and washers of corrosion resistant material easily removed from the case.
- L. Cover threaded main case bolts holes.
- M. Provide meter coupling washers of vulcanized hard red fiber, 1/8 - inch thick, suitable for use with standard 5/8 - inch and 1 - inch water meters.
- N. Provide measuring chambers of synthetic polymer of positive displacement type and not cast as part of the main case.

- O. Provide interchangeable piston assemblies in all measuring chamber assemblies of the same size that operate against a replaceable control roller allowing for repair to AWWA standards.
- P. Provide meters with an unconditional guarantee for performance meeting AWWA new meter accuracy standards for a period of 5 years from the date of shipment.
- Q. Provide meters with an unconditional guarantee for performance meeting AWWA repaired meter accuracy standards for a period of 15 years from the shipment date.
- R. Provide meters with accuracy for normal flow of registration of not less than 98.5% and not more than 101.5%. At minimum flow, the meter should register not less than 95% and not more than 101% in accordance with the latest revision of AWWA Standard C700.
- S. Provide meters capable of component repair without entire meter replacement.

2.03 COMMERCIAL COLD WATER DISPLACEMENT METERS

- A. Provide commercial displacement cold water meters manufactured in conformance with the latest revision of AWWA Standard C700.
- B. Supply registers operating by permanent drive magnets with straight reading with 6 numeral wheels measuring in cubic feet including a low flow indicator on the face dial.
- C. Provide outer meter casings of bronze composition.
- D. Provide meters with measuring chambers separate from the outer casting and constructed of bronze, stainless steel, hard rubber or an approved synthetic polymer.
- E. Provide meters with discs constructed of hard rubber or approved synthetic polymer.
- F. Provide meters with accuracy for normal flow of registration of not less than 98.5% and not more than 101.5%. At minimum flow, the meter should register not less than 95% and not more than 101% in accordance with the latest revision of AWWA Standard C700.
- G. Provide meters capable of component repair without entire meter replacement.

2.04 COMMERCIAL TURBINE WATER METERS

- A. Provide commercial Class II in-line high velocity type turbine water meters manufactured in accordance with the latest revision of AWWA Standard C701.
- B. Supply registers operating by permanent drive magnets with straight reading with

6 numeral wheels measuring in cubic feet including a low flow indicator on the face dial.

- C. Provide outer meter casings of bronze composition.
- D. Provide meter register that is hermetically sealed.
- E. Provide turbines and rotors manufactured of vulcanized hard rubber or approved synthetic polymer having sufficient rigidity and strength for the meter to operate at the maximum operating capacity.
- F. Provide turbine spindles manufactured of phosphor bronze, stainless steel, Mondel, or approved suitable corrosion resistant materials.
- G. Provide rotor spindles manufactured of phosphor bronze, stainless steel nickel alloy, or approved synthetic polymer.
- H. Provide meters with accuracy for normal flow of registration of not less than 98.5% and not more than 101.5% in accordance with the latest revision of AWWA Standard C701.

2.05 COMMERCIAL COMPOUND WATER METERS FOR SIZES GREATER THAN 2 INCH

- A. Provide Class II commercial compound meters for sizes greater than 2 inch manufactured in accordance with the latest revision of AWWA Standard C702.
- B. Supply registers operating by permanent drive magnets with straight reading with 6 numeral wheels measuring in cubic feet.
- C. Provide meters manufactured with stainless steel external fasteners and tapped bosses on the top of the case near the outlet for testing purposes.
- D. Provide 2-inch meters with oval flanges.
- E. Provide 3-inch and larger meters with ductile iron companion flanges of the same size and type as the meter flanges.
- F. Provide meters with the required gaskets, bolts, and nuts.
- G. Provide meters with rigid, easily removable, lead free strainers with a minimum effective straining area of double the water main case inlet.
- H. Use of synthetic polymers will not be acceptable.
- I. Provide meters with accuracy for normal flow of registration of not less than 98.5% and not more than 101.5%. At minimum flow, the meter should register not less than 95% and not more than 101%. If the accuracy of the meter falls below 98.5%, the accuracy of the changeover flow rates will not be less than 90% and not more than 103% of the indicated difference in the flow rate in accordance with the latest revision of AWWA Standard C702.

2.06 COMMERCIAL FIRE SERVICE WATER METERS FOR 4 -INCH AND LARGER ABOVE

- A. Provide commercial Type II compound fire service meters for 4-inch and larger above manufactured in accordance with the latest revision of AWWA C703.
- B. Provide register operated by permanent drive magnets with straight reading with 6 numbering wheels measuring in cubic feet.
- C. Provide meters manufactured with stainless steel external fasteners
- D. Provide meters with ductile iron companion flanges of the same size and type as the meter flanges.
- E. Provide meters with the required gaskets, bolts, and nuts.
- F. Provide a separate strainer unit with the main case and cover manufactured of bronze or cast iron coated with an approved no-corrosive material and a stainless steel strainer unit. Provide stainless steel bolts for use with the strainer unit.
- G. Provide hermetically sealed registers.
- H. Furnish outer casing of bronze composition.
- I. Provide measuring chamber constructed of bronze, stainless steel, or hard rubber not cast as a part of the outer casing.
- J. Provide turbines and rotors made of vulcanized hard rubber having sufficient rigidity and strength to operate at the rated capacity of the meters.
- K. Furnish turbine spindles made of phosphor bronze, stainless steel, Mondel, or other approved suitable corrosion resistant materials.
- L. Furnish rotor spindles made of phosphor bronze, stainless steel, or nickel alloy.
- M. Use of synthetic polymers will not be acceptable.
- N. Provide all bronze bypass assembly with lockable ball valves and check valve.
- O. Provide meters with accuracy for normal flow of registration of not less than 98.5% and not more than 101.5%. At minimum flow, the meter should register not less than 95% and not more than 101%. If the accuracy of the meter falls below 97%, the accuracy of the changeover flow rates will not be less than 85% of the indicated flow spread at the crossover flow in accordance with the latest revision of AWWA Standard C703.

PART 3: EXECUTION

3.01 INSTALLATION

- A. Install meters plumb and as shown or as located by MWS.

END OF SECTION

SECTION 33 13 10
DISINFECTION OF WATER MAINS

PART 1: GENERAL

1.01 SCOPE

- A. Disinfecting water mains, valves, fittings, temporary water mains, and appurtenances

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit a disinfection plan in accordance with procedures specified in Tennessee Department of Environment and Conservation (TDEC) Chapter 0400-45-01-.17.(8) and the latest American Water Works Association (AWWA) C651 standards and as indicated. The disinfection plan shall be reviewed and approved by MWS a minimum of two weeks prior to construction. The disinfection plan shall include, but not be limited to: an overall explanation of the disinfection process; the method of disinfection; the number and location of sampling points depicted on a copy of the construction drawings; and a description, location, and sample procedure of all tie-ins.
- C. Submit a revised disinfection plan in accordance with procedures specified in TDEC Chapter 0400-45-01-.17.(8) and the latest AWWA C651 standards as warranted or requested by MWS.

1.03 MEASUREMENT AND PAYMENT

- A. Consider expenses for disinfection of water mains incidental to the Work with no separate payment allowed.

1.04 GENERAL

- A. Comply with TDEC Chapter 0400-45-01-.17.(8) and the latest AWWA C651 standards.
- B. Install a temporary water main cap on ends of new water mains and tap sampling cap with a pluggable outlet of adequate size to be utilized as a sampling, filling and/or flushing location.

PART 2: PRODUCTS

2.01 NOT USED

PART 3: EXECUTION

3.01 NOT USED

END OF SECTION

SECTION 33 14 13
ACCEPTANCE TESTING FOR WATER

PART 1: GENERAL

1.01 SCOPE

- A. Pressure and leakage tests for water mains and appurtenances

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit a water test plan.

1.03 MEASUREMENT AND PAYMENT

- A. Consider expenses for acceptance testing for water mains incidental to the Work with no separate payment allowed.
- B. Provide labor, equipment, or any other devices necessary for proper testing at no cost.

1.04 GENERAL

- A. Provide pressure and leakage testing of water mains and appurtenances in conformance with the latest revision of AWWA Standard C600.
- B. Test water main in lengths between line valves or plugs not more than 1,000 feet in urban areas and 2,500 feet in rural areas.
- C. Provide and install temporary plugs and blocking adequate for tests.
- D. Do not make connections to the existing water system until the new water main has been tested, disinfected, and accepted by MWS.
- E. Be prepared to test completed and/or relatively short sections of water main at the direction of MWS to expedite areas that need to be backfill promptly.
- F. Coordinate with MWS to test water mains and provide other necessary equipment other than the MWS supplied pressure recording equipment.
- G. Provide a MWS approved backflow prevention device with an annual certificate of inspection.
- H. Notify MWS 48 hours prior to the scheduled testing of a section of water main.
- I. Remedy conditions that may cause a greater leakage and/or loss of pressure of the section and retest the section until it meets the specified requirements.

PART 2: PRODUCTS

2.01 NOT USED

PART 3: EXECUTION

3.01 PRESSURE TEST

- A. Perform pressure tests for newly installed water main sections in the presence of MWS.
- B. Supply pressure at 1.5 times the stated working pressure of the water main at the lowest elevation along the test section or 150 psi whichever is greater.
- C. Maintain pressure for a minimum of 4 hours with no more than a 5 psi variance for the duration of the test.
- D. Introduce water slowly to vent all air for the section of pipe being tested.
- E. Install temporary corporation stops where permanent components such as fire hydrants, blow offs, and/or air release valves, are not located at high points.
- F. Fill each section to be tested with water from the distribution system utilizing a ¾ inch or greater corporation stop / service tap, Type K copper tubing, and MWS approved backflow preventer.
- G. Add makeup water with the amounts shown in Table 1 to the water main section as directed and measured by MWS if the specified testing pressure cannot be maintained. Add makeup water only one time during the test.
- H. Do not exceed indicated maximum amount shown in Table 1 per hour per 1,000 feet for the 4 hour test.

Table 1 – Hydrostatic Testing Allowance per 1,000 Feet of Main Tested – Gallons Per Hour*																
Average Test Pressure (psi)	Nominal Pipe Diameter - inches															
	3"	4"	6"	8"	10"	12"	16"	18"	20"	24"	30"	36"	42"	48"	54"	60"
450	0.43	0.57	0.86	1.15	1.43	1.72	2.29	2.58	2.87	3.44	4.30	5.16	6.02	6.88	7.74	8.60
400	0.41	0.54	0.81	1.08	1.35	1.62	2.16	2.43	2.70	3.24	4.05	4.86	5.68	6.49	7.30	8.11
350	0.38	0.51	0.76	1.01	1.26	1.52	2.02	2.28	2.53	3.03	3.79	4.55	5.31	6.07	6.83	7.58
300	0.35	0.47	0.70	0.94	1.17	1.40	1.87	2.11	2.34	2.81	3.51	4.21	4.92	5.62	6.32	7.02
275	0.34	0.45	0.67	0.90	1.12	1.37	1.79	2.02	2.24	2.69	3.36	4.03	4.71	5.38	6.05	6.72
250	0.32	0.43	0.64	0.85	1.07	1.28	1.71	1.92	2.14	2.56	3.21	3.85	4.49	5.13	5.77	6.41
225	0.30	0.41	0.61	0.81	1.01	1.22	1.62	1.82	2.03	2.43	3.04	3.65	4.26	4.86	5.47	6.08
200	0.29	0.38	0.57	0.76	0.96	1.15	1.53	1.72	1.91	2.29	2.87	3.44	4.01	4.59	5.16	5.73
175	0.27	0.36	0.54	0.72	0.89	1.07	1.43	1.61	1.79	2.15	2.68	3.22	3.75	4.29	4.83	5.36
150	0.25	0.33	0.50	0.66	0.83	0.99	1.32	1.49	1.66	1.99	2.48	2.98	3.48	3.97	4.47	4.97
125	0.23	0.30	0.45	0.60	0.76	0.91	1.21	1.36	1.51	1.81	2.27	2.72	3.17	3.63	4.08	4.53
100	0.20	0.27	0.41	0.54	0.68	0.81	1.08	1.22	1.35	1.62	2.03	2.43	2.84	3.24	3.65	4.05

* Source: AWWA C600 Table 4A

- I. Locate and repair water main sections unable to maintain specified test pressure and retest water main sections to the satisfaction of MWS.
- J. Assume expense for location, repair, and retesting of defective water mains.

- K. Remove and plug additional corporation stops in the water main upon completion of testing.

END OF SECTION

SECTION 33 31 00
GRAVITY SEWER MAINS

PART 1: GENERAL

1.01 SCOPE

- A. Gravity sewer mains, connections, abandonments, and excavation and backfill.

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit manufacturer's product data for proposed gravity sewer main pipe, joints, joint materials, specials, interior coatings, and fittings for approval.
- C. Submit crushed stone bedding and envelope material sieve analysis and compaction methods.
- D. Submit abandonment plan, bypass pumping requirements, proposed grouting sequence, and plugging, if any, and other information pertinent to completion of the Work.
- E. Submit an installation plan for gravity sewer main taps and connections to be performed on existing gravity sewer mains.
- F. Submit cut sheets for each individual sewer line segment indicating the following information: beginning and ending structures with stationing conforming to the drawings, distance, gradient between structures of the segment, size and type of pipe material, the location of service connections, the depths of cut of the segment, alignment, deflection angle, and other pertinent information. Cut sheets require MWS review and approval prior to commencing excavation.
- G. Submit asphaltic binder information certifying material is in conformance with the latest revision of Metro Public Works standard specification Section 02575 if gravity sewer mains or service lines are to be installed within a Metro Public Works roadway or the latest revision of the applicable TDOT asphaltic binder specification if gravity sewer mains or service lines are to be installed within a TDOT roadway.
- H. Submit flowable fill information certifying material is in conformance with the latest revision of Metro Public Works standard specification Section 02225 if gravity sewer mains or service lines are to be installed within a Metro Public Works roadway or the latest revision of the applicable TDOT flowable specification if gravity sewer mains or service lines are to be installed within a TDOT roadway.

- I. Submit outside roadway backfill material source, quality information, and compaction methods.
- J. Submit Proctor Density Test results in accordance with the latest revision of ASTM D698 or ASTM D1557 when required by MWS.
- K. Submit compaction field testing results in accordance with the latest revision of ASTM D6938 or other approved method when required by MWS.

1.03 MEASUREMENT AND PAYMENT

- A. MWS will compensate for furnishing and installing gravity sewer mains or service lines at the contract unit price per linear foot for the gravity sewer main or service lines installed complete and ready for operation. Measure the gravity sewer main or service lines horizontally along the centerline of the pipe in place from centerline of structure to centerline of structure, including fittings such as tees or tee wyes, and cleanouts. MWS will compensate for furnishing and installing vertical stacks at the contract unit price per vertical foot installed complete and ready for operation.
 - 1. Include cost in the unit price for gravity sewer mains or service lines for labor, equipment, material, cutting, laying to grade and alignment, joints, bypass pumping, standby time and delay in MWS locating and gaining access to existing gravity sewer mains or service lines, hydrostatic testing and other testing required, and all incidentals necessary for a complete and operable installation.
 - 2. Include cost in the unit price for gravity sewer mains or service lines for fittings, such as tees, tee wyes, and/or cleanouts whether indicated on the Drawings or not.
 - 3. Include cost in the unit price for gravity sewer mains or service lines for excavation. Excavation is unclassified with no distinction made between rock and/or dirt excavation. Rock excavation beyond anticipated or indicated in a provided geotechnical report will not be considered basis for additional payment.
 - 4. Include cost in the unit price for gravity sewer mains or service lines for crushed stone bedding, crushed stone envelope, and additional crushed stone used as backfill material between top of the crushed stone pipe envelope and the bottom of the flowable fill.
 - 5. Include cost in the unit price for gravity sewer mains or service lines for

outside of roadway backfill material.

6. Include cost in the unit price for gravity sewer mains or service lines for dewatering operations including but not limited to water filtration systems for groundwater, obtaining permits with appropriate agencies on dewatering activities, and appropriately filtering and properly disposing of groundwater in accordance with permits.
 7. Include cost in the unit price of gravity sewer mains or service lines for grade and alignment survey staking operations performed by a Tennessee registered land surveyor.
 8. Undercutting of undesirable material at the trench base and approved refill material to be paid with Unforeseen Work Elements allowance bid item.
- B. MWS will compensate for furnishing and installing taps and connections at the contract unit price per each for each tap and connection complete and ready for operation.
1. Include all cost in the unit price for taps and connections for labor, equipment, excavation, material, backfilling, and all incidentals necessary for a complete and operable installation.
- C. MWS will compensate for cutting and plugging in order to abandon a gravity sewer main or service line at the contract unit price per each.
1. Include all cost in the unit price for cutting and plugging for labor, equipment, materials, bypass pumping, permanent solid gravity sewer main plug, and all incidentals necessary for a complete gravity sewer main abandonment operation.
 2. Include all cost in the unit price for pipe grout, labor, and all incidentals necessary for a complete abandonment.
- D. MWS will compensate for furnishing and installing flowable fill at the contract unit price per theoretical cubic yard calculated utilizing the specified trench width per gravity sewer main or service line size, the length, and the specified flowable fill depth; not the actual amount of flowable fill if more material is installed.
1. Include all cost in the unit price for flowable fill for excavation, material, labor, and all incidentals necessary for a complete installation.
- E. MWS will compensate for furnishing and installing asphalt binder at the contract unit price per theoretical cubic yard calculated utilizing the specified trench width per gravity sewer main or service line size, the length, and the specified binder

depth; not the actual amount of binder if more material is installed.

1. Include all cost in the unit price for asphalt binder for excavation, material, labor, and all incidentals necessary for a complete installation.

F. MWS will compensate for furnishing and installing miscellaneous concrete at the contract unit price per cubic yard for concrete installed between a proposed gravity sewer main or service line traversing perpendicular and above an existing water main.

1. Include all cost in the unit price for miscellaneous concrete for excavation, materials, labor, and all incidentals necessary for a complete installation.

1.04 GENERAL

A. Calculate Bid Schedule payment items of flowable fill and asphalt binder by the following table. If a wider than indicated trench width is utilized during construction, payment will only be compensated based on the trench width limits detailed in the following table.

Maximum Trench Width Limits in Feet for Compensation for Binder and Flowable Fill Items per Pipe Size in Inches and Depth in Feet			
Pipe Size (inches)	Trench Depth (feet)		
	Up to 5	Greater Than 5 to 10	Greater Than 10
4	2.5	3.0	4.0
6	3.0	3.5	4.5
8	3.0	3.5	4.5
10	3.5	4.0	5.0
12	3.5	4.0	5.0
15	4.0	4.5	5.5
16	4.0	4.5	5.5
18	4.0	4.5	5.5
20	4.5	5.0	6.0
21	4.5	5.0	6.0
24	5.0	5.5	6.5
30	-	6.0	7.0
36	-	6.5	7.5
42	-	7.5	8.5
48	-	8.0	9.0
54	-	8.5	9.5
60	-	9.5	10.5
64	-	10.0	11.0
66	-	10.0	11.0

- B. Bury gravity sewer mains and service lines in roadways to the slope and alignment requirements indicated on the Drawings. Utilize crushed stone material compacted in maximum 8-inch lifts at the proper moisture content as the supplementary trench backfill material between the crushed stone envelope and the flowable fill.
- C. Bury gravity sewer mains and service lines outside of roadways to the slope and alignment requirements indicated on the Drawings. Utilize suitable native backfill material compacted in 12-inch lifts.
- D. Maintain existing gravity sewer services during the Work.
- E. Do not plug manholes or structures on the existing system and/or new gravity sewer mains placed in service without a written bypass plan.
- F. MWS will make every reasonable effort to locate and uncover all manholes and/or structures to divert wastewater when required for the Work. Circumstances may prevent timely location and access due to such items as weather conditions, lack of access to a location, high wastewater flows, and/or a lack of forces due to higher priority situations. Consider standby time due to these types of delays incidental to the Work with no separate payment allowed.
- G. Perform Proctor Density Test in accordance with the latest revision of ASTM D698 or ASTM D1557 when required by MWS. Test to be performed by an independent MWS approved materials testing firm. Pay for test if Work is found to be noncompliance.
- H. Perform compaction field testing results in accordance with the latest revision of ASTM D6938 or other approved method when required by MWS. Compaction tests to be performed by an independent MWS approved materials testing firm. Pay for test if Work is found to be noncompliance.
- I. Abandon gravity sewer mains with a permanent concrete cap and fill with grout for a distance of approximately 20 feet into the main.

PART 2: PRODUCTS

3.01 GENERAL

- A. Provide gravity sewer main products and accessories from manufacturers in accordance with MWS Approved Material List.
- B. Provide pipe material for gravity sewer mains and service lines as indicated on the Drawings.

- C. Provide TDOT No. 57 or No. 67 crushed stone for pipe bedding, pipe envelope, and for locations where additional pipeline depth is required within roadways prior to excavatable flowable fill and/or to avoid existing utilities.
- D. Provide TDOT No.57 or No. 67 crushed stone for refill for undercutting of the pipeline trench.
- E. Provide asphaltic binder in conformance with the latest revision of Metro Public Works standard specification Section 02575 when the gravity sewer main or service line is to be installed within a Metro Public Works roadway and provide asphaltic binder in conformance with the latest revisions of the applicable TDOT specification when the gravity sewer main or service line is to be installed within a TDOT roadway.
- F. Provide excavatable flowable fill in conformance the latest revision of Metro Public Works standard specification Section 02225 when a gravity sewer main or service line is to be installed within a Metro Public Works roadway and provide excavatable flowable fill in conformance with the latest revisions of the applicable TDOT specification when the gravity sewer main or service line is to be installed within a TDOT roadway.
- G. Provide Grade B or Grade C cement based dry pack grout for abandonment of gravity sewer mains in conformance with the latest revision of ASTM C1107.

PART 3: EXECUTION

3.01 GENERAL

- A. Provide the services of a Tennessee registered land surveyor for grade and alignment survey operations.
- B. Set grade stakes, lines, bench marks and elevations, and provide proper equipment to verify alignment and/or grade. Provide grade hubs no more than 100 feet apart with center line hubs no more than 50 feet apart to check laser equipment and grade between manholes. Provide offset stakes at each manhole, junction structure, or change in alignment location. Preserve survey staking, check staking, and reset missing, disturbed, or damaged staking, and/or property boundaries.
- C. Deliver gravity sewer main products and accessories to job site free of damages and/or defects. If damages or defects are discovered, provide new material at no cost to MWS.
- D. Store materials on site in enclosures or under protective above ground coverings.

- E. Keep interiors of gravity sewer main products free of dirt and debris.
- F. Install gravity sewer main, joints, gaskets and fittings in accordance with the latest revision of ASTM D2321 and manufacturer's recommendations
- G. Install gravity sewer mains and service lines to the gradient and alignment indicated on the Drawings.
- H. Install gravity sewer mains and service lines in crushed stone gravel bedding in the dry.
- I. Install dewatering systems, if necessary, for excavation and gravity sewer main installation. Provide water filtration systems for groundwater, obtain permits with appropriate agencies for dewatering activities and appropriately filter and properly dispose of groundwater in accordance with permits.
- J. Clean the inside of the bell and the outside of the spigot of the pipe, grind or smooth rough edges of the spigot of the pipe, and wipe clean as recommended by the pipe manufacturer prior to insertion of the gasket and final joints and/or fittings assembly.
- K. Maintain a minimum of 10 feet horizontal separation when installing a gravity sewer main or service line is sharing a parallel alignment with a water main or water service line.
- L. If the new gravity sewer main or service line is installed over an existing water main or existing water service pipe, maintain a minimum vertical separation of 24 inches from the bottom of the gravity sewer main or service line to the top of the water main. Attempt to place the crossing at a point to keep the water main joints at equal distances and as far as possible from the gravity sewer main or service line. Install concrete material between the existing water main and gravity sewer main crossing for the entire width of the distance between the utilities and for a length of at least 6 feet centered at the point of crossing.

3.02 EXCAVATION

- A. No blasting will be permitted.
- B. MWS may limit the method of excavation if conditions warrant such as trenching within areas of high concentration of utilities.
- C. Contact Tennessee One Call Center (1-800-351-1111) the location of buried facilities pursuant to TCA 65-31-101 through TCA 65-31-133; however, take sole responsibility for the location of all affected underground utilities.
- D. Locate and preserve existing utilities. The types and locations of known existing

utilities as indicated on the Drawings are approximate. Repair or replace damaged utilities, whether shown on the Drawings or not, at no cost to MWS.

- E. Notify MWS immediately, stop the Work, and wait for MWS direction before resuming the Work if solvents, petroleum products, or any unknown chemical substance is discovered during excavation.
- F. Consider all excavation material unclassified, whether a geotechnical report is provided or not.
- G. Saw cut pavement to trench width limits when excavation is within a roadway.
- H. Excavate trench width to permit a minimum of 6 inches between the edge of the trench and the outside of the gravity sewer main and/or service line.
- I. Excavate to allow for a minimum of 6 inches of crushed stone bedding below the bottom of the gravity sewer main and/or service line.
- J. Remove unstable soil at the trench bottom if discovered and refill area with appropriate material. Notify and receive approval from MWS prior to undercutting and removing undesirable material at the trench base and utilizing approved refill material.
- K. Remove all loose material from the trench bottom. Do not lay gravity sewer mains and accessories directly on rock.
- L. Excavate in accordance with Trench Safety Systems, TOSHA and OSHA regulations, and permits.
- M. Dispose of surplus excavated material at a Metro approved permitted site. Do not place excavated material on private property.

3.03 BACKFILL WITHIN ROADWAY

- A. Take precautions not to damage the gravity sewer main and accessories during backfill operations. Replace damaged items at no cost to MWS.
- B. Install specified backfill material for the full width of the excavated trench and to specified depths.
- C. Install No. 57 or No. 67 crushed stone compacted to 95% Standard Proctor Density in 8-inch lifts for pipe bedding and pipe envelope. Place crushed stone bedding 6 inches below the bottom of the gravity sewer main and/or service line. Place crushed stone envelope to a height of 8 inches above the top of the gravity sewer main and/or service line. Utilize crushed stone material compacted in maximum 8-inch lifts at the proper moisture content as the supplementary trench backfill material between the crushed stone envelope and the flowable fill.

- D. Install flowable fill above crushed stone envelope at a minimum thickness of 14 inches for MPW roadways and 23 inches for TDOT roadways.
- E. Install asphalt binder above flowable fill at a minimum thickness of 8 inches for MPW roadways and 11 inches for TDOT roadways compacted flush with the roadway surface elevation. Maintain smooth driving surface until final paving is complete.
- F. Remove the indicated thickness of asphalt binder as part of the milling operations when preparing to pave the roadway.
- G. Install the indicated thickness of asphaltic surface mix as part of the paving operations in accordance with Metro Public Works or TDOT specifications.
- H. Remediate any settlement of backfill material for a period of one year after final completion and final acceptance of the Work by MWS.

3.04 BACKFILL OUTSIDE OF ROADWAY

- A. Take precautions not to damage the gravity sewer main and accessories during backfill operations. Replace damaged items at no cost to MWS.
- B. Install specified backfill material for the full width of the excavated trench.
- C. Install No. 57 or No. 67 crushed stone compacted to 95% Standard Proctor Density in 8-inch lifts for pipe bedding and pipe envelope. Place crushed stone bedding 6 inches below the bottom of the gravity sewer main and/or service line. Place crushed stone envelope to a height of 8 inches above the top of the gravity sewer main and/or service line.
- D. Install native soil compacted to 90% maximum Proctor Density in 12-inch lifts above the crushed stone envelope to finished grade. Do not utilize rock greater than 8 inches as backfill.
- E. Remediate any settlement of backfill material for a period of one year after final completion and final acceptance of the Work by MWS.
- F. Seed and straw disturbed area to reestablish growth. Replace trees and vegetation removed during clearing and excavation with trees and vegetation of equal size or larger.

END OF SECTION

SECTION 33 31 13.17
REINFORCED CONCRETE PIPE AND FITTINGS

PART 1: GENERAL

1.01 SCOPE

- A. Reinforced Concrete Pipe and fittings for gravity sanitary sewers.

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit for MWS approval descriptive information and shop drawings covering complete details of pipe, manufacture, including concrete design mix, reinforcement, lining material, joints, joint materials, fittings, and special pieces.
- C. Submit a Certification of Inspection stating: the quantity of pipe, including joints, and pipe length in the shipment, the pipe fabricated in accordance with American Concrete Pipe Association QCast Quality Assurance Program requirements, including reinforcement and wall thickness, dates of inspection, dates and results of concrete cylinders and cores compressive tests (3-edge bearing test for 0.01-inch crack strength), pipe piece number, lay schedule number in line, and subjected to and is shipped in conformance with the latest revision of ASTM C76 and ASTM C443.
- D. Submit a Certification of Inspection stating the coarse aggregate utilized in in conformance with the latest revision of ASTM C33, the Portland cement utilized is Type I/II, the water to cement ratio is no more than 0.43 by weight, all reinforcement is in conformance with the latest revision of ASTM A82, A185, A496, or A497, utilized a corrosion protection additive and if indicated, a lining system, and all joints are manufactured in conformance with the latest revision of ASTM C443.
- E. Submit, prior to fabrication and shipment, a laying schedule of all pipes including all fittings, adapters, and specials, stationing, pipe class, class coding, stationing for all gradient changes, and the transition stations for the various pipe classes and the limits of each.

1.03 MEASUREMENT AND PAYMENT

- A. Compensation for reinforced concrete pipe and fittings is not addressed in this section; refer to gravity sewer mains specification section.
- B. Consider all requirements in this section incidental to the Work with no separate payment allowed.

PART 2: PRODUCTS

2.01 REINFORCED CONCRETE PIPE AND FITTINGS

- A. Provide 4000 psi concrete strength, Wall B or Wall C, Class III, Class IV, or Class V pipe indicated on the Drawings in conformance with the latest revision of ASTM C76.
- B. Provide pipe reinforcement with steel areas and clearances for the entire pipe length in conformance with the latest revisions of ASTM C76 and the following:
 - 1. For plain steel wire in conformance with ASTM A82;
 - 2. For plain steel welded wire in conformance with ASTM A185; and
 - 3. For fabricated deformed steel mats in conformance with ASTM C496 or ASTM C497.
- C. Provide two full circular steel cages of reinforcement for pipe 42-inch and larger and do not use elliptical or quadrant steel cages.
- D. Provide steel end ring type joints with extruded or molded and cured rubber gaskets in conformance with ASTM C443.
- E. Provide Xypex C1000 or approved equal corrosion resistant additive in an amount per manufacture's recommendation.
- F. If indicated on the Drawings, provide a mechanically cast lining material system, either a minimum 0.065-inch thick PVC or a minimum 80 mils dry film thickness HDPE. Provide locking studs that penetrates the concrete when the pipe or fittings are cast, and a flap or Type P-1 joint for welding by a certified welder to each adjacent liner section into the pipe wall.
- G. Provide standard pipe lengths of 12 feet.
- H. Provide pipe without lifting holes in the walls.
- I. Transport, handle, and store pipe and/or fittings as recommended by the manufacturer.

PART 3: EXECUTION

3.01 GENERAL

- A. Install pipe and fittings in accordance with the laying schedule provided by the manufacturer.
- B. Install pipe and fittings in conformance with the American Concrete Pipe Association requirements.

- C. Repair the interior lining/coating of pipe and/or fittings as recommended by the lining/coating manufacturer utilizing a certified manufacturer's representative or their designate.

END OF SECTION

SECTION 33 31 51
BYPASS PUMPING

PART 1: GENERAL

1.01 SCOPE

- A. Temporary bypass pumping

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 – Submittal Procedures.
- B. A minimum of 7 days prior to starting the work, submit to MWS for review, a detailed Bypass Pumping Plan with descriptions outlining provisions and precautions to be taken regarding handling wastewater flows and protection of facilities and environment including, but not limited to, the following:
 - 1. Staging areas for pumps;
 - 2. Sewer plugging method and types of plugs;
 - 3. Size and location of manholes or access points for suction and discharge hose or piping;
 - 4. Size of pipeline or conveyance system to be bypassed;
 - 5. Number, size, material, location and method of installation of suction piping;
 - 6. Number, size, material, method of installation and location of installation of discharge piping;
 - 7. Bypass pump sizes, manufacturer, capacity, number of each size to be on site and power requirements;
 - 8. Calculations of static lift, friction losses, and flow velocity (pump curves showing pump operating range shall be submitted);
 - 9. Standby power generator size, location;
 - 10. Downstream discharge plan, including anticipated average daily and peak hydraulic data;
 - 11. Method of protecting discharge manholes or structures from erosion and damage;
 - 12. Thrust and restraint block sizes, calculations, and locations;
 - 13. Sections showing suction and discharge pipe depth, embedment, select fill and special backfill;
 - 14. Method of noise control for each pump and/or generator;
 - 15. Any temporary pipe supports and anchoring requirements;

16. Indicate on the Drawings locations and computations for access to bypass pumping;
 17. Manpower/staffing requirements needed for bypass pumping operations;
 18. Traffic and/or street closure plan if applicable;
 19. Calculations for selection of bypass pumping pipe size;
 20. Schedule for installation of and maintenance of bypass pumping lines;
 21. Plan indicating selection of location of bypass pumping line locations and areas to be fenced;
 22. All items related to testing, inspection, maintenance, and monitoring as described;
 23. Bypass pumping/piping emergency plan; and
 24. Bypass Pumping System Inspection Checklist.
- C. MWS review of a Bypass Pumping Plan does not relieve any responsibility for adequacy or proper execution of the plan.

1.03 MEASUREMENT AND PAYMENT

- A. Consider expenses for bypass pumping incidental to the Work with no separate payment allowed.

1.04 GENERAL

- A. Furnish all material, labor, equipment, power, maintenance, and other items necessary to implement a temporary sewer bypass pumping system for the purpose of diverting existing flow to complete the Work.
- B. Do not discharge or release wastewater or debris into the environment.
- C. Take sole responsibility for site cleanup consistent with MWS's Spill and Overflow Response Plan and fines or penalties enacted by the Tennessee Department of Environmental and Conservation, the United States Environmental Protection Agency, or other regulatory groups or programs if a discharge or release of wastewater or debris occurs during bypass pumping operations.
- D. Ensure temporary sewer bypass pumping activities are completed in full compliance with the Metro Stormwater Management Regulations and no illicit discharges of pollutants to a location that would create contaminated stormwater runoff to a storm sewer, a stormwater conveyance, or a stream within Metro Nashville Davidson County shall occur per Metro Ordinance §15.64.205 - Non-stormwater discharges.

- E. Locate all bypass pumping equipment and accessories above 100 year flood elevation where possible.
- F. Provide, if required by MWS, trailer mounted or portable, bypass pumping assemblies conforming to all requirements.
- G. Take sole responsibility for the design, installation, and operation of the bypass pumping system.
- H. Employ the services of a vendor who can demonstrate a specialization in the design and operation of temporary bypass pumping systems. Provide at least five (5) references of projects of similar size and complexity within the past three (3) years.
- I. Meet the requirements of all codes and regulatory agencies having jurisdiction.
- J. Divert the flow around the work area in a manner that will not cause damage, backup, overflow, or surcharge the system; protect public and private property; and protect water resources, wetlands, and other natural resources.
- K. Maintain uninterrupted sewer service.
- L. Adhere to any satellite city ordinances or apply for variances as needed.
- M. Schedule bypassing during low sewer flows times when possible.
- N. Use of open trenches or channels to convey flow will not be permitted under any circumstances.

PART 2: PRODUCTS

2.01 EQUIPMENT

- A. Provide electric or diesel powered pumps with fully automatic self-priming without the need for foot valves or vacuum pumps that can continue to operate in dry conditions.
- B. Place pumps with start/stop controls in temporary berms designed to contain fluids.
- C. Use coupled, flanged, or proper butt-fusion high density polyethylene (HDPE) discharge pipe free of visible cracks, discoloration, pitting, varying wall thickness, holes, or other deleterious faults with a minimum pressure rating of 2.5 times the total dynamic head of pumps and keep a HDPE fusion machine and qualified operator onsite for the duration of bypass pumping operations to perform immediate repairs.

- D. Provide flexible hose and couplings that are abrasive resistant and suitable for the intended services and internal and external loadings including traffic loading where applicable.
- E. Use short sections of discharge hose only with the written approval from MWS.
- F. If multiple pumps are used with a header system, supply check valves so pumps can be removed, serviced, and/or replaced while the system remains operational.
- G. Keep an adequate supply of spare parts, accessories, and hoisting equipment for pumps and piping onsite for immediate repairs.
- H. Use adequate insulation / protection at the suction and discharge locations to reduce sewer gases and odors to the surrounding area during bypass pumping operations.
- I. Provide noise attenuators for pumps and/or generators to muffle sound to conform to noise ordinances.

2.02 DESIGN REQUIREMENTS

- A. Obtain hydraulic data from MWS, if available.
- B. Design bypass pumping systems to operate 24 hours per day and have sufficient capacity to safely divert 2 times the peak flow around the work area.
- C. Provide 100% redundant standby pumps of each size isolated with valves from the primary bypass pumping system that automatically switch from the initial system upon failure.
- D. Determine discharge and suction piping sizing according to flow calculations and system operating calculations.
- E. Provide redundant piping for relatively long bypass lengths or large diameter bypass lines, if required by MWS.
- F. Design the bypass pumping system to overcome any existing force main pressure on discharge.
- G. Make special design considerations for pump suction lifts greater than 23 feet.

PART 3: EXECUTION

3.01 QUALITY CONTROL AND MAINTENANCE

- A. Perform hydrostatic leakage and pressure tests of the bypass pumping discharge piping using clean water and 2.5 times the dynamic head of the pumps prior to actual operation of the system for each setup.
- B. Notify MWS 24 hours prior to testing.

- C. Physically inspect the bypass pumping system on a continuous basis of at least every two hours and document inspections with an approved Bypass Pumping System Inspection Checklist containing all components of the bypass system.
- D. Ensure the temporary bypass system is properly maintained and a responsible, adequately trained operator is available at all times when pumps are operating.
- E. Provide telemetry with an auto dialer feature or designated personnel to continuously monitor the bypass pumping system during all hours of operations.
- F. Immediately alert MWS of malfunctions or high levels of bypass pumping operations.
- G. Provide inline stream monitoring systems if bypass pumping activities are to be conducted near streams, water conveyance areas, or any case where a potential exists for wastewater to discharge into a waterway. Mount monitoring systems in the receiving streams and in the immediate downstream areas of where the bypass piping goes back to gravity. Monitoring systems to have the minimum following characteristics:
 - 1. Measures real time conductivity and dissolved oxygen in at least 30 minute intervals;
 - 2. Web-portal capabilities with alarm functions for dissolved oxygen and conductivity;
 - 3. Capabilities of sending email and text message alarms to at least five devices;
 - 4. Solar battery charging capabilities.

3.02 INSTALLATION AND REMOVAL

- A. Locate, protect, and minimize disturbance of existing utilities in the area selected for bypass pipelines.
- B. Incorporate a primary and secondary plugging device when plugging or blocking flows and remove plugging device in a manner that permits the sewage flow to return to normal without surge or causing other major disturbances downstream.
- C. Do not install bypass pipelines in wetland areas.
- D. Locate bypass pipelines, if possible, off streets and sidewalks.
- E. When bypass pipelines cross local streets and/or private driveways cover with temporary pavement.
- F. Restore property to preconstruction conditions upon completion of bypass pumping operations.

- G. Obtain written approval from the property owner for placement of bypass equipment and/or piping on private property.

END OF SECTION

SECTION 33 31 61

ACCEPTANCE TESTING FOR SANITARY SEWERS

PART 1: GENERAL

1.01 SCOPE

- A. Acceptance testing for gravity sewer mains, sanitary sewer force mains, low pressure sanitary sewer mains, and sewer manholes.

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit a test plan in accordance with these specifications.
- C. Submit signed test reports for all sanitary sewer testing required.

1.03 MEASUREMENT AND PAYMENT

- A. Consider expenses for acceptance testing of sanitary sewers incidental to the Work with no separate payment allowed.
- B. Provide labor, equipment, or any other devices necessary for proper testing at no cost.

1.04 PERFORMANCE REQUIREMENTS

- A. Supply pipe materials, manholes, and other sanitary sewer appurtenances that will meet performance requirements.
- B. Ensure sewer service connections and service lines meet performance requirements.
- C. Install gravity flow sanitary sewers with straight alignments and uniform grades between manholes.
- D. Install sewer pipe with no more than 5 percent barrel deflection.
- E. Provide installed sewer pipes with no visual seal, longitudinal, and/or transverse cracks.
- F. Provide installed sewer pipes with no measureable leakage and/or infiltration.

1.05 TESTING REQUIREMENTS

- A. Perform Mandrel Test, Low Pressure Air Test, and internal video observations for newly installed gravity sanitary sewers.
- B. Perform Hydrostatic Pressure Test for newly installed sanitary force mains.
- C. Perform Vacuum Test for newly installed sanitary sewer manholes.
- D. Perform Infiltration Test, Exfiltration Test, and/or Smoke Test at the direction of MWS.

1.06 OBSERVATION

- A. Perform testing in the presence of MWS.
- B. Observable leakage, infiltration, grade defects, and/or cracks will not be accepted.

1.07 REMEDIATION

- A. Repair, correct, and retest manholes or sections of pipe which fail to meet specified requirements when tested.
- B. Repair deficiencies in sanitary sewer pipe by re-bedding pipe, re-laying pipe, and/or removing and replacing pipe that does not conform to the Drawings and Specifications at no additional cost.

PART 2: PRODUCTS

2.01 NOT USED

PART 3: EXECUTION

3.01 MANDREL TEST

- A. Perform testing no sooner than 30 days after backfilling of line segment.
- B. Construct or furnish mandrel with a minimum diameter of 95 percent of the inside diameter of the pipe being tested.
- C. Construct or furnish mandrel with metal or rigid plastic material that can withstand 200 psi without being deformed.
- D. Construct or furnish mandrel to have nine or more nonadjustable or noncollapsible runners or legs.
- E. Construct or furnish the barrel section of the mandrel with a diameter of 75 percent of the inside diameter of the pipe being tested.
- F. Pull approved mandrel by hand through sewer sections. Replace any section of sewer not passing mandrel.
- G. Retest repaired or replaced sewer sections.

3.02 LOW PRESSURE AIR TEST

- A. Perform low pressure air test on gravity sanitary sewer mains less than a 36-inch inside diameter in accordance with the latest version of ASTM C 828, ASTM C 924, as ASTM F1417 as applicable.
- B. Use testing pneumatic plugs that can remain in place when pressurized to 25 psig without external aids.
- C. For pipes 36 inches inside diameter and larger test pipe at each joint. 10 seconds is the minimum time allowable for pressure to drop from 3.5 psig to 2.5 psig.
- D. For pipe less than 36 inch inside diameter test in accordance with the following:

1. Determine ground water level.
2. Plug both ends of pipe. For concrete pipe, flood pipe and allow 2 hours to saturate concrete. Then drain and plug concrete pipe.
3. After manhole-to-manhole section of sanitary sewer main has been sliplined and prior to any service lines being connected to new liner, plug liner at each manhole with pneumatic plugs.
4. Pressurize pipe to 4.0 psig. Increase pressure 1.0 psi for each 2.3 feet of ground water over highest point in system. Allow pressure to stabilize for 2 to 4 minutes. Adjust pressure to start at 3.5 psig (plus adjustment for ground water table). See Table 1 below:
5. To determine air loss, measure time interval for pressure to drop to 2.5 psig. Time must exceed that listed in the table below for pipe diameter and length. For sliplining, use diameter of carrier pipe.

TABLE 1 - LOW PRESSURE AIR TEST (TIME ALLOWED FOR PRESSURE LOSS FROM 3.5 PSIG TO 2.5 PSIG)														
Pipe Diam. (in)	Min. Time (min /sec)	Length for min. time (ft)	Time for Longer Length (sec)	Specification Time for Length (L) shown (min:sec)										
				100 ft	150 ft	200 ft	250 ft	300 ft	350 ft	400 ft	450 ft	500 ft	550 ft	600 ft
6	5:40	398	0.854	5:40	5:40	5:40	5:40	5:40	5:40	5:42	6:25	7:07	7:50	8:33
8	7:33	298	1.519	7:33	7:33	7:33	7:33	7:36	8:52	10:08	11:24	12:40	13:56	15:12
10	9:27	239	2.374	9:27	9:27	9:27	9:54	11:52	13:51	15:50	17:48	19:47	21:46	23:45
12	11:20	199	3.419	11:20	11:20	11:20	14:15	17:06	19:57	22:48	25:39	28:30	31:20	34:11
15	14:10	159	5.342	14:10	14:10	17:48	22:16	26:43	31:10	35:37	40:04	44:31	48:58	53:25
18	17:00	133	7.692	17:00	19:14	25:39	32:03	38:28	44:52	51:17	57:42	64:06	70:31	76:56
21	19:50	114	10.47	19:50	26:11	34:54	43:38	52:21	61:05	69:48	78:32	87:15	95:59	104:42
24	22:40	99	13.67	22:48	34:11	45:35	56:59	68:23	79:47	91:10	102:34	113:58	125:22	136:46
27	25:30	88	17.30	28:51	43:16	57:42	72:07	86:33	100:58	115:24	129:49	144:14	158:40	173:05
30	28:20	80	21.36	35:37	53:25	71:14	89:02	106:51	124:39	142:28	160:16	178:05	195:53	213:41
33	31:10	72	25.85	43:06	64:38	86:11	107:44	129:17	150:50	172:23	193:55	215:28	237:01	258:34

3.03 HYDROSTATIC PRESSURE TESTING FOR SANITARY SEWER FORCE MAINS AND LOW PRESSURE SANITARY SEWER MAINS

- A. Perform Hydrostatic pressure testing in accordance with the latest version of applicable AWWA standard.
- B. Pressurize line to 1.5 times the stated working pressure of the pipeline at the lowest elevation or 150 psi whichever is greater.
- C. Maintain pressure for a minimum of 4 hours with no more than a 5 psi variance

for the duration of the test.

- D. Introduce water slowly to vent all air for the section of pipe being tested.
- E. If permanent air vents such as air release valves, are not located at all high points on the section, install corporation cocks at points to expel air as the line is filled with water. Remove corporation cock and plug the line after pressure test has passed.
- F. If the specified testing pressure cannot be maintained, makeup water may be added into the pipeline to main the pressure as directed by the on-site project representative. No more than the amount shown Table 2 - Pressure Testing Make Up Allowance Table below shall be allowed as make up water. The quantity shown is the maximum amount allowed per hour per 1,000 feet for the 4 hour test. The addition of makeup water shall be done only one time and in the presence of MWS allowing visual measurement of the amount added.

Table 2 - Pressure Testing Make Up (Allowance) Water to Maintain Testing Pressure*										
Gallons allowed per hour per 1,000 feet of main tested										
Pipe Diameter	Average Test Pressure (psi)									
	100	125	150	175	200	225	250	275	300	350
1"	0.07	0.08	0.08	0.09	0.10	0.10	0.11	0.11	0.12	0.13
1.25"	0.08	0.09	0.10	0.11	0.12	0.13	0.13	0.14	0.15	0.16
1.5"	0.10	0.11	0.12	0.13	0.14	0.15	0.16	0.17	0.18	0.19
2"	0.14	0.15	0.17	0.18	0.19	0.20	0.21	0.22	0.23	0.25
2.5"	0.17	0.19	0.21	0.22	0.24	0.25	0.27	0.28	0.29	0.32
3"	0.20	0.23	0.25	0.27	0.29	0.30	0.32	0.34	0.35	0.38
4"	0.27	0.30	0.33	0.36	0.38	0.41	0.43	0.45	0.47	0.51
6"	0.41	0.45	0.50	0.54	0.57	0.61	0.64	0.67	0.70	0.76
8"	0.54	0.60	0.66	0.72	0.76	0.81	0.85	0.90	0.94	1.01
10"	0.68	0.76	0.83	0.89	0.96	1.01	1.07	1.12	1.17	1.26
12"	0.81	0.91	0.99	1.07	1.15	1.22	1.28	1.37	1.40	1.52
16"	1.08	1.21	1.32	1.43	1.53	1.62	1.71	1.79	1.87	2.02
18"	1.22	1.36	1.49	1.61	1.72	1.82	1.92	2.02	2.11	2.28
20"	1.35	1.51	1.66	1.79	1.91	2.03	2.14	2.24	2.34	2.53
24"	1.62	1.81	1.99	2.15	2.29	2.43	2.56	2.69	2.81	3.03
30"	2.03	2.27	2.48	2.68	2.87	3.04	3.21	3.36	3.51	3.79
36"	2.43	2.72	2.98	3.22	3.44	3.65	3.85	4.03	4.21	4.55
42"	2.84	3.17	3.48	3.75	4.01	4.26	4.49	4.71	4.92	5.31
48"	3.24	3.63	3.97	4.29	4.59	4.86	5.13	5.38	5.62	6.07
54"	3.65	4.08	4.47	4.83	5.16	5.47	5.77	6.05	6.32	6.83
60"	4.05	4.53	4.97	5.36	5.73	6.08	6.41	6.72	7.02	7.58

* Source: ANSI/AWWA C600-11 Table 5A

3.04 INTERNAL VIDEO OBSERVATIONS

- A. Deliver a color video media compatible with MWS current operating software and devices.
- B. Identify each media with labels showing Project Name, Contractor's name, and

each manhole-to-manhole pipe segment of sewer line.

- C. Audio commentary in video media to be sufficiently free from electrical interference and background noise to provide complete intelligibility of oral report.
- D. Visually display and provide commentary in video media which contain the following: narrative of location, direction of view, manhole numbers/stations, length of segment, pipe diameter and material, date, time of observation, and location of laterals and other key features.
- E. Utilize video observation equipment with current technology and standards including rotating head, capable of 90-degree rotation from horizontal and 360-degree rotation about its centerline.
- F. Utilize video observation equipment capable of measuring distance traveled the in sewer, accurate to plus or minus 2 feet in 1,000 feet.
- G. Provide 360-degree sweep of pipe interior and provide commentary on points of interest and document with MWS standard notations.
- H. Points of interest may include, but are not limited to the following: defects, encrustations, mineral deposits, debris, sediment, and any location determined not to be installed to specifications and drawings.
- I. Maximum recording rate of travel shall be 30 feet per minute.
- J. Do not exceed depth of flow shown in Table 3 below for respective pipe sizes as measured in manhole.
- K. When depth of flow at upstream manhole of sewer line section being worked is above maximum allowable, reduce flow to level shown in Table 3 below, by plugging or blocking of flow, or by pumping and bypassing of flow as specified.

Table 3 - Maximum Depth of Flow for internal video observation	
Nominal Pipe Diameter	Maximum Depth of Flow
6" - 10"	20 percent of pipe diameter
12" - 24"	25 percent of pipe diameter

3.05 VACUUM TESTING FOR MANHOLES

- A. Install vacuum test head assembly at top access point of manhole and adjust for proper seal on straight top section of manhole structure. Following manufacturer's instructions and safety precautions, inflate sealing element to recommended maximum inflation pressure; do not over-inflate.

- B. Evacuate manhole with vacuum pump to 10 inches mercury (Hg), disconnect pump, and monitor vacuum for time period specified in Vacuum Test Time Table 4 below:
- C. If drop in vacuum exceeds 1 inch Hg over specified time period tabulated in Table 4 below, locate leaks, complete repairs necessary to seal manhole and repeat test procedure until satisfactory results are obtained.

TABLE 4 - MINIMUM TESTING TIMES FOR SANITARY MANHOLES – VACUUM TEST			
DEPTH (FT)	TIME IN SECONDS BY DIAMETER		
	48"	60"	72"
4	10	13	16
8	20	26	32
12	30	39	48
16	40	52	64
20	50	65	80
24	60	78	96
*	5.0	6.5	8.0

*Add T times for each additional 2-foot depth.
(The values listed above have been extrapolated from ASTM C924-85)

3.06 EXFILTRATION TEST

- A. Determine ground water elevation.
- B. Plug sewer in downstream manhole and plug incoming pipes in upstream manhole
- C. Install riser pipe in outgoing pipe of upstream manhole when highest point in service lead (house service) is less than 2 feet below bottom of manhole cone.
- D. Fill sewer pipe and manhole of pipe riser with environmentally acceptable biodegradable dyed water to point 2-1/2 feet above highest point in sewer pipe, house lead, or ground water table, whichever is highest
- E. Allow water to stabilize for one to two hours. Take water level reading to determine drop of water surface, in inches, over one-hour period, and calculate water loss (1 inch of water in 4 feet diameter manhole equals 8.22 gallons) or measure quantity of water required to keep water at same level. Loss shall not exceed that calculated from allowable leakage according to the Table 5 - Water Test Allowable Leakage below.

3.07 INFILTRATION TEST

- A. Determine ground water elevation. Ground water elevation must be not less than

- 2 feet above highest point of sewer pipe or service lead (house service)
- B. Plug incoming pipes in upstream manhole.
- C. Insert calibrated 90 degree V-notch weir in pipe on downstream manhole.
- D. Allow water to rise and flow over weir until it stabilizes.
- E. Take five readings of accumulated volume over period of 2 hours and use average for infiltration. Average must not exceed that calculated for 2 hours from allowable leakage according to Table 5 - Water Test Allowable Leakage below.

TABLE 5 - WATER TEST ALLOWABLE LEAKAGE				
DIAMETER OF RISER OR STACK IN INCHES	VOLUME PER INCH OF DEPTH		ALLOWANCE LEAKAGE*	
	INCH	GALLONS	PIPE SIZE IN INCHES	GALLONS/MINUTE PER 100FT.
1	0.7854	.0034	6	0.0039
2	3.1416	.0136	8	0.0053
2.5	4.9087	.0212	13	0.0066
3	7.0686	.0306	12	0.0079
4	12.5664	.0306	15	0.0099
5	19.6350	.0544	18	0.0118
6	28.2743	.1224	21	0.0138
8	50.2655	.2176	24	0.0158
			27	0.0177
			30	0.0197
			36	0.0237
			42	0.0276
For other diameters, multiply square of diameters by value of 1" diameter			Equivalent to 50 gallons per inch of inside diameter per mile per 24 hours	
* Allowable leakage rate shall be reduced to 10 gallons per inch of inside diameter per mile per 24 hours, when sewer is identified as located within 25-year flood plain				

3.08 SMOKE TEST PROCEDURE FOR POINT REPAIRS

- A. Perform smoke test under the direction of MWS.
- B. Utilize Smoke generator that produces a minimum of 2500 standard cubic feet per minute
- C. Give written notices to area residents no fewer than 2 days prior to proposed testing. Also give notice to local police and fire departments 24 hours prior to actual smoke testing.
- D. Operate equipment according to manufacturer's recommendation
- E. Conduct test by forcing smoke from smoke generators through sanitary sewer

main and service connections. Operate smoke generators for minimum of 5 minutes.

- F. Introduce smoke into upstream and downstream manhole as appropriate. Monitor tap/connection for smoke leaks. Note sources of leaks.
- G. Repair and replace taps or connections noted as leaking and then retest. Taps and connections may be left exposed in only one manhole section at time. When repair or replacement, testing or retesting, and backfilling of excavation is not completed within one work day, properly barricade and cover each excavation.
- H. For houses where smoke does not issue from plumbing vent stacks to confirm reconnection of sewer service to newly installed liner pipe, perform dye test to confirm reconnection. Introduce dye into service line through plumbing fixture inside structure or sewer cleanout immediately outside structure and flush with water. Observe flow at service reconnection or downstream manhole. Detection of dye confirms reconnection.

END OF SECTION

Mandrel Test Data Sheet

Metro Water Service

Date: _____

Project: _____

Material: _____

Sheet #: _____

Max Allowed Deflection: _____

Upstream MH Sta. #	Downstream MH Sta. #	Pipe Dia. (inches)	Length (feet)	Pass or Fail

MWS Representative: _____
(Signature)

Date: _____

Contractor: _____
(Signature)

Date: _____

PIPE VS. MANDREL DIAMETER

Material and Wall Construction	Nominal Size(Inches)	Average I.D. (Inches)	Minimum Mandrel Diameter (Inches)
PVC-Solid (SDR 26)	6	5.764	5.476
	8	7.715	7.329
	10	9.646	9.162
PVC-Solid (SDR 35)	12	11.737	11.150
	15	14.374	13.655
	18	17.629	16.748
	21	20.783	19.744
	24	23.381	22.120
	27	26.351	25.033
PVC-Truss	8	7.750	7.363
	10	9.750	9.263
	12	11.790	11.201
	15	14.770	14.032
PVC-Profile (ASTM F 794)	12	11.740	11.153
	15	14.370	13.652
	18	17.650	16.768
	21	20.750	19.713
	24	23.500	22.325
	27	26.500	25.175
	30	29.500	28.025
	36	35.500	33.725
	42	41.500	39.425
HDPE-Profile	48	47.500	45.125
	18	18.000	17.100
	21	21.000	19.950
	24	24.000	22.800
	27	27.000	25.650
	30	30.000	28.500
	36	36.000	34.200
	42	42.000	39.900
	48	48.000	45.600
	54	54.000	51.300
Fiberglass-Centrifugally Cast (Class SN	60	60.000	57.000
	12	12.85	11.822
	18	18.66	17.727
	20	20.68	19.646
	24	24.72	23.484
	30	30.68	29.146
	36	36.74	34.903
	42	42.70	40.565
	48	48.76	46.322
54	54.82	52.079	
60	60.38	57.361	

Leakage Testing for Sanitary Sewer Lines Metro Water Service

Project: _____ Sheet #: _____ Location: _____
 Inspector: _____ Date: _____ Contractor: _____

Line Test Log

Test #	Manhole UP	Manhole Down	Line Length	Line Diameter	Avg. Depth of Line	Avg. Depth of Ground-water	Start Air Pressure	End Air Pressure	Time Elapsed	Time Allowed (per table*)	Pass or Fail	Inspector	Contractor
1													
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													
14													
15													

TABLE 1 - LOW PRESSURE AIR TEST (TIME ALLOWED FOR PRESSURE LOSS FROM 3.5 PSIG TO 2.5 PSIG)

Pipe Diam. (in)	Min. Time (min /sec)	Length for min. time (ft)	Time for Longer Length (sec)	Specification Time for Length (L) shown (min:sec)											
				100 ft	150 ft	200 ft	250 ft	300 ft	350 ft	400 ft	450 ft	500 ft	550 ft	600 ft	
6	5:40	398	0.854	5:40	5:40	5:40	5:40	5:40	5:40	5:40	5:42	6:25	7:07	7:50	8:33
8	7:33	298	1.519	7:33	7:33	7:33	7:33	7:36	8:52	10:08	11:24	12:40	13:56	15:12	
10	9:27	239	2.374	9:27	9:27	9:27	9:54	11:52	13:51	15:50	17:48	19:47	21:46	23:45	
12	11:20	199	3.419	11:20	11:20	11:20	14:15	17:06	19:57	22:48	25:39	28:30	31:20	34:11	
15	14:10	159	5.342	14:10	14:10	17:48	22:16	26:43	31:10	35:37	40:04	44:31	48:58	53:25	
18	17:00	133	7.692	17:00	19:14	25:39	32:03	38:28	44:52	51:17	57:42	64:06	70:31	76:56	
21	19:50	114	10.47	19:50	26:11	34:54	43:38	52:21	61:05	69:48	78:32	87:15	95:59	104:42	
24	22:40	99	13.67	22:48	34:11	45:35	56:59	68:23	79:47	91:10	102:34	113:58	125:22	136:46	
27	25:30	88	17.30	28:51	43:16	57:42	72:07	86:33	100:58	115:24	129:49	144:14	158:40	173:05	
30	28:20	80	21.36	35:37	53:25	71:14	89:02	106:51	124:39	142:28	160:16	178:05	195:53	213:41	
33	31:10	72	25.85	43:06	64:38	86:11	107:44	129:17	150:50	172:23	193:55	215:28	237:01	258:34	

SECTION 33 33 00
LOW PRESSURE SANITARY SEWERS

PART 1: GENERAL

1.01 SCOPE

- A. Low pressure sanitary sewer mains for sizes smaller than 3 inches for grinder pump systems, taps and connections, abandonments, and excavation and backfill.

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit manufacturer's product data for proposed low pressure sanitary sewer pipe, joints, joint materials, specials, and fittings for approval.
- C. Submit crushed stone bedding and envelope material sieve analysis and compaction methods
- D. Submit abandonment plan, bypass pumping requirements, and plugging, if any, and other information pertinent to completion of the Work.
- E. Submit asphaltic binder information certifying material is in conformance with the latest revision of Metro Public Works standard specification Section 02575 if the low pressure sanitary sewer is to be installed within a Metro Public Works roadway or the latest revision of the applicable TDOT asphaltic binder specification if the low pressure sanitary sewer is to be installed within a TDOT roadway.
- F. Submit flowable fill information certifying material is in conformance with the latest revision of Metro Public Works standard specification Section 02225 if the low pressure sanitary sewer is to be installed within a Metro Public Works roadway or the latest revision of the applicable TDOT flowable specification if the low pressure sanitary sewer is to be installed within a TDOT roadway.
- G. Submit outside roadway backfill material source, quality information, and compaction methods.
- H. Submit Proctor Density Test results in accordance with the latest revision of ASTM D698 or ASTM D1557 when required by MWS.
- I. Submit compaction field testing results in accordance with the latest revision of ASTM D6938 or other approved method when required by MWS.

1.03 MEASUREMENT AND PAYMENT

- A. MWS will compensate for furnishing and installing low pressure sanitary sewers

at the contract unit price per linear foot for the low pressure sanitary sewer installed complete and ready for operation. Measure the low pressure sanitary sewer horizontally along the centerline of the pipe in place including valves, bends, reducers, and offsets.

1. Include cost in the unit price for low pressure sanitary sewer for labor, equipment, material, cutting, laying, joints, lowering, raising, other offsets necessary to avoid obstructions, field adjustments of alignment, rodding, temporary filling/flushing caps, standby time and delay in MWS access of existing wastewater system assets, hydrostatic testing and other testing required, and all incidentals necessary for a complete and operable installation.
 2. Include cost in the unit price for low pressure sanitary sewers for fittings whether fittings and/or offsets are indicated on the Drawings or not.
 3. Include cost in the unit price for low pressure sanitary sewers for excavation. Excavation is unclassified with no distinction made between rock and/or dirt excavation. Rock excavation beyond anticipated or indicated in a provided geotechnical report will not be considered basis for additional payment.
 4. Include cost in the unit price for low pressure sanitary sewers for crushed stone bedding, crushed stone envelope, and additional crushed stone used as backfill material when water main exceeds minimum depths.
 5. Include cost in the unit price for low pressure sanitary sewers for outside of roadway backfill material.
 6. Include cost in the unit price for low pressure sanitary sewers for dewatering operations including but not limited to water filtration systems for groundwater, obtaining permits with appropriate agencies on dewatering activities, and appropriately filtering and properly disposing of groundwater in accordance with permits.
 7. Undercutting of undesirable material at the trench base and crushed stone refill material to be paid with Unforeseen Work Elements allowance bid item.
- B. MWS will compensate for furnishing and installing taps and connections at the contract unit price per each for each taps and connection complete and ready for operation.
1. Include all cost in the unit price for taps and connections for labor, equipment, excavation, material, rodding, backfilling, and all incidentals necessary for a

complete and operable installation.

- C. MWS will compensate for cutting and plugging in order to abandon an existing low pressure sanitary sewer at the contract unit price of each for each cutting and plugging operation.
 - 1. Include all cost in the unit price for cutting and plugging for labor, equipment, materials, permanent solid low pressure sanitary sewer plug, removing valve boxes over valves on abandoned low pressure sanitary sewers, and all incidentals necessary for a complete low pressure sanitary sewer abandonment operation.
- D. MWS will compensate for furnishing and installing flowable fill at the contract unit price per theoretical cubic yard calculated utilizing the specified trench width per low pressure sanitary sewer size, the length of low pressure sanitary sewer installed, and the specified flowable fill depth; not the actual amount of flowable fill if more material is installed.
 - 1. Include all cost in the unit price for flowable fill for excavation, material, labor, and all incidentals necessary for a complete installation.
- E. MWS will compensate for furnishing and installing asphalt binder at the contract unit price per theoretical cubic yard calculated utilizing the specified trench width per low pressure sanitary sewer main size, the length of low pressure sanitary sewer main installed, and the specified asphalt binder depth; not the actual amount of asphalt binder if more material is installed.
 - 1. Include all cost in the unit price for asphalt binder for excavation, material, labor, and all incidentals necessary for a complete installation.
- F. MWS will compensate for furnishing and installing miscellaneous concrete at the contract unit price per cubic yard for concrete installed between a proposed low pressure sanitary sewer traversing perpendicular and above an existing water main.
 - 1. Include all cost in the unit price for miscellaneous concrete for excavation, materials, labor, and all incidentals necessary for a complete installation.
- G. MWS will compensate for furnishing and installing temporary low pressure sanitary sewer at the contract unit price per linear foot for the temporary low pressure sanitary sewer installed complete and ready for operation if indicated on the Bid Schedule. MWS will not compensate for furnishing and installing temporary low pressure sanitary sewers if being installed for contractor's ease of

construction and convenience, or being installed due to contractor's negligence. Measure the temporary low pressure sanitary sewer horizontally along the centerline of the pipe in place including valves, bends, reducers, and offsets.

1. Include all cost in the unit price for temporary low pressure sanitary sewers for labor, equipment, excavation, material, cutting, laying, temporary fittings, temporary valves, backfill, testing, temporary connections to the existing wastewater system, temporary service connections, and all incidentals necessary for a complete and operable installation.

1.02 GENERAL

- A. Calculate Bid Schedule payment items of flowable fill and asphalt binder based on a trench width of 2.5 feet. If a wider trench width is utilized during construction, payment will only be compensated based on the trench width of 2.5 feet.
- B. Bury low pressure sewers and backfill trench in roadways in accordance with the following table. Bury pipe at minimum depths unless additional depth is required to avoid an obstruction. Utilize crushed stone material compacted in maximum 8-inch lifts at the proper moisture content as the supplementary trench backfill material when low pressure sewers must be installed below the minimum depths.

	MPW Roadway	TDOT Roadway
Asphalt Binder above Flowable Fill to Grade	8"	11"
Flowable Fill above Crushed Stone Envelope	14"	23"
Crushed Stone Envelope above Top of Pipe	8"	8"
Total Cover (Min Depths)	30"	42"
Crushed Stone Bedding Below Bottom of Pipe	6"	6"

- C. Bury low pressure sanitary sewer and backfill trench outside of roadways in accordance with the following table. Bury pipe at minimum depths unless additional depth is required to avoid an obstruction. Utilized native backfill material compacted in 8-inch lifts as the supplementary trench backfill material when the low pressure sanitary sewer must be installed below the minimum depths.

Total Cover (Minimum Depth)	Crushed Stone Bedding below Bottom of Pipe	Crushed Stone Envelope above Top of Pipe	Native Soil above Crushed Stone Envelope to Finished Grade
-----------------------------	--	--	--

30"	6"	8"	22"
-----	----	----	-----

- D. Maintain existing wastewater services throughout construction.
- E. Request shut down isolation times and durations in writing to MWS 7 days in advance for approval.
- F. Provide sewer customers at least 24 hour notice prior to an interruption of sewer service.
- G. Do not operate valves on the existing system and/or new low pressure sanitary sewers placed in service.
- H. MWS will make every reasonable effort to isolate and shut off the flow of waste water of existing low pressure sewer systems when required for the Work. Circumstances may prevent timely waste water shut offs such as but not limited to faulty valves, excess wastewater flows, access to locations, weather conditions, and lack of forces due to higher priority situations. Consider standby time due to these types of delays incidental to the Work will no separate payment allowed.
- I. Do not make connections to the existing wastewater system until applicable tests including; hydrostatic testing have been performed and reported to MWS and found to be in compliance.
- J. Install temporary caps on new low pressure sanitary sewer and tap caps with a pluggable outlet of adequate size to be utilized as a filling and/or flushing location.
- K. Install a solid permanent low pressure sanitary sewer plug on the end of an existing low pressure sanitary sewer when performing a cutting and plugging operation for abandonment of a low pressure sanitary sewer.
- L. Properly abandon valve boxes over valves on abandoned low pressure sanitary sewers.
- M. Perform Proctor Density Test in accordance with the latest revision of ASTM D698 or ASTM D1557 when required by MWS. Test to be performed by an independent MWS approved materials testing firm. Pay for test if Work is found to be noncompliance.
- N. Perform compaction field testing results in accordance with the latest revision of ASTM D6938 or other approved method when required by MWS. Compaction tests to be performed by an independent MWS approved materials testing firm. Pay for test if Work is found to be noncompliance.

PART 2: PRODUCTS

2.01 GENERAL

- A. Provide low pressure sanitary sewer products and accessories from manufacturers in accordance with MWS Approved Materials List.
- B. Provide SDR 21 PVC pipe for low pressure sanitary sewer mains unless otherwise indicated on the Drawings.
- C. Provide No. 57 or No. 67 crushed stone for pipe bedding, pipe envelope, and additional backfill material when low pressure sanitary sewer exceeds minimum buried depths.
- D. Provide asphaltic binder in conformance with the latest revision of Metro Public Works standard specification Section 02575 when the low pressure sanitary sewer is to be installed within a Metro Public Works roadway and provide asphaltic binder in conformance with the latest revisions of the applicable TDOT specification when the low pressure sanitary sewer is to be installed within a TDOT roadway.
- E. Provide excavatable flowable fill in conformance the latest revision of Metro Public Works standard specification Section 02225 when a low pressure sanitary sewer is to be installed within a Metro Public Works roadway and provide excavatable flowable fill in conformance with the latest revisions of the applicable TDOT specification when the low pressure sanitary sewer is to be installed within a TDOT roadway.
- F. Provide Certa-Lok Yelomine restraint joint pipe and fittings or approved equal for temporary low pressure sanitary sewers. Provide a temporary low pressure sanitary sewer and fittings with a pressure rating equal to 1.5 times the working pressure and adequately sized to maintain the existing level of wastewater service.
- G. Provide full ported PVC bodied valve with the following: water pressure rating of 200psi at 72.4° F; C37700 brass ball; ASTM B16 brass stem; ASTM D 2241 steel handle; O-ring backing cushioned valve seats; NPT threaded for ½” to 2” or IPS socket for ½” to 4” connections; and the stem to have double O-ring seals and a safety shear point above the O-rings.
- H. Provide check valves with a water pressure rating of 200 psi at 72.4° F.

PART 3: EXECUTION

3.01 GENERAL

- A. Deliver low pressure sanitary sewer products and accessories to job site free of damages and/or defects. If damages or defects are discovered, provide new material at no cost to MWS.
- B. Store materials on site in enclosures or under protective above ground coverings.
- C. Support pipe at least every 10 feet of its length during handling, take special care to avoid placing undue stress on the pipe during handling, and avoid any actions that may damage the bell or spigot ends of the pipe.
- D. Keep interiors of low pressure sanitary sewer products free of dirt and debris.
- E. Install low pressure sanitary sewer, joints, and fittings per manufacturer's recommendations.
- F. Install low pressure sanitary sewers to maintain minimum cover as specified.
- G. Install low pressure sanitary sewer pipe in crushed stone gravel bedding in the dry.
- H. Install dewatering systems, if necessary, for excavation and low pressure sanitary sewer installation. Provide water filtration systems for groundwater, obtain permits with appropriate agencies for dewatering activities and appropriately filter and properly dispose of groundwater in accordance with permits.
- I. Do not deflect low pressure sanitary sewers in excess of the manufacturer's recommendations.
- J. Clean the inside of the bell and the outside of the plain end of the pipe with a wire brush wipe clean prior to joint assembly.
- K. Clean all gaskets prior to joints and/or fittings assembly.
- L. Grind all rough edges of the plain end of a field cut pipe.
- M. Maintain a minimum of 10 feet horizontal separation when installing a low pressure sanitary sewer sharing a parallel alignment with a water main or water service line.
- N. If sufficient cover is available, install the low pressure sanitary sewer under existing water mains or water service lines when sharing perpendicular alignments. Maintain a minimum vertical separation of 18 inches from the bottom of the existing water main or the existing water service line to the top of the new low pressure sanitary sewer.
- O. If the low pressure sanitary sewer is installed over the existing water main or

existing water service pipe, maintain a minimum vertical separation of 24 inches from the bottom of the low pressure sanitary sewer to the top of the existing water main. Center the low pressure sanitary sewer at the point of the crossing to keep the water main joints at equal distances and as far as possible from the low pressure sanitary sewer. Install concrete material between the existing water main and the low pressure sanitary sewer crossing for the entire width of the distance between the utilities and for a length of at least 6 feet centered at the point of crossing.

3.02 EXCAVATION

- A. No blasting will be permitted.
- B. MWS may limit the method of excavation if conditions warrant such as trenching within areas of high concentration of utilities.
- C. Contact Tennessee One Call Center (1-800-351-1111) the location of buried facilities pursuant to TCA 65-31-101 through TCA 65-31-133; however, take sole responsibility for the location of all affected underground utilities.
- D. Notify MWS immediately, stop the Work, and wait for MWS direction before resuming the Work if solvents, petroleum products, or any unknown chemical substance is discovered during excavation.
- E. Locate and preserve existing utilities. The types and locations of known existing utilities as indicated on the Drawings are approximate. Repair or replace damaged utilities at no cost to MWS.
- F. Consider all excavation material unclassified, whether a geotechnical report is provided or not.
- G. Saw cut pavement to trench width limits when excavation is within a roadway.
- H. Excavate trench width to permit a minimum of 6 inches between the edge of the trench and the outside of the low pressure sanitary sewer.
- I. Excavate to allow for a minimum of 6 inches of crushed stone bedding below the bottom of the low pressure sanitary sewer.
- J. Remove unstable soil at the trench bottom if discovered and refill area with appropriate material.
- K. Excavate to allow minimum low pressure sanitary sewer pipe cover per low pressure sanitary sewer size and roadway conditions as indicated.
- L. Excavate in accordance with Trench Safety Systems, TOSHA and OSHA regulations, and permits.

- M. Dispose of surplus excavated material at a Metro approved permitted site. Do not place excavated material on private property.

3.02 BACKFILL WITHIN ROADWAY

- A. Take precautions not to damage the low pressure sanitary sewer and accessories during backfill operations. Replace damaged items at no cost to MWS.
- B. Install specified backfill material for the full width of the excavated trench and to specified depths.
- C. Install No. 57 or No. 67 crushed stone compacted to 95% Standard Proctor Density in 8-inch lifts for pipe bedding and pipe envelope. Place crushed stone bedding 6 inches below the bottom of the low pressure sanitary sewers. Place crushed stone envelope to a height of 8 inches above the top of the low pressure sanitary sewers. Utilize crushed stone material compacted in maximum 8-inch lifts at the proper moisture content as the supplementary trench backfill material when low pressure sanitary sewer must be installed below the minimum depths.
- D. Install flowable fill above crushed stone envelope at indicated depths.
- E. Install asphalt binder above flowable fill at the indicated depths compacted flush with the roadway surface elevation. Maintain smooth driving surface until final paving is complete.
- F. Remove the indicated thickness of asphalt binder as part of the milling operations when preparing to pave the roadway.
- G. Install the indicated thickness of asphaltic surface mix as part of the paving operations in accordance with Metro Public Works or TDOT specifications.
- H. Remediate any settlement of backfill material for a period of one year after final completion and final acceptance of the Work by MWS.

3.03 BACKFILL OUTSIDE OF ROADWAY

- A. Take precautions not to damage the low pressure sanitary sewers and accessories during backfill operations. Replace damaged items at no cost to MWS.
- B. Install specified backfill material for the full width of the excavated trench.
- C. Install No. 57 or No. 67 crushed stone compacted to 95% Standard Proctor Density in 8-inch lifts for pipe bedding and pipe envelope. Place crushed stone bedding 6 inches below the bottom of the low pressure sanitary sewer. Place crushed stone envelope to a height of 8 inches above the top of the low pressure

sanitary sewer. Utilize crushed stone material compacted in maximum 8-inch lifts at the proper moisture content as the supplementary trench backfill material when low pressure sanitary sewers must be installed below the minimum depths.

- D. Install native soil compacted to 90% maximum Proctor Density in 12-inch lifts above the crushed stone envelope to finished grade. Utilize native soil material as the supplementary trench backfill material when low pressure sanitary sewers must be installed below the minimum depths. Do not utilize rock greater than 8 inches as backfill.
- E. Remediate any settlement of backfill material for a period of one year after final completion and final acceptance of the Work by MWS.
- F. Seed and straw disturbed area to reestablish growth. Replace trees and vegetation removed during clearing and excavation with trees and vegetation of equal size or larger.

END OF SECTION

SECTION 33 33 13

GRINDER PUMPS

PART 1: GENERAL

1.01 SCOPE

- A. Grinder Pumps including controls and electrical components

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit manufacturer's product data for proposed grinder pumps and components for approval.
- C. Furnish five sets of notarized shop drawings of the grinder pump components complete with the manufacturer's product data, including the tank, pump(s), piping, redundant check valve, alarm panel, and electrical components, and certification of testing and inspection stating the grinder pump components were constructed and satisfactorily tested in full compliance with these specifications and sworn to by the factory inspector in the presence of a Notary Public.
- D. Provide certification that the installer has the proper manufacturer's certification and training to perform the Work.
- E. Submit a start-up report after installation including pump information, test results, and other items concerning the installation.

1.03 MEASUREMENT AND PAYMENT

- A. MWS will compensate for furnishing and installing grinder pumps at the contract unit price per each complete and ready for operation.
- B. Include all cost in the unit price for grinder pumps for grinder pump unit, which includes pump(s), tank, piping, connections to existing septic tank field piping, connection to the proposed or existing low pressure sewer main, alarm panel, and electrical work, excavation, concrete pad, bedding, concrete anchors, backfill, testing, service, site grading and landscaping, and all incidentals necessary for a complete and operable installation.
- C. No payment will be made for connection of electrical work required by an existing customer in order to connect the grinder pumping unit.

PART 2: PRODUCTS

2.01 GRINDER PUMP UNITS

- A. Provide grinder pump units, including alarm panel and redundant check valve, from the manufacturer in accordance with MWS published Approved Materials List.
- B. Provide the required electrical disconnect box, conduit, and conductors for connection of grinder unit to alarm panel and electrical disconnect box.
- C. Provide the gravity sewer piping, connections for the grinder pump unit, and the pump discharge low pressure sewer connection.
- D. Provide a manufacturer's recommended redundant check valve for installation on the discharge low pressure sewer at a MWS determined location.

PART 3: EXECUTION

3.01 INSTALLATION

- A. Excavate hole to a depth that the unit's removable cover extends approximately one inch to four inches above the finished grade and excavate to a sufficient diameter for the installation of poured concrete ballast. Locate excavation where no permanent obstructions will be within six feet of the unit or the discharge lines.
- B. Slope the finished grade surrounding the unit away from the enclosure.
- C. Install a minimum of 12 inches of TDOT Type A, Grade D crushed stone in bottom of the excavation for unit placement.
- D. Install the grinder pump unit as recommended by the manufacturer's written instructions.
- E. Install the unit level and fill the wet well with water to the manufacturer's recommended level to prevent the unit moving while pouring concrete ballast and backfilling around the unit.
- F. Pour concrete for ballast per the manufacturer's recommendations.
- G. Connect the existing septic tank piping and the proposed low pressure sewer discharge to the grinder pumping unit as recommended by the manufacturer.
- H. Install a cleanout at the location directed by MWS.
- I. Verify the grinder pump unit is properly vented to ensure correct operation.
- J. Install the redundant check valve at the location directed by MWS.
- K. Install the required electrical conduit and conductors to the alarm panel and electrical disconnect location and perform electrical connections as recommended by the manufacturer.
- L. Backfill and compact the area surrounding the grinder unit with TDOT Type A, Grade D crushed stone to the depth 12 inches below finished grade.

- M. Backfill, grade, and landscape disturbed area to preconstruction condition or better.
- N. Properly seal around the alarm panel as recommended by the manufacturer.
- O. Connect the alarm control and electrical disconnect at the location acceptable with property owner and MWS.
- P. Provide the services of manufacturer's representative on-site during installation to ensure the grinder pump unit is installed, tested, and started properly.

END OF SECTION

SECTION 33 34 00
SEWER FORCE MAINS

PART 1: GENERAL

1.01 SCOPE

- A. Sewer force mains, connections, abandonments, and excavation and backfill.
Does not include small diameter grinder systems.

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit manufacturer's product data for proposed force main pipe, joints, joint materials, specials, and fittings for approval.
- C. Submit crushed stone bedding and envelope material sieve analysis and compaction methods.
- D. Submit abandonment plan, bypass pumping requirements, and plugging, if any, and other information pertinent to completion of the Work.
- E. Submit asphaltic binder information certifying material is in conformance with the latest revision of Metro Public Works standard specification Section 02575 if the force main is to be installed within a Metro Public Works roadway or the latest revision of the applicable TDOT asphaltic binder specification if force main is to be installed within a TDOT roadway
- F. Submit flowable fill information certifying material is in conformance with the latest revision of Metro Public Works standard specification Section 02225 if the force main is to be installed within a Metro Public Works roadway or the latest revision of the applicable TDOT flowable specification if force main is to be installed within a TDOT roadway.
- G. Submit outside roadway backfill material source, quality information, and compaction methods.
- H. Submit Proctor Density Test results in accordance with the latest revision of ASTM D698 or ASTM D1557 when required by MWS.
- I. Submit compaction field testing results in accordance with the latest revision of ASTM D6938 or other approved method when required by MWS.

1.03 MEASUREMENT AND PAYMENT

- A. MWS will compensate for furnishing and installing force mains at the contract unit price per linear foot for the force main installed complete and ready for operation.
Measure the force main horizontally along the centerline of the pipe in place

including valves, bends, reducers, and offsets.

1. Include cost in the unit price for force mains for labor, equipment, material, cutting, laying, joints, lowering, raising, other offsets necessary to avoid obstructions, field adjustments of alignment, bypass pumping, standby time and delay in MWS isolation of existing sewer system, hydrostatic testing and other testing required, and all incidentals necessary for a complete and operable installation.
 2. Include cost in the unit price for force mains for fittings whether fittings and/or offsets are indicated on the Drawings or not.
 3. Include cost in the unit price for force mains for excavation. Excavation is unclassified with no distinction made between rock and/or dirt excavation. Rock excavation beyond anticipated or indicated in a provided geotechnical report will not be considered basis for additional payment.
 4. Include cost in the unit price for force mains for crushed stone bedding, crushed stone envelope, and additional crushed stone used as backfill material when force main exceeds minimum depths.
 5. Include cost in the unit price for force mains for outside of roadway backfill material.
 6. Include cost in the unit price for force mains for dewatering operations including but not limited to water filtration systems for groundwater, obtaining permits with appropriate agencies on dewatering activities, and appropriately filtering and properly disposing of groundwater in accordance with permits.
 7. Undercutting of undesirable material at the trench base and approved refill material to be paid with Unforeseen Work Elements Allowance bid item.
- B. MWS will compensate for furnishing and installing connections at the contract unit price per each for each connection complete and ready for operation.
1. Include all cost in the unit price for connections for labor, equipment, excavation, material, backfilling, bypass pumping, and all incidentals necessary for a complete and operable installation.
- C. MWS will compensate for cutting and plugging in order to abandon a force main at the contract unit price of each for each cutting and plugging operation.
1. Include all cost in the unit price for cutting and plugging for labor, equipment, materials, permanent solid force main plug, removing valve boxes over valves on abandoned force mains, bypass pumping, and all incidentals necessary

for a complete force main abandonment operation.

- D. MWS will compensate for furnishing and installing flowable fill at the contract unit price per theoretical cubic yard calculated utilizing the specified trench width per force main size, the length of force main installed, and the specified flowable fill depth; not the actual amount of flowable fill if more material is installed.
 - 1. Include all cost in the unit price for flowable fill for excavation, material, labor, and all incidentals necessary for a complete installation.
- E. MWS will compensate for furnishing and installing asphalt binder at the contract unit price per theoretical cubic yard calculated utilizing the specified trench width per force main size and the length of force main install, not the actual amount of asphalt binder if more material is installed.
 - 1. Include all cost in the unit price for asphalt binder for excavation, material, labor, and all incidentals necessary for a complete installation.
- F. MWS will compensate for furnishing and installing miscellaneous concrete at the contract unit price per cubic yard for concrete installed between a proposed force main traversing perpendicular and above an existing water main.
 - 1. Include all cost in the unit price for miscellaneous concrete for excavation, materials, labor, and all incidentals necessary for a complete installation.

1.04 GENERAL

- A. Calculate Bid Schedule payment items of flowable fill and asphalt binder by the following table. If a wider than indicated trench width is utilized during construction, payment will only be compensated based on the trench width limits detailed in the following table.

Nominal Pipe Diameter (inches)	Trench Width (feet)
12 and smaller	2.5
14	3.0
16	3.0
18	3.0
20	3.5
24	4.0
30	4.5
36	5.0
42	6.0

48	6.5
54	7.0
60	8.0
64	8.5

- B. Bury force main and backfill trench in roadways in accordance with the following table. Bury pipe at minimum depths unless additional depth is required to avoid an obstruction. Utilize crushed stone material compacted in maximum 8-inch lifts at the proper moisture content as the supplementary trench backfill material when force main must be installed below the minimum depths.

Nominal Pipe Size	MPW Roadway		TDOT Roadway
	Smaller than 12"	12" and Larger	All Pipe Sizes
Asphalt Binder above Flowable Fill to Grade	8"	8"	11"
Flowable Fill above Crushed Stone Envelope	14"	20"	23"
Crushed Stone Envelope above Top of Pipe	8"	8"	8"
Total Cover (Min Depths)	30"	36"	42"
Crushed Stone Bedding Below Bottom of Pipe	6"	6"	6"

- C. Bury force main and backfill trench outside of roadways in accordance with the following table. Bury pipe at minimum depths unless additional depth is required to avoid an obstruction. Utilized suitable native backfill material compacted in 12 inch lifts as the supplementary trench backfill material when force main must be installed below the minimum depths.

Nominal Force Main Size	Total Cover (Minimum Depth)	Crushed Stone Bedding below Bottom of Pipe	Crushed Stone Envelope above Top of Pipe	Native Soil above Crushed Stone Envelope to Finished Grade
Smaller than 12"	30"	6"	8"	22"
12" and Larger	36"	6"	8"	28"

- D. Request shut down isolation times and durations in writing to MWS 7 days in advance for approval.
- E. Do not make connections to the existing sewer system until applicable tests including hydrostatic testing have been performed and reported to MWS and found to be in compliance.

- F. Install a solid permanent force main plug on the end of an existing force main when performing a cutting and plugging operation for abandonment of an existing force main.
- G. Properly abandon valve boxes and/or manholes over valves on abandoned force mains.
- H. Perform Proctor Density Test in accordance with the latest revision of ASTM D698 or ASTM D1557 when required by MWS. Test to be performed by an independent MWS approved materials testing firm. Pay for test if Work is found to be noncompliance.
- I. Perform compaction field testing results in accordance with the latest revision of ASTM D6938 or other approved method when required by MWS. Compaction tests to be performed by an independent MWS approved materials testing firm. Pay for test if Work is found to be noncompliance.

PART 2: PRODUCTS

2.01 GENERAL

- A. Provide force main products and accessories from manufacturers in accordance with MWS Approved Material List.
- B. Provide ductile iron restrained joint pipe for force mains unless otherwise indicated on the Drawings.
- C. Provide No. 57 or No. 67 crushed stone for pipe bedding, pipe envelope, and additional backfill material when force main exceeds minimum buried depths.
- D. Provide asphaltic binder in conformance with the latest revision of Metro Public Works standard specification Section 02575 when the force main is to be installed within a Metro Public Works roadway and provide asphaltic binder in conformance with the latest revisions of the applicable TDOT specification when the force main is to be installed within a TDOT roadway.
- E. Provide excavatable flowable fill in conformance the latest revision of Metro Public Works standard specification Section 02225 when a force main is to be installed within a Metro Public Works roadway and provide excavatable flowable fill in conformance with the latest revisions of the applicable TDOT specification when the force main is to be installed within a TDOT roadway.

PART 3: EXECUTION

3.01 GENERAL

- A. Deliver force main products and accessories to job site free of damages and/or

defects. If damages or defects are discovered, provide new material at no cost to MWS.

- B. Store materials on site in enclosures or under protective above ground coverings.
- C. Keep interiors of force main products free of dirt and debris.
- D. Install force main, joints, and fittings per manufacturer's recommendations.
- E. Install force main with spigot ends toward the direction of flow. Form a concentric joint with each section of adjoining pipe.
- F. Install force main to maintain minimum cover as specified.
- G. Install force main pipe in crushed stone gravel bedding in the dry.
- H. Install dewatering systems, if necessary, for excavation and force main installation. Provide water filtration systems for groundwater, obtain permits with appropriate agencies for dewatering activities and appropriately filter and properly dispose of groundwater in accordance with permits.
- I. Do not deflect force mains in excess of the manufacturer's recommendations.
- J. Clean the inside of the bell and the outside of the plain end of the pipe with a wire brush wipe clean prior to joint assembly.
- K. Clean all gaskets prior to joints and/or fittings assembly.
- L. Grind all rough edges of the plain end of a field cut pipe.
- M. Maintain a minimum of 10 feet horizontal separation when installing a force main sharing a parallel alignment with a water main or water service line.
- N. Install the force main under existing water mains or water service lines when sharing perpendicular alignments. Maintain a minimum vertical separation of 18 inches from the bottom of the water main or water service line to the top of the force mains.

3.02 EXCAVATION

- A. No blasting will be permitted.
- B. MWS may limit the method of excavation if conditions warrant such as trenching within areas of high concentration of utilities.
- C. Contact Tennessee One Call Center (1-800-351-1111) the location of buried facilities pursuant to TCA 65-31-101 through TCA 65-31-133; however, take sole responsibility for the location of all affected underground utilities.
- D. Locate and preserve existing utilities. The types and locations of known existing utilities as indicated on the Drawings are approximate. Repair or replace damaged utilities, whether shown on the Drawings or not, at no cost to MWS.

- E. Notify MWS immediately, stop the Work, and wait for MWS direction before resuming the Work if solvents, petroleum products, or any unknown chemical substance is discovered during excavation.
- F. Do not remove any structures unless the structure is indicated to be removed on the Drawings or written approval is received by MWS.
- G. Consider all excavation material unclassified, whether a geotechnical report is provided or not.
- H. Saw cut pavement to trench width limits when excavation is within a roadway.
- I. Excavate trench width to permit a minimum of 6 inches between the edge of the trench and the outside of the force main.
- J. Excavate to allow for a minimum of 6 inches of crushed stone bedding below the bottom of the force main.
- K. Remove unstable soil at the trench bottom if discovered and refill area with appropriate material. Notify and receive approval from MWS prior to undercutting and removing undesirable material at the trench base and utilizing approved refill material.
- L. Remove all loose material from the trench bottom. Do not lay force mains and accessories directly on rock.
- M. Excavate to allow minimum force main cover per force main size and roadway conditions as indicated.
- N. Excavate in accordance with Trench Safety Systems, TOSHA and OSHA regulations, and permits.
- O. Dispose of surplus excavated material at a Metro approved permitted site. Do not place excavated material on private property.

3.03 BACKFILL WITHIN ROADWAY

- A. Take precautions not to damage the force main and accessories during backfill operations. Replace damaged items at no cost to MWS.
- B. Install specified backfill material for the full width of the excavated trench and to specified depths.
- C. Install No. 57 or No. 67 crushed stone compacted to 95% Standard Proctor Density in 8-inch lifts for pipe bedding and pipe envelope. Place crushed stone bedding 6 inches below the bottom of the force main. Place crushed stone envelope to a height of 8 inches above the top of the force main. Utilize crushed stone material compacted in maximum 8-inch lifts at the proper moisture content

as the supplementary trench backfill material when force main must be installed below the minimum depths.

- D. Install flowable fill above crushed stone envelope at indicated depths.
- E. Install asphalt binder above flowable fill at the indicated depths compacted flush with the roadway surface elevation. Maintain smooth driving surface until final paving is complete.
- F. Remove the indicated thickness of asphalt binder as part of the milling operations when preparing to pave the roadway.
- G. Install the indicated thickness of asphaltic surface mix as part of the paving operations in accordance with Metro Public Works or TDOT specifications.
- H. Remediate any settlement of backfill material for a period of one year after final completion and final acceptance of the Work by MWS.

3.04 BACKFILL OUTSIDE OF ROADWAY

- A. Take precautions not to damage the force main and accessories during backfill operations. Replace damaged items at no cost to MWS.
- B. Install specified backfill material for the full width of the excavated trench.
- C. Install No. 57 or No. 67 crushed stone compacted to 95% Standard Proctor Density in 8-inch lifts for pipe bedding and pipe envelope. Place crushed stone bedding 6 inches below the bottom of the force main. Place crushed stone envelope to a height of 8 inches above the top of the force main.
- D. Install native soil compacted to 90% maximum Proctor Density in 12-inch lifts above the crushed stone envelope to finished grade. Utilize native soil material as the supplementary trench backfill material when force main must be installed below the minimum depths. Do not utilize rock greater than 8 inches as backfill.
- E. Remediate any settlement of backfill material for a period of one year after final completion and final acceptance of the Work by MWS.
- F. Seed and straw disturbed area to reestablish growth. Replace trees and vegetation removed during clearing and excavation with trees and vegetation of equal size or larger.

END OF SECTION

SECTION 33 39 13

MANHOLES

PART 1: GENERAL

1.01 SCOPE

- A. Precast concrete manholes and accessories.

1.02 SUBMITTALS

- A. Conform to the requirements of Section 01 33 00 Submittal Procedures.
- B. Submit manufacturer's product data for proposed manhole and accessories for approval.
- C. Submit crushed stone bedding, backfill material sieve analysis, and compaction methods.

1.03 MEASUREMENT AND PAYMENT

- A. MWS will compensate for furnishing and installing manholes up to 6 feet in depth and accessories at the contract unit price per each for the manhole and accessories installed complete and ready for operation.
 - 1. Include all cost in the unit price for labor, excavation, bedding, backfill, restoration, manhole including any reinforcement, waterproofing admixture, manhole base, fillet (invert), manhole steps, pipe resilient connectors, stub-outs, plugs, sealants, testing, and any incidentals needed for a complete installation.
 - 2. Undercutting of undesirable material at the trench base and crushed stone refill material to be paid with Unforeseen Work Elements allowance bid item.
- B. MWS will compensate for furnishing and installing frames and covers and accessories at the contract unit price per each installed complete and ready for operation of the type indicated.
 - 1. Include all cost in the unit price for labor, materials, equipment, sealants, testing, and any incidentals needed for a complete installation.
- C. MWS will compensate for furnishing and installing additional manhole sidewall at the contract unit price per vertical foot that exceeds the 6-foot manhole depth, complete in place. Measurement of additional manhole sidewall will be made vertically in place from the invert of the outlet sewer pipe to the bottom side of the frame and cover, excluding the initial 6 feet.

1. Include all cost in the unit price for additional manhole sidewall for labor, equipment, excavation, material, backfilling, and all incidentals necessary for a complete and operable installation.
- D. MWS will compensate for furnishing and installing manhole connections to existing sewers at the contract unit price per each for the manhole connection made complete and ready for operation.
1. Include all cost in the unit price for manhole connections to the existing system for labor, equipment, excavation, material, precast or cored hole, resilient connector, stainless steel external band, insulator ring, backfilling, and all incidentals necessary for a complete and operable installation.
 2. Compensation for sewer connections to proposed manholes will not be permitted.
 3. Compensation for manhole connections is permitted only for existing sanitary sewers. Payment for connections in conjunction with water main installation will not be permitted.
- E. MWS will compensate for furnishing and installing manhole vent pipe assemblies at the contract unit price per each for each manhole vent pipe assembly installed complete and ready for operation.
1. Include all cost in the unit price for manhole vent pipe assemblies for labor, pipe, fittings, interior and exterior coatings, connection to the manhole, concrete foundation, excavation, bedding, insect screen, and all incidentals necessary for a complete and operable installation.
- F. MWS will compensate for furnishing and installing manhole stub outs for future sewer connections at the contract unit price per each installed complete and ready for operation.
1. Include all cost in the unit price for labor, excavation, bedding, backfill, pipe material, connection to manhole, stub out plug, and all incidentals necessary for a complete and operable installation.
- G. MWS will compensate for furnishing and installing drop pipe assemblies at the contract unit price per each assembly installed complete and ready for operation.
1. Include all cost in the unit price for labor, excavation, bedding, backfill, pipe material, pipe bends, hand formed mortar stop, manhole

connections, and all incidentals necessary for a complete and operable installation.

1.04 GENERAL

- A. Use various lengths of manhole sections in combination to provide correct height with fewest joints.
- B. For stub outs provide a 24-inch long stub out with resilient connector to the size, line, and gradient indicated on the Drawings for future sewer mains. Provide a bell end of a joint of pipe and plug and seal the bell with a plug. Consider the stub out as a part of the manhole when performing vacuum testing.
- C. Construct drop pipe assemblies when the upstream proposed sewer invert is 2 feet or greater above the downstream discharging sewer invert where indicated on the Drawings. Drop pipe assemblies must be approved by MWS for each proposed location. Inside manhole drop pipe assemblies are not permitted.
- D. Backfill drop assembly with 3000 psi concrete to form solid encasement for all drop connections. Extend concrete encasement minimum of 4-inches outside bells as indicated on the Drawings.
- E. Locate vent pipes outside of roadway as indicated on the Drawings and provide vent outlet assemblies as indicated on the Standard Details with the opening of the vent pipe no less than 9 feet above the existing ground and a minimum of 1 foot above the 100-year flood plain elevation.
- F. For manholes in conjunction with water main use, cutouts or holes should be 6-inches or greater from the floor base.
- G. Provide water additive, pre-packaged, inorganic, flowable, non-gas liberating, non-metallic, cement-based non-shrink grout having a minimum 28-day compressive strength of 7,000 psi meeting the latest revision of ASTM Designation C 1107 when connecting to existing structures.

PART 2: PRODUCTS

2.01 MANHOLES

- A. Provide concentric manholes with steps.
- B. Provide a minimum 4,000 psi, 28-day compressive strength precast concrete manholes to support an AASHTO H-20 vehicle loading.
- C. Brick masonry materials for manholes or manhole adjustments are not permitted.
- D. Provide manhole waterproofing admixture of XYPEX C1000 or approved equal at 3% during the batching operation. Add dye to verify XYPEX C1000 admixture

was added during batching operation.

- E. Provide manholes and accessories conforming to the latest requirements of ASTM C478 and ASTM C913.
- F. Provide precast base riser section with integral floors.
- G. Provide adjustment rings set to the cone section by low strength waterproof and water tight epoxy.
- H. Provide a double seal of flexible bitumastic joint sealant joints between the sections of precast manhole sidewalls and provide a single seal of flexible bitumastic joint sealant between the precast concrete sidewall and manhole cover frame conforming to the latest revisions of ASTM C990.
- I. Mark the date of manufacture and name or trademark of manufacturer on inside of the manhole barrel.
- J. Provide manhole sections without penetrations for lifting.
- K. Provide a flexible connector assembly with a 2-foot section of piping immediately outside of the manhole.
- L. For manholes larger than 48-inch diameter, provide precast base sections with flat slab top precast sections when transitioning to 48-inch diameter manhole access riser sections. Provide concentric transitions located to provide minimum of 7-foot head clearance from base to underside of transition section.

2.02 DOG HOUSE MANHOLES

- A. Provide dog house manholes only at locations where indicated on the Drawing and only with MWS approval.
- B. Spray or trowel apply coating to the dog house manhole interior base section the greater of 4 feet or 2 feet above the largest diameter pipe. Provide epoxy resin, similar to Warren Environmental Systems S-301, polyurea similar to SpectraShield, or a urethane similar to Sprayroq SprayWall system formulated for application within a sanitary sewer environment or approved equals.
- C. The cured epoxy or urethane resin system shall conform to the following minimum structural standards:

Minimum Requirements			
Cured Product	Test Method	Urethane Results	Epoxy Results
Compressive Strength	ASTM D695	10,500 psi	12,000 psi
Tensile Strength	ASTM D638	7,000	7,000
Flexural Strength	ASTM D790	12,000 psi	11,000 psi
Flexural Modulus	ASTM D790	550,000 psi	500,000 psi
Shore D Hardness	ASTM D2240	90	83 - 85
Adhesion to Concrete	ASTM D4541	Substrate failure	Substrate failure

2.03 FRAMES AND COVERS

- A. Provide cast iron frames, grates, rings, and covers in conformance with the MWS Approved Materials List and as indicated on the Standard Details and conforming to the latest requirements of ASTM A48, Class 30 and AASHTO H-20 vehicle loading.
- B. Provide castings that conform to the shapes and dimensions with the logos and wording indicated on the Standard Details. Provide castings that are smooth, clean, complete, free from blisters, defects, and any other surface imperfections. Defective castings will not be permitted.
- C. Provide frames and covers where the cover securely rests on the frame without rocking and the cover is in complete contact with the frame for the entire perimeter of the contact surface.
- D. When inside roadways, secure the frame and cover to the manhole cone section with high strength waterproof epoxy.
- E. When outside roadways, provide flexible bitumastic joint sealant between manhole frame and top cone section.
- F. When outside roadways, secure the frame and cover to the manhole cone section with a minimum of two concrete anchors 7/8 inch in diameter spaced 180 degrees apart imbedded a minimum of 3 inches.
- G. Use concrete adjustment rings when vertical adjustments are 2 inches or greater with a maximum total adjustment of 18 inches.
- H. Provide two non-penetrating pick holes in manhole covers as indicated on the Standard Details.

- I. Provide watertight manhole frames and covers where indicated on the Drawings or when subjected to ponding. Provide watertight frames and covers with exterior cover having non-penetrating concealed pick holes and the interior cover being a solid, gasket locking T-bar design as indicated on the Standard Details. Watertight manhole frames and covers shall be provided with minimum of four bolts and gasket designed to seal frame to cone.

2.04 PIPE CONNECTIONS TO MANHOLE

- A. Provide connectors from the MWS Approved Materials List.
- B. Provide Kor-N-Seal resilient connector, A-Lok resilient connector, or an approved equal conforming to the latest revisions of ASTM Designation C 923 for pipe to manhole connections.
- C. Provide a stainless steel external band around the resilient connector and external band around the pipe.
- D. Provide the manhole manufacturer's insulator ring.
- E. Fill the void between the pipe and the connector with an approved flexible gasket material.
- F. Where rigid joints between pipe and cast-in-place manhole base are specified, provide polyethylene-isoprene water-stops in conformance with the latest revisions of ASTM C923.
- G. For water main to manhole connections, seal the space between the pipe and the manhole sidewall with an assembly consisting of a rubber gasket and a stainless steel clamp with a minimum width of 9/16 inches.
- H. Provide a distance of at least 16 inches measured from the top of the pipe opening to the top of the base or sidewall section.

2.05 STEPS

- A. Insert and securely embed steps in the manhole sidewall as indicated on the Standard Details.
- B. Provide non-skid design steps manufactured of either plastic coated steel constructed of ½-inch steel reinforcing rods encapsulated in polypropylene plastic or aluminum magnesium silicide alloy in conformance with Federal Specifications QQ-A-200/8.
- C. Provide steps that will support a 1,000 pound load.

2.06 VENT PIPES

- A. Provide 4" diameter class 350 ductile iron pipe.

- B. Apply two coats of aluminum epoxy at a thickness of 5.0 millimeters and a top coat of dark green asphaltic polyurethane at 3.0 to 5.0 millimeters to the exposed vent pipe.

PART 3: EXECUTION

3.01 GENERAL

- A. Install and verify that lines and grades are constructed in accordance with the Drawings.
- B. Provide an adequate foundation for all manhole structures by removing and replacing unsuitable material with well-graded granular material, by tightening with coarse rock, or by such other means as provided for foundation preparation of the connected sewers, or as directed by MWS.
- C. Set manhole frame for the cover on the manhole sidewall in a double seal bed of flexible bitumastic joint sealant such as Ram-Nek at the required elevation and red head anchor the frame to the manhole sidewall as indicated on the Drawings.
- D. Tilt the surface of the frame and cover to conform to the slope, crown, or grade of the existing or proposed surface where manholes are constructed in paved areas or fill slopes.
- E. Perform vertical adjustments to proposed and existing frame and covers with concrete adjustment rings in the available heights or with flexible bitumastic joint sealant as required.
- F. Dewater sufficiently to maintain the ground water level at or below the bottom of the manhole foundation prior to and during the placement of the foundation.
- G. Place precast base on minimum 6-inch foundation of crushed stone or concrete foundation slab for a 48-inch diameter manhole and an 8-inch foundation for manholes larger than 48-inches in diameter.
- H. If excavation for pipe installation requires undercutting adjacent to the manhole, undercut to competent material for the manhole.
- I. Notify MWS immediately when unsatisfactory material is encountered in the manhole foundation subgrade. Undercut, with MWS approval, up to 12-inches of additional material to achieve suitable foundation.
- J. Protect manholes from damage until Work has been accepted. Repair damage to manholes at no additional cost to MWS.
- K. Provide a minimum of 72 hour notice to customers whose sanitary sewer service is to be interrupted for any reason.

3.02 PRECAST MANHOLE SECTIONS

- A. Install sections, joints, and flexible bitumastic joint sealant material in accordance with manufacturer's recommendations and as indicated on the Drawings.
- B. Install precast adjustment rings above tops of cones or flat-top sections as required to adjust finished elevation and to support manhole frames.
- C. Wrap the outside of the manhole at each riser joint with bitumastic waterproofing material per manufacturer's recommendations. No grout is permitted on the interior of manhole riser joints prior to testing.
- D. When installing a manhole 14 feet or greater depth, properly cure concrete foundation pad for 72 hours prior to manhole installation.

3.03 PIPE CONNECTIONS AT MANHOLES

- A. Install approved resilient connectors at each pipe entering and exiting manholes in accordance with manufacturer's instructions and as indicated on the Drawings.
 - 1. For connecting steel, ductile iron, PVC, or other smooth exterior pipes to the manhole, seal the space between the pipe and manhole wall with an assembly consisting of rubber gaskets or links mechanically compressed to form watertight barrier.
 - 2. For connecting concrete, cement mortar coated, or smooth exterior pipes to the manhole, seal the space between the pipe and manhole wall with an assembly consisting of stainless steel power sleeve, stainless steel take-up clamp with a minimum width of 9/16 inch and a rubber gasket.
- B. Fill the space between manhole wall and pipe connection with non-shrinking flexible gasket material.
- C. Utilize a manhole supplier specified torque wrench to seat the resilient connector with an approved flexible gasket material.

3.04 INVERT CHANNELS FOR SANITARY SEWERS

- A. Construct invert channels to provide smooth flow transition waterway with no disruption of flow at pipe-manhole connections. Conform to following criteria:
 - 1. Slope of invert bench: 1-inch per foot minimum; 1-¹/₂-inches per foot maximum
 - 2. Depth of bench invert to equal the crown of the largest pipe diameter.
- B. Construct a 0.2 foot invert cross slope through manhole with smooth transition of invert through manhole, unless otherwise indicated on Drawings. Form invert channels with concrete if not integral with manhole base section. For direction

changes of mains, construct channels with curves tangent to direction of mains with maximum possible radius of curvature. Provide curves for side inlets and smooth invert fillets for flow transition between pipe inverts.

3.05 BACKFILL

- A. Place and compact backfill materials in area of excavation surrounding manholes in accordance with the requirements of gravity sewer mains.
- B. Provide positive drainage away from all manhole frames to natural grade in unpaved areas.

END OF SECTION

SECTION 02225
EARTHWORK FOR STRUCTURES AND PIPELINES

PART 1 - GENERAL

1.1 DESCRIPTION OF WORK

- A. Structure excavation and foundation preparation shall consist of necessary excavating, removal, and satisfactory disposal of all material within the limits hereinafter stipulated and preparing the foundation for the installation or construction of bridges, culverts, underdrains, and other structures not otherwise provided for by TDOT Standard Specifications all in accordance with TDOT Standard Specifications and this Section and in reasonably close conformity with the lines, grades, and typical cross sections shown in the plans or established by the Engineer.
- B. This Work shall also include the construction and subsequent removal of all bracing, shoring, cribbing, cofferdams, etc.; all pumping and bailing; all backfilling; and the disposal of excess or unsuitable material.

1.2 RELATED WORK SPECIFIED ELSEWHERE

Section 01050 - Field Engineering
Section 01410 - Testing Laboratory Services
Section 01560 - Project Erosion and Siltation Control
Section 02100 - Clearing and Grubbing
Section 02200 - Earthwork
Section 02210 - Embankments
Section 02350 - Piling
Section 02500 - Paving and Surfacing
Section 02720 - Storm Sewers and Drain Systems
Section 03300 - Cast-In-Place Concrete
Section 04400 - Stone Masonry

1.3 APPLICABLE SPECIFICATIONS

"STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", Latest Revision, Tennessee Department of Transportation (TDOT)

"SUBDIVISION SPECIFICATIONS FOR STREETS AND ROADS", Latest Revision, Metropolitan Government of Nashville and Davidson County

1.4 APPLICABLE REFERENCES

"American Association of State Highway and Transportation Officials" (AASHTO), Latest Revision

"Underground Utility Damage Prevention Act of the State of Tennessee", Latest Revision

"Stormwater Management Manual" (SMM), Latest Revision, Metropolitan Government of Nashville and Davidson County

"Occupational Safety and Health Act" (OSHA), Latest Revision, State and Federal Governments

"American Society of Testing and Materials" (ASTM), Latest Revision

1.5 CLASSIFICATION

Structure excavation and foundation preparation will be classified and paid for under the following designations:

A. Culvert Excavation (unclassified).

Structure excavation and foundation preparation performed within the limits stipulated in TDOT Standard Specifications Subsections 204.08 and 204.10 and paragraphs 4.1 and 4.3 for all box bridges, pipe culverts, sewers, conduits, all other culverts, and all minor structures of any type and description will not be measured and paid for directly but the cost will be incidental in other items unless otherwise noted in the plans.

B. Dry Excavation (bridges).

Structure excavation and foundation preparation performed above the datum line (established by elevation and definitely set out in the plans) and within the limits stipulated in TDOT Standard Specifications Subsections 204.08 (a) and 204.10 (a) and subparagraphs 4.1 A and 4.3 A and not classified as rock excavation (bridges) as indicated or directed will be classified and paid for as dry excavation (bridges).

C. Wet Excavation (bridges).

Structure excavation and foundation preparation performed below the datum line (established by elevation and definitely set out in the plans) and within the limits stipulated in TDOT Standard Specifications Subsections 204.08 (a) and 204.10 (a) and subparagraphs 4.1 A and 4.3 A and not classified as rock excavation (bridges) as indicated or directed will be classified and paid for as wet excavation (bridges).

D. Rock Excavation (bridges).

1. Structure excavation and foundation preparation performed either above or below the datum line (established by elevation and definitely set out in the plans) and within the limits stipulated in TDOT Standard Specifications Subsections 204.08 (a) and 204.10 (a) and subparagraphs 4.1 A and 4.3 A and consisting of material which cannot be economically excavated without the use of explosives also any boulder, slab, or fragment of rock having a volume of not less than one half (1/2) cubic yard, all portland cement concrete, and all masonry (dry mortar) as indicated or directed will be classified and paid for as rock excavation (bridges).

2. Cemented gravel, cemented chert, soft shale, or soft slate even though requiring the use of explosives for economical excavation will not be classified as rock.

E. Bridge Excavation (unclassified).

Bridge excavation (unclassified) shall be structure excavation and foundation preparation performed either above or below the datum line (established by elevation and definitely set out in the plans) as stipulated in TDOT Standard Specifications Subsections 204.08 (a) and 204.10 (a) and subparagraphs 4.1 A and 4.3 A regardless of the nature of the material excavated.

F. Rock Drilling (bridges).

Rock drilling as herein set out covers the drilling or sinking of test holes through or in rock in order to verify the condition of the foundation.

G. Bedding Material for Support for Pipe Culverts.

Class A - portland cement concrete Class A.
Class B - specially selected granular soil.

PART 2 - MATERIALS

2.1 FOUNDATION FILL MATERIAL

Material for foundation fill material shall consist of suitably graded sand, gravel, slag, or stone as approved by the Engineer.

2.2 BEDDING MATERIAL

- A. Material for Class B bedding for pipe culverts shall consist of sand or a natural sandy soil all of which passes a three-eighths (3/8) inch sieve and not more than ten (10) percent passes a no. 200 sieve, or stone, gravel, chert, or slag meeting the grading requirements for either grading C, D, or E in TDOT Standard Specifications Subsection 903.05.
- B. In rock cuts or other areas designated by the Engineer where a free drainage bedding or backfill material is required the material shall be crushed stone, crushed slag, or washed gravel meeting the requirements in TDOT Standard Specifications Subsection 903.17 and Section 02720 - Storm Sewers and Drain Systems.

2.3 CONCRETE

Concrete shall conform to the requirements in TDOT Standard Specifications Section 604 and Section 03300 - Cast-In-Place Concrete. Unless otherwise shown in the plans or in the special provisions Class A concrete shall be used for foundation seals and shall meet the requirements in TDOT Standard Specifications Subsection 604.19 and Section 03300 - Cast-In-Place Concrete. Concrete for culvert pipe cradles shall be Class A.

2.4 BACKFILL MATERIAL

- A. Material for backfill shall be fine compactable soil selected from structure excavation if approved by the Engineer as being suitable. Additional material needed shall be obtained from roadway or borrow excavation as described in TDOT Standard Specifications Section 203 and Section 02200 - Earthwork.

- B. Granular backfill material for structures shall be Class A aggregate, grading D meeting the requirements in TDOT Standard Specifications Subsection 903.05

2.5 FLOWABLE FILL

When required by the plans backfill material (flowable fill) will be placed at locations shown in the plans or as directed by the Engineer. Flowable fill shall be of such consistency and strength as to not settle and of such consistency and strength that it can be removed with out the use of heavy equipment after final set.

- A. Materials used in the placement of flowable fill shall meet the following requirements:

<u>Material</u>	<u>TDOT Subsection</u>	<u>Public Works Section</u>
portland cement, type I	901.01	03300
fine aggregate*	903.01	03300
fly ash (Class C or Class F)	AASHTO M 295	03300
water	918.01	03300
air entraining admixtures**	918.09	03300

* Any clean fine aggregate with one hundred (100) percent passing a three-eighths (3/8) inch mesh sieve and not more than fifteen (15) percent passing a no. 200 sieve may be used.

**High air generators or forming agents may be used in lieu of conventional air entraining admixtures and may be added at jobsite and mixed in accordance with manufacturers recommendation.

- B. Flowable fill is a mixture of portland cement, fly ash, fine aggregate, air entraining admixture, and water and contains a low cementitious content for reduced strength development. Submit mix designs to the Engineer for approval. The following are suggested mix guides for excavatable and non-excavatable flowable fill:

<u>Material</u>	<u>Excavatable Per Cubic Yard</u>	<u>Non-Excavatable Per Cubic Yard</u>
portland cement, type I	75 lbs. - 100 lbs.	75 lbs. - 150 lbs.
fly ash (Class C or Class F)	none	150 lbs. - 600 lbs.
water	*	*
air**	5% - 35%	5% - 15%
28 day compressive strength**	100 psi max.	125 psi min.
unit weight (wet)**	90 lbs - 110 lbs.	100 lbs. - 125 lbs.

* Mix designs shall produce a consistency that will result in a flowable self leveling product at time of placement.

**The requirements for percent air, compressive strength, and unit weight are for laboratory designs only and are not intended for jobsite acceptance requirements.

Fine aggregate shall be proportioned to yield one cubic yard (1 yd³).

- C. The above proportions may be adjusted by the Engineer to obtain the consistency required for satisfactory flow. Consistency shall be determined as follows: place an open ended cylinder (pipe) three (3) inches in diameter by six (6) inches in height in an upright position on a smooth level surface. Fill the cylinder with a representative sample of the flowable fill proposed for use. Remove the cylinder by lifting it straight up thus allowing sample to diffuse on the smooth level surface. The flowable fill should diffuse into a circular shape having an approximate diameter of not less than eight (8) inches.
- D. Each consistency test shall represent up to one hundred (100) cubic yards of flowable fill at each installation.
- E. Use flowable fill manufactured at plants that qualify as approved sources in accordance with the "Standard Operating Procedure for Ready-Mix Concrete". Revolution counter requirements are waived.
- F. Deliver flowable fill using concrete construction equipment. Place flowable fill by chute, pumping, or other methods approved by the Engineer. Tremie flowable fill through water.
- G. Use straps, soil anchors, or other approved means of restraint to ensure correct alignment when flowable fill is used as backfill for pipe or where floatation or misalignment may occur.
 - 1. Protect flowable fill from freezing for a period of thirty-six (36) hours after placement.
 - 2. Place flowable fill to the designated fill line without vibration or other means of compaction. Do not place flowable fill during inclement weather, e.g. rain or ambient temperature below forty (40) degrees Fahrenheit.
 - 3. Take all necessary precautions to prevent any damages caused by the hydraulic pressure of the fill during placement prior to hardening. Provide the means to confine the material within the designated space.
- H. Acceptance of flowable fill will be based on a minimum temperature of flowable fill at the point of delivery of fifty (50) degrees Fahrenheit.
- I. The Contractor shall furnish certification that all flowable fill delivered to the project contains the relative proportions of solid materials specified above.

PART 3 - EQUIPMENT

All equipment necessary for the satisfactory performance of this Work shall be on the project and approved before the Work will be permitted to begin.

PART 4 - EXECUTION

4.1 EXCAVATION

- A. Bridges, Box Culverts and Other Major Structures.

Before excavation is started the Engineer or Contractor when required will set stakes locating and outlining the structure and cross section for excavation computations. No excavation shall be started prior to that time.

1. All structure excavation shall be cut to the lines and elevations indicated in the plans or as directed by the Engineer. Working variations outside the neat lines will be permitted however only that excavation outlined under TDOT Standard Specifications Subsection 204.12 and paragraph 5.1 below will be measured for payment.
2. No excavated materials shall be deposited or disposed of outside the construction lines unless directed by the Engineer.
3. When solid rock is encountered in roadway cut sections and channel sections under bridges presplitting operations shall be performed in accordance with the provisions in TDOT Standard Specifications Subsection 203.04. Hole spacing along bridge abutment sites shall not exceed twelve (12) inches.
4. Inclined surfaces of rock used as foundation shall be excavated either level or in steps. When necessary as determined by the Engineer to obtain good bond the surface of rock foundation shall be roughened or suitable anchors installed.
5. Existing concrete foundations, boulders, or ledge streaks of rock projecting into the bottom of the excavation shall be removed to a depth of six (6) inches below foundation elevation and the space backfilled with approved material and thoroughly compacted.
6. Excavation below bridge foundation elevations as given shall be done only upon direction of the Engineer. All materials moved without such authority shall be replaced by the Contractor without compensation by constructing a sub-footing of the same materials as the footing of the structure unit and six (6) inches wider on every side.

B. Pipe Culverts.

In addition to any of the foregoing provisions that are applicable the following procedures will be required:

1. in excavating for pipe culverts the width of the pipe trench shall be sufficient to permit satisfactory jointing of the pipe and thorough tamping of the bedding material under and around the pipe.
2. when rock, hardpan, or other unyielding material is encountered in the pipe trench it shall be removed below the foundation grade for a depth of six (6) inches or as directed by the Engineer.

C. Utilization of Excavated Materials.

All suitable excavated material shall be utilized as backfill or embankment. Excess or unsuitable material shall be disposed of in such a manner as not to obstruct the

stream or otherwise impair the efficiency or appearance of the structure. No excavated material shall be deposited at any time in such a manner as to endanger a partly finished structure.

1. The Contractor shall handle and deposit excavated materials in such a manner as to furnish proper protection to materials which will be incorporated in the structure.
2. In streams the disposal of material will be subject to the laws of the U.S. Government and requirements set out in the standard permit form of the applicable government agency approving the location and plans and authorizing the construction of the structure.

4.2 PROTECTION OF EXCAVATION

The Contractor will be held responsible for protecting his excavation and shall take every precaution to maintain the excavation intact.

- A. Cofferdams or cribs used in the preparation and protection of the foundation in general shall be carried well below the bottom of the footings, shall be substantially braced in all directions, and shall be of such construction as will permit them to be pumped and maintained free of water until the construction therein has been completed. Unless otherwise specifically indicated in the plans the interior dimensions of the cofferdam will be such as to give sufficient clearance to provide for the construction and inspection of forms and to provide for the handling and pumping of leakage outside of the footing area. Cofferdams or cribs which tilt or move out of position during the process of sinking shall be righted or enlarged in order to provide the necessary clearance.
- B. Cofferdams or cribs shall be so constructed as to protect the foundation and the construction therein against damage from a rise in the stream.
- C. Timber or bracing of a cofferdam or crib may extend into or through the substructure only with the written permission of the Engineer obtained before the construction of the cofferdam or crib has been started. In addition the cofferdams for structure widening shall not be braced off of the existing structure.
- D. The Contractor shall submit drawings showing details of his proposed cofferdam or crib construction. The type and clearance of cofferdams or cribs insofar as they affect the finished structure or part thereof will be subject to the approval of the Engineer but the design and successful construction shall be the responsibility of the Contractor.
- E. Cofferdams or cribs with all falsework, sheeting, bracing, etc., shall be removed by the Contractor after the completion of the substructure therein unless otherwise directed. The removal shall be affected in such a manner as not to disturb nor mar the completed work.
- F. If the foundation excavation has become disturbed or distorted it shall be cleaned out and restored to satisfactory condition at the Contractor's expense.

4.3 FOUNDATION PREPARATION

A. Bridges, Box Culverts, and Other Major Structures.

The preparation of foundations for bridges, box culverts, and other major structures in addition to the stipulations set out in TDOT Standard Specifications Subsections 204.08 and 204.09 and this Section shall be in accordance with the following:

1. When the foundation has been completed to foundation elevation as given the Engineer shall be notified and the construction therein withheld pending his inspection and approval of the foundation.
2. When directed by the Engineer the Contractor shall test each foundation unless piles are indicated in the presence of the Engineer by sinking not less than three (3) holes nor more than six (6) holes to a depth of between six (6) feet to ten (10) feet in order to verify the apparent conditions of the foundations.
3. Should these test holes disclose unsatisfactory foundation conditions the excavation shall be carried lower as directed by the Engineer and new tests made until a satisfactory foundation is secured. The costs incurred in sinking test holes will not be paid for directly but shall be included in the Contract Unit Bid Price for other items of construction unless specified otherwise on the Contract drawings.
4. When rock is encountered in the excavation for the foundation it shall be cleared off and the Engineer notified. Test holes shall then be drilled in the rock as shown in the plans or directed by the Engineer to determine the lines of demarcation, the classification, and the stability of the rock. The excavation shall then be continued to the elevation designated by the Engineer and test holes if required by the Engineer shall again be drilled and excavation continued until a foundation approved by the Engineer is secured.
5. Rock used as foundation shall be stripped and cleaned of all overlying materials. All loose, disintegrated, or light slabby portions of the rock shall be removed.
6. In rock foundations when the rock is shattered below the foundation elevation the shattered material shall be removed and the space so created rebuilt with the same type of construction as the proposed overlying construction. The additional quantities thus made necessary shall not be included in the pay quantities for this item.
7. When the plans indicate that piles shall be driven or if after foundation excavation has been completed it becomes necessary to reinforce the foundation by driving piles therein any bulge of the foundation material caused by the driving of the piles shall be removed at the Contractor's expense to the elevation indicated or directed and the foundation trued to an even surface over its entire area.

8. Unsatisfactory material in the foundation shall be removed and replaced with satisfactory material designated by the Engineer. This material shall be placed in layers not exceeding six (6) inches in loose depth and compacted to ninety-five (95) percent of maximum density up to the foundation elevation.
9. Any pumping that may be permitted from the interior of any foundation enclosure shall be done in such a manner as to preclude the possibility of any portion of concrete material being carried away. Any pumping required during the placing of concrete or for a period of at least twenty-four (24) hours thereafter shall be done from a suitable sump located outside the concrete forms.
10. When conditions are encountered which render it impracticable to dewater the foundation before placing the footing the Engineer may permit the construction of a concrete foundation seal of such dimensions as he may consider necessary and of such thickness as to resist any possible uplift. Before pouring the seal the foundation shall be cleaned of all objectionable material by the use of sand pumps, spud bars, or other means which will accomplish the purpose satisfactorily. The seals shall then be constructed in accordance with the provisions in TDOT Standard Specifications Subsection 604.19 and Section 03300 - Cast-In-Place Concrete. Pumping to dewater a sealed cofferdam shall not commence until the seal has set sufficiently to withstand the hydrostatic pressure. The foundation shall then be dewatered and the seal thoroughly cleaned of all laitance and generally prepared for further construction.
11. Measurement and payment for concrete foundation seal will be as provided for under TDOT Standard Specifications Subsections 604.31 and 604.32 and Section 03300 - Cast-In-Place Concrete except as provided for in TDOT Standard Specifications Subsection 204.13 and part 5 below.

B. Pipe Culverts.

Bedding for pipe culverts shall conform to the requirements given below for Class A, B, or C bedding whichever is shown in the plans or in the special provisions. If the class of bedding is not shown Class C bedding shall be placed.

1. Class A bedding for pipe culverts shall consist of a continuous concrete cradle constructed in conformity with the details shown in the plans and the applicable requirements in TDOT Standard Specifications Section 604 and Section 03300 - Cast-In-Place Concrete.
2. Class B bedding shall be constructed by bedding the culvert pipe in a trench cut in natural ground or compacted embankment to a depth as shown in the plans. The pipe shall be bedded on a six (6) inch thickness of Class B material and sufficient additional Class B material accurately shaped by a template to fit the lower part of the pipe exterior for at least ten (10) percent of its overall height. Class B material shall then be rammed and tamped in layers not over six (6) inches in loose thickness around the pipe to a minimum depth of that shown in the plans. The remaining depth of trench shall then be backfilled and compacted as outlined in TDOT

Standard Specifications Subsection 204.11 (b) and paragraph 4.4 below. When bell and spigot pipe is to be placed recesses shall be dug in the bedding material of sufficient width and depth to accommodate the bell without its resting on the bottom of the recess. The width of the recess shall not exceed the width of the bell by more than two (2) inches.

3. Class C bedding shall be constructed by bedding the culvert pipe in a shallow trench cut in natural ground or compacted embankment to a depth of not less than ten (10) percent of the outside vertical pipe diameter and shall be shaped to fit the lower pipe exterior for the specified embedment. When bell and spigot pipe is to be placed recesses shall be dug in the earth foundation of sufficient width and depth to accommodate the bell without its resting on the bottom of the recess. The width of the recess shall not exceed the width of the bell by more than two (2) inches.

4.4 BACKFILLING

All backfill that becomes a part of the roadway prisms or their foundations shall be placed in layers and compacted to ninety-five (95) percent density in accordance with the provisions in TDOT Standard Specifications Section 205 and Section 02210 - Embankments.

A. Bridges, Box Culverts, and Other Major Structures.

1. All areas which have been excavated the volume of which is not occupied by the structure shall be refilled with acceptable earth material to the normal ground surface unless otherwise directed. This backfill shall be accomplished by building up in layers not more than six (6) inches in loose depth for mechanical tamps and ten (10) inches in loose depth for tamping rollers on both sides of the structure or around the structure unit maintaining the layers at equal elevation and thoroughly compacting each layer by tamping with suitable rapid striking power driven mechanical tampers and sheepfoot rollers before the succeeding layer is placed.
2. Granular backfill material for structures Class A, grading D will be placed such that the compacted depth shall not exceed six (6) inches per layer and the density requirements shall be in accordance with TDOT Standard Specifications Section 303 and Section 02500 - Paving and Surfacing.
3. When any part of the structure is to function as a retainer for backfill such as abutments, retaining walls, wing walls, arches, side walls of box culverts, or minor structures the boundary slopes shall be stepped in order to prevent any wedge action.
4. Backfill shall not be placed against a structure or a section or unit thereof until the Work described in TDOT Standard Specifications Subsections 604.20 and 604.22 and Section 03300 - Cast-In-Place Concrete has been performed and representative specimens of the concrete in the structure, section, or unit cured by the methods and in the manner the concrete which the test specimens represent is cured attain a compressive strength of three thousand (3000) pounds per square inch. In addition to the above requirements the concrete shall have been placed a minimum of seven (7)

days not counting the days of twenty-four (24) hours each in which the temperature falls below forty (40) degrees Fahrenheit or twenty-one (21) calendar days whichever occurs first. Backfill behind abutments held at the top by a superstructure and behind the sidewalls of culverts shall be carried up simultaneously behind abutments or sidewalls.

B. Pipe Culverts.

After the bedding has been prepared and the pipe installed the trench shall be backfilled with bedding material and/or fine compactable soil selected from excavation or borrow in accordance with the plans. Prior to backfilling concrete pipe the joints shall be cured in accordance with the provisions in TDOT Standard Specifications Subsection 607.07 and Section 02720 - Storm Sewers and Drain Systems. The material shall be placed along each side of the pipe in layers not over six (6) inches in loose depth. Each layer shall be moistened or dried if necessary to near optimum moisture content and thoroughly compacted with mechanical tampers. Special care shall be taken to compact thoroughly the material under the haunches of the pipe and to insure that the backfill material is in intimate contact with the side of the pipe. The backfill shall be brought up evenly on both sides of the pipe and for the full required length. Except as may be required where the imperfect trench method is prescribed the backfill material shall be placed for the full depth of the trench.

1. When the top of the pipe is above the top of the trench embankment material shall be placed and compacted in layers not more than six (6) inches in loose depth for a width on each side of the pipe equal to at least twice the horizontal inside diameter of the pipe or twelve (12) feet whichever is less. The embankment on each side of the pipe for a distance equal to the horizontal inside diameter of the pipe shall be of the same material and compacted in the same manner as required for backfill in the foregoing paragraph. The remainder of the fill material shall be soil which can be readily compacted and shall contain no frozen lumps, chunks or plastic clay, stones that would be retained on a three (3) inch sieve, or other objectionable material. It shall be compacted as required for backfill or by rolling in accordance with the applicable requirements in TDOT Standard Specifications Section 204 and this Section. The embankment shall be placed evenly on both sides of the pipe for the full width of the roadbed up to an elevation a minimum of one (1) foot above the top of the pipe. Above this elevation and also above the top of a backfilled trench that is one (1) foot or more above the top of the pipe embankment shall be placed in accordance with the applicable requirements in TDOT Standard Specifications Section 205 and Section 02210 - Embankments except those requirements where the imperfect trench method is prescribed.
2. When the imperfect trench method is required by the plans the pipe shall be bedded, the trench backfilled, and the embankment placed as prescribed above to a height above the top of the pipe equal to the vertical outside diameter of the pipe plus one (1) foot. A trench equal in width to the outside horizontal diameter of the pipe shall then be excavated in the newly placed backfill or embankment directly over the pipe keeping the trench walls as nearly vertical as possible and down to an elevation one (1) foot above the top of pipe. The lower one-fourth (1/4) of the trench shall be

backfilled with straw or other highly compressible material and the remainder of the trench backfilled with the excavated trench material deposited in the loosest possible manner. After the trench backfill has been completed the remainder of the embankment shall be constructed by normal methods to the finished grade line.

3. When the material specified in TDOT Standard Specifications Subsection 903.17 and Section 02720 - Storm Sewers and Drain Systems is used for Class B bedding the compaction and density requirements will be waived. The height of the lift may be increased up to a maximum of three (3) feet after the material has been thoroughly forced under the haunches of the pipe.

C. Backfill Material (flowable fill).

1. Flowable fill shall be placed at locations shown in the plans or as directed by the Engineer. The flowable fill shall be covered or otherwise protected while in the plastic state. No embankment or base shall be placed on the flowable fill prior to final set or hardening as determined by the Engineer.
2. Prior to placement of the flowable fill pipe and bedding shall be installed in accordance with the TDOT Standard Specifications and this Section and with details shown in the plans. All sections of pipe shall be securely braced or anchored both horizontally and vertically if necessary to prevent movement of the pipe during placement of the flowable fill. Pipe sections shall be joined so as to prevent the influx of flowable fill around the joints. The Contractor shall replace at his expense any pipe or sections of pipe which do not conform to the above requirements.

PART 5 - MEASUREMENT AND PAYMENT

5.1 METHOD OF MEASUREMENT

- A. Structure excavation will be measured by the cubic yard in its original position only.
- B. Water and its removal will not be measured as it is a necessary part of the Work.
- C. Excavation below foundation elevation as indicated or directed made at the direction of the Engineer will be measured and computed for payment provided the cause which made this extra excavation necessary is not attributable to the Contractor.
- D. No allowance will be made for excavation necessary in connection with the construction of box bridges, box culverts, retaining walls, or minor structures including pipe culverts and sewers unless otherwise indicated in the plans except that undercutting for these structures made at the direction of the Engineer to remove unsuitable foundation material will be classified and paid under item 203-05 undercutting as provided in TDOT Standard Specifications Section 203 and Section 02200 - Earthwork.
- E. When the plans provide for direct payment of excavation necessary in connection with the structures numerated in TDOT Standard Specifications Subsection 204.12

and the preceding subparagraph the excavation including any undercutting made at the direction of the Engineer to remove unsuitable foundation material will be classified and paid as item 204-01 culvert excavation (unclassified) with the following exception: excavation within the limits of box bridges and box culverts with a bottom width between the inner faces of the outside walls greater than fourteen (14) feet that is performed above the flow line of the structure and with a bottom width equal to the distance between the inner faces of the outside walls and then on a one to one (1:1) slope to the normal ground surface will be measured and paid for as item 203-08 channel excavation (unclassified).

- F. Material used to replace approved undercutting for box bridges, box culverts, retaining walls, or minor structures including pipe culverts and sewers will be paid under item 204-08 foundation fill material and the measurement will be the same quantity as the approved undercutting it replaces.
- G. Materials excavated prior to the necessary measurements having been obtained by the Engineer cannot be measured in their original position and therefore will not be computed for payment.
- H. Slides, cave-ins, and excavation extending outside of the workable limits will not be computed for payment.
- I. Material in a foundation which has bulged due to the driving of piles and which must be removed will not be measured or computed for payment.
- J. No excavation above the normal ground surface will be measured for payment unless otherwise shown in the plans.
- K. The normal ground surface as used in TDOT Standard Specifications Section 204 and this Section is defined as the bottom of channel excavations when channel excavation is indicated in the Contract Documents, the template section of the roadway in cuts, or the natural ground surface whichever is at the lower elevation. When it is required that the structure excavation be made in new embankment the normal ground surface shall be the planes of the new embankment at the elevation specified or directed for construction in advance of performing the required structure excavation but in no case shall the normal ground surface be above the planes of the new embankment.
- L. Unless otherwise provided by the plans no separate measurements or payment will be made for the construction and removal of cofferdams, cribs, or other protective measures provided to safeguard an excavation such being considered incidental to the Work. However when items for cofferdams or cribs for individual piers or bents are provided by the plans such will be measured in individual lump sum items for the pier or bent designated.
- M. When the plans indicate that direct payment will be made for excavation for box bridges, box culverts, retaining walls, or minor structures including pipe culverts and sewers the volume of culvert excavation (unclassified) will be determined by measuring the actual quantity excavated between the normal ground surface and the foundation elevation as approved provided the limits of the excavation do not extend beyond the vertical planes located eighteen (18) inches horizontally outside the neat lines of the section of the structure at foundation elevation as indicated or

directed. For box bridges and box culverts without bottom slabs the foundation elevation is considered to be the bottom of footings and the flow line elevation between footings. No allowance will be made for overlapping areas.

- N. Where internal forming is required as for cut off walls, etc., the limits of excavation to be measured for payment will be twelve (12) inches horizontally outside the neat lines of the completed Work and vertically from foundation elevation to the bottom of the completed excavation.
- O. No increase or decrease in payment will be allowed for changes in amount of excavation due to the shifting of locations of structures from that shown in the plans or for the additions of structures to those shown in the plans when the plans do not indicate that direct payment will be made for this excavation. Further if this area of excavation namely eighteen (18) inches horizontally outside of the neat line of the structure at foundation elevation overlaps an area in which the excavation is computed on a separate Contract Unit Bid Price the excavation in the overlapping area will not be allowed.
- P. The volume of culvert excavation (unclassified) for pipe culverts when direct payment for this excavation is indicated in the plans will be determined by measuring the actual quantity excavated between the normal ground surface and the bottom of the excavation for the pipe as approved provided the limits of the excavation do not extend beyond two (2) vertical planes separated by a horizontal distance equal to the outside diameter of the pipe plus three (3) feet.
- Q. Rock required to be removed and the space backfilled in order to prepare a satisfactory bed for pipe culverts will be computed only for a depth of six (6) inches below the bed of the pipe as approved. No allowance shall be made for the material used in backfilling except bedding material when specified.
- R. No allowance will be made for shaping necessary to accommodate the bells of the pipe.
- S. The volume of dry excavation (bridges), wet excavation (bridges), rock excavation (bridges), and bridge excavation (unclassified) will be determined by measuring the actual quantity excavated between the normal ground surface and the bottom of the excavation as approved provided the limits of the excavation do not extend beyond vertical planes located eighteen (18) inches horizontally outside of the neat lines of the section of the structure at foundation elevation or where a concrete seal is used do not extend beyond the neat lines of the concrete seal as specified or directed.
- T. The volume of excavation necessary to form struts, diaphragms, beams, etc., will be determined by measuring the actual volume excavated between the normal ground surface and a plane located twelve (12) inches below the members provided the limits of the excavation do not extend beyond vertical planes located eighteen (18) inches horizontally beyond the limits of the members.
- U. In computing extra depth excavation the working limits established herein will be adhered to.

- V. Rock drilling performed in accordance with TDOT Standard Specifications Subsection 204.10 (a) and this Section will be measured by the linear foot.
- W. The volume of Class A bedding shall be based on the theoretical quantity in cubic yards per foot of pipe as shown on the standard drawings.
- X. The volume of Class B bedding shall be based on the theoretical quantity in cubic yards per foot of pipe as shown on the standard drawings.
- Y. Backfill material (flowable fill) shall be measured by the cubic yard complete in place. Measurement shall be made along the centerline of the pipe for the width of trench shown in the plans. Depth for payment shall be based on field measurements of the actual trench depth prior to placement. The volume of any portion of the pipe enclosed by the flowable fill shall be deducted.

5.2 BASIS OF PAYMENT

- A. Structure excavation and foundation preparation of the various classes will be paid for only on the volume computed as set out in TDOT Standard Specifications Subsection 204.12 and paragraph 5.1 above except that foundation fill material will be paid for by the cubic yard as measured in the hauling vehicles.
- B. Embankment construction, sloping, shaping, dressing, disposal of excess or unsuitable material, final cleanup, etc., will not be paid for directly but the cost of performing the requirements therewith shall be absorbed in the pay items hereinafter provided.
- C. Unless otherwise indicated in the plans no direct payment will be made for foundation preparation and backfill and the costs involved shall be included in the Contract Unit Bid Price for other items of construction.
- D. Material moved prior to securing the necessary measurement; material specified to be moved under TDOT Standard Specifications Section 203 and Section 02200 - Earthwork; slides or cave-ins occurring outside of the working limits stipulated TDOT Standard Specifications Subsections 204.08 and 204.10 and paragraphs 4.1 and 4.3 above; material excavated outside of said working limits; material excavated even though within the said working limits below foundation elevation as indicated or directed and made necessary on account of the construction methods of the Contractor or failure on his part to provide sufficient or proper protection; presplitting of rock; material excavated below foundation when shooting; bulged material caused by driving piles in a foundation; water and its removal; and in general material moved which it would have been unnecessary to move in order to complete the structure in accordance with the plans, TDOT Standard Specifications and this Section, or the directions of the Engineer will not be paid for.
- E. Culvert Excavation (unclassified).

When direct payment is provided by the plans this item will be paid for at the Contract Unit Bid Price per cubic yard for culvert excavation (unclassified) which price shall be full compensation for all structure excavation and foundation preparation classified as culvert excavation (unclassified) performed within the

limits stipulated in TDOT Standard Specifications Subsections 204.08 and 204.10 and paragraphs 4.1 and 4.3 above and which has been performed in accordance with the conditions, stipulations, provisions, and requirements contained therein.

F. Dry Excavation (bridges).

This item will be paid for at the Contract Unit Bid Price per cubic yard for dry excavation (bridges) which price shall be full compensation for all structure excavation and foundation preparation classified as dry excavation (bridges) which has been performed in accordance with the conditions, stipulations, provisions, and requirements contained herein.

G. Wet Excavation (bridges).

This item will be paid for at the Contract Unit Bid Price per cubic yard for wet excavation (bridges) which price shall be full compensation for all structure excavation and foundation preparation classified as wet excavation (bridges) which has been performed in accordance with the conditions, stipulations, provisions, and requirements contained herein.

H. Rock Excavation (bridges).

This item will be paid for at the Contract Unit Bid Price per cubic yard for rock excavation (bridges) which price shall be full compensation for all structure excavation and foundation preparation classified as rock excavation (bridges) and which has been performed in accordance with the conditions, stipulations, provisions, and requirements contained herein.

I. Bridge Excavation (unclassified).

This item will be paid for at the Contract Unit Bid Price per cubic yard for bridge excavation (unclassified) which price shall be full compensation for all structure excavation and foundation preparation which has been performed in accordance with the conditions, stipulations, provisions, and requirements contained herein.

J. Extra Depth Structure Excavation and Foundation Preparation.

Extra depth structure excavation and foundation preparation classified as culvert excavation (unclassified) made necessary by the Engineer establishing the foundation below the elevation indicated in the plans will be paid for at the Contract Unit Bid Price per cubic yard for culvert excavation (unclassified) and this price shall be accepted by the Contractor as full compensation for performing this extra depth structure excavation and foundation preparation in accordance with the conditions, stipulations, provisions, and requirements set out in TDOT Standard Specifications and this Section for structure excavation and foundation preparation of this class.

1. Extra depth structure excavation and foundation preparation for bridges made necessary by the Engineer requiring excavation below the foundation elevation indicated in the plans will be paid for on a basis of the Contract Unit Bid Price per cubic yard for dry excavation (bridges), wet excavation (bridges), or rock excavation (bridges) as classified for the actual quantity

in cubic yards excavated from the designated zone this zone being between the elevation shown in the plans and the final approved elevation as directed by the Engineer plus the additional percentages for each zone corresponding to the depths lowered below plan elevation as set out in the following schedule:

<u>Sub-Item Designation</u>	<u>Depth Lowered Below Plan Elevation</u>				<u>Additional Percent</u>
	<u>Zone No.</u>	<u>More Than</u>	<u>Not Over</u>		
None	0	0 feet	4 feet		0.0
a	1	4 feet	8 feet		50.0
b	2	8 feet			80.0

2. In the above table the depths to be used for computing the volumes of material for payment under any sub-item will be the depths applicable to each zone between the foundation elevation as indicated in the plans and the final foundation elevation as approved by the Engineer for example: if the foundation has been lowered seven and one-half (7 1/2) feet below the foundation elevation as indicated in the plans the volume for the sub-item shall be computed for a depth of three and one-half (3 1/2) feet and multiplied by the Contract Unit Bid Price for the class of material excavated plus fifty (50) percent. The volume of material down to a level four (4) feet below the foundation elevation as indicated in the plans shall be paid for at the Contract Unit Bid Price for the class of material excavated.
3. The Contract Unit Bid Price for the class of material excavated plus the additional percentage shown in TDOT Standard Specifications Subsection 204.13 and above provided shall be accepted by the Contractor as full compensation for performing extra depth structure excavation and foundation preparation classified as dry excavation (bridges), wet excavation (bridges), or rock excavation (bridges) in accordance with the conditions, stipulations, provisions, and requirements set out in TDOT Standard Specifications and this Section for structure excavation and foundation preparation of the respective classes.

K. Rock Drilling (bridges).

This item will be paid for at the Contract Unit Bid Price per linear foot for rock drilling (bridges).

L. Concrete for Class A Bedding.

Concrete for Class A bedding will be paid for at the Contract Unit Bid Price per cubic yard for bedding material (pipe) Class A complete in place.

M. Material for Class B Bedding.

Material for Class B bedding will be paid for at the Contract Unit Bid Price per cubic yard for bedding material (pipe) Class B complete in place.

N. Cofferdams or Cribs.

When items for cofferdams or cribs have been provided for and installed for a designated pier or bent the lump sum item shall be full compensation for the furnishing and installation of all material, maintenance, removal, satisfactory clean up of the area, and for all tools, equipment, labor, and incidentals necessary to complete the Work. Concrete seals shall also be included except when otherwise noted in the plans.

O. Foundation Preparation.

When the plans indicate that direct payment will be made for foundation preparation the lump sum item shall be full compensation for the preparation of foundations for all substructures. The cost of cofferdams, shoring, pumping, or seal concrete unless otherwise noted shall be incidental to the lump sum bid for foundation preparation. Excavation required for the foundation preparation shall be paid as defined by TDOT Standard Specifications and this Section except that no percent increase will be allowed for extra depth excavation.

P. Backfill Material (flowable fill).

Accepted quantities of backfill material (flowable fill) shall be paid for at the Contract Unit Bid Price per cubic yard which shall be full compensation for all materials, mixing, transporting, placing, and finishing of the flowable fill as well as all labor, tools, equipment, and other incidentals necessary for the satisfactory completion of the Work. No measurement and payment will be made for material placed outside the neat line limits or outside the adjusted limits or for unused or wasted material.

END OF SECTION - 02225

SECTION 02520
CEMENT CONCRETE CURB, GUTTER, AND COMBINED CURB AND GUTTER

PART 1 - GENERAL

1.1 DESCRIPTION OF WORK

This Work shall consist of curb, gutter, or combined curb and gutter constructed of portland cement concrete in accordance with TDOT Standard Specifications Section 702 and this Section at the locations and in reasonably close conformity with the lines, grades, and dimensions shown on the plans or established by the Engineer.

1.2 RELATED WORK SPECIFIED ELSEWHERE

Section 01580 - Traffic Signals
Section 01710 - Cleanup and Restoration
Section 02200 - Earthwork
Section 02210 - Embankments
Section 02500 - Paving and Surfacing
Section 02522 - Cement Concrete Sidewalks, Driveways, and Median Pavement
Section 03300 - Cast-In-Place Concrete

1.3 APPLICABLE SPECIFICATIONS

"STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", Latest Revision, Tennessee Department of Transportation (TDOT)

"SUBDIVISION SPECIFICATIONS FOR STREETS AND ROADS", Latest Revision, Metropolitan Government of Nashville and Davidson County

1.4 APPLICABLE REFERENCES

"American Association of State Highway and Transportation Officials" (AASHTO), Latest Revision

"American Society for Testing and Materials" (ASTM), Latest Revision

"American Concrete Institute" (ACI), Latest Revision

"Americans with Disabilities Act" (ADA), Latest Revision

"Americans with Disabilities Act Accessibility Guidelines" (ADAAG), Latest Revision

"Architectural Barriers Act" (ABA), Latest Revision

PART 2 - MATERIALS

2.1 GENERAL REQUIREMENTS

Materials shall meet the applicable requirements in TDOT Standard Specifications Sections 604 and 913 and in Section 03300 - Cast-In-Place Concrete together with the conditions and requirements set forth in this Section.

2.2 PREFORMED JOINT FILLER

Prefomed joint filler shall conform to the requirements in TDOT Standard Specifications Subsection 905.01 and in Section 03300 - Cast-In-Place Concrete unless otherwise specified in the plans.

2.3 DRAIN PIPE

This pipe shall conform to AASHTO M 178 or AASHTO M 179 for the specified material and diameters. Unless otherwise specified the pipe shall be of standard quality class. When specified the pipe spigot shall have integral spacer lugs to provide for an annular opening and self centering feature.

2.4 CONCRETE

Concrete for curb, gutter, and combined curb and gutter shall be Class A concrete meeting all the requirements prescribed in TDOT Standard Specifications Section 604 and in Section 03300 - Cast-In-Place Concrete with the following modifications:

- A. When the use of a curb machine is authorized the Contractor may request a concrete design based on the following:

<u>Water</u>	<u>Cement</u>	<u>Combined Coarse and Fine Aggregate</u>
4 gallons (maximum) coarse aggregate fine aggregate	94 lbs.	505 lbs. size nos. 7, 57, 67, or 78 45% to 60%

- B. Entrained air will not be required in curb concrete made with the above combination.
- C. The water and percentages of fine and coarse aggregate may be adjusted within the above limits to permit satisfactory placement.
- D. Compressive test specimens may be made by the vibratory method in accordance with AASHTO T 23 or other approved methods.

PART 3 - EQUIPMENT

- A. Forms except the templates between ten (10) foot sections may be either wood or metal meeting the requirements prescribed in TDOT Standard Specifications Subsection 701.03. The templates shall be one-eighth (1/8) inch thick metal of the same width as that of the curb, gutter, or combination curb and gutter and not less than one-quarter (1/4) inch more in depth than the respective depth of the type curb and gutter being constructed. The templates shall have lugs or other devices to hold them in position during placing of the concrete and shall be of such design as to permit removal without causing damage to the concrete. For gutters a strike off template of the form and shape of the gutter shall be used to shape the top surface of the gutter.

- B. Compaction of subgrade shall be accomplished by any type of tamping or rolling equipment that will produce the desired results.
- C. Mixers shall meet the requirements in TDOT Standard Specifications Subsection 604.12 and in Section 03300 - Cast-In-Place Concrete. A curb machine that will place the concrete in a satisfactory manner may be used when approved by the Engineer. Finishing equipment shall include satisfactory floats, edgers, spades, and tamps.

PART 4 - EXECUTION

4.1 GENERAL

Curb, gutter, or combined curb and gutter shall meet all the applicable requirements of the ADA, ADAAG, and ABA. The normal gutter slope of 1:12 (vertical:horizontal) shall be reduced to 1:20 (vertical:horizontal) at combination curb ramps (Metro Standard Drawings ST-301 and ST-302).

4.2 PRELIMINARY WORK

Clearing and grubbing, removal of structures and obstructions, excavation and undercutting, and embankment construction shall be performed in accordance with the provisions in TDOT Standard Specifications Sections 201, 202, 203, and 205 and in Section 02100 - Site Preparation, Section 02200 - Earthwork, Section 02210 - Embankments, and Section 02225 - Earthwork for Structures and Pipes respectively.

4.3 SUBGRADE PREPARATION

Subgrade preparation for curb, gutter, and combined curb and gutter shall be made to the required depth and to a width that will permit the installation and bracing of the forms. The subgrade shall be shaped and compacted to a firm even surface in reasonably close conformity with the grade and section shown in the plans. All soft and yielding material shall be removed and replaced with acceptable material which shall then be compacted as directed.

4.4 EXPANSION JOINTS

Expansion joints shall be formed at the intervals and locations shown in the plans using preformed filler three-quarters (3/4) inch thick unless otherwise specified. They shall be placed in line with corresponding expansion joints in adjoining pavement or other construction. Joint filler shall be cut to the full cross section of the curb, gutter, or curb and gutter.

4.5 LIMITATIONS OF MIXING

Limitations on the mixing of concrete shall be as prescribed in TDOT Standard Specifications Subsection 501.11 and in Section 03300 - Cast-In-Place Concrete.

4.6 MIXING, PLACING, AND FINISHING CONCRETE

Concrete shall be mixed in accordance with the requirements in TDOT Standard Specifications Subsection 604.14 and in Section 03300 - Cast-In-Place Concrete.

- A. Immediately before placing the concrete the subgrade shall be thoroughly wetted and the forms given a coating of light oil. The forms shall be thoroughly cleaned and oiled each time before using. Placing concrete shall be performed as provided for in TDOT Standard Specifications Subsection 501.12 except that the mechanical spreader will not be required.
- B. The concrete shall be placed immediately after mixing. The edges, sides, or faces shall be thoroughly spaded and vibrated sufficiently to consolidate the concrete thoroughly and bring the mortar to the surface after which the surface shall be finished smooth and even by means of a wooden float.
- C. Concrete curb, gutter, and combined curb and gutter shall be constructed reasonably true to line, grade, and cross section and unless otherwise specified in the plans in sections having uniform lengths of ten (10) feet. The length of these sections may be reduced where necessary for closures but no section less than six (6) feet will be permitted. The templates shall be set carefully before the placing of the concrete and allowed to remain in place until the concrete has set sufficiently to hold its shape but shall be removed while the forms are still in place. The forms on the face of all curbs shall be removed as soon as the concrete will hold its shape and the surface then floated with a wooden float to a smooth and even finish. No plastering will be permitted. Unless otherwise specified the top edges of the curb and the edge of the gutter shall be rounded to the radius as shown on the standard drawings and the edges on each side of templates and expansion joint material shall be finished with an edging tool with a radius of not over one-quarter (1/4) inch and then all lines or marks shall be removed with a wet brush. The back of curbs shall be finished not less than three (3) inches below the top of backfill against the curb. Any exposed surface or surfaces against which some rigid type of construction is to be made shall be left smooth and uniform so as to permit free movement of the curb, gutter, or combined curb and gutter.
- D. All tool marks shall be removed with a wetted brush or wooden float and the finished surface shall present a uniform and pleasing appearance.
- E. When the use of curb machines is permitted finishing shall be performed as specified above except that contraction joints may be sawed a minimum depth of one-quarter (1/4) the thickness of the section at intervals not less than six (6) feet nor more than ten (10) feet in lieu of constructing the curbs in sections.
- F. Weep holes or drainage openings shall be placed through curbs as indicated in the plans or as directed by the Engineer and coarse aggregate shall be placed behind each opening as needed.

4.7 PROTECTION AND CURING

- A. Immediately after finishing the concrete protection and curing shall be performed in accordance with the provisions in TDOT Standard Specifications Subsection 501.18.
- B. The Contractor shall protect the curb, gutter, and combined curb and gutter until finally accepted. Any concrete that is damaged during that period shall be repaired by removing and reconstructing each ten (10) foot section that has been damaged. This reconstruction shall be at the Contractor's expense.

4.8 BACKFILLING

Immediately after the concrete has set sufficiently and the forms have been removed the space back of the curb or combined curb and gutter shall be filled with suitable material. This material shall be placed in layers not exceeding four (4) inches in loose thickness and compacted until firm and stable.

4.9 FINAL CLEANUP

Final cleanup shall be performed in accordance with the requirements in TDOT Standard Specifications Subsection 104.11 and in Section 01710 - Cleanup and Restoration.

PART 5 - MEASUREMENT AND PAYMENT

5.1 METHOD OF MEASUREMENT

- A. Concrete curb, concrete gutter, and concrete combined curb and gutter will be measured for payment by the cubic yard complete in place. The volume per linear foot of length shall be obtained from the dimensions shown in the plans. Linear measurements will be surface measurements taken along the center of gravity of the section.
- B. No measurement will be made for preparing the subgrade, for backfill, for expansion joint materials, or drain pipe unless otherwise indicated in the plans.
- C. No measurement for payment will be made for curb integral with concrete pavement or concrete base unless otherwise specified in the plans or in this CONTRACT.

5.2 BASIS OF PAYMENT

The accepted quantities of concrete curb, concrete gutter, or concrete combined curb and gutter will be paid for at the Contract Unit Bid Price per cubic yard for the respective items.

END OF SECTION - 02520

SECTION 02522
CEMENT CONCRETE SIDEWALKS, DRIVEWAYS, AND MEDIAN PAVEMENT

PART 1 - GENERAL

1.1 DESCRIPTION OF WORK

This Work shall consist of constructing sidewalks, driveways, and median pavement exclusive of sidewalks, driveways, and median pavement that are integrally part of structures of portland cement concrete on a prepared subgrade in accordance with TDOT Standard Specifications Section 701 and this Section and in reasonably close conformity with the lines, grades, and typical cross sections shown in the plans or established by the Engineer.

1.2 RELATED WORK SPECIFIED ELSEWHERE

Section 01580 - Traffic Signals
Section 01710 - Cleanup and Restoration
Section 02200 - Earthwork
Section 02210 - Embankments
Section 02500 - Paving and Surfacing
Section 02520 - Cement Concrete Curb, Gutter, and Combined Curb and Gutter
Section 03300 - Cast-In-Place Concrete

1.3 APPLICABLE SPECIFICATIONS

"STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", Latest Revision, Tennessee Department of Transportation (TDOT)

"SUBDIVISION SPECIFICATIONS FOR STREETS AND ROADS", Latest Revision, Metropolitan Government of Nashville and Davidson County

1.4 APPLICABLE REFERENCES

"American Association of State Highway and Transportation Officials" (AASHTO), Latest Revision

"American Society for Testing and Materials" (ASTM), Latest Revision

"American Concrete Institute" (ACI), Latest Revision

"Americans with Disabilities Act" (ADA), Latest Revision

"Americans with Disabilities Act Accessibility Guidelines" (ADAAG), Latest Revision

"Architectural Barriers Act" (ABA), Latest Revision

PART 2 - MATERIALS

2.1 GENERAL REQUIREMENTS

Materials shall meet the requirements in TDOT Standard Specifications Sections 604 and 913 and in Section 03300 - Cast-In-Place Concrete together with the conditions and requirements set forth in this Section.

2.2 PREFORMED JOINT FILLER

Prefomed joint filler shall conform to the requirements in TDOT Standard Specifications Subsection 905.01 and in Section 03300 - Cast-In-Place Concrete. Joint filler for brick sidewalk shall be portland cement with prepared color added conforming to ASTM C 150. Sand shall conform to ASTM C 144.

2.3 DRAIN PIPE

Drain pipe shall conform to the requirements in TDOT Standard Specifications Subsection 914.04 and in Section 02520 - Cement Concrete Curb, Gutter, and Combined Curb and Gutter unless otherwise specified in the plans.

2.4 CONCRETE

Concrete for sidewalks, driveways, and median pavement shall be Class A concrete meeting all the requirements prescribed in TDOT Standard Specifications Section 604 and in Section 03300 - Cast-In-Place Concrete.

2.5 BRICK

Brick when made from clay or shale shall conform to ASTM 902 including BX for dimensional tolerance. When made of concrete they shall conform to ASTM C 55. The kind and grade shall be as specified in the plans. Brick shall be full depth two and one-quarter (2 1/4) inches thick and shall be four inches by eight inches (4" x 8") in area unless otherwise shown in the plans or directed by the Engineer. Contractor shall submit sample for approval.

2.6 ASPHALT

Setting bed for brick sidewalk shall be a three-quarter (3/4) nominal inch deep binder mix and binder base shall be a four (4) inch deep binder mix both conforming to the applicable requirements in TDOT Standard Specifications Sections 307 and 407 and in Section 02500 - Paving and Surfacing. Contractor shall determine the exact proportions to produce the best possible mixture for construction of the bituminous setting bed and binder base to meet construction requirements and shall submit design mix to the Engineer for approval.

2.7 NEOPRENE MODIFIED ASPHALT ADHESIVE

Neoprene modified asphalt adhesive under brick shall conform to the following specifications "or equal":

mastic (asphalt adhesive)	
solids (base)	75% ± 1%
pounds/gallon	8 lbs. - 8.5 lbs.
solvent mineral spirits (over 100° Fahrenheit flash)	
base (2% neoprene, 10% asbestos-free fibers, 88% asphalt)	
melting point - ASTM D 36	150° Fahrenheit mix
penetration - 77° Fahrenheit 100 gram load 5 sec.	23 - 27
ductility - ASTM D 113-44 at 77° Fahrenheit	
2 inches/min.	39 - 49 inches/min.

2.8 MORTAR

Cement and sand used for preparation of mortar shall conform to the requirements in TDOT Standard Specifications Section 607 and in Section 02720 - Storm Sewers and Drain Systems.

PART 3 - EQUIPMENT

- A. Forms shall be of wood, metal, or other suitable material and shall extend for the full depth of the concrete. All forms shall be true to line, free from warp, and of sufficient strength to resist the pressure of the concrete without springing. Curved forms of proper radius shall be used on all radial sections and shall be of a design acceptable to the Engineer. Bracing and staking of forms shall be such that the forms remain in both horizontal and vertical alignment until their removal.
- B. Mixers shall meet the requirements in TDOT Standard Specifications Subsection 604.12 and in Section 03300 - Cast-In-Place Concrete.
- C. Satisfactory floats, templates, straightedges, edgers, spades, and tamps shall be furnished. Compaction of subgrade shall be accomplished by any type of tamping or rolling equipment that will produce the desired results.
- D. A slip form paver which is capable of producing the required results may be used in lieu of forms.

PART 4 - EXECUTION

4.1 PRELIMINARY WORK

Clearing and grubbing, removal of structures and obstructions, excavation and undercutting, and embankment construction shall be performed in accordance with the provisions in TDOT Standard Specifications Sections 201, 202, 203, and 205 and in Section 02100 - Site Preparation, Section 02200 - Earthwork, Section 02210 - Embankments, and Section 02225 - Earthwork for Structures and Pipelines respectively.

4.2 SUBGRADE PREPARATION

Subgrade preparation for sidewalks, driveways, and median pavement shall be made to the required depth and to a width that will permit the installation and bracing of the forms. The subgrade shall be shaped and compacted to a firm even surface in reasonably close conformity with the grade and cross section shown in the plans. All soft and yielding

material shall be removed and replaced with acceptable material which shall then be compacted as directed.

4.3 EXPANSION JOINTS

- A. Unless otherwise indicated in the plans or directed by the Engineer premolded expansion joint filler one-half (1/2) inch in thickness shall be placed at locations and in line with expansion joints in the adjoining pavement, gutter, or curb. All premolded expansion joint filler shall be cut to full width or length of the proposed construction and shall extend to within one-half (1/2) inch of the top or finished surface. All longitudinal expansion joints shall be placed as indicated in the plans or as directed by the Engineer. All expansion joints shall be true, even, and present a satisfactory appearance.
- B. Construction joints shall be formed around all appurtenances such as manholes, utility poles, etc., extending into and through the sidewalk or median area. Premolded expansion joint filler one-half (1/2) inch thick shall be installed in these joints. Expansion joint filler of the thickness indicated shall be installed between concrete sidewalks and any fixed structure such as a building or bridge. One-half (1/2) inch thick expansion joint filler shall be installed between concrete curb and median pavement and unless otherwise specified between concrete curb and sidewalk. This expansion joint material shall extend for the full depth of the walk or median pavement.

4.4 LIMITATIONS OF MIXING

Limitations on the mixing of concrete shall be as prescribed in TDOT Standard Specifications Subsection 501.11 and in Section 03300 - Cast-In-Place Concrete.

4.5 MIXING AND PLACING CONCRETE

- A. Concrete shall be mixed in accordance with the provisions in TDOT Standard Specifications Subsection 604.14 and in Section 03300 - Cast-In-Place Concrete. Placing concrete shall be performed as provided for in TDOT Standard Specifications Subsection 501.12 except that mechanical spreaders will not be required. Immediately before placing the concrete the subgrade shall be thoroughly wetted and the forms given a coating of light oil. The forms shall be thoroughly cleaned and oiled each time before using.
- B. Concrete sidewalks, driveways, and medians shall be constructed to the dimensions and finished elevations as specified in the plans.
- C. Sidewalks shall be constructed with materials which produce one of the following results:
 - 1. standard portland cement concrete (white concrete) with a coarse broomed finish.
 - 2. portland cement concrete containing river gravel to produce an exposed aggregate finish.
 - 3. brick sidewalk.

- D. Joints shall be constructed at intervals of twenty-five (25) feet to thirty (30) feet except for closures but no interval less than six (6) feet will be permitted.
- E. A four (4) feet wide grass area furnishing zone adjacent to curb shall be provided for placement of light standards, poles, fire hydrants, mailboxes, etc.
- F. A minimum three (3) feet wide clearance shall be provided through the path of travel.
- G. Where a grass area furnishing zone is not provided a maximum two (2) feet wide furnishing zone adjacent to curb shall be provided maintaining a minimum three (3) feet clearance through the path of travel.
- H. Place premolded expansion joints, longitudinal expansion joints, and construction joints in accordance with the requirements in paragraph 4.3 above.
- I. Ramps (curb and driveway) shall be constructed to the dimensions and finished elevations as specified in the plans or Contract Documents and shall also conform to the requirements of the ADA, ADAAG, and ABA. Surface of ramp shall be stable, firm, and slip resistant. Surface texture of ramp shall be that obtained by a coarse brooming transverse to the slope of the ramp. Ramps shall not be constructed using brick or an exposed aggregate concrete finish and shall not contain longitudinal or transverse expansion joints or groves.
- J. Where existing sidewalks, ramps, islands, or medians are to be removed for replacement or to permit other construction the limits of construction shall be considered as extending to the next existing joint marking beyond the normal limits of replacement and/or other construction.
- K. Where sidewalks, islands, or medians are constructed adjacent to permanent structures or other rigid construction on one (1) side and curb on the other extend expansion joint of premolded material only along back at curb and place for the full depth of the slab. Place a premolded expansion joint between the sidewalk and adjacent curb at all crosswalks both public and private. Fasten premolded expansion joint filler to prevent displacement.
- L. Where sidewalk is constructed in conjunction with adjacent curb the expansion joints in the curb and sidewalk shall coincide. Where such construction is adjacent to existing curb the expansion joints shall if practicable coincide. Prior to placing concrete around any permanent structure place premolded expansion joint material around such structure for the full depth of the sidewalk.
- M. Where existing structures such as light standards, poles, fire hydrants, etc., are within the limits of the sidewalk area place premolded expansion joint around the structure for the full depth of the concrete.

4.6 FINISHING

The concrete shall be struck off with a transverse template resting upon the side forms. After the concrete has been struck off to the required cross section it shall be finished with floats and straightedges until the required surface requirements have been obtained.

- A. When the surface of the concrete is free from water and just before the concrete obtains its initial set it shall be finished and swept lightly with a broom in order to produce a sandy texture. The longitudinal surface variations shall be not more than one-quarter (1/4) inch under a twelve (12) foot straightedge nor more than one-eighth (1/8) inch on a five (5) foot transverse section. The surface of the concrete shall be so finished as to drain completely at all times.
- B. The edges of the sidewalks, driveways, and median pavement shall be carefully finished and rounded with an edging tool having a radius of one-half (1/2) inch.
- C. The surface of sidewalks shall be divided into blocks by the use of a grooving tool. The grooves shall be spaced approximately five (5) feet apart and the blocks shall be rectangular unless otherwise ordered by the Engineer. The grooves shall be cut to a depth of not less than one (1) inch. The edges of the grooves shall be edged with an edging tool having a radius of one-quarter (1/4) inch. Grooves shall be placed in median pavement in line with corresponding joints in adjoining construction or as directed by the Engineer.
- D. Unless otherwise indicated in the plans marks or grooves may be placed at right angles to the center line of driveways and approximately eight (8) inches apart. These markings shall be between one-eighth (1/8) inch to one-quarter (1/4) inch in depth and shall be made with a suitable marking tool. A grooving tool six (6) inches to eight (8) inches in width with multiple grooves for grooving alternate strips eight (8) inches apart may be used. Any irregularities caused by the edges of the marking tool shall be removed by the use of a wetter brush or wooden float. All marking edges shall be rounded satisfactorily.
- E. Grooves shall not be placed in the surface of sidewalks or driveways reinforced for beam action where the full thickness of concrete is required for strength.
- F. The edges of the concrete at expansion joints shall be rounded with an edging tool having a radius of one-quarter (1/4) inch. All marks caused by edging shall be removed with a wetted brush or wooden float. The top and ends of expansion joint material shall be cleaned of all concrete and the expansion joint material shall be so trimmed as to be slightly below the surface of the concrete.

4.7 PROTECTION AND CURING

Forms may be removed at any time that removal will not damage the concrete. No pressure shall be exerted upon the concrete in removing forms.

- A. Curing and protection during cold weather shall be performed as provided for in TDOT Standard Specifications Subsection 501.18.
- B. Pedestrians will not be allowed upon concrete sidewalks, driveways, or medians until twelve (12) hours after finishing concrete and no vehicles or loads shall be permitted on any sidewalk, driveway, or median until the Engineer has determined that the concrete has attained sufficient strength for such loads. An accessible alternative route(s) meeting the requirements of the ADA and approval of the Engineer shall be provided by the Contractor.

- C. The Contractor shall construct and place such barricades and protection devices as are necessary to keep pedestrians and other traffic off the sidewalk, driveway, or median. An accessible alternative route(s) meeting the requirements of the ADA and approval of the Engineer shall be provided by the Contractor.
- D. Any sidewalk, driveway, or paved median damaged prior to final acceptance of the project shall be repaired at the Contractor's expense by removing concrete within groove limits and replacing it with concrete of the type and finish in the original construction.

4.8 BACKFILLING

Immediately after removing the side forms the spaces along the edges of sidewalk or driveway shall be filled with suitable material. This material shall be placed in layers not exceeding four (4) inches in loose thickness and compacted until firm and stable.

4.9 BRICK SIDEWALK (GENERAL)

- A. Before beginning work on brick sidewalk all necessary clearing and grubbing, removal of structures and obstructions, excavation and undercutting, and embankment construction shall be performed in accordance with the provisions in TDOT Standard Specifications Sections 201, 202, 203, and 205 and in Section 02100 - Site Preparation, Section 02200 - Earthwork, Section 02210 - Embankments, and Section 02225 - Earthwork for Structures and Pipelines.
- B. Subgrade preparation for brick sidewalks shall be done in accordance with the provisions in paragraph 4.2 above. The foundation for this type of construction shall present a uniform bearing surface and if a reinforced foundation is necessary it shall be constructed of Class A concrete in accordance with the applicable provisions and requirements set out in TDOT Standard Specifications Section 604 and in Section 03300 - Cast-In-Place Concrete.
- C. Brick sidewalk shall not be constructed in freezing weather nor when bricks contain frost.
- D. Brick for exposed surfaces, corners, etc., shall be selected from approved brick as to color and uniformity.
- E. All brick shall be thoroughly cleaned and well moistened with water immediately before being laid and the bed which is to receive the brick shall be thoroughly cleaned and well moistened with water before placing thereon.
- F. All brick laid in freshly made mortar shall be laid in a substantial and workmanlike manner and true to the lines and grades indicated in the plans or as directed by the Engineer.
- G. Care shall be taken to keep the exposed surface of brick free from mortar stains. Immediately after laying brick face shall be cleaned thoroughly of all mortar stains.
- H. In case any brick is moved, has settled, or the joints broken after laying the brick shall be taken up, the mortar thoroughly cleaned from the brick, bed, and joints, and the brick re-laid in fresh mortar.

- I. When brick is to be laid in sand it shall be laid with sand swept butt joints on a one-half (1/2) inch sand setting bed.
- J. When brick is to be laid on concrete the concrete shall be a solid four (4) inch thick slab with 6-6-10-10- welded wire mesh reinforcing (if shown in plans or directed by Engineer). Punch holes for concrete slab shall be one (1) inch in diameter at twelve (12) inches center to center spacing each way.
- K. Prime concrete base with emulsified asphalt (RS-1 or CRS-1) if there is to be vehicular traffic over brick.
- L. After the modified asphalt adhesive is applied (if called for to be used in the plans or directed by the Engineer) carefully place brick by hand in straight courses with hand tight joints and uniform top surface. Good alignment shall be kept and the pattern shall be that shown in the plans or directed by the Engineer.
- M. New brick and mortar shall match existing brick and mortar in color and size where integrating with existing sidewalks. Contractor shall submit samples of all brick to Engineer for approval.
- N. Brick sidewalk shall be protected and kept wet for a period of forty-eight (48) hours after laying brick.

4.10 PLACING BITUMINOUS SETTING BED FOR BRICK

To install the setting bed over the asphalt binder or concrete base surface place control bars directly over the base. The depth control bars shall be set carefully to bring the brick when laid to proper grade. Thickness of the finished setting bed shall be no more than one (1) inch or less than one-half (1/2) inch.

- A. The setting bed shall be rolled with a power roller to a nominal depth of three-quarter (3/4) inch. The thickness shall be adjusted so that when the brick is placed the top surface of the brick shall be at the required finished grade. However under no circumstances shall the setting bed exceed one (1) inch.
- B. A coating of two (2) percent neoprene modified asphalt adhesive shall be applied by squeegeeing or troweling over the top surface of the bituminous setting bed so as to provide a bond under the brick.
- C. After the modified asphalt adhesive is applied (if called for to be used in the plans or directed by the Engineer) carefully place the pavers by hand in straight courses with hand tight joints and uniform top surface. Good alignment shall be kept and the pattern shall be that shown in the plans or as directed by the Engineer.
- D. Hand tight joints shall read from zero (0) inches to maximum one-quarter (1/4) inch for brick. Sweep a dry mixture of one (1) part portland cement to match color of brick and three (3) parts sand until joints are flush with top surface. Fog lightly with water. Joints may recede up to one-eighth (1/8) inch. Cement stains that remain should be cleaned. Screenings or other suitable fillers are also acceptable.
- E. Prime concrete or asphalt binder base with emulsified asphalt (RS-1 or CRS-1) if there is to be vehicular traffic over brick.

4.11 FINAL CLEANUP

Final cleanup shall be performed in accordance with the requirements in TDOT Standard Specifications Subsection 104.11 and in Section 01710 - Cleanup and Restoration.

PART 5 - MEASUREMENT AND PAYMENT

5.1 METHOD OF MEASUREMENT

- A. Sidewalks and driveways will be measured by the square foot complete in place. The area shall be obtained by surface measurements. Where standard widths are constructed the measurements shall not exceed the standard widths shown in the plans unless on written direction of the Engineer. Sidewalks of each thickness and driveways will be measured separately. Concreted median pavement will be measured by the cubic yard complete in place. The volume shall be obtained from the specified thickness shown in the plans and surface measurements for width and length.
- B. No measurement for payment will be made for preparing the subgrade, for backfill, expansion joint materials, or drain pipe unless otherwise indicated in the plans as these are necessary parts of the construction.

5.2 BASIS OF PAYMENT

The accepted quantities of sidewalk of each thickness and driveway will be paid for at the Contract Unit Bid Price per square foot for the respective items complete in place. The accepted quantities of concrete median pavement will be paid for at the Contract Unit Bid Price per cubic yard complete in place.

END OF SECTION - 02522

SECTION 02523
Detectable Warnings

PART 1 - GENERAL

1.1 DESCRIPTION OF WORK

This Work shall consist of installing detectable warnings by surface application or by cast in place on a prepared surface in accordance with TDOT Standard Specifications Section 701 and this Section and in reasonably close conformity with the lines and grades shown in the plans or established by the Engineer.

1.2 RELATED WORK SPECIFIED ELSEWHERE

Section 01710 - Cleanup and Restoration
Section 02520 - Cement Concrete Curb, Gutter, and Combined Curb and Gutter
Section 02522 - Concrete Walks, Driveways, and Ramps

1.3 APPLICABLE SPECIFICATIONS

"STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", Latest Revision, Tennessee Department of Transportation (TDOT)

"SUBDIVISION SPECIFICATIONS FOR STREETS AND ROADS", Latest Revision, Metropolitan Government of Nashville and Davidson County

1.4 APPLICABLE REFERENCES

"American Association of State Highway and Transportation Officials" (AASHTO), Latest Revision

"Americans with Disabilities Act" (ADA), Latest Revision

"Americans with Disabilities Act Accessibility Guidelines" (ADAAG), Latest Revision

"Architectural Barriers Act" (ABA), Latest Revision

"Draft Public Rights-of-Way Accessibility Guidelines", June 17, 2002, ADAAG

Public Works policy and procedure for detectable warnings installation, Latest Revision

1.5 APPROVED LIST

<u>Company</u>	<u>Product</u>
Flint Trading, Inc. 115 Todd Court P.O. Box 160 Thomasville, NC 27361-0160 336-475-6600	Top Mark Preformed Thermoplastic Detectable Warning for surface applied construction.

<u>Company</u>	<u>Product</u>
Engineering Plastics, Inc. 300 International Drive Suite 100 Williamsville, NY 14221 916-549-9700	Armor-Tile Detectable Warning Strips for cast-in place and surface applied construction.
Detectable Warning Systems, Inc. 6435 Joshua Tree Avenue Orange, CA 92867 866-999-7452	E-Z Set Warning Panels for cast-in-place construction
Transpo Industries, Inc. 20 Jones Street Rochelle, NY 10801 914-636-1000	Step-Safe Precast Polymer Concrete Tactile Dome Safety Tile for cast-in-place construction
ADA Solutions, Inc. 10 Elizabeth Drive - Unit 5 Chelmsford MA 01824 800-372-0519 978-262-9125 (fax) http://www.adatile.com	Detectable Warning Strips for cast-in place and surface applied construction.

Or approved equal

PART 2 - MATERIALS

2.1 GENERAL REQUIREMENTS

Layout of the detectable warnings shall meet the requirements in the "Draft Public Rights-of-Way Accessibility Guidelines", June 17, 2002, ADAAG.

2.2 MATERIAL

The material used for the detectable warnings shall be an integral part of the walking surface and shall contrast visually with adjoining surfaces. The materials for the detectable warnings shall meet the manufacturer's requirements of section 1.5.

2.3 DOMES SIZE AND DIMENSIONS

- A. Size. The truncated domes in a detectable warning surface shall have a base diameter of 0.9 inches minimum to 1.4 inches maximum, a top diameter of 50% of the base diameter minimum to 65% of the base diameter maximum, and a height of 0.2 inches.
- B. Alignment. Domes shall be aligned on a square grid in the predominant direction of travel to permit wheels to roll between domes.
- C. Spacing. Truncated domes in a detectable warning surface shall have a center-to-center spacing of 1.6 inches minimum and 2.4 inches maximum, and a base-to-base spacing of 0.65 inches minimum, measured between the most adjacent domes on square grid.

2.4 VISUAL CONTRAST

The visual contrast between the detectable warning and an adjoining surface will be either light-on-dark or dark-on-light. The material used to provide visual contrast shall be an integral part of the detectable warning surface.

2.5 PLACEMENT

- A. Detectable warnings will be built in or applied on the ramp that is from the landing to the roadway.
- B. The detectable warning surface shall be located so that the edge nearest the curb line or other potential hazard is 6 inches minimum to 8 inches maximum from the curb line or other potential hazard.
- C. Detectable warnings shall be 24 inches in the direction of travel and extend the full width of the curb ramp, blended transition, or depressed curb. A depressed curb is a curb that has a height less than or equal to $\frac{1}{4}$ ".

2.6 LOCATION

- A. Detectable warnings shall be installed where a sidewalk crosses a vehicular way, excluding unsignalized driveway crossings.
- B. Detectable warnings shall be installed where a rail system crosses pedestrian facilities that are not shared with vehicular ways.
- C. Detectable warnings shall be installed at islands and medians that are within the roadway.
- D. Detectable warnings shall be installed where required by proposed Chapter 11 of the "Draft Public Rights-of-Way Accessibility Guidelines", June 17, 2002, ADAAG, by the Access Board.

PART 3 - EQUIPMENT

The equipment used for the installation of the detectable warnings is to be as specified by the manufacture's recommendations as listed in Section 1.5.

PART 4 – EXECUTION

4.1 GENERAL REQUIREMENTS

The installation of the detectable warnings is to be as specified by the manufacture's recommendations as listed in Section 1.5.

4.2 SURFACE APPLIED PROCESS

Surface applied detectable warnings occur after the surface that is to receive the detectable warnings has cured. The surface will be prepared as per the manufacture's recommendations.

Detectable Warning Strips

4.3 CAST-IN-PLACE PROCESS

Cast-in-place applied detectable warnings occur during the installation of the surface that is to receive the detectable warnings.

4.4 FINISHING

The detectable warnings shall be installed in reasonably close conformity with the lines and grades shown in the plans or established by the Engineer.

4.5 FINAL CLEANUP

Final cleanup shall be performed in accordance with the requirements in TDOT Standard Specifications Subsection 104.11 and in Section 01710 - Cleanup and Restoration. The detectable warnings shall be cleaned of all excess materials and debris.

PART 5 - MEASUREMENT AND PAYMENT

5.1 METHOD OF MEASUREMENT

- A. Detectable warnings will be measured by the square foot complete in place. The area shall be obtained by surface measurements. Where standard widths are constructed the measurements shall not exceed the standard widths shown in the plans unless on written direction of the Engineer.
- B. No measurement for payment will be made for preparing the surface to receive the detectable warnings unless otherwise indicated in the plans.

5.2 BASIS OF PAYMENT

The accepted quantities of detectable warnings will be paid for at the Contract Unit Bid Price per square foot complete in place.

END OF SECTION – 02523

Section 02575
PAVEMENT REPAIR SPECIFICATION

Part 1 – GENERAL

1.1 Description of Work

Provide the necessary plant, labor, materials and equipment to restore and maintain the various streets and driveway surfaces of all type, pavement and driveway bases, curbs, curb and gutter, and sidewalks disturbed, damaged, or demolished during the performance of the work.

1.2 Related Work Specified Elsewhere

Section 02500 – Paving and Surfacing

Section 02520 – Concrete Curb and Gutter

Section 02522 – Concrete Walks, Driveways, and Ramps

Section 02580 – Pavement Markings

Section 03300 – Concrete Formwork, Reinforcement and Materials

Subdivision Street Design Standards and Specifications

1.3 Applicable Specifications

A. American Society for Testing and Materials (ASTM).

B. Tennessee Department of Transportation, Standard Specifications for Road and Bridge Construction (TDOT).

C. Metro Standard Drawings, ST – 270, ST – 271, ST – 273, ST – 274, ST - 275

1.3 Applicable References

American Association of State Highway and Transportation Officials (AASHTO), latest revision.

American Society for Testing and Materials, (ASTM), latest revision.

1.4 Permits

Before performing any work, the contractor shall secure the required excavation and temporary lane/road closure permits to work within Metro and State right-of-way.

PART 2 – MATERIALS

- 2.1 The quality of materials and workmanship used in the restoration of existing roadway pavements and driveways shall produce a surface equal to or better than the condition before the work began.
- 2.2 Concrete shall be Class A air-entrained Portland cement type as specified in Metro Section 03300. Flowable fill shall conform to TDOT Standard Specifications, Subsection 204.06.
- 2.3 Mineral Aggregate Base: Class A aggregate, Grading D crushed stone (TDOT Standard Specifications, Subsection 303.01, Subsection 903.05).
- 2.4 Bituminous Prime coats: Emulsified Asphalt RS-2 AE-P (TDOT Standard Specifications, Subsection 904.03).
- 2.5 Crushed Stone Chips: Size 7 or 8 (TDOT Standard Specifications, Subsection 903.14).
- 2.6 Double Bituminous Surface: For both courses, Grade RS-2 (TDOT Standard Specifications, Subsection 904.03).
- 2.7 Asphaltic Concrete Binder: Grading B, BM, BM-s, or CW as directed by the Metro Public Works inspector (TDOT Standard Specifications, Section 307).
- 2.8 Bituminous Tack Coat: Grade SS-1 (TDOT Standard Specifications, Sections 403, Subsection 904.03)
- 2.9 Asphaltic Concrete Surface: Grading D or E, as directed by the Metro Public Works inspector, (TDOT Standard Specifications, Section 411).
- 2.10 Quick Dry Traffic Marking Paint (White and Yellow), or Thermo-Plastic depending on existing marking and loops.

PART 3 – GENERAL NOTES Applicable to Metro Standard Drawings ST – 270, and ST - 271

- 3.1 All backfill operations require grading D crushed stone or flowable fill and an inspection by a Metro Public Works inspector. Contractor shall provide Metro Public Works inspector a minimum of 24 hours advance notice for all inspections.
- 3.2 Asphalt pavement may not be installed until the backfill operations have been approved by a Metro Public Works inspector.

- 3.3 Diagonal repairs must be squared off, milled and paved.
- 3.4 Any disturbed pavement markings must be restored to current Metro standards.
- 3.5 Final acceptance by Metro Public Works is required before the work is considered complete.
- 3.6 In the event of any conflict, discrepancy, of inconsistency among the plans submitted with the permit and these notes, the requirements of the Standard Drawings and Metro Standards shall govern.

PART 4 - RECESSED TRENCH NOTES

Applicable to Metro Standard Drawing ST - 271

- 4.1 Once the backfill operations on a recessed trench have been approved by a Metro Public Works inspector, the contractor must schedule an inspection for the final repair. The final repair shall have nine (9) inches of binder placed in a minimum of three (3) layers and compacted with mechanical compaction equipment.
- 4.2 Asphalt surface material shall be placed in two (2) inch thickness and compacted within 1-3 days after the binder is placed.

PART 5 - FLUSH TRENCH NOTES

Applicable to Metro Standard Drawing, ST – 270

- 5.1 Once the backfill operations on a flush trench have been approved by a Metro Public Works inspector, the contractor must schedule an inspection for the final repair. The final repair shall have eleven (11) inches of binder placed in a minimum of three (3) layers and compacted with mechanical compaction equipment
- 5.2 All repairs shall include full lane width resurfacing except when using infrared technology. See attached Infrared specifications.
- 5.3 The binder surface shall be milled or heated using infrared technology two (2) inches in depth and replaced with two (2) inches of surface mix and compacted with mechanical equipment.
- 5.4 All longitudinal repairs more than forty (40) feet in length must be milled and paved.

PART 6 – EXECUTION - Subgrade

6.1 Subgrade

- A. Before any material aggregate base is installed, contractor shall compact the subgrade of the area to be paved to 95% of the optimum density as determined by ASTM D 698.
- B. The backfill material shall contain no topsoil or organic matter. For all areas where subgrade has been prepared, test for uniformity of support by driving a loaded dump truck at a speed of 2 to 3 mph over the entire surface. Make further improvements on all areas that show a deflection of 1 inch or more. When completed, the finished subgrade shall be hard, smooth, stable, and constructed in reasonably close conformance with the lines and grades that existed prior to the beginning of construction.

6.2 Mineral Aggregate Base

- A. Install a mineral aggregate base to the type specified sections 4.2 B and 4.2C in accordance with Section 303 of the TDOT Standard Specifications. The maximum compacted thickness of any one layer shall be 6 inches, and the total thickness of the base shall be that indicated by the Standard Drawings shown in the Subdivision Street Design Standards and Specifications.
- B. When a base is compacted, cut back the surface course of the existing pavement a minimum of 1 foot beyond the limit of the joint between the old and new base course. Take special care to ensure good compaction of the new base course at the joint. Apply and compact the surface to conform to the existing pavement so that it will have no surface irregularity.
- C. Where flowable fill is required it shall conform to TDOT Standard Specifications Section 204.06, Excavatable Flowable Fill (EFF). Typically a 28 day compressive strength shall be 30 psi. Refer to ST-270 drawing for proper placement.

6.3 Double Bituminous Surface

- A. Apply the first course at a rate of 0.38 to .042 gallon per square yard with either emulsified asphalt, Grade RS-2 and then immediately cover with Size 6 crushed stone chips at a rate of 33 to 37 pounds per square yard. After this is rolled, apply the second course at a rate of 0.30 to 0.35 gallons per square yard. Then roll the entire area.
- B. After the application of the cover aggregate, lightly broom or otherwise maintain the surface for a period of 4 days, or as directed by a Metro Public Works inspector. Maintenance of the surface shall include the distribution of cover aggregate over the surface to absorb any free bitumen and cover any areas deficient in aggregate. Sweep

excess material from the entire surface with rotary brooms. Sweep the surface at the time determined by a Metro Public Works inspector.

6.4 Asphaltic Concrete Binder

- A. Apply a bituminous prime coat of emulsified asphalt, Grade AE-P at a rate of 0.38 to 0.42 gallon per square yard. Take care to prevent the bituminous material from splashing on exposed faces of curbs and gutters, walls, walks, trees, etc. If such splashing does occur, remove it immediately. After the prime coat has properly cured, apply an asphaltic concrete binder to the thickness shown on the thickness shown on the standard drawings in the Subdivision Street Design Standards and Specifications.
- B. Carefully place material to avoid segregation of the mix. Broadcasting of the material will not be permitted. Remove any lumps that do not readily break down.
- C. If milling of the street is required, the thickness of the binder course as specified by a Metro Public Works inspector shall be maintained after milling.

6.5 Asphaltic Concrete Surface

If the asphaltic concrete surface is to be placed directly on the mineral aggregate base, place the bituminous prime coat as described above. If the surface course is to be placed on a binder course, then apply a bituminous tack coat of the sort specified above under MATERIALS at a rate of 0.05 to 0.10 gallons per square yard. Take care to prevent splashing of the bituminous material on the exposed faces of the curbs, gutters, walls, walks, trees, etc. If such splashing does occur, the material shall be removed by the contractor. After the prime or tack has been properly cured, apply the asphaltic concrete surface to the thickness shown on the drawings in the Subdivision Street Design Standards and Specifications. Apply the surface course as described above for the asphaltic concrete binder course, Sections 4.4.

6.6 Smoothness

The finished surfaces shall conform to the lines and grades that existed prior to construction. No deviation, variations, or irregularities exceeding ¼ inch in any direction when tested with 12 foot straightedge will be permitted in the finished work, nor will any depressions that will not drain properly. All defects shall be corrected by the contractor.

6.7 Sampling and Testing

A Metro Public Works inspector may require that tests be made on the completed elements of the pavement to ascertain the compacted thickness of the base and surface courses. If sections with deficiencies are found, the full section for a reasonable distance on each side of the deficiency shall be refused. All such sections shall be removed and reinstalled. All test holes in connection with the thickness test shall be patched.

PART 7 – EXECUTION – Excavations

- 7.1 Where trenches have been opened in any roadway or street that is a part of the State of Tennessee Highway system, restore surfaces in accordance with the requirements of TDOT. All other restoration shall be done in accordance with the Metro Standard Drawings and these specifications.
- 7.2 Excavations in the pavement area shall require that pavement surface edges be saw-cut or cold plane milled to provide a straight and smooth edge.
- 7.3 Flowable fill will be required on all arterials, collectors, and downtown streets. Flowable fill shall meet the requirements in TDOT Standard Specifications, Section 204, except as modified by Public Works technical specifications 02225, latest revision. Flowable fill may also be required in areas of special significance as determined by a Metro Public Works inspector.
- 7.4 Upon completion of installation of utility or other work if a temporary patch is to be used, placement of compacted backfill or mineral aggregate base or grading D crushed stone (6” layers) and temporary asphalt patch (2” cold mix) shall be placed and rolled or mechanically compacted until such time that the permanent repair will be constructed as shown on Metro Public Works Standard Drawing ST-270 or ST-271.
- 7.5 All final repairs shall use a minimum two (2) foot trench width and a one (1) foot cutback on all sides of the excavation as shown on Metro Public works Standard Drawing ST-270 or ST -271, except at the edge of pavement.
- 7.6 Upon completion of installation of utility or other work, placement of compacted backfill mineral aggregate base capped off with 8” to 12” of grading D crushed stone (6” layers), asphaltic concrete binder (3” layers), and surface shall be placed as shown on Metro Public works Standard Drawing ST-270 or ST -271.

- 7.7 Milling and paving the full lane or roadway width is required where successive or continuous excavations are planned so as not to “checkerboard” the roadway and to provide a smooth riding surface.

New Excavations (Without Existing Patches):

If two or more excavations are made in the roadway the contractor will be required to mill and pave the full width of the lane or roadway throughout the entire length of the project. Exceptions can be made with the approval from the director of Metro Public Works.

If a continuous longitudinal trench is made in the roadway, the entire length of the trench shall be milled and paved the width of the lane impacted. If the continuous trench is within 100 feet of an intersection, the restoration limits shall extend to the radius points of the intersection. If the continuous trench falls between the edge of pavement and a construction joint, milling and paving can be completed to the existing construction joint.

New Excavations (With Existing Patches)

New excavations made within 20 feet of any existing patches less than 5 years old from the same utility company, the contractor will be required to pave the patches as one continuous patch. Once the number of patches made from the same utility company exceeds 5 excavations/patches within a street block 500 feet or less, the entire lane or roadway shall be milled and paved.

Relief from the standard requirements due to special circumstances can be requested by the contractor to The Director of Metro Public Works or their designee.

- 7.8 Asphalt repairs adjacent to curb and gutter work encroaching more than 24-inches into the roadway shall require full lane width paving. If a construction joint falls within the road centerline and the edge of pavement, the milling and paving can be completed to the existing construction joint.
- 7.9 Curb and gutter, sidewalk, and shoulders, shall be restored as required to match existing construction. Replace damaged sections with complete new sections from expansion joint to expansion joint. Patching curb, gutter, or sidewalk will not be permitted.
- 7.10 When a manhole top or other utility casting requires adjustment to an elevation one inch or more above the existing pavement grade a temporary ramp shall be constructed by feathering bituminous concrete 360 degrees around the casting. A taper slope of not less than two feet per inch shall be used. Taper shall be removed prior to placement of bituminous concrete surface course.

- 7.11 Where asphaltic concrete surface courses are required for a continuous trench or five (5) successive cuts or more are made at intervals of 300 feet or less, the asphaltic surface course shall not be placed for a minimum of 30 days after the binder is placed flushed in the trench according to Metro Standard Drawing 270. However, due to seasonal limitations, or other factors deemed appropriate, the Metro Public Works inspector may grant variances to this requirement on a case by case basis.
- 7.12 All repairs within the right of way shall be warranted for a period of one (1) years following the date of final acceptance. Evidence of settling, pumping, or cracking represents a warranty violation. Construction Requirements of TDOT Standard Specifications Section 407 shall apply.
- 7.13 In addition to this section, all pavement restoration for the various types of streets shall be in conformance with Metro Public Works Standard Drawings and Section 02500.

SECTION 02500
PAVING AND RESURFACING

PART 1 - GENERAL

1.1 DESCRIPTION OF WORK

- A. This Work shall consist of furnishing and placing one (1) or more courses of aggregates and additives if required on a prepared subgrade in accordance with TDOT Standard Specifications Section 303 and this Section and in reasonably close conformity with the lines, grades, thickness, and typical cross sections shown in the plans or established by the Engineer. Mineral aggregates base shall be type A or type B whichever is shown in the plans and called for in the bid schedule.
- B. This Work shall consist of a foundation composed of a hot mixture of aggregate and asphalt prepared in a hot bituminous mixing plant. It shall be constructed in one (1) or more layers on a prepared subgrade, granular subbase, or base in accordance with TDOT Standard Specifications Section 307 and this Section and in reasonably close conformity with the lines, grades, thicknesses, and typical cross sections shown in the plans or as directed by the Engineer.
- C. This Work shall consist of an application of bituminous material and cover material if required on a designated base in accordance with the requirements in TDOT Standard Specifications Section 402 and this Section and in reasonably close conformity with the lines shown in the plans or established by the Engineer.
- D. This Work shall consist of furnishing and applying bituminous material to a previously prepared base or surface to provide a bond for a superimposed course in accordance with the requirements in TDOT Standard Specifications Section 403 and this Section.
- E. This Work shall consist of a bituminous mat composed of mineral aggregate bonded with bituminous material. It shall be constructed on a designated surface in accordance with TDOT Standard Specifications Section 404 and this Section and in reasonably close conformity with the lines, grades, and cross sections indicated in the plans or established by the Engineer.
- F. This Work shall consist of an application of bituminous material followed by an application of cover material in accordance with TDOT Standard Specifications Section 405 and this Section and in reasonably close conformity with the lines, grades, and cross section shown in the plans or established by the Engineer.
- G. TDOT Standard Specifications Section 407 and this Section include general requirements that are applicable to all types of bituminous pavements of the plant mix type irrespective of gradation of aggregate, kind and amount of bituminous material, or pavement used. Deviations from these general requirements will be indicated in the specific requirements for each type.
- H. This Work shall consist of one (1) or more courses of bituminous mixture constructed on the prepared foundation in accordance with TDOT Standard Specifications Section 407 and this Section and the specific requirements of the type under CONTRACT and in reasonably close conformity with the lines, grades,

typical cross sections, and rate of application or thickness shown in the plans or established by the Engineer.

- I. This Work shall consist of an asphaltic concrete pavement composed of a mixture of coarse aggregate, fine aggregate, mineral filler if specified or required, and asphalt cement constructed on a prepared roadbed in accordance with TDOT Standard Specifications Section 411 and this Section and in reasonably close conformity with the lines, grades, typical cross section, and rate of application shown in the plans or established by the Engineer. The provisions in TDOT Standard Specifications Section 407 and this Section shall apply to this construction unless otherwise stipulated.
- J. This Work shall consist of cold planing an existing bituminous plant mix pavement in accordance with the requirements in TDOT Standards Specifications Section 415 and this Section and in reasonably close conformity with the lines and grades shown in the plans or established by the Engineer.

1.2 RELATED WORK SPECIFIED ELSEWHERE

Section 01340 - Shop Drawings, Product Data, and Samples
Section 01410 - Testing Laboratory Services
Section 01580 - Traffic Signals
Section 02200 - Earthwork
Section 02210 - Embankments
Section 02225 - Earthwork for Structures and Pipelines
Section 02520 - Cement Concrete Curb, Gutter, and Combined Curb and Gutter
Section 02522 - Cement Concrete Sidewalks, Driveways, and Median Pavement
Section 02580 - Pavement Markings
Section 03300 - Cast-In-Place Concrete

1.3 APPLICABLE SPECIFICATIONS

"STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", Latest Revision, Tennessee Department of Transportation (TDOT)

"SUBDIVISION SPECIFICATIONS FOR STREETS AND ROADS", Latest Revision, Metropolitan Government of Nashville and Davidson County

1.4 APPLICABLE REFERENCES

"American Association of State Highway and Transportation Officials" (AASHTO), Latest Revision

"American Society for Testing and Materials" (ASTM), Latest Revision

PART 2 - MATERIALS

2.1 MINERAL AGGREGATE BASE

- A. The mineral aggregate shall meet the requirements in TDOT Standard Specifications Subsection 903.05 for Class A or Class B aggregates depending upon whether type A or type B base is required in the construction. Type A base

will require the use of Class A aggregate grading D. Either Class A or Class B aggregate may be used for type B base.

1. When the stationary plant method for mixing is used the aggregate will be accepted for gradation immediately following mixing or immediately prior to mixing based on periodic samples taken from the pugmill output or from the belt feeding the pugmill.
 2. When two (2) or more materials are blended on the road by means of mechanical mixers the aggregate will be accepted for gradation after mixing and before compaction based on samples taken from each layer of base material. Aggregate that does not require blending will be accepted for gradation at the aggregate production plant based on samples taken from stockpiles of plant production immediately prior to delivery to the road.
- B. Calcium chloride shall meet the requirements in TDOT Standard Specifications Subsection 918.02 for type 1, type 2, or calcium chloride liquor.
- C. Sodium chloride shall meet the requirements in TDOT Standard Specifications Subsection 918.03.

2.2 BITUMINOUS PLANT MIX BASE (HOT MIX)

- A. The materials used in this construction shall conform to the requirements in TDOT Standard Specifications Subsections 903.06, 918.09 (B), and 904.01.
- B. The specific grading of aggregate to be used will be specified in the CONTRACT or shown in the plans. Mineral aggregate, bituminous material, and the plant mix will be accepted as provided for in TDOT Standard Specifications Subsection 407.02.

2.3 PRIME COAT

- A. Materials shall meet the requirements in TDOT Standard Specifications Subsections 903.13, 904.02, and 904.03.
- B. The ranges of application temperatures in degrees Fahrenheit shall be as shown in TDOT Standard Specifications Subsection 402.02.

2.4 TACK COAT

Bituminous materials shall conform to the requirements in TDOT Standard Specifications Subsections 904.01 through 904.03 and 918.09 (B).

- A. The ranges of application temperatures in degrees Fahrenheit shall be as shown in TDOT Standard Specifications Subsection 403.02.
- B. When emulsified asphalt is used water as approved by the Engineer may be added to the asphaltic emulsion and thoroughly mixed therewith in such proportion not to exceed thirty (30) percent by volume of added water that the resulting mixture will give the desired cover of residual bitumen. The exact quantity of added water will be established by the Engineer.

2.5 DOUBLE BITUMINOUS SURFACE TREATMENT

- A. Materials used in this construction shall meet the requirements in TDOT Standard Specifications Subsections 903.14, 904.02, and 904.03.
- B. The ranges of application temperatures in degrees Fahrenheit shall be as shown in TDOT Standard Specifications Subsection 404.02.

2.6 BITUMINOUS SEAL COAT

- A. Materials used in this construction shall meet the requirements in TDOT Standard Specifications Subsections 903.13 and 904.01 through 904.03.
- B. Application temperatures for bituminous materials in degrees Fahrenheit shall be as shown in TDOT Standard Specifications Subsection 405.02.

2.7 BITUMINOUS PLANT MIX PAVEMENTS (GENERAL)

The individual materials shall meet the applicable requirements in TDOT Standard Specifications.

- A. Aggregates shall meet the applicable requirements in TDOT Standard Specifications Section 903.
- B. Mineral filler shall meet the requirements in TDOT Standard Specifications Subsection 903.16.
- C. Bituminous materials shall meet the applicable requirements in TDOT Standard Specifications Section 904.
- D. Chemical additive shall meet the requirements in TDOT Standard Specifications Subsection 918.09 (B).
- E. Aggregate shall be separated into coarse and fine aggregate stockpiles. When coarse aggregate is stockpiled by means causing segregation it shall be separated into coarse and medium coarse stockpiles.
- F. Each size and type of aggregate shall be stocked in a separate pile, bin, or stall. The storage yard shall be maintained in an orderly condition with a walkway between stockpiles that are not separated by partitions. The stockpiles shall be readily accessible for sampling.
- G. The mineral aggregate will be conditionally accepted for quality in the stockpile at the producer's site. The bituminous material may be conditionally accepted at the asphalt terminal. Acceptance of the aggregate gradation and asphalt cement content shall be determined from hot bin samples or sample(s) taken from the completed mix at the asphalt plant after it has been loaded onto the trucks for transport to the project as specified herein.
- H. Where anti-stripping additive other than hydrated lime as described in TDOT Standard Specifications Subsection 918.09 (B) and this Section is required it shall be added by approved on line blending equipment at the Contractor's mixing plant.

The dispenser shall be capable of adding heat stable anti-stripping additive within a tolerance of ten (10) percent of the specified rate.

2.8 ASPHALTIC CONCRETE SURFACE (HOT MIX)

- A. Materials used in this construction shall meet the requirements in TDOT Standard Specifications Subsections 903.11, 903.16, 904.01, and 918.09 (B).
- B. The mineral aggregate, bituminous material, and plant mix will be accepted as provided for in TDOT Standard Specifications Subsection 407.02.

PART 3 - EQUIPMENT

All equipment necessary for the satisfactory performance of this construction shall be on the project and approved before Work will be permitted to begin. The equipment used for this construction shall meet the requirements specified in TDOT Standard Specifications Subsections 303.05, 307.04, 402.03, 403.03, 404.03, 405.03, 407.04 through 407.08, 411.04, and 415.02.

PART 4 - EXECUTION

4.1 MINERAL AGGREGATE BASE

Mineral aggregate base shall conform in general construction requirements, mixing, spreading, shaping and compaction, maintenance, thickness requirements, and surface requirements to the requirements in TDOT Standard Specifications Subsections 303.06 through 303.12.

4.2 BITUMINOUS PLANT MIX BASE (HOT MIX)

Bituminous plant mix base (hot mix) shall conform in composition of mixtures, general construction requirements, preparation of subgrade, subbase, or surface, and thickness and surface requirement to the requirements in TDOT Standard Specifications Subsections 307.03 and 307.05 through 307.07.

4.3 PRIME COAT

Prime coat shall conform in limitations, preparation of surface, application of prime, application of cover material, and maintenance and protection to the requirements in TDOT Standard Specifications Subsections 402.04 through 402.08.

4.4 TACK COAT

Tack coat shall conform in preparation of surface and application of bituminous material to the requirements in TDOT Standard Specifications Subsections 403.04 and 403.05.

4.5 DOUBLE BITUMINOUS SURFACE TREATMENT

Double bituminous surface treatment shall conform in limitations, preparing designated surface, applications of bituminous material and mineral aggregate, rolling and curing, shoulders, and maintenance and protection to the requirements in TDOT Standard Specifications Subsections 404.04 through 404.09.

4.6 BITUMINOUS SEAL COAT

Bituminous seal coat shall conform in limitations, preparing the designated surface, application of bituminous material, spreading and rolling aggregate, shoulders, and maintenance and protection to the requirements in TDOT Standard Specifications Subsections 405.04 through 405.09.

4.7 BITUMINOUS PLANT MIX PAVEMENT (GENERAL)

Bituminous plant mix base (hot mix) shall conform in composition of mixtures (includes Contractor's quality control system), weather limitations, conditioning of existing surface, preparation of bituminous material, preparation of aggregates, mixing, spreading and finishing, compaction (includes density requirements and test strips), joints, pavement samples, and surface requirements to the requirements in TDOT Standard Specifications Subsections 407.03 and 407.09 through 407.18.

4.8 ASPHALTIC CONCRETE SURFACE (HOT MIX)

Asphaltic concrete surface (hot mix) shall conform in composition of mixtures, general construction requirements, preparing the designated surface, mixing, and surface requirements to the requirements in TDOT Standard Specifications Subsections 411.03 and 411.05 through 411.08.

4.9 COLD PLANING OF BITUMINOUS PLANT MIX PAVEMENTS

Cold planing of bituminous plant mix pavements shall conform in general requirements and surface requirements to the requirements in TDOT Standard Specifications Subsections 415.03 and 415.04.

4.10 PAVEMENT REPAIR

Where trenches have been opened in any roadway or street that is a part of the State highway system surfaces shall be restored in accordance with the requirements of the Tennessee Department of Transportation. All other restoration shall be done in accordance with this Section and Public Works details.

- A. Excavation in the pavement area shall require that pavement surfaces be cut and brought to a neat line by use of an air hammer, saw, or other suitable equipment.
- B. Upon completion of installation of utility backfill fill the trench with mineral aggregate type A, grading D (crusher run stone) and temporary asphalt patch with two (2) inches of cold mix or hot bituminous seal coat until such time that the permanent pavement patch is constructed.
- C. Complete the pavement restoration for the various types of roadway typical sections in conformance with Public Works details and this Section.
- D. Concrete curb or combined curb and gutter, driveways, median pavement, and sidewalks shall be restored as required to match existing construction. Replace damaged sections with complete new sections or squares. Patching of damaged sections will not be permitted.

- E. Maintain restored sections and surfaces as part of this CONTRACT for a period of one (1) year following the date of final acceptance.
- F. The minimum width to be trimmed on each side of the trench line as seen in the section may be waived or amended upon approval of the Inspector however a minimum width of replacement shall be four (4) feet to allow for a roller.
- G. All excavations made within public right-of-way will require excavation and street closure permits from the Department of Public Works prior to commencing Work.
- H. Flowable fill shall meet the requirements in TDOT Standard Specifications Section 204 except as modified in Pubic Works Technical Specifications Section 02225 latest revision.
- I. When a manhole top or other utility casting requires adjustment to an elevation one (1) inch or more above the existing pavement grade and is exposed to traffic before final paving is completed a temporary ramp shall be constructed by feathering bituminous concrete for three hundred sixty (360) degrees around the manhole or utility casting. A taper slope of not less than two (2) feet per one (1) inch shall be used. During the paving operation but prior to the placement of the topping course the bituminous concrete taper shall be removed from around the manhole to a minimum depth of one (1) inch below the top of manhole.

4.11 CASTING ADJUSTMENTS

Manholes, catch basins, inlets, valve boxes and all other utility structures shall be constructed in accordance with Section 611.10 of the TDOT "Standard Specifications for Road and Bridge Construction". All castings and fittings shall be placed in the positions indicated on the Plans or as directed by the Engineer, and shall be set true to line and grade.

- A. Drainage grates located within the right of way shall be bicycle friendly as shown on Metro Public Works Standard Drawings ST- 506, ST- 506a or ST-506b. Exceptions to these standards require prior written approval of the Metro Engineer.
- B. Backfill of the new adjusted casting shall be accomplished using an asphalt binder as defined in Section 307 of the TDOT "Standard Specifications for Road and Bridge Construction" and shall be placed in accordance with Section 407.09, 407.11, and 407.15 with regard to Weather Limitations, Material Temperature, and Compaction requirements. Binder shall be placed in no more than 3 inch lifts and compacted using a compaction process to achieve required density..

PART 5 - MEASUREMENT AND PAYMENT

5.1 METHOD OF MEASUREMENT

A. Mineral Aggregate Base.

Mineral aggregate for mineral aggregate base, type A or type B will be measured by the ton in accordance with the provisions in TDOT Standard Specifications Section 109.

1. When mixing is performed in a stationary plant the weight of all surface moisture on the aggregate at the time of weighing in excess of eight (8) percent will be deducted. No direct payment for water will be made.
2. When mixing is performed on the road the weight of surface moisture on the aggregate at the time of weighing in excess of eight (8) percent will be deducted. Water added to the materials on the road at the direction of the Engineer will be measured for payment.
3. Water measured for payment as provided in TDOT Standard Specifications Subsection 303.13 and above will be measured by the M.G. (1000 gallons) by means of calibrated tanks or distributors or by means of accurate water meters.
4. Sodium chloride will be measured by the ton in accordance with the provisions in TDOT Standard Specifications Section 109.
5. Calcium chloride will be measured by the ton.
6. Calcium chloride received in liquid form will be weighed as provided for in TDOT Standard Specifications Section 109. The weight of liquid calcium chloride will be converted to tons by using the following formulae:

32% solution:

$$\frac{((\text{total tons of 32\% solution}) \times 0.32)}{(0.94)} = \text{tons}$$

38% solution:

$$\frac{((\text{total tons of 38\% solution}) \times 0.38)}{(0.94)} = \text{tons}$$

7. When calcium chloride liquor in a solution of 32% or more but less than 38% is used it will be paid for as a 32% solution. A solution of 38% or greater will be paid for as a 38% solution.

B. Bituminous Plant Mix Base (hot mix).

Aggregate and asphalt cement for bituminous plant mix base (hot mix) will be measured by the ton in accordance with the provisions in TDOT Standard Specifications Subsection 407.19 and subparagraph 5.1 G below. Materials for

prime or tack coat if specified will be measured as prescribed in TDOT Standard Specifications Sections 402 or 403 and subparagraphs 5.1 C and D below.

1. If recycled mix is used the completed mix including new mineral aggregate, planings, asphalt cement, and additive shall be measured by the ton in accordance with TDOT Standard Specifications Section 109. For bidding purposes the asphalt cement content of the specified mixes shall be as shown in the Contract Documents. In the event that the Engineer sets an asphalt content other than that stated in the Contract Documents a price adjustment will be made based on the asphalt content set by the Engineer and the invoice price of the asphalt cement F.O.B. the asphalt plant. The price adjustment will be calculated according to the formula in the Contract Documents.
2. The liquid anti-strip additive will be measured by the gallon and paid as outlined in TDOT Standard Specifications Subsection 307.09 and subparagraph 5.2 B below. Hydrated lime will be measured by the ton and paid as outlined in TDOT Standard Specifications Subsection 307.09 and subparagraph 5.2 B below.
3. No direct payment will be made for polymer or latex additives and cost thereof shall be included in the Contract Unit Bid Price for the modified asphalt cement or modified mixture.

C. Prime Coat.

Bituminous material and cover material will be measured by the ton in accordance with the provisions in TDOT Standard Specifications Section 109. Net certified weights may be used as a basis of measurement for cover material aggregate subject to correction for aggregate that is lost, wasted, or otherwise not incorporated in the Work. Water used at the direction of the Engineer to dampen the base prior to applying bituminous materials shall be measured by the M.G. (1000 gallons) by means of calibrated tanks or distributors or by means of accurate water meters.

D. Tack Coat.

Bituminous material for tack coat will be measured by the ton in accordance with the provisions in TDOT Standard Specifications Section 109. Water used for dilution of asphalt emulsion will not be measured for payment.

E. Double Bituminous Surface Treatment.

Mineral aggregate and bituminous material will be measured by the ton in accordance with the provisions in TDOT Standard Specifications Section 109. Net certified weights may be used as a basis of measurement for mineral aggregate subject to correction for aggregate that is lost, wasted, or otherwise not incorporated in the Work.

F. Bituminous Seal Coat.

Mineral aggregate and bituminous material will be measured by the ton in accordance with the provisions in TDOT Standard Specifications Section 109. Net certified weights may be used as a basis of measurement for mineral aggregate subject to correction for aggregate that is lost, wasted, or otherwise not incorporated in the Work.

G. Bituminous Plant Mix Pavements (general).

Chemical additives or modifiers when required will not be measured for payment but will be considered as part of the asphalt cement.

1. Mineral filler will not be measured separately for payment but will be included in mineral aggregates.
2. Asphalt cement and mineral aggregate including mineral filler when required will be measured by the ton.
3. Where the mix is loaded from a storage or surge bin the quantities will be determined by weighing the completed mix on truck scales meeting the requirements in TDOT Standard Specifications Section 109 and calculating the weight of asphalt cement and mineral aggregate based on percentages measured into the mix by the appropriate scales or meters described in TDOT Standard Specifications Subsection 407.04.
4. Where the mix is loaded directly into the hauling equipment from a batch plant asphalt cement and mineral aggregate will be measured in batch quantities by scales or scales and meters as described in TDOT Standard Specifications Subsection 407.04 (b).
5. Where a continuous mix plant is used bituminous material for bituminous plant mix pavement will be measured by the ton in accordance with the provisions in TDOT Standard Specifications Section 109. The mineral aggregate including mineral filler when required will be determined by weighing the bituminous pavement mixture on truck scales meeting the requirements in TDOT Standard Specifications Section 109 and deducting the weight of the bituminous material from the weight of total mixture accepted.
6. When the Work described under TDOT Standard Specifications Subsection 407.10 is required the removal and disposal of existing surface (concrete) will be measured by the square yard in accordance with the provisions in TDOT Standard Specifications Section 109. Such measurement shall include the removal of bituminous overlay.
7. The removal and disposal of existing surface (bituminous) will be measured by the cubic yard in accordance with the provisions in TDOT Standard Specifications Section 109. Such measurement shall include the removal of base material except concrete as directed by the Engineer.

8. Removal of unsatisfactory subgrade material where existing pavement has been removed will be measured by the cubic yard in accordance with the provisions in TDOT Standard Specifications Subsection 203.09 and Section 02200 - Earthwork. Material used to replace such undercutting will be measured and paid for in accordance with the specification for the type of material used.
9. Bituminous mixtures used to fill openings left by pavement removal will be measured for payment in accordance with the provisions in TDOT Standard Specifications Subsection 407.19 and subparagraph 5.2 G. Base materials used to fill openings left by base removal will be measured as provided for in the respective TDOT Standard Specifications sections for each type specified.
10. Adjustment of catch basin grates and frames, water valve boxes, gas valve boxes, and manhole covers and frames shall be measured per each when required.

H. Asphaltic Concrete Surface (hot mix).

Mineral aggregate including mineral filler when required and asphalt cement for asphaltic concrete surface (hot mix) will be measured as prescribed in TDOT Standard Specifications Subsection 407.19 and subparagraph 5.1 G above. Mineral filler when required will not be measured for payment separately but will be included as mineral aggregate.

1. Asphaltic concrete surface (hot mix) (shoulders) including new mineral aggregate, plantings, asphalt cement, and additive shall be measured by the ton in accordance with TDOT Standard Specifications 109. For bidding purposed the asphalt cement content of the specified mix shall be as shown in the Contract Documents for 411 E used as a surface on the shoulders. In the event that the Engineer sets an asphalt content other than that stated in the Contract Documents a price adjustment will be made based on the asphalt content set by the Engineer and the invoice price of the asphalt cement F.O.B. the asphalt plant. The price adjustment will be calculated according to the formula shown in the Contract Documents.
2. The liquid anti-strip additive will be measured by the gallon and paid as outlined in TDOT Standard Specifications Subsection 411.10 and subparagraph 5.2 G below. Hydrated lime will be measured by the ton and paid as outlined in TDOT Standard Specifications Subsection 411.10 and subparagraph 5.2 G below.
3. No direct payment will be made for polymer or latex additives and cost thereof shall be included in the Contract Unit Bid Price for the modified asphalt cement or modified mixture.

I. Cold Planing of Bituminous Plant Mix Pavements.

Cold planing of bituminous pavement will be measured by the ton of material removed, by the cubic yard of material removed, or by the square yard of planed pavement. The method of measurement will depend upon the pay item designated in the proposal.

1. Where payment is by the ton the material removed from areas acceptably planed will be measured by the ton in accordance with TDOT Standard Specifications Section 109.
2. Where payment is by the cubic yard the material removed from areas acceptably planed will be measured by the cubic yard in accordance with TDOT Standard Specifications Section 109.
3. Where payment is by the square yard the pavement acceptably planed will be measured by the square yard in accordance with TDOT Standard Specifications Section 109.
4. Unless otherwise specified water used to control dust will not be measured for separate payment but will be considered incidental to the planing operation.
5. Salvage value of cold planings will be measured in the same units and by the same method as cold planing of bituminous pavement.

5.2 BASIS OF PAYMENT

A. Mineral Aggregate Base.

1. The accepted quantities of mineral aggregate base of the type specified will be paid for at the Contract Unit Bid Price per ton for mineral aggregate, per ton for calcium chloride, per ton for sodium chloride and per M.G. (1000 gallons) for water complete in place.
2. The Work required for preparation of subgrade as provided for under TDOT Standard Specifications Subsection 303.06 and this Section will be measured and paid for in accordance with the provisions in the applicable TDOT Standard Specifications Sections or Subsections and Public Works Technical Specifications Section under which the Work is performed.

B. Bituminous Plant Mix Base (hot mix).

The accepted quantities of bituminous plant mix base (hot mix) complete in place will be paid for at the Contract Unit Bid Price per ton for the aggregate and/or the asphalt cement. Accepted quantities of prime coat or tack coat will be paid for in accordance with the provisions in TDOT Standard Specifications Sections 402 or 403 respectively and this Section.

1. In cases where the combined specific gravity of the mineral aggregate exceeds two and eighty-hundredths (2.80) the tonnage of mineral aggregate will be adjusted for payment by multiplying the tonnage of mineral aggregate used by a specific gravity of two and eighty-hundredths (2.80) and dividing by the higher specific gravity.
 2. The Work required for preparation of subgrade, subbase, base, or surface as provided for under TDOT Standard Specifications Subsection 307.06 and this Section will be measured and paid for in accordance with the provisions in the applicable TDOT Standard Specifications Sections or Subsections and Public Works Technical Specifications Section under which the Work is performed.
 3. If recycled mix is used the accepted quantities of bituminous plant mix base (hot mix) complete in place will be paid for at the Contract Unit Bid Price per ton of the total mix which will include mineral aggregate, planings, asphalt cement, and additive. Payment will be made to the Contractor for additional asphalt cement as provided for in TDOT Standard Specifications Section 307 and this Section at the purchase price F.O.B. the asphalt mixing plant as verified by invoice and no compensation will be allowed for further handling or processing. The Department of Public Works will be reimbursed from monies due the Contractor for a decrease in asphalt cement content in the amount equal to the purchase price F.O.B. the asphalt plant.
 4. The liquid anti-strip additive will be paid for based on certified invoices of material cost not to exceed fifteen (15) dollars per gallon. Hydrated lime anti-strip additive will be paid for based on certified invoices of material cost not to exceed ninety (90) dollars per ton. This payment shall be full compensation for all labor, materials, equipment, and other incidentals incurred in utilizing the anti-strip additive.
- C. Prime Coat.
- The accepted quantities of prime coat will be paid for at the Contract Unit Bid Price per ton for bituminous material, per ton for cover material, and per M.G. (1000 gallons) for water complete in place.
- D. Tack Coat.
1. The accepted quantities of tack coat will be paid for at the Contract Unit Bid Price per ton for bituminous material complete in place.
 2. The Work required for preparing the designated surface as provided for under TDOT Standard Specifications Subsection 403.04 and this Section will be measured and paid for in accordance with the provisions in the applicable TDOT Standard Specifications Sections or Subsections and Public Works Technical Specifications Section under which the Work is performed.

E. Double Bituminous Surface Treatment.

1. The accepted quantities of double bituminous surface treatment will be paid for at the Contract Unit Bid Price per ton for bituminous material and per ton for mineral aggregate complete in place.
2. The Work required for preparing the designated surface as provided for under TDOT Standard Specifications Subsection 404.05 and this Section will be measured and paid for in accordance with the provisions in the applicable TDOT Standard Specifications Sections or Subsections and Public Works Technical Specifications Section under which the Work is performed.

F. Bituminous Seal Coat.

1. The accepted quantities of bituminous seal coat will be paid for at the Contract Unit Bid Price per ton for bituminous material and per ton for mineral aggregate complete in place.
2. The Work required for preparing the designated surface as provided for under TDOT Standard Specifications Subsection 405.05 and this Section will be measured and paid for in accordance with the provisions in the applicable TDOT Standard Specifications Sections or Subsections and Public Works Technical Specifications Section under which the Work is performed.

G. Bituminous Plant Mix Pavements (general).

All Work performed and measured as prescribed in TDOT Standard Specifications Section 407 and this Section will be paid for as provided in the respective TDOT Standard Specifications sections for each type specified. Acceptance of the mixture, defective materials, acceptance procedures, additional tests, and acceptance for mix density on the roadway will be paid for as described in TDOT Standard Specifications Subsection 407.20.

H. Asphaltic Concrete Surface (hot mix).

The accepted quantities of asphaltic concrete surface (hot mix) will be paid for at the respective Contract Unit Bid Price per ton for mineral aggregate and asphalt cement.

1. Asphaltic concrete surface (hot mix) (shoulders) containing recycled material complete in place will be paid for at the Contract Unit Bid Price per ton of the total mix which will include mineral aggregate, planings, asphalt cement, and additive. Payment will be made to the Contractor for additional asphalt cement as provided for in TDOT Standard Specifications Section 411 and this Section at the purchase price F.O.B. the asphalt mixing plant as verified by invoice and no compensation will be allowed for further handling or processing. The Department of Public Works will be reimbursed from monies due the Contractor for a decrease in asphalt cement content in the amount equal to the purchase price F.O.B. the asphalt plant.

2. The liquid anti-strip additive will be paid for based on certified invoices of material cost not to exceed fifteen (15) dollars per gallon. Hydrated lime anti-strip additive will be paid for based on certified invoices of material cost not to exceed ninety (90) dollars per ton. This payment shall be full compensation for all labor, materials, equipment, and other incidentals incurred in utilizing the anti-strip additive.
3. In cases where the combined specific gravity of mineral aggregate exceeds two and eighty-hundredths (2.80) the tonnage of mineral aggregate will be adjusted for payment by multiplying the tonnage of mineral aggregate used by a specific gravity of two and eighty-hundredths (2.80) and dividing by the higher specific gravity.
4. The Work required for preparing the designated surface as provided for under TDOT Standard Specifications Subsection 411.06 and this Section will be measured and paid for in accordance with the provisions in the applicable TDOT Standard Specifications Sections or Subsections and Public Works Technical Specifications Section under which the Work is performed.
5. When the approved job mix formula includes a mixture of limestone with gravel, granite, slag, quartzite, or gneiss tests for the percent loss on ignition of the limestone aggregate in the asphalt paving mix shall be performed according to the provisions in TDOT Standard Specifications Subsection 407.03.
6. In the event the percent of loss on ignition in the aggregate differs by more than plus or minus two (± 2) percent from the loss on ignition indicated in the job mix formula a deduction in payment in the Contract Unit Bid Price for the mix shall be made not as a penalty but as liquidated damages. The percent of total payment to be deducted shall be five (5) times the percent that the loss on ignition exceeds the job mix formula tolerance of plus or minus two (± 2) percent.
7. All mix produced with aggregate tested and found to have a loss on ignition that differs more than plus or minus six (± 6) percent from the loss on ignition indicated in the job mix formula shall be replaced or overlaid at the expense of the Contractor.
8. For the purpose of determining the deduction lots of approximately five thousand (5000) square yards will be used. The sampling and testing to establish the loss on ignition will be performed in accordance with the Department of Public Works sampling and testing procedures. In event the initial tests indicates a variation in the loss on ignition of greater than plus or minus two (± 2) percent than the value shown on the mix design the additional sampling necessary to establish the loss on ignition of the aggregate in each lot shall be performed by the Contractor with the cost of the sampling being included in the Contract Unit Bid Price for the paving items.
9. Any deduction for excess variation in loss on ignition shall be made under item 411-03.40.

- I. Cold Planing of Bituminous Plant Mix Pavements.
 1. The accepted quantity of cold planed bituminous pavement will be paid for at the Contract Unit Bid Price which payment shall be full compensation for all labor, materials, equipment, hauling, and incidentals necessary to plane the pavement, control dust, and dispose of the cuttings.
 2. The Contract Unit Bid Price for salvage value of cold planing will be deducted from monies due the Contractor to compensate the Department of Public Works for the removed material.

END OF SECTION - 02500

SECTION 02720
STORM SEWERS AND DRAIN SYSTEMS

PART 1 - GENERAL

1.1 DESCRIPTION OF WORK

- A. This Work shall consist of the construction of pipe culverts, side drains, slope drains, and storm sewers of the kinds and dimensions shown in the plans and/or Contract Documents or stipulated in the proposal. The construction shall be accomplished in accordance with this Section and in reasonably close conformity with the lines, grades, and cross sections shown in the plans and/or Contract Documents or established by the Engineer. The Work shall include such labor, materials, and equipment as shall be necessary to make connections with other drainage structures as shown in the plans and/or Contract Documents or as directed by the Engineer.
- B. This Work shall consist of removing and relaying pipe culverts and storm sewers as shown in the plans and/or Contract Documents, stipulated in the proposal, or directed by the Engineer. Removal and relaying shall be accomplished in accordance with this Section and in reasonably close conformity with the lines, grades, and cross sections shown in the plans and/or established by the Engineer. The Work shall include such labor and materials as shall be necessary to make connections with other drainage structures as shown in the plans and/or Contract Documents or as directed by the Engineer. This item shall not include pipes which are to be removed but not to be incorporated in the Work.
- C. This Work shall consist of furnishing and constructing or placing pipe drains not classified as pipe culverts or storm sewers, sanitary sewers, or underdrains. Pipe drains shall be constructed of the kinds and sizes of pipe as shown in the plans and/or Contract Documents, called for in the proposal, or established by the Engineer. Pipe drains shall be constructed above or below ground, at the locations and in reasonably close conformity with the lines and grades shown in the plans and/or Contract Documents or established by the Engineer, and in accordance with this Section. The Work shall include all incidentals, appurtenant materials, and Work necessary to perform and to complete the construction.
- D. This Work shall consist of constructing curb inlets, combination inlets, and headwalls (pipe end walls) at the locations shown in the plans and/or Contract Documents and in reasonably close conformity to the lines, grades, and design dimensions shown in the plans and/or Contract Documents or as directed by the Engineer and in accordance with the provisions in this Section. The Work shall include the furnishing and installation of such incidental appurtenances and connections to pipe and other structures as shall be required to complete the construction as shown in the plans and/or Contract Documents or as directed by the Engineer.
- E. This Work shall consist of the construction of underdrains composed of stone, gravel, slag, sand, or any one of these materials and perforated pipe, semi-circular

SECTION 02720-2
STORM SEWERS AND DRAIN SYSTEMS

drain pipe (with connections), or filter cloth. They shall be constructed in accordance with this Section, on prepared foundations at the locations shown in the plans and/or Contract Documents, and in reasonably close conformity to the lines and grades indicated thereon or as directed by the Engineer. The Work shall include all necessary excavation and backfill together with such Work and materials as shall be necessary to make connections with other drainage structures as shown in the plans and/or Contract Documents.

- F. Cement concrete ditch paving shall consist of the construction of paved ditches on a prepared subgrade. The pavement shall be constructed to the specified thickness and within reasonably close conformity to the lines, grades, and cross sections indicated in the plans and/or Contract Documents or as directed by the Engineer and in conformity with the requirements and provisions set out in this Section.

1.2 RELATED WORK SPECIFIED ELSEWHERE

Section 01340 - Shop Drawings, Product Data, and Samples
Section 01410 - Testing Laboratory Services
Section 01560 - Erosion and Siltation Control
Section 01710 - Cleanup and Restoration
Section 02200 - Earthwork
Section 02225 - Earthwork for Structures and Pipelines
Section 02270 - Rip-Rap
Section 02930 - Seeding and Sodding
Section 03300 - Cast-In-Place Concrete

1.3 APPLICABLE SPECIFICATIONS

"STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", Latest Revision, Tennessee Department of Transportation (TDOT)

"SUBDIVISION SPECIFICATIONS FOR STREETS AND ROADS", Latest Revision, Metropolitan Government of Nashville and Davidson County

1.4 APPLICABLE REFERENCES

"Stormwater Management Manual" (SMM), Latest Revision, Metropolitan Government of Nashville and Davidson County

"American Society for Testing and Materials" (ASTM), Latest Revision

"American Association of State Highway and Transportation Officials" (AASHTO), Latest Revision

"American Concrete Institute" (ACI), Latest Revision

"Standard Building Code Requirements for Reinforced Masonry", Latest Revision, American National Standards Institute (ANSI)

SECTION 02720-3
STORM SEWERS AND DRAIN SYSTEMS

"Standard for Cast Iron Pit Cast Pipe", Latest Revision, American National Standards Institute (ANSI)

1.5 QUALITY ASSURANCE

All precast concrete items shall be products of one (1) or more manufacturer having demonstrated competence in the design and production of precast concrete specialties of the types specified herein for a minimum of three (3) years.

PART 2 - MATERIALS

2.1 GENERAL REQUIREMENTS

Materials used in this construction shall meet the requirements in TDOT Standard Specifications Sections 607, 609, 610, 611, 703, and 710 in addition to the general requirements in this Section.

- A. Where slope drains are specified they shall be metal pipe meeting the requirements in paragraph 2.3 below or plastic pipe meeting the requirements in paragraph 2.11 below.
- B. Where pipe culverts (side drains) are specified they shall be in accordance with the following:
 - 1. Pipe culverts (side drains) fifteen (15) inches through thirty-six (36) inches shall be one (1) of the following:
 - a. Class III concrete pipe meeting the requirements in either paragraph 2.2 below or AASHTO M 86.
 - b. Metal pipe meeting the requirements in paragraph 2.3 below.
 - 2. Pipe culverts (side drains) larger than thirty-six (36) inches shall be either Class III concrete pipe meeting the requirements in paragraph 2.2 below or metal meeting the requirements in paragraph 2.3 below.
- C. Materials for special end connections to other pipes or structures required to complete the Work as indicated in the plans and/or Contract Documents or directed by the Engineer shall conform to the requirements in this Section and the applicable subsections in TDOT standard specifications unless otherwise specified.
- D. Reinforced concrete pipe shall be flat base, round, or oval as shown in the plans and/or Contract Documents.
- E. The sizes of pipe shall be identified by the nominal inside diameter. The pipe shall be of the sizes stipulated in this CONTRACT, shown in the plans and/or Contract Documents, or established by the Engineer.
- F. Steel and aluminum pipe are considered as optional for corrugated metal pipe, pipe

SECTION 02720-4
STORM SEWERS AND DRAIN SYSTEMS

arches, and underdrains. The Contractor may use either he prefers however in no case shall different metals or corrugations be mixed in a single line of pipe.

- G. When paved or coated corrugated metal pipe and pipe arches are specified either aluminum coating or bituminous coating shall be used. The aluminum or bituminous coated pipe shall conform to the requirements of AASHTO M 274 or AASHTO M 190 respectively.
- H. When precoated corrugated metal pipe and pipe arches are specified polymer coating shall be used in accordance with paragraph 2.21 below. Coupling bands and all hardware except nuts, bolts, and washers shall be of the same material and coating as the pipe.
- I. When corrugated metal pipe arches are specified as "size equivalent round" the dimensions shall be as shown in the plans and/or Contract Documents.
- J. Where pipe drains (bridge drains) are specified they shall be metal pipe meeting the requirements in paragraph 2.3 below or plastic pipe meeting the requirements in paragraph 2.11 below.
- K. Concrete shall be Class "A" and manufactured, placed, and cured in accordance with the applicable requirements in Section 03300 - Cast-In-Place Concrete.
- L. All bolts, anchors, frames, hangers, etc., for castings and plates shall be as approved by the Engineer.
- M. The Contractor may use either the curb inlet and combination inlet section detailed in the plans and/or Contract Documents or substitute comparable sections of cast in place concrete, precast reinforced concrete, or brick masonry as shall be applicable. When a substitution is proposed for a curb inlet or combination inlet section detailed in the plans and/or Contract Documents the Contractor shall construct the substitute section in accordance with the applicable standard drawing as approved by the Engineer. In the event the Department of Public Works and/or TDOT has no standard drawing of the substitute section the Contractor shall submit shop drawings of the revised section to the Engineer for approval prior to construction. After securing the necessary approval the Contractor shall furnish the Engineer a permanent four (4) mil mylar reproducible of the design.
- N. The paint system to be used shall be indicated in the plans and/or Contract Documents.
- O. All materials and devices used in making connections shall be approved by the Engineer before being used.
- P. Underdrains shall be of the kinds specified. Unless otherwise specified circular pipe for underdrains shall have a diameter of four (4) inches. Semi-circular pipe for underdrains shall have a diameter of four and five-eighths (4 5/8) inches. In the case of pipe the size shall be understood to mean the nominal inside diameter.
- Q. Pipe shall have a minimum cover of eighteen (18) inches above the top of the pipe.

2.2 REINFORCED CONCRETE PIPE

Reinforced concrete storm sewer pipe shall be Class III unless otherwise specified in the plans and/or Contract Documents and shall conform to ASTM C 76 for the specified diameters. Horizontal and vertical elliptical pipe shall conform to ASTM C 507 and arch pipe shall conform to ASTM C 506.

- A. Precast reinforced concrete end sections shall conform to the cited specifications to the extent to which they apply.
- B. Pipe shall have ends sealed inside and outside of pipe with mortar or bituminous type joints and shall be accepted on the basis of plant load bearing tests, material tests, and inspection of pipe for visual defects and imperfections.
- C. Joints shall be made with portland cement mortar, rubber gaskets, or other types of joints recommended by the pipe manufacturer and approved by the Engineer.

2.3 CORRUGATED METAL PIPE CULVERTS, PIPE ARCHES, AND UNDERDRAINS

Zinc coated (galvanized) corrugated iron or steel pipe, pipe arches, or underdrains and all special sections such as elbows and flared end sections shall be the same thickness and shall conform to AASHTO M 36. Shop formed elliptical pipe and shop strutted pipe shall be furnished only where shown in the plans and/or Contract Documents.

- A. Aluminum coated steel pipe shall conform to AASHTO M 274.
- B. Corrugated aluminum pipe, pipe arches, or underdrains and all special sections such as elbows and flared end sections shall be the same gauge and shall conform to the applicable requirements of AASHTO M 196.
- C. Galvanized corrugated structural plate for pipe, pipe arches, and arches shall conform to the requirements of AASHTO M 167.
- D. Mechanically galvanized zinc coating meeting ASTM B 695, Class 50 shall be acceptable as an alternate for hot dipped galvanizing AASHTO M 232 as applicable to hardware for fabrication of structural plate pipe, pipe arches, and arches.
- E. Corrugated aluminum alloy structural plate for pipe, pipe arches, and arches shall conform to the requirements of AASHTO M 219.
- F. When material supplied for any of the items mentioned above are to be bituminous coated the metal to be coated shall be free of grease, dirt, and other contaminants. Bituminous coating and paving shall conform to the requirements of AASHTO M 190. The coating shall be applied in accordance with recommended procedures and as directed by the Engineer.
- G. Joints for metal pipe shall be constructed using metal connecting bands of the

SECTION 02720-6
STORM SEWERS AND DRAIN SYSTEMS

same gauge as the main line pipe and shall be installed so as to prevent infiltration of water or backfill material.

- H. All corrugated metal pipe installed shall have a continuous helical lock seam or a continuous welded helical seam. Riveted seams, spot welded seams, or non-helical corrugated metal pipe are prohibited.

2.4 JOINT MORTAR

Pipe joint mortar shall consist of one (1) part portland cement and two (2) parts sand with water necessary to obtain the required consistency. Portland cement shall conform to the requirements in Section 03300 - Cast-In-Place Concrete, type I. The sand shall conform to the requirements in TDOT Standard Specifications Subsection 903.02. The water shall be approved for quality by the Engineer. Mortar shall be used within thirty (30) minutes after its preparation.

2.5 RUBBER GASKETS

Rubber gaskets shall conform to the requirements of ASTM C 443.

2.6 HEMP OR OAKUM GASKETS

Gaskets of hemp or oakum packing for joint filler shall be closely twisted and shall be of the size and type required for the pipe under construction. Gaskets shall be in one (1) piece of sufficient length to pass around the pipe and lap.

2.7 NON-REINFORCED CONCRETE PIPE

Non-reinforced concrete storm sewer pipe shall be Class III unless otherwise specified in the plans and/or Contract Documents and shall conform to ASTM C 14 for the specified diameters.

2.8 VITRIFIED CLAY PIPE

Vitrified clay pipe shall conform to AASHTO M 65 for the specified diameters and strength classes for circular unperforated pipe.

2.9 DUCTILE IRON OR CAST IRON PIPE

Ductile iron pipe shall conform to the requirements of ASTM A 716 for the specified diameters and strength classes. Unless otherwise specified either smooth, corrugated, or ribbed pipe shall be furnished. Pipe of diameter in excess of forty-eight (48) inches shall conform to ANSI standard for cast iron pit cast pipe for the specified diameter and strength class. Cast iron drain pipe shall conform to ASTM A 74. Unless otherwise specified ductile iron pressure pipe for water lines or sewer construction shall conform to the requirements of ASTM A 377 for the diameters and working pressures specified.

2.10 PAINT

SECTION 02720-7
STORM SEWERS AND DRAIN SYSTEMS

Paint shall meet the applicable requirements in TDOT Standard Specifications Section 910.

2.11 PLASTIC PIPE

Plastic pipe shall be corrugated polyethylene tubing and shall conform to the applicable requirements in this Section. The materials shall meet the requirements of ASTM F 667 and AASHTO M 294, type S smooth wall (large diameter). The pipe and fittings shall be free of foreign inclusions and visible defects. Corrugated polyethylene tubing shall be used in conformance to the applicable requirements in the "SUBDIVISION SPECIFICATIONS FOR STREETS AND ROADS", Latest Revision.

2.12 STRUCTURAL STEEL

All rolled plates, shapes, and bars for structural use shall conform to ASTM A 36 unless otherwise specified.

2.13 BUILDING BRICK

Brick when made from clay or shale shall conform to AASHTO M 114. When made of concrete they shall conform to ASTM C 55. The kind and grade shall be as specified.

2.14 SEWER BRICK

Brick shall conform to AASHTO M 191 and unless otherwise specified or indicated shall be grade SM size eight inch by three and five-eighths inch by two and one-quarter inch (8" x 3 5/8" x 2 1/4").

2.15 MASONRY MORTAR

Mortar shall be composed of one (1) part portland cement and two (2) parts sand. Hydrated lime in an amount not to exceed ten (10) percent may be added to portland cement. Water shall be added to the mixture in such quantity as to form a stiff paste.

A. The mortar shall be hand mixed or machine mixed. In the preparation of hand mixed mortar the sand, cement, and hydrated lime shall be thoroughly mixed together in a clean tight mortar box until the mixture is of uniform color after which water shall be added. Machine mixed mortar shall be prepared in an approved mixer and shall be mixed not less than one and one-half (1 1/2) minutes.

B. Mortar shall be used within thirty (30) minutes after mixing. Retempering of mortar shall not be permitted.

C. Cement and water used for mortar shall conform to the applicable requirements in Section 03300 - Cast-In-Place Concrete. Sand shall conform to the applicable requirements in TDOT Standard Specifications Subsection 903.02. Hydrated lime shall conform to the applicable requirements of ASTM C 206.

2.16 STEEL BAR REINFORCEMENT

SECTION 02720-8
STORM SEWERS AND DRAIN SYSTEMS

Steel bar reinforcement shall conform to the applicable requirements in Section 03300 - Cast-In-Place Concrete.

2.17 GRAY IRON CASTINGS

All castings shall be of the type specified and shall be within reasonably close conformity with the dimensions shown in the plans and/or Contract Documents. The castings shall conform to ASTM A 48 with the additional requirements herein and unless otherwise specified all castings shall be Class 30.

- A. At the option of the Engineer castings may be tested for strength by the transverse method in accordance with ASTM A 438 and in conformance with the requirements in TDOT Standard Specifications Subsection 908.07.
- B. When the transverse test method is used and the test bar fails to meet the load requirements as prescribed in TDOT Standard Specifications Subsection 908.07 the broken end of the bar may be machined by the manufacturer and tested for tensile strength. If this tension specimen conforms to the requirements of the specified class it shall be considered as having met irrespective of the transverse breaking load.
- C. Test bars for both transverse and tension testing shall be cast in accordance with ASTM A 48, table II, test bar B.
- D. All castings shall be cleaned of sand and scale by sand blasting or other effective methods so as to present a smooth, clean, and uniform surface and treated with two (2) coats of bituminous seal paint.
- E. Gray iron castings shall have the date of manufacture cast into each unit.
- F. Curb inlet and combination inlet castings shall have the lid and lid seat of the rim machined to form a true bearing. Frames and covers shall have ground bearing surfaces to prevent rocking and rattling under traffic as shown in the plans and/or Contract Documents.
- G. All castings shall weigh at least ninety-five (95) percent of the theoretical weight shown in the plans and/or Contract Documents.

2.18 MANHOLES AND METER AND VALVE BOXES

- A. Manholes and meter and valve boxes set in paved areas (street or sidewalks) within the right-of-way shall be gray iron casting or concrete. The castings shall conform to ASTM A 48 with the additional requirements herein and unless otherwise specified all castings shall be Class 30.
- B. All lids and frames shall be gray iron casting or concrete with gray iron casting lid

SECTION 02720-9
STORM SEWERS AND DRAIN SYSTEMS

and gray iron casting frame and shall conform to ASTM A 48 with the additional requirements herein and unless otherwise specified all castings shall be Class 30.

2.19 COMBINATION INLET STEPS

Combination inlet steps shall be a composite of a no. 4 grade 60 deformed steel bar encased in copolymer polypropylene plastic of the "press fit" design rubber or aluminum. The steps shall conform with the requirements in the "SUBDIVISION SPECIFICATIONS FOR STREETS AND ROADS", Latest Revision, and the plans and/or Contract Documents.

2.20 PRECAST CURB INLETS AND COMBINATION INLETS

Precast curb inlets and combination inlets shall conform to ASTM C 478.

2.21 PERFORATED CONCRETE PIPE

Perforated concrete pipe shall conform to AASHTO M 175 or to ASTM C 444 for the specified diameters and unless otherwise specified it shall be standard strength.

2.22 PRECOATED GALVANIZED STEEL CULVERTS AND UNDERDRAINS

Precoated galvanized steel pipe shall conform to AASHTO M 245, grade 10/10 unless otherwise specified.

2.23 AGGREGATE FOR UNDERDRAINS

Aggregate for underdrains shall be crushed stone, crushed slag, or washed gravel meeting the quality requirements of ASTM D 692 and the grading requirements for size 6, 7, 8, 57, or 78 in TDOT Standard Specifications Subsection 903.22.

2.24 FILTER CLOTH

Filter cloth material shall meet the requirements in Section 02270 - Rip-Rap.

2.25 CONCRETE HEADWALLS

Cast in place headwalls shall be reinforced concrete and shall be in conformance with the requirements in the "SUBDIVISION SPECIFICATIONS FOR STREETS AND ROADS", Latest Revision, and the plans and/or Contract Documents. Concrete shall be Class "A" as specified in Section 03300 - Cast-In-Place Concrete.

2.26 PRECAST CONCRETE

Precast concrete structures produced by the dri-cast method shall be in conformance with ASTM C 478. Precast concrete bases, riser sections, cones, and headwalls shall conform to the requirements in the "SUBDIVISION SPECIFICATIONS FOR STREETS AND ROADS", Latest Revision, and the plans and/or Contract Documents. The applicable provisions in Section 03300 - Cast-In-Place Concrete shall apply to the production of curb

SECTION 02720-10
STORM SEWERS AND DRAIN SYSTEMS

inlets, combination inlets, and headwalls except that the design mix (f'_c) shall be four thousand (4000) pounds per square inch. Reinforcing steel for precast boxes, curb inlets, and combination inlets shall conform to the requirements in Section 03300 - Cast-In-Place Concrete.

2.27 CONCRETE CAPPING

Concrete for concrete capping shall be Class "A" in conformance with Section 03300 - Cast-In-Place Concrete.

2.28 CEMENT CONCRETE DITCH PAVING

Concrete for cement concrete ditch paving shall be Class "A" concrete meeting all the requirements prescribed in Section 03300 - Cast-In-Place Concrete.

PART 3 - EQUIPMENT

All equipment necessary for the satisfactory performance of this Work shall be on hand and approved by the Engineer prior to construction. The equipment provided by the Contractor shall include hoisting equipment capable of handling and placing the pipe in final position without damage to the pipe. Mechanical tamps shall also be included.

- A. Forms shall be either wood or metal meeting the requirements in Section 02522 - Concrete Walks, Driveways, and Ramps. A strike off template of the form and shape of the ditch section shall be used to shape the top surface of the paved ditch.
- B. Compaction of subgrade shall be accomplished by any type of tamping or rolling equipment that shall produce the required results.
- C. Mixers shall meet the requirements in Section 03300 - Cast-In-Place Concrete. Mechanical ditch paving machines shall be used when approved by the Engineer.
- D. Finishing equipment shall include satisfactory floats, edgers, spades, and tamps.

PART 4 - EXECUTION

4.1 GENERAL

Maintain a minimum ten (10) feet horizontal distance between storm sewer and water main.

- A. Clearing and grubbing, removal of structures and obstructions, excavation and undercutting, and embankment construction shall be performed in accordance with the provisions in Section 02100 - Clearing and Grubbing and Section 02200 - Earthwork.
- B. Temporarily support, protect, and maintain all underground and surface structures

SECTION 02720-11
STORM SEWERS AND DRAIN SYSTEMS

and utilities encountered in the process of the Work. Where the grade or alignment of the pipe is obstructed by existing utilities such as conduit, pipe, or other obstruction the Contractor shall immediately notify the Engineer and utility company concerning conflict.

- C. Bedding and backfill material for pipe culverts, curb inlets, combination inlets, headwalls, and any other storm and/or drainage structures shall conform to the requirements in Section 02225 - Earthwork for Structures and Pipelines. When no bedding is specified the requirements for Class "C" bedding shall apply
- D. When excavation is made across private property the topsoil and/or sod disturbed by the excavation operations shall be salvaged, maintained and/or stored, and replaced in its original position in conformance to Section 01560 - Erosion and Siltation Control, Section 01710 - Cleanup and Restoration, Section 02200 - Earthwork, and Section 02930 - Seeding and Sodding unless otherwise specified.
- E. Install piping in such a manner as to obtain sufficient flexibility and to prevent excessive stresses in materials and excessive bending movements at joints. Conduct Work in strict conformance with the procedures established by the manufacturers of the various types of pipe.
- F. In no case shall the type of pipe change between drainage structures.

4.2 STRUCTURE EXCAVATION & FOUNDATION PREPARATION FOR PIPE CULVERTS

This Work shall be performed in accordance with the provisions in Section 02225 - Earthwork for Structures and Pipelines.

- A. The bedding for pipe culverts shall conform to the requirements in Section 02225 - Earthwork for Structures and Pipelines for Class "A", Class "B", or for Class "C". When no bedding class is specified the requirements for Class "C" bedding shall apply. Bedding for pipe culverts and storm sewer cross drains shall have a longitudinal camber of the magnitude specified by the Engineer.
- B. When excavation is made for installing storm sewers across private property the topsoil and sod disturbed by the excavation operations shall be salvaged and replaced in its original position unless otherwise specified. All costs of restoring the area to its original conditions shall conform to the requirements in Section 01710 - Cleanup and Restoration.

4.3 LAYING PIPE CULVERTS AND STORM SEWERS

Lay pipe to a true uniform line and grade from elevations indicated in the plans and/or Contract Documents with continuous bearing of barrel on cradle or bedding material.

- A. Pipe culverts and storm sewers shall be laid beginning at the downstream end of the pipe line. The lower segment of the pipe shall be in contact with the shaped bedding throughout its full length. Bell or groove ends of rigid pipe and outside circumferential laps of flexible pipe shall be placed facing upstream and the spigot

SECTION 02720-12
STORM SEWERS AND DRAIN SYSTEMS

ends of rigid pipe shall be placed facing downstream. Flexible pipe shall be placed with longitudinal laps or seams at the sides. Lay each section of pipe in such a manner as to form a close concentric joint with the adjoining section and to prevent any sudden offsets in the flow line.

- B. Paved invert pipe shall be laid so that the longitudinal center line of the paved segment coincides with the flow line. Vertical, oval, and elliptically reinforced pipes shall be placed with the major axis of the reinforcement within five (5) degrees of a vertical plane through the longitudinal axis of the pipe.
- C. All areas of flexible pipe where the spelter or bituminous coating has been damaged shall be painted with two (2) coats of hot asphaltic paint or otherwise repaired in a satisfactory manner.
- D. Insure that pipe is well bedded on a solid foundation. Correct any defects due to settlement. Excavate bell holes sufficiently large to insure proper jointing and pipe support. Exercise precautions to include the furnishing and placing of bedding to prevent any pipe from resting directly on rock.
- E. Plug or regrout lift holes left in the pipe prior to backfilling operations.
- F. As the Work progresses clear the interior of the pipe of all dirt and superfluous materials of every description.
- G. Keep trenches and excavations free of water during construction and until final inspection. Do not lay pipe in water or in a frozen bedding condition. Prevent flotation and relay pipe that has floated.

4.4 JOINING PIPE

Rigid pipe shall be of bell and spigot or tongue and groove design unless one (1) type is specified. The method of joining pipe sections shall be such that the ends are fully entered and the inner surfaces are reasonably flush and even.

- A. Joints for rigid pipe shall be made with portland cement mortar, rubber gaskets, or other types of joints recommended by the pipe manufacturer and approved by the Engineer shall be permitted.
- B. For mortar joints the pipe ends shall be thoroughly cleaned and wetted with water before the joint is made. Stiff mortar shall then be placed in the lower half of the bell or groove of the pipe section already laid and on the upper half of the spigot or tongue of the section to be laid. The two (2) pipe sections shall then be tightly joined with their inner surfaces flush and even. The inside of the joint shall then be finished smooth and any surplus material removed from the pipe. The completed mortar joints shall be protected against rapid drying by suitable covering material.
- C. Rubber ring gaskets shall then be installed so as to form a flexible watertight seal.

SECTION 02720-13
STORM SEWERS AND DRAIN SYSTEMS

When other type joints are permitted they shall be installed or constructed in accordance with the recommendations of the manufacturer.

- D. Pipe shall be inspected before any backfill is placed. Any pipe found to be out of alignment, unduly settled, or damaged shall be taken up and relaid or replaced.
- E. Flexible pipe shall be firmly joined by approved coupling bands. For flexible pipe joints the connecting band shall be of the same material and thickness as the main pipeline. The band shall be installed as to the manufacturer's specifications. The band when installed shall prevent the infiltration of water or backfill material.

4.5 FIELD STRUTTING

When strutting or vertical elongation is required it shall be performed in accordance with the details shown in the plans and/or Contract Documents. Ties and struts shall be left in place until the embankment is completed unless otherwise specified.

4.6 BACKFILL

After the pipe is installed the trench shall be backfilled in accordance with the provisions in Section 02225 - Earthwork for Structures and Pipelines.

4.7 DISPOSAL OF EXCESS OR UNSUITABLE MATERIAL

Excess or unsuitable material shall be disposed of according to the requirements in Section 02200 - Earthwork or as directed by the Engineer. Excavated material shall be utilized as prescribed in Section 02225 - Earthwork for Structures and Pipelines.

4.8 REMOVAL OF PIPE

The pipe shall be carefully removed and so handled as not to damage or cause the pipe to be unfit for relaying. The Contractor shall be required to replace at his own expense pipe of the kind and quality damaged by his negligence or inefficient handling.

4.9 PREPARATION OF PIPE FOR RELAYING

The pipe shall be thoroughly cleaned inside and outside of dirt, debris, mortar, and other foreign matter.

- A. The Contractor shall perform any necessary cutting of salvaged pipe in order to obtain required lengths and shall furnish coupling bands, gaskets, and other jointing materials necessary to make all connections.
- B. All pipe to be relaid shall be sound and in good condition. Any broken or deteriorated section of pipe or connection shall be rejected for use.

4.10 RELAYING OR PLACING PIPE AND BACKFILL FOR PIPE REMOVED AND RELAI

SECTION 02720-14
STORM SEWERS AND DRAIN SYSTEMS

The requirements for relaying or placing pipe of the various types specified shall be as prescribed in paragraphs 4.3 through 4.5 above. Backfilling shall be performed in accordance with the provisions in Section 02225 - Earthwork for Structures and Pipelines.

4.11 STRUCTURE EXCAVATION, FOUNDATION PREPARATION, AND BEDDING FOR PIPE DRAINS

Structure excavation and foundation preparation shall be performed in accordance with the provisions in Section 02225 - Earthwork for Structures and Pipelines. Bedding for pipe drains unless otherwise stipulated shall be Class "C" bedding as prescribed in Section 02225 - Earthwork for Structures and Pipelines. Backfilling of trenches shall be performed according to the requirements in Section 02225 - Earthwork for Structures and Pipelines.

4.12 SUSPENDING PIPE DRAINS

Where pipe drains are to be placed above the ground surface they shall be suspended as shown in the plans and/or Contract Documents or as directed by the Engineer. They shall be securely and rigidly held in place.

4.13 PLACING AND JOINTING PIPE DRAINS

- A. Pipe for drains shall be placed in conformity with all applicable requirements in paragraph 4.3 above. Jointing of concrete, clay, and corrugated metal drain pipe shall be performed in accordance with the provisions in paragraph 4.4 above.
- B. Jointing of cast iron pipe shall be performed in accordance with the recommendations of the manufacturer using the fittings and methods recommended by the manufacturer.

4.14 PAINTING PIPE DRAINS

Concrete, vitrified clay, and corrugated metal pipe drains shall not be painted even if these are to be exposed unless otherwise shown in the plans and/or Contract Documents.

- A. Cast iron drains that are to be exposed and which do not have a bituminous coating shall be painted in accordance with the applicable requirements in TDOT Standard Specifications Section 603. Cast iron pipe drains which have a bituminous coating shall be cleaned and treated with two (2) coats of bituminous material of such kind and grade that the finished coating shall be tough when cold and not tacky during hot weather.
- B. Painting shall include all hangers, braces, and other appurtenances.

4.15 CURB INLET AND COMBINATION INLET CONSTRUCTION

All concrete construction shall be accomplished in accordance with the requirements in Section 03300 - Cast-In-Place Concrete. All brick construction shall be performed in accordance with the provisions in TDOT Standard Specifications Section 613.

- A. Construct curb inlets and combination inlets in accordance with this Section and

SECTION 02720-15
STORM SEWERS AND DRAIN SYSTEMS

the plans and/or Contract Documents. Unless modifications to the existing system are being performed provide monolithic base of precast construction.

- B. Construct appropriate flow channels in the bottom of curb inlets and combination inlets conforming to the requirements in "SUBDIVISION SPECIFICATIONS FOR STREETS AND ROADS", Latest Revision, and as shown in the plans and/or Contract Documents. Flow channel construction shall provide a smooth transition between adjacent sections.
- C. Cast in place concrete for curb inlets and combination inlets shall be placed monolithically. Concrete shall be allowed to drop freely up to five (5) feet in height. Where greater drops are required a tremie or other device shall be used.
- D. Joints for brickwork shall be completely filled and shall be smooth and free from surplus mortar on the inside of the structure. Brick shall be laid radially with every sixth (6th) course laid as a stretcher course. Brick curb inlets and combination inlets shall be pargeted over the entire inside surface of the walls.
- E. Inlet and outlet pipe shall extend through the walls of curb inlets and combination inlets for a sufficient distance beyond the outside surface to allow for connections but shall be cut off flush with the wall on the inside surface unless otherwise directed. Tightly mortar in pipe with quick setting non-shrink grout.
- F. The concrete or brick mortar shall be so constructed around the pipes as to prevent leakage and form a neat connection.
- G. Firmly anchor steps where required to wall according to manufacturer's recommendations. Steps shall project not less than five (5) inches from the inner surface of the wall. Steps set in vertical alignment shall be not less than twelve (12) inches wide.
- H. Bedding and backfill material shall be placed in conformance to the provisions in Section 02225 - Earthwork for Structures and Pipelines.
- I. No backfill or traffic shall be allowed on precast sections until seven (7) calendar days have elapsed since the representative test specimens have attained the required compressive strength.

4.16 INVERTS

Inverts shall be of Class "A" concrete and shall conform to the shapes indicated in the plans and/or Contract Documents. The inverts shall be so constructed as to cause the least possible resistance to flow. The shape of the inverts shall conform uniformly to inlet and outlet pipes. A smooth and uniform finish shall be required.

4.17 CASTINGS AND FITTINGS

SECTION 02720-16
STORM SEWERS AND DRAIN SYSTEMS

Castings and fittings shall be handled in a manner that shall prevent damage. All damaged castings and fittings shall be rejected.

- A. All Castings and fittings shall be placed in the positions indicated in the plans and/or Contract Documents or as directed by the Engineer and shall be set true to line and grade.
- B. If castings are to be set in concrete or cement mortar all anchors or bolts shall be in place and position before the concrete or mortar is placed. The casting shall not be disturbed until the mortar or concrete has set.
- C. When castings are to be placed upon previously constructed masonry the bearing surface of masonry shall be brought true to line and grade and present an even bearing surface in order that the entire face or back of the casting shall come in contact with the masonry. Castings shall be set in mortar beds or anchored to the masonry as indicated in the plans and/or Contract Documents or as directed by the Engineer.
- D. All castings shall be set firm and snug and shall not rattle. Adjust the frame and castings to finished grade by brick or concrete adjusting ring construction. Unless otherwise specified gray iron castings shall be cleaned and treated with two (2) coats of bituminous paint.

4.18 MANHOLES AND METER AND VALVE BOXES

All manhole and meter and valve box lids and frames shall be set firm and snug and shall not rattle. Adjust the frame and castings to finished grade by brick or concrete adjusting ring construction. Unless otherwise specified gray iron casting lids and frames shall be cleaned and treated with two (2) coats of bituminous paint.

4.19 AGGREGATE UNDERDRAINS

- A. The trenches to receive the aggregate shall be excavated at the locations and to the dimensions shown in the plans and/or Contract Documents or as directed by the Engineer. The trench shall be deep enough to intercept the water bearing strata and shall be finished smooth and uniform.
- B. Aggregate meeting the requirements in paragraph 2.22 above shall be placed in the trench in six (6) inch layers to the depth shown in the plans and/or Contract Documents. Each layer shall be well tamped with an approved tamp.

4.20 AGGREGATE UNDERDRAINS (WITH PIPE)

The trench to receive the pipe shall be excavated at the locations shown in the plans and/or Contract Documents or as directed by the Engineer. In case the dimensions are not shown the width of the trench shall be not less than the outside diameter of the pipe plus twelve (12) inches. The trench shall be deep enough to intercept the water bearing strata and to allow installation of the pipe and cover material. Unless otherwise shown in

SECTION 02720-17
STORM SEWERS AND DRAIN SYSTEMS

the plans and/or Contract Documents a two (2) inch layer of aggregate shall be spread on the bottom of the trench, compacted, and brought to uniform grade.

- A. The pipe shall be embedded firmly in the layer of aggregate. Perforated pipe shall be laid with the flow sector and perforations at the bottom.
- B. If an underdrain is extended through a dry fill or other section where perforated pipe is undesirable it shall be constructed with the pipe specified and all joints shall be mortar joints, approved manufactured joints, or made with connecting bands.
- C. After the pipe has been laid and approved the backfilling shall be carefully done so that the pipe shall not become displaced. The backfilling around the pipe shall be with the aggregate specified. The aggregate around and over the pipe shall be placed in six (6) inch layers and each layer thoroughly tamped with a vibratory compactor.
- D. Lateral and other connections shall be made where indicated in the plans and/or Contract Documents or as directed by the Engineer.

4.21 FILTER CLOTH AND AGGREGATE UNDERDRAIN (WITH AND WITHOUT PIPE)

Trenches shall be excavated at the location indicated in the plans and/or Contract Documents and to the detailed depth and width. The sides and bottom of the trenches shall be prepared to a relatively smooth condition free of sharp objects, obstructions, depressions, and debris which might damage the filter cloth during installation.

- A. The material removed from the trench shall be removed from the area and disposed of outside of the right-of-way at locations obtained by the Contractor unless the Engineer authorizes its disposition within designated locations.
- B. Filter cloth shall be placed in accordance with the provisions in Section 02270 - Rip-Rap.
- C. The aggregate shall be placed in six (6) inch layers and each layer compacted by the use of vibratory compactor to the satisfaction of the Engineer before making the filter cloth closure at the top of the trench. The exposed end of the outfall pipe shall be protected by an endwall matching the existing slope.
- D. The end of the outfall pipe shall be beveled to fit the slope of the endwall. Should the outlet end of the pipe or the endwall fall within the limits of ditch paving that portion of the ditch paving within the endwall limits necessary to provide a connection with the new endwall shall be removed to neat lines and the endwall made to blend with the ditch paving.

4.22 CEMENT CONCRETE DITCH PAVING

Concrete lined ditches shall be constructed as detailed in the plans and/or Contract Documents as to cross section, thickness of concrete, and grade.

SECTION 02720-18
STORM SEWERS AND DRAIN SYSTEMS

- A. Subgrade preparation for ditch paving shall be made to the required depth and to a width that shall permit the installation and bracing of forms. The subgrade shall be shaped and compacted to a firm even surface in reasonably close conformity with the grade and section shown in the plans and/or Contract Documents or as directed by the Engineer. All soft and yielding material shall be removed and replaced with acceptable material which shall then be compacted as directed.
- B. Joints shall be formed at the intervals and locations shown in the plans and/or Contract Documents. Joint filler for expansion joints shall be cut to the full cross section of the ditch pavement.
- C. Limitations on the mixing of concrete shall be as prescribed in Section 03300 - Cast-In-Place Concrete.
- D. Concrete shall be mixed in accordance with the requirements in Section 03300 - Cast-In-Place Concrete.
- E. Immediately before placing the concrete the subgrade shall be thoroughly wetted and the forms given a coating of light oil. The forms shall be thoroughly cleaned and oiled each time before using.
- F. The concrete shall be placed immediately after mixing. The edges shall be spaded and the concrete thoroughly consolidated after which the surface shall be finished smooth and even by means of a wooden float.
- G. The edges of the paved ditch shall be rounded to a radius of one-half (1/2) inch and edges along expansion and contraction joints shall be finished with an edging tool with a radius of not over one-quarter (1/4) inch and then all edging tool marks removed with a float and brush.
- H. Immediately after finishing the concrete it shall be cured as specified in TDOT Standard Specifications Subsection 501.18.
- I. The Contractor shall protect the ditch paving until final acceptance of the project. Any concrete that is damaged prior to acceptance shall be repaired by removing and reconstructing the damaged sections. Such reconstruction shall be at the Contractor's expense.
- J. Immediately after the concrete has set sufficiently and the forms have been removed the spaces on each side of the ditch paving shall be filled with suitable material and thoroughly compacted or when sod is specified it shall be laid in accordance with the provisions in Section 02930 - Seeding and Sodding.

4.23 CAPPING EXISTING DRAINAGE STRUCTURES AND/OR PIPE

At all locations shown in the plans and/or Contract Documents or where directed by the Engineer the Contractor shall cap existing drainage structures and/or cut and cap existing pipe. This item shall include excavation, cutting existing pipe, furnishing and installing an approved cap and necessary concrete blocking, backfill, and all labor and materials

SECTION 02720-19
STORM SEWERS AND DRAIN SYSTEMS

required for a complete installation.

4.24 ADJUSTING AND/OR REWORKING EXISTING DRAINAGE STRUCTURES

At all locations shown in the plans and/or Contract Documents or where directed by the Engineer the Contractor shall adjust and/or rework existing drainage structures. This item shall include excavation; adjusting and/or cutting existing pipe; adjusting existing frame, grate, and/or covering; adjusting and/or reworking drainage structure depth, width, and elevation as shown in the plans and/or Contract Documents; backfill; and all labor and materials required for a complete installation.

4.25 FINAL CLEANUP

Final cleanup shall be performed as prescribed in Section 01710 - Cleanup and Restoration.

- A. All excess or unsuitable material shall be disposed of as directed by the Engineer.
- B. All material becoming the property of the Metropolitan Government shall be stored as directed by the Engineer.

PART 5 - MEASUREMENT AND PAYMENT

5.1 MEASUREMENT

- A. Pipe culverts and storm sewers of the different types classes, shapes, and sizes specified shall be measured for payment at a Contract Unit Bid Price per linear foot along the centerline of the installed pipe for each type, class, shape, and size constructed complete in place which shall be full compensation for excavation (unless otherwise specified), bedding and backfill material, labor and materials used in making joints and connections to other structures, strutting when required, and completing all incidentals necessary to complete the item. When the plans and/or Contract Documents provide for direct payment for structure excavation measurement and payment shall be in accordance with Section 02225 - Earthwork for Structures and Pipelines for culvert excavation (unclassified).
- B. Pipe culverts (side drains) and slope drains shall be measured for payment at a Contract Unit Bid Price per linear foot along the centerline of installed pipe for each size constructed complete in place which shall be full compensation for labor and material for making joints, excavation, bedding and backfill material, and all incidentals necessary to complete the Work. No measurements for payment shall be made in excess of the ordered length of the pipe. Pipe culverts (side drains) shall be ordered in increments of two (2) feet.
- C. Curb inlets and combination inlets shall be measured for payment at a Contract Unit Bid Price per each for the various types, diameters, and ranges of depth complete in place as indicated in the plans and/or Contract Documents which shall be full compensation for performing all operations incidental thereto such as excavation, bedding, and backfill and for furnishing all materials, equipment, tools,

SECTION 02720-20
STORM SEWERS AND DRAIN SYSTEMS

labor, and incidentals necessary to complete the item. Steps, type of structure (brick or precast), casting and frames, mortar, and any other incidental items necessary for complete installation shall not be paid for directly but the cost thereof shall be included in the Contract Unit Bid Price of the curb inlet or combination inlet. Measurement for payment shall be based upon vertical depth from invert of curb inlet or combination inlet to top of structure. Standard depth of structure shall be from zero (0) feet to six (6) feet. Additional depth shall be paid for on a one (1) foot vertical increment. When the plans provide for direct payment for structure excavation measurement and payment shall be in accordance with Section 02225 - Earthwork for Structures and Pipelines for structure excavation.

- D. Concrete headwalls shall be field measured to calculate the amount of in place concrete for each headwall and paid at a Contract Unit Bid Price per cubic yard complete in place which shall be full compensation for excavation, bedding and backfill material, and all Work and incidental items necessary to complete the item.
- E. Steel bar reinforcement shall be measured for payment at a Contract Unit Bid Price per pound complete in place.
- F. If precast headwalls are approved by the Engineer payment shall be at a Contract Unit Bid Price per each complete in place which shall be full compensation for excavation, bedding and backfill material, steel reinforcement, and all Work and incidental items necessary for complete installation.
- G. Concrete lined ditch shall be measured for payment at a Contract Unit Bid Price per cubic yard complete in place which shall be full compensation for excavation, preparing the subgrade, backfill, and expansion joint materials unless otherwise indicated in the plans and/or Contract Documents. The volume per linear foot of length shall be obtain from the dimensions shown in the plans and/or Contract Documents. Linear measurements shall be surface measurements along the center line of the concrete lined ditch.
- H. Cutting and capping existing drainage structure and/or pipe shall be measured for payment at a Contract Unit Bid Price per each which shall be full compensation for the actual number of existing drainage structures capped or existing pipe cut and/or capped complete in place including frames, grates, concrete, excavation, backfill, and all Work and incidental items necessary for complete installation. No separate payment shall be made for excavation, backfill, and rodding or blocking.
- I. Adjusting and/or reworking existing drainage structures or existing drainage structure covers, grates, and frames shall be measured for payment at a Contract Unit Bid Price per each which shall be full compensation for the actual number of existing drainage structures adjusted and/or reworked or the actual number of existing drainage structure covers, grates, and frames adjusted complete in place including concrete, excavation, and backfill. No separate payment shall be made for excavation, backfill, labor, or materials.

SECTION 02720-21
STORM SEWERS AND DRAIN SYSTEMS

- J. Pipe removed and relaid of the various kinds shall be measured for payment at a Contract Unit Bid Price per linear foot along the center line of the pipe and from end to end of the pipe for each type of pipe complete in place including incidentals after relaying which shall be full compensation for structure excavation, bedding, and backfill. When the plans and/or Contract Documents provide for direct payment of structure excavation measurement and payment shall be in accordance with Section 02225 - Earthwork for Structures and Pipelines for culvert excavation (unclassified) and the volume occupied by the pipe shall be included in the measurement for payment.
- K. Pipe drains of the various kinds and sizes shall be measured for payment at a Contract Unit Bid Price per linear foot complete in place along the centerline of the pipe and from end to end of the pipe including incidentals which shall be full compensation for excavation, foundation preparation, backfilling, hangers, braces, supports, and etc., for suspending or hanging pipe drains. The kinds and sizes determined by the diameter of each pipe shall be measured separately.
- L. Underdrains of the various kinds and sizes shall be measured for payment at a Contract Unit Bid Price per linear foot along the centerline of the underdrain and from end to end of the underdrain for the individual kinds and sizes complete in place which shall be full compensation for all excavation, backfill, connections, specials, and all incidentals necessary to complete the construction.
- M. Filter cloth underdrain shall be measured for payment at a Contract Unit Bid Price per linear foot along the center of each line complete in place for each type of underdrain (with or without pipe) actually installed which shall be full compensation for this item including the furnishing and installation of the four (4) inch perforated underdrain pipe and pipe elbow when an underdrain outlet is required.
- N. Lateral underdrains shall be measured for payment at a Contract Unit Bid Price per linear foot complete in place with measurements made along the center of the outfall pipe from the center of the filter cloth underdrain to the centroid of the beveled outfall end which shall be full compensation for excavation of the trench, outlet pipe and the installation of the materials, the backfill of the trench and compaction thereof, the disposal of excess materials, returning the shoulder and slope to the previously existing normal condition, and for all tools, equipment, labor, and incidentals necessary to complete this item of Work.
- O. Lateral endwalls shall be measured for payment at a Contract Unit Bid Price per each complete in place for the type and size as indicated in the plans and/or Contract Documents which shall be full compensation for excavation, concrete, backfill, compaction, disposal of excess material, and for all tools, equipment, labor, and incidentals necessary to complete this item of Work.
- P. Six (6) inch perforated pipe with vertical drain system shall be measured for payment at a Contract Unit Bid Price per linear foot along the centerline of the underdrain and from end to end of the underdrain complete in place which shall be full compensation for the pipe and pipe elbows, the installation of materials including the polyethylene sheeting, and for all tools, equipment, labor, and

SECTION 02720-22
STORM SEWERS AND DRAIN SYSTEMS

incidentals necessary to complete this item of Work.

- Q. Concrete pipe culverts and concrete storm sewers of the different classes, shapes, and sizes specified shall be measured by the linear foot of pipe installed and accepted. The quantity of pipe cut off not to exceed two (2) feet shall be paid for at the Contract Unit Bid Price for pipe in place.
- R. Corrugated metal pipe and corrugated metal structural plate pipe shall be measured by the linear foot of pipe installed and accepted. Measurements shall be made as follows:
1. Metal pipe and metal structural plate pipe with square and vertical ends or with skewed and vertical ends shall be measured in place end to end of the metal on the center line of the structure.
 2. Metal pipe and metal structural plate pipe with square ends beveled and with ends skewed and beveled except arch pipe shall be measured in place by averaging the end to end distances at the top and bottom of the pipe measured parallel to the center line of the structure.
 3. Metal arch pipe and metal structural plate arch pipe with square ends beveled and with ends skewed and beveled shall be measured in place end to end of the metal along the invert of the structure.
- S. Slope drains shall be measured in the same manner as specified for corrugated metal pipe in subparagraph R above.
- T. Unless otherwise indicated in the plans and/or Contract Documents no measurement of structure excavation shall be made and the cost involved shall be included in the Contract Unit Bid Price for other items of construction. When the plans and/or Contract Documents provide for direct payment of structure excavation measurement and payment shall be made in accordance with Section 02225 - Earthwork for Structures and Pipelines.
- U. No payment shall be made for labor and materials used in making branch connections. The length of pipe in the branch connection shall be measured and included in the quantity of pipe installed in the branch line.
- V. Strutting of corrugated metal pipe and corrugated metal structural plate pipe shall not be paid for separately but the costs thereof shall be included in the Contract Unit Bid Price per linear foot of pipe.
- W. Pipe removed but not relaid shall not be measured for payment. Excavation including the volume occupied by the pipe made for the removal of pipe under this Section shall be measured for payment in accordance with the provisions set out in Section 02225 - Earthwork for Structures and Pipelines for culvert excavation (unclassified).
- X. Payment for pipe used to replace pipe which has been rejected except pipe to be

SECTION 02720-23
STORM SEWERS AND DRAIN SYSTEMS

replaced at the Contractor's expense shall be made under the type and kind of pipe being replaced.

- Y. Pipe used in weep holes and drainage openings six (6) inches in diameter or less through concrete abutments, decks, slabs, floors, walls, etc., shall not be measured for payment directly or under the pay items in this Section but are treated under Section 03300 - Cast-In-Place Concrete.
- Z. When the bid schedule contains items for various components of curb inlets, combination inlets, and endwalls measurement shall be made in accordance with the following:
 - 1. Brick masonry shall be measured by the mega (one thousand (1000)) brick complete in place in accordance with the provisions set out in TDOT Standard Specifications Section 613.
 - 2. Portland cement concrete and steel bar reinforcement shall be measured in accordance with the provisions out in Section 03300 - Cast-In-Place Concrete.
 - 3. Structural steel and gray iron castings shall be measured by the computed weight based on the dimensions shown in the plans and/or Contract Documents and deducting for open holes. To this weight shall be added five (5) percent allowance for fillets and overruns. Scale weights may be substituted for computed weights of small complex parts for which accurate computations would be difficult.
 - 4. Steps shall not be paid for directly but the cost thereof shall be included in the Contract Unit Bid Price of the pay items of other materials with which the structure is constructed.
 - 5. Unless otherwise indicated in the plans and/or Contract Documents no measurement of structure excavation shall be made and the costs involved shall be included in the Contract Unit Bid Price for the structure being constructed. When the plans and/or Contract Documents provide for direct payment for structure excavation measurement and payment shall be in accordance with Section 02225 - Earthwork for Structures and Pipelines.
- AA. Testing shall be paid according to the requirements in Section 01410 - Testing Laboratory Services.
- AB. Temporary erosion control devices shall be measured for payment according to the requirements in Section 01560 - Erosion and Siltation Control.
- AC. Cleanup and restoration of areas and facilities disturbed by construction operations shall be considered and integral part of Work and therefor shall not be measured for payment.
- AD. Rip-rap used for inlet and/or outlet protection shall be measured for payment

SECTION 02720-24
STORM SEWERS AND DRAIN SYSTEMS

according to the requirements in Section 02270 - Rip-Rap.

5.2 PAYMENT SUMMARY

<u>NO.</u>	<u>ITEM</u>	<u>UNIT OF MEASURE</u>
2720.1	Reinforced Concrete Pipe (size)	L.F.
2720.2	Corrugated Metal Pipe (size)	L.F.
2720.3	Corrugated Metal Pipe Arch (size)	L.F.
2720.4	Reinforced Concrete Pipe Arch (size)	L.F.
2720.5	Ductile Iron Pipe (size)	L.F.
2720.6	Polyvinyl Chloride Pipe (size)	L.F.
2720.7	Corrugated Polyethethylene Pipe (with smooth interior)	L.F.
2720.8	Single Inlet with (type) Frame and Casting	Each
2720.9	Double Inlet with (type) Frame and Casting	Each
2720.10	Triple Inlet with (type) Frame and Casting	Each
2720.11	Combination Inlet with (type) Frame and Casting	Each
2720.12	Extra Depth	V.F.
2720.13	Class "A" Concrete (pipe headwall)	C.Y.
2720.14	Steel Bar Reinforcing (pipe headwall)	Lb.
2720.15	Class "A" Concrete (concrete lined ditch)	C.Y.
2720.16	Precast Concrete Headwall (pipe size)	Each
2720.17	Capping Existing Drainage Structure (type)	Each
2720.18	Cutting and/or Capping Existing Pipe (size)	Each
2720.19	Adjusting Existing Drainage Structure (type)	Each
2720.20	Reworking Existing Drainage Structure (type)	Each
2720.21	Pipe Culvert (side drain)	L.F.
<u>NO.</u>	<u>ITEM</u>	<u>UNIT OF MEASURE</u>

SECTION 02720-25
STORM SEWERS AND DRAIN SYSTEMS

2720.22	Slope Drain	L.F.
2720.23	Pipe Removed and Relaid (type)	L.F.
2720.24	Pipe Drain	L.F.
2720.25	Underdrain (type)	L.F.
2720.26	Filter Cloth Underdrain (with or without pipe)	L.F.
2720.27	Lateral Underdrain	L.F.
2720.28	Lateral Endwall	Each
2720.29	Perforated Pipe With Vertical Drain System 150 mm (six inch)	L.F.

END OF SECTION - 02720



TDOT

Department of
Transportation



**STANDARD SPECIFICATIONS
FOR ROAD AND BRIDGE
CONSTRUCTION**

January 1, 2021

**TENNESSEE
DEPARTMENT
OF
TRANSPORTATION**

**STANDARD
SPECIFICATIONS
FOR
ROAD AND BRIDGE
CONSTRUCTION**



Tennessee Department of Transportation, Authorization No. 401093, 5,000 copies, January 2021. This public document was promulgated at a cost of \$5.83 per copy.

January 1, 2021

TENNESSEE DEPARTMENT OF TRANSPORTATION



The mission of the Tennessee Department of Transportation is to provide a safe and reliable transportation system that supports economic growth and quality of life.

Table of Contents

Part 1 – General Provisions

SECTION 101 – DEFINITIONS AND TERMS	2
SECTION 102 – BIDDING REQUIREMENTS AND CONDITIONS	12
SECTION 103 – AWARD AND EXECUTION OF CONTRACT	19
SECTION 104 – SCOPE OF WORK	21
SECTION 105 – CONTROL OF WORK	33
SECTION 106 – CONTROL OF MATERIALS	58
SECTION 107 – LEGAL RELATIONS AND RESPONSIBILITY	64
SECTION 108 – PROSECUTION AND PROGRESS	79
SECTION 109 – MEASUREMENT AND PAYMENT	100

Part 2 – Earthwork

SECTION 201 – CLEARING AND GRUBBING	124
SECTION 202 – REMOVAL OF STRUCTURES AND OBSTRUCTIONS	129
SECTION 203 – EXCAVATION AND UNDERCUTTING	138
SECTION 204 – STRUCTURE EXCAVATION FOUNDATION PREPARATION, AND BACKFILL	153
SECTION 205 – EMBANKMENTS	174
SECTION 206 – FINAL DRESSING	182
SECTION 207 – SUBGRADE CONSTRUCTION AND PREPARATION	183
SECTION 208 – SHOULDERS AND DITCHES	188
SECTION 209 – PROJECT EROSION PREVENTION AND SEDIMENT CONTROL	191

Part 3 – Base and Subgrade Treatments

SECTION 302 – SUBGRADE TREATMENT (LIME).....	210
SECTION 303 – MINERAL AGGREGATE BASE	220
SECTION 304 – SOIL-CEMENT BASE	230
SECTION 306 – PORTLAND CEMENT CONCRETE BASE	238
SECTION 307 – BITUMINOUS PLANT MIX BASE (HOT MIX).....	242
SECTION 309 – AGGREGATE-CEMENT BASE COURSE	252
SECTION 310 – CONDITIONING MINERAL AGGREGATE BASE	259
SECTION 312 – AGGREGATE-LIME-FLY ASH STABILIZED BASE COURSE	262
SECTION 313 – TREATED PERMEABLE BASE	270

Part 4 – Base and Subgrade Treatments

SECTION 401 – MINERAL AGGREGATE SURFACE.....	276
SECTION 402 – PRIME COAT	279
SECTION 403 – TACK COAT	284
SECTION 405 – BITUMINOUS SEAL COAT	288
SECTION 407 – BITUMINOUS PLANT MIX PAVEMENTS (GENERAL).....	296
SECTION 410 – BITUMINOUS PLANT MIX SURFACE COURSE (COLD MIX)	348
SECTION 411 – ASPHALTIC CONCRETE SURFACE (HOT MIX)....	352
SECTION 414 – EMULSIFIED ASPHALT SLURRY SEAL AND MICRO-SURFACING	363
SECTION 415 – COLD PLANING OF BITUMINOUS PLANT MIX PAVEMENTS	381

Part 5 – Rigid Pavement

SECTION 501 – PORTLAND CEMENT CONCRETE PAVEMENT	386
--	-----

Part 6 – Structures

SECTION 601 – TIMBER STRUCTURES	420
SECTION 602 – STEEL STRUCTURES	427
SECTION 603 – PAINTING.....	480
SECTION 604 – CONCRETE STRUCTURES	498
SECTION 606 – PILING.....	558
SECTION 607 – PIPE CULVERTS AND STORM SEWERS	578
SECTION 608 – SANITARY SEWERS.....	587
SECTION 609 – PIPE REMOVED AND RELAID.....	592
SECTION 610 – PIPE DRAINS.....	596
SECTION 611 – MANHOLES, CATCH BASINS, INLETS, AND PIPE END WALLS	600
SECTION 612 – STONE MASONRY	605
SECTION 613 – BRICK MASONRY	613
SECTION 615 – PRECAST/PRESTRESSED CONCRETE BRIDGE MEMBERS.....	618
SECTION 616 – POST-TENSIONED PRESTRESSED CONCRETE....	634
SECTION 617 – BRIDGE DECK SEALANT	646
SECTION 619 – POLYMER MODIFIED CONCRETE BRIDGE DECK OVERLAY FOR NEW AND EXISTING BRIDGES.....	650
SECTION 620 – BRIDGE RAILINGS	659
SECTION 621 – TEMPORARY STRUCTURES.....	661
SECTION 622 – SHOTCRETE.....	664
SECTION 623 – BRIDGE EXPANSION JOINTS	671

Part 7 – Incidental Construction and Services

SECTION 701 – CEMENT CONCRETE SIDEWALKS, DRIVEWAYS AND MEDIAN PAVEMENT	681
SECTION 702 – CEMENT CONCRETE CURB, GUTTER, AND COMBINED CURB AND GUTTER	687
SECTION 703 – CEMENT CONCRETE DITCH PAVING	692
SECTION 705 – GUARDRAIL	696
SECTION 706 – GUARDRAIL ADJUSTED, REMOVED AND RESET	701
SECTION 707 – FENCES	705
SECTION 708 – MONUMENTS AND MARKERS	710
SECTION 709 – RIPRAP AND SLOPE PAVEMENT.....	714
SECTION 710 – UNDERDRAINS	722
SECTION 711 – CONCRETE MEDIAN BARRIER.....	728
SECTION 712 – TEMPORARY TRAFFIC CONTROL	731
SECTION 713 – HIGHWAY SIGNING	748
SECTION 714 – ROADWAY AND STRUCTURE LIGHTING	756
SECTION 715 – ASPHALTIC CONCRETE CURB (HOT MIX).....	780
SECTION 716 – PAVEMENT MARKINGS.....	784
SECTION 717 – MOBILIZATION OF FORCES, SUPPLIES AND EQUIPMENT	799
SECTION 722 – FIELD OFFICE.....	801
SECTION 730 – TRAFFIC SIGNALS.....	807
SECTION 740 – GEOSYNTHETICS	866

Part 8 – Roadside Development

SECTION 801 – SEEDING.....	869
SECTION 802 – LANDSCAPE PLANTING.....	876
SECTION 803 – SODDING	887
SECTION 805 – EROSION CONTROL BLANKETS	893
SECTION 806 – ROADSIDE MAINTENANCE.....	896

Part 9 – Materials

SECTION 901 – HYDRAULIC CEMENT	900
SECTION 903 – AGGREGATES	901
SECTION 904 – BITUMINOUS MATERIALS	930
SECTION 905 – JOINT MATERIALS	936
SECTION 906 – DAMPPROOFING AND WATERPROOFING MATERIALS	940
SECTION 907 – CONCRETE REINFORCEMENT	943
SECTION 908 – STRUCTURAL STEEL AND APPURTENANT MATERIALS	946
SECTION 909 – FENCE, GUARD RAIL AND BARRIER.....	956
SECTION 910 – PAINT	966
SECTION 911 – LUMBER, TIMBERS, AND TIMBER PILES.....	971
SECTION 912 – BRICK	974
SECTION 913 – CEMENT CONCRETE CURING MATERIALS	976
SECTION 914 – NON-METALLIC PIPE	977
SECTION 915 – METALLIC PIPE	980
SECTION 916 – HIGHWAY SIGNING MATERIALS	982
SECTION 917 – ROADWAY AND STRUCTURE LIGHTING MATERIALS	991
SECTION 918 – LANDSCAPING MATERIALS	1002
SECTION 919 – PAVEMENT MARKING MATERIAL AND MARKERS.....	1006
SECTION 920 – EROSION CONTROL MATERIALS.....	1014
SECTION 921 – MISCELLANEOUS MATERIALS.....	1015

PART 1 – GENERAL PROVISIONS

SECTION 101 – DEFINITIONS AND TERMS 2
SECTION 102 – BIDDING REQUIREMENTS AND CONDITIONS 12
SECTION 103 – AWARD AND EXECUTION OF CONTRACT 19
SECTION 104 – SCOPE OF WORK 21
SECTION 105 – CONTROL OF WORK 33
SECTION 106 – CONTROL OF MATERIALS 58
SECTION 107 – LEGAL RELATIONS AND RESPONSIBILITY 64
SECTION 108 – PROSECUTION AND PROGRESS 79
SECTION 109 – MEASUREMENT AND PAYMENT 100

101.01

SECTION 101 – DEFINITIONS AND TERMS

101.01 General.....	2
101.02 Abbreviations.....	3
101.03 Terms	4

101.01 General

These Standard Specifications for Road and Bridge Construction apply to the bidder, before the award of the Contract, and to the Contractor after award. The sentences that direct the Contractor to perform work are written in the active voice/imperative mood. These directions to the Contractor are written as commands. For example, a requirement to provide cold weather protection could be expressed as:

Passive Voice / Indicative Mood: Cold weather protection for concrete shall be provided by the Contractor.

Active Voice / Indicative Mood: The Contractor shall provide cold weather protection for concrete.

Active Voice / Imperative Mood: Provide cold-weather protection for concrete.

As shown in the above examples, in the active voice/imperative mood, the subject “the bidder” or “the Contractor” is understood. In these Specifications, this implied subject is typically the Contractor, although in certain situations, the subject may also be a vendor, fabricator, or manufacturer engaged by the Contractor to supply material, products, or equipment for use on the Project.

Sentences defining the actions or responsibility of the Department or its representative are generally written in active voice/indicative mood. Sentences written in the active voice/indicative mood identify the party responsible for performing the action. For example, “The Engineer will determine the density of the compacted material.”

The following words refer to actions of the Department or its representative: “directed,” “required,” “ordered,” “approved,” “rejected,” “acceptable,” and “satisfactory.” These and words with similar meaning shall be understood to

convey the same intent as if followed by the words “by the Engineer” or “to the Engineer.”

The titles or headings of the Sections and Subsections in these Specifications are intended for convenience of reference and shall not be considered as having any bearing on the interpretation of the Specifications.

101.02 Abbreviations

These Specifications and other Contract documents use the following abbreviations:

ANLA	American Nursery Landscaping Association
AAR	Association of American Railroads
ACI	American Concrete Association
AASHTO	American Association of State Highway and Transportation Officials
AISC	American Institute of Steel Construction
ANSI	American National Standards Institute
ASLA	American Society of Landscape Architects
ASTM	American Society for Testing and Materials
AWPA	American Wood Preservers Association
AWWA	American Water Works Association
AWS	American Welding Society
FHWA	Federal Highway Administration
FSS	Federal Specifications and Standards, General Services Administration
IEEE	Institute of Electrical and Electronic Engineers
IES	Illuminating Engineering Society
IMSA	International Municipal Signal Association
ITE	Institute of Traffic Engineers
ICEA	Insulated Cable Engineers Association
ISSA	International Slurry Surfacing Association
MUTCD	Manual on Uniform Traffic Control Devices
NEC	National Electrical Code
NEMA	National Electrical Manufacturers Association
NCHRP	National Cooperative Highway Research Program
OSHA	Occupational Safety and Health Administration
SAE	Society of Automotive Engineers
SPIB	Southern Pine Inspection Bureau
SSPC	Society for Protective Coatings

101.03

TCA	Tennessee Code Annotated
TDEC	Tennessee Department of Environment and Conservation
UL	Underwriters Laboratories, Inc.

101.03 Terms

Wherever, in these Specifications or elsewhere in the Contract, the following terms, or pronouns in place of them, are used, the intent and meaning shall be interpreted as follows:

Addendum. Written interpretation or modification of any of the Contract documents, which is delivered to prospective bidders prior to the opening of proposals.

Advertisement. The public announcement provided by the Notice to Contractors, as required by law, inviting proposals for the Work to be performed or materials to be furnished.

Amendment. A revision to the electronic bid file, which may include adjusting a quantity, or adding, deleting, or revising Contract item(s).

Award. The formal acceptance by the Department of a proposal.

Base Course. The layer or layers of specified or selected material of designed thickness placed on a subbase or a subgrade to support a surface course.

Bidder. A pre-qualified individual, partnership, firm, corporation, or joint venture acting directly or through a duly authorized representative to submit a proposal to perform the advertised Work.

Box Bridge. A box culvert type structure consisting of a single box or multiple boxes, with or without a bottom slab, having a length, measured along the centerline of the roadway, of more than 20 feet between the inside faces of the outside walls.

Bridge. A structure erected over a stream, watercourse, highway, railroad or opening, for carrying traffic, having a length, measured along the centerline of the roadway, of more than 20 feet between the faces of end supports.

Calendar Day. Every day shown on the calendar.

Change Directive. An action taken by the Department, when the Contractor has filed a claim, that allows the Department to compensate the Contractor for completed additional work as determined to be fair and reasonable by the Department and that does not require the consent or signature of the Contractor or Surety.

Change Order. A written agreement entered into by and between the Department and the Contractor, with the written assent of the Surety, covering modifications or alterations beyond the scope of the original Contract, and establishing any necessary new Contract items, any other basis of payment, and any time adjustments for the work affected by the changes. This Agreement becomes a part of the Contract when properly executed and approved.

Commissioner. The Commissioner of the Department of Transportation of the State of Tennessee.

Completion Date. The calendar date by which the Contract shall be completed when such date is shown in the proposal instead of a stipulation of a number of working days, or the date of final acceptance of the Work.

Construction Change. A completed document, approved by the Engineer, covering changes in the Plans, Specifications or quantities, and additional items and the basis of payment that have been established by a previously executed Change Order.

Contract. The written agreement between the Department and the Contractor setting forth the obligations of the parties thereunder, including but not limited to, performance of the Work, which includes the furnishing of labor, equipment, and materials, and the basis of payment.

The Contract includes the Instructions to Bidders; the proposal; all conditions and terms of the Contract form; Contract Payment and Performance Bond; Letter of Credit where applicable; Specifications, Supplemental Specifications, Special Provisions, and Addenda; Standard Drawings and Contract Plans; the Work Order; and Construction Changes and Change Orders that are required to complete the construction of the Project in an acceptable manner including authorized time extensions thereof; all of which constitute one instrument.

Contract Payment and Performance Bond. The approved form of security, executed by the Contractor and its Surety or Sureties, guaranteeing

101.03

complete execution of the Contract and all Change Orders, and the payment of all legal debts pertaining to the performance of the Work.

Contract Time. The number of working days or calendar days allowed for completion of the Contract or an item(s) of work, or the number of calendar days between the time of starting as determined by the Work Order, and the Completion Date including all authorized time extensions.

Contractor. The individual, firm, partnership, limited liability company, corporation, joint venture, or other business entity contracting with the Department for performance of the Work.

Controlling Activity of Work. Any portion of the Work, a change in which would cause an adverse impact to the critical path schedule.

Critical Path. The sequence and duration of activities of work that control the duration of the Project.

Critical Path Method (CPM). A process for defining the time-frame required and relationship (logic ties) between critical and non-critical activities associated with construction projects and their completion dates.

Department. The Department of Transportation of the State of Tennessee.

Detour. A temporary rerouting of road users onto an existing highway in order to avoid a temporary traffic control zone.

Disadvantaged Business Enterprise (DBE). A for-profit small business concern that is at least 51% owned by one or more individuals who are both socially and economically disadvantaged or, in the case of a corporation, in which at least 51% of the stock is owned by one or more such individuals, and whose management and daily business operations are controlled by one or more of the socially and economically disadvantaged individuals who own it. Black Americans, Hispanic Americans, Native Americans, Asian-Pacific Americans, and Subcontinent Asian Americans, as defined in 49-CFR Section 26.5, women, and any additional groups whose members are designated as socially and economically disadvantaged by the U.S. Small Business Administration are rebuttably presumed to be socially and economically disadvantaged. Other individuals may also qualify as socially and economically disadvantaged on a case-by-case basis.

Engineer. The Chief Engineer of the Department of Transportation or a duly authorized assistant or representative.

Equipment. All machinery, apparatus, and tools necessary for the proper construction and acceptable completion of the Project, plus the necessary repair parts, tools, and supplies for upkeep and maintenance.

Extra Work. An item of work not provided for in the Contract as awarded but found essential to the satisfactory completion of the Contract within its intended scope.

Force Account. A method of payment for Extra Work when a Change Order is not arrived at between the Engineer and the Contractor.

Highway, Road, and Street. Each of these words is a general term denoting a public way for the purpose of vehicular travel including the entire area within the right-of-way.

Holidays. Holidays recognized by the State of Tennessee occur as follows:

New Year's Day	January 1
Martin Luther King Day	Third Monday in January
Presidents' Day	Third Monday in February
Good Friday	Friday before Easter
Memorial Day	Last Monday in May
Independence Day	July 4
Labor Day	First Monday in September
Columbus Day	Second Monday in October
Veterans Day	November 11
Thanksgiving Day	Fourth Thursday in November
Christmas Day	December 25

All days appointed by the Governor of this State, or by the President of the United States, as days of fasting or thanksgiving.

Plan notes precluding restrictions to traffic on holiday weekends, unless specifically noted otherwise, do not apply to weekends associated with Martin Luther King Day, Presidents' Day, Columbus Day, and Veterans Day.

Inspector. The authorized representative of the Engineer assigned to make detailed inspections of materials and Contract performance.

Instructions to Bidders. Instructions included in the document entitled "Instructions to Bidders," which give information to the bidder with regard to preparing the Proposal Guaranty and the Letter of Credit where applicable. It also covers submission or delivery of the Proposal to the Department.

101.03

Item (Contract Item, Pay Item, or Bid Item). A specifically described unit of work for which a price is provided in the Contract.

Laboratory. The official testing laboratories of the Department or such other laboratories as may be designated or approved by the Engineer, acting only within the scope of the duties assigned to them individually.

Letter of Credit. A contractual promise to honor drafts presented for funds upon compliance with the terms and conditions specified. The Department shall have the authority to approve the issuer and prescribe said terms and conditions.

Major and Minor Items. Major Items will be determined as follows:

1. Any original Contract Item having a value of 15% or more of the original Contract amount, based on the original estimated quantity, shall be a Major Item.
2. The accumulation of the least number of individual items that total at least 40% of the original Contract amount also shall be Major Items. The items shall be totaled sequentially starting with the largest item (based on original prices and quantities).

Any items that do not meet 1 or 2 above are Minor Items.

Materials. Any substance specified to be furnished or proposed for use in the construction of the Project and its appurtenances.

Notice to Contractors. A notice to Contractors and other interested parties of proposed construction to be bid giving the date the bids are to be received and the location and general description of the Work to be performed.

Pavement Structures. The combination of base course and surface course placed on a subgrade to support the traffic load and distribute it to the roadbed.

Plans. The approved plans, profiles, cross-sections, standard roadway and structure drawings, working drawings and supplemental drawings, or exact reproductions thereof, which show the location, character, dimensions, and details of the construction to be performed under the Contract.

Prequalification. The procedure established and administered by the Department by virtue of which prospective bidders are required to establish their responsibility and qualifications in advance of submission of Proposals.

Project. The specific improvement, together with all appurtenances, to be constructed under the Contract.

Proposal. The offer of a bidder, on the prescribed form, to perform the Work at the prices quoted.

Proposal Form. The approved form on which the Department requires that Proposals be prepared and submitted for the performance of the Work.

Proposal Guaranty. The security furnished with a Proposal to guarantee that the bidder will enter into a Contract if the bidder's Proposal is accepted and the Contract is awarded to it.

Qualified Products List (QPL). A listing of products that have been tested or analyzed by the Department and have been approved for use on the Department's road construction projects.

Right-of-Way. A general term denoting land, property, or interest therein, usually in a strip, acquired for or devoted to a highway and its appurtenant structures.

Roadbed. The graded portion of a highway prepared as a foundation for the pavement structure and shoulders.

Roadside. A general term denoting the area adjoining the outer edge of the roadway. Extensive areas between the roadways of a divided highway may also be considered roadside.

Roadside Development. Those items necessary to the complete highway that provide for the preservation of landscape materials and features; the rehabilitation and protection against erosion of all areas disturbed by construction through seeding, sodding, mulching and the placing of other ground covers; and such suitable planting and other improvements as may increase the effectiveness and enhance the appearance of the highway.

Roadway. The portion of a highway within limits of construction.

101.03

Shoulder. The portion of the roadway contiguous with the traveled way for accommodation of stopped vehicles for emergency use, and for lateral support of base and surface courses.

Special Provisions. Provisions inserted into a contract revising the Standard or Supplemental Specifications, and covering conditions unique to the individual project.

Specialty Item. Work items identified in the contract that are not bid but are normally associated with highway construction and require highly specialized knowledge, abilities, craftsmanship, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid on the contract in general. These items are to be limited to minor components of the overall contract.

Specifications. A general term applied to all directions, provisions, and requirements pertaining to the performance of the Work.

Standard Specifications. The *Tennessee Department of Transportation Standard Specifications for Road and Bridge Construction* and its revisions effective on the Contract execution date.

State. The State of Tennessee.

Subcontractor. Any individual, firm, partnership, limited liability company, corporation, joint venture, or other business entity to whom the Contractor or any Subcontractor, regardless of tier, sublets any part of the Work under the Contract.

Subgrade. The top surface of a roadbed upon which the pavement structure and shoulders are constructed.

Substructure. That part of the structure below the bearings of simple and continuous spans, skewbacks of arches and tops of footings of rigid frames, together with the backwalls, wingwalls and wing protection railings.

Superintendent. The Contractor's authorized representative in responsible charge of the Work.

Superstructure. The entire structure except the substructure.

Supplemental Specifications. Approved additions and revisions to the Standard Specifications.

Surety. A company authorized to guarantee a bidder's proposal and a contractor's performance and payment obligations under a contract, which is authorized to do business in the State of Tennessee and is listed on the United States Department of the Treasury Financial Management Service list of approved bonding companies.

Work. The furnishing of all labor, materials, equipment, and incidentals necessary for the satisfactory completion of the Project, including the carrying out of all duties and obligations imposed by the Contract.

Working Day. A calendar day, exclusive of Saturdays, Sundays, and Holidays, on which weather or other conditions not under the control of the Contractor will allow construction operations to proceed for at least 5 hours of the day with the normal working force engaged in performing the Work, which are normal to progress at the time, as determined by the Engineer.

Working Drawings. Stress sheets, shop drawings, erection plans, falsework plans, framework plans, cofferdam plans, bending diagrams for reinforcing steel, or any other supplementary plans or similar data that the Contractor is required to submit to the Engineer for approval.

Work Order. Written notice to the Contractor to proceed with the Work under the Contract, including, when applicable, the date of beginning of Contract Time.

102.01

SECTION 102 – BIDDING REQUIREMENTS AND CONDITIONS

102.01	Prequalification Questionnaire and Competency of Bidders	12
102.02	Contents of Proposal Forms	12
102.03	Interpretation of Quantities in Bid Schedule.....	13
102.04	Examination of the Site, the Work, the Plans, the Permits, and the Specifications.....	13
102.05	Preparation of Proposals	14
102.06	Delivery of Proposals.....	15
102.07	Withdrawal of Proposal.....	15
102.08	Public Opening of Proposals.....	15
102.09	Rejection of Proposals.....	16
102.10	Proposal Guaranty.....	17
102.11	Licensing of Bidders	17

102.01 Prequalification Questionnaire and Competency of Bidders

Each prospective bidder and subcontractor must file a “Prequalification Questionnaire” and be prequalified by and in good standing with the Department according to Rules of the Tennessee Department of Transportation, Chapter 1680-05-03, Prequalification of Contractors. Good standing means that the bidder or subcontractor is currently pre-qualified and not subject to any temporary disqualification according to Chapter 1680-05-03, Prequalification of Contractors, and not subject to suspension, debarment, or voluntary exclusion according to Rules of the Tennessee Department of Transportation, Chapter 1680-05-01, Contractor Debarment and Suspension. Notify the Department if there is any subsequent change in the name, organization, or contact information provided.

The Department will determine prequalification status and reserves the right to refuse bid authorization or subcontractor approval based on the factors listed in Chapter 1680-05-03.07.

102.02 Contents of Proposal Forms

Upon request, the Department will furnish the bidder an electronic proposal form containing an “Instructions to Bidders” form, Supplemental Specifications, Special Provisions, and Proposal Guaranty form. The

proposal form will state the location and description of the contemplated construction. The proposal form will state the time in which the Work must be completed, the amount of the Proposal Guaranty, and the date, time, and place for the opening of proposals. The Plans and Specifications are as much a part of the proposal form as if they were bound therein. All of the documents contained therein are part of the proposal.

The prospective bidder will be required to pay the Department the sum stated in the Instructions to Bidders for each electronic proposal form. Plans will be available for the sum stated in the Notice to Contractors.

102.03 Interpretation of Quantities in Bid Schedule

The quantities appearing on the electronic bidding file are approximate only and are prepared for the comparison of bids and award of Contract. The Department does not guarantee or assume any responsibility that quantities shown on the Plans or given in the electronic bidding file will hold in the construction of the Project, and the Contractor shall not claim deception or misunderstanding because of variation in these quantities or variation from the location, character of the work, or any other conditions. The Department will pay the Contractor only for the actual quantities of work performed and accepted, and materials furnished in accordance with the Contract. The schedule of quantities of work to be done and materials to be furnished may be increased, decreased, or omitted as provided under **104.02**.

102.04 Examination of the Site, the Work, the Plans, the Permits, and the Specifications

The bidder assumes the responsibility to examine the site of the Work, including the surrounding terrain, borrow sites, and access facilities, and the Plans, Specifications, and all other documents making up the Proposal and Addenda. It is mutually agreed that submission of a proposal is considered prima facie evidence that the bidder has performed a reasonable site investigation and is familiar and satisfied with the character, quality, and quantity of work to be performed, materials to be furnished, the permits, and proposal requirements.

When requested and available, the Department will provide for the bidder's review one or more of the following:

1. Record drawings.

102.05

2. Information relative to subsurface exploration, borings, soundings, water levels, or profiles.
3. The results of other preliminary investigations.

A reasonable site investigation includes a review of these documents.

The Department makes no guarantees regarding the character or extent of utilities, water levels, soil, rock, or other subsurface conditions the bidder may encounter during the Work. The Department interpolates test data from completed borings in its reports and representations of subsurface conditions, and does not guarantee the accuracy of these interpolations, nor does the Department guarantee the accuracy of the test data except at the exact points where samples were taken. The Department requires bidders to make their own evaluation of subsurface conditions and to determine how these conditions may affect the methods and cost of construction. Material quality within sources naturally varies, so expect this.

Immediately notify the Department of any apparent error, omission, or ambiguity in any part of the proposal. The Department will review the apparent error, omission, or ambiguity, and will issue an addendum to all prospective bidders, as appropriate.

If the Department becomes aware of a change in the information provided at any time during the bidding process, it will provide reasonable written notice of the new information to the bidders or Contractor.

102.05 Preparation of Proposals

A document entitled "Instructions to Bidders" is included with the electronic proposal form. Electronically sign both the proposal form and the proposal guaranty form as directed in these instructions using the electronic bidding file furnished by the Department. Submit the completed electronic bidding file, inclusive of the proposal form as described in **102.02** and the bid prices described below, to the Department as directed in the applicable part of these instructions.

The electronic bidding file contains the contract bid items and associated estimated quantities. The following stipulations shall apply to electronic bidding:

1. Compare the bid quantities shown on the Plans to those contained on the electronic bidding file to ensure they are the same. Immediately notify the Department of any discrepancies.
2. For any revisions to the proposal regarding bid items or quantities, the Department will provide an amendment to the electronic bidding file indicating the revision date. Use the amended electronic bidding file in formulating the bid.

For proposals containing alternates, bid on only one alternate for each construction item. Enter prices for the intended alternate item(s) of construction and leave the undesired alternate item(s) of construction blank. The electronic bidding program allows for only one alternate to be bid. If prices are entered for more than one alternate, the electronic bidding program will not tabulate the total.

The electronic bidding program will perform all extensions of the estimated quantities and unit or lump sum prices, calculate the total bid, and allow the printing of a complete set of bid item sheets with appropriate subtotals and grand total bid price.

102.06 Delivery of Proposals

Submit each proposal via the Internet using the electronic bidding program. The Department will not consider or accept a proposal that has not been received by the time, date, and at the place set forth for the bid opening in the Instruction to Bidders.

102.07 Withdrawal of Proposal

A bidder may withdraw a proposal through the electronic bidding program prior to the hour of bid opening as indicated in the Instruction to Bidders.

102.08 Public Opening of Proposals

The Department will open proposals and will either read them publicly, or furnish and post bid totals on the date, time, and place indicated in the Instruction to Bidders. Bidders, authorized agents, and interested parties are invited to be present.

102.09

102.09 Rejection of Proposals

The Department will not reject proposals solely because their consideration is conditioned upon the elimination of other proposals submitted by the same bidder at the bid opening, provided that the Department reserves the right to make awards on combination bids or separate bids as it determines to be in its best interests. A bidder may tie the acceptance or rejection of two or more proposals on the condition that either all proposals are accepted or all are rejected, in which case the bids will be rejected unless each bid is the lowest responsive bid on each project.

The Department may reject a proposal if any of the unit prices contained therein are mathematically unbalanced, either excessive or below the Engineer's estimate. A materially unbalanced bid generates a reasonable doubt that award to the bidder submitting a mathematically unbalanced bid will result in the lowest ultimate cost to the Department. A mathematically unbalanced bid contains lump sum or unit bid items that do not reflect reasonable actual costs and a proportionate share of bidder's anticipated profit, overhead costs, and other indirect costs.

The Department may reject any proposals as non-responsive if:

1. Proposals fail to contain a unit price for each item listed.
2. Proposals are not prepared on the prescribed forms.
3. Proposals show any unauthorized omissions, conditions, alterations of form, additions, or irregularities of any kind.
4. Proposals show unauthorized alternate bids. In the case of authorized alternate items, a unit price on only one of the alternates will be required, unless otherwise specified in the Contract.
5. Proposals are not electronically signed by an authorized representative of the bidder. The electronic signature on the electronic bidding file serves as signatures for the proposal form, proposal certification form and the proposal bond form, if applicable.
6. When electing to submit a Proposal Guaranty, the bidder fails to submit a signed Proposal Guaranty in the proper character and amount indicated on the proposal form.

7. The Proposal Guaranty is not properly signed by the Agent or Attorney-in-Fact representing a Surety accompanied by a dated and valid Power of Attorney for the Attorney-in-Fact. The date on the Power of Attorney must match the date on the Proposal Guaranty.
8. A bidder is not prequalified and in good standing on the date of letting in accordance with **102.01** and Chapter 1680-05-03, Prequalification of Contractors.
9. There are reasonable grounds for believing that any bidder is interested in more than one proposal on the same project, or that there has been collusion among the bidders. Evidence of collusion will cause a rejection of all proposals in which the bidders involved are interested.
10. The apparent low bidder fails to complete and submit the Department form "Certification Regarding Subcontractor Bid Quotes" (Bidders List) electronically before the close of business (4:30 PM Central Time) within seven (7) calendar days after the date on which bids are required to be submitted.
11. A bidder fails to deposit bid escrow documentation, if required.
12. A bidder fails to acknowledge addenda.
13. A bidder does not obtain or have a license with the Tennessee Department of Commerce and Insurance (TDCI), Board for Licensing Contractors (BLC) within twenty-one (21) days in accordance with **102.11**.

102.10 Proposal Guaranty

With each electronic bid, submit an electronic Proposal Guaranty in accordance with the Instructions to Bidders. Ensure that the Proposal Guaranty form is complete and furnished by a Surety as defined in **101.03**, and that the Proposal Guaranty has a Power of Attorney executed by the Surety. The proposal and the Proposal Guaranty shall be valid and binding for sixty (60) days subsequent to the date of opening bids.

102.11 Licensing of Bidders

All Contractors, except mowing and litter removal Contractors, must be licensed with the Tennessee Department of Commerce and Insurance,

102.11

Board for Licensing Contractors (BLC). The Contractor must be licensed in the general classification (e.g. Heavy Construction (HC); Highway, Railroad, Airport (HRA) Construction; Specialty (S); Municipal and Utility Construction (MU); or Electrical Contracting (CE)) for the type of work in the Project that they will perform. Contractors for mowing or litter removal type contracts must be registered with the Secretary of State (i.e., have a valid Certificate of Existence/Authorization), if applicable, before a Contract will be awarded.

A proposal submitted by a bidder will be considered for award for 21 days after the proposals are opened. If the bidder does not have a license with the BLC, on or before twenty-one (21) days after proposals are opened, the bidder will be considered non-responsive and its proposal will be rejected as irregular. The next lowest responsible bidder will then be considered for award. If the next lowest responsible bidder does not have a license on or before the twenty-one (21) days after the proposals are opened, they also will be considered non-responsive, and the subsequent bidder will then be considered. The Department may retain the Proposal Guaranty, not as a penalty, but as liquidated damages in the event a bidder does not have a license at the time of award.

Bidders that are domestic or foreign corporations, limited liability companies, limited partnerships, or limited liability partnerships, must be in good standing with the Secretary of State (i.e., have a valid Certificate of Existence/Authorization). If a bidder is not in good standing with the Secretary of State on or before twenty-one (21) days after proposals are opened, the bidder will be considered non-responsive and its proposal will be rejected.

SECTION 103 – AWARD AND EXECUTION OF CONTRACT

103.01 Consideration of Proposals	19
103.02 Return of Proposal Guaranties	19
103.03 Material Guaranty	19
103.04 Award of Contract.....	20
103.05 Cancellation of Award	20
103.06 Execution of Contract and Contract Payment and Performance Bond	20
103.07 Failure to Execute Contract.....	20

103.01 Consideration of Proposals

The electronic bid is the only official bid.

After the proposals are opened, the Department will compare proposals based on the summation of the products of the unit bid prices and the approximate quantities. The results of such comparisons are public information.

The Department reserves the right to reject any or all proposals, to waive technicalities, or to advertise for new proposals in the best interests of the Department.

103.02 Return of Proposal Guaranties

As soon as the proposal prices have been compared, the Department will return Proposal Guaranties accompanying the proposals not likely in its judgment to be involved in making the award. The Department will return all other Proposal Guaranties to the remaining bidders after satisfactory Contract and Contract Payment and Performance Bond or Letter of Credit, where applicable, have been executed and accepted.

103.03 Material Guaranty

Before Contract award, the Department may require the bidder to furnish a complete statement of the origin, composition, or manufacture of any or all materials proposed to be used in the construction of the Project, together with samples. The samples may be subjected to tests, provided for in these Specifications, to determine their quality and fitness for the construction.

103.04

103.04 Award of Contract

The Department will either award a contract to the lowest responsive bidder according to TCA §54-5-116 within thirty (30) days after the formal opening of proposals, or it will reject all proposals received on the Project.

If a bidder submits qualified bids where the bidder ties acceptance or rejection of two or more proposals on the condition that either all proposals are accepted or all are rejected, the bids will be rejected unless each bid is the lowest responsive bid on each project. If the combination bid is rejected, the Department may award the Contract to the second lowest responsive bidder.

The Department will only award a contract to a contractor that is licensed in accordance with **102.11**.

103.05 Cancellation of Award

The Department reserves the right to cancel the award of any contract, at any time prior to execution of the Contract by all parties without liability.

103.06 Execution of Contract and Contract Payment and Performance Bond

The bidder to whom the Contract is awarded shall sign and return the Contract to the Department along with the fully executed Contract Payment and Performance Bond or Letter of Credit, where applicable, in a sum equal to 100% of the amount of the Contract, within ten (10) days after the receipt of notice of award and receipt of contract forms from the Department.

A contract is not considered binding until it has been executed by all parties.

103.07 Failure to Execute Contract

If the bidder fails to execute the Contract and to file an acceptable Contract Payment and Performance Bond or Letter of Credit, where applicable, within ten (10) days after notice of award, the Department may cancel the award and retain the Proposal Guaranty, not as a penalty, but as liquidated damages. The Department may then award the Contract to the next lowest responsive bidder, re-advertise the Work, or take other action, as the Department may decide.

SECTION 104 – SCOPE OF WORK

104.01 Intent of Contract	21
104.02 Changes in Plans or in Character of Construction	21
104.03 Contract Change Notification	23
104.04 Maintenance of Traffic.....	25
104.05 Maintenance During Construction	27
104.06 Movement of Heavy Equipment	27
104.07 Operation of Earthmoving and Hauling Equipment.....	27
104.08 Dust Control.....	28
104.09 Rights in and Use of Materials Found on the Work.....	28
104.10 Final Cleanup	29
104.11 Value Engineering Change Proposal (VECP).....	29

104.01 Intent of Contract

It is the intent of the Contract to provide for the construction and completion of the Work in accordance with the Plans, Specifications, and all other Contract documents.

104.02 Changes in Plans or in Character of Construction

The Department reserves the right to make changes to the Work at any time including alterations in the Plans, increases or decreases in quantities, Extra Work, or eliminated items. Such changes shall not invalidate the Contract nor release the Surety. The Contractor agrees to perform the Work as altered, the same as if it had been a part of the original Contract.

Under no circumstances shall changes in the Plans or in the character of the Work involve work beyond the termini of the proposed construction except as may be necessary to satisfactorily complete the Project.

A. Differing Site Conditions

During the progress of the Work, if subsurface or latent physical conditions are encountered at the site differing materially from those indicated in the Contract or if unknown physical conditions of an unusual nature, differing materially from those ordinarily encountered and generally recognized as inherent in the Work provided for in the

104.02

Contract, are encountered at the site, promptly notify the Engineer in writing of the specific differing conditions in accordance with **104.03** before the site is disturbed and before the affected work is performed. Upon written notification, the Engineer will investigate the conditions, and if it is determined that the conditions materially differ and cause an increase or decrease in the cost or time required for the performance of any work under the Contract, the Engineer will make an appropriate Contract adjustment, excluding loss of anticipated profits, in accordance with **108.07** and **109.04** and the Contract modified in writing accordingly.

The Department will not allow Contract adjustments under this Subsection for any portion of the Work unaffected by differing site conditions.

B. Suspensions of Work Ordered By the Engineer

If the performance of all or any portion of the Work is suspended or delayed by the Engineer in writing for an unreasonable period of time (not originally anticipated, customary, or inherent to the construction industry) and the Contractor believes that additional compensation, contract time, or both compensation and time is due as a result of such suspension or delay, the Contractor shall notify the Engineer in writing and provide information in accordance with **104.03**. If the Engineer agrees that the cost or time required for the performance of any work under the Contract has increased as a result of such suspension and the suspension was caused by conditions beyond the control of and not the fault of the Contractor, its suppliers, or subcontractors at any tier, and not caused by weather, the Engineer will make appropriate Contract adjustments in accordance with **108.06** and **109.04**.

No Contract adjustment will be allowed under this Subsection to the extent that performance would have been suspended or delayed by any other cause, or for which an adjustment is provided for or excluded under any other term or condition of this Contract.

C. Significant Changes in the Character of Work

The term “significant change” will apply only to the following circumstances:

1. When the character of the Work as altered differs materially in kind or nature from that involved or included in the original proposed construction, or
2. When a Major Item is increased or decreased by more than 25% of the original estimated Contract quantity. Adjustments shall apply only to that portion in excess of 125% of original Contract quantity, or in case of a decrease, to the actual quantity performed.

If the Contractor believes there to be a significant change in the character of work, notify the Engineer in writing and provide information in accordance with **104.03**. If the alterations or changes in quantities significantly change the character of Work, the Department will make appropriate Contract adjustments, excluding loss of anticipated profits, in accordance with **108.06** and **109.04** as applicable.

D. Extra Work

When necessary or desirable to complete the Contract, the Engineer may direct the Contractor to perform work not provided for in the Contract, but essential to the satisfactory completion of the Work within the intended scope. The Department will pay for Extra Work in accordance with **109.04** and will determine additional time in accordance with **108.07**.

E. Eliminated Items

The Department may partially or completely eliminate Contract items and will reimburse the Contractor only for those costs in accordance with **109.05** incurred before the Contractor's receipt of written notification of the elimination.

104.03 Contract Change Notification

It is the responsibility of the Contractor to provide reasonable written notice when conditions are believed to require a change to the Contract. The Department will only consider requests for changes to the Contract when the Contractor meets the notification procedures specified in this Subsection.

A. Written Notification by Contractor

Provide immediate written notification to the Engineer upon discovering a condition that may require a change to the Contract. Provide the

104.03

following information, in writing, within fourteen (14) calendar days of notification:

1. A description of the condition, including the time and date first identified, and the location, if appropriate.
2. An explanation of why the condition represents a change to the Contract, with references made to **104.02** and other pertinent portions of the Contract.
3. A statement of all changes considered necessary to the Contract price(s), delivery schedule(s), phasing, and time. Because of its preliminary nature, the Department recognizes that this information may rely on estimates.

After notifying the Engineer, continue to perform the Work under the Contract including the work subject to the condition, and maintain records of actual labor, equipment, and materials used in accordance with **109.04**.

B. Written Acknowledgement by Engineer

The Engineer will provide written acknowledgement of the Contractor's written notice within five (5) calendar days.

C. Written Response by Engineer

The Engineer will provide a written response within fourteen (14) calendar days of receiving the Contractor's written notice that includes one of the following:

1. confirmation that a change is necessary in accordance with **104.02**, and direction on how the Work will proceed.
2. A denial of the request for a change, which will include references to the Contract as to why the condition does not represent a change.
3. A request for additional information stating the specific information needed and the date by which it must be received. The Department will respond to the additional information provided within fourteen (14) calendar days.

When a change is necessary, the Engineer will make appropriate adjustments to the Contract price and time, if warranted, in accordance with **108.07, 109.04, 109.05.A, and 109.06**. If the Contractor disagrees with the Engineer's decision or does not agree with the Contract adjustments, the Contractor may pursue the issue as a claim in accordance with **105.16**.

104.04 Maintenance of Traffic

Unless otherwise provided, keep all roadways and access for vehicular travel open to all traffic while under construction. Maintain all traffic control features over the section of road under construction in accordance with the MUTCD and with **712** of these Specifications. Where indicated on the Plans, bypass the traffic over approved detour routes. Keep the portions of the Project being used by the public, whether it is through or local traffic, in such condition that traffic is adequately and safely accommodated. The Department will change the traffic control plan when necessary to maintain safety or reduce traffic congestion. Construct and maintain in a safe condition temporary approaches or crossings and intersections with trails, roads, streets, businesses, parking lots, railroads, residences, garages, and farms. Provide for mowing or other vegetation removal to ensure safe sight distance at intersections. Do not use median crossovers on controlled access routes for construction traffic, except in areas, approved by the Engineer, where traffic control devices allow for the safe movement of construction traffic.

The Department will pay for materials used at the direction of the Engineer to construct and maintain approaches, crossings, intersections, and other features at Contract unit prices unless the Contractor is responsible for the damage. Maintenance of traffic control features, mowing, and pothole patching (cold mix) are incidental to the work and the responsibility of the Contractor.

Except in emergencies, lane closures are not permitted on any State routes without the explicit consent of the Engineer. On projects where work is required in traffic lane(s) or where a lane closure is necessary for public safety, submit a request to the Department at least seven (7) working days prior to the date of the anticipated lane closure(s). If all lanes in one or both directions on an interstate route are to be closed for any length of time, submit a request at least fourteen (14) calendar days before the anticipated event. All requests for lane closure(s) must list the exact location, the time that the closure will begin, the estimated duration of the closure, and reasons for the proposed lane closure. Unless otherwise stated in the Contract, the

104.04

Department will assess liquidated damages of \$1000 per hour per lane for roadways greater than 25,000 ADT and \$500 per hour per lane for areas less than 25,000 ADT for any closure that exceeds the approved lane closure duration.

If a holiday falls on Saturday or Sunday, do not close lanes or restrict traffic from the preceding Friday at 6 am to the following Monday at 6 am.

Do not close lanes or restrict traffic on the following days without the Engineer's written consent:

- Easter: After 6:00 pm on the Thursday preceding Good Friday through and including Easter Sunday
- Memorial Day: After 12:00 noon on the preceding Friday through Memorial Day
- Independence Day: The observed holiday and up to two preceding or following weekdays plus weekend days either preceding or following the holiday.
- Labor Day: After 12:00 noon on the preceding Friday through Labor Day
- Thanksgiving: After 12:00 noon on Wednesday before Thanksgiving through Sunday following Thanksgiving
- Christmas/New Year's Day: December 24 through January 1 and any preceding and/or following days that fall on a weekend

The Engineer will allow off-road work on the above days only to the extent that no impact will be caused to the highway users. The Department will assess a \$5,000 penalty against subsequent Contractor payment estimates for each violation of this rule.

The Department will maintain all public highways, roads and streets that are designated on the Plans as detours, but not designated as "Haul Roads".

During any written suspension of Work, make passable and open to traffic portions of the Project and temporary roadways as may be directed by the Engineer for the temporary accommodation of traffic during the anticipated period of suspension. Maintain temporary routes or lines of travel until the

Engineer orders by written notification the resumption of construction operations. When work is resumed, replace or renew any work or materials lost or damaged because of such temporary use of the Project. Remove, to the extent directed by the Engineer, any work or materials used in the temporary maintenance, and complete the Project in every respect as though its prosecution had been continuous. The Department will pay for materials used for maintenance and restoration of the Work when directed by the Engineer, at Contract unit prices.

104.05 Maintenance During Construction

Maintain the Work during construction and until the Project, or section(s) thereof, is accepted in accordance with **105.13**.

Continuously maintain the Work with adequate equipment and forces so that the roadway or structures are kept in satisfactory condition at all times. When placing a new course upon a previously constructed course or subgrade, maintain the previous course or subgrade during all construction operations. Provide litter pickup, mowing, and vegetation removal throughout the life of the Project in accordance with **806**.

The costs for maintenance work during construction and before the Project is accepted will not be paid separately, but is incidental to the cost of the Work.

104.06 Movement of Heavy Equipment

The Contractor's attention is called to the application of local, State, and Federal regulations governing construction work. Various municipalities as well as the Department require a permit for moving heavy equipment. The Contractor is responsible for applying for and procuring such permits, when required, from the appropriate municipal officials and the Department of Transportation.

104.07 Operation of Earthmoving and Hauling Equipment

When operating earthmoving equipment or hauling equipment on or across city streets or public roads, obtain specific written permission for such operations from the appropriate officials and deliver a copy of such permission to the Engineer prior to commencement of such operations. Keep the affected streets or public roads reasonably free of loose earth and debris during movement of equipment, and thoroughly clean the affected streets or roads at the end of each day they have been used.

104.08

Provide flagging services in accordance with **712.04** as directed by the Engineer at locations where earthmoving equipment crosses or enters a city street or public road.

Repair damage to city streets, public roads, and adjacent property as directed by the Engineer at no additional cost to the Department.

The cost of cleaning city streets or public roads, of any required flagging of city streets or public roads, and of any repairs to city streets, public roads, or adjacent property will not be paid separately, but is incidental to the cost of the Work.

104.08 Dust Control

Take all available precautions to control dust. If the Engineer judges dust to be a problem, control the dust by sprinkling, by applying calcium chloride, or by other methods as directed. Payment for dust control is incidental to applicable Contract items and will be full compensation for the work required to control dust. No additional compensation will be allowed for delays caused by necessary dust control operations.

104.09 Rights in and Use of Materials Found on the Work

Use stone, gravel, sand, or other material determined suitable by the Engineer, as may be found in the excavation for the Project. The Department will pay for the excavated materials at the corresponding bid price for the excavated material. Replace excavated material used for embankments, backfills, or approaches with other material acceptable to the Engineer at no additional cost to the Department. No charge for the materials so used will be made against the Contractor. Do not excavate or remove any material from within the right-of-way that is not within the grading limits, as indicated by the slope and grade lines, without the Engineer's written authorization.

The material from any existing structures, water lines, sewers, utilities, and similar features, which are required to be removed in the course of construction, shall become the property of the Contractor to use or dispose of in accordance with the applicable statutes or regulations governing such materials, unless otherwise shown on the Plans.

Commercial grade coal found in the excavation for the Project shall become the property of the Contractor and shall be removed from the Project or shall be disposed of in a suitable waste site as approved by the Engineer. Replace all coal found in the excavation with an equivalent amount of acceptable

material at no cost to the Department when needed for construction of the Project.

104.10 Final Cleanup

Before final acceptance of the Work, clean the entire right-of-way, all material pits, all waste areas, all areas and access roads used by the Contractor, all streams affected by the Work, and all ground occupied by the Contractor, in connection with the Work. Remove all forms, false work and temporary structures, temporary erosion control measures, excess materials, equipment, rubbish, and waste. Leave all parts of the Work in a neat and presentable condition. Stabilize the entire right-of-way, all material pits, all waste areas, all areas and access roads used by the Contractor according to the TN NPDES Construction General Permit criteria or the agreed upon Reclamation Plan. Mow the right-of-way as required for final cleanup. If the Project was graded under a previous contract, perform final cleanup within the construction limits of the current work being performed and other areas disturbed or otherwise requiring cleanup due to the Contractor's operations. Do not deposit rubbish, waste, or debris on or in sight of the right-of-way. Replace and repair all damage to private and public property in accordance with **107.14**.

104.11 Value Engineering Change Proposal (VECP)

The Contractor may request a modification to the Plans, the Specifications, or other Contract requirements based on a Value Engineering Change Proposal (VECP) submitted to the Department specifying a cost reduction change. This will not apply to a proposal unless it is identified as a VECP at the time of its submittal.

VECP are those proposals that would require a change in the Contract and would result in an immediate net savings to the Department without impairing the essential functions and characteristics of the Project, including but not limited to, any warranties, service life, reliability, economy of operation, and maintenance and safety features. The Department will not normally consider VECPs that propose a total savings of less than \$25,000 unless there are other non-monetary savings to be realized.

The Contractor may submit for review a "VECP Concept" provided that it contains enough information to clearly define the work involved and the benefits to be realized. Provide all applicable design criteria that will be used in the VECP design. Written notification by the Department that the review has been completed and that the VECP Concept appears to be favorable

104.11

merely indicates that the engineering and plan development may continue for submittal of the VECP and is not authorization to begin any construction work contemplated by the VECP. Should the final design not reflect the expected benefits, the Department may reject the VECP Concept and the VECP without recourse by the Contractor.

Submit the following information to the Engineer as a minimum, with each VECP, allowing adequate time for Department analysis and processing without interference with project schedules:

1. A description of the difference between the existing Contract requirements and the proposed change, and the comparative advantages and disadvantages of each including cost and time savings.
2. An itemized list of the Contract changes required if the VECP is accepted, and any recommendation as to how to make each such change.
3. A separate detailed cost estimate for:
 - a. the affected portions of the existing Contract requirements, and
 - b. the VECP.
4. A prediction of the effects the proposed change will have on other Department costs, such as costs of maintenance and operation.
5. A statement of the time by which a Change Order must be issued in order to obtain the proposed cost reduction for the Project, noting the effect on the Contract completion time or delivery schedule.
6. The date(s) of known previous or concurrent submissions of the same VECP and previous actions by the Department.
7. The Contract items affected by the proposed change, including the associated quantity changes.

The Department may determine at any point during the evaluation process that the VECP is not cost effective and reject the VECP without recourse by the Contractor.

While a VECP is being considered by the Department, continue to perform the Work in accordance with the requirements of the Contract. The Department shall not be liable for failure to accept or act upon any VECP within the proposed time for review and processing or for any delays to the Work due to the submitted VECP. The Department will be the sole judge of the acceptance or rejection of a VECP, either wholly or in part. If an agreement has not been reached by the date that the Contractor's VECP specifies that a decision should be made, or such other date as the Contractor may have specified in writing, the VECP shall be deemed rejected.

The Contractor shall have no claim against the Department for additional costs or delays resulting from the rejection of a VECP, including but not limited to, VECP Concept or VECP acceptance, engineering and development costs, loss of anticipated profits, and increased material or labor costs.

The Department will not normally consider a VECP that would require any changes in pavement design, right-of-way, relocation of bridges, or any changes that would require modification of the approved environmental documents for the project. Right-of-way cannot be purchased as part of a VECP. The Department will not accept a VECP that is similar to a change in the Plans or Specifications under consideration by the Department for the Project at the time the VECP is submitted; nor will the Department accept a VECP based upon, or similar to, Standard Specifications, general use Special Provisions or Standard Drawings adopted by the Department after the advertisement for the Contract. VECP savings will only be applied to the specific Contract under which they are proposed. The Department reserves the right to make such changes without compensation to the Contractor in accordance with **104.02**.

The Department will determine the estimated net savings from the adoption of all or any part of the VECP. In determining the estimated net savings, the Department may disregard the Contract bid prices if, in its judgment, such prices do not represent a fair measure of the value of the work to be performed or to be deleted.

If the Department accepts the VECP, the Contractor grants to the Department all rights to adoption of the VECP for general use on other contracts without obligation or compensation of any kind.

Acceptance of a VECP will be by Change Order incorporating the changes necessary to allow the VECP, or any part of it, to be put into effect. The

104.11

Change Order will also set forth the estimated net savings to the Department and further provide that the Contractor be paid 50% of the actual net savings.

The cost to develop, design, and implement the VECP, including redesign by a Tennessee-licensed engineer, preparation of new reproducible plans, and any other information requested by the Department to facilitate its review, is incidental to the Contractor and will not be reimbursed as part of the VECP net savings payment. The cost to the Department to review the VECP is incidental to the Department and will not affect the VECP payment.

The Department will determine the actual net savings when the work in the VECP and Change Order is completed. If upon completion of the work proposed in the VECP, the Department determines that the Change Order did not adequately address a change in quantities for other pay items that were either increased or decreased substantially as a result of the VECP, those additional costs or savings will be included in the actual net savings determination. The Department will make a single payment to the Contractor representing 50% of the actual net savings once all items are considered.

If the completed VECP results in an increase in cost such that there is no net savings, the Department will reimburse those costs above the original Contract amount reflected in the VECP and Change Order at a rate of 50%.

The preparation of the VECP, its acceptance and performance of the work shall not extend the Contract completion time unless the Change Order provides for an extension.

SECTION 105 – CONTROL OF WORK

105.01 Authority of the Engineer	33
105.02 Plans and Working Drawings.....	34
105.03 Conformity with Plans and Specifications	36
105.04 Coordination of Plans and Specifications	37
105.05 Duties of Contractor.....	38
105.06 Planning of the Operations-Preconstruction Conference	39
105.07 Cooperation with Utilities, Railroads, and Pipelines	40
105.08 Cooperation between Contractors	42
105.09 Construction Stakes, Lines, and Grades.....	42
105.10 Authority and Duties of Inspectors	46
105.11 Inspection of Work	47
105.12 Removal of Unacceptable and Unauthorized Work.....	48
105.13 Completion of Specific Sections of a Project.....	48
105.14 Opening Sections of a Project to Traffic.....	49
105.15 Acceptance.....	49
105.16 Claims for Adjustment and Disputes	49
105.17 Alternative Equipment	55
105.18 Method of Measurement	56
105.19 Basis of Payment.....	57

105.01 Authority of the Engineer

The Engineer will have full professional and executive charge of supervision of the Work, and will decide all questions that may arise concerning the following:

1. The quality and acceptability of materials furnished and work performed,
2. The rate of progress of the Work,
3. The quantity of work that has been performed at any given time,
4. All questions that may arise as to the interpretation of the Plans and Specifications,
5. The acceptable fulfillment of the Contract, and
6. Contractor compensation.

105.02

In all of these matters, the decision of the Engineer will be final and binding; decisions of a purely contractual or legal nature will be subject to appeal in writing by the Contractor to the Commissioner.

The Engineer will have the authority to suspend the Work and withhold payment wholly or in part, if the Contractor furnishes materials or uses workmanship that are not fully acceptable, or fails to comply fully with any orders or with any provisions of the Contract. The Engineer also may suspend the Work, wholly or in part, for such periods as it deems necessary, due to unsuitable weather, conditions considered unsuitable for the prosecution of the Work, or as deemed to be in the public interest.

105.02 Plans and Working Drawings

All contractors and subcontractors directly engaged in the erection or removal of falsework, temporary structures, structural steel, precast prestressed or mild steel reinforced concrete bridge beams or girders over active highway traffic lanes, on any route, railroad or any stream deemed navigable to commercial or pleasure water craft, shall submit an erection plan prepared and stamped by a Professional Engineer licensed in the State of Tennessee. See also **602.41**, **602.42**, and **604.06**.

The Contract Plans, generally, will show sufficient details and dimensions to define the Work. When additional details and dimensions are needed, prepare working drawings and submit them to the Engineer for approval. Submission of working drawings will not serve to change the intent of the Contract documents. The Contractor may instruct the fabricator to submit shop or working drawings directly to the Department. The Department will construe the fabricator to be an agent of the Contractor and will consider any changes to the Contract Plans submitted by the fabricator as made by the Contractor. The Contractor shall bear all costs for changes other than those required by the Department. Unless otherwise noted on the Plans or Specifications, shop drawings for all types of structures shall be submitted by, or on behalf of the Contractor, directly to the Division of Structures, for processing and distribution by the checking agency. Proof of appropriate fabricator certification for the type of structure to be fabricated shall be submitted along with the shop drawings.

Submit shop drawings for the following items:

Structural steel, metal bridge rails, bearing devices (shop drawings not required for plain elastomeric bearing pads), bridge deck drains (shop drawings not required if fabricated according to applicable Standard

Drawing), navigation lighting support brackets, precast prestressed concrete beams, precast prestressed concrete deck panels, precast reinforced concrete beams, precast concrete box and three-sided culverts (not required if built in accordance with Department standards or published ASTM standards), post-tensioned concrete, roadway expansion devices, steel stay-in-place forms, energy attenuation devices, overhead and cantilever sign structures, high mast light foundations, retaining walls and noise walls, cofferdams, and any other items when shown on the Plans.

Also submit required erection drawings for all bridge structures to be erected over active roads, railroads, and navigable waterways; drawings of falsework, bracing, cofferdams, sheeting, and bending of reinforcing steel; and other supplementary plans required by the Engineer and specified in **602.42**.

Each shop drawing sheet shall contain in the title block the following: the project number, county, bridge name, bridge number (or structure type and number), station and contract. Shop drawings whose title sheets do not include the foregoing identification will be returned for correction before any reviews for approval are conducted.

Submit shop drawings in sets with the drawing numbers running consecutively in each set. Do not resubmit shop drawings marked "APPROVED" or "APPROVED AS NOTED" unless specifically instructed.

All shop drawings shall be submitted electronically. The preferred format for electronic submittals is *.pdf format. Submittals shall be sent to the following email address: TDOT.Structures.ShopDrawings@tn.gov. Paper copies of shop drawings for steel girders will be required when requested by the designer for review.

Except for Strain Poles, Street Lighting Poles, High Mast Poles with Accompanying Lowering Devices, Photometrics and Cofferdams, the fabricator shall furnish the Division of Structures an electronic copy of as-built shop drawings after the structure is complete and before final payment will be made. A *.pdf file is the preferred format for electronic copies. Submittals shall be sent to the following email address: TDOT.Structures.ShopDrawings@tn.gov.

All working drawings shall be approved by the Engineer; such approval will be general in nature and will not operate to relieve the Contractor of its responsibility under the Contract for the successful completion of the Work. In addition to such approval, working drawings involved in construction over

105.03

or under railroad tracks will require approval of the railroad company before approval is granted by the Engineer. Submit plans for any cofferdams, sheeting and bracing details for bents or piers adjacent to a track, and falsework for erecting the spans over tracks, and the method of installation for the protection of the tracks, to the Engineer. Do not begin such work until these plans are approved by the Department and the Chief Engineer of the railroad. Approval of these plans will not relieve the Contractor from liability. The above also applies in connection with the installation of pipes, culverts, and other work adjacent to or under railroad tracks. The Department will not pay for the cost of preparing working drawings separately. These costs will be included in the prices of the respective Contract items involved.

Shop drawings for structural steel bridge components, precast or precast prestressed bridge, noise wall or retaining wall components and post-tensioning systems shall be accompanied on the first submittal by evidence of appropriate certification as described in **602, 615, 616, and 908**.

Complete Shop Drawing, Working Drawing, or Erection Plan packages submitted for review, acceptance, or approval by the Department will be approved or denied within thirty (30) days of receipt per submittal. If revised or additional drawings are required, appropriate additional time will be allowed for review, acceptance, or approval. If the approval process exceeds thirty (30) days, the Department may extend the completion date if the delay adversely affects the critical path. When multiple drawings are submitted at the same time, each drawing must be prioritized according to the critical path submitted for the Project to not overload the approval process.

105.03 Conformity with Plans and Specifications

Perform all Work and furnish all materials in reasonably close conformity with the lines, grades, cross-sections, dimensions, and material requirements, including tolerances, as shown on the Plans or as specified.

If materials, or the finished product in which they are used, or various other facets of the Work, are found not to be within reasonably close conformity with the Plans and Specifications, the Engineer will determine if the Work, as performed, is in reasonably close conformity to be adequate for the basic engineering purpose. If adequate, the Engineer may accept the material or work in question subject to an appropriate adjustment in the Contract price, and the materials or work will be permitted to remain in place. If the Engineer rejects the work as unacceptable for the intended purpose, the Contractor shall remove and replace the material or work in question, at no cost to the Department in accordance with **105.12**.

If the material or work is accepted under such conditions, the Engineer will document the basis of acceptance by Change Order providing for an appropriate adjustment in the Contract price or materials as the Engineer deems necessary based on engineering judgment. If the material or work includes predetermined pay factor adjustments, the Engineer will determine the price adjustment based on the measured level of conformance to the specifications.

All products must be listed on the Qualified Products List (QPL) and perform as specified at the time of use regardless of Letting date. Any products removed from the QPL or that do not perform as specified, must be supplied or replaced at the Contractor's expense.

Products listed on the QPL which fail to comply with Departmental performance expectations shall be removed from the QPL. Products removed from the QPL shall be replaced with an equivalent product from the QPL. At the Departments discretion, an equitable adjustment may be made to the contract for invoice price deviations.

105.04 Coordination of Plans and Specifications

These Specifications, the Supplemental Specifications, the Plans, Special Provisions, and all other documents that are part of the Contract, are intended to be complementary and to describe and provide for a complete Contract. Requirements in one of these are as binding as if occurring in all of them. In case of discrepancy the governing order is as follows:

1. Special Provisions
2. Plans
3. Supplemental Specifications
4. Standard Specifications

In interpreting Plans, calculated dimensions will govern over scaled dimensions; Contract Plans, typical cross-sections, and approved working drawings will govern over standard sheets.

If the Contract contains technical specifications relating to utility items or building structures, and the technical specifications conflict with these Specifications, the Standard Specifications will govern when the work is performed within the roadway template, shoulder to shoulder.

Do not take advantage of any error or omission in the Plans or Specifications or of any discrepancy between the Plans, the Specifications, or any other of

105.05

the Contract documents. Notify the Engineer immediately in accordance with **104.03** upon discovering any apparent error or discrepancy. The Engineer will provide an interpretation and final decision. At the Contractor's request, the Engineer will provide the final decision in writing.

105.05 Duties of Contractor

Maintain one complete set of the Contract documents, including applicable Standard Drawings, on the Project at all times. The Department will supply, without cost, two copies of the proposal form and Plans, except Standard Roadway and Structure Drawings. The Department will provide the Contractor with Standard Roadway and Structure Drawings at cost upon request.

Provide copies, in the number required by the Engineer, of all statements of proposed subcontracts. Sublet contracts in accordance with **108.01**.

Provide the Engineer with information requested by the Department related to the purchase or delivery of materials.

Give the Work the constant attention necessary to facilitate its proper progress. Cooperate with the Engineer, the Engineer's assistants and inspectors, and with other contractors in every way possible. Before starting the Work, designate in writing a representative with the authority to represent and act for the Contractor. The representative shall be present at the site of the Work at all times while work is actually in progress on the Contract. When work is not in progress or has been suspended, make arrangements acceptable to the Engineer for any emergency work that may be required. Furnish a representative irrespective of the amount of the work sublet or remaining to be performed on the Project. Whenever the representative is not present or unavailable on any particular part of the Work where it may be necessary to give direction, the Engineer may provide direction, which the superintendent or foreman who may have charge of the particular work shall receive and follow.

Designate a responsible individual as a customer service representative. This representative shall be authorized to address any customer service inquiry on the Contractor's behalf. In addition, when a Preconstruction Public Meeting is planned, the customer service representative shall attend and present the schedule and technical information regarding the Contract.

Designate a responsible individual within the Contractor organization to attend and participate in a Post Construction Project Review on all projects

with an original contract bid price of \$10,000,000.00 or more. The Department will conduct this review as soon as practical following the completion of the Work. The review shall be held to identify all significant project problems and make recommendations on how these problems can be avoided on future projects. Items to be discussed shall include, but are not limited to, cost overruns, Change Orders, completeness and accuracy of plans, and Contract obligations.

105.06 Planning of the Operations-Preconstruction Conference

After the Contract is fully executed and before beginning work, provide the Engineer with a complete and practicable plan of operations in accordance with **108.03**, which shall provide for the orderly and continuous performance of the Work. The contractor must attend a preconstruction conference arranged by the Engineer. Make available at the meeting all data necessary to substantiate the plan of operation and scheduling. When applicable, also provide the following at the conference:

1. Plan of Operation;
2. Material Suppliers List, including name and location of suppliers;
3. 24-hour emergency contact information for Traffic Control, Erosion Control, Customer Service, and Employee Safety professionals;
4. Copy of Signed Agreement between Contractor and DBE Subcontractor;
5. Detouring/Controlling Traffic Plan;
6. Erosion control and storm water pollution prevention plan;
7. Traffic Control Certification Letter;
8. Proposed traffic signing diagram;
9. Contractor Employee Safety and Health Program (ESHP) Certification Letter;
10. Listing of all subcontractors and the items and/or material they are involved with;

105.07

11. Buy America including all steel to be used including utilities, traffic and other steel components incorporated into the Project; and
12. Submit schedule for meeting Certified Payroll timeframes required under 29 CFR Sections 3.3, 3.4, and 5.5 for Contractor payroll and Subcontractor's payroll on the contract. Submit the weekly pay period end days and payroll payment days for the Contractor and Subcontractors on the project.

Ensure that all subcontractors have a safety program or participate in that of the Contractor. The Contractor is responsible for work site safety and conducting all operations to protect the workers engaged in duties connected with the Work.

In addition to this basic plan of operations, notify the Engineer of planned or contemplated operation details sufficiently in advance of starting each phase so that the Engineer may arrange for inspection. Such notice shall include the nature and location of the work planned or contemplated, the date and time of starting, and any hours outside of the conventional working day and working week during which the prosecution of such work is contemplated. Performing any work without notifying the Engineer and in the absence of inspection or a written waiver will constitute sufficient grounds for rejection of that portion of the Work.

105.07 Cooperation with Utilities, Railroads, and Pipelines

The Department will notify all utility companies, including pipeline and railroad companies, having facilities within the Project limits concerning the planned construction. The Department will make every reasonable effort to cause such parties to make the adjustments in elevation or location that may be necessary to avoid conflict with the construction and with the completed project, and to protect property from damage during construction.

In general, the Contract will indicate the various utility items known to exist, will indicate items to be adjusted or capital improvements proposed by the owners, and will designate items that are to be adjusted by the Contractor.

The location shown on the Plans for utilities are provided by the utility owners and may not be complete or accurate, especially with regard to underground installations. Contact the owners of the various utilities to determine the exact location of the utilities and the owner's schedule of any work the utility may be doing. Unless otherwise noted, the utility company

or its representative will perform all utility adjustments. Cooperate with the owners of the utilities in their adjustment operations.

Provide all necessary protective measures to safeguard existing utilities from damage during construction of the Work. Correct and pay for repairs to damaged utilities that result from the Contractor's breach of the standard of care, and restore damaged facilities to their preexisting condition.

The Engineer may require advance clear cutting at any location where clearing is called for in the Plans or Specifications, and where clear cutting is necessary for utility relocation. Costs for advance clear cutting are incidental to the price bid for the clearing item specified.

If special equipment is required to work over and around the utilities, provide such equipment. The cost of protecting utilities from damage and furnishing special equipment is incidental to the price bid for other items of construction.

At least three (3) business days prior to the start of operations around the utility, notify each individual utility owner of the plan of operation, and request that they to properly locate their respective utility on the ground.

It is understood and agreed that the Contractor has considered in its bid all of the known permanent and temporary utility appurtenances in their present and relocated positions, and any proposed utility capital improvements, that the Contractor has contacted each utility owner in regard to its proposed schedule of work and that no additional compensation will be allowed for any delays, inconvenience or damage sustained due to utilities or utility adjustment. However, the Department may consider interference caused by utilities on contracts when assessing time in accordance with **108.06**.

Where construction operations require the use of a temporary crossing with the railroad or railroad companies specifically named in the proposal:

1. Request the railroad company to construct the temporary crossings and notify the railroad company 6 weeks in advance of the time the temporary crossings are to be used. This request is subject to the Contractor executing such agreements and furnishing such insurance as the railroad company may require.
2. Assume responsibility for determining and complying with the requirements of the railroad company covering the location, installation, protection, maintenance, use, and removal of such temporary crossing. Bear all costs and expenses related to the

105.08

temporary crossing, including installation, protection, maintenance, and removal, contractual liability insurance, and incidental work such as drainage facilities and removal, alteration, and replacement of railroad fences.

105.08 Cooperation between Contractors

The Department reserves the right, at any time, to contract for and perform additional work on or near the Work. When separate contracts are let within the limits of a project, cooperate fully with the other contractors. Conduct the Work and place and dispose of materials to not interfere with or hinder the progress or completion of the portions of the Work being performed by other contractors within the project limits. Coordinate work with that of the other contractors in an acceptable manner and in proper sequence with regard to the work of other contractors. Each contractor involved shall assume all liability, financial or otherwise, in connection with its contract, and shall protect and save harmless the Department from any and all damages and claims that may develop because of inconvenience, delay, or loss experienced by any contractor because of the presence and operations of others. In the event of confusion, disagreement, or lack of cooperation between two or more contractors working within the same project limits, the Engineer will issue orders as may be necessary to coordinate the performance of all work.

105.09 Construction Stakes, Lines, and Grades

The Contractor shall cooperate in the matter of setting and preserving stakes, bench marks, lines, and grades for controlling the construction. Carefully preserve stakes and markings the Engineer may set for either its own or the Contractor's guidance. In case of negligence by the Contractor or its employees resulting in the destruction of such stakes or markings, the Department at its discretion may deduct an amount equal to the cost of replacing the same from subsequent estimates due the Contractor.

The Department will make all measurements and surveys that involve the determination of final pay quantities, including original and final cross-sections for all earthwork.

If Construction Stakes, Lines and Grades is included in the proposal form as a bid item, the following shall apply:

1. The Engineer will locate and reference the control points, i.e. PI's and POT's as shown on the Plans along the proposed mainline, and will establish benchmarks for the proper layout of the Work. The

Contractor shall locate ramps, sideroads, or similar features, make all calculations involved, and provide and place all layout stakes including those required to establish the limits of the right-of-way as shown on the Plans or as directed by the Engineer.

2. To avoid conflicts with utility installations, cooperate with the involved utility companies by timely locating highway features such as culverts, manholes, catch basins, substructure elements of bridges, and guardrail. Provide stakes for right-of-way or slopes, ditch or stream bed grades, or other essential survey staking to prevent utility conflicts with the highway construction. Frequently, this will be required as the first item of work, and at any location on the Project as directed by the Engineer. If the Contract requires adjustment or relocation of utility facilities, all layout of this work shall be the Contractor's responsibilities.
3. Place and preserve adequate ties to all control points necessary for the accurate re-establishment of all base lines or centerlines shown on the Plans, whether placed or found on the Project.
4. Place centerline stakes, subgrade hubs, stone pins, etc. at regular intervals as directed by the Engineer but not to exceed 300 feet on even stations. This frequency is intended as a maximum and in no way relieves the Contractor of the responsibility to ensure the project is constructed in accordance with the grades and lines (within specified tolerances) and that field personnel have adequate reference points to verify compliance.
5. Calculate all grades. Do not stake the project based solely on cross sections. Use cross sections for reference. Check all dimensional details shown on the Plans, including elevations to ensure accuracy of the required layout. Check all bridge substructures for location, dimensional layouts, and elevations by means of two independent layout methods. Provide right-of-way or slope stakes, ditch or stream bed grades, or other essential survey staking as directed by the Engineer. Call to the Engineer's attention all errors and apparent discrepancies found in the Plans. Provide, set, and properly reference all stakes, references, and batter boards, including original, additional, or replacements that may be required for the construction operations. Take sole and complete responsibility for the accuracy of the line and grade of all features of the Work.

105.09

6. Where pre-splitting is specified, provide the actual longitudinal profile of the rock surface for review by the Engineer and, where applicable, for adjustment of the width of the catchment area prior to any pre-splitting activity.
7. Conduct sufficient field checks of features such as existing streams, drainage, structures, pavement elevations, and road and street tie points to ensure the proposed work on the Plans will correspond with the existing and/or proposed surroundings
8. When requested by the Engineer, provide copies of all data used in establishing line and grade for all features of work, including, but not limited to, the data used in setting and referencing all stakes and layout markings.
9. When requested by the Engineer, provide safe facilities for convenient access by Department forces to control points, batter boards, and references.
10. If electing to use the Global Positioning System (GPS), submit a comprehensive written GPS Work Plan to the Engineer for Department review and acceptance at the preconstruction conference or at least 15 days before starting work using GPS. Department acceptance of the plan will in no way relieve the Contractor of the responsibility to provide accurate survey data and achieve the grades and tolerances noted in the Plans and specifications. Update the plan as necessary during construction and notify the Engineer of all changes. The GPS Work Plan shall describe how GPS enabled Automated Machine Guidance technology will be integrated into other technologies employed on the project. At a minimum, the GPS Work Plan shall include the following:
 - a. Designate which portions of the Contract will be done using GPS enabled Automated Machine Guidance and which portions will be constructed using conventional survey methodology.
 - b. Describe the manufacturer, model, and software version of the GPS equipment. The equipment shall have a degree of accuracy capable of meeting the specified tolerances applicable for the Work.

- c. Provide information on the qualifications of Contractor staff. Include formal training and field experience. Designate a single staff person as the primary contact for GPS technology issues.
- d. Describe how project control will be established. Include a list and map showing control points enveloping the site, and evidence that the control has been verified and correlated to the nearest TDOT Continuous Operating Reference Station (CORS) or provide a local base station, as appropriate. Provide the Engineer access to the local base station if utilized.
- e. Describe site calibration procedures. Include a map of the control points used for site calibration and control points used to validate the site calibration. Describe the frequency of site calibration and machine verification and how these will be documented.
- f. Describe the quality control procedures for verifying mechanical calibration and maintenance of construction and guidance equipment. Include the frequency and type of verification performed to ensure the constructed grades conform to the Contract Documents.
- g. Maintain a current copy of the GPS Work Plan at the project site.

Coordinate with the Engineer to verify the GPS derived lines and grades as needed by establishing test strips or other means. Test strips will be conducted on subgrade or other approved features, with at least one test strip of 500 feet per mile of roadway on each side of centerline or as directed by the Engineer. Make corrections and adjustments as needed if the results indicate more than a 1 inch difference between the Contractor's and the Engineer's results. The cost for test strips and other verification means will not be paid for directly but will be incidental to the price of other items. Provide the Engineer with at least 5 working days notice to schedule verification of test strips. No consideration for additional time or compensation will be made for any delays associated with the verification of the GPS derived grades, lines, and stakes.

105.10

11. For all staking, use qualified engineering or surveying personnel who are trained and skilled in construction layout and staking of the type required for the Project, and who are acceptable to the Engineer. Ensure that staking is performed under the direct supervision of a Tennessee licensed Professional Engineer or a Tennessee Registered Land Surveyor experienced in the direction of such work and who is acceptable to and may be available to meet with the Engineer.
12. The Engineer may check the control of the Work, as established by the Contractor, at any time as the Work progresses. The Engineer, at any time during the Project, may request documentation, ground control, or other information as may be needed to check on the control of the Work. The Department will inform the Contractor of the results of these checks, but by so doing in no way relieves the Contractor of its responsibility for the accuracy of the layout work. Correct and replace as required, at no additional expense to the Department, any deficient layout and construction work that may be the result of inaccuracies in layout operations, failure to report inaccuracies in layout operations, or failure to report inaccuracies found in work done by the Department or by others. If, as a result of these inaccuracies, the Department is required to make further studies, redesign, or both, all expenses incurred by the Department due to such inaccuracies may be deducted from subsequent payment estimates due the Contractor.
13. Provide all necessary personnel, engineering equipment and supplies, materials, transportation, and work incidental to the accurate and satisfactory completion of this work.

The Department will measure and pay for Construction Stakes, Lines, and Grades in accordance with **105.18** and **105.19** respectively.

105.10 Authority and Duties of Inspectors

Inspectors employed by or contracted with the Department will inspect all work done and all materials furnished. Such inspection may extend to any part or to all of the Work and to the preparation, fabrication, or manufacture of materials to be used. The Inspectors will have the authority to reject defective material and to suspend construction that is being improperly done, subject to the Engineer's final decision. Inspectors will not be authorized to revoke, alter, enlarge, or relax the provisions of the Specifications, nor will they be authorized to approve or accept any portion of the completed Project,

or to issue instructions contrary to the Plans and Specifications. At the Contractor's request, the Inspector will provide written instructions on important items.

105.11 Inspection of Work

The Engineer or its representative will inspect all materials and each part or detail of the Work. Inspection and tests are for the sole benefit of the Department and do not relieve the Contractor of the responsibility for providing adequate quality control measures, and responsibility for damage to or loss of material before acceptance. Provide access to all parts of the Work at all times and provide all information, facilities, and assistance as may be required for the Engineer to make complete and detailed inspection. All work done or materials used without supervision or inspection by an authorized Department representative may be ordered removed and replaced at no cost to the Department unless the Department representative failed to inspect after having been given reasonable notice in writing that such portion of the Work was ready for inspection.

At any time before acceptance of the Work, the Engineer may direct the Contractor to remove or uncover portions of the Work for inspection. If examination discloses that the Work is acceptable under the terms of the Contract, restore the Work to its original condition. The Department will pay for the cost of exposing the Work for examination and of returning it to the original condition as Extra Work. If the Work exposed and examined is not acceptable for the intended purpose, the Contractor will bear the cost of uncovering, removing, and replacing all of the material involved, and restoring the Work in accordance with the Specifications and Plans.

When any unit of government or political subdivision or any railroad corporation is to pay a portion of the cost of the Work covered by the Contract, its respective representatives will have the right to inspect the Work. Such inspection will not make any unit of government or political subdivision or any railroad corporation a party to the Contract, and in no way interferes with the rights of either party hereunder.

If the Contractor fails to comply with any order of the Engineer made under the provisions of this Subsection, the Engineer will have authority to repair or replace unacceptable work and deduct the costs from any monies due the Contractor. If monies due or to become due the Contractor are not sufficient to defray the costs of such repairs or replacements, then the Department will hold the Contractor's Surety liable for the costs incurred. Any Construction performed by the Department under these provisions will not waive any

105.12

provisions of the Contract nor relieve the Contractor in any way from the responsibility for the Work.

105.12 Removal of Unacceptable and Unauthorized Work

If the Engineer rejects portions of the Work found to be unacceptable in accordance with **105.03**, or found to be unacceptable prior to final acceptance of the Work due to poor workmanship, the use of defective materials, or damage through carelessness, the Contractor shall immediately remove and replace this work in an acceptable manner.

The Department is not obligated but may consider payment for work under the Contract for the following reasons:

1. Work that has been done without lines and grades having been given by the Engineer or established by the Contractor's forces, if appropriate,
2. Work done contrary to the instructions of the Engineer,
3. Work done beyond the lines shown on the Plans or as given,
4. Unauthorized work or Extra Work done without the Engineer's authority, or
5. Work performed without an approved subcontract.

The Engineer may direct the Contractor to remove or replace such work at no cost to the Department.

105.13 Completion of Specific Sections of a Project

The Department may require a specific section or sections of a Project to be completed and accepted before completion of the entire Project. Such section(s) shall be a reasonable length, as determined by the Engineer, and completed in full accordance with the Contract. When sections are completed, the Engineer, after final inspection, will accept the section(s) and relieve the Contractor of any further work or maintenance costs for the accepted section(s). The acceptance of a section or sections of a Project shall in no way waive or alter any of the terms of the Contract.

105.14 Opening Sections of a Project to Traffic

If directed by the Engineer, open certain sections of the Project to traffic even if they are not fully completed. If the paving, including the connections through the structures, is completed on any of the sections involved, the Engineer, after final inspection, may accept the pavement and relieve the Contractor of further maintenance expense in connection with the section. If the pavement is not fully completed on any of the sections ordered opened, the Contractor shall maintain the paving in accordance with **104.05**. In either case, the Contractor shall maintain the other portions of the Work in the same sections of the Project according to the Contract.

105.15 Acceptance

Upon due notice from the Contractor of presumptive completion of the entire Project, the Engineer will make an inspection. If the Engineer finds that all construction provided for and contemplated by the Contract is satisfactorily complete, then the inspection will constitute the final inspection and the Engineer will make the final acceptance and notify the Contractor in writing of this acceptance effective on the final inspection date.

If, however, the inspection discloses any work not in close conformity with the Plans and Specifications, in whole or in part, the Engineer will instruct the Contractor to correct the unsatisfactory work. The Contractor shall immediately comply with and execute such instructions. After correction of the Work, the Engineer will make another inspection, which shall constitute the final inspection, provided the Work has been satisfactorily completed. If satisfactory, the Engineer will make the final acceptance and notify the Contractor in writing of this acceptance to be effective on the final inspection date. Final acceptance under this subsection does not waive any of the Department's legal rights under **107.19**.

105.16 Claims for Adjustment and Disputes

The claims process described within this subsection details the process within the Department for receiving, reviewing, and deciding on claims submitted. If such claims cannot be successfully negotiated or resolved within this process, the Contractor has the right to submit a formal claim through the Tennessee Claims Commission.

105.16

A. Notice of Intent to File a Claim

If the Contractor has requested additional compensation, time, or both under **104.02** or **108.07**, has provided notification in accordance with **104.03**, and the Engineer has denied the request for a change to the Work, the Contractor may provide notice of intent to file a claim. The Contractor shall provide such notice in writing within thirty (30) calendar days of receiving the Engineer's decision as provided in **104.03**.

After filing the notice of intent to file a claim, the Contractor shall maintain adequate records related to the claim, including records of the disputed labor, equipment and materials, and, if applicable, monthly schedule updates showing critical path delays to the completion date. Update and disclose this information to the Department monthly. The Department may audit claim records at any time. Unless the Engineer suspends in writing the affected work, the Contractor shall continue to perform the disputed work. If such notice to file a claim is not given, or if the Engineer is not given sufficient opportunity for keeping strict account of the Contractor's actual costs, then the Contractor waives any claim for additional compensation. Such notice by the Contractor and the Engineer's accounting of the cost shall not in any way prove or substantiate the validity of the claim. Nothing in this Subsection shall be construed as establishing any claim contrary to the terms of **104.02** or **108.07**.

B. Informal Claim Meeting

Upon written request by the Contractor submitted with its notice of intent to file a claim, and within thirty (30) days of such request, the Department will afford the Contractor an opportunity to discuss the disputed matters informally with a Department official having the authority to resolve the dispute. The Contractor may use this opportunity to present relevant information and respond to any information provided by the Engineer or other Department officials with knowledge of the Work. Proceedings in the Informal Claim Meeting are an attempt to mutually resolve a claim without litigation and are not admissible for any purpose in any proceeding contemplated in this Subsection **105.16** or any formal administrative hearing.

If as a result of the Informal Claim Meeting the Department and the Contractor reach an agreement to resolve the claim, the Department will prepare a Change Order setting forth the terms of any additional compensation or time, or both, as agreed, and the Change Order will be

processed for approval in accordance with the Department's standard procedures.

If the Department agrees that the Contractor is due additional compensation, time, or both, but the Department and the Contractor cannot agree on the amount, the Department may at any time after the Informal Claim Meeting issue a Change Directive providing for additional compensation, time, or both, as the Department determines to be fair and reasonable. The Contractor shall perform the Work in accordance with the Change Directive, but such performance shall not constitute a waiver of the Contractor's claim regarding the disputed work. The Contractor may continue to pursue a claim as provided in this section.

C. Submission of Claim

Within ninety (90) calendar days after submitting the notice of intent to file a claim, or within ninety (90) days of the completed disputed Work, whichever is later, or such time agreed upon by the parties in writing, the Contractor shall submit a complete claim package. The claim package shall include all documents supporting the claim and provide sufficient detail to enable the Department to ascertain the basis and amount of the claim. If requested by the Contractor, the Department may extend the ninety (90) day period in writing. As a minimum, the following information shall be submitted with each claim:

1. A claim certification containing the language shown in Figure 105.16-1 for direct claims by the Contractor, or Figure 105.16-2 for pass-through claims, as appropriate;
2. A detailed factual statement of the claim for additional compensation, time, or both, providing all necessary dates, locations, and items of work affected by the claim;
3. The date on which facts were discovered that gave rise to the claim;
4. The specific provisions of the Contract that support the claim and a statement of the reasons why such provisions support the claim;
5. If an extension of contract time is sought, a schedule analysis as required by **108.07**; and

105.16

6. If additional compensation is sought, the amount and specifics of the compensation.

CONTRACTOR'S CLAIM CERTIFICATION
Under penalty of law for perjury or falsification, the undersigned, (Authorized Representative) _____, (title) _____, of (company) _____, hereby certifies that the claim of \$ _____ for extra compensation and ____ Days additional time, made herein for work on this Contract:
<ol style="list-style-type: none">(1) Is true and made in good faith(2) The supporting data is accurate and complete;(3) The claim is fully supported under the Contract between the parties; and(4) The claim amount accurately reflects the Contractor's actual incurred costs or delay.
I have reviewed the documents submitted and know the facts and information to be true based upon my personal knowledge and belief.
This claim package contains all available documents that support the claims made herein and I understand that no additional information, other than for clarification and data supporting previously submitted documentation, may be presented by me.
Dated _____/s/_____
Subscribed and sworn before me this __ day of _____
_____.
_____ NOTARY PUBLIC
My Commission Expires: _____

Figure 105.16-1: Contractor's Claim Certification

PASS-THROUGH CLAIM CERTIFICATION

Under penalty of law for perjury or falsification, the undersigned, (Authorized Representative) _____, (title) _____ (company), _____, hereby certifies that the claim of \$ _____ for extra compensation and ___ Days additional time, made herein for work on this Contract:

- (1) Is true and made in good faith
- (2) The supporting data is accurate and complete;
- (3) The claim is fully supported under the Contract between the parties; and
- (4) The claim amount accurately reflects the Contractor's actual incurred costs or delay.

I have reviewed the documents submitted and know the facts and information to be true based upon my personal knowledge and belief.

This claim package contains all available documents that support the claims made herein and I understand that no additional information, other than for clarification and data supporting previously submitted documentation, may be presented by me.

Dated _____/s/ _____
 Subscribed and sworn before me this __ day of _____.

 NOTARY PUBLIC
 My Commission Expires: _____

Dated _____/s/ _____

The Contractor certifies that the claim being passed through to TDOT is passed through in good faith and is accurate and complete to the best of my knowledge and belief.

Dated _____/s/ _____
 Subscribed and sworn before me this __ day of _____.

 NOTARY PUBLIC
 My Commission Expires: _____

Figure 105.16-2: Pass-Through Claim Certification

D. Department Decision

When the Contractor properly files a claim and allows for reasonable and timely access to the Contractor's books and records, the Department will review the claim and render a written decision to the Contractor to either affirm or deny the claim, in whole or in part, within sixty (60) calendar days after receipt of the claim package or at such time agreed upon by the parties.

The Department will assemble and maintain a claim record consisting of all information submitted by the Contractor in support of the claim and all other information considered by the Department in reaching a decision. Once the Department assembles the claim record, the submission and consideration of additional information or data, other than for clarification and support of previously submitted documentation, will not be permitted. The Department will provide a copy of the claim record and the written decision to the Contractor describing the information considered by the Department in reaching a decision and the basis for that decision.

If the Department decides to affirm the claim, an adjustment will be made in accordance with **108.07** and **109.04** as applicable. If the Department denies the claim, the Contractor may either accept the Department decision as final or file a written appeal to the Department's authorized representative identified in the final decision letter within sixty (60) calendar days from the receipt of the Department decision.

If a written appeal is not properly or timely filed, the Engineer's decision is final and binding, and the Contractor waives any further rights to pursuing the claim.

If the Department fails to render a written decision within sixty (60) calendar days after receipt of the claim package, or within any extended time period as agreed to by the parties, the Department will send written notice to the Contractor that the decision period has ended and that the Contractor's time period for written appeal has begun.

E. Appeal Process

When a claim is appealed in writing, the Department will provide the claim record to the duly authorized representative responsible for review of the appeal. Within fifteen (15) calendar days after the submission of the appeal, either party may submit a written request for a hearing with

the duly authorized representative. The duly authorized representative will review the claim and render a decision to affirm, overrule, or modify the Department decision within sixty (60) calendar days or such time agreed upon by the parties after receiving the written appeal.

The Department will not consider any new information that was not previously made a part of the claim record, other than clarification of the previously submitted documentation. The Contractor shall have sixty (60) calendar days to accept or reject the duly authorized representative's decision. The Contractor shall notify the Department of its acceptance or rejection in writing. If the Contractor accepts the duly authorized representative's decision, the decision will be implemented with a Change Order in accordance with the applicable Contract provisions. If the Contractor disagrees with the decision, the Department may issue a Change Directive to implement the decision, and the Contractor shall perform the Work in accordance with the Change Directive. Performance of the Work in accordance with the Change Directive shall not constitute a waiver of the Contractor's right to pursue a formal claim with the Claims Commission as provided below.

The Contractor may file a claim with the Tennessee Claims Commission in accordance with TCA § 9-8-307. The parties understand and agree that the Contractor's failure to bring suit within one-hundred-eighty (180) calendar days of the duly authorized representative's decision, or such other time agreed upon by the parties, shall be deemed an acceptance of the decision and a complete bar to any such claims or causes of action based on the claim.

105.17 Alternative Equipment

Although certain Specification Sections may specify use of equipment of a particular size and type, or use of certain methods to perform portions of the Work, it is to be understood that the development and use of new or improved equipment or methods are encouraged.

The Contractor may request, in writing, permission from the Engineer to use equipment of a different size or type in place of the equipment specified. The Contractor may request to use new methods in the same way.

If the Engineer grants such permission, it shall be understood that permission is granted for the purpose of testing the quality of work actually produced by such equipment or method and is subject to continuous attainment of results that are equal to, or better than that which can be obtained with the equipment or method specified. The Engineer will withdraw such permission at any

105.18

time if it is determined that the alternative equipment or method is not producing work that is equal, in all respects, to that which can be produced by the equipment and methods specified. Upon withdrawal of such permission by the Engineer, the Contractor shall use the equipment or method originally specified, and remove and dispose of or otherwise remedy, at no additional cost to the Department, all defective or unsatisfactory work produced with the alternative equipment or method.

The Contractor shall not pursue any claim against the Department for either withholding or granting permission to use alternative equipment or methods or for the withdrawal of such permission.

The Engineer will only grant permission to use alternative equipment in place of equipment specified where such equipment is new and improved, or more adaptable to the work being performed. The approval for use of particular equipment on any project should not in any way be considered as an approval of the use of such equipment on any other project. The Engineer will grant permission to use alternative methods under the same rules governing equipment.

COMPENSATION

105.18 Method of Measurement

The Department will measure construction Stakes, Lines and Grades as a percentage of the lump sum price bid for the completion of the work specified in **105.09** and partial payment will be made according to the schedule in Table 105.18-1.

Table 105.18-1: Payment Schedule for Construction Stakes, Lines and Grades

Estimate Number or Percent of Total Contract Amount of Previous Estimate	Total Percent of Construction Stakes, Lines, and Grades Lump Sum Bid Item
Estimate # 1	20%
Estimate # 2	40%
10%	50%
20%	60%
40%	70%
60%	80%
80%	100%

105.19 Basis of Payment

The Department will make partial payments for Construction Stakes, Lines and Grades on the basis of a percentage of the lump sum price bid in accordance with the schedule shown in Table 105.18-1. Submit a certification of the personnel and the name, license number, and qualifications of the Tennessee licensed Professional Engineer or a Tennessee Registered Land Surveyor who is performing the work, as specified in **105.09**, Construction Stakes, Lines, and Grades at the preconstruction meeting. No payment for Construction stakes, lines, and grades will be made until the certification has been received.

Such payment is full compensation for furnishing, setting, maintaining, and resetting, when necessary, the stakes, and for providing all labor, equipment, materials, and incidentals to complete the work as specified.

106.01

SECTION 106 – CONTROL OF MATERIALS

106.01 Quality of Materials	58
106.02 Material Information	58
106.03 Local Material Sources	58
106.04 Sampling and Testing, or Inspection.....	59
106.05 Source or Plant Inspection.....	60
106.06 Field Laboratory.....	60
106.07 Notice of Source or Arrival of Materials.....	62
106.08 Handling and Storage of Materials.....	62
106.09 Resampling and Testing, or Reinspection.....	63
106.10 Defective Material.....	63

106.01 Quality of Materials

Only use materials in the Work that conform to all of the Contract quality requirements. Control and incorporate materials to produce completed construction that conforms to and is fully acceptable under the terms of the Contract.

Where reference is made in the Contract to certain manufacturers' materials or products, it is not the intent to preclude the use of others, but rather to establish minimum acceptable design standards. The Contractor may substitute material and products of other manufacturers provided they are equal to or better than the minimum design standards and are approved by the Department.

106.02 Material Information

When local material reports are available the Department will provide the Contractor the test report per the specific request. In furnishing such reports, the Department will not be responsible for materials failing to conform to the test reports either as to quality or quantity.

106.03 Local Material Sources

If the Contractor desires preliminary tests of local materials, it shall deliver samples of the materials to the Laboratory. The Department will test one sample (and one referee sample as needed), and in such time as the work load

in the Laboratory may permit. Acceptable test results on preliminary samples will not guarantee acceptance of materials from the same source later.

106.04 Sampling and Testing, or Inspection

Incorporate into the Work only those materials that have been sampled and tested, inspected, and approved by the Engineer. Untested or unaccepted materials used in the Work without the Engineer's written permission shall be removed and replaced at no cost to the Department. Unless otherwise specified, sampling and testing, or inspection will be conducted by qualified representatives in accordance with the most current published national standard specifications, AASHTO or ASTM methods on the date of the Advertisement. Furnish all materials for sampling and testing at no cost to the Department. The Department will perform acceptance and verification sampling and testing, or inspection at no expense to the Contractor. If the Department does not elect to sample and test or inspect at the source, it will sample and test, or inspect, materials after delivery to the site or to the production facility. Furnish all facilities and provide all reasonable assistance to secure and transport samples, and move materials being inspected.

The Departmental procedures will provide sampling and testing frequencies for the acceptance, quality control, independent assurance, verification, or certification for materials and products.

The Engineer may accept certain materials or products and assemblies based on Certificate of Compliance signed by the manufacturer or its authorized representative, stating that such materials, products, and assemblies fully comply with the requirements of the Contract. For each lot of such materials or assemblies delivered to the Work, provide a Certificate of Compliance that clearly identifies the lot. Provide all necessary paperwork with certification submittals as specified in Departmental Procedures.

Furnish a notarized Certificate of Compliance for a non-bid item, not permanently incorporated in the Work, but that must meet a designated specification upon delivery of the material to the Project and prior to its being used.

The Department may sample and test materials, products, or assemblies accepted on the basis of Certificate of Compliance at any time, and may reject such materials and assemblies if found to be in non-conformance with the Contract.

106.05

106.05 Source or Plant Inspection

The Contractor is entirely responsible for securing satisfactory material. However, if the volume of any given material, the progress of construction, and other considerations of interest to the Department so justify, the Department may inspect materials at the source of supply. The Department will undertake such inspection only when the Engineer is assured of the fullest cooperation and assistance of the Contractor and of the material producer involved. Provide required copies of all orders, shipping information, and other Procedural Documentation.

Provide the representatives of the Department with free and safe access at all times to parts of the site or producer's facility concerning the manufacture and production of material for the Project. If the Contractor is not the owner of the place where fabrication, preparation, or manufacture is in progress, the plant owner is deemed to be the agent of the Contractor with respect to the obligation assumed hereunder.

106.06 Field Laboratory

Furnish Type A or Type B laboratory(s) or both, as required to be used exclusively for testing purposes. Provide suitable field laboratories or inspection offices at the production facility at which off-site inspection is provided by the Department under **106.05**. Locate the laboratory(s) as directed by the Engineer. Install, equip, and make building(s) ready for use before the Contractor's operations require field testing.

All Contractor and producer laboratories must be inspected and qualified in accordance with TDOT procedures before the Contractor can perform any work.

A. Type A

Laboratory consisting of a building, room, or dedicated area having at least 120 square feet of floor area with a minimum width of 8 feet and a minimum height of 7 feet. Provide laboratory space that is floored, roofed, sealed inside, weather-tight, and furnished with electricity. Furnish an organized space as necessary for the testing to be completed.

Provide lights, electrical outlets, and adequate ventilation for the tests being performed. Provide suitable heat and air conditioning. Equip the laboratory with an oven capable of maintaining a temperature of 230 °F

plus or minus 9 °F. Stove tops and hot plates may be used to determine moisture conditions of aggregates.

When the determination of aggregate gradation is required, furnish the following equipment:

1. Scales of appropriate capacity and design to weigh the required samples. Scales are to be sensitive to within 0.1% of the sample to be weighed. Provide standard weights for scale calibration. Scale calibration should be completed every six months, by an independent source, with no calibration exceeding 6 months to the day.
2. Screens of appropriate size and mesh to separate the samples into the required series of sizes. Woven wire cloth shall conform to AASHTO M 92. Screens for running gradations of coarse aggregates shall meet AASHTO T 27 and **905**.
3. A mechanical shaker approved by the Engineer and suitable for running both coarse and fine aggregate.
4. Facilities to perform wash tests according to AASHTO T 11 that include an adequate and suitable water supply.

B. Type B

In addition to meeting all the requirements for a Type A Laboratory, a Type B Laboratory shall be equipped with the following:

1. Laboratory space with a minimum of 300 square feet.
2. Two vacuum extractors, each having a minimum bowl capacity of 100 troy ounces meeting the requirements of AASHTO T 164, or one vacuum extractor and one ignition furnace meeting the requirements of AASHTO T 308. Supply an adequate amount of an approved solvent from the Department's Qualified Products List and provide for storage and disposal of the waste solvent in accordance with the regulations promulgated under the Tennessee Hazardous Waste Management Act.

To ensure adequate ventilation, house the extractor and drying equipment in an enclosed hood. Equip the hood with an exhaust fan vented to the outside and mounted at the appropriate location in

106.07

order to remove the vapors of the solvent. Where the extractor is installed outside the laboratory, only vent the drying equipment as outlined above.

3. Supply apparatus meeting the requirements of AASHTO T 166, Section 3.1 and 3.2 for determining the bulk specific gravity of compacted asphalt mix. When required by the Contract, supply an apparatus meeting the requirements of AASHTO T 209, Section 3.1 through 3.5 for determining the maximum specific gravity of an asphalt mix.
4. Supply a minimum of two suitable thermometers with an approximate temperature range of 50 to 400 °F.
5. Provide a furnace capable of performing loss on ignition tests for a minimum 10-troy ounce sample.
6. When required as specified in **407.03**, provide equipment needed to perform Marshall Tests according to AASHTO T 245. The compactor shall be a Marshall Mechanical type with rotating mold(s) and slanted foot hammers that produce a modified kneading action.

Unless otherwise specified in the Contract, the Department will not pay for Field Laboratories as a separate item but will consider it incidental to the applicable contract items.

106.07 Notice of Source or Arrival of Materials

Purchase all materials sufficiently in advance of incorporating into the Work to allow the Engineer to conduct sampling and testing, or inspection. Provide the Department, in writing, the name and location of suppliers that will furnish materials for the Project. When the Department does not elect to perform materials sampling and testing, or inspection at the source, advise the Engineer in writing within 24 hours after materials requiring sampling for testing, or inspection, are delivered to the site of the Work.

106.08 Handling and Storage of Materials

Transport all materials in tight, clean vehicles, and prevent contamination, segregation, or other damage to the materials when in route to the job site or the production facility, and when moved from point to point at later stages.

Store materials to preserve their quality and fitness for use. When considered necessary, store materials in weatherproof buildings, place them on wooden platforms or other hard, clean surfaces but not on the ground, and cover them when directed. Locate stored materials to facilitate prompt inspection. Do not use private property for storage purposes without written permission of the owner or lessee. If using portions of the right-of-way for storage of materials or erection of production facilities, obtain the specific approval of the Engineer.

106.09 Resampling and Testing, or Reinspection

At the option of the Engineer, the Department may resample and test all materials or re-inspect at any time after delivery to the site, or to any production facility. If such materials are found to be unacceptable, the Department will reject the materials.

106.10 Defective Material

Do not deliver to the site materials found to be unacceptable or rejected elsewhere. Remove rejected materials from the site or production facility at no cost to the Department.

107.01

**SECTION 107 – LEGAL RELATIONS AND
RESPONSIBILITY**

107.01	Laws to be Observed.....	64
107.02	Load Restrictions on Projects Under Construction	65
107.03	Permits, Licenses, and Taxes	66
107.04	Patented Devices, Materials, and Processes	66
107.05	Restoration of Surfaces Opened by Permit	66
107.06	Federal Aid Provisions.....	67
107.07	Bridges over Navigable Waters.....	68
107.08	Environmental Protection.....	68
107.09	Sanitary Provisions	73
107.10	Safety	73
107.11	Use of Explosives.....	74
107.12	Promptness of Performance	74
107.13	Legal Responsibilities of the Contractor	75
107.14	Contractor’s Responsibility for Work	76
107.15	Liability Insurance	76
107.16	Right-of-Way	76
107.17	Personal Liability of Public Officials.....	77
107.18	Claims Against the Department	77
107.19	No Waiver of Legal Rights	77
107.20	Certified Payrolls	78
107.21	Quarantine Restrictions – Pest Control	78

107.01 Laws to be Observed

Keep fully informed and comply with all of the following that affect the conduct of the Work or those engaged or employed on the Work: Federal and State laws, local laws and ordinances, regulations, and all orders and decrees of bodies or tribunals having jurisdiction or authority related to the Work.

Protect and indemnify the State and its representatives against claims or liability arising from or based on the violation of any such law, ordinance,

regulation, order, or decree, whether by the Contractor, its employees, subcontractors and suppliers, or any others engaged by the Contractor.

Should the Contractor’s unapproved activities relating to the performance of the Work be in violation of any of the above laws or regulations and cause fines and/or penalties to be assessed against the Department, the Department may deduct all fines and penalties from monies due the Contractor.

107.02 Load Restrictions on Projects Under Construction

A. Delivery of Materials

The gross weight of trucks delivering material to construction projects shall be governed by State Law as set forth in Tennessee Code and Federal Law. Conspicuously display the tare weight, the allowable gross weight for State Highways, and the allowable gross weight for the Interstate System on the side of all delivery trucks. Use the Bridge Formula to determine allowable Interstate System gross weights as defined in the FHWA’s publication, *Bridge Formula Weights*.

Do not operate equipment of excessive weight or loading that may cause damage to structures, the roadway, or to any other type of construction. Limit the hauling of materials over the base course or surface course under construction as directed by the Engineer. Do not load a concrete pavement, base, or structure before the expiration of the cure period. Assume responsibility for all damage done by equipment used in construction of the Project.

Where it is necessary to haul material over a structure without a posted load limit, limit the gross loads to the weights listed below. Do not exceed the loads posted for structures with weight limitations unless adequate shoring is provided and written permission is granted by the Department’s Division of Structures.

Maximum axle load	20,000 pounds
Maximum load per axle on tandem axles	17,000 pounds
Maximum total load.....	80,000 pounds

Place approved temporary guides on the bridge floor, as directed by the Engineer, to position the wheel loads directly over the bridge girders as nearly as possible. Keep the bridge floor free of debris to reduce impact forces. Limit the maximum speed to 15 miles per hour.

107.03

Once hauling over the bridge is complete, clean the bridge floor, curbs, and rail in a manner acceptable to the Engineer.

B. Construction Loads

Construction loads include all material, component, equipment, and personnel loads applied to the roadway or structure other than those attributable to permanent elements of the roadway structure in their final state of construction. Do not place any construction loads that are non-essential to the active construction work on roadways or structures. Limit the hauling of materials over the roadway base course or surface course under construction as directed by the Engineer. Construction loads are not allowed on concrete pavements, base, or structures before the end of the curing period. For concrete structures without posted load limitations, refer to **604.28** for construction loading limitations and requirements applied to these bridges or structures.

107.03 Permits, Licenses, and Taxes

Obtain all permits and licenses, pay all charges, fees, and taxes, and give all notices and submit all paperwork necessary and incidental to the due and lawful prosecution of the Work, except those permits and licenses that the Department is required to obtain.

107.04 Patented Devices, Materials, and Processes

Provide suitable legal agreement with the patentee or owner for any design, device, material, or process covered by letters of patent or copyright used in the construction of the Work. The Contractor and the Surety shall indemnify and save harmless the State, any political subdivision within the State, or any affected third party from any and all claims for infringement by reason of the use of any such patented design, device, material, process, trademark, or copyright. Indemnify the State for costs, expenses, and damages that it may be obligated to pay by reason of an infringement, during the prosecution or after the completion of the Work.

107.05 Restoration of Surfaces Opened by Permit

The right to construct or reconstruct any utility service in the highway, road, or street that is under construction or reconstruction as part of the Project, or to grant permits for same, is expressly reserved to the Department for the proper authorities of the municipality or other governing units in which utility work is done. During the life of the Contract, allow parties bearing such

permits, and only such parties, to make openings in the pavement. Permits, in general, will require the utility companies to restore the Work to the condition that existed prior to the utility adjustment. When restoration is not made by the utility and when directed by the Engineer, make all necessary repairs due to such openings in a manner acceptable to the Engineer. The Department will make payment for such restoration at the unit prices for Contract items applicable to the work, or as Extra Work as provided for under **104.02** and in accordance with **109.04**. The Department will not pay for any damages associated with the digging up of the street or right-of-way or for any delay occasioned by the restoration.

107.06 Federal Aid Provisions

1. When the United States Government pays for all or any part of the Project cost, observe the Federal laws and the rules and regulations made pursuant to such laws. Allow for the inspection of the Work by appropriate Federal Agencies. Such inspection will not make the Federal Government a party to this Contract, and will in no way interfere with the rights of either party.
2. Comply with Section 106 of the National Historic Preservation Act for all waste and borrow areas outside the Project right-of-way. Furnish the Engineer and the Environmental Division with an Archaeological Clearance certified by the State Historic Preservation Office at least thirty (30) calendar days before starting work on all non-commercial material sources requiring excavation or fill.
3. Regardless of prior certification, if prehistoric remains or human burial sites are encountered at any time during construction, suspend operations and immediately notify the Engineer and the State Historic Preservation Office.
4. Comply with Section 7 of the Endangered Species Act for all waste and borrow areas outside the Project right-of-way. Furnish the Engineer and the Environmental Division with Threatened and Endangered Species Clearance from the Tennessee Wildlife Resource Agency and the U.S. Fish and Wildlife Service at least thirty (30) calendar days before starting work on all waste and borrow sites located outside the Project right-of-way.

107.07

107.07 Bridges over Navigable Waters

Conduct all work in or over navigable waters to not interfere with the free navigation of the waterways and not impair the existing navigable depths except as allowed by permit issued by the U.S. Army Corps of Engineers or the U.S. Coast Guard.

Comply with all provisions and requirements set forth in all applicable permits. Direct all required correspondence with the Coast Guard, or such agency as may have jurisdiction, through the office of the Engineer. Provide all Contractor required permits to the Engineer before beginning work in or over navigable waters.

Comply fully and faithfully with the various requirements established by the Corps of Engineers, the Coast Guard, and other agencies that may have jurisdiction over the work in and over navigable waters applicable to the Contract, and which may not be covered by existing permits. Such work may include, but not necessarily be limited to, dredging, location and safeguards for cofferdams and temporary falsework, anchorage of barges and construction equipment, temporary restriction of channel width, lighting during construction, and removal of all temporary construction.

107.08 Environmental Protection

A. Protection of Streams, Lakes and Reservoirs

Exercise every reasonable precaution throughout the life of the Project to prevent silting of rivers, streams, and impoundments (lakes, reservoirs, and similar). Construct drainage facilities as well as other Contract work that will help control siltation in conjunction with earthwork operations or as soon thereafter as is practicable.

Before suspending construction operations for any appreciable length of time, shape the top of earthwork to allow the runoff of water, and construct temporary earth berms along the top edges of embankments to intercept runoff water. Construct temporary erosion and sediment control measures deemed necessary by the Engineer in the immediate vicinity of rivers, streams, or impoundments. Comply with the provisions and requirements of all the applicable permits. Maintain these temporary measures, which may include berms, dikes, slope drains constructed of concrete, metal, or wood, or stabilized by paving or covering with waterproof materials, or sedimentation basins, until the

permanent drainage facilities and erosion control features are complete and operative.

Obtain necessary permits related to operations not covered by the Plans, including use of waste and borrow sites. Obtain necessary permits for offsite staging areas. Determine if additional permits or modifications to existing permits are required to complete the Work as shown on the Plans. All costs associated with any support activities including obtaining permission from landowners, permits, and compliance are to be included in the bid cost for the project.

The Department will acquire the necessary permits related to waters of the United States as defined in 33 CFR Part 323 or waters of the State as defined in TCA §69-3-103 for construction indicated on the Plans. These permits will govern the Contractor's method of construction. Permit modifications will be allowed only when required to complete the Work shown on the Plans. Permit modification will not be allowed for Contractor convenience. The Department may assist in the acquisition of additional permits or permit modifications when deemed necessary to complete the Work shown on the Plans.

Unless otherwise approved in writing by the Engineer, restrict construction operations in rivers, streams, and impoundments to permitted areas necessary to complete the Work as indicated on the Plans and in the field Stormwater Pollution Prevention Plan (SWPPP). Comply with the provisions and requirements of all the applicable permits. Do not perform in-stream work where a channel change is required until after the new channel has been completed and the water diverted to the new channel. As soon as practicable, clear rivers, streams, and impoundments of all falsework, temporary piling, debris, or other obstructions placed therein or caused by the construction operations.

Provide temporary bridges or other structures in accordance with all permits when crossing live streams with construction equipment.

The location, permitting, and use of waste and borrow sites, other than commercially operated sources, shall be subject to the requirements of the Department's manual *Procedures for Providing Offsite Waste and Borrow on TDOT Construction Projects*.

Exercise every reasonable precaution throughout the life of the Project to prevent the discharge of any substance into the waters of the United States and waters of the State or to place or cause any substance to be

placed where it, either by itself or in combination with other substances, may cause harm, potential harm, or detriment or damages by alteration of the physical, chemical, biological, bacteriological, or radiological properties of such waters. Prevent changes in temperature, taste, color, turbidity, or odor as will result or likely result in harm, potential harm, or detriment to the public health, safety, or welfare, or the foregoing to the health of animals, birds, fish or aquatic life, or render or will likely render such waters potentially less useful for domestic, municipal, individual, agricultural, recreational, or other reasonable uses, or leave or will leave such waters in such condition as to violate any Federal, State, and local standards of water quality. Do not discharge pollutants such as chemicals, fuels, lubricants, bitumens, raw sewage, and other harmful materials into or alongside of rivers, streams, and impoundments or into natural or manmade channels leading thereto. If a discharge as described above occurs, stop the Work, notify the Engineer, and the Tennessee Department of Environment and Conservation, Division of Water Resources, and take immediate actions to contain and remediate the discharge. Perform containment and remediation work at no cost to the Department.

Conduct and schedule operations to not interfere with the movement and habitat of species such as mussels, fish, and birds as indicated in plans or permits. Comply with the provisions and requirements of all applicable permits and United States Fish and Wildlife Service Biological Opinion.

Exercise every reasonable precaution to prevent fish kills while performing any Work activity in waters of the United States and waters of the State. Pay any costs incurred by the Tennessee Wildlife Resources Agency to monitor for fish kills during blasting or demolition of structures. If a discharge or change described above results in a fish kill, pay any fines or costs related to the fish kill.

If the Work involves painting or texturing bridges over the waters of the State, before starting such work, submit to the Engineer for approval a proposed remedial plan to contain and remove accidental discharges into the water. On the receipt of this proposed plan, the Department will assign an Inspector to ensure adherence to these Contract requirements. The Inspector will have full authority to suspend any work that is not in compliance with the Contract.

Unless otherwise provided for in the Contract, the work described herein will be considered incidental to various Contract items.

B. Forest Protection

In carrying out work within or adjacent to State or National Forests, or other wooded areas, comply with all regulations of the State Fire Marshal, Division of Fire Prevention, Department of Commerce and Insurance of the State, or other authority having jurisdiction, governing the protection of forests and work within forests, and observe all sanitary laws and regulations when performing work in forest areas. Keep the areas in an orderly condition, dispose of all refuse, obtain permits for the construction and maintenance of all construction camps, stores, warehouses, residences, latrines, cesspools, septic tanks, and other structures in accordance with the requirements of the Forest Supervisor.

Take all reasonable precautions to prevent and suppress forest fires and require employees and subcontractors, both independently and at the request of Forest officials, to do all that is reasonably within their power to prevent and suppress and to assist in preventing and suppressing forest fires. Make every effort to immediately notify a Forest official of the location and extent of any fire discovered.

C. Hazardous or Toxic Waste

When the Contractor's operations encounter or expose any abnormal condition that may indicate the presence of hazardous or toxic waste, discontinue such operations in the vicinity of the abnormal condition and immediately notify the Engineer in accordance with **104.03**. The presence of barrels; discolored earth, metal, wood, and similar; visible fumes; abnormal odors; excessively hot earth; smoke; or other conditions that appear abnormal may be indicators of hazardous or toxic wastes and shall be treated with extraordinary caution. Do not resume operations until so directed by the Engineer.

Dispose of all hazardous or toxic waste encountered during construction in accordance with the requirements and regulations of the applicable Federal, State, and local laws.

For necessary work performed to dispose of hazardous or toxic waste, the Department will make payment at the unit prices for Contract items applicable to such work, or as Extra Work under **104.02** and in accordance with **109.04**.

D. Air Pollution Responsibilities

Comply with all Federal, State, and local air pollution control rules, regulations, ordinances, and statutes that apply to work performed pursuant to the Contract, including, but not limited to, applicable air pollution control rules, regulations, ordinances, and statutes specified in the Tennessee Department of Environment and Conservation's (TDEC) Air Pollution Control Regulations and municipal regulations pertaining to air pollution.

Notify the TDEC Division of Air Quality Control a minimum of ten (10) days prior to demolition of any bridge or major structure.

E. Migratory Birds

The following procedure will be automatically implemented by TDOT, unless FWS approves in writing deviations due to special circumstances, or for a specific variance.

Cliff swallow and barn swallow nests, eggs, or birds (young and adults) will not be disturbed between April 15 and July 31. From August 1 to April 14, nests can be removed or destroyed, and measures implemented to prevent future nest building at the site (i.e., closing off area using netting).

Exceptions:

- (1) If there are no eggs in the nests prior to April 15, TDOT will be allowed to destroy the nests and prevent further nest building at the site, by installing netting. Net openings shall be ½ inch or smaller after installation, and shall be installed securely and in such a manner that it will not pose a safety hazard. Absence of eggs prior to net installation must be documented by using appropriate means for determination, such as, but not limited to, site visits and photographs.
- (2) If there are no birds (young or adult) left in any of the nests at a specific site prior to July 31, the nests can be removed or destroyed. Absence of birds must be documented by using appropriate means for determination, such as, but not limited to, site visits, photographs, and observations of no birds using the nests.

Osprey, Double Crested Cormorants, Great Horned Owls, Barn Owls, Black Vulture, and Eastern Phoebes: if these avian species are encountered on a bridge project, TDOT Ecology should be contacted immediately for further assistance.

The Contractor will be assessed the amount of any and all fines and penalties assessed against and cost incurred by TDOT which are the result of the Contractor's failure to comply with this specification. TDOT will not be responsible for any delays or costs due to the Contractor's failure to comply. Additional compensation or contract time due to noncompliance will not be granted.

All costs incurred with this specification will not be measured or paid for separately, but will be considered included in the contract unit prices bid for other items of the contract.

107.09 Sanitary Provisions

Provide and maintain in a neat, sanitary condition accommodations for employees as may be necessary to comply with the requirements of the State and local Boards of Health, or of other bodies or tribunals having jurisdiction.

107.10 Safety

A. Public Convenience and Safety

Conduct the Work at all times to ensure the least possible obstruction to traffic. Provide for the safety and convenience of the general public and the residents along the highway, and for the protection of persons and property as specified in **104.04, 104.05, 104.06, and 104.08.**

B. Employee Safety and Health Program

The Contractor is responsible for work site safety and conducting all operations to protect the workers engaged in duties connected with the Work. Provide an Employee Safety and Health Program (ESHP) at the preconstruction conference that meets or exceeds all Federal, State, and local safety and health standards and is certified by the safety professional responsible for developing the ESHP. Certification of the ESHP is required before any work can begin. Maintain an original copy of the ESHP and provide to the Department upon request.

107.11

The Contractor is responsible for implementing, monitoring, updating, and revising the ESHP. Describe in detail how the ESHP is implemented and monitored. Provide guidelines for protecting personnel from hazards associated with project operations and activities. Establish the policies and procedures for safety practices that are necessary for the Work to be in compliance with the requirements of TOSHA, the MUTCD, and other State and Federal regulatory agencies with jurisdiction, rules, regulations, standards, or guidelines in effect at the time the Work is in progress. If an incident occurs that requires hospitalization or TOSHA Citation to be submitted, send notification of the incident to the Engineer and forward to the Regional Safety Coordinator.

All workers within the right-of-way shall wear head protection meeting current ANSI requirements. Also, all workers within the right-of-way shall wear high-visibility safety apparel. High-visibility apparel shall be considered personal protective clothing that meets performance Class 2 or Class 3 of the ANSI/ISEA 107-2004 publication. Class 3 apparel shall be required for night work.

107.11 Use of Explosives

When using explosives, exercise the utmost care not to endanger life or property, and comply with applicable Federal, State, and local laws regarding the use of explosives, including new work. Assume responsibility for all damage resulting from the use of explosives.

As required by State law, notify each property owner and public utility company having structures or facilities in proximity to the Work before using explosives. Provide such notice sufficiently in advance to allow owners to protect their property from damage.

107.12 Promptness of Performance

These Specifications, and orders issued by the Engineer, describe actions, which in many cases, if not performed promptly by the Contractor, may result in danger to life or property, loss to the Department, or delay to the Work. If the Contractor fails to act with appropriate or required promptness, the Engineer may, with written notice, have the necessary act performed by others. In such case, the Department will deduct the costs involved from monies due or to become due the Contractor or may proceed in accordance with **108.10**.

107.13 Legal Responsibilities of the Contractor

In addition to the specific legal responsibilities set forth in **107.01** through **107.11**, the Contractor is charged with other broad legal responsibilities under these Specifications. These responsibilities include but are not limited to various areas as follows:

1. To perform the Work in accordance with all Contract terms.
2. To maintain traffic in accordance with **104.04**, including the use of all proper and necessary protective devices and procedures.
3. To conduct all operations to protect the members of the general public, residents near the Project, workmen engaged in or on the Work, and representatives of the State, the Federal Government and railroads, while they are engaged in duties connected with the Work. This responsibility also extends to the protection of public and private property under all circumstances.
4. To hold harmless and defend against all claims of any nature arising out of or resulting from the performance of the Work, the State, any political subdivision thereof, and all employees of the State, and the Federal Government, provided that such claim, damage, loss or expense is attributable to bodily injury, sickness, disease or death, or to injury or destruction of tangible property (other than the Work itself), but only to the extent caused by the negligent acts or omissions of the Contractor, a subcontractor, or anyone directly employed by them for whose acts they may be liable. This responsibility generally extends to innocent third parties.
5. To pay just claims for materials, supplies, equipment, tools, labor, injury or damage to persons or property, and all other items, against the Contractor or any subcontractor or supplier in connection with the Work.

Be fully familiar with these responsibilities and with the many others that are stated in the Contract; and make certain that all things required to be performed are performed to fulfill the responsibilities involved and that all appropriate and required precautions are taken at all times.

107.14

107.14 Contractor's Responsibility for Work

Until final written acceptance of the Project by the Engineer, maintain charge and care of the Work, and take every precaution against injury or damage to any part thereof by the action of the elements or from any other cause, whether arising from the execution or the non-execution of the Work. Rebuild, repair, restore, and make good all injuries or damages to the Work occasioned by any of the above causes before final acceptance, and bear the expense thereof, except for damage to the Work due to unforeseeable causes beyond the control of and without the fault or negligence of the Contractor, including but not limited to, acts of nature, the public enemy, or governmental authorities.

For damage to acceptably installed items of Work caused by the traveling public on sections of the Project open to traffic, the Contractor shall repair the Work at the applicable Contract unit price. An acceptably installed item shall be complete in place meeting the required specifications. For this purpose, limit the acceptably installed items of Work to the following items used for safety and traffic control: traffic signal systems, signs, lighting, guardrail, impact attenuators, median barriers, parapet rails, and permanent pavement markings. If the damage to the above items necessitates only minor repairs, perform the work in accordance with **109.04.C** or as directed by the Engineer.

107.15 Liability Insurance

In addition to any other forms of bonds or guaranties or insurance required under the Contract, when any part of the Work is to be constructed on railroad-owned property, procure and maintain liability insurance coverage of the kinds and amounts, and in the manner stipulated in the Special Provisions of the Contract. If a Special Provision is not stipulated in the Contract, coordinate with the railroad to determine the disposition of railroad protective insurance and any associated flagging. The costs involved in furnishing the insurance specified will not be paid for directly but will be incidental to other items of Work.

107.16 Right-of-Way

The Department will secure all necessary right-of-way in advance of construction unless specified in the Contract with an availability date. The Contractor shall waive any and all claims for interference, delay, or damage if it accepts a limited work order or unconditional work order to proceed with

the construction knowing that the rights-of-way have been only partially secured or that the right-of-way are still encumbered.

107.17 Personal Liability of Public Officials

In carrying out any of the provisions of these Specifications, or in exercising any power of authority granted to them by or within the scope of the Contract, the Commissioner, Engineer, or their authorized representatives have no liability either personally or as officials of the State. It is understood that in all such matters they act solely as agents and representatives of the State.

107.18 Claims Against the Department

No claims against the Department will be considered except those filed in accordance with **105.16**.

107.19 No Waiver of Legal Rights

The Department will not be precluded or estopped from correcting any measurement, estimate, or certificate made either before or after the completion of the Work or by final acceptance of the Work in accordance with **105.15**, nor from showing that the Work or materials do not in fact conform to the Contract. The Department may recover from the Contractor or its Sureties, or both, such overpayment or damages as it may sustain or damages due to the Contractor's failure to comply with the terms of the Contract. The Department will retain and apply monies owed to the Contractor under any contract or claim, and will recover by process of law such sums in order to correct any error or make good any defects in the Work or materials.

The following Department actions do not operate as a waiver of the Department's rights or powers under the Contract or rights to damages or other relief:

1. Acceptance by the Department, or any representative of the Department;
2. Payment for or acceptance of the whole or any part of the Work;
3. Extension of Contract time; or
4. Possession of the Work taken by the Department.

A waiver by the Department of any breach of the Contract shall not be held to be a waiver of any other or subsequent breach. The Contractor, without prejudice to the terms of the Contract, shall be liable to the Department for

107.20

latent defects, fraud, or such gross mistakes as may amount to fraud, or as regards the Department's rights under a warranty or guarantee.

107.20 Certified Payrolls

As specified by Minimum Wage Scales for Federal-Aid and State Funded Construction contract provisions, submit certified payrolls for Contractor and subcontractor workforce to the Engineer weekly for each week in which any work is performed. Once construction begins, if in any week the Contractor or subcontractor does not perform work, submit the following statement to the Engineer: "No work performed by (contractor name) for the week ending _____."

107.21 Quarantine Restrictions – Pest Control

Agricultural pests such as Soybean Cyst Nematode, Fire Ant, and Japanese Beetle have infested certain areas in several southeastern states including Tennessee. The Plant Pest Control Division of the U.S. Department of Agriculture and the Tennessee Department of Agriculture restrict the movement of certain items from infested areas to prevent the spread of these pests to non-infested areas.

For all hay, straw, or other baled plant material coming from Imported Fire Ant (IFA) Quarantine areas in Tennessee or from states other than Tennessee, provide a permit from that state's Department of Agriculture or other appropriate regulatory agencies. The permit shall state that material has been inspected and found to be free of IFA.

Soil and construction equipment operating in regulated areas are subject to plant quarantine regulations. In general, these regulations provide for the cleaning of equipment before it is moved from regulated areas. Complete information may be secured from State or Federal plant pest control inspectors. It will be the responsibility of the Contractor to comply with all rules and regulations established by the Tennessee Department of Agriculture.

Contractors working in quarantine areas should contact the above agency at an early date in order not to delay the inspection and movement of equipment from an infested area.

SECTION 108 – PROSECUTION AND PROGRESS

108.01	Subletting of Contract	79
108.02	Beginning of Construction	81
108.03	Prosecution of Construction.....	81
108.04	Character of Workers; Methods and Equipment.....	89
108.05	Temporary Suspension of Construction.....	90
108.06	Determination of Time for Completion	91
108.07	Determination of Contract Time Extensions and Excusable Delays	91
108.08	Final Acceptance.....	94
108.09	Failure to Complete the Work on Time	94
108.10	Termination of the Contract.....	95

108.01 Subletting of Contract

Do not sublet, allow second tier sublet, sell, transfer, assign, or otherwise dispose of the Contract or any portion thereof or a right, title, or interest in the Contract without the Engineer’s written consent. If the Engineer consents to subletting or second tier subletting a portion of the Contract, the Contractor shall self-perform work amounting to not less than 30% of the total original Contract cost. For items designated in the Contract as “specialty items,” the Contractor may sublet or second tier sublet this work and deduct the cost of such specialty items from the total original cost before computing the amount of the Work required to be self-performed by the Contractor with its own organization.

As stated above, unless there is a Special Provision 108A in the proposal, the following items are designated as Specialty Items:

- Item 105-01 – Construction Stakes, Lines and Grades
- Item 202-01.02 – Removal of Asbestos
- Item 209 – EPSC
- Item 411-12.** Shoulder Scoring
- Item 501-03.12 – Concrete Shoulder Rumble Strip
- Item 602-03 – Steel Structures
- Item 602-04 – Steel Structures
- Item 602-10.13 / .14 – Navigational Lighting
- Item 602-10.81 – Heat Straightening

108.01

Item 603-02 – Repainting Steel Structures
Item 603-05 – Containment and Disposal of Waste
Item 604-04.01 – Applied Texture Finish (New Structures),
Item 604-04.02 – Applied Texture Finish (Existing Structures)
Item 604-04.62 – Clean and Texture Finish Median Barrier
Item 604-05.31 – Bridge Deck Grooving (Mechanical)
Item 604.07 – Retaining Wall
Item 604-42.01 – Underwater Divers
Item 606-26.05 – Core Drilling for Piles (Abandoned)
Item 617 – Bridge Deck Sealant
Item 624 – Retaining Wall Items
Item 625-01.08,10,11 – Inclinator, Drilled Shaft Inspections
Item 640 – Weigh Station Items
Item 705 – Guardrail, Anchors, etc.
Item 706 – Guardrail Items
Item 707 – Fencing Items
Item 712 – Traffic Control Items
Item 713 – Signing Items
Item 714 – Lighting Items
Item 716 – Pavement Marking Items
Item 720-03, 720-04, 720-05, 720-06, 720-07, 720-08, 720-09 –
Railroad Highway Crossing
Item 721-01.06 – Irrigation System Repair
Item 721-10, 721-11.20, 721-11.30, 721-12 – Landscape and
Irrigation
Item 725 – ITS items
Item 730 – Traffic Signal Items
Item 79* – Utility Items
Item 750.01 – Mitigation Site
Item 801 – Seeding
Item 802 – Landscaping Items
Item 803-01 – Sodding
Item 805 – Erosion Control
Item 806 – Project Mowing

When portions of the Contract are to be sublet, the Contractor shall furnish all statements of proposed subcontracts on the proper form with the required number of copies. The Department must approve each proposed subcontract or tiered subcontract before that particular subcontract is put into effect. Upon request, the Department will furnish the proper prequalification forms to the Contractor.

As a part of this proposal the Contractor agrees as follows:

1. No personnel will work on the Project under the terms of this Contract except legal employees and legal employees of official subcontractors.
2. Contractor books and records will be available for inspection by State or Federal auditors at any time to confirm the above requirement.

The Contractor shall incorporate the provisions of the preceding two paragraphs into all subcontracts. Violation of these terms may subject the Contractor or subcontractors to suspension from eligibility to bid on construction projects, at the Commissioner's discretion.

Subletting or transferring the Contract will not release the Contractor from liability under the Contract and bonds.

108.02 Beginning of Construction

Do not begin the Work before receipt of the Work Order. The Work Order will stipulate the expected start date for construction and the date from which Contract time will be charged.

108.03 Prosecution of Construction

Plan and execute the Work in a manner to meet the required Contract time set forth in the Proposal. Provide adequate manpower, equipment, and materials in accordance with the plan of operations and scheduling requirements described herein so that construction of the various items or groups of items can be carried out and completed within the Contract time based on a completion date or dates, or calendar or working days. Once Work has begun on a given schedule or portion thereof, prosecute the Work fully and continuously according to the details and requirements of the Contract to its completion.

The following Progress schedules will be required at a minimum:

A. Project Durations Less Than 90 Days

Submit a plan of operation with sufficient detail to show the sequence and location of operations and the period of time required for completion of the portion of the Work under each item or group of like items. Indicate in a plan of operations the manpower and equipment required to

108.03

handle the phases of the Work. The Engineer will use a straight-line plot to determine progress.

B. Project Durations 90 Days to 24 Months

At the preconstruction meeting, submit a base line bar chart to the Engineer for review. Submit a hard copy and an electronic copy in the native file format in which the bar chart was generated. The baseline bar chart progress schedule shall include the following:

1. Activities that describe the essential features of the Work, activities that might delay Contract completion, and controlling activities;
2. The planned start and completion dates for each activity, the duration of each activity in workdays; and the calendar (number of workdays per week, holidays, number of shifts per day, and number of hours per shift) as described in the narrative. Durations should be no more than 20 workdays, unless approved by the Engineer;
3. The sequencing of all activities including predecessor(s) and successor(s). If scheduling software is used to create the bar chart schedule, submit related reports such as a predecessor and successor report, a sort by total float, and a sort by early start;
4. Dates related to the procurement of materials, equipment, and articles of special manufacture; and dates related to the submission of working drawings, plans, and other data specified for review or approval by the Department;
5. Dates related to key Department inspections;
6. Dates related to specified activities by the Department and third parties; and
7. A schedule timeline broken down into weekly time periods with a vertical line to identify the first working day of each week.

Include as part of the schedule a narrative listing:

1. The quantity and estimated daily production rate for controlling activities;

2. A calendar describing the number of work days per week, holidays, number of shifts per day, and number of hours per shift;
3. The planned number and types of crews;
4. Lists of Contractor's expected equipment, Subcontractors, and each Subcontractor's expected equipment; and
5. A number of anticipated adverse weather days for each month (for calendar day or completion date contracts).

The Engineer and Contractor will review the draft baseline schedule at the preconstruction conference. The Engineer will accept the baseline schedule, provide review comments, or request additional information. As necessary, make appropriate adjustments or provide additional information. The Department may withhold payments or only make payments for the value of materials in accordance with **109.08** until the Engineer accepts the baseline schedule. The Engineer's acceptance is based solely on whether the schedule meets the requirements of **108.03**. Review comments made by the Engineer on the baseline schedule will not relieve the Contractor from compliance with the Contract.

The Contractor is responsible for scheduling, sequencing, and prosecuting the Work to comply with Contract requirements. The cost of preparing and updating the schedule is incidental to all Contract items.

Conduct periodic job site meetings with the Engineer monthly or as required by the complexity of the Project to assess progress. Submit an updated schedule on a monthly basis and submit within 10 calendar days following the progress estimate pay period cutoff date, to reflect actual progress and to document approved Contract Change Orders. Include the actual start and finish of each activity, percentage complete, the original duration and remaining duration of activities started and ongoing, and a summary of schedule changes necessitated by changes to the Project directed by the Engineer, as well as any resulting from changes in the Contractor's planning or progress of the Work. Include with the monthly schedule update a cover letter that:

1. Identifies and explains any schedule revisions since the prior monthly update;
2. Includes a general description of the progress of the Work since the prior monthly update; and

108.03

3. Identifies any items of special interest.

The Engineer reserves the right to reject any such revisions. Submit the schedule updates to the Engineer for review within 48 hours after the job site meeting. If the Contractor fails to provide monthly schedule updates by the stipulated due date, the Engineer may withhold up to 10% of the monthly progress estimate payment until such time as an update has been provided and accepted in accordance with this provision.

C. Project Durations Greater Than 24 Months or When Required By Contract

Develop a Critical Path Method (CPM) project execution schedule and subsequent updates as required or as specifically requested by the Engineer. Generate the CPM schedule using Primavera Project Management (P6) scheduling software.

1. **CPM Schedule Submission Requirements.** Include with all schedule submissions to the Engineer one hard copy and one electronic copy of the schedule. Provide the following items with each schedule submission:
 - a. Electronic schedule file in .xer format;
 - b. Gantt Chart in PDF format fit to 11x17 inch paper and showing the Activity ID, Activity Description, Original Duration, Remaining Duration, Total Float, and Calendar ID. The Gantt Charts to be included are:
 - i. The project Critical Path sorted by early start;
 - ii. All uncompleted work activities as of the data date sorted by area and early start;
 - iii. 60-day look-ahead sorted by early start;
 - c. Narrative report in PDF file format fit to 8.5x11 inch paper and including:
 - i. Detailed approach to sequencing the work, including assumptions and restrictions considered in development and updates of the schedule;

- ii. Description of the Critical Path;
- iii. Description of the near-critical paths, defined as those activities not on the Critical Path with total float less than 20 days of total float;
- iv. Identification of potential conflicts that may affect the schedule and how they might be mitigated;
- v. Identification of submittal approvals necessary for the work to proceed as shown;
- vi. Description of the calendars including identification of workdays per week, holidays, number of shifts per day, and number of hours per shift;
- vii. Description of how the schedule accommodates adverse weather days for each month; and
- viii. Description of execution plan, including number and type of crews, a list of subcontractors' crews, and expected equipment, but not limited to large equipment transport and delivery, transportation permits for oversized/overweight loads, and availability.

2. **Initial Project Schedule.** Within thirty (30) calendar days after the Contract Award, submit an Initial Project Schedule (IPS) to the Engineer for review and acceptance. A detailed plan shall be completed as described in Baseline CPM Schedule, for all work contemplated for the first one hundred and twenty (120) calendar days after the Work Order is issued. The IPS shall begin with the date of Award and also include all other work thereafter in sufficient detail to identify the Critical Path and identify all contractual milestones.

Submission of the IPS shall be in accordance with the requirements of this subsection. The IPS will be reviewed at the Pre-Construction Conference. IPS schedule must be accepted prior to Contractor beginning Work.

3. **Baseline CPM Schedule.** Within ninety (90) calendar days after the Effective Date, submit a draft baseline CPM schedule to the Engineer and hold a meeting to review. Define and sequence

108.03

activities to accurately describe the Project and to meet Contract requirements, the scope of work, phasing, accommodations for traffic, and interim, milestone, and project completion dates. Use working days to create the schedule, beginning with the date of Award. The baseline CPM shall include, in their entirety, the detailed activities representing the entire duration of the Project. Ensure that the CPM schedule identifies and includes the following:

- a. Planned start and completion dates for each activity;
- b. Alphanumeric coding structure and activity identification system;
- c. Duration of each activity (stated in working days, and with no activities of more than twenty (20) working days, unless approved by the Engineer;
- d. Finish-to-start relationships among activities, without leads or lags, unless otherwise approved by the Engineer;
- e. Interim, milestone, and project completion dates specified in the Contract as the only contractual constraints in the schedule logic;
- f. The Critical Path identifying the controlling activities of the Work;
- g. The project identification number shall remain the same for the entire duration of the Project;
- h. Activities related to the procurement of materials, equipment, and articles of special manufacture;
- i. Activities related to the submission of working drawings, plans, and other data specified for review or approval by the Engineer;
- j. Activities related to Department inspections and approvals; and
- k. Specified activities performed by the Department, subcontractors, suppliers, and third parties such as utilities and railroads.

Float is defined as the amount of time between the date when an activity can start (early start) and the date when an activity must start (late start). Float is a shared commodity between the Contractor and the Department, and either party has full use of the float until it is depleted. Do not use float suppression techniques, such as preferential sequencing (arranging critical path through activities more susceptible to a Department-caused delay), special lead/lag logic restraints, zero total or free float constraints, extended activity times, manipulated calendars, or constraint dates other than as required by the Contract.

The Engineer and Contractor will review the draft baseline CPM schedule at a meeting specific for the review of the schedule. The Engineer will accept the draft baseline CPM schedule, provide review comments, or request additional information. Make appropriate adjustments or provide additional information within 14 calendar days. The Department may withhold payments or only make payments for the value of materials in accordance with **109.08** until the Engineer accepts the baseline CPM schedule. The Engineer's acceptance is based solely on whether the baseline schedule meets the requirements of **108.03**. Review comments made by the Engineer on the initial schedule will not relieve the Contractor from compliance with the Contract. The Contractor is responsible for scheduling, sequencing, and prosecuting the Work to comply with the Contract requirements. The cost of preparing and updating the schedule is incidental to all Contract items.

4. **Schedule Updates.** Update the schedule on a monthly basis to show current progress. Include the following with each update:
 - a. Actual start and finish dates of each activity or remaining durations of activities started but not yet completed;
 - b. "Out of Sequence Progress" activities that have posted progress without predecessors being completed are not allowed without written approval of the Engineer;
 - c. Updated Critical Path; and
 - d. Narrative report, as outlined in **108.03.C.1.c**, and also including:

108.03

- i. Sources of delay with a detailed history of the delay, corrective action, and schedule adjustments to correct the delay;
- ii. Work planned for the succeeding update period;
- iii. Pending change orders; and
- iv. Changes made to the CPM schedule. Changes include additions, deletions, or revisions to activities due to the issuance of a change order, changes to an activity duration, changes to relationships between activities, or changes to the planned sequence of Work or the method and manner of its performance including any schedule changes due to changes in the planning or progress of the Work.

Submit the updated schedule electronically to the Engineer in accordance with the requirements of this subsection. The Engineer reserves the right to reject any schedule updates because of changes in relationships between activities on the critical path, inadequate or inaccurate narrative updates, or other deficiencies in the schedule updates as required in this subsection. If the Contractor fails to provide monthly schedule updates, or address the Engineer's comments regarding the monthly schedule update, within 10 calendar days following the progress estimate pay period cut off date, the Engineer may withhold up to 10% of the monthly estimate payment, until such time as an acceptable update has been provided.

D. Schedule Revisions

The Engineer will determine the progress of the Contract by either the time versus money straight line method or the schedule updates submitted by the Contractor. If actual construction falls behind the plan of operations or schedule by more than 15% or 60 calendar days, whichever is less, offer for approval a revised schedule that reflects timely completion. Otherwise, the Engineer may request a revised schedule. Circumstances that may lead to such a request include the following:

1. A delay (actual or projected) to scheduled milestone or project completion dates 15% or more behind schedule;

2. A difference between the actual sequence or duration of work and that depicted in the schedule; and
3. The issuance of a Change Order that alters the planned sequence of work or the method and manner of its performance by adding, deleting, or revising activities.

Prepare and submit the revised schedule within ten (10) calendar days after the Engineer's request. The Engineer may accept the revised schedule, reject the revised schedule, or request additional information. Address the reasons for rejection or submit the information requested no more than ten (10) calendar days after the Engineer's request.

If the Contractor cannot justify the unsatisfactory progress, the Department may remove the Contractor from the Department's list of qualified bidders in accordance with **102.01**. In addition to the Contractor, any affiliated or subsidiary companies, companies in which the Contractor holds a significant interest, and companies in which officers or stockholders hold a significant interest may be removed from the Department's list of qualified bidders. The Department will give appropriate written notice to the Contractor.

The Department will not reinstate a Contractor disqualified from bidding until the Department considers the progress satisfactory or until the Contract(s) is completed and accepted, whichever occurs first. The above sanction will remain in effect until rescinded by the Department.

Do not stop prosecution of the Work without the written consent of the Engineer. If the Work is stopped, give 24 hours' notice to the Engineer before resuming operations. Unless provided for in the Contract, conduct night work only with the Engineer's written permission.

108.04 Character of Workers; Methods and Equipment

A. Workers

Employ, at all times, satisfactory labor and equipment for prosecuting the required classes of work to full completion in the manner and time specified. The Engineer may direct the Contractor in writing to discharge any personnel employed by the Contractor or by any subcontractor, who in the opinion of the Engineer, does not perform work in a proper and skillful manner, or who is disrespectful,

108.05

intemperate, disorderly, or otherwise objectionable. Such personnel shall not be employed again on the Work.

Do not engage the services of any person or persons who are, or have been, during the period of the Contract, in the employment of the Department, except regularly retired employees, without the Engineer's written approval. In addition, do not engage the services of any firm or any principal officer or employee of a firm that participated in the development of the design of the Project to be constructed under the Contract.

B. Methods and Equipment

Provide equipment of sufficient size and mechanical condition to produce a satisfactory quality of work and meet the time schedule in the plan of operations. During the course of construction, maintain all equipment in satisfactory operating condition. The Engineer may order the Contractor to remove from the Work equipment that becomes less than satisfactory. Do not use equipment that will damage any portion of the Work, or other property, either public or private.

When the methods and equipment for accomplishing the construction are not specified in the Contract, use any methods or equipment that will accomplish the work in conformance with the Contract requirements.

When construction methods and equipment are specified, use such methods and equipment unless the Engineer authorizes alternative methods or equipment in accordance with **105.17**. The Department will not change the basis of payment for the Contract items or time as a result of the substitution of methods or equipment.

108.05 Temporary Suspension of Construction

If it should become necessary to temporarily suspend construction for an undefined period, store all materials to not obstruct or impede the traveling public and to prevent damage to the materials. During the suspension, take every precaution to prevent damage or deterioration of the Work; provide suitable drainage of the road by opening ditches, shoulder drains, and other similar measures; and erect temporary structures where necessary.

108.06 Determination of Time for Completion

Complete the Work in accordance with **104.01** and **105.03** within the number of working days or calendar days, or by the completion date specified in the Contract.

A. Working Days

For working day contracts, the Contract time consists of the number of working days specified to completion. The Engineer will assess working days and apprise the Contractor, monthly, of the number of accumulated working days charged against the Contract. File any protest in connection with working day charges within five (5) working days of receipt of the Engineer's assessment. The Engineer will review such protest and the supporting information and will render a decision either affirming or correcting, in writing, the accumulated number of working days previously reported.

B. Calendar Days or Completion Date

For calendar day contracts, the Contract time consists of the number of calendar days stated in the Contract counting from the effective date of the Engineer's order to commence with the Work, including all Sundays, holidays and non-work days to completion. For completion date contracts, complete the Work on or before the fixed calendar date specified in the Contract.

The Engineer will extend the Contract time for completion for the number of calendar days elapsing between the effective dates of any orders of the Engineer to suspend work and to resume work for Engineer-ordered suspensions, or for excusable delays in accordance with **108.07**.

108.07 Determination of Contract Time Extensions and Excusable Delays**A. General**

The Engineer will extend the Contract time or completion date only if an excusable delay, in accordance with **108.07.B** and **108.07.C**, affects the critical path of the Work shown on the accepted progress schedule.

Time extensions will be evaluated using the most recently submitted and accepted project schedule in accordance with **108.03**. Notify the

108.07

Engineer in accordance with **104.03** and submit a written request for a time extension including a schedule update with an analysis showing the impact of the delay on the critical path and documentation to support this request.

If the Engineer finds that the Work was delayed because of conditions beyond the control and without the fault of the Contractor, and the request is justified, the Engineer will extend the time for completion by a properly executed Change Order in such amount, either calendar days or working days, as properly supported by the schedule analysis. The extended time for completion will be in full force and effect as though it were the original time for completion.

If the Project does not require a schedule in accordance with **108.03**, and satisfactory fulfillment of the Contract requires a change to the Work in accordance with **104.02**, which may require a time extension, the Engineer will evaluate the Contractor's request and determine whether the change has affected the completion of the Project. If the change resulted in an increase in quantities for a major item of work, as defined in **101.03**, the Engineer may proportionally increase the Contract time allowed for performance of the major item of work.

If the Project contains an incentive provision for early completion and the Engineer has extended the Contract time or completion date, the incentive date for early completion will not be adjusted unless otherwise allowed in the Contract or approved by the Engineer.

B. Excusable, Non-Compensable Delays

Excusable, non-compensable delays are delays caused by force majeure events that are not the fault of either the Contractor or the Department. The Department will not provide additional compensation for excusable, non-compensable delays. The following force majeure events may be causes for excusable non-compensable delays:

1. **Natural Disasters** – Floods, fires, tornadoes, earthquakes, infestations, epidemics, pandemics, or other natural disasters where a Declaration of Emergency has been declared for the affected area of the State;
2. **Extreme or Adverse Weather** – Unusually severe or adverse weather for an extended period of time that greatly exceeds weather pattern history as determined by the Engineer;

3. **Major Acts of Violence** – War, invasion, hostilities (whether war is declared or not), terrorist threats or acts, riots, or other civil unrest;
4. **Utility Delays** – Delays caused by utilities unless caused by the failure of the Department to follow the procedures set forth in TCA §54-5-801 et seq.
5. **Government Actions** – Actions by governmental agencies or courts, such as those described in **108.10.B**, that stop or delay the Contractor’s performance of the Work if the Contractor was not at fault in creating the condition that led to the government agency or court action;
6. **Shortage of Materials** – Extraordinary delays in material deliveries that the Contractor cannot foresee resulting from freight embargoes, government acts, or area wide material shortages; and
7. **Labor Disputes** – Delays from labor strikes, stoppages, or slowdowns that are beyond the Contractor’s, subcontractor’s, or supplier’s power to settle and not caused by improper acts or omissions of the Contractor or subcontractors.

If the Contractor incurs liquidated damages pursuant to **108.09** and if the Department extends the Contract time for an excusable, non-compensable delay, the Department will relieve the Contractor from associated liquidated damages under **108.09** commensurate with the time extension.

C. **Excusable, Compensable Delays**

Excusable, compensable delays are delays affecting the critical path of Work that are determined to be the result of changes in the Work in accordance with **104.02**.

If the Contractor incurs liquidated damages pursuant to **108.09** and if the Department extends the Contract time for an excusable, compensable delay, the Department will relieve the Contractor from associated liquidated damages under **108.09** commensurate with the time extension. The Department will determine compensation for delay in accordance with **109.06**.

108.08

D. Concurrent Delays

Concurrent delays are separate critical delays that occur at the same time. When an excusable, non-compensable delay is concurrent with an excusable, compensable delay, the Contractor is entitled to additional time but not entitled to additional compensation. When a non-excusable delay is concurrent with an excusable delay, the Contractor is not entitled to a time extension or additional compensation.

108.08 Final Acceptance

The Engineer will make final acceptance in accordance with **105.15** and the following:

A. State Funded Projects

Upon presumptive completion of the Project and due notice from the Contractor, the Engineer will make an inspection. If all items of work are satisfactorily completed, the Engineer will accept the Project and stop time charges as of the date of the inspection. However, if the inspection reveals that some items of work remain to be completed, the Engineer will direct the Contractor to complete these items and continue charging time until all Work has been satisfactorily completed, regardless of the number of inspections required prior to final acceptance.

B. Federal-Aid Projects

The procedure for Federal-aid projects will be the same as noted above for wholly State funded projects except that time charges will be suspended during the time interval between presumptive acceptance by the Engineer and the date of inspection by the FHWA. Should the FHWA find any work unsatisfactory during the inspection, the Engineer will resume time charges from the day after the inspection date until the work is corrected. In the event further inspections by FHWA are required, the procedure described herein will be repeated until final acceptance of the Project.

108.09 Failure to Complete the Work on Time

For each calendar day over and above the stipulated completion date on which any portion of the Work remains incomplete, the Department will deduct a sum of money from monies due the Contractor, not as a penalty but

as liquidated damages. The amounts to be deducted shall be as specified in Table 108.09-1.

Table 108.09-1: Liquidated Damages for Failure to Complete the Work on Time

Original Contract Amount (\$)			Daily Charge (\$/day)
0	to	500,000	400.00
> 500,000	to	1,000,000	580.00
> 1,000,000	to	2,000,000	800.00
> 2,000,000	to	10,000,000	1,000.00
>10,000,000	to	20,000,000	1,600.00
>20,000,000			2,500.00

Allowing the Contractor to continue and finish the Work or any part of it after the completion date, or after the date to which the time for completion may have been extended, will in no way waive the rights of either party under the Contract.

108.10 Termination of the Contract

A. Default

The Department reserves the right to terminate, by a written Contract Termination Notice, any Contract, of which these Specifications are a part, if the Contractor:

1. Fails to begin construction in accordance with the terms of the Work Order;
2. Fails to furnish sufficient labor or proper materials, or to use proper construction methods and equipment;
3. Performs the Work improperly and fails to remove and replace portions of the Work that are found to be unsatisfactory;
4. Discontinues prosecution of the Work without the Engineer's consent, or fails to resume operations at any time ordered to do so;

108.10

5. Fails to maintain traffic in a safe and efficient manner, or to maintain completed portions of the Work effectively;
6. Fails to maintain a rate at which construction progress, in the Engineer's opinion, is sufficient to ensure completion of the Work within the specified time;
7. Fails, in any degree, to maintain the same financial responsibility on the basis of which the Department pre-qualified the Contractor for submitting a proposal for the Work and awarded the Contract; or
8. Fails or refuses to follow the proper orders of the Engineer.

Under any such circumstance, the Engineer will serve written notice on the Contractor and its Surety of intent to terminate the Contract for reasons that will be set forth therein. If within fifteen (15) days of delivery of such notice, the Contractor and its Surety, or the Surety has not taken sufficient steps to satisfy the Engineer of the correction of the circumstance at fault, the Department may, in its absolute discretion, order the Contract terminated.

The Department may then appropriate or use any or all materials and equipment on the ground as may be suitable and acceptable and may enter into an agreement for the completion of the Contract according to the terms and provisions thereof, or use such other methods as in the opinion of the Engineer will be required for the completion of the Contract in an acceptable manner.

The Department will deduct from any monies due or which may become due the Contractor, all costs and charges incurred by the Department, together with the cost of completing the Work under Contract. If such costs exceed the sum that would have been payable under the Contract, then the Contractor and the Surety shall be liable and shall pay to the Department the amount of such excess.

The Department will not relieve the Contractor and the Contractor's Surety of the liability for liquidated damages assessed in accordance with **108.09** because of the default.

If it is determined that the Department's default of the Contractor is improper, the default will revert to a termination for convenience, and the Department will compensate the Contractor in accordance with **109.05.B**.

B. Without Fault

The Department may, by a written Contract Termination Notice, with the approval of the FHWA where applicable, terminate any contract or a portion thereof after determining that for reasons beyond the control of the Contractor, the work contracted for cannot be completed. Such reasons for termination may include, but need not necessarily be limited to, one of the following:

1. An Executive Order of the President of the United States with respect to the prosecution of war or in the interest of national defense.
2. The Engineer and Contractor each make a determination that, due to a shortage of critical materials required to complete the Work caused by allocation of these materials to work of a higher priority by the Federal Government or any agency thereof, it will be impossible to obtain these materials within a practical time limit and that it would be in the public interest to discontinue construction.
3. An injunction is imposed by a court of competent jurisdiction that stops the Contractor from proceeding with the Work and causes a delay of such duration that it is in the public interest to terminate the Contract and the Contractor was not at fault in creating the condition that led to the court's injunction. The Engineer's decision as to what is in the public interest and as to the Contractor's fault, for the purpose of termination, shall be final. Restraining orders or injunctions obtained by a third party citizen action resulting from Federal or State environmental protection laws, or where acts or omissions or persons or agencies whether or not the Contractor primarily caused the issuance of such order or injunction, shall also be cause for termination.

C. Convenience

The Department may, by a written Contract Termination Notice, with the approval of the FHWA where applicable, terminate any contract, or any portion thereof for the Department's convenience, when the Engineer determines that a termination is in the best interest of the Department.

The Department may terminate the Contract for convenience at any time after the Department has made a determination to award a contract. Reasons for termination may include, but are not limited to:

108.10

1. Insufficient funds by the Department due to extenuating circumstances;
2. Occurrence of an environmental situation of a significant nature that would require extensive and time-consuming delays in the work for the purposes of identification, evaluation, and possibly mitigation;
3. Occurrence of a previously undiscovered error in the bid documents; and
4. Any other circumstances the Department determines to be in the best interest of the Department or the public.

In addition to the general reservation of the right to terminate for convenience under this Subsection, the bidding documents may provide for a termination of the Contract for convenience under this Subsection upon the occurrence or non-occurrence of a specified event after bid opening.

Under any of the above circumstances for termination, the Engineer will deliver to the Contractor and the Surety a written Contract Termination Notice for reasons that will be set forth therein. The Notice shall specify the extent to which performance of work is terminated under the Contract and the effective date of termination. Unless otherwise directed by the Engineer, upon receipt of a Contract Termination Notice, the Contractor, or its Surety, shall immediately:

1. Stop work as directed in the Notice;
2. Place no further orders or subcontracts for materials, services, or facilities except as approved by the Engineer to complete work not terminated;
3. Terminate all orders and subcontracts for the terminated work;
4. Deliver to the Engineer completed or partially completed plans, drawings, information, and other property required to be furnished under the Contract;
5. Take actions that the Engineer directs to protect and preserve Contract-related property that is in the possession of the Contractor in which the Department has or may acquire an interest;

6. Provide all other information included in this section and as requested by the Engineer; and
7. Complete all work not terminated.

If the Department terminates the Contract or any portion thereof before completion of all items of work in the Contract, the Department will make payment for the actual number of units of items of work completed at the Contract unit prices and as mutually agreed for items or work partially completed in accordance with **109.05**. The Department will not pay claims for loss of overhead or anticipated profits, including anticipated earnings on usage of owned equipment, and impact, delay, or other direct or indirect costs resulting from this termination as part of any settlement. The Department will pay for items that are eliminated in their entirety by the termination in accordance with **109.05**.

The Department may purchase acceptable materials, obtained by the Contractor for the Work, that have been inspected, tested, and accepted by the Engineer, and that are not incorporated in the Work. Submit the proof of actual cost, as shown by receipted bills and actual cost records. The Engineer, as shown by actual cost records, may designate all actual costs for delivery at such points of delivery to be added to this cost. If the Engineer and the Contractor do not agree to purchase such materials, the Department may reimburse the Contractor for any reasonable restocking fees and handling costs incurred by the Contractor in returning unused materials to the vendor. If only portions of the Work are eliminated, the Department may stop delivery and payment for unnecessary materials.

Termination of a Contract or a portion thereof shall not relieve the Contractor of its responsibility for the completed work or work not included in the Notice of Termination, nor shall it relieve the Surety of its obligation for and concerning any just claims arising out of the work performed or remaining to be performed.

109.01

SECTION 109 – MEASUREMENT AND PAYMENT

109.01	Measurement of Quantities	100
109.02	Scope of Payment.....	105
109.03	Compensation for Altered Quantities.....	106
109.04	Methods of Payment for Additional or Altered Work.....	106
109.05	Payment for Eliminated, Altered, or Terminated Work	114
109.06	Compensable Delay Costs.....	115
109.07	Non-Recoverable Costs.....	118
109.08	Partial Payment	119
109.09	Payment for Stockpiled Materials	119
109.10	Final Payment	121
109.11	Payment of Costs Owed to the Department	122

109.01 Measurement of Quantities

The Engineer will measure all work completed under the Contract according to United States standard measure, using measurement methods and computations conforming to sound engineering practice.

The Engineer will measure actual quantities of work completed as described in the subsections entitled “Method of Measurement” for specific items of work. The Department will make payment based on these actual measured quantities. Accept estimated quantities designated in the Contract to be used as final payment quantities for the final payment, unless revised by approved Change Order.

If there is a disagreement between the Contractor and the Department concerning the measured quantity of any pay item, the Department will re-measure the item provided the Contractor enters into a Change Order to bear the expense of the re-measurement should it show no substantial change in the pay item quantity. The definition of “substantial change” will be stated in the Change Order and will depend on the item being checked and the nature of the specific Project.

The Engineer will measure completed work as follows:

A. Lump Sum or Each

The term “lump sum” or “each” when used as a unit of payment will mean full compensation for all resources necessary to complete the item.

B. Length

The Engineer will measure items paid by the linear foot such as pipe culverts or guardrail along the finished surface of the item parallel to the item base or foundation, unless otherwise shown on the Plans.

The Engineer will measure timber by the 1,000 feet board measure (MFBM) incorporated in the structure based on nominal widths and thicknesses and the extreme length of each piece. The Engineer will measure timber piling by the linear foot.

A Station when used as a definition or term of measurement is 100 linear feet.

C. Area

Unless otherwise specified, the Engineer will make longitudinal measurements for surface area computations along the actual surfaces and not horizontally and will make no deductions for individual fixtures having an area of 9 square feet or less. Unless otherwise specified, transverse measurements for surface area computations will be the neat dimensions shown on the Plans or as directed in writing by the Engineer.

D. Volume

The Engineer will measure structures according to neat lines shown on the Plans or as altered to fit field conditions as directed by the Engineer.

In computing excavation volumes, the Engineer will use the average end area method or other methods commonly accepted as standard practice in the industry.

For materials to be measured by volume in the vehicle, haul the material in vehicles of a size or type approved by the Engineer. Ensure that the body shape of vehicles used for this purpose allows that the actual contents can be readily and accurately measured. The Engineer will measure materials at the point of delivery.

109.01

When requested by the Contractor and approved in writing, the Engineer may weigh the materials and convert mass to cubic yards for payment purposes. The Engineer will determine the volume to weight conversion factors. The Engineer and the Contractor must agree to the conversion factors in writing before this method of measurement of pay quantities is used.

The Engineer will measure bituminous materials by the gallon or ton. Volumes will be measured at 60 °F or, when measured at other temperatures, will be corrected to the equivalent volume at 60 °F according to ASTM D1250 for asphalts or ASTM D633 for tars.

E. Weight

The term “ton” will mean the short ton consisting of 2,000 pounds avoirdupois.

Unless otherwise specified, the Engineer will accept certified weights for materials measured or proportioned by weight that are shipped by rail or truck transport, provided that only the actual weight of the material used is paid for.

For bituminous materials, net certified scale weights or weights based on certified volumes in the case of rail or truck transport shipments, unless otherwise specified, will be used as a basis of measurement, subject to correction when bituminous material has been lost, wasted, or otherwise not incorporated in the Work.

In all cases where measurement of materials is based on certified weights, provide the Engineer with certified weigh bills showing the net tons of materials received in each shipment. The Engineer will not pay for materials in excess of the amounts represented by the certified weigh bills.

Certified Weigh Tickets for Asphalt Mixtures and Aggregate Materials shall list on the ticket:

1. Material Type, Item Description
2. TDOT Mix Design Number (where applicable)
3. Project Number, County, Route
4. Date
5. Ticket number
6. Gross weight of the loaded truck

7. Tare weight of the truck
8. Net weight of the material to be paid
9. Running Daily Total for the particular material
10. Truck number
11. Truck legal limit
12. Time loaded

Employ a Certified Public Weigher as defined in the Certified Public Weigher Law of 1981, Tennessee Code Annotated, Section 47-26-801, et seq., as amended. The Engineer will measure all applicable materials in accordance with the Certified Public Weigher Law and Department policy on scales approved by the Engineer. Certified Weigher licenses shall be posted near the scale beam or weight indicator in full view at all times. Certified Weigher shall be the only person allowed to operate the scale or weigh recording equipment. Provide weight (haul) tickets in accordance with State law and Standard Specifications and as directed by the Engineer. These requirements apply to entities located both inside and outside the state of Tennessee.

Certified Weigher shall weigh each load with the maximum load not to exceed the legal limit established by law. The proposed haul route shall be known prior to deployment. Loads in excess of the Legal Weight limit shall be rejected and no payment will be issued.

Provide a standard brand of platform truck scales with a sufficient rated capacity to weigh the maximum gross load to which they will be subjected. Do not use truck scales to measure weights in excess of the manufacturer's rated capacity. Clearly post the manufacturer's rated capacity on the scale manufacturer's plate and in the shelter provided for the weigher.

At the time of installation or modification of existing scales, test the scales before using to ensure they are within the allowable tolerances. Use a qualified scale technician to perform any alteration (e.g., electrical readout) or change in the rated capacity. Document all changes or alterations made by the scale technician and furnish a copy of the documentation to the Department.

House the recording mechanism of the scale in a suitable shelter furnished with adequate light, heat, chairs, tables, and storage drawers as needed for the convenience of the weigher. In addition, keep the scale platform and scale pit free of debris that could affect the accuracy of the scales.

109.01

Provide digital readout and scale printers as the primary weight indicator or as accessory equipment. The Department will inspect and approve all scale control and recording equipment.

Ensure the scale's accuracy within a tolerance of 0.5%. Provide a straight approach at each end of the platform scale in the same plane as the platform and of sufficient length and width to ensure the level positioning of vehicles longer than the scale platform during weight determinations. Weigh each truck and trailer with no brakes set on any wheel. Locate the scale platform so that surface water will drain away from it and to allow for an adequate foundation of concrete or other approved materials. Construct the foundation of sufficient strength and durability to withstand repeated capacity loading without affecting the accuracy of the scales.

The scales shall be calibrated and certified by an independent certified scale company. The calibration and certification shall be performed on a semiannual basis; January through June and July through December. No calibration shall be within 60 calendar days of the previous calibration. Scales shall be validated on a quarterly basis to ensure their continued accuracy. Validation shall be made by a verified known weight, or other scales that are approved by the Department or other State Agency. A verified known weight shall be checked for continued accuracy each time the scales are calibrated. The results shall be maintained onsite and made available for review to Departmental personnel. If deficiencies are reported, all corrections shall be performed, documented, and verified prior to supplying material for TDOT projects.

Weigh tickets shall be certified either manually or electronically. If certified manually, the Certified Weigher shall sign their official registered signature and place their seal on the original ticket. The ticket shall be filled out in ink and delivered to the project site with the material.

For materials directly paid for by the ton, the Engineer will be furnished a daily recap of all materials delivered to the project. The daily recap sheet must list the ticket number, type of material by item number, and a quantity of materials for each load hauled. Any discrepancy between the certified weigh bills and the daily recap will be reviewed along with the contractor's initialed copy of weigh bills.

The truck tare to be used in the weighing operation shall be the weight of the empty truck determined with full tank(s) of fuel and the operator

seated in the cab. A daily weight shall be recorded at the beginning of each work day prior to use of truck. If preferred, a new tare may be determined for each load. When a new tare is obtained for each load, the requirement for full tank(s) of fuel shall be waived.

All weight of trucks shall be recorded to the nearest 20 pounds. The cost of providing facilities and equipment for the accurate weighing, proportioning, or measuring of materials is incidental to the associated pay items in the Contract.

109.02 Scope of Payment

The Department will pay, and the Contractor agrees to accept, the compensation provided in the Contract for the work acceptably completed and measured for payment under each Contract item. Payment of a Contract item is full compensation for furnishing all materials, equipment, tools, labor, and incidentals required to complete the item; and for all risk, loss, damage, or expense arising out of the nature or the performance of the work, subject to **107.19** and **109.11**.

If the "Basis of Payment" clause in the Specifications relating to a unit price in the bid schedule requires that the price of the Contract item cover and be considered compensation for certain work or material essential to the item, the Department will not measure or pay for this same work or material under any other pay item that may appear elsewhere in the Specifications.

When two or more projects are included in the same Contract, the Contractor will be required to furnish any item listed in the Contract to any or all of the projects at the Contract unit price.

The Department requires that the Contractor pay subcontractors, material suppliers, and haulers promptly for their work after receipt of payment for the associated work from the Department. The Contractor shall pay each subcontractor, material supplier, and hauler for work performed or materials supplied under its subcontract no later than thirty (30) calendar days from the date the Contractor receives payment for the work from the Department. Any payment to the Contractor from which any amount has been withheld in accordance with **107.19** or **109.11** shall constitute full payment for the associated work, and the Contractor shall remain obligated to pay all subcontractors, material suppliers, and haulers fully and promptly for all associated work. The same prompt payment requirements apply to subcontractors at all tiers.

109.03

Ensure each subcontractor, including all Disadvantaged Business Enterprises (DBE), certified Small Business Enterprises (SBE), and DBE or SBE haulers or material suppliers, has registered for AASHTOWare Project Civil Rights & Labor (CRL) prior to commencing Work.

Document within CRL the actual amount paid to all subcontractors, material suppliers, and haulers during the monthly estimate period for which the certification is being made. The Department will withhold estimate payments if the required information is not submitted or if subcontractors, at any tier, material suppliers, or haulers are not paid after the thirty (30) calendar day time period. Any delay or postponement of payment beyond the thirty (30) calendar day timeframe will be subject to terms listed in TCA §12-4-707(b). The Contractor shall remain obligated to pay all subcontractors, material suppliers, and haulers fully and promptly for all work associated with a pay estimate from the Department, notwithstanding any withholding of payment from the Contractor for failure to pay a subcontractor, material supplier, or hauler within thirty (30) calendar days.

The contractor, subcontractors, at any tier, material suppliers, or haulers shall not withhold any retainage from progress payments made to their subcontractors.

109.03 Compensation for Altered Quantities

When the accepted quantities of work for Contract items vary from the quantities in the bid schedule, the Department will pay in full at the original Contract unit prices for the accepted quantities of work measured in accordance with **109.01**. The Department will not make any price adjustment for variations in quantities except as provided for in **104.02**.

109.04 Methods of Payment for Additional or Altered Work

If the Department revises the Contract in accordance with **104.02**, the Department will adjust the Contract price using one of the following methods. The Department reserves the right to request detailed cost information for any request for a change to the Contract in accordance with **104.03** and may at any time direct the Contractor to perform all or part of the revised work by force account in accordance with **109.04.C**.

A. Contract Bid Item Prices

Before proceeding to another pricing method, the Engineer will attempt to price the revised work before the revised work is performed using Contract unit prices.

B. Negotiated Prices

If the Engineer and the Contractor cannot agree on a revised price in accordance with **109.04.A**, both shall attempt to negotiate new unit or lump sum prices before the revised work is performed. With negotiated prices, the Contractor must substantiate that the proposed prices are comparable to prices that would have resulted from a competitively bid contract. The basis for pricing may include:

1. Original Contract bid prices adjusted for increased or decreased material, equipment, or labor costs in accordance with **109.04.C**.
2. A bid item history exists for the revised work, and the proposed bid price is within 10% of the Regional 3-year historic cost for that item.
3. For work in unusual circumstances or with unusual site conditions, the average bid price for the three lowest bidders in the tabulation of bids for that work. If fewer than three bids are received, this option will not be used.
4. A cost analysis of the Contractor's detailed estimate of labor, equipment, materials, and markups in accordance with **109.04.C** to determine the reasonableness of costs.

When a Change Order is executed covering the revised work, the Department will make payment in accordance with the terms of the agreement. Profit and overhead shall not exceed 15% of the subtotal of materials, labor, and equipment. When a Change Order is initiated for subcontractor work, the administrative fee shall not exceed 5% of the subcontractor's total of materials, labor, equipment, profit, and overhead. If the Department negotiates with the Contractor, but does not agree on a price adjustment, the Engineer may direct the Contractor to perform all or part of the revised work by force account.

C. Force Account

When the Engineer directs the Contractor to perform work by force account, the Contractor shall be compensated in the manner described hereinafter. Submit a plan of operation for how force account work will be performed including a work schedule, estimated size of the work crew, an equipment list, and anticipated materials. The Department will not allow the Contractor to perform force account work without this plan. The Department will make payments in the manner specified below, and this payment will be full compensation for the prosecution of the work performed on this basis.

- 1. Labor.** For all labor and foremen in direct charge of the specific operations, the Department will pay the rate of wage or scale as previously shown on submitted certified payrolls, unless otherwise agreed upon in writing before the start of the force account work, for each and every hour that said labor and foremen are actually engaged in such work excluding general superintendence. The wages shall be comparable to wages or scale paid by the Contractor for work of a like nature on the Contract items. The Department will allow overtime only after authorized by the Engineer prior to the start of the force account work. If the labor or foremen are employed partly on specific force account work and partly on other work, the Department will prorate the amount of overtime to be reimbursed based on the number of hours worked on the specific force account work during the payroll period. The Department will not pay for commuting time to and from the Project under force account.

The Department will pay an additional amount for profit and overhead equal to 20% of the labor wages (excluding labor burden). When such amounts are required by collective bargaining agreement or other employment contract generally applicable to the classes of labor employed on the Work, the Department will pay the actual labor burden costs paid to, or on behalf of, such labor forces by reason of subsistence and travel allowances (i.e. per diem and lodging), health and welfare benefits, pension fund benefits, and other benefits. The Department will pay the Contractor's actual labor burden costs up to a maximum of 45% of all base (actual) wages paid to labor and foreman for the specific force account work. The Department will not pay labor burden additives for unauthorized overtime. The Contractor shall submit actual labor burden rates to the Engineer for approval before beginning force

account work. If the Contractor cannot verify the actual labor burden rates, the Department will add to all base (actual) wages paid to labor and foreman for the specific force account work a flat 20% of the total of such base (actual) wage. These wages and percentage markups are full compensation for all costs associated with labor for the specific force account work.

2. **Bond, Insurance, and Tax.** The Department will pay the actual invoiced costs for property damage, liability, and workers' compensation insurance premiums, unemployment insurance contributions, and social security taxes on the force account work. Furnish satisfactory evidence of the rate or rates paid for such bond, insurance, and tax costs.
3. **Materials.** For materials accepted by the Engineer and used in the performance of the force account work, the Department will pay the actual cost of such materials delivered to the Project site, including transportation charges not included in unit prices (exclusive of machinery rentals as specified in **109.04.C.4**), to which 15% of the materials costs will be added for profit and overhead.

Obtain competitive quotes from multiple materials suppliers and determine the most cost effective quote offering the best value to the Department. Provide statements supported by supplier invoices for all materials including transportation charges. However, if materials used on force account work are taken from the Contractor stock, then instead of invoices, furnish an affidavit certifying that the materials were taken from the Contractor's stock, that the quantity claimed was actually used, and that the material and transportation costs claimed represent the actual costs to the Contractor. The Contractor's authorized representative shall date and sign the statements.

4. **Equipment.** Equipment used for force account work shall be of the size, type, and number necessary to perform the required work in an economic and expeditious manner. Obtain equipment rental rates for any machinery or special equipment (other than small tools) and transportation costs to deliver equipment to the Project site. The rates shall be agreed upon and authorized by the Engineer before the start of force account work. The equipment hours for operating or standby time will be reported to the nearest 1/2 hour.

109.04

Submit for approval a list of all Contractor-owned equipment or equipment rented from another contractor (i.e., an entity not in the commercial rental business), including the manufacturer, make, model, year of manufacture, type of fuel, and other necessary information to determine proper hourly payment rates.

If a pick-up or light duty truck is necessary to perform force account work, the Department will pay at a rate consistent with the rates in *The Rental Rate Blue Book for Construction Equipment* published by Equipment Watch for the actual hour of operation performing the Work. A pick-up or light duty truck will be paid at the hourly operating cost for no more than 2 hours of any given day that the Work is performed. All other time will be paid at the standby cost, not to exceed 8 hours total on any given day.

Small tools, generally defined as hand-held with or without an engine and that are listed in *The Rental Rate Blue Book for Construction Equipment*, will be paid that rate for the hours used except that in no case shall payment exceed replacement cost of the item. The Engineer may approve specialty type small tools to be included in the equipment list.

Equipment rental rates will be determined by the current monthly rates established in *The Rental Rate Blue Book for Construction Equipment*. Reimbursement will not exceed the purchase price or salvage value, whichever is less. Maximum allowable equipment rates are determined as follows:

- a. The hourly ownership cost is calculated by dividing the monthly ownership cost by 176. The hourly ownership cost is then multiplied by adjustment factors for age and region to calculate the hourly adjusted ownership cost. Do not use the weekly, daily, or hourly ownership costs shown in the Blue Book.
- b. The hourly operating cost shall not exceed the estimated operating cost in the Blue Book. The hourly operating cost shall include all costs and labor for routine maintenance and servicing, including but not limited to: fuel, lubrication, filters, blades, belts, pumps, lines, hoses, teeth, tires, tracks, and all other incidentals needed to operate and maintain the equipment. The Department will pay hourly rates for the actual time that the equipment is in operation.

- c. The hourly rate is calculated by adding the hourly adjusted ownership cost and the hourly operating cost.
- d. Standby cost will not be paid for more than 8 hours in a day or 40 hours in a week.
- e. The hourly standby rate is calculated by multiplying the hourly adjusted ownership cost by 50%.
- f. The monthly rate includes the basic machine plus any attachments.

Standby rates shall apply when equipment required to remain on the worksite but is temporarily not in operation for the Work. The equipment must be approved by the Engineer to standby for later use to complete the Work. In general, standby rates shall apply when equipment is not in use, but will be needed again to complete the Work and the cost of moving the equipment will exceed the accumulated standby cost. If the standby cost should exceed the equipment moving cost to or from the work site, the Contractor will be entitled to the moving cost only. Standby rates will be used under the following conditions:

- a. The equipment is totally dedicated to the force account work and not used intermittently on other work.
- b. Standby cost will be considered only after equipment has been operated on force account work.
- c. Standby cost will not be paid for more than 8 hours in a day or 40 hours in a week.
- d. The sum of standby time and operating time shall not exceed 8 hours per day.
- e. Standby payment will not apply to days not normally considered to be work days such as holidays, weekends, or days of inclement weather when no other work is taking place.

The Department will not pay for standby time when equipment is inoperable, for time spent repairing equipment, or for the time elapsed after the Engineer has advised the Contractor that the equipment is no longer needed. The Department will determine if it

109.04

will be more cost effective to pay standby time on approved equipment on site or for multiple mobilizations.

If equipment is needed, which is not included in the Blue Book rental rates, the Department and Contractor will agree upon reasonable rental rates in writing before the equipment is used. The Contractor shall provide invoices to support equipment charges by individuals or firms other than the Contractor.

5. **Rented or Leased Equipment.** The Department will pay for equipment that is rented or leased from a commercial rental company at actual invoice price, provided the prices are fair and reasonable but not to exceed the monthly rate published in *The Rental Rate Blue Book for Construction Equipment*. The Department will pay a markup of 15% for all rented/leased equipment for profit and overhead. The Contractor shall submit for approval the hourly operating cost for all rented/leased equipment if the rent/lease agreement does not include these expenses. The markup will not apply to hourly operating costs. Rented or leased equipment will not be subject to payment for standby time. The Contractor shall obtain competitive rates from multiple rental companies or equipment suppliers to determine the most cost effective rate offering the best value. The Department will determine if it will be more cost effective to leave the equipment on site and pay the invoice price or pay for multiple mobilizations.
6. **Transporting Equipment.** When it is necessary to transport approved equipment to the Project site, the Department will pay for these costs and the costs to return equipment to its original location, subject to the following conditions:
 - a. The equipment is obtained from the nearest approved source;
 - b. The return charges do not exceed the delivery charges;
 - c. Haul rates do not exceed the established rates of licensed haulers; and
 - d. Such charges are restricted to those units of equipment not already available and not on or near the Project.

If the equipment is transported by the Contractor, the Department will pay by hourly rate, as calculated in accordance with **109.04.C.4**,

for other equipment if not already covered in the rental rate. If the equipment is transported by common carrier, then payment will be the actual invoiced amount with no markup. If equipment is delivered to the Project site and used for other Contract items, then the Department will not pay for return costs.

7. **Subcontracting and Professional Services.** If a subcontractor at any tier performs force account work or associated professional services, the Department will pay for the actual reasonable cost of such subcontract work in accordance with **109.04.C** as if the subcontractor was the contractor. The contractor may apply an administrative fee of 5% for all approved force account work completed by subcontractors and for approved special services associated with the force account work. No allowance will be made for subcontractors contracting lower tier subcontractors. Submit invoices for all subcontracted and professional services rendered (i.e. those not subject to Davis-Bacon or State prevailing wage rates).
8. **Miscellaneous Costs.** The Department will make no additional payment for general superintendence (Superintendent), time keepers, the use of small tools, or other costs for which no special allowance is provided. These costs are incidental to the force account work.
9. **Compensation.** The Contractor's representative and the Engineer will compare records of the cost of work done as ordered on a force account basis at the end of each day's work. The force account calculation is not intended to itemize incidental work. Compensation for incidental work is included in the allowable additives for labor and material costs.
10. **Statements.** The Department will not make payment for work performed on a force account basis until the Contractor has furnished the Engineer with duplicate certified and itemized statements of the cost of force account work detailed as follows:
 - a. Name, classification, date, daily hours, total hours, rate, and extension for each laborer and foreman;
 - b. Designation, dates, daily operating and standby hours, total hours, rental rate, and extension for each unit of machinery and equipment;

109.05

- c. Quantities of materials, prices, and extensions;
- d. Transportation of equipment and materials; and
- e. Cost of property damage, liability and workers' compensation insurance premiums, unemployment insurance contributions and social security tax.

Provide support for all statements with receipted invoices for all materials used, including transportation charges. The Contractor's authorized representative shall date and sign the statements.

109.05 Payment for Eliminated, Altered, or Terminated Work

The Department reserves the right, in accordance with **104.02**, to eliminate or alter any portions of the Contract relating to the construction of any item or items or terminate the Contract for convenience as provided in **108.10.C**. The Department will pay a fair and reasonable amount covering all items of cost incurred prior to the date of cancellation, alteration, suspension, or termination of the Work as ordered by the Department.

A. Eliminated or Altered Items

The Department will purchase acceptable material ordered by the Contractor or delivered to the Project site prior to the date of elimination, alteration, or suspension of the item or items at actual cost plus delivery cost, including freight, unloading, and hauling unless otherwise provided. The purchased materials will become the property of the Department. No allowance will be made for anticipated profits. These provisions will likewise apply to elimination or alteration of any extra and force account work for which a Change Order has been executed.

The Department will not consider for purchase any materials used in construction items that are subject to variation in quantities, and that are ordered by the Contractor without the consultation or approval of the Engineer prior to the ordering of such materials. In addition, the Department will not consider for purchase materials ordered by the Contractor prior to the preconstruction meeting without the Engineer's written approval.

B. Termination for Convenience

If the Contract or any portion is terminated for convenience before completion of all items of Work in the Contract, the Department will pay for the actual number of Contract items completed at the Contract unit prices and mutually agreed as provided herein for items or work partially completed, or will pay on a force account basis, as determined by the Engineer. The Department may purchase acceptable material ordered by the Contractor or delivered to the Project site before the date of elimination or alteration, or suspension of the item or items at actual cost plus delivery cost, including freight, unloading, and hauling unless otherwise provided. The materials will become the property of the Department. The Department will not pay for loss of overhead or anticipated profits, including anticipated earnings on usage of owned equipment, and impacts or other direct or indirect costs resulting from the termination.

The Department will pay for organization of the Work when not otherwise included in the Contract. The Department will pay for moving equipment to and from the Project site when the volume of work completed is too small to compensate the Contractor for these expenses under the Contract unit prices. If the Work is suspended in advance of the termination date, the Department also may consider reimbursing the Contractor for such cost items as mobilization, subcontractor costs not otherwise paid for, actual equipment standby costs for work stopped in advance of the termination date, and guaranteed payments for private land usage as part of the original Contract when not otherwise included in the Contract.

Termination of a contract or a portion thereof shall not relieve the Contractor of its responsibilities for the completed Work or Work to be completed that is not covered by the Notice of Termination, nor shall it relieve the Surety of its obligation for and concerning any just claims arising out of the Work performed or to be performed. Submit a claim request for additional costs, not covered in this section or elsewhere in the Contract, within sixty (60) calendar days of the effective termination date in accordance with **105.16**.

109.06 Compensable Delay Costs

For a compensable delay determined in accordance with **108.07**, the Department will grant additional time and/or pay for the computed delay costs for the actual number of days impacted by the determined delay.

109.06

Seasonal limitations (i.e., a winter shutdown period or other seasonal restrictions noted in the plans or specifications) will not be considered in the calculation of time-related delay costs.

Compensable delay costs will not be paid unless the compensable delay causes completion of the Work to exceed the original or previously adjusted Contract completion date. Compensable delay costs will not be considered for previously negotiated Change Orders or for costs that have already been included in bid items, negotiated prices, or force account payments described in **109.04**; no additional consideration will be given for home office overhead and/or field office overhead.

The Department will not pay for delay costs until the Contractor submits an itemized statement of these costs in accordance with **109.04.C**. The following cost categories may apply:

A. Escalated Labor

To receive compensation for escalated labor, demonstrate that the delay forced the Work to be performed during a period when labor costs were higher than planned at the time of bid. Provide adequate support documentation for the escalated labor costs, allowances, and benefits as specified in **109.04.C**.

B. Materials Escalation or Material Storage

The Department will pay the Contractor for increased material costs or material storage costs only if the delay resulted in material cost escalation or extended storage costs. Fuel and asphalt costs are indexed and therefore excluded from escalation. Obtain the Engineer's approval before storing materials due to a delay.

C. Equipment Standby or Equipment Demobilization

The Contractor will provide costs for demobilization of equipment, and the Department will decide whether to pay for demobilization or equipment standby costs for a compensable delay. If not otherwise compensated under force account, the Department will pay the Contractor in accordance with **109.04.C.4** for equipment standby costs, other than small tools, that cannot be used for active work and must remain on the Project associated with the delay. Alternatively, the Department will pay for the Contractor's transportation costs to remove

and return equipment not required on the Project during delays. No other equipment costs are recoverable as a result of delay.

D. Extended Field Overhead

Extended field overhead costs are only those that are not included in the cost of the Work (such as bid items, negotiated prices or force accounts).

Project specific extended field overhead costs shall include only the cost of general supervision, field office facilities and supplies, maintenance of field operations, traffic control maintenance, and extended erosion control inspection. General supervision costs include the actual time that the Superintendent and/or Superintendent's assistant are actively engaged in overseeing the day to day operation of the Work. Watchmen and clerical staff will be considered for the time they are directly engaged in the Work and are located on the project site. Names, titles, and salary for salaried personnel assigned to the project shall be provided to the Engineer and approved before being charged to the project. For salaried personnel working on that specific project, divide the weekly salary by 5 days per week to calculate the daily wage rate. Pick-ups or light duty trucks for the approved general supervision Superintendent and/or Superintendent's assistant will be paid in accordance with **109.04.C.4**. Field office facilities and supplies costs include, but are not limited to, field office trailers, tool trailers, office equipment rental, temporary toilets, and other incidental facilities and supplies. Maintenance of field operations include, but are not limited to, land-line telephone, electric, water, and other similar expenses. Costs for cell phones, tablets/computers, and software are included in home office overhead described in **109.06.E**.

Compute these costs on a calendar day basis using actual costs incurred due to the delay to provide project specific general supervision, field office facilities and supplies, maintenance of field operations, traffic control maintenance, and extended erosion control inspection. If requested by the Contractor the Department may consider, at its sole discretion, calculating a daily extended field overhead rate as a percentage (in accordance with Table 109.06-1) of the original Contract amount divided by the Contract duration.

109.07

Table 109.06-1: Extended Field Overhead Rate

Original Contract Amount (\$)	Extended Field Overhead Rate
0 to 2,000,000	1%
>2,000,000 to 10,000,000	1.5%
>10,000,000 to 20,000,000	2%
>20,000,000 to 50,000,000	3%
>50,000,000	3.5%

E. Home Office Overhead and Profit

The Department will pay home office overhead and profit at a rate of 15% for items A through D above that are approved by the Engineer.

F. Insurance and Bond Costs and Additional taxes

The Department will pay for documented additional or escalated premiums on bonds and insurance, and additional taxes incurred during the delay.

109.07 Non-Recoverable Costs

The Department will not provide additional compensation for the following items and the Contractor agrees that it shall not claim for the following items of cost:

1. Home office overhead and profit in excess of that provided above;
2. Those items in **109.06** not eligible for reimbursement;
3. Loss of anticipated profits;
4. Labor inefficiencies and loss of productivity;
5. Attorney fees, claim preparation expenses, and cost of litigation; and

6. Consequential damages, including but not limited to, interest of monies in dispute, loss of bonding capacity, any indirect costs or expenses, interest on investment or any resultant insolvency.

109.08 Partial Payment

The Department will make monthly payments to the Contractor for work performed and materials placed under the Contract, and for materials delivered and stored in accordance with **109.09**. The monthly payment is an estimate, and all partial payments are subject to correction in the Final Payment. The Department will not make partial payments of less than \$1,000.

The Department will not withhold retainage from the Contractor.

After the first partial payment, the Department reserves the right to withhold subsequent partial payments until the Contractor satisfies the Department that the work for which payment is made was performed in accordance with the Contract, and each subcontractor or supplier has been paid for labor, material, and equipment costs on a current basis, or there exists a valid basis for withholding payment to subcontractors or suppliers.

Partial payment for work or materials does not constitute acceptance or approval of defective work or material. Should the Department discover defective construction or material, or a reasonable doubt exists as to the satisfactory quality of any part of the construction completed prior to final acceptance and payment, the Department reserves the right to deduct from current or future pay estimates an amount sufficient to ensure the repair or replacement of such work by the Contractor or by others as may prove necessary.

109.09 Payment for Stockpiled Materials

When requested in writing by the Contractor and approved by the Engineer, the Department may make partial payment of non-perishable materials that will be permanently incorporated into the Project. Stockpile these materials in an approved manner on or near the Project site or in special cases at an offsite location because of fabrication. Limit these off-site locations to special cases where the material cannot be readily stockpiled at the Project site such as steel structure components and prefabricated bridge components. Clearly mark material stored at an off-site location with the Project information. Provide a map noting the location. Store the stockpiled material in an approved manner so that the quality of the material is not compromised.

109.09

The Department will not make payment prior to inspection and documentation by the Engineer. Clearly identify material, whether stored on-site or off-site, in order to reference the quantity and assigned Project.

The Department may only consider partial payment for an invoice or accumulation of invoices totaling \$5,000 for each eligible pay item. Individual invoices shall not total less than \$2,500. Invoices may include tax and freight. Partial payment shall not exceed 100% of the invoice amount or 75% of the Contract unit price, whichever is less.

Materials that may be included in partial payments are: aggregates (stored at the Project, not at a quarry), reinforcing steel, bridge piling, structural steel (fabricated units or steel delivered to fabricator if designated for particular project), precast concrete structures, traffic signal equipment, electrical equipment, fencing materials, sign materials, guardrail, and others as approved by the Engineer.

Materials that may not be included in partial payments are: living or perishable plant materials, seed, fuel, used materials, form lumber, falsework, temporary erosion items, and other temporary items that will not become part of the completed Work.

When requesting payment for stockpiled materials, provide a written request to the Engineer that contains the following information:

1. Contract and Project numbers,
2. Item number and description as stated in the Contract proposal,
3. Quantity and unit of measure as stated in the contract proposal and/or project documents,
4. Conversion factor, if applicable,
5. Written statement of assurance that material will be used on the specific project,
6. Written consent of contractor's surety,
7. Material certifications/test reports for the material, and

8. Copy of certified paid invoice (in order to certify, a representative of the supplier must mark the amount of the invoice as actually paid, and shall sign and date it).

If the certified paid invoice is unavailable, the Engineer may conditionally approve a stockpile payment with receipt of the Surety's consent and a copy of the unpaid invoice. However, the Contractor shall submit the certified paid invoice within thirty (30) calendar days following the date of the progress payment for which the stockpiled material was paid. If the certified paid invoice is not submitted, the Department will deduct the stockpile payment from the next progress payment. Additional requests for stockpile payment of that item must be accompanied by a certified paid invoice, or the request for stockpile payment will not be paid.

Stockpile payments shall not exceed the Contract amount, unless the Contract amount is increased by an approved Change Order. The Department will not make payment for items that will be incorporated permanently into the Project within thirty (30) calendar days from request of stockpile payment.

Protect the stockpile materials from the elements and against loss or damage by any cause. If any stockpiled materials are lost, stolen, impaired or damaged after partial payment has been made, the Department will deduct the monetary value of the lost, stolen, impaired or damaged material from the next estimate, and will not make further payment until such material has been satisfactorily replaced in accordance with the Contract.

109.10 Final Payment

After inspecting and accepting the Project in accordance with **105.15**, the Engineer will prepare a pre-final estimate for the Contract that reflects the following:

1. All accepted final contract quantities,
2. All previous partial payments, and
3. Any increases or deductions made in accordance with the Contract.

The Engineer will submit the pre-final estimate to the Contractor for review and acceptance. Within thirty (30) calendar days of receipt of this estimate, notify the Engineer of whether the final quantities are acceptable or not acceptable. If not acceptable, provide an item-by-item list with reasons for disagreement with the pre-final estimate. After considering the reasons for disagreement, the Engineer may or may not revise the final estimate based on its review of the Contractor's justification.

109.11

When the Project has been accepted, the Department will advertise a thirty (30) calendar day notice in accordance with TCA §54-5-122, in a newspaper published in the county where the Work is done, if there is a newspaper published there, and if not, in a newspaper in an adjoining county. The notice will state that settlement is about to be made and all claimants must file notice of their claims with the Department in accordance with TCA §54-5-122. The period for filing a notice of claim shall not be less than thirty (30) calendar days after the last published notice. No notice of claim is valid unless it is certified and filed after the publication of the first notice.

The Contractor shall furnish evidence to satisfy the Department that all the materials used have been paid for, its subcontractors or agents have been fully paid, and all of the Contractor's laborers and other employees have been fully paid.

If no claims are filed within the thirty (30) calendar day period, and the Contractor has provided the required evidence of payment and releases, the Department will make full settlement and final payment to the Contractor.

The Engineer will not require the Contractor to maintain the Project or perform any further construction after final acceptance in writing by the Engineer, except as otherwise provided.

109.11 Payment of Costs Owed to the Department

Notwithstanding anything to the contrary in the Contract, the Contractor shall be liable to the Department for any or all of the following: fraud or such gross mistakes as may amount to fraud, the Department's rights under any warranty or guarantee, or latent defects in the Work.

The Department reserves the right to set off the following against any contractual amount otherwise due the Contractor or its Sureties, or both:

1. All costs that the Department has incurred due to Contractor or Surety noncompliance with this Contract, and
2. Any other amounts that the Contractor or its Sureties, or both, owe the Department.

PART 2 – EARTHWORK

SECTION 201 – CLEARING AND GRUBBING	124
SECTION 202 – REMOVAL OF STRUCTURES AND OBSTRUCTIONS	129
SECTION 203 – EXCAVATION AND UNDERCUTTING	138
SECTION 204 – STRUCTURE EXCAVATION FOUNDATION PREPARATION, AND BACKFILL.....	153
SECTION 205 – EMBANKMENTS.....	174
SECTION 206 – FINAL DRESSING	182
SECTION 207 – SUBGRADE CONSTRUCTION AND PREPARATION.....	183
SECTION 208 – SHOULDERS AND DITCHES.....	188
SECTION 209 – PROJECT EROSION PREVENTION AND SEDIMENT CONTROL	191

201.01

SECTION 201 – CLEARING AND GRUBBING

201.01 Description	124
201.02 Reserved.....	124
201.03 Clearing and Grubbing.....	124
201.04 Disposal of Debris.....	127
201.05 Method of Measurement	128
201.06 Basis of Payment.....	128

DESCRIPTION

201.01 Description

This work consists of clearing, grubbing, removing, and disposing of all vegetation and debris within the designated limits, except such objects that are to remain or are to be removed according to other items of work. This work also includes preserving from injury or defacement all vegetation and objects designated to remain.

201.02 Reserved

CONSTRUCTION REQUIREMENTS

201.03 Clearing and Grubbing

A. General

The Engineer, or Contractor when required, will establish right-of-way and construction lines. The Engineer will designate all trees, shrubs, plants, and other objects to remain.

Avoid clearing and grubbing operations in areas designated to remain undisturbed in the Project's Stormwater Pollution Prevention Plan and applicable environmental permits.

Perform clearing and grubbing in advance of excavation and embankment operations.

B. Preparation

Before beginning construction activities, clearly mark the limits of disturbance (clearing limits) with stakes or other acceptable visible markers. Also mark all environmentally sensitive areas, such as streams, wetlands, buffers, and ARAP boundaries, included in the Project limits with markers that are readily visible to project personnel, including equipment operators.

C. Clearing and Grubbing Activities

1. **Within the Right-of-Way.** Clear all dead trees, stumps, brush, projecting roots, hedge, weeds, pole stubs, logs, and other objectionable material from the right-of-way necessary for construction, as directed by the Engineer.

Clear all hedges, weeds, pole stubs, logs, and other objectionable material, that are located inside the right-of-way but outside the construction lines, flush to the ground surface.

2. **Within 5 Feet of the Construction Lines.** Completely grub all trees, stumps, roots, pole stubs, brush, hedge, and other protruding obstructions within the area bounded by lines 5 feet outside the construction lines. The Contractor may leave in place sound, undisturbed stumps and roots that will be a minimum of 5 feet below subgrade or slope of embankment under the following conditions:
 - a. Undercutting or other corrective measures, or topsoil stripping, is not stipulated in the Plans or directed by the Engineer; and
 - b. Stumps do not extend more than 6 inches above the ground surface.
3. **More than 5 Feet Outside the Construction Lines.** Do not disturb, and protect from damage and injury, living trees that have not been marked for removal by the Engineer and that are located more than 5 feet outside the construction lines of the road. Treat cut or scarred surfaces of trees or shrubs with a paint prepared especially for tree surgery.

201.03

Cut off trees marked for removal by the Engineer, to within 6 inches of the ground surface. Trim all stumps to within 6 inches of the ground surface.

4. **Swampy Areas.** When embankments are to be constructed in swampy areas, and undercutting or other corrective measures are not shown on the Plans or directed by the Engineer, the Contractor may, with the Engineer's approval, cut off undisturbed trees and stumps at not more than 6 inches above the ground surface or low water level and leave the stump and root mass in place.
5. **Borrow Pit Areas.** In areas approved as borrow pits by the Engineer, clear and grub all trees, stumps, brush, and heavy vegetation.

In areas designated for obtaining construction material other than borrow, clear and grub trees, stumps, brush, and vegetation, and strip overburden lying above the material to be obtained.

Complete this work prior to removing borrow or construction materials.

6. **Drainage Areas and Structures.** Clear slopes of cuts, embankments, ditches, channels, waterways, and all structures, both old and new, of all brush, hedges, weeds, heavy vegetation, and other objectionable material. Maintain such areas in a neat and satisfactory condition until the Project is accepted.

Clear areas that are within the limits of drainage structures of all objectionable material to within 3 inches of the ground surface. Such areas shall extend the full length of the structures, as measured along the centerline of the highway, and to the right-of-way lines along lines parallel to the centerline of the inlet and outlet channel or drainage of the structure. These areas shall also include the entire area of all easements obtained for drainage purposes.

7. **Removing Branches.** Remove, as directed by the Engineer, low hanging, unsound, or unsightly branches on trees or shrubs designated to remain. Trim tree branches that extend over the roadbed to provide a clear height of 20 feet above the roadbed surface. Perform trimming operations using skilled workmen and good tree surgery practices.

D. Backfilling

Within the areas where embankments are to be constructed, backfill all depressions resulting from grubbing operations with suitable excavation material, and compact as specified in **205** to the natural ground elevation before starting embankment construction.

Backfill, with suitable material, all depressions in excavation areas that lie below the finished subgrade elevation due to grubbing operations, and compact to the finished subgrade elevation as specified in **205** during the excavation operations.

Complete backfilling a satisfactory distance ahead of embankment construction operations.

201.04 Disposal of Debris

Properly dispose of wood debris that is chipped onsite so that does not become part of embankment.

If burning perishable material, follow applicable laws and ordinances. Ensure burning operations proceed under the constant care of competent watchmen, at times and in a manner that will not harm the surrounding vegetation, adjacent property, or anything designated to remain within the right-of-way.

If the construction is through land subject to scour, the Engineer may direct the Contractor to dispose of stumps, logs, brush, and similar material in the scoured ditches within the right-of-way, and to cover the material so deposited with suitable excavation or borrow material. If the Contractor obtains permission to dispose of such material in scoured ditches on private property that is within view of the roadway, the Contractor shall thoroughly cover the material so deposited with suitable material at no cost to the Department.

All merchantable timber in the clearing area that has not been removed from the right-of-way before the start of construction shall become the property of the Contractor unless otherwise specified.

201.05

COMPENSATION

201.05 Method of Measurement

If the Contract contains an item for Clearing and Grubbing on a lump sum basis, the Department will not measure the area cleared and grubbed.

In cases where changes in the Contract documents affect the right-of-way area or when additional Clearing and Grubbing is required in conjunction with Road and Drainage Excavation (Additional Material) under **203**, the Department will make a proportionate adjustment for the increased or decreased area; however, if the bid schedule includes the item for Adjusted Clearing and Grubbing, then the Department will measure and pay for these area adjustments by the acre.

Unless otherwise shown on the Plans, no separate measurement or payment will be made for the items of work defined under Clearing and Grubbing.

For Contractor-supplied borrow pits, the Contractor shall include clearing and grubbing costs in the unit price bid for Borrow Excavation under **203**. For Department-obtained designated borrow pit areas, the Department will measure and pay for clearing and grubbing by the acre, provided the item for Clearing and Grubbing (Borrow Pits) is in the Contract. If the item for Clearing and Grubbing (Borrow Pits) is not in the Contract, the Contractor shall include the costs of clearing and grubbing such designated borrow pit areas in the unit price bid for Borrow Excavation.

If the Contract does not contain an item for Clearing and Grubbing, the Department will consider all Clearing and Grubbing required within the construction limits as incidental to other items of work.

201.06 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Clearing and Grubbing	Lump Sum
Clearing and Grubbing (Borrow Pits)	Acre
Adjusted Clearing and Grubbing	Acre

Such payment is full compensation for providing all materials, equipment, labor, and incidentals to complete the work as specified.

SECTION 202 – REMOVAL OF STRUCTURES AND OBSTRUCTIONS

202.01	Description.....	129
202.02	Reserved.....	129
202.03	General.....	130
202.04	Removal of Bridges, Culverts, and Other Drainage Structures....	131
202.05	Removal of Pipe.....	133
202.06	Removal of Pavement, Sidewalks, and Curbs Constructed of Portland Cement Concrete	133
202.07	Removal of Underground Storage Tanks.....	133
202.08	Water Well Abandonment	134
202.09	Method of Measurement	136
202.10	Basis of Payment.....	136

DESCRIPTION

202.01 Description

This work consists of removing, entirely or partially, and disposing of all buildings, fences, structures, old pavements, abandoned pipelines, and other obstructions not designated or permitted to remain, except for obstructions to be removed and disposed of under other contract items. The work also includes backfilling the resulting trenches, holes, and pits, and salvaging designated materials.

If the Contract does not include pay items for Removal of Structures and Obstructions, include such work in the prices bid for other items of construction.

202.02 Reserved

202.03

CONSTRUCTION REQUIREMENTS

202.03 General

Raze, remove, and dispose of all buildings and foundations, structures, fences, and other obstructions as shown on the Plans. Do not remove utilities and obstructions for which other provisions have been made.

Remove material designated for salvage in readily transportable pieces, and store the removed pieces at specified locations within the Project limits. Replace with new material, at no additional cost to the Department, those materials designated for salvage that are damaged during removal, transport, or storage operations. Take ownership of material not designated for the Department's use, and dispose of such material beyond view from the Project limits.

The Department reserves the right to dispose of buildings on any tract before they are torn down or removed by the Contractor. If structures designated for removal by the Contractor contain friable asbestos, conduct demolition activities according to TDEC policy and regulations, including providing prior notification to TDEC of all pending demolitions. The Department will remove friable asbestos from other structures to be demolished either prior to, or concurrently with, the Work. The Department's removal of friable asbestos may or may not include complete demolition of the structure. Remove structures, or portions of a structure, remaining after the Department's removal of asbestos under the appropriate item or in accordance with **202.01**, as applicable.

Buildings and other structures that the Plans show as being removed or disposed of by other agencies will not be held as a charge or responsibility of the Contractor, except that the Contractor waives any and all claims for interference, delay, or damage due to their removal or non-removal.

Remove foundations of buildings and other structures to a depth of not less than 1 foot below natural ground, except that within construction limits, remove to a depth of not less than 2 feet below subgrade elevation. Break up basement floors to prevent water retention. Fill basements or cavities left by structure removal to the level of the surrounding ground or to subgrade elevation within the prism of construction. Compact the material placed in these cavities as specified in **205**.

202.04 Removal of Bridges, Culverts, and Other Drainage Structures

Do not remove structures in use by traffic until after making arrangements to accommodate traffic.

Remove all bridges, culverts, and drainage structures from streams according to the terms and conditions specified in the applicable environmental permits, including the TN Construction General Permit. Use highly visible markers to clearly mark permit boundaries and disturbed area limits.

Unless otherwise specified or directed, remove portions of bridge substructures that are located outside a stream to 1 foot below the adjacent ground level or natural stream bottom, or the lowest scour elevation shown on the Plans. For those portions that are located in a stream or wetland, adhere to the permit form of the applicable State and Federal agencies approving the location and plans and authorizing the construction of the bridge. Remove, as necessary, those portions of existing structures that lie entirely or partially within the limits of a new structure to accommodate the construction of the proposed structure.

Without causing unnecessary damage, dismantle bridges designated for salvage, and store such material as specified in **202.03**.

Remove bridge decks according to the following:

1. Where bridge decks are to be entirely removed, but the girders are to remain in service:
 - a. The Contractor may apply transverse saw cuts to help remove the concrete deck, but the depth of the cut may not exceed:
 - (1) 3 inches for decks supported by steel beams or girders;
 - (2) 3 inches for decks supported by prestressed concrete beams; and
 - (3) 1 inch for decks of cast-in-place hollow box or t-beam bridges.
 - b. Use pneumatically or electrically operated chipping hammers, not exceeding 60 pounds in weight, to remove the remainder of the slab depth under the cuts.

202.04

- c. Longitudinal saw cuts may be full depth, but no closer than the following:
 - (1) For decks supported by steel beams or girders, within 1 inch of the widest top flanges;
 - (2) For decks supported by prestressed beams, within 1 inch of the top flange; and
 - (3) For decks of hollow boxes or t-beam bridges, within 1 inch of the web, unless otherwise shown on the Plans.
2. To remove slab overhangs, the Contractor may use concrete saws to remove the top 1 inch of the slab and pneumatically or electrically operated chipping hammers, not exceeding 60 pounds in weight, to remove the remainder of the concrete. Do not damage transverse slab reinforcing bars.
3. When removing bridge decks as part of a complete bridge demolition, the Contractor may use concrete saws to remove the deck, but the depth of the cuts may not exceed the following:
 - a. For decks supported by steel beams or girders, the plan depth of slab minus 1 inch.
 - b. For decks of hollow box or t-beam bridges, if not otherwise shown on the Plans, the Contractor shall submit a plan to the Engineer for approval.

Do not use hoe rams, pneumatic shears, pavement breakers, or other heavy equipment to remove slabs where girders or adjacent slab portions are to remain.

Complete blasting or other operations necessary to remove an existing structure or obstruction without damaging new construction. Complete such operations prior to placing the new work, or take adequate precautions to prevent such damage.

202.05 Removal of Pipe

Remove, and store when necessary, pipe designated for salvage so that no loss or damage occurs. Replace, at no cost to the Department, sections damaged by negligence or by the use of improper methods.

202.06 Removal of Pavement, Sidewalks, and Curbs Constructed of Portland Cement Concrete

As directed, dispose of pavement, base course, sidewalks, curbs, gutters, and similar features constructed of Portland cement concrete designated for removal. If the Plans do not identify the existence of concrete pavement under asphaltic pavement, do not interpret this as meaning that no concrete is present. Remove and dispose of concrete pavement, parking strip, and base, all with or without bituminous overlay, concrete curb and gutter, sidewalk, driveways, and similar features as follows or as directed:

1. If the items are no more than 2 feet below subgrade elevation, remove and dispose of the items according to **202**.
2. If the items are more than 2 feet below subgrade elevation, break them into sections no greater than 2 feet in maximum dimension and leave in place, unless doing so will interfere with succeeding items of construction. Include the cost of this work in the unit price bid for other items of construction.
3. If the items are above subgrade elevation, include their removal and disposal with the work performed under **203**.
4. When specified, remove and stockpile ballast, gravel, bituminous pavement, or other pavement materials in accordance with **202.03**; otherwise, dispose of such materials as directed.

202.07 Removal of Underground Storage Tanks

A Petroleum Underground Storage Tank refers to any one or combination of tanks including underground piping, which is used or has been used to contain petroleum substances and the volume of which is 10% or more beneath the surface of the ground.

The Department will remove and dispose of Petroleum Underground Storage Tanks or Tank Systems through its Environmental Consultant. This work will include removal and disposal of piping, pumps, and other tank fixtures,

202.08

the investigation and testing of the tank(s) for leakage, and backfilling the resulting holes or trenches as shown on the Plans or as approved by the Engineer. The Department's Environmental Consultant will perform this work according to the Tennessee Petroleum Underground Storage Tank Act, TDEC policies and regulations, the United States Environmental Protection Agency, and local ordinances or statutes governing removal of Underground Storage Tanks.

If the Contract includes an item for Removal and Disposal of Underground Tanks, before work begins, submit an application for closure of each Petroleum Underground Storage Tank or Tank System to the TDEC, Division of Underground Storage Tanks. In addition, the Contractor shall:

1. Provide the Engineer with copies of the application for closure, the TDEC's approval of that application, laboratory test reports, closure notification form, and all pertinent correspondence.
2. Engage a laboratory approved by the TDEC to perform all required sampling and testing for leakage and contamination before and after removal of the tank(s). Upon receipt of written approval from the TDEC, remove the tank(s) according to TDEC regulations. If soil testing either before or after tank removal reveals soil contamination, remove and dispose of the contaminated soil according to TDEC regulations.
3. After removal, take ownership of the tank(s) and tank fixtures unless otherwise shown on the Plans. Ownership of the tank(s) shall not relieve the Contractor of the responsibility of labeling, transporting, and disposing of the tank(s) according to TDEC regulations.
4. After removing the tank(s) and contaminated soil, backfill the hole or trench as necessary with material specified on the Plans or approved by the Engineer.

202.08 Water Well Abandonment

Locate and seal abandoned water wells, and remove and dispose of pumps, pipe, and other related items not provided for elsewhere in the Contract. Perform all work according to applicable TDEC regulations.

Seal abandoned wells as follows:

A. Wells with a Diameter of 1 Foot or Less

Retain a licensed driller or pump installer to remove all pumps and related plumbing. Clear the bore hole of all other obstructions. A licensed well driller shall clean the bore hole by drilling, blowing, or bailing as applicable. To disinfect the well, add laundry bleach to the water in the well to equal 1 quart of bleach for each 100 gallons of water. Obtain the number of gallons of water in the well as follows:

$$V = [D_{\text{well}} - D_{\text{swl}}] \times 0.0408 (\text{Dia}^2)$$

Where:

V	=	volume of water in the well in gallons
D _{well}	=	total depth of the well in feet
D _{swl}	=	depth to static water level in feet
Dia	=	diameter of the well in inches

After disinfecting the well, the licensed well driller shall fill the well using flowable fill. Use bentonite or other approved colloidal reagent as an admixture in an amount equal to 1.5% by volume of the cement.

The flowable fill material shall extend from the bottom of the well to within 5 feet of the final surface where the well is in a roadway cut, or to within 5 feet of the existing ground surface where the well is located under roadway embankment or where the well is outside of the construction limits. Pipe the flowable fill directly to the point of application by a tremie or dump bailer to avoid segregation or dilution. Cut off the well casing flush with the top of the flowable fill material.

B. Wells with Diameter Greater than 1 Foot

Remove all pumps and related plumbing, and clear the well of all other obstructions as described in **202.08.A**. Disinfect the water in the well by adding 1 quart of bleach for each 100 gallons of water. Compute the amount of bleach to be used as described in **202.08.A**.

Fill the bottom 5 feet of the well or a depth equal to the depth of the water, whichever is greater, with flowable fill as specified in **202.08.A**. Fill the remainder of the well with compacted soil. Remove projecting well casings or walls or cut off 5 feet below the existing or proposed ground surface, as applicable.

202.09

If flowable fill loss is excessive due to crevices in the borehole wall, use Mineral Aggregate, Type A Base, Grading D, meeting **903.05**, to seal the crevices. After sealing the crevices, resume filling with flowable fill.

Immediately after sealing the wells, provide an affidavit to the Tennessee Water Supply Division stating the name of the licensed contractor(s) who performed the cleaning and sealing of the wells, the project number, location of the wells, type and sequence of material used, volume of material used, and date completed.

COMPENSATION

202.09 Method of Measurement

If the Contract specifies that Removal of Structures and Obstructions is on a lump sum basis, the work will include all structures and obstructions encountered within the right-of-way, except for structures and obstructions specified for removal on a unit basis.

If the Contract specifies removal of specific items on a unit basis, the Department will measure the quantity of each item by the unit stipulated in the Contract.

202.10 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Removal of Structures and Obstructions	Lump Sum, or Each
Removal of Pipe (Size, Sta)	Linear Feet
Removal of Rigid Pavements, Sidewalks, etc.	Square Yard
Removal of Undergrounds Tanks (Tract No. _____)	Lump Sum
Removal of Buildings (Tract No. _____)	Lump Sum
Water Well Abandonment	Lump Sum

Payment for Removal of Underground Tanks (Tract No. _____) includes locating, drilling, testing, removing, and disposing of Underground Storage Tanks, piping, pumps, and other tank fixtures, any portion of which is on the designated tract, and hauling, placing, and compacting backfill where required.

If soil testing reveals contamination, the Department will pay for the removal and disposal of contaminated soil under the item for Road and Drainage Excavation (Unclassified) in accordance with **203**, provided the volume is 500 cubic yards or less. However, the Department may consider the removal, disposal, and replacement of contaminated soil in excess of 500 cubic yards as Extra Work under **104.02.D** and will then pay for such work in accordance with **109.04**.

Payment for Water Well Abandonment includes all labor, equipment, materials, including flowable fill, and incidentals necessary to complete the work.

Payment for removing specific obstruction items, including Removal of Pipe and Removal of Rigid Pavements, Sidewalks, etc., includes the removal of such items; excavation and subsequent backfill incidental to their removal; salvage of materials removed, their custody, preservation, and storage within the right-of-way; and disposal.

The Department will only make payment when payment for all or any part thereof is provided for in a pay item.

203.01

SECTION 203 – EXCAVATION AND UNDERCUTTING

203.01 Description	138
203.02 Classification.....	138
203.03 Reserved.....	141
203.04 General.....	141
203.05 Undercutting.....	145
203.06 Stripping, Stockpiling, and Placing Topsoil.....	146
203.07 Disposing of Excess or Unsuitable Material	147
203.08 Shaping and Dressing.....	147
203.09 Method of Measurement	147
203.10 Basis of Payment.....	151

DESCRIPTION

203.01 Description

This work consists of excavating and grading the roadway (including the removal of slides), borrow pits, waterways, and ditches (including structure inlet and outlet ditches, channels, waterways, and similar features, even if they extend beyond the highway limits); excavating for intersections, approaches, and benches under the side-hill embankments; excavating unsuitable material from roadbed and beneath embankment areas; excavating selected material found in the roadway that is required for specific use in the construction; the construction and removal of detours authorized by the Engineer or otherwise shown on the Plans; trimming and shaping of all slopes; and disposing of all excavated material.

The work also includes all embankment construction as specified in **205**, shoulder and ditch construction as specified in **208**, and if the Contract includes construction of pavement or other surfacing, Subgrade Construction and Preparation as specified in **207**.

203.02 Classification

The Department will classify excavation as follows:

A. Road and Drainage Excavation (Unclassified)

The Department will consider all excavation performed under this item, including Portland cement concrete located above subgrade elevation, other than Borrow Excavation, Channel Excavation, and Undercutting, as unclassified excavation regardless of the nature of the material excavated.

B. Borrow Excavation

Borrow Excavation consists of material required for the construction of embankments or other portions of the work.

The Contractor may use excavated materials, other than Borrow Excavation (Unclassified), on the Project as specified in **104.09** provided it meets the specifications of the designated borrow material. However, if the flattening of certain cut slopes on projects graded under previous contracts is desirable and approved in writing by the Engineer, the Contractor may use this material for borrow if the material is satisfactory and in accordance with plans approved by the Engineer, and if the requirements of **203.04.E** regarding borrow areas are met.

Do not obtain borrow material from wetland areas, unless otherwise shown on the Plans and approved by applicable environmental permits.

The Department will classify borrow as:

1. **Borrow Excavation (Solid Rock)**, which consists of removing and placing non-degradable rock that cannot be economically excavated by the proper use of a power shovel or without the use of explosives.
2. **Borrow Excavation (Unclassified)**, which consists of removing and placing all approved material included under the classification of Borrow Excavation (Solid Rock) and all other approved material.
3. **Borrow Excavation (Graded Solid Rock)**, which consists of removing and placing sound, non-degradable rock having the following characteristics:
 - a. Maximum particle size of 3 feet in any direction.

203.02

- b. Particle size distribution in which at least 50% of the rock is uniformly distributed between 1 foot and 3 feet in diameter, and no more than 10% is less than 2 inches in diameter.
- c. Roughly equi-dimensional in shape.
- d. No thin, slabby material.

Process the material until it meets the required gradation and quality requirements of **903.25**. Obtain the Engineer's approval before using the material.

- 4. **Borrow Excavation (Select Material)**, which is used for special construction purposes and meets the requirements set forth in the Contract or shown on the Plans.

Borrow material other than solid rock, graded solid rock, or select materials shall be AASHTO M 145, classification A-6 or better if reasonably available. If classification A-6 is not reasonably available, the borrow shall be no worse than the predominant soil type in the roadway excavation based on AASHTO classification.

Do not use material obtained from an approved borrow source off the right-of-way to produce processed aggregate as described in **903**. Borrow Excavation (Graded Solid Rock) may be obtained from an approved borrow source. Do not use material excavated from an offsite borrow source in base or other paving courses above the elevation of the subgrade.

Unless otherwise designated in the Contract, arrange for obtaining borrow material according to the manual *Procedures for Providing Offsite Waste and Borrow on TDOT Construction Projects*.

C. Channel Excavation (Unclassified)

This item consists of removing and disposing of all material excavated in widening, deepening, and straightening existing channels or constructing new ones, which have a bottom width of more than 14 feet as shown on the Plans. Perform similar excavation activities for channels with a bottom width of 14 feet or less, as shown on the Plans, under the Road and Drainage Excavation (Unclassified) item. The

Department will measure Channel Excavation (Unclassified) within the limits of box bridges or box culverts according to **204.12.A.2.b**. Construct channel excavation that includes an existing stream or a proposed stream relocation in accordance with the applicable environmental permits.

D. Undercutting

This item consists of removing and disposing of unsatisfactory materials below grade in cut sections and from areas upon which embankments are to be placed, and may also include excavating material below the foundation elevation for pipe, box culverts, and box bridges as provided for in **204.12**. Undercutting does not include the stripping, stockpiling, and placing of topsoil, as specified in **203.06**, nor does it include step-benching in the preparation of embankment areas on hillsides, as provided for under **205.03**.

203.03 Reserved

CONSTRUCTION REQUIREMENTS

203.04 General

Perform the required Clearing and Grubbing, Removal of Structures and Obstructions, and placement of Erosion Control Devices as specified in **201**, **202**, and **209**, respectively, before starting excavation, grading, and embankment operations.

Address both natural and created steep slope areas as required in the TN Construction General Permit. Maintain and stabilize steep slopes according to the TN Construction General Permit and all applicable environmental permits.

Remove excavation materials so that the slopes may be neatly trimmed to the lines given. The Engineer may change the slopes shown on the original cross-sections, depress raised medians or islands, raise depressed medians or islands, or daylight cuts to increase or decrease the quantity of Road and Drainage Excavation (Unclassified) if the material can be excavated without blasting and these changes are set in the slope stakes before excavation of the affected slopes, medians, or islands begins.

203.04

Use all suitable materials removed from the excavation areas to construct embankments, intersecting road approaches, and in such other places as directed by the Engineer. Construct embankment as specified in **205**.

Remove all loose rock on cut slopes immediately.

Do not waste, deposit or dispose of excavated material outside the construction lines without the Engineer's approval. Ensure that all excavation material wasted, deposited, or disposed of outside the construction lines is in accordance with the manual *Procedures for Providing Offsite Waste and Borrow on TDOT Construction Projects*.

Temporarily discontinue excavating operations upon encountering remains of prehistoric archeological sites or artifacts of historical or archaeological significance. The Engineer will contact archaeological authorities to determine the disposition thereof.

Scarify, obliterate, and apply topsoil and seed to all existing roads within the right-of-way, and not in the graded area, which are to be abandoned. Obliteration of old roadways shall include all grading operations necessary to incorporate the old roadway into the new roadway and surroundings to provide a natural terrain appearance from the new roadway.

A. Additional Material

If more material is required to complete the embankments after all cuts have been brought to grade and all Road and Drainage Excavation (Unclassified) has been removed from within the balance, obtain additional materials from within the right-of-way by flattening, widening, or daylighting cut slopes, or by depressing raised medians or islands at locations designated and as directed by the Engineer, provided:

1. The cost of this material is more economical than borrow excavation.
2. The material is available within the adjusted balance where the shortage exists, or the material may be hauled outside the limits of adjusted balance if the cost of the material is more economical than borrow after considering the additional cost of overhaul.
3. The material can be excavated without blasting.

4. There is a minimum of 20 feet between the top of the existing slope and the top of the new slope and a minimum of 5 feet between the top of the new slope and right-of-way line or Control Access fence. The 20-foot minimum will not apply when the existing slope is 4:1 or flatter or to overlapping or near overlapping slopes in medians or between parallel roads or ramps. The Engineer may reduce the 20-foot minimum at the Contractor's written request.
5. The material has not been designated as potentially acid producing material.

B. Rock Cuts

Construct roadbed through rock cuts to the grading line shown on the Plans, with an allowable working tolerance of plus 1 inch to minus 3 inches. Bring portions of the roadway that are less than 3 inches below grade up to grade with spalls or other suitable granular material that is available from the excavation within the balance. If such excavation is not available, the Engineer may direct the Contractor to use approved base material for capping.

If the roadbed is excavated in excess of 3 inches below the grading line shown on the Plans, provide and place, at no additional cost to the Department, sufficient amounts of spalls or base material to bring the roadbed to a line 3 inches below the grading line.

Where the Plans require placement of sod on rock cuts, remove the rock to 1 foot below the grading line and backfill to grade with earthen material before placing the sod.

Where boulder formations occur, scarify the roadbed in the excavation area and remove all boulders to a depth of 12 inches below grade. Backfill and compact resulting cavities with suitable material.

C. Presplitting and Blasting

Presplit all rock cuts at the outside limits of the cut areas. Presplitting shall consist of forming a plane of split rock, for the entire depth of the cut or to a predetermined bench level, prior to any primary blasting.

To accomplish presplitting, drill holes of appropriate size to the desired depth along the outside limits of the cut area, load such holes with appropriate charges of explosives, stem with minus 3/8-inch clean stone

203.04

chips to the collar of each hole, and simultaneously detonate the charges. The initial horizontal spacing of holes and vertical spacing of charges and blasting cord for simultaneous detonation shall be as recommended by a reliable powder company. Adjust horizontal hole spacing and vertical spacing of charges as necessary to obtain a relatively smooth shear plane. Do not use sand, gravel, clay, or dirt for stemming. In drilling holes for presplitting, ensure that the drills are plumbed for vertical slopes or set on the required slope when other than vertical slopes are specified, and that all holes are drilled in the same plane. Presplitting will not be required on slopes flatter than 1:1. Presplit rock cuts under bridge sites as specified in this Subsection, but comply with the hole spacing specified in **204.08.A**.

After presplitting is done, drill primary blast holes at least 3 feet from the presplit face. Provide blasting records to the Engineer upon request. Do not perform blasting within 300 feet of any structure or concrete until at least 72 hours after concrete placement. Replace and/or repair all damage associated with blasting operations at no cost to the Department.

D. Unsuitable Soil

The Engineer will designate as unsuitable those soils that cannot be properly compacted in embankments. Dispose of all unsuitable soil as directed and at no additional cost to the Department.

If the location of unsuitable soil is shown on the Plans, remove and replace as shown.

E. Borrow Areas

Notify the Engineer before opening any borrow area to allow adequate time for the Engineer to take cross-section elevations and measurements of the ground surface after being stripped, and to test the borrow material before use. Obtain approval for the borrow area according to the *Procedures for Providing Offsite Waste and Borrow on TDOT Construction Projects*. Allow at least 30 days for testing borrow materials or other material from roadside pits proposed for construction purposes.

Borrow materials shall not contain acid producing materials. Representative samples of the proposed borrow material shall be independently tested for pH (EPA600/2-78-054 or ASTM D4239).

Material with a pH less than 5 is considered acid producing and will not be accepted.

Unless otherwise allowed, do not place borrow material until after the roadway excavation material has been placed in the embankments. If the Contractor places more borrow than is required and thereby causes a waste of excavation, the Department will deduct the amount of such waste from the measured borrow volume. Do not excavate beyond the dimensions and elevations established.

The Contractor may remove highway fencing to obtain borrow materials. Replace the fencing removed with new fence at no cost to the Department, and assume responsibility for confining livestock, as necessary.

Excavate borrow pits to be self-draining where possible and practicable, and of a shape that can be easily cross-sectioned.

After completing excavation operations, provide the area with a neat appearance. Cover all self-draining borrow areas with topsoil and stabilize. Provide and place topsoil and seeding (with mulch) as specified in **203.06** and **801**, respectively.

For borrow pits 1 acre or larger in size that are not self-draining, refer to Sections 53-801 through 53-809 of the TCA. Full information regarding the requirements to be complied with and the necessary permits that the property owner must secure for the construction of a pond, lake, borrow pits, etc., 1 acre or larger that is not constructed to drain, will be supplied upon application to the TDEC.

203.05 Undercutting

The Department will designate areas to be undercut on the Plans if appropriate information is available. However, the Engineer may increase, decrease, or shift such designated areas as conditions require during construction.

Backfill undercut areas with suitable material from within the grading balance, or in the first 1,000 feet of the adjacent balances if obtainable. If road and drainage excavation is not available, use borrow excavation as backfill.

203.06

Conduct operations so that the Engineer can take the necessary cross-sectional measurements.

Compact backfill materials as specified in **205**.

If disposing of undercutting material off the right-of-way, adhere to the manual *Procedures for Providing Offsite Waste and Borrow on TDOT Construction Projects*, and obtain advance approval for the disposal site from the Engineer, Environmental Coordinator, and the Environmental Division.

203.06 Stripping, Stockpiling, and Placing Topsoil

The Engineer will designate areas for stripping and stockpiling existing topsoil between slope stake points in both cut and fill areas. Strip the quantity of material necessary to cover all areas to be seeded with 2 to 3 inches of topsoil. If the quantity of topsoil available in such areas is insufficient, obtain additional topsoil from an approved borrow area according to the manual *Procedures for Providing Offsite Waste and Borrow on TDOT Construction Projects*.

The Engineer will designate areas to be deleted from stripping operations because of rock or other unsuitable material.

Before performing stripping operations, notify the Engineer. Stockpile the stripped topsoil in the areas designated by the Engineer. Neatly dress each stockpile, when completed, to facilitate measurement.

Immediately before the Contractor prepares an area for seeding, the Engineer will take cross-section measurements of the topsoil stockpiles. Until the construction sequence for seeding has been established and is ready to proceed, the Engineer will not cross-section stockpiles, and the Contractor shall not spread topsoil.

Place a 2 to 3-inch layer of topsoil on all areas requiring seeding or sod, except for cut slopes steeper than 2:1. On cut slopes steeper than 2:1 that require seeding or sod, spread topsoil to a depth of 1 to 2 inches, as directed by the Engineer. Cover rock slopes and other rock areas that require seeding with 9 inches of suitable material and 2 to 3 inches of topsoil. After placing the stockpiled topsoil, neatly dress the former stockpile areas and allow the Engineer to take final cross-sections.

203.07 Disposing of Excess or Unsuitable Material

Use excess excavation material to raise, widen, or flatten the slopes of embankments; to fade embankments into cuts; or to place in such other locations and for such purposes as the Engineer may direct.

The Engineer will provide specific instructions regarding the disposal of surplus material. Place and compact excess or unsuitable material within the right-of-way limits as specified in **205.04**. Foundation preparation for and drainage through these waste areas shall be equivalent to that provided for the adjacent roadway embankment.

If no suitable place can be found to dispose of excess or unsuitable material within the right-of-way, the Engineer may direct the Contractor to provide a suitable offsite disposal area at no additional cost to the Department in accordance with the manual *Procedures for Providing Offsite Waste and Borrow on TDOT Construction Projects*.

Ensure the offsite disposal grading plan is properly designed (including but not limited to slope stability and fill placement recommendations) regulated, and implemented.

203.08 Shaping and Dressing

Trim and shape the slopes of all excavated areas, ditches, waterways, channels, borrow pits, and embankments to be in reasonably close conformity with the cross-sections shown on the Plans or as directed by the Engineer.

Scale all loose fragments, projecting points, and debris from rock cuts, and leave in a neat, safe, and workmanlike condition.

Dispose of excess material created by trimming slopes, resloping, and shaping as specified in **203.07**.

Perform Final Dressing as specified in **206**.

COMPENSATION**203.09 Method of Measurement**

Where excavation of different classifications overlap, the following order of measurement and computation for payment applies:

203.09

1. Road and Drainage Excavation (Unclassified) or Channel Excavation (Unclassified) shall supersede Structure Excavation and Foundation Preparation. Road and Drainage Excavation (Unclassified) shall supersede Channel Excavation (Unclassified).
2. Excavation, the cost of which is included in lump sum items or the unit price bid for other items of construction, shall supersede all other classifications.

Excavation of embankment will not be measured for payment unless the Engineer approved the excavation in writing.

Where it is impracticable to measure material by the cross-section method due to the erratic location of isolated deposits, the Department may use methods involving three-dimensional measurements.

The Department will measure water used in the work by the M.G. (1,000 gallons) using calibrated tanks or distributors, or accurate water meters.

A. Road and Drainage Excavation

1. The Department will measure Road and Drainage Excavation by the number of cubic yards of material, acceptably excavated, measured in its original position by cross-sectioning the area excavated. The Engineer may determine cross-sections from conventional manual surveys, aerial surveys, Digital Terrain Modeling, or a combination of these methods.
2. The Department will measure excavation required to bench side-hill slopes of embankment construction as follows:
 - a. Excavation in solid rock will be paid for as Road and Drainage Excavation (Unclassified) whether the excavation material is bladed and dozed or picked up and hauled.
 - b. For excavation in other than solid rock:
 - (1) The Department will measure excavated material that is picked up and hauled as Road and Drainage Excavation (Unclassified).

- (2) The Department will not directly measure excavation material moved by blading or dozing and will consider such work as incidental to other items.
3. When the Plans specify or the Engineer directs that rock embankment material be obtained from the roadway excavation, all costs of constructing the rock embankment material, including, but not limited to, excavating, reserving, hauling and placing, will be measured and paid for under the item for Road and Drainage Excavation (Unclassified) and no additional compensation will be made for this work.
 4. Authorized excavation of rock, shale, or unsuitable material below grade consists of that excavation necessary to provide the designed thickness of backfill. If the plane of the designated bottom of excavation falls within a layer or stratum of rock, the below-grade excavation to the bottom of the layer, not exceeding 3 inches below grade, will be considered as authorized and will be measured for payment. If the Engineer directs the Contractor to use approved base material to bring portions of the roadway that are less than 3 inches below grade up to grade, the Department will measure and pay for the furnishing and placing of such base material in tons under the applicable item in **303.15**. If base material is not a bid item in the Contract, the Contractor shall provide the material under the provisions of **104.02.D**.

If the roadway is excavated in excess of 3 inches below the grading line shown on Plans, the Contractor shall furnish and place, at no cost to the Department, sufficient amount of spalls or approved base course material, or other suitable approved granular material, to bring the roadway to a line 3 inches below the grading line.

B. Road and Drainage Excavation (Additional Material)

1. If the Engineer adjusts the slopes shown on the original cross-sections, depresses raised medians or islands, or flattens, widens, or daylight cuts, the Department will measure the additional material thus obtained in cubic yards under Road and Drainage Excavation (Additional Material).
2. If additional material is paid for under the item for Road and Drainage Excavation (Additional Material) and additional clearing and grubbing is required, the Department will measure and pay for

203.09

the additional clearing and grubbing by the acre, provided the item for Adjusted Clearing and Grubbing is in the Contract, or as negotiated. No additional payment will be made for extra handling of stockpiled topsoil made necessary by the use of the item for Road and Drainage Excavation (Additional Material).

C. Borrow Excavation

The Department will measure and pay for Borrow Excavation by the cubic yard or ton in accordance with **109**.

D. Presplitting

If the Contract contains an item for Presplitting, the Department will measure presplitting of rock cuts by the number of square yards of rock face determined by multiplying the difference in elevation in yards between the bottom and top of face at each station and intermediate stations (where break sections are needed to accurately show the work) by the length of face in yards taken from cross-sections. If the Contract does not have an item for Presplitting, the required presplitting shall be included in the price bid for Road and Drainage Excavation or Channel Excavation (Unclassified).

E. Undercutting

1. The Department will measure unsuitable materials excavated and removed to obtain proper compaction in cut sections, in foundations for fill sections, and for pipe and box culverts in accordance with **204.12**. The removal and disposal of this unsuitable material will be classified as Undercutting, unless otherwise specified.
2. The Department will not measure suitable material temporarily removed and replaced to facilitate compaction of the material for the full depth shown on the Plans.
3. The Department will measure Undercutting by the cubic yard based on cross-sectional measurement or the most feasible method.

F. Topsoil

1. Except for topsoil obtained from a source outside the right-of-way, the Department will measure and pay for stripping and stockpiling

of topsoil as Road and Drainage Excavation (Unclassified) by the cubic yards of material in its original position.

2. The Department will measure the Placing and Spreading of stockpiled topsoil on slopes and elsewhere within the right-of-way by the cubic yards of material in the stockpile as determined using the cross-section method.
3. Furnishing and Spreading Topsoil obtained from an approved borrow source located outside the right-of-way will be measured by the cubic yards of material removed as determined by cross-sectioning the area before and after removal.

203.10 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Road and Drainage Excavation (Unclassified)	Cubic Yard
Road and Drainage Excavation (Additional Material)	Cubic Yard
Channel Excavation (Unclassified)	Cubic Yard
Borrow Excavation (_____)	Cubic Yard or Ton
Presplitting of Rock Excavation	Square Yard
Undercutting	Cubic Yard
Placing and Spreading Topsoil	Cubic Yard
Furnishing and Spreading Topsoil	Cubic Yard
Water	M.G.

Such payment is full compensation for providing all materials, including hauling excavation and borrow, and providing all equipment, labor, and incidentals to complete the work as specified.

The Department will pay for Road and Drainage Excavation (Additional Material) at a rate per cubic yard equal to 1.5 times the contract unit price for Road and Drainage Excavation (Unclassified).

The Department will pay for excavation required to correct slides, regardless of its location relative to the theoretical slope line, or excavation required to prevent potential slides including blasting, and the dressing, reshaping or flattening of the affected slopes as directed by the Engineer, under the item for Road and Drainage Excavation (Additional Material). If it becomes

203.10

necessary to flatten a slope to correct a slide or prevent a potential slide after the cut has been started but not completed, payment under Road and Drainage Excavation (Additional Material) will be limited to material removed between the original staked slope line and the newly established slope line above the elevation to which the cut has been made. The Department will pay for all other material at the contract unit price of Road and Drainage Excavation (Unclassified). Seeding, sod and other items required to repair the slide area will be paid for at the contract unit price bid for the respective items.

The Department will pay for Undercutting at the contract unit price per cubic yard. If unsuitable material not described in the Plans is encountered and no contract unit price has been established for Undercutting, the Department will pay for this work at a rate per cubic yard equal to 1.5 times the contract unit price for Road and Drainage Excavation (Unclassified) due to the nature of the unforeseen, slower production work. However, if the unsuitable material is known and described in the Plans and has been accounted for in grading quantities (either Undercutting or Road and Drainage), it will be paid at the contract bid price.

If the Plans require placement of sod on rock cuts, the Department will pay for rock removal, earthen backfill, and sod placement under Road and Drainage Excavation (Unclassified) and Sodding (New Sod).

The Department will pay for furnishing and placing topsoil and seeding waste areas inside the right-of-way at the contract unit prices for the respective items. The Department will not directly pay for furnishing and placing topsoil and seeding waste and borrow areas located outside the right-of-way.

The Department will pay for the removal of concrete pavement, base, parking strip, and sidewalk, curb and gutter, and similar features under the classifications specified in **202.06** and **203.02.A**.

The Department will pay for roadway obliteration as Road and Drainage Excavation (Unclassified). The Department will pay for the application of topsoil and seed to obliterated roadways under the items for Topsoil and Seeding.

**SECTION 204 – STRUCTURE EXCAVATION
FOUNDATION PREPARATION, AND BACKFILL**

204.01 Description	153
204.02 Classification	153
204.03 Foundation Fill Material	155
204.04 Bedding Material	155
204.05 Reserved.....	155
204.06 Backfill Material	155
204.07 Reserved.....	158
204.08 Excavation	158
204.09 Protection of Excavation.....	160
204.10 Foundation Preparation	161
204.11 Backfilling	163
204.12 Method of Measurement.....	165
204.13 Basis of Payment.....	169

DESCRIPTION

204.01 Description

This work consists of excavation, foundation preparation, and backfill for the installation or construction of bridges, culverts, underdrains, and other structures not otherwise provided for in the Specifications.

This work also includes constructing and subsequently removing all bracing, shoring, cribbing, and cofferdams, all pumping and bailing, backfilling, and disposing of excess or unsuitable material.

204.02 Classification

The Department will classify and pay for Structure Excavation and Foundation Preparation under the following designations:

204.02

A. Culvert Excavation (Unclassified)

Structure Excavation and Foundation Preparation performed within the limits specified in **204.08** and **204.10**, for all box bridges, pipe culverts, sewers, conduits, all other culverts, all minor structures of any type and description, will not be measured and paid for directly but the cost will be incidental to other items, unless otherwise shown on the Plans.

B. Dry Excavation (Bridges)

Structure Excavation and Foundation Preparation performed above the datum line (established by elevation and definitively shown on the Plans) and within the limits specified in **204.08.A** and **204.10.A** and not classified as Rock Excavation (Bridges), as indicated or directed, will be classified and paid for as Dry Excavation (Bridges).

C. Wet Excavation (Bridges)

Structure Excavation and Foundation Preparation performed below the datum line (established by elevation and definitively shown on the Plans) and within the limits specified in **204.08.A** and **204.10.A** and not classified as Rock Excavation (Bridges), as indicated or directed, will be classified and paid for as Wet Excavation (Bridges).

D. Rock Excavation (Bridges)

Structure Excavation and Foundation Preparation performed either above or below the datum line (established by elevation and definitively shown on the Plans) and within the limits specified in **204.08.A** and **204.10.A** and consisting of material which cannot be economically excavated without the use of explosives, also any boulder, slab, or fragment of rock having a volume of not less than 1/2 cubic yards, all Portland cement concrete, all masonry (dry mortar), as indicated or directed, will be classified and paid for as Rock Excavation (Bridges).

Cemented gravel, cemented chert, soft shale, or soft slate, even though requiring the use of explosives for economical excavation, will not be classified as rock.

E. Bridge Excavation (Unclassified)

Bridge Excavation (Unclassified) shall be structure excavation and foundation preparation performed either above or below the datum line

(established by elevation and definitively shown on the Plans) as stipulated in **204.08.A** and **204.10.A** regardless of the nature of the material excavated.

F. Rock Drilling (Bridges)

Rock Drilling includes the drilling or sinking of test holes through or in rock to verify the condition of the foundation.

MATERIALS

204.03 Foundation Fill Material

Material for foundation fill shall consist of suitably graded sand, gravel, slag or stone, as approved by the Engineer.

204.04 Bedding Material

A. Support for Pipe Culverts

For Class A bedding, use Portland Cement Concrete, Class A meeting **604**.

For Class B bedding, use sand or a natural sandy soil, all of which passes a 3/8-inch sieve and not more than 10% passes a No. 200 sieve, or a Type A or Type B Aggregate, Grading C, D, or E meeting **903.05**.

B. Areas Requiring Free Drainage Material

In rock cuts or other areas designated by the Engineer that require a free drainage bedding or backfill material, provide crushed stone, crushed slag, or washed gravel meeting **903.17**.

204.05 Reserved

204.06 Backfill Material

A. General

Material for backfill shall be fine compatible soil selected from structure excavation if approved by the Engineer as being suitable. Obtain

204.06

additional material needed from roadway or borrow excavation as specified in **203**.

Granular Backfill Material for Structures shall be Type A aggregate, Grading D meeting **903.05**.

B. Flowable Fill

If shown on the Plans, place as backfill material a controlled low strength material (CLSM) (flowable fill) at the locations shown on the Plans or as directed by the Engineer.

Materials used in the placement of CLSM shall meet the following requirements:

Portland Cement, Type I.....	901.01
Fine Aggregate.....	903.01
Water.....	921.01
Chemical Admixtures and Additives	921.06
Air Entraining Admixtures	921.06.A.2
Fly Ash, Class C or Class F	921.15
Ground granulated blast furnace slag (GGBFS)	921.16

Submit for approval a proposed mix design for CLSM as specified in **604.03**.

As defined herein, there are three types of CLSM: general use flowable fill, excavatable flowable fill, and early strength flowable fill.

As part of acceptance testing, the Department will determine the consistency of CLSM in accordance with the procedure described below. This method applies to each of the types of CLSM.

- a. Place an inverted slump cone on a smooth, level surface.
- b. Fill the inverted slump cone with a representative sample of the flowable fill without rodding in one lift.
- c. Remove the slump cone by lifting it straight up, thus allowing the sample to diffuse on the smooth, level surface.

- d. The flowable fill should diffuse into a circular shape having an approximate diameter of not less than 15 inches.

Each consistency test will represent up to 100 cubic yards of flowable fill at each installation.

The Engineer may adjust the Specification Limits identified below to obtain the consistency required for satisfactory flow.

1. **General Use Flowable Fill.** When not otherwise shown on the Plans, or specified in the Contract, provide general use flowable fill proportioned to meet the consistency of a 15-inch minimum spread.
2. **Excavatable Flowable Fill (EFF).** If shown on the Plans, design, proportion, and deliver to the Project an EFF that meets the performance requirements specified in Table 204.06-1.

Table 204.06-1: Specification Limits for EFF

Property	Specification Limit
Air content (ASTM D6023)	Maximum 30% ⁽¹⁾
Consistency	15 inches minimum as tested per 204.06.B
Compressive strength (ASTM D4832) ⁽²⁾	30 psi minimum at 28 days 100 psi maximum at 28 days
⁽¹⁾ When using air entrained mixture design	
⁽²⁾ ASTM D4832 4 x 8 inch cylinder molds may be used. The preferred capping method to be used is wetsuit neoprene restrained in rigid retainers.	

The Contractor may adjust the mixture design with the Engineer's approval to obtain the required properties.

3. **Early Strength Flowable Fill (ESFF).** If shown on the Plans, design, proportion, and deliver to the Project ESFF that meets the performance requirements specified in Table 204.06-2.

204.07

Table 204.06-2: Specification Limits for ESFF

Property	Specification Limit
Air content (ASTM D6023)	Maximum 30% ⁽¹⁾
Consistency	15 inches minimum as tested per 204.06.B
Compressive strength (ASTM D4832) ⁽²⁾	30 psi minimum at 24 hours

⁽¹⁾ When using air entrained mixture design.

⁽²⁾ ASTM D4832 4 x 8 inch cylinder molds may be used. The preferred capping method to be used is wetsuit neoprene restrained in rigid retainers.

Include in the proportions of ESFF sufficient amounts of cementitious materials, high range water reducers, accelerators, and other chemical admixtures so the ESFF can be loaded/backfilled as specified.

The Contractor may adjust the mixture design with the Engineer's approval to obtain the required properties.

4. Provide an approved Concrete Daily Report, and furnish the resources, information, and tools that will meet the requirements of **501.03.B**. To produce the desired consistency, the Contractor may use chemical admixtures, air entraining admixtures, or both, at no additional cost to the Department.

204.07 Reserved

CONSTRUCTION REQUIREMENTS

204.08 Excavation

A. Bridges, Box Culverts, and Other Major Structures

Before the start of excavation, the Engineer, or Contractor when required, will set stakes locating and outlining the structure and cross-section for excavation computations.

Before starting excavation, clearly mark the limits of disturbed area and undisturbed area using highly visible markers that are readily visible to project personnel including equipment operators.

Excavate to the lines and elevations shown on the Plans or as directed by the Engineer. The Engineer will allow working variations outside the neat lines; however, the Department will only measure that excavation specified in **204.12** for payment.

Do not deposit or dispose of any excavated materials outside the construction lines unless directed and approved by the Engineer according to the manual *Procedures for Providing Offsite Waste and Borrow on TDOT Construction Projects*.

If solid rock is encountered in roadway cut sections and channel sections under bridges, perform presplitting operations as specified in **203.04.C**. Hole spacing along bridge abutment sites shall not exceed 12 inches. If overshooting of rock beyond the cut sections shown on the bridge plans requires modification of bridge abutments or span lengths, make such modifications at no additional cost to the Department.

Excavate inclined surfaces of rock used as foundation either level or in steps. When necessary to obtain good bond, as determined by the Engineer, roughen the surface of rock foundation or install suitable anchors. Over-excavations that require re-design, increased bridge length, increased quantities, supplemental retaining walls or other earth retaining structures, shall be at no additional cost to the Department.

Remove existing concrete foundations, boulders, or ledge streaks of rock projecting into the bottom of the excavation to a depth of 6 inches below foundation elevation. Backfill and compact the resulting cavity with approved material.

Only excavate below the specified bridge foundation elevations as directed by the Engineer. Replace, at no cost to the Department, all materials moved without such authority by constructing a sub-footing of the same materials as the footing of the structure unit and 6 inches wider on every side.

B. Pipe Culverts

Excavate for pipe culverts as specified in **204.08.A** and as follows:

204.09

1. The width of the pipe trench shall be as shown on the Plans to allow satisfactory joining of the pipe, thorough tamping of the bedding material under and around the pipe, and placement of flowable fill.
2. Remove rock, hardpan, or other unyielding material encountered in the pipe trench to below the foundation grade for a depth of 6 inches, or as directed by the Engineer.

C. Use of Excavated Materials

Use suitable excavated material as backfill or embankment. When disposing of excess or unsuitable material, do not obstruct the stream or otherwise impair the efficiency or appearance of the structure. Deposit excavated material so as not to damage a partly finished structure.

Carefully handle, deposit, and protect excavated materials that will be incorporated in the structure.

In streams, dispose of material according to the laws of the U.S. Government, the requirements in the TN Construction General Permit, and all other applicable environmental permits.

204.09 Protection of Excavation

Protect excavation areas and ensure that the excavation remains intact.

If OSHA regulations require shoring, submit to the Engineer, prior to starting work, computations and drawings, prepared by and stamped by a Professional Engineer licensed in the State of Tennessee, showing the basis for the design.

If using cofferdams or cribs for foundation construction, ensure that they are carried to sufficient depths below the bottom of the footings, are substantially braced in all directions, and are as watertight as necessary for proper performance of the work.

When dewatering work areas, comply with the requirements of the TN Construction General Permit, and do not violate water quality standards. Unless otherwise shown on the Plans, construct cofferdams so that the interior dimensions provide sufficient clearance for the construction and inspection of forms, and to allow for pumping of leakage outside of the footing area. If cofferdams or cribs tilt or move out of position during the process of sinking, right, reset, or enlarge them to provide the necessary clearance at no additional cost to the Department.

Construct cofferdams or cribs to protect the foundation and the construction therein against damage from a rise in the stream.

With the Engineer's written permission, obtained before the start of cofferdam or crib construction, the Contractor may extend timber, or bracing of a cofferdam or crib, into or through the substructure. Do not brace the cofferdams for structure widening off of the existing structure.

Before starting any work, submit drawings to the Engineer, prepared and stamped by a Professional Engineer licensed in the State of Tennessee, showing details of the proposed cofferdam or crib construction. The type and clearance of cofferdams, or cribs, insofar as they affect the finished structure or part thereof, will be subject to the Engineer's approval, but the design and successful construction of cofferdams or cribs is the Contractor's responsibility. Do not begin work in a stream without receipt of the applicable permits from State and Federal agencies. Ensure that cofferdam construction is in accordance with all permit requirements.

Unless otherwise directed, remove cofferdams or cribs, with all falsework, sheeting, bracing, and related appurtenances, after completing the substructure therein, unless otherwise directed. Complete the removal without disturbing or marring the completed work.

If the foundation excavation becomes disturbed or distorted, clean out and restore it to satisfactory condition at no additional cost to the Department.

204.10 Foundation Preparation

A. Bridges, Box Culverts, and Other Major Structures

Prepare foundations for bridges, box culverts, and other major structures according to the following:

1. After completing the foundation preparation to the specified elevation, notify the Engineer and await the Engineer's inspection and approval before resuming construction therein.
2. When directed by the Engineer, unless piles are indicated, test each foundation in the presence of the Engineer by sinking three to six test holes to a depth of between 6 and 10 feet.

204.10

If these test holes reveal unsatisfactory foundation conditions, continue the excavation lower, as directed by the Engineer, and conduct new tests until a satisfactory foundation is obtained.

3. If rock is encountered in the excavation for the foundation, remove loose fragments and debris and notify the Engineer. Drill test holes in the rock as shown on the Plans or as directed by the Engineer to determine the lines of demarcation, the classification, and the stability of the rock. Continue the excavation to the elevation designated by the Engineer. If required by the Engineer, drill test holes and continue excavation until a foundation approved by the Engineer is secured.

Strip and clean rock used as foundation of all overlying materials. Remove all loose, disintegrated, or light slabby portions of the rock.

In rock foundations, if the rock is shattered below the foundation elevation, remove the shattered material and rebuild the resulting space with the same type of construction as the proposed overlying construction, at no additional cost to the Department.

4. If the Plans require driven piles, or if after the foundation excavation has been completed it becomes necessary to reinforce the foundation by driving piles, remove any resulting bulges of the foundation material, at no additional cost to the Department, to the elevation indicated or directed, and bring the foundation to an even surface over its entire area.
5. Remove unsatisfactory material in the foundation and replace with satisfactory material designated by the Engineer. Place the satisfactory material in layers not exceeding 6 inches in loose depth and compact to 100% of maximum density up to the foundation elevation.
6. If pumping from the interior of a foundation enclosure, prevent the possibility of concrete material being carried away. Use a suitable sump located outside the concrete forms to perform any pumping required during the placing of concrete, or for a period of at least 24 hours thereafter. When dewatering work areas, comply with the requirements of the TN Construction General Permit, and do not cause a water quality violation.

7. If conditions make it impracticable to dewater the foundation before placing the footing, the Engineer may allow the Contractor to construct a concrete foundation seal of the dimensions and thickness necessary to resist possible uplift.
 - a. Before pouring the seal, clean the foundation of all objectionable material using sand pumps, spud bars, or other suitable means.
 - b. Construct the seals as specified in **604.18**.
 - c. Allow the seal to set sufficiently to withstand the hydrostatic pressure before starting pumping for dewatering operations.
 - d. Dewater the foundation and thoroughly clean the seal of all laitance and ensure that it is generally prepared for further construction.

B. Pipe Culverts

Bedding and trench installation shall conform to the requirements in the Standard Drawings, Specifications, or the Plans. Pipe Culvert shall be placed into an excavated trench. When existing embankment areas are not available to excavate for a trench, follow guidance in Standard Drawings for induced trench method. Bedding for plastic pipe shall be Class B, Type A or B Aggregate, Grading D or E meeting **903.05**.

If placing bell and spigot pipe, dig recesses in the bedding material of sufficient width and depth to ensure that the bell will not rest on the bottom of the recess. The width of the recess shall not exceed the width of the bell by more than 2 inches. If the class of bedding is not shown, cut a shallow trench in natural ground or compacted embankment to a depth of not less than 10% of the outside vertical pipe diameter, and shape to fit the lower pipe exterior for the specified embedment. If placing bell and spigot pipe culvert, dig recesses in the earth foundation of sufficient width and depth to ensure that the bell will not rest on the bottom of the recess. The width of the recess shall not exceed the width of the bell by more than 2 inches.

204.11 Backfilling

Place all backfill, other than flowable fill, which will become a part of the roadway prisms or their foundations, in layers, and compact to the density as

204.11

specified in **205.04**, Standard Drawings, or the Plans. Place flowable fill, if called for on the Plans, as specified in **204.06.B**.

A. Bridges, Box Culverts, and Other Major Structures

Backfill all excavated areas not occupied by structures with acceptable earth material to the normal ground surface, unless otherwise directed. Place backfill in layers, not more than 6 inches in loose depth for mechanical tamps and 10 inches in loose depth for tamping rollers, on both sides of the structure or around the structure unit, maintaining the layers at equal elevation and thoroughly compacting each layer by tamping with suitable rapid-striking power-driven mechanical tampers or sheepsfoot rollers before placing the succeeding layer.

Place Granular Backfill Material for Structures (Type A, Grading D) meeting **204.06**, so that the compacted depth does not exceed 6 inches per layer. Compact every 6-inch layer to 100% density.

If any part of the structure is to function as a retainer for backfill, such as abutments, retaining walls, wing walls, arches, side walls of box culverts, or minor structures, step the boundary slopes as necessary to prevent wedge action during backfilling.

Do not place backfill against a structure or any section or unit thereof, until the following conditions have been met:

1. Forms have been removed and concrete surfaces have been finished as specified in **604.21** and **604.22**, respectively;
2. Representative specimens of the structural concrete, cured by the same methods and in the same manner as the concrete in the structure, attain a compressive strength of 3,000 psi; and
3. The concrete has been in place a minimum of 7 days, not counting the days of 24 hours each in which the temperature falls below 40 °F, or 21 calendar days, whichever occurs first.

When backfilling behind abutments held at the top by a superstructure, and behind the sidewalls of culverts, bring up backfill simultaneously behind abutments or sidewalls.

Promptly backfill box culverts and bridge ends after the strength requirements have been met, but no longer than 30 days following

strength attainment, and before placing a bridge deck, or as directed by the Engineer.

B. Pipe Culverts

After the bedding has been prepared and the pipe culvert installed; place backfill and embankment uniformly as shown in the Standard Drawings, Specifications, or Plans. Compact material with mechanical tampers to the required density. Above the top of a backfilled trench, place embankment as specified in the applicable section of **205**, except for those requirements related to the induced trench method. Backfill for plastic pipe culvert shall be Class B, Type A or B Aggregate, Grading D or E meeting **903.05**. Use vibratory plate type compactors to achieve required density. Do not use hydrohammer compactors over the top of the pipe culvert. Engineer shall approve compaction equipment.

C. Backfill Material (Flowable Fill)

Place Excavatable Flowable Fill at the locations shown on the Plans or as directed by the Engineer. Cover or otherwise protect the flowable fill while in the plastic state. Do not place embankment or base materials on the flowable fill prior to final set or hardening as determined by the Engineer.

Before placing flowable fill, install pipe and bedding as shown on the Plans and Standard Drawings. Securely brace or anchor all sections of pipe both horizontally and vertically, as required, to prevent movement of the pipe during placement of the flowable fill. Join pipe sections to prevent the influx of flowable fill around the joints. Replace, at no cost to the Department, all pipe or sections of pipe that cannot withstand placement of flowable fill. Make provisions to form up, or provide earthen berms, to prevent the flowable fill from escaping at the ends of the trench and around headwalls.

COMPENSATION

204.12 Method of Measurement

The normal ground surface, as used in this Section, is defined as the bottom of channel excavations when channel excavation is indicated in the contract documents, the template section of the roadway in cuts, or the natural ground surface, whichever is at the lower elevation. When structure excavation is

204.12

required in new embankment, the normal ground surface shall be the planes of the new embankment at the elevation specified or directed for construction in advance of performing the required structure excavation, but in no case shall the normal ground surface be above the planes of the new embankment.

A. Structure Excavation

1. The Department will measure structure excavation by the cubic yards of material in its original position only.
2. The Department will measure excavation necessary to construct box bridges, box culverts, retaining walls or minor structures, including pipe culverts and sewers, as follows:

- a. Unless otherwise shown on the Plans, no allowance will be made for excavation, except that undercutting for these structures made at the direction of the Engineer to remove unsuitable foundation material will be classified and paid under the item for Undercutting, in accordance with **203.10**.
- b. If the Plans provide for direct payment of excavation, the excavation, including undercutting made at the direction of the Engineer to remove unsuitable foundation material, will be classified and paid for as Culvert Excavation (Unclassified) with the following exception:

Excavation within the limits of box bridges, box culverts with a bottom width between the inner faces of the outside walls greater than 14 feet, that is performed above the flow line of the structure, and with a bottom width equal to the distance between the inner faces of the outside walls on a 1:1 slope to the normal ground surface, will be measured and paid for under the item for Channel Excavation (Unclassified).

3. If the Plans provide for direct payment of excavation, the Department will measure the actual volume of material excavated, provided it does not extend beyond the following limits of excavation:
 - a. For box bridges, box culverts, retaining walls or minor structures, including pipe culverts and sewers, the volume of Culvert Excavation (Unclassified) measured will extend horizontally to the vertical planes located 18 inches outside the

neat lines of the section of the structure at foundation elevation, as indicated or directed, and vertically between the normal ground surface and the foundation elevation, as approved. For box bridges and box culverts without bottom slabs, the foundation elevation is considered to be the bottom of footings and the flow line elevation between footings. No allowance will be made for overlapping areas.

- b. Where internal forming is required, as for cut off walls and similar features, the quantity measured will extend horizontally 12 inches outside the neat lines of the completed work and vertically from the foundation elevation to the bottom of the completed excavation.
- c. For pipe culverts, the volume of Culvert Excavation (Unclassified) measured will extend vertically between the normal ground surface and the bottom of the excavation for the pipe, as approved, and horizontally to not beyond two vertical planes separated by a horizontal distance equal to the outside diameter of the pipe plus 3 feet.
- d. Where rock removal is necessary to prepare a satisfactory bed for pipe culverts, the quantity removed will be measured to a depth of 6 inches below the bed of the pipe, as approved. No allowance will be made for the material used in backfilling, except bedding material when specified.
- e. The volume of Dry Excavation (Bridges), Wet Excavation (Bridges), Rock Excavation (Bridges), and Bridge Excavation (Unclassified) measured will extend vertically between the normal ground surface and the bottom of the excavation as approved, and horizontally to the vertical planes located 18 inches outside of the neat lines of the section of the structure at foundation elevation. Where a concrete seal is used, the limits of excavation will not extend beyond the neat lines of the concrete seal, as specified or as directed by the Engineer.
- f. For excavation necessary to form struts, diaphragms, beams, and similar features, the volume measured will extend vertically between the normal ground surface and a horizontal plane located 12 inches below the members, and horizontally to the vertical planes located 18 inches beyond the limits of the members.

204.12

4. No increase or decrease in payment will be allowed for changes in amount of excavation due to the shifting of location of structures from that shown on the Plans or for the addition of structures to those shown on the Plans when the Plans do not indicate that direct payment will be made for this excavation. Further, if this area of excavation, namely 18 inches horizontally outside of the neat line of the structure at foundation elevation, overlaps an area in which the excavation is computed on a separate unit price, the excavation in the overlapping area will not be allowed.
5. The Department will measure extra excavation below foundation elevation, as shown on the Plans or as directed by the Engineer, if due to causes not attributable to the Contractor's actions.

In computing extra depth excavation, the working limits established herein will be adhered to.

6. No allowance will be made for shaping necessary to accommodate the bells of the pipe.
7. The Department will measure Rock Drilling performed as specified in **204.10.A** by the linear foot.

B. Protection of Excavation

1. If items for cofferdams or cribs for individual piers or bents are provided by the Plans, the Department will measure this work in individual lump sum items for the pier or bent designated.
2. If a bid item for sheet piles is provided on the Plans, the Department will measure and pay as specified. If payment for the sheet piles is by the square foot, the Department will measure based on the as-designed sheet pile length to retain and counteract lateral earth forces, plus 1 foot.

C. Bedding and Backfill

1. If payment for bedding is provided on the Plans, the Department will determine the volumes of Class A and Class B bedding based on the theoretical quantity, in cubic yards per foot of pipe, as shown on the Standard Drawings or Plans.

2. The Department will measure Backfill Material (Flowable Fill) based on the theoretical quantity in cubic yards, as shown on the Standard Drawings. Measurement will be made along the centerline of the pipe for the width of trench shown on the Plans.
3. Material used to replace approved undercutting for box bridges, box culverts, retaining walls or minor structures, including pipe culverts and sewers, will be paid under the item for Foundation Fill Material, and the measurement will be the same quantity as the approved undercutting it replaces.

The Department will not measure for payment:

1. Materials moved from their original position before being measured by the Engineer;
2. Slides, cave-ins, and excavation extending outside of the workable limits;
3. Removal of foundation material that has bulged due to driving piles;
4. Excavation above the normal ground surface, unless otherwise shown on the Plans;
5. Water and its removal; and
6. Construction and/or removal of cofferdams, cribs, sheet piles, or other protective measures provided to safeguard an excavation, unless otherwise shown on the Plans.

204.13 Basis of Payment

If provided for on the Plans, the Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Culvert Excavation (Unclassified)	Cubic Yard
Dry Excavation (Bridges)	Cubic Yard
Wet Excavation (Bridges)	Cubic Yard
Rock Excavation (Bridges)	Cubic Yard
Bridge Excavation (Unclassified)	Cubic Yard

204.13

Extra Depth Structure Excavation and Foundation Preparation	Cubic Yard
Rock Drilling (Bridges)	Linear Foot
Bedding Material (Pipe) Class A	Cubic Yard
Bedding Material (Pipe) Class B	Cubic Yard
Cofferdam	Lump Sum
Foundation Preparation	Lump Sum
Backfill Material (Flowable Fill)	Cubic Yard

Such payment is full compensation for providing all materials, equipment, labor, and incidentals to complete the work as specified, including performing embankment construction, sloping, shaping, dressing, disposal of excess or unsuitable material, and final cleanup.

The Department will pay for Structure Excavation and Foundation Preparation of the various classes based on the volume computed in accordance with **204.12**.

A. Extra Depth Structure Excavation and Foundation Preparation

The Department will pay for Extra Depth Structure Excavation and Foundation Preparation, classified as Culvert Excavation (Unclassified), made necessary by the Engineer establishing the foundation below the elevation shown on the Plans, at the contract unit price per cubic yard for Culvert Excavation (Unclassified).

Extra Depth Structure Excavation and Foundation Preparation for bridges made necessary by the Engineer requiring excavation below the foundation elevation shown on the Plans, will be paid for at the contract price per cubic yard for Dry Excavation (Bridges), Wet Excavation (Bridges), Rock Excavation (Bridges), as classified for the actual quantity in cubic yards, excavated from the designated zone, this zone being between the elevation shown on the Plans and the final approved elevation, as directed by the Engineer, plus the additional percentages for each zone corresponding to the depths lowered below Plan elevation as specified in Table 204.13-1.

Table 204.13-1: Designated Zone for Extra Depth Structure Excavation

Sub-Item Designation	Zone No.	Depth Lowered below Plan Elevation		
		More than (ft)	Additional Not Over (ft)	Percent
None	0	0	4	0
a	1	4	8	50
b	2	8		80

Using Table 204.13-1, the Department will compute the volumes of material for payment under any sub-item based on the depths applicable to each zone between the foundation elevation as shown on the Plans and the final foundation elevation as approved by the Engineer. For example: If the foundation were lowered 7-1/2 feet below the foundation elevation shown on the Plans, the Department will compute the volume for the sub-item for a depth of 3-1/2 feet and multiplied by the contract unit price for the class of material excavated plus 50%. The volume of material down to a level 4 feet below the foundation elevation shown on the Plans will be paid for at the contract unit price for the class of material excavated.

B. Cofferdams or Cribs

If items for cofferdams or cribs have been provided for and installed for a designated pier or bent, the lump sum item is full compensation for the furnishing and installation of all material, maintenance, removal, and satisfactory cleanup of the area, and for all tools, equipment, labor, and incidentals necessary to complete the work. Concrete seal shall also be included, except when otherwise shown on the Plans, in which case, measurement and payment for concrete foundation seal will be as provided for under **604.30** and **604.31**.

C. Foundation Preparation

1. Unless otherwise shown on the Plans, no direct payment will be made for Foundation Preparation and Backfill.
2. If Foundation Preparation is a separate pay item, the lump sum price is full compensation for the preparation of foundations for all substructures. The cost for cofferdams, shoring, pumping, or seal concrete required to establish the approved footing shall be

204.13

incidental to the lump sum bid for Foundation Preparation, except payment will be made at 40% of the price bid for the footing concrete when approved by the Engineer:

- a. For leveling placed within the neat lines of the bottom of the footing, where permitted, and
 - b. For additional seal concrete required by changes directed by the Engineer. Payment will be made only for the additional seal concrete placed within vertical planes located 18 inches horizontally outside of the neat lines of the bottom of the footing. No payment of seal concrete will be made for any depth the seal is embedded in sound material below the elevation of the bottom of the pier footing as shown on the Plans to allow placement of an adequate seal.
3. The Department will not allow a percentage increase for extra depth excavation required for the foundation preparation.
 4. Unless otherwise provided, the Department will not pay for the sinking of test holes to test foundations.

D. Backfill Material (Flowable Fill)

Payment for Excavatable Flowable Fill as backfill material for pipe will be included in the unit price paid for pipe unless otherwise shown on the Plans.

E. Backfill and Bedding Material

Payment for granular backfill and concrete or aggregate bedding material will be included in the unit price paid for pipe unless otherwise shown on the Plans.

The Department will not pay for: material moved before it has been measured by the Engineer; material specified to be moved under **203**; slides or cave-ins occurring outside of the working limits specified in **204.08** and **204.10**; material excavated outside of said working limits; material excavated, even though within the said working limits, below foundation elevation, as indicated or directed, and made necessary on account of the construction methods of the Contractor, or its failure to provide sufficient or proper protection; presplitting of rock; material excavated below foundation when shooting; bulged material caused by driving piles in a foundation; water and

204.13

its removal; and in general, material moved which would have been unnecessary to move to complete the structure in accordance with the Plans, these Specifications, or the directions of the Engineer.

205.01

SECTION 205 – EMBANKMENTS

205.01 Description 174

205.02 Materials 174

205.03 Preparation of Embankment Areas 174

205.04 Formation of Embankments 176

205.05 Stability of Embankments and Cut Slopes 179

205.06 Disposal of Excess or Unsuitable Material 180

205.07 Method of Measurement 180

205.08 Basis of Payment..... 180

DESCRIPTION

205.01 Description

This work consists of constructing roadway embankments, including preparing the area upon which they are to be placed; constructing dikes within or outside the right-of-way; placing and compacting approved material within roadway areas where unsuitable material has been removed; and placing and compacting embankment material in holes, pits, and other depressions within the roadway area.

MATERIALS

205.02 Materials

For embankment and backfill, only use approved materials, consisting of Road and Drainage Excavation, Channel Excavation, and Borrow Excavation material as specified in **203**, or excess material as specified in **204**.

CONSTRUCTION REQUIREMENTS

205.03 Preparation of Embankment Areas

Before beginning embankment construction in any area, complete Clearing and Grubbing, Removal of Structures and Obstructions, and installation of preliminary erosion control measures according to the approved SWPPP as specified in **201**, **202**, and **209** respectively.

Address both natural and created steep slope areas as required in the TN Construction General Permit. Maintain and stabilize steep slopes according to the TN Construction General Permit and all applicable environmental permits.

Remove snow, ice, and mud before placing embankment materials on the ground. Do not place embankment materials on top of ground surfaces and existing embankment layers that are frozen.

Fill all depressions or holes below the natural ground surface, whether caused by grubbing or otherwise, with suitable material and compact to the ground surface before starting embankment construction.

Unless otherwise shown on the Plans or specified in the Special Provisions, if constructing embankment of less than 3 feet below subgrade:

1. Remove all sod and vegetative matter from the surface.
2. Remove unsuitable material and replace with suitable material.
3. Break up the cleared surface by plowing, scarifying, or stripping to a minimum depth of 6 inches, and then re-compact this area.
4. If a compacted road surface containing granular materials lies within 3 feet of the subgrade, scarify the old road surface to a depth of at least 6 inches, and then re-compact the scarified material.

Remove and dispose of concrete pavement, parking strip, and base, all with or without bituminous overlay, concrete curb and gutter, sidewalk, driveways, and similar features as specified in **202.06** or as otherwise directed by the Engineer.

When placing embankment material on or against existing slopes that are steeper than 4:1, cut benches into the existing slope while bringing up the new embankment material in layers. Cut each bench of sufficient width to accommodate the operation of placing and compacting equipment. Begin each successive cut at the intersection of the original ground and the vertical side of the previous cut. Re-compact the cut material along with the new embankment material at no additional cost to the Department.

Before placing embankment material on a structure or any unit of a structure, ensure that the surrounding backfill has been completed and thoroughly compacted to ground surface.

205.04

205.04 Formation of Embankments

Do not incorporate or bury any perishable materials, such as brush, hedge, roots, stumps, and parts of trees, in the embankments. Do not place rock, broken concrete, or other solid objects in embankments areas where piling will be installed.

Construct embankments to provide adequate surface drainage at all times. If roadway embankment materials consist predominantly of soil, place the material in horizontal layers not to exceed 10 inches in loose thickness, and compact each layer to a density not less than 95% of maximum density. Unless otherwise specified, compact the top 6 inches of the roadbed in both cut and fill sections to 100% of maximum density as specified in **207.04**. The Department inspector conducting the density tests shall be a certified Nuclear Gauge Technician.

The Engineer will determine maximum density and optimum moisture according to AASHTO T 99. For material with less than 5% retained on a No. 4 sieve, method A with 4-inch mold will be used. For material with more than 5% retained on a No. 4 sieve but less than 50% retained on a 3/4-inch sieve, Method D with corrections according to AASHTO T 224 will be used.

Use the correction on soils containing less than 50% plus 3/4-inch material.

Determine the density of the soil in place according to an approved AASHTO method. Compact each embankment layer to the required density, and obtain the Engineer's approval before placing material for the next succeeding layer. Keep placing and compacting areas separate.

When constructing embankment across low swampy ground that will not support earth moving equipment, construct the lower part of the fill in a uniformly distributed layer of a thickness not greater than necessary to support the hauling equipment while placing subsequent layers. Construct the embankment full width unless otherwise shown on the Plans or approved by the Engineer. The Engineer will waive the density requirement for such a lift, but the moisture content of the material used shall not exceed the optimum moisture range for 95% density for that material. Comply with the maximum thickness and minimum density requirements for all succeeding layers of the embankment.

When a minimum of 95% of maximum density is required, ensure that the moisture content of the material being compacted meets both of the following conditions:

1. The moisture content shall be within the range of values at which 95% of the maximum density can be obtained as indicated by the moisture-density relationship curve; and
2. The moisture content shall not exceed the optimum moisture content to the extent that the material pumps under loads applied by the construction equipment.

Even if the required density is achieved and the moisture content is in range, if pumping occurs, remove the affected sections.

When 100% of maximum density is required, the moisture content of the material being compacted shall meet condition (2) above and shall not vary from the optimum moisture content by more than plus or minus 3%.

Aerate the material, or distribute and incorporate water uniformly into the material, as necessary, to control the moisture content within the applicable limits.

If the excavated material consists predominantly of rock, the following shall apply:

A. Definition of Material

If deemed necessary by the Engineer, the Contractor shall conduct test or tests with a 60,000-pound static tamping foot roller (costs to be included in other items) to determine whether the material is degradable or non-degradable. Consider material that readily breaks down under three passes of the 60,000-pound static tamping foot roller as degradable.

B. Non-Degradable Rock

If sound, non-degradable rock is encountered in the unclassified excavation, the Engineer may require the Contractor to provide a mechanical means for separating the sound rock from degradable rock and other soils. The Engineer may allow the use of sound, non-degradable rock in the backfilling of benches, lower and outside portions of embankments, rock buttresses, or other areas.

If the material for embankments consists of sound, non-degradable rock of a size that makes placing the material in 10-inch layers impracticable, place the material in layers no thicker than 3 feet. Do not use rock fragments greater than 2 feet in maximum dimension. With the

205.04

Engineer's approval, the Contractor may place occasional individual rocks and boulders not exceeding 4 feet in height in the exterior portions of the embankment next to the slope face. Place such rocks to prevent nesting and fill the adjacent voids with fine fragments to form a dense and compact mass.

Do not dump rock material into its final position. Place rock by blading or dozing in a manner that will minimize voids, pockets, and bridging. Ensure that each layer is leveled the full width of the embankment. Rolling is not required if the rock embankment consists of sound, non-degradable material placed in greater than 10-inch layers.

C. Degradable Rock

Compact degradable rock for use in embankment with an approved vibratory tamping-foot roller in conjunction with a static tamping-foot roller. The minimum weight for the static tamping-foot roller shall be 60,000 pounds. The minimum compaction effort, as rated by the manufacturer, for the vibratory tamping-foot roller shall be 55,000 pounds. Submit roller specifications to the Engineer for approval before use.

Place degradable rock in 10-inch maximum loose lifts and provide a minimum of three passes with the static roller and two passes with the vibratory roller. The Engineer may direct additional passes with either or both rollers until satisfactory breakdown and compaction is accomplished. Do not place degradable rock in the top 5 feet of an embankment unless approved by the Engineer.

If embankment composed of degradable rock does not contain sufficient moisture to compact properly, the Engineer will require the Contractor to apply water in sufficient quantities to achieve the approximate optimum moisture for the particular material involved. Uniformly mix the added water with the material for the entire depth of the lift by blading, discing, or other approved methods.

D. Combination of Degradable and Non-Degradable Rock

Do not blend or combine degradable rock and non-degradable rock in a common lift without the Engineer's written approval.

If approved, place embankment material consisting of a mixture of degradable rock and non-degradable rock, or rock and soil, in layers not

exceeding 10 inches in thickness unless otherwise directed by the Engineer. If the combined material is predominantly sound, non-degradable rock with fragments thicker than 10 inches, the Engineer may increase the layer thickness to be consistent with the size of the material, not to exceed 3 feet. Place the mixture by blading or dozing in a manner that will minimize voids, pockets, and bridging. Compact the mixture with suitable compaction equipment as defined in **205.04.A**, and apply water to facilitate compaction as directed by the Engineer. Uniformly mix the added water with the material for the entire depth of the lift by blading, discing, or other approved methods.

E. Density Requirements

Density requirements will not apply to portions of embankments constructed of materials that cannot be tested by approved methods.

When the Plans require Solid Rock Fill, the material shall meet the quality requirements in **903.25**. Do not use plastic soil or shale material. Place Solid Rock Fill as shown on the Plans or as directed by the Engineer.

Construct the roadway through rock fills to the grading line shown on the Plans with an allowable working tolerance of plus 1 to minus 3 inches. Bring up to grade those portions of the roadway that are then below grade with spalls or other suitable granular material that is available from the excavation within the balance. If no such excavation is available, the Engineer may direct the Contractor to use approved base material for bringing the fill to grade, not to exceed the specified 3-inch limit.

If embankment material is to be placed on both sides of a concrete wall or box type structure, bring the material up equally on both sides of the structure.

At the location of abutments, bents, and similar features, construct embankment to the finished grade before starting excavation on the respective section of the substructure, unless otherwise shown on the Plans. If embankment material is to be placed on only one side of abutments, wing walls, piers, and similar features, do not begin construction until the superstructure is in place. Perform compaction operations without causing wedge action or placing excessive pressure against the structure.

205.05 Stability of Embankments and Cut Slopes

Assume responsibility for the stability of all embankments and cut slopes until final acceptance. In accordance with **105.16** and as determined by the

205.06

Engineer, replace or rework all portions that have become displaced or damaged at no additional cost to the Department.

205.06 Disposal of Excess or Unsuitable Material

Dispose of excess or unsuitable material as specified in **203.07**.

COMPENSATION

205.07 Method of Measurement

The Department will not measure embankment. The Contractor shall construct embankments under the items described in **203** and **204** that apply to the materials used to construct the embankments.

The Department will measure excavation to bench side-hill slopes for embankment construction in accordance with **203.09.A.2**.

205.08 Basis of Payment

The Department will not directly pay for embankments. The contract unit prices for the materials with which embankments are acceptably constructed is full compensation for all embankment construction, including materials, equipment, labor, and incidentals to complete the work as specified.

If the Contractor encounters pumping of soil despite having achieved the required density and moisture content, the Department will pay for the removal of these sections as Undercutting by the cubic yard in cut sections only. No such payment will be made in fill sections.

If the excavated material consists predominantly of rock, the Department will pay for water required and provided by the Contractor to facilitate compaction at the unit price per M.G. (1,000 gallons) for Water, which price is full compensation for furnishing and applying the water, mixing, labor, and equipment. The Department will consider all other costs associated with the constructing embankment of material consisting predominantly of rock, including providing suitable compaction equipment and separating sound rock from degradable rock and soils, as included in the unit price for Road and Drainage Excavation (Unclassified).

If the Engineer directs the Contractor to use approved base material to bring portions of the roadway that are less than 3 inches below grade up to grade,

205.08

the Department will measure and pay for the furnishing and placing of such base material in tons under the applicable item in **303.15**. If base material is not a bid item in the Contract, the Contractor shall provide the material under the provisions of **104.02.D**.

If, despite proper construction and protection, damage to the embankments or cut slopes occurs due to unusual natural causes such as cloudbursts, floods, slides or subsidence, the Department will pay for the material used to make the necessary repairs at the contract unit price for the material classification designated by the Engineer to be used for this purpose. The Department will pay for removal of slides in accordance with **203.10**.

206.01

SECTION 206 – FINAL DRESSING

206.01 Description 182
 206.02 Reserved..... 182
 206.03 Method and Scope of Work 182

DESCRIPTION

206.01 Description

This work consists of dressing all slopes and areas, including borrow pits and embankments, and generally preparing the Project for final inspection and acceptance. The costs of this work are incidental to other items of construction.

206.02 Reserved

CONSTRUCTION REQUIREMENTS

206.03 Method and Scope of Work

Perform final dressing by hand work and machines to produce a uniform satisfactory finish to all parts of the roadway and other components of the Project. Shape the roadbed, shoulders, ditches, and slopes to within reasonably close conformity to the specified lines, grades, and cross-sections. Dress spoil banks, borrow areas, waste areas, and similar areas. Clear rock cuts of all loose fragments, and leave in a neat, safe, and workmanlike condition.

Clean the right-of-way of all weeds, briars, and brushes unless otherwise shown on the Plans. Clear and clean all structures, both old and new, of all brush, drifts, heavy vegetation, sediment, rubbish, obstructions, and other objectionable material.

Perform final dressing before sodding and seeding operations if the Contract includes these construction items.

Run tracked machines used in dressing slopes up and down slopes as opposed to longitudinally.

SECTION 207 – SUBGRADE CONSTRUCTION AND PREPARATION

207.01 Description.....	183
207.02 Reserved.....	183
207.03 Preparing Subgrade.....	183
207.04 Compacting Subgrade.....	184
207.05 Drainage and Protection.....	184
207.06 Checking Subgrade.....	185
207.07 Disposal of Excess or Unsuitable Material.....	185
207.08 Method of Measurement.....	185
207.09 Basis of Payment.....	186

DESCRIPTION

207.01 Description

This work consists of constructing and preparing part of or all the roadbed to a condition suitable for supporting the immediate construction of a base or pavement.

207.02 Reserved

CONSTRUCTION REQUIREMENTS

207.03 Preparing Subgrade

Perform Excavation and Undercutting as specified in **203**.

Where the roadbed is below grade, haul, spread, and compact, as specified in **205**, suitable material in sufficient quantity to bring the roadbed to grade.

Where the roadbed has been seeded for erosion protection or has established vegetative growth, clip the roadbed to remove vegetation and other deleterious material before placing the base or subbase material. Correct depressions resulting from the removal of deleterious material by hauling, spreading, and compacting suitable material as specified in **205**.

207.04

Where subbases are to be constructed on the subgrade, extend the limits of subgrade preparation across the entire section that will receive the subbase course, including the shoulders.

Where forms are required to construct base or pavement, prepare the subgrade 12 inches wider, on each side, than the neat width of the base or pavement.

207.04 Compacting Subgrade

On subgrades that require reworking, remove all vegetation within the limits of subgrade preparation, and dispose of this material as directed by the Engineer before beginning reworking and re-compacting operations.

The density of the finished subgrade shall not be less than 100% of the maximum density. The optimum moisture, maximum density, and density of the soil in place will be determined in accordance with **205.04**. If field tests show failure to meet the density requirement, loosen the subgrade by discing, harrowing, or other approved methods to a depth of not less than 6 inches, then reshape and re-compact the subgrade material as specified in **205.04**. Moisten or aerate the subgrade material as necessary during mixing and compacting to provide optimum moisture content as specified in **205.04**.

Rework, or remove and replace, all soft, yielding material that will not compact readily, and compact the replacement material as specified in **205**.

207.05 Drainage and Protection

Grade the subgrade to provide for ready drainage of water from the subgrade. Maintain ditches and drains to provide proper drainage during the construction.

Take all precautions necessary to protect the subgrade from damage. Limit hauling over the finished subgrade to that which is essential for construction purposes.

Correct ruts or rough places that develop in a completed subgrade and re-compact as necessary.

207.06 Checking Subgrade

Check the lines, cross-sections, and grades of the subgrade as completed to ensure they are in reasonably close conformity with those shown on the Plans for the bottom of subbase, base, or pavement, or with those established by the direction of the Engineer.

Construct the subgrade to the grading line shown on the Plans, with an allowable working tolerance of plus or minus 1 inch.

Recheck the subgrade as specified in the respective sections governing construction of the particular type of base and pavement.

207.07 Disposal of Excess or Unsuitable Material

Dispose of excess or unsuitable material as specified in **203.07**.

COMPENSATION**207.08 Method of Measurement**

The Department will measure items of construction as follows:

1. Subgrade Construction and Preparation will be measured by the station (100 feet) along the median centerline of the Project for divided sections, and along the centerline of the pavement for 2-lane and other undivided sections, excluding bridges.
2. The volume of excess or additional material moved, or of unsuitable material removed, will be measured in cubic yards by the cross-section method, or if that method is unfeasible, by some other method, with the volume computed for payment in accordance with **109**.
 - a. If grading has been performed under a previous Contract, the Department will measure the number of cubic yards of unsuitable material below subgrade elevation, acceptably removed and disposed of, in both cut and fill sections under the item for Road and Drainage Excavation (Unclassified) in accordance with **203.09.A**.

207.09

- b. If grading is included in the Contract, the Department will measure the number of cubic yards of unsuitable material below subgrade elevation in cut sections, acceptably removed and disposed of, under the item for Undercutting in accordance with **203.09.E**. In the subgrade of embankment sections, the Department will not measure the removal and disposal of excess or unsuitable material for payment.
3. Water required for compaction by the M.G. (1,000 gallons) will be measured using calibrated tanks or distributors, or accurate water meters.

207.09 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Subgrade Construction and Preparation	Station

Payment for Subgrade Construction and Preparation per 100-foot station is full compensation for shaping and compacting the roadbed, all ramps, service roads, approaches, roadside rest areas, and similar features, as shown on the Plans. If the material to be placed or removed does not exceed a depth of 3 inches, this payment also includes the moving or furnishing of all additional material required, or the disposal of excess material. If a depth of 3 inches is exceeded, the Department will pay for the total quantity of material removed or placed at the appropriate contract unit price per cubic yard for Borrow Excavation (Unclassified) or Road and Drainage Excavation (Unclassified), as provided in **203**.

If the Contract includes the construction of the combined grading, drainage, and pavement structure, the Department will consider the construction and preparation of the subgrade as incidental to the construction and preparation of the road, and the material moved will be classified and included in the computation of pay items provided in **203**.

If the Contract provides for the construction of a subbase, base, or pavement on a road that has been graded under a previous contract, and the item for Subgrade Construction and Preparation is included in the Contract, the Department will pay for this item at the contract unit price per 100-foot station. Payment for material moved will be subject to the stipulations set forth above.

207.09

Unless otherwise shown on the Plans, the Department will consider clipping of a roadbed that has been seeded as incidental to other items of construction.

The Department will pay for Water applied as directed by the Engineer at the contract unit price per M.G. (1,000 gallons), as provided in **203**.

208.01

SECTION 208 – SHOULDERS AND DITCHES

208.01 Description	188
208.02 Materials	188
208.03 Equipment	188
208.04 General	189
208.05 Final Cleanup	189
208.06 Method of Measurement	189
208.07 Basis of Payment	189

DESCRIPTION

208.01 Description

This work consists of constructing shoulders and ditches adjacent to both sides of the base or pavement to obtain proper drainage.

MATERIALS

208.02 Materials

The Contractor may obtain material for constructing shoulders as approved by the Engineer. Provide additional material, if required, from approved sources.

EQUIPMENT

208.03 Equipment

The Contractor may perform compaction operations using any type roller that will produce the required results.

CONSTRUCTION REQUIREMENTS

208.04 General

While constructing shoulders, protect the surface and edges of pavement. Do not start shoulder work until the pavement has developed effective resistance to damage.

Complete shoulder construction by blading, moistening as may be necessary, and thoroughly compacting. After completion, maintain the shoulders with respect to lines, grades, and cross-sections until final acceptance of the Project.

208.05 Final Cleanup

Perform Final Dressing as specified in **206**.

Dispose of excess or unsuitable material as specified in **203.07**.

Perform final cleanup as specified in **104.10**.

COMPENSATION

208.06 Method of Measurement

The Department will measure:

1. Shoulder and ditch construction by the mile along each respective shoulder and/or ditch constructed or reworked;
2. Material required in excess of that obtained by cleaning outside ditches by taking cross-sections of the approved borrow pit or pits before and after removal of the material; and
3. Water by the M.G. (1,000 gallons) using calibrated tanks or distributors, or accurate water meters.

208.07 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

208.07

<i>Item</i>	<i>Pay Unit</i>
Shoulders and Ditches	Linear Mile

The Department will pay for material required in excess of that obtained by cleaning outside ditches at the contract unit price per cubic yard for Borrow Excavation (Unclassified).

The Department will pay for water applied as directed by the Engineer at the contract unit price per M.G. (1,000 gallons).

SECTION 209 – PROJECT EROSION PREVENTION AND SEDIMENT CONTROL

209.01 Description.....	191
209.02 Classification	191
209.03 Reserved.....	192
209.04 Project Review	192
209.05 Preconstruction Conference	192
209.06 Construction Requirements.....	193
209.07 Construction of Structures	196
209.08 Method of Measurement	206
209.09 Basis of Payment.....	207

DESCRIPTION

209.01 Description

This work consists of implementing temporary and permanent best management practices (BMPs) to prevent erosion and control sediment through the use of structural and non-structural controls.

Implement erosion prevention and sediment control (EPSC) measures during all phases of construction. Ensure that all EPSC measures shown on the Stormwater Pollution Prevention Plan (SWPPP) are in place before beginning soil disturbing activities.

Comply with all provisions of the SWPPP, noting that additional EPSC measures beyond those shown in the SWPPP may be needed to maintain compliance with permits.

209.02 Classification

The Department will classify structural and non-structural BMPs according to the manual for *Management of Storm Water Discharges Associated with Construction Activities*.

BMPs are structural and non-structural controls required for the Project. Implement BMPs according to the more restrictive of the TN Construction General Permit, the manual for *Management of Storm Water Discharges*

209.03

Associated with Construction Activities, the project SWPPP, and Roadway Standard Drawings.

209.03 Reserved

CONSTRUCTION REQUIREMENTS

209.04 Project Review

At the preconstruction conference, discuss with the Engineer the potential problems with implementing EPSC measures due to construction activities, as well as the actions to be taken to prevent such problems. If the Contractor's operations and construction staging differ significantly from the Project SWPPP, propose modifications to the SWPPP, as specified in **209.05**, that do not conflict with the requirements of the TN Construction General Permit, the conditions of any ARAP for the Project, and other environmental permits. Comply with all provisions of the SWPPP during the term of the Contract.

If a waste or borrow area is needed, prepare a Waste and Borrow Plan according to the manual *Procedures for Providing Offsite Waste and Borrow on TDOT Construction Projects*.

209.05 Preconstruction Conference

The Department will hold a preconstruction conference for every project. For sites that have environmental permits, the Department will also hold an environmental preconstruction conference. These conferences may be held jointly or separately, as determined by the Engineer.

At the preconstruction conference, submit for approval a phasing plan that identifies:

1. All areas within the right-of-way designated for clearing and grubbing, grading, bridges and other structures at water courses, paving, and incidental construction activities; and
2. Areas outside the right-of-way that will be disturbed by the construction such as waste and borrow areas (which must have an approved Waste and Borrow Plan and be properly permitted), haul roads, utilities, and staging areas, and utility work in general.

If the phasing plan requires additional EPSC measures, or modifications to the existing SWPPP, submit these modifications to the Engineer for discussion during the preconstruction conference. The modifications shall incorporate and supplement, as applicable, the basic control devices shown on the Plans to provide acceptable temporary and permanent EPSC measures during all stages of construction as well as to comply with all applicable environmental permit conditions. The modifications shall also include controls for managing and stabilizing natural and created steep slope areas as defined in the TN Construction General Permit. Do not begin work until the Engineer has accepted the erosion prevention and sediment control plan, including the phasing of temporary and permanent erosion control measures. Rejection of all or part of the plan is not a basis for an extension of contract time.

Discuss with the Engineer how utilities will be managed on the Project, specifically whether or not the utilities are within the construction contract. Coordinate a start date for utilities with the Engineer if utility work will begin before the Project start date. Unless approved in advance by the Engineer, utilities that are within the construction contract cannot begin construction on the Project until the Engineer has approved the work.

Update the EPSC plan as work progresses to show changes due to revisions in work schedules or sequence of construction, or when directed by the Engineer. Install additional measures in the field as needed to manage erosion and sediment and to prevent pollutants from discharging into waters of the State or off the Project.

The environmental preconstruction conference will include a review of the Project's environmental permits and all additional environmental commitments required for the Project. This meeting will address the required marking of clearing limits and the marking of sensitive environmental areas in accordance with applicable environmental permits. Discuss potential problems with implementing the requirements of any environmental permits due to construction activities, as well as actions to be taken to prevent conflicts between environmental permits and construction activities.

209.06 Construction Requirements

Mark the disturbed area limits and environmental boundaries in the field before starting construction in each section or portion of the Project. Before or simultaneously with clearing and grubbing operations, install EPSC devices according to the approved SWPPP. Such work may involve the construction of temporary berms, dams, silt fences, sediment basins, lined

209.06

channels, permanent cut-off ditches, slope drains, or other control devices as necessary to prevent and control erosion.

Do not pump water from cofferdams or other dewatering activities directly into streams. Pump such water into sediment basins, traps, or filter bags, or otherwise adequately treat before discharging. Do not start grading operations until the EPSC devices are in place to the satisfaction of the Engineer. If adequate controls are in place, the Contractor may clear and grub areas to be graded according to the TN Construction General Permit before starting grading operations. Protect stockpiled topsoil or fill material to prevent sediment runoff from contaminating surrounding areas or entering nearby streams. To reduce sediment in runoff, promptly install EPSC structures during all construction phases and maintain these measures until the areas they are serving have been permanently stabilized.

Identify both natural and created steep slope areas as defined in the TN Construction General Permit. Ensure the SWPPP is updated to reflect all steep slope areas. Manage and stabilize steep slopes according to the TN Construction General Permit and other applicable environmental permits.

Stage construction operations so that graded or otherwise disturbed erodible surfaces remain protected as the Work progresses. Once started, complete grading of roadway cuts or embankments as a continuous, viable operation to subgrade elevation, unless otherwise approved in writing by the Engineer. As grading operations progress, perform final dressing, place topsoil, and protect exposed erodible cut or embankment slopes with permanent seeding, sodding, matting, or other acceptable EPSC measures in vertical increments not exceeding 25 feet. Do not allow any portion of these slopes to remain unprotected longer than allowed by the TN Construction General Permit unless the Engineer determines that weather conditions or other special circumstances prevent prompt placement of permanent control measures. Implement temporary erosion control measures as directed by the Engineer.

Perform seeding, sodding, matting, or other acceptable EPSC operations within 48 hours of the occurrence of either of the following:

1. Each 25-foot vertical increment is graded, or
2. Upon suspension or completion of grading operations in a specific area.

The above requirements for progressive erosion prevention and sediment control also apply to graded areas off the right-of-way, such as waste areas, borrow areas, and haul roads. Develop a Borrow and Waste Plan for all waste

or borrow areas selected according to the Statewide Storm Water Management Plan and the manual *Procedures for Providing Offsite Waste and Borrow on TDOT Construction Projects*.

Incorporate all permanent EPSC practices into the Project as soon as practicable and in accordance with the TN Construction General Permit. To the extent practicable, coordinate temporary and permanent erosion prevention and sediment control work. Use temporary EPSC features to control erosive conditions before permanent control features can be installed or to temporarily control erosion that develops during construction, but which is not associated with permanent control features on the Project. Perform temporary stabilization of disturbed areas according to the TN Construction General Permit.

Where construction activities cross or border areas of depression (i.e., sinkholes without openings or open throats), install and maintain EPSC measures as shown on the Plans and as required by the TN Construction General Permit and all other applicable environmental permits. If construction activities encounter an open throated sinkhole (Class V Injection Well), immediately notify the Engineer and implement the applicable measures as described in the approved SWPPP. Prevent silt or other potential pollutants from entering the sinkhole opening.

Remove temporary EPSC measures when no longer needed or permanent control measures are installed. Any materials removed shall become the property of the Contractor.

Inspect EPSC measures on a regular basis. Remove accumulated sediment and maintain the structural components of the EPSC measures as necessary to ensure that they continue to function properly. Repair EPSC measures damaged by the Contractor's sediment removal operations at no additional cost to the Department. Upon complete removal of sediment traps, special ditches, and similar structures, restore the area upon which they were constructed by placing topsoil, seed, and mulch, or otherwise stabilizing.

If temporary EPSC measures are required due to the Contractor's negligence, carelessness, or failure to install permanent controls as a part of work as scheduled, and are ordered by the Engineer, perform such work at no additional cost to the Department.

If there is a conflict between these requirements, the TN Construction General Permit, and the laws, rules, or regulations of other Federal, State, or local agencies, adhere to the more restrictive laws, rules, or regulations.

209.07

209.07 Construction of Structures

Structural controls include, but are not limited to, bonded fiber matrix, riprap, inlet protection, check dams, silt fence, and sediment basins. Install and maintain structural measures according to the manual for Management of Storm Water Discharges Associated with Construction Activities, TN Construction General Permit, and the Roadway Standard Drawings.

A. Sediment Filter Bags

The Contractor may use sediment bags on slope drains, pipe culverts, and box bridges, or for pumping sediment from sediment traps and sediment basins. Perform such work as shown on Plans or as directed by the Engineer.

Provide filter bags consisting of a non-woven geotextile bag resistant to rot, mildew, puncture, and tearing, and that has a minimum seam breaking strength of 200 pounds. The seams shall demonstrate less elongation and deformation than the geotextile fabric. The Division of Materials and Tests will certify the fabric for the Temporary Sediment Filter Bags and place them on the Department's Qualified Products List.

Ensure that each bag has a permanently attached label from the manufacturer designating the bag's maximum allowable flow rate in gallons per minute. Do not allow the flow into the filter bag to exceed the designated flow rate. Connect the filter bag to the pump hose as recommended by the manufacturer. Upon Project completion, remove the sediment filter bag and permanently stabilize the disturbed areas at the dewatering structure location. Dispose of the bag and the sediment contained in the bag as directed by the Engineer.

B. Sandbag Berms and Temporary Plugs

The Contractor may use sandbag berms and temporary plugs for velocity control, runoff management, sediment control, and separating streamflow from work areas. Do not use sandbag measures for filtration, in high concentrated flow areas where the bags may be displaced by flow, and in areas where equipment and/or traffic may damage the bags. Place sandbags so that their ends tightly abut and overlap to direct flow away from bag joints.

Sandbags for the sandbag berms and channel plugs shall be made of durable, weather resistant geotextile, having tight enough pores to retain

the bag filler material. Use of burlap is not acceptable for sandbags used in sandbag berms and temporary plugs. Typical bags measure approximately 24 inches x 12 inches x 6 inches. Use clean, non-cohesive sand as fill material for the sandbags.

Where sandbags are used to construct sandbag berms or temporary plugs across a ditch or channel, install the sandbags along a level contour. Turn the sandbags at the ends of the measure upstream.

The Contractor may install sandbag berms in both unpaved and paved ditches and channels. Construct the sandbag berm to be wider than the high water mark of the ditch or channel to prevent undercutting. The center of the sandbag berm shall be lower than either of the edges. For multiple sandbag berms installed in ditches, the maximum spacing between the berms should be such that the toe of the upstream sandbag berm is at the same elevation as the top of the downstream sandbag berm.

To temporarily separate stream flow from work areas, construct sandbag temporary plugs as necessary. Construct temporary plugs to prevent leaks between bags.

Remove and replace torn or damaged sandbags to prevent the bag filler material from becoming a stormwater pollutant. Remove any sediment accumulations at sandbags when the sediment accumulation has reached half the original height of the sandbags. If the ends of sandbag structures are breached, place new bags in the breach, and extend the ends of the berm to a higher elevation. If needed, repair the bank damage. If sandbags are undermined, do not repair the sandbags in place as additional undermining may occur. Move the sandbags downstream of the damaged location.

Upon Project completion, remove all sandbags and permanently stabilize disturbed areas underlying the sandbags with measures such as permanent seed and mulch.

C. Flocculants

Furnish and apply flocculant materials to control erosion on disturbed areas and for use with sediment control devices to reduce turbidity from stormwater runoff.

1. **Equipment.** If using a liquid application system, it may be necessary to pump a surfactant through the delivery system before

209.07

injecting liquid flocculant and afterwards to prevent clogging of pipes and valves.

After applying flocculant materials, clean all application equipment according to the flocculant manufacturer's recommendations to prevent the formation of dried residue that may impede future equipment performance.

Apply dry flocculant materials with a hand-held fertilizer spreader or a tractor-mounted spreader. If approved by the flocculant manufacturer, the Contractor may mix certain dry flocculants with dry silica sand to aid in spreading.

2. **Limitations.** Do not apply cationic PAM blends.

Do not apply flocculants directly to streams, wetlands, or other natural water resources; to sediment ponds; or to slopes that produce runoff directly into a stream, wetland, or other natural water resource. Apply flocculants so that all flocculant-applied runoff flows into a sediment trap, sediment pond, or series of multiple sediment-control BMPs prior to discharge from the site. Always use flocculants for both erosion and sediment control in conjunction with approved stormwater BMPs, as shown on the Standard Drawings.

Perform dry flocculant applications in dry weather conditions with light winds. Do not apply anionic PAM during rainfall or onto saturated soils.

Do not apply flocculants over snow-covered surfaces or over surfaces of pure sand or gravel with no fines.

Apply flocculants at least 60 feet from any stream, wetland, or other natural water resource located on or adjacent to the construction site.

Do not apply emulsion forms of coagulant/flocculants directly to stormwater runoff or to streams, wetlands, or other water resources due to surfactant toxicity. Emulsions may only be used to prepare liquid flocculants specifically used for erosion control applications, such as soil binders and tackifiers.

3. **Preparation of Treatment Areas.** Before using flocculants, obtain and test site-specific soil samples to identify the optimum flocculant

blends to use for effectiveness. Obtain soil samples from each soil horizon to be accessed during excavation.

4. **Application Requirements.** Use flocculants in conjunction with other BMPs (with the bulk of structural sediment-control BMPs, including sediment ponds, positioned down slope of the flocculant-application areas) to increase flocculant performance. Direct stormwater runoff from flocculant-treated soils to pass through a series of sediment control BMPs prior to discharge to surface waters, with flow passing through a minimum of three enhanced rock check dams and a silt trap. It is preferable that runoff from flocculant-treated areas be directed into a sediment pond.

Store flocculant materials in covered areas. Many flocculants demonstrate a decrease in effectiveness after exposure to sunlight and air. Anionic PAM loses its effectiveness within three months after exposure to sunlight and air. Anionic PAM as well as certain other flocculant materials, when combined with water, become very slippery and can produce a safety hazard. Take care to prevent spills of flocculants, in liquid, emulsion, or powder form, onto paved surfaces.

Application of flocculants will be most effective when applied as follows:

1. During rough grading operations;
2. On stockpiles and borrow areas;
3. Temporary haul roads before placement of crushed rock surface;
4. Compacted soil road base;
5. After final grading and before paving and/or final seeding;
6. Along the interior surface area of ditches;
7. Sites where work has been temporarily suspended (e.g., winter shutdown), and
8. Areas that will be mulched.

209.07

The use of a visible tracer or colorant to visibly track flocculant application is recommended.

For liquid applications of flocculants, use source water for mixing with a low turbidity (20 NTUs or less).

For turbidity reduction within sediment ponds, apply flocculants to conveyance ditches above the pond that discharge into the pond.

For dewatering and suspended solids removal of turbid pooled water within pipe trenches, silt traps, or other areas, flocculants may be introduced, in either liquid or solid forms, into the turbid water during pumping/evacuation of the pooled water, with the discharge either pumped through a filter bag or jute-lined treatment ditch prior to ultimate discharge. Strictly adhere to the application rates as given in this specification for turbidity reduction for anionic PAM, and as given by the manufacturers' requirements for other types of flocculants, during dewatering.

- a. **Anionic Polyacrylamide.** Before using any flocculant, submit the flocculant manufacturer's written application, storage, and mixing requirements and specifications to the Engineer.

Store, handle, mix, and apply anionic PAM in strict accordance with the flocculant manufacturer's recommendations and in strict compliance with OSHA Material Safety Data Sheet requirements and all applicable Federal, State, and local regulations. Use proper personal protective equipment when handling the flocculant per industry, manufacturer, State, and Federal regulations.

Do not exceed the specified maximum application rates for anionic PAM. Applying additional PAM beyond the rates specified will not improve the effectiveness of PAM but could present toxicity issues to receiving streams down gradient of the PAM application zone.

(1) For Erosion Control Applications on Sloped Areas

- a) For hydroseeding applications, add anionic PAM as the last component to the hydroseeding mixture. When mixing, never add water to anionic PAM. Add PAM at a slow rate to water. Mixing of anionic PAM

for hydroseeding shall include agitation of the PAM/water mixture. Apply using a method that will ensure uniform flocculant coverage over the target application area.

- b) Never use anionic PAM as the sole erosion control method for slopes; accompany slope applications of PAM with mulching.
- c) For PAM tackifiers, dissolve dry PAM with a known quantity of clean water in a container for several hours (preferably overnight). Apply PAM using a hydro-mulch machine at a rate ranging from 0.5 pounds to 1.0 pound (maximum) per 1,000 gallons of water per acre of application area.
- d) For soil binder applications, dissolve pre-measured dry PAM with a known quantity of clean water in a container for several hours (preferably overnight.) Apply PAM at a rate ranging from 2/3 pounds to 1 pound (maximum) per 1,000 gallons of water per acre of bare soil.
- e) Mix emulsion batches according to the recommendations of the flocculant manufacturer to determine the proper product type and application rate to meet site-specific requirements. Apply using a method that will ensure uniform coverage over the target application area.
- f) When using an emulsion form of anionic PAM to slopes, apply no greater than 1.5 gallons emulsion per acre per event. Solution mixtures shall be 1.5 gallons (maximum) anionic PAM emulsion per 3,000 gallons of water. Do not use water volumes that are less than 3,000 gallons of water due to increased viscosity issues.
- g) Spray the anionic PAM/water mixture uniformly across the dry soil slope until completely wetted.
- h) For dry anionic PAM applications for erosion control, apply anionic PAM as a powder at the following rates:

209.07

- For slopes less than 25%, apply at a maximum rate of 10 pounds per acre
 - For slopes greater than or equal to 25%, apply at a maximum rate of 20 pounds per acre
- i) Reapply liquid anionic PAM for erosion control on actively worked areas after a 48-hour period.
 - j) Do not apply liquid anionic PAM to the same slope area more than once in a 48-hour period and no more than seven times in a 30-day period.
 - k) For inactive slope areas where anionic PAM has been applied, reapply once every two months.
 - l) Anionic PAM applications (dry or liquid) shall not exceed 200 pounds per acre per year.

(2) For Turbidity Reduction within Ditches

- a) If possible, apply flocculant as erosion control in the watershed above the treatment ditches in conjunction with the application of flocculants within treatment ditches for turbidity control.
- b) Line the surface area of stormwater ditches, as well as the surface area of ditch check dams, with jute mesh.
- c) Apply dry powder anionic PAM over the jute mesh at a rate of 0.25 pounds to 0.5 pounds per 1,000 square feet of ditch surface area.
- d) Reapply dry powder anionic PAM to jute mesh in ditches every three to five storm events. Dry anionic PAM application shall not exceed 4.6 pounds per 1,000 square feet per year.
- e) Ensure anionic PAM bricks/logs are of appropriate size, shape, and number to deliver the appropriate dosage to the water within the conveyance. Obtain brick/log dissolution rates and dosages from the flocculant manufacturer.

- f) Locate anionic PAM bricks/logs in a shaded, preferably moist, installation zone during application.
 - g) Place anionic PAM bricks/logs near the main flow area of the ditch, at an appropriate distance above sediment ponds or traps to maximize mixing and flocculation. Refer to the manufacturer's guidance for flocculant mixing time and block/log spacing configurations.
 - h) Install one anionic PAM brick/log for every 65 to 70 gallons per minute of flow to be treated, unless otherwise specified by the flocculant manufacturer.
 - i) Unless otherwise specified by the flocculant manufacturer, anionic PAM bricks/logs are estimated to treat, on average, 475,000 to 550,000 total gallons of flow volume.
 - j) Install stakes, mesh bags, cages, and other mechanisms to anchor bricks/logs in place to provide stability during flows and to maximize exposure of the brick/log surface area to flows.
 - k) Replace anionic PAM bricks/logs at least every 3 to 4 months or earlier if bricks/logs have excessive sediment/debris deposition on the outer brick/log surface area or excessive degradation of brick/log mass.
- b. **Miscellaneous Coagulants/Flocculants.** Miscellaneous flocculant materials shall include all other flocculants that are not polyacrylamide blends and that have been pre-approved for use on Department projects through the Materials and Testing Division.

Before using any flocculant, submit the manufacturer's written application, storage, and mixing requirements and specifications to the Engineer.

Store, handle, mix, and apply flocculants in strict accordance with the flocculant manufacturer's recommendations and in strict compliance with OSHA Material Safety Data Sheet

209.07

requirements and all applicable Federal, State, and local regulations. Use proper personal protective equipment when handling the flocculant per industry, manufacturer, State, and Federal regulations.

Do not exceed the manufacturer's specified application rates for flocculants.

For erosion and sediment control applications for sloped areas and ditches:

1. Strictly follow the manufacturer's requirements for application mixtures and rates.
 2. With hydroseeding applications, mix flocculants according to the manufacturer's written recommendations.
 3. Do not use flocculants as the sole erosion control method for slopes; accompany slope applications of flocculants with mulching. Use flocculant for turbidity reduction in ditches in conjunction with other structural sediment-control BMPs.
 4. Re-application frequency and rates shall strictly follow the manufacturer's written recommendations, as provided to the Department and the Contractor.
 5. Store flocculants according to the manufacturer's written requirements, as provided to the Department and the Contractor.
5. **Documentation and Maintenance.** Flocculants will enhance the deposition of soil solids in downstream ditches, pipes, and ponds. Inspect these hydraulic structures regularly, and routinely remove solids from these structures to ensure optimization of performance.

Provide suitable means for storing and protecting flocculants against moisture and sunlight.

Department field personnel will maintain records of all flocculant applications including the following information:

- a) Date, time, and specific location of application;
 - b) Rates of application;
 - c) Method of application;
 - d) Weather conditions, and
 - e) Type of flocculant applied including manufacturer name and product name.
6. **Final Cleanup.** Clean liquid or dry flocculant spills according to the manufacturer's requirements. Thoroughly rinse flocculant mixing and application equipment with water to prevent residue formation. The Contractor may apply rinse residues to exposed slopes for erosion control. Keep the amount of unused flocculant mixtures to a minimum. Dispose of excess flocculant material in compliance with Federal, State, and local environmental regulations. Do not dispose of excess material within stormwater conveyances, sewers, or streams.

Where temporary erosion prevention and sediment control or pollution prevention work is acceptably performed and failure of all or any part of the system occurs but is not attributed to the Contractor's negligence, carelessness, or failure to install permanent controls and falls within the specifications for a work item that has a contract price, the Department will pay for units of work at the proper contract prices except as noted below. Should the temporary EPSC work not be comparable to the project work under the applicable contract items, the Department will direct the Contractor to perform the work on a force account basis, or by agreed unit prices as specified in **109.04**.

Except as noted below, the Department may pay the Contractor to replace temporary EPSC measures installed according to the Plans or as approved by the Engineer provided such devices are no longer effective due to deterioration or functional incapacity that is not attributable to improper installation, lack of reasonable maintenance, or failure of the Contractor to pursue timely installation of permanent control devices according to the Plans and Specifications or as directed by the Engineer.

Unless provided for on the Plans, the Department will not directly pay for temporary and permanent EPSC measures in disturbed areas outside the right-of-way, such as borrow areas, waste areas, and haul roads, unless the

209.08

borrow areas or waste areas are provided for by the Department, and except for permanent Seeding (with Mulch) on borrow areas and waste areas within the limitations specified in **203.04.E** and **203.07**, respectively. Where the Plans show separate quantities for erosion prevention and sediment control or pollution prevention items to be used outside the right-of-way in connection with waste areas, borrow areas or other project related construction, the Department will pay for the items used and accepted up to the plan quantities; but the cost of any overruns in these items, or the cost of any additional items required for erosion prevention and sediment control or pollution prevention off the right-of-way, shall be borne by the Contractor unless prior written approval is received from the Engineer.

If the Contractor fails to control project related erosion or the discharge of pollutants, either on or off the right-of-way, the Engineer may withhold payment of future progress estimates until the Contractor has satisfactorily performed the necessary corrective measures. If deemed necessary, the Engineer may employ outside assistance or use Department forces to provide the needed protective measures, and will charge all incurred direct costs plus project engineering costs to the Contractor by appropriate deductions from the Contractor's monthly progress estimate.

COMPENSATION

209.08 Method of Measurement

The Department will measure EPSC measures according to the appropriate Standard Drawing or as specified below.

The Department will measure:

1. Temporary seeding and mulching operations in accordance with the appropriate provisions of **801.09**.
2. Seeding (without Mulch) and Crown vetch mixture (without Mulch) per unit.
3. Accepted quantities of Road and Drainage Excavation by the cubic yard.
4. Sediment removal and disposal for maintaining erosion prevention and sediment control measures by the cubic yard.

5. Sandbags by the square foot area of berm face.
6. Flocculants used for turbidity reduction by the actual weight in pounds of flocculant materials applied, or, for brick or log forms of flocculant material, by the unit, per each.
7. Flocculants used as either a soil binder or tackifier for erosion control applications by the acre.

209.09 Basis of Payment

The Department will not make separate payment for Non-Structural BMPs.

The Department will pay for accepted quantities of EPSC measures based on the item numbers and measurement and payment information provided on the Standard Drawings.

Unless otherwise stated on the corresponding Standard Drawings, payment for EPSC measures is full compensation for all materials and labor necessary to construct, maintain, and remove the measures.

For catch basin filter assemblies, structure maintenance including cleaning to prevent clogging is included in the contract unit price for the structure. The Department will not directly pay for sediment removal and disposal for maintaining these assemblies.

The Department will pay for Seeding (with Mulch), Seeding (without Mulch), Temporary Seeding (with Mulch) Crown vetch mixture (without Mulch), and Mulch items in accordance with **801.10**.

The Department will pay for accepted quantities of Road and Drainage Excavation at the contract unit price per cubic yard.

Unless otherwise specified, the Department will pay for sediment removal and disposal for maintaining EPSC measures at the contract unit price per cubic yard.

The Department will pay for rock used for inlet and outlet control on EPSC measures at the contract unit price per ton.

The Department will pay for pipe used to construct EPSC measures in accordance with **607.13**.

209.09

The Department will pay for concrete used to construct spillways or other sediment control structures in accordance with **703**.

The Department will pay for water used to prepare the seed bed and for maintenance at the contract unit price per M.G. (1,000 gallons) of water.

The Department will pay for sandbags at the contract unit price per bag.

The Department will pay for accepted quantities of flocculants at the contract unit price. Such payment is full compensation for all equipment, materials, labor, and incidentals necessary to apply the flocculant materials.

The Department will pay for sediment filter bags at the contract unit price for the size bag used. Such payment includes installation and replacement as needed, along with all materials, equipment, tools, labor, and incidentals to complete the work. The Department will pay for removal and disposal of material from bag by the cubic yard at the contract unit price for sediment removal.

**PART 3 – BASE AND SUBGRADE
TREATMENTS**

SECTION 302 – SUBGRADE TREATMENT (LIME)..... 210
SECTION 303 – MINERAL AGGREGATE BASE 220
SECTION 304 – SOIL-CEMENT BASE 230
SECTION 306 – PORTLAND CEMENT CONCRETE BASE 238
SECTION 307 – BITUMINOUS PLANT MIX BASE (HOT MIX)..... 242
SECTION 309 – AGGREGATE-CEMENT BASE COURSE 252
SECTION 310 – CONDITIONING MINERAL AGGREGATE BASE .. 259
SECTION 312 – AGGREGATE-LIME-FLY ASH STABILIZED
BASE COURSE 262
SECTION 313 – TREATED PERMEABLE BASE..... 270

302.01

SECTION 302 – SUBGRADE TREATMENT (LIME)

302.01 Description	210
302.02 Reserved.....	210
302.03 Materials	210
302.04 Equipment	211
302.05 Limitations	212
302.06 Preparing the Existing Subgrade	212
302.07 Extra Depth Stabilization	213
302.08 Applying Lime	213
302.09 Initial Mixing and Mellowing	214
302.10 Final Mixing.....	214
302.11 Compaction and Finishing	215
302.12 Curing	216
302.13 Tolerances and Reconstruction	216
302.14 Method of Measurement	217
302.15 Basis of Payment.....	219

DESCRIPTION

302.01 Description

This work consists of treating in-place subgrade material with lime, and includes preparing the existing subgrade, distributing the specified percentage of lime, initial mixing, mellowing, final mixing, compacting, finishing, and curing.

302.02 Reserved

MATERIALS

302.03 Materials

A. Lime

Provide either hydrated lime or quicklime meeting **921.04**.

B. Water

Only use water that meets the requirements of **921.01**.

C. Soil

Use in-place subgrade material, removing unsuitable soil and replace it with suitable material.

Before the work is started, sample the in-place material and perform laboratory testing to determine the percentage of lime required and the appropriate optimum moisture content of the lime-soil mixture according to AASHTO T 99, Method C. Submit the design to the Department for approval.

D. Bituminous Material

For use as a curing agent, provide bituminous material as specified in:

- PG64-22, 70-22, 76-22, and 82-22 **904.01**
- Emulsified Asphalt,
- Types allowed for Tack Coat in **403**..... **904.03**

Provide emulsified asphalt, of a type allowed for Tack Coat in **403**, meeting the test requirements specified in Table 904.03-1.

The Contractor may select the type of bituminous material to use for curing.

EQUIPMENT

302.04 Equipment

A. Distributing Equipment

Provide equipment to distribute the lime uniformly, at the required rate and without excessive loss.

B. Mixers

Provide an acceptable mixer capable of attaining final mixing specified in **302.10**.

302.06

C. Compaction Equipment

Provide compaction equipment of the size and weight required to obtain the specified density and quality of finished surface.

CONSTRUCTION REQUIREMENTS

302.05 Limitations

Handle and store lime in completely enclosed, moisture resistant containers until immediately before use. Store bagged lime in weatherproof buildings with adequate protection from ground dampness.

Do not stabilize areas that will not be covered with the succeeding stage of sub-base or base construction during the same construction season.

Do not apply lime:

1. to frozen subgrade material;
2. if the air temperature in the shade is less than 40 °F;
3. during periods of high winds; and
4. to areas that cannot be mixed and sealed as specified in **302.09** on the same day as application.

Do not leave lime exposed to the open air for a period of 6 hours or more.

Do not allow traffic or equipment on the spread lime other than that required for spreading, watering, or mixing.

302.06 Preparing the Existing Subgrade

Grade and shape the existing roadway in reasonably close conformity with the lines, grades, and cross-sections shown on the Plans or as directed by the Engineer.

Remove all grass turfs and other deleterious substances from the subgrade and prepare the subgrade as specified in **207.03**.

Correct wet or unstable underlying foundation material, if encountered, as directed by the Engineer.

302.07 Extra Depth Stabilization

If directed by the Engineer, perform extra depth lime stabilization as follows:

1. Blade the overlying material to the sides, and incorporate the lime slurry or, in dry applications, the hydrated lime and any necessary water, into the underlying material at the rate and to the depth specified.
2. Thoroughly mix and compact the lime-soil mixture to obtain the required stability.
3. Moisten the compacted surface, and cover with the previously windrowed subgrade material.
4. Compact the overlying subgrade material, which will serve as the curing medium.

Curing and mellowing periods will not be required for the lime-stabilized underlying material unless otherwise directed by the Engineer.

302.08 Applying Lime

After preparing the subgrade as specified in **302.06**, apply lime using the dry or slurry application method for either hydrated lime or quicklime. Use the slurry application method unless otherwise shown on the Plans.

A. Dry Application

Spread hydrated lime at the required rate, using an approved spreader that will uniformly distribute the material without excessive loss, or by bag distribution.

B. Slurry Preparation and Application

Mix lime with water in approved agitating equipment, and apply to the roadway as a thin water suspension or slurry through approved distributing equipment. The distributing equipment shall be equipped to continuously agitate the mixture from the mixing site until applied on the roadbed. Proportion the mixture so that the dry solids content is at least 30% by weight.

302.09

In preparing, transporting, distributing, and mixing slurry with the soil, do not cause injury, damage, discomfort, or inconvenience to individuals or private property.

302.09 Initial Mixing and Mellowing

In dry applications, immediately after applying the hydrated lime, scarify the course, if necessary, and mix to the required depth, width, and cross-sections.

In slurry applications, before applying the lime slurry, scarify or partially pulverize with approved mixing equipment the full width of the course to be treated, as directed by the Engineer, to the depth required for stabilization. Perform successive passes over a measured section until the specified percentage of lime has been distributed. After each successive pass, incorporate the slurry into the soil with approved mixing equipment.

Incorporate lime into the soil to the depth needed to provide a finished course of lime-treated material conforming to the specified thickness and surface requirements.

Continue mixing, and applying water as necessary, until a homogeneous mixture of soil, lime, and water is obtained. During this initial mixing operation, add the quantity of water needed for the moisture content of the mixture to reach 5% above its optimum moisture content, plus or minus 3%, unless otherwise directed by the Engineer.

If applying the lime as a slurry, ensure that the water added with the slurry does not cause the moisture content of the lime-soil mixture to exceed the above tolerance.

After completing mixing operations, reshape the treated course to the approximate lines, grades, and cross-sections, and seal with a pneumatic-tire roller, and other approved equipment as necessary, and allow the treated course to mellow for 2 to 7 days as directed by the Engineer. During the mellowing period, maintain the entire surface of the treated course in a moist condition.

302.10 Final Mixing

After the required mellowing period, reshape and grade the initially mixed material to the required lines, grades, and cross-sections.

Thoroughly mix the previously mixed material with approved mixers while adding water as necessary.

Continue mixing until 100% of the material, except for gravel and stone, will pass a 1-inch sieve, and 60% by dry weight will pass the No. 4 sieve.

The quantity of water added shall be such that at the end of the final mixing and during compaction and finishing operations the percentage of moisture in the mixture and the unpulverized soil lumps will not vary more than plus or minus 3% from the specified optimum moisture of the lime-soil mixture.

302.11 Compaction and Finishing

Immediately after completing the final mixing, blade the material to uniform thickness and shape, and start compaction operations. Use sheepsfoot rollers to compact the material in a continuous operation until the entire depth of the lime-soil mixture is uniformly compacted to the required density. The Contractor may remove the sheepsfoot rollers when a surface mulch not exceeding 1 inch remains. Lightly scarify the resulting surface and shape to the required lines, grades, and cross-sections within the tolerances specified in **302.13**. Perform final rolling with the roller specified by the Engineer.

The completed lime stabilized subgrade shall be smooth, dense, well bonded, unyielding, and free of cracks or loose material.

Compact the lime-soil mixture in layers as shown on the Plans. The Department will determine the maximum density and optimum moisture content of the lime-soil mixture according to AASHTO T 99. The sample used to determine the maximum density and optimum moisture content will be representative field samples of the lime-soil mixture that have undergone the same treatment as the lime treated subgrade being tested.

For density testing purposes, the Department will divide the completed subgrade treatment into lots of approximately 10,000 square yards, and will perform five density tests on each lot. The average dry density of each lot shall not be less than 95% of maximum density, and no individual test shall be less than 92% of maximum density.

Immediately scarify, moisten (if required), rework, and compact to the required density all areas that do not meet density requirements at no additional cost to the Department.

302.12

302.12 Curing

After finishing the lime-treated subgrade as specified in **302.11**, seal the surface by applying one of the bituminous materials specified in **302.03.D** using a pressure distributor at the rate of 0.10 to 0.25 gallons per square yard, as directed by the Engineer or as shown on the Plans. Heat or otherwise prepare the bituminous material to ensure uniform distribution and apply as soon as possible.

302.13 Tolerances and Reconstruction

The Department will determine the thickness of the completed lime-treated subgrade by measuring test holes at random locations as specified in Departmental procedures. The measured thickness at the locations shall not deviate from that shown on the Plans by more than plus 1-1/2 inches or minus 1 inch.

Immediately reconstruct areas of lime-treated subgrade that do not meet thickness requirements. For areas having a thickness greater than that allowed, add sufficient lime to correct the deficiency in lime content. Perform reconstruction, including adding lime, to correct the thickness deviation at no cost to the Department.

As directed by the Engineer, repair areas of lime-treated subgrade that become unstable or that lose the required density or surface finish. Use additional lime and water if and as directed.

Limit hauling over the treated subgrade to the minimum amount necessary to construct the overlying base or sub-base.

When at least one course of base or sub-base has been constructed upon the treated subgrade, the Contractor may resume hauling, provided the layer or layers of base or sub-base are constructed and maintained as specified in **303.10** and **303.11**.

COMPENSATION

302.14 Method of Measurement

A. Lime

The Department will measure Lime by the ton. Quantities and percentages of lime shown on the Plans are based on preliminary soil investigations and dry laboratory sample tests using hydrated lime. The Engineer will establish the actual application rate from dry density tests conducted just before the start of stabilization work. For quicklime, the Department will determine the accepted quantity by converting the quicklime to an equivalent quantity of hydrated lime as follows:

$$\text{EHL} = 1.32 \text{ QL} \left[1 - \frac{\text{I}}{100} \right]$$

Where:

EHL= Equivalent amount of hydrated lime in tons
 QL = Tons of quicklime accepted
 I = Percent of impurities in the quicklime

The Department will deduct for quantities of lime that have been wasted or not actually used in the work.

If sacked lime is used, the Department will use the net weight as packed by the manufacturer for measurement.

B. Processing of Subgrade Treatment (Lime)

The Department will determine the area processed by the square yards of treated subgrade, as computed using the length measured at the surface of the treated subgrade and the width shown on the Plans or designated by the Engineer.

C. Extra Depth Stabilization

1. Direction Application Method. The Department will classify processing performed using the Direct Application Method, as specified in **302.07**, as Subgrade Treatment, and will measure this work for payment as follows:

302.14

- a. If the thickness of the layers processed is equal to or greater than the Plan thickness for normal stabilization, the Department will measure processing by the square yards of each extra depth layer processed.
- b. If the thickness of the layers processed is less than the Plan thickness for normal stabilization, the Department will measure the area in square yards of each extra depth layer processed and will adjust this area to determine the quantity for payment by multiplying the number of square yards processed by the thickness of the layer and dividing by the Plan thickness for normal stabilization. To determine the area of extra depth layers, the Department will measure the length and width used in accordance with **302.14.B**.

2. **Drill-Lime Method.** The Department will measure drilling necessary to complete Extra Depth Stabilization by the total quantity in linear feet of all holes drilled, from either the finished subgrade or from the top of base to the bottom of the drilled holes.

D. Water

The Department will measure water by the M.G. (1,000 gallons) using calibrated tanks or distributors, or accurate water meters. The quantity measured for payment will be the amount necessary for subgrade preparation, initial mixing, mellowing, final mixing, compacting, finishing, and curing. The Department will not measure water used to prepare or apply slurry.

E. Bituminous Material

The Department will measure in tons the quantity of bituminous material used and accepted.

F. Preparation of Existing Subgrade

The Department will classify and measure the materials moved, furnished, or disposed of to prepare the subgrade in accordance with **302.06** as provided for under **207**.

302.15 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Hydrated Lime	Ton
Bituminous Material	Ton
Soil-Lime Processing	Square Yard
Drilling for Subgrade Treatment	Linear Feet
Water	M.G.

Such payment is full compensation for providing all materials, equipment, labor, and incidentals to complete the work as specified.

The Department will pay for moving, furnishing, or disposing of material under **207** if the Contract is for any of the following:

1. Combined grading, drainage and paving project,
2. Construction of a base and/or pavement on a road that has been graded under a previous Contract, or
3. Base and/or paving project that includes sections of grading.

For Extra Depth Stabilization, the Department will not pay for any shifting of the overlying material; however, the Department will pay for the lime and water used and for the mixing of the underlying material with the lime and water.

If repairs to the lime-treated surface are made necessary by a cause beyond the Contractor's control, the Department will pay for the construction items involved at the contract unit prices.

303.01

SECTION 303 – MINERAL AGGREGATE BASE

303.01 Description	220
303.02 Aggregate	220
303.03 Calcium Chloride	221
303.04 Reserved.....	221
303.05 Emulsified Asphalt.....	221
303.06 Equipment	221
303.07 General.....	222
303.08 Mixing.....	223
303.09 Spreading	224
303.10 Shaping and Compaction	225
303.11 Maintenance	227
303.12 Thickness Requirements	227
303.13 Surface Requirements	227
303.14 Method of Measurement	228
303.15 Basis of Payment.....	229

DESCRIPTION

303.01 Description

This work consists of furnishing and placing one or more courses of aggregates, and additives if required, on a prepared subgrade.

Mineral aggregates base shall be Type A or Type B, whichever is shown on the Plans and called for in the bid schedule. Recycled Concrete Aggregate (RCA) may be used as an alternate for Type A or Type B base material.

MATERIALS

303.02 Aggregate

Depending upon whether the Plans require Type A or Type B base, provide mineral aggregate meeting **903.05**. For Type A base, use aggregate of Grading D. For Type B base, the Contractor may use aggregate of Grading C or D. For RCA, use grading specified in **903.05.C**.

The Engineer will accept aggregate for gradation as follows:

1. When the stationary plant method for mixing is used, the Engineer will accept aggregate immediately after or prior to mixing, based on periodic samples taken from the pugmill output or from the belt feeding the pugmill.
2. When two or more materials are blended on the road using mechanical mixers, the Engineer will accept aggregate after mixing and before compaction, based on samples taken from each layer of base material
3. For aggregate that does not require blending, the Engineer will accept aggregate at the aggregate production plant, based on samples taken from stockpiles of plant production immediately before delivery to the road.

303.03 Calcium Chloride

Provide calcium chloride meeting **921.02** for Type 1, Type 2 or calcium chloride liquor.

303.04 Reserved

303.05 Emulsified Asphalt

Use emulsified asphalt of a type allowed for Prime Coat in **401**, meeting the test requirements specified in **904.03**.

EQUIPMENT

303.06 Equipment

Provide a stationary mixing plant, mechanical road mixer, or motor grader, whichever is applicable to the type of work to be performed, as specified in **303.08**.

A. Stationary Mixing Plant

Provide an approved twin-shaft pugmill capable of producing a constant, uniform mixture. Equip the mixing plant with the following:

303.07

1. suitable truck-loading hopper with a gate that will prevent segregation of the material when dumped into the truck;
2. A spray bar, capable of ensuring an even wetting of the aggregate, mounted at the entrance of or above the pugmill;
3. A meter, valve, or other approved type of regulating device to control the flow of water through the spray bar to maintain a uniform moisture content in the mixture;
4. A separate, quick, and automatically operating on-and-off device to shut the water off instantly when the pugmill stops; and
5. Adjustable mechanical feeders for each size material capable of regulating a constant, uniform flow of material.

B. Mechanical Mixer (for Road Mixing)

Provide a pugmill or rotary type mechanical mixer capable of producing a uniform blend of all materials to the full depth of the course being placed. The mixer may be either self-propelled or trailer-drawn.

C. Compaction Equipment

Provide one or more rollers of a type and sufficient weight to obtain the required density and seal the surface of the base course.

CONSTRUCTION REQUIREMENTS

303.07 General

Construct Mineral Aggregate Base, Type A, Type B, or RCA in one or more layers, to the compacted thickness shown on the Plans.

Prepare the subgrade as specified in **207** or **302**, whichever is applicable.

Obtain the Engineer's approval of the subgrade before spreading any mineral aggregate. Subgrade that has been previously checked and approved, but subsequently subjected to freezing conditions or prolonged wet weather, shall be rechecked for approval.

Do not spread mineral aggregate on a subgrade that is frozen or contains frost.

Do not haul over any material that has been placed until it has been spread, mixed, shaped and compacted to the required density.

303.08 Mixing

A. Mixing Methods

Unless otherwise specified, mix the base course material, including an additive if shown on the Plans, by one or more of the following three methods:

- 1. Stationary Plant Method.** Mix the base course material and water in an approved stationary mixing plant as specified in **303.06.A**. Add sufficient water during the mixing operation to provide a moisture content satisfactory for compacting. If combining materials to meet the grading requirements, blend the materials, as specified in **903.05**, before mixing. Ensure that all material fed into the plant travels the full length of the pugmill.
- 2. Road Mix Method (Mechanical Mixer).** After placing the material for each layer of base course through an aggregate spreader or windrow-sizing device, mix the material using approved mechanical mixing machines as specified in **303.06.B**.

During mixing, add sufficient water to provide a moisture content satisfactory for compacting.

- 3. Road Mix Method (Motor Grader).** After depositing and uniformly spreading material for each layer of base course, sprinkle it with just enough water to moisten all particles, but without causing segregation of sizes or softening of the subgrade. Immediately after applying water, thoroughly mix the material by windrowing and spreading with motor graders until the mixture is uniform throughout.

For Mineral Aggregate Base, Type A, use the stationary plant method. For Mineral Aggregate Base, Type B, requiring the blending of two or more materials, use either the stationary plant method or the road mix method (mechanical mixer), except as provided for in **903.05**. For Mineral Aggregate Base, Type B, requiring additive, use either stationary plant mixing or road mixing. When using RCA as a replacement for Mineral Aggregate Base, Type A or Type B, use the intended method of mixing for the material listed above.

303.09

B. Use of Calcium Chloride

If using calcium chloride, incorporate it in either the solid or liquid form, at the approximate rate of 6 pounds per ton of aggregate, noting that:

- 6 pounds is equivalent to 1.29 gallons 60 °F 32% solution
- 6 pounds is equivalent to 1.02 gallons 60 °F 38% solution

For stationary plant mixing, proportion chloride material, in solid form, through a hopper equipped with an approved vibratory feeder and an adjustable opening capable of accurately controlling the flow of material. Proportion calcium chloride liquor using an approved calibrated meter that has a registering capacity capable of indicating the total amount of liquid used during any single day's operation.

For road mixing, add the chloride material to the aggregate at the point in the mixing operation and in the manner directed by the Engineer.

303.09 Spreading

Spread material as follows according to the mix method used:

A. Stationary Plant Mixing

After mixing, transport material to the site for each layer of base while it contains the proper moisture content. Spread the material to the required thickness and cross-section using an approved mechanical spreader.

B. Road Mixing (Mechanical Mixer)

Before mixing, spread material with an approved mechanical spreader that can be adjusted to spread materials in the proper proportions.

C. Road Mixing (Motor Grader)

After thoroughly mixing the aggregate and water, spread the base material while at optimum moisture content in layers of specified thickness and cross-section using approved motor graders.

If the required compacted depth of the base course exceeds 6 inches, construct the base in two or more layers of approximate equal thickness. The maximum compacted thickness of any one layer shall not exceed 6 inches.

In some cases, the Plans may show the base as extending for the full width of the roadbed. In other cases, the edges of the base may be shown as coinciding with the inside edges of the shoulders. In the latter case, place shoulder material to a minimum width of 3 feet before spreading each layer of base material in order to confine the base material and to allow for proper compaction.

The Contractor may spread and mix any base material used for constructing detours, for maintenance of traffic, for backfilling rock cuts, and for capping rock fills as specified in **303.09.B**.

303.10 Shaping and Compaction

A. Final Shaping

Immediately after spreading, shape the base material to the required degree of uniformity and smoothness. Except where using mechanical aggregate spreading equipment to place the base material, use a motor grader to shape each layer before compacting. If the mechanical spreading equipment fails to shape the base material properly, use a motor grader or other approved means to perform final shaping.

B. Compaction

Compact the base material to the required density before any appreciable evaporation of surface moisture occurs. Continuously compact each layer until the minimum density requirement, as specified in **303.10.C.2**, is achieved. The Contractor may use any type of compacting equipment provided the required density is attained.

If the density requirement does not apply, as provided for in **303.10.C.3**, gradually compact the base material, progressing from the edges of the base to the center, parallel with the centerline of the road. Continue compacting until the base layer has been compacted to its full width as directed by the Engineer. Where lifts of shoulder materials are placed to confine the base material, overlap the initial pass of the compacting equipment with the shoulder to a width of not less than 12 inches.

Construct the surface of each layer so that the aggregates become firmly keyed and a uniform texture is produced. Maintain the surface in this condition until it is covered by the following stage of construction or until final acceptance of the project. Correct irregularities by loosening the material at those places and adding or removing material as required.

303.10

Use approved distributors to apply water uniformly over the base materials during compaction in sufficient quantity to allow for proper compaction without causing softening of the underlying subgrade due to excessive water use.

C. Compaction Acceptance

1. **Lot Sizes and Testing.** For density testing purposes, the Department will divide each completed layer into lots of approximately 10,000 square yards, and will average the results of five density tests performed on each lot. Smaller lots may be considered as directed or approved by the Engineer.
2. **Density Requirements**
 - a. **Type A Base.** The average density of each lot of Type A base, unless otherwise specified, shall be not less than 100% of maximum density as determined according to AASHTO T 99, Method D, with no individual test less than 97% of maximum density.
 - b. **Type B Base.** The average density of each lot of Type B base, unless otherwise specified, shall be not less than 97% of maximum density as determined according to AASHTO T 99, Method D, with no individual test being less than 95% of maximum density.
 - c. **RCA Base.** The average density of each lot of RCA base, unless otherwise specified, shall be not less than 100% of maximum density as determined according to AASHTO T 99, Method D, with no individual test less than 97% of maximum density. The moisture content shall be within plus or minus 3% of the optimum moisture content as determined by Departmental analysis. Mixing of the material with water shall be completed per **303.08**.

If the specified density is not obtained for either type of base, rework or replace the material to comply with the density requirement.

3. **Exclusions.** Unless otherwise specified, the density requirements specified in **303.10.C.2** will not apply to:

- a. Type A or Type B base construction on projects that do not include the construction of a surface upon the base, or to
- b. Projects having a specified total base thickness of less than 4 inches.

When the specified density requirements do not apply, the Engineer will consider the desired degree of compaction to have been reached when the surface is tightly bound and shows no undue rutting or displacement under operation of the roller or other equipment. Obtain the Engineer's approval of the compaction of each layer before placing material for the next successive layer. Keep placing and compacting areas separate.

303.11 Maintenance

Maintain the completed base in a smooth and uniform condition until it is covered by the following stage of construction or the Project has been completed and accepted. Comply with the requirements of **104.05** regarding maintenance and protection.

303.12 Thickness Requirements

Construct the base to the grade and compacted thickness shown on the Plans, with an allowable working tolerance of plus or minus 1/2 inch. The thickness will be measured at such frequency as established by the Department using test holes or other approved methods.

303.13 Surface Requirements

The surface of the finished base shall be in reasonably close conformity to the lines, grades, and cross-sections shown on the Plans or established by the Engineer and shall have a satisfactorily smooth riding quality.

303.14

COMPENSATION

303.14 Method of Measurement

A. Mineral Aggregate for Mineral Aggregate Base, Type A, Type B, or RCA

The Department will measure Mineral Aggregate for Mineral Aggregate Base, Type A, Type B, or RCA, by the ton, in accordance with **109**.

B. Water

The Department will deduct the weight of total moisture, as determined by dry weights, of the base material at the time of weighing in excess of 3% of optimum moisture content.

The Department will not measure or pay for water when mixing is performed in a stationary plant,

When road mixing is performed, the Department will measure water added to the material at the direction of the Engineer by the M.G. (1,000 gallons) using calibrated tanks or distributors, or accurate water meters.

C. Calcium Chloride

The Department will measure calcium chloride by the ton. The Department will weigh calcium chloride received in liquid form as specified in **109**, and will convert the weight of liquid calcium chloride to tons as follows:

1. 32% Solution

$$\text{Tons Calcium Chloride} = \frac{(\text{Total tons of 32\% solution}) \times 0.32}{0.94}$$

2. 38% Solution

$$\text{Tons Calcium Chloride} = \frac{(\text{Total tons of 38\% solution}) \times 0.38}{0.94}$$

The Department will consider calcium chloride liquor used in a solution of 32% or more, but less than 38%, as a 32% solution. The Department will consider a solution of 38% or greater as a 38% solution.

303.15 Basis of Payment

- A. The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Mineral Aggregate, Type _____ Base	Ton
Calcium Chloride	Ton
Water	MG

The Department will pay for the work required to prepare the subgrade in accordance with **303.07** as provided for in the applicable Section or Subsection under which the work is performed.

B. Adjustments

Specific Gravity. In cases where the Bulk SSD specific gravity of the mineral aggregate exceeds 2.85, the Department will adjust the tonnage of mineral aggregate for payment by multiplying the tonnage of mineral aggregate used by a specific gravity of 2.85 and dividing by the higher specific gravity.

304.01

SECTION 304 – SOIL-CEMENT BASE

304.01	Description	230
304.02	Materials	230
304.03	Equipment	231
304.04	Limitations	231
304.05	Preparing the Existing Subgrade	232
304.06	Pulverizing	232
304.07	Cement Application, Mixing, and Spreading	232
304.08	Compaction	233
304.09	Finishing	234
304.10	Construction Joints	234
304.11	Thickness and Surface Tolerances	234
304.12	Curing	234
304.13	Reconstruction and Replacement	235
304.14	Traffic	235
304.15	Maintenance	235
304.16	Method of Measurement	236
304.17	Basis of Payment	236

DESCRIPTION

304.01 Description

This work consists of mixing in-place or select soil with Portland cement, and moistening and compacting the soil-cement mixture in one or more courses.

MATERIALS

304.02 Materials

Provide materials as specified in:

Portland Cement, Type I	901.01
Portland-Pozzolan Cement, Type IP	901.01

304.03

Bituminous Curing Seal, Emulsified Asphalt, Types allowed for Tack Coat in 403	904.03
Select Material for Soil-Cement Base.....	921.05

Provide water as specified in **921.01**.

Provide emulsified asphalt, of a type allowed for Tack Coat in **403**, meeting the test requirements specified in Table 904.03-1.

The Contractor may select the kind of bituminous material to use for curing.

Submit a sample of the cement and the select material to be used to the Materials and Tests Laboratory for approval at least 15 days before use.

EQUIPMENT

304.03 Equipment

Provide a mechanical cement spreader that will distribute the cement uniformly at the required rate without excessive loss.

Provide mechanical mixers meeting **309.03.B**; or a stationary mixing plant meeting **309.03.A**.

CONSTRUCTION REQUIREMENTS

304.04 Limitations

Only process the amount of soil-cement that will be covered with the succeeding stage of base or pavement construction during the same construction season. Only apply cement to subgrade or select material that is unfrozen and when the air temperature in the shade is at least 40 °F and rising.

Limit application of cement to an area that will allow for continuous operations and for the completion of all but the final surface finish within three hours from the time the cement is applied. Do not leave any uncompacted soil-cement mixture undisturbed for more than 30 minutes.

If the uncompacted soil-cement mixture is wetted by rain so that the average moisture content exceeds the specified tolerance, reconstruct the entire section as specified in **304.13**.

304.05

304.05 Preparing the Existing Subgrade

If in-place soil is to be used, grade and shape the area to be treated as required to construct the soil-cement base in reasonably close conformity with the lines, grades, thickness, and cross-sections shown on the Plans. Place any additional soil needed as directed and blend with the in-place material. Remove unsuitable soil or material and replace with acceptable soil. When removing and replacing unsuitable soil, and placing additional soil, comply with the pertinent provisions of **203**.

Where only select material is to be used, prepare the subgrade as specified in **205**, **207**, or **302**, whichever is applicable.

Slightly dampen the subgrade just before spreading the select material or soil-cement mixture upon it.

304.06 Pulverizing

If required, before applying cement, scarify the soil and pulverize for sufficient depth and width to achieve the cross-section shown on the Plans. Pulverize the soil-cement mixture so that, at the completion of mixing, at least 80% of the dry material passes the No. 4 sieve and 100% of the combined material passes the 1-inch sieve, exclusive of gravel or stone retained on these sieves. Remove material retained on a 3-inch sieve and other unsuitable material.

304.07 Cement Application, Mixing, and Spreading

Use an approved mechanical spreader to spread select material on the subgrade before mixing to the required thickness, width, and cross-section. The Engineer will establish the percentage of cement to be used based on tests of the in-place soil or select material.

Apply the specified quantity of Portland cement uniformly over the spread select material or in-place soil. Do not apply cement if the moisture content of the soil exceeds 3% the optimum moisture content specified by the Engineer for the soil-cement mixture. Before starting mixing, replace spread cement that has been lost due to the Contractor's negligence at no additional cost to the Department.

Use a mechanical mixer to perform road mixing. At least one pass of the mixer may be required before adding water. When required, add water uniformly by distributors or other approved methods to bring the mixture to

the required moisture content. Continue mixing until the pulverization requirements of **304.06** are met and a homogeneous mixture of soil, cement, and water is obtained.

If using stationary plants or mixers, ensure they are equipped with feeding and metering devices that will introduce the cement, soil, and water into the mixer in the quantities specified. All material fed into the plant shall travel the full length of the pugmill. Continue mixing until a uniform and intimate mixture of cement, soil, and water has been obtained. Transport the mixture from the plant to the road in numbered trucks equipped with tight metal rear-end dump beds. Provide a sufficient number of trucks to ensure satisfactory progress of construction operations.

Spread the material using approved mechanical spreaders within one hour after being discharged from the mixer and in ample time to secure compaction during daylight hours. If the moisture content of the uncompacted mixture exceeds the specified tolerance, reconstruct the material as specified in **304.13**. When mixing, handling, and placing the base material, take care to prevent segregation.

When using select material, place shoulder material for a width of at least 3 feet before spreading the base material in order to confine the base material and allow satisfactory compaction along the edges of the base.

304.08 Compaction

At the start of compaction, the percentage of moisture in the mixture and in the pulverized soil lumps, based on oven-dry weights, shall not vary more than plus or minus 2% from the specified optimum moisture content, and shall be less than the quantity that will cause the soil-cement mixture to become unstable during compaction and finishing. The Contractor may use any type of compaction equipment that will produce the required results. Extend compaction efforts over the edges of the base material into the shoulders.

During final rolling, reshape the surface of the base course and lightly scarify to loosen any imprints left by the compacting or reshaping equipment.

The Department will divide the soil-cement base into lots of approximately 10,000 square yards for density testing purposes, and will perform five density tests on each lot. The average dry density of each lot shall be not less than 95% of maximum density as determined according to AASHTO T 134, and no individual test shall be less than 92% of the maximum density.

304.09

Rework material not meeting the required density at no additional cost to the Department, unless conditions exist as described in **304.13**. At the beginning of a project or at any time thereafter the Engineer may evaluate the rolling procedures.

Complete compaction and final shaping operations within three hours from the time the cement is mixed with the soil or select material.

304.09 Finishing

After compaction, shape the surface of the soil-cement to the required lines, grades, and cross-sections. Sprinkle the surface until it is damp, but not wet, and clip with a motor grader as directed by the Engineer. Dispose of the material removed by clipping. Following clipping, seal the surface with a roller.

304.10 Construction Joints

At the beginning of each day's construction, form a straight transverse construction joint by cutting back into the previously completed work to form a true vertical face free of loose or shattered material.

304.11 Thickness and Surface Tolerances

The Department will determine the thickness of the base by measuring test holes dug at random locations. The measured thickness shall not deviate from that shown on the Plans by more than plus 1-1/2 inches or minus 1 inch. Reconstruct or replace work found not to be within this tolerance as specified in **304.13**.

The finished base shall meet the surface requirements specified in **407.18**, and when tested as specified in that Subsection, the deviation of the surface from the testing edge of the straight edge shall not exceed 1/2 inch.

304.12 Curing

After the soil-cement has been finished, protect it against drying for 7 days by applying one of the bituminous materials specified in **304.02**. Apply the curing material at the rate shown on the Plans as soon as possible after completing the base construction, but in no case later than 24 hours after completing finishing operations. Maintain the finished soil-cement in a continuously moist condition until the curing material is placed.

If construction equipment or other traffic must use the bituminous-covered surface before the bituminous material has dried sufficiently to prevent pickup, first apply sufficient granular cover, consisting of clean sand passing a 3/8-inch sieve or other approved material.

During the 7-day protection period, maintain the curing material to ensure that all the soil-cement remains effectively covered.

Protect finished portions of soil-cement that are traveled on by equipment used in constructing an adjoining section to prevent equipment from marring or damaging completed work.

Sufficiently protect soil-cement from freezing for 7 days after its construction.

304.13 Reconstruction and Replacement

If reconstruction becomes necessary, repeat all construction procedures and adhere to the time limitations specified in **304**; however, the Engineer will determine the amount of cement to be used in the reconstructed soil-cement base.

Replace faulty work for the full depth of treatment. Correct low areas by replacing the material for the full depth of treatment rather than by adding a thin layer of soil-cement to the completed work.

304.14 Traffic

The Contractor may open completed portions of soil-cement to local traffic after the 7-day curing period, provided the soil-cement has hardened sufficiently to prevent marring or distorting of the surface by equipment or traffic. However, provide ingress and egress for property owners and public crossroads as necessary before the 7-day curing period.

304.15 Maintenance

Maintain the soil-cement in good condition until all work has been completed and accepted. Immediately repair defects that may occur at no additional cost to the Department.

304.16

COMPENSATION

304.16 Method of Measurement

The Department will measure:

1. Processing by the square yards of completed base, as determined using the actual length measured along the centerline of the roadbed and the width shown on the Plans or designated by the Engineer.
2. Material moved to prepare the existing subgrade, in accordance with **304.05**.
3. Portland Cement incorporated in the work by the ton in accordance with **109**.
4. Bituminous Material used for curing seal by the ton in accordance with **109**.
5. Water used in mixing and finishing operations by the M.G. (1,000 gallons) using calibrated tanks or distributors, or accurate meters.
6. Select Material for Soil-Cement Base, added to that already on the road, by the cross-section method in approved borrow pits.

The Department will not measure or pay for water added to emulsified asphalt used for curing.

304.17 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Processing (Soil-Cement Base)	Square Yard
Portland Cement (Soil-Cement Base)	Ton
Bituminous Material	Ton
Water	MG
Select Material (Soil-Cement Base)	Cubic Yard

304.17

The Department will not pay for reconstructive work, including additional cement and processing, required due to the Contractor's negligence.

The Department may use net certified weights as a basis of measurement for cover material aggregate, subject to correction for aggregate that is lost, wasted, or otherwise not incorporated in the Work.

306.01

**SECTION 306 – PORTLAND CEMENT CONCRETE
BASE**

306.01 Description	238
306.02 Materials	238
306.03 Equipment	239
306.04 Proportioning	239
306.05 General	239
306.06 Surface Finish and Tolerances	239
306.07 Integral Curb	239
306.08 Tolerance in Base Thickness.....	240
306.09 Method of Measurement	240
306.10 Basis of Payment.....	240

DESCRIPTION

306.01 Description

This work consists of constructing a single course of Portland Cement Concrete Base, with or without reinforcement, as specified, on a prepared surface.

MATERIALS

306.02 Materials

Provide materials as specified in:

Portland Cement, Type I.....	901.01
Fine Aggregate	903.01
Coarse Aggregate.....	903.03
Concrete Reinforcement	907
Curing Materials	913
Water.....	921.01
Air Entraining Admixtures	921.06.A.2
Chemical Admixtures and Additives	921.06

EQUIPMENT

306.03 Equipment

Provide equipment as specified in **501.04**.

CONSTRUCTION REQUIREMENTS

306.04 Proportioning

Proportion materials for concrete base as specified in **501.03.A**.

306.05 General

Prepare the subgrade as specified in **205**, **207**, or **302**, whichever is applicable. Perform sub-base or subgrade treatment, when specified, according to the applicable Sections of Part 3 of these Specifications.

To construct cement concrete base, apply the applicable methods and procedures specified in **501.07**, **501.10**, **501.12** through **501.15**, **501.16.A** through **501.16.F**, **501.17** through **501.24**, and **604.11** through **604.13**.

306.06 Surface Finish and Tolerances

Slightly roughen the surface of the concrete base by brooming. Meet the surface tolerances specified in **501.17**.

306.07 Integral Curb

Construct edging (integral curb), when shown on the Plans or required by the Engineer, of the same concrete mixture as is used in the base. Construct edging to the width and height shown on the typical cross-section by securely fastening auxiliary forms to the regular side forms of the base. Except as otherwise directed by the Engineer, construct edging immediately after the final floating of the base and before the concrete in the base upon which the edging is to be constructed has taken its initial set. Roughen the surface of the base before placing edging material upon it. At the end of the day's work, the Contractor may temporarily omit the curb from a section of the base sufficient in length to provide for backing-up of the paving train the following day, provided the base upon which the curb is to be placed is roughened sufficiently to bond the curb to the base. Remove all laitance from this section for the full width of the curbs by wire brushes or other satisfactory

306.08

means. Ensure that the concrete placed in the edging is well consolidated to avoid honeycombing. The top of the edging shall be smooth and uniform and given a wood float finish. Shape the inside and outside edges with edging tools as shown on the Plans. For final finishing of the edging, wipe the surface with a soft brush having a width not less than the width of the edging.

306.08 Tolerance in Base Thickness

For base thickness, meet the tolerance specified for pavement thickness in **501.24**.

COMPENSATION

306.09 Method of Measurement

The Department will measure Portland Cement Concrete Base (Plain) and Portland Cement Concrete Base (Reinforced) of the various thicknesses specified by the square yard in accordance with **109**.

If during construction the Engineer orders the cement increased or decreased from that approved for the job mix by more than 8 pounds per cubic yard, the Department will calculate the quantity of increased or decreased cement in accordance with **501.25**. These calculations will provide the basis for payment to the Contractor for additional cement, or for reimbursement to the Department for reduction in cement, as applicable.

306.10 Basis of Payment

A. General

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Portland Cement Concrete Base (Plain) ___"	Square Yard
Portland Cement Concrete Base (Reinforced) ___"	Square Yard

Such payment is full compensation for furnishing and placing all materials, including edging when specified, and for providing reinforcing, dowels, and joint materials.

The Department will pay for additional cement required if the cement is increased by more than 8 pounds per cubic yard at the purchase price, F.O.B. the unloading point, as verified by invoices, and will provide no additional compensation for further handling.

If the cement is decreased by more than 8 pounds per cubic yard, the Department will be reimbursed from any monies due the Contractor an amount equal to the purchase price of the cement, F.O.B. the unloading point, and no other charges will be included. The Department will not pay for any changes in the proportions of the aggregates.

The Department will not make additional payment for concrete slab placed in excess of Plan thickness.

The Department will not pay for any concrete base removed by order of the Engineer for deficiency in thickness or for otherwise not meeting Specification requirements.

The Department will pay for work required to prepare the subgrade or sub-base in accordance with **306.05**.

B. Thickness Adjustments

Where the average thickness of base is deficient in thickness by more than 1/4 inch, but not more than 1 inch, the Department will pay an adjusted price as specified in the Table 306.10-1.

Table 306.10-1: Concrete Base Deficiency

Deficiency in Thickness as Determined by Cores (inches)	Proportion of Concrete Price Allowed
1/4	100%
> 1/4 through 1/2	75%
> 1/2 through 3/4	60%
> 3/4 through 1	50%

Where the thickness of base is deficient by more than 1 inch and, in the Engineer's judgment, the area of such deficiency should not be removed and replaced, the Department will not make payment for the area retained.

307.01

SECTION 307 – BITUMINOUS PLANT MIX BASE (HOT MIX)

307.01 Description	242
307.02 Materials	242
307.03 Composition of Mixtures	243
307.04 Equipment	249
307.05 General	249
307.06 Preparing the Subgrade, Sub-base, or Surface	249
307.07 Thickness and Surface Requirement	250
307.08 Method of Measurement	250
307.09 Basis of Payment.....	250

DESCRIPTION

307.01 Description

This work consists of constructing one or more base course layers of aggregate and asphalt, prepared in a hot bituminous mixing plant and spread and compacted on a prepared subgrade, granular sub-base, or base.

MATERIALS

307.02 Materials

Provide materials as specified in:

Aggregate for Mixture, Grading A, ACRL, AS, B, BM, BM2, C, CS, or CW.....	903.06
Asphalt Cement, Grade PG 64-22, 70-22, 76-22, 82-22	904.01
Bituminous Additives	921.06.B

The specific grading of aggregate to be used will be specified in the Contract or shown on the Plans. The Engineer will accept mineral aggregate, bituminous material, and the plant mix in accordance with **407.02**.

307.03 Composition of Mixtures

A. General

The bituminous base and/or leveling course shall be composed of aggregate and bituminous materials. The hot plant mixes shall comply with the applicable requirements of **407.03**.

Combine the specified mineral aggregate and asphalt cement in proportions that will meet the design composition limits specified in Table 307.03-1.

Table 307.03-1: Mixture Composition

Mixtures	Proportions of Total Mixture, Percent by Weight	
	Combined Mineral Aggregate, %	Asphalt Cement, % ⁽¹⁾
Grading AS and ACRL	96.3 - 97.7	2.3 - 3.7
Grading A	95.8 - 96.7	3.3 - 4.2
Grading B, BM, and BM2	93.8 - 95.8	4.2 - 6.2
Grading C and CW	93.8 - 95.8	4.2 - 6.2
Grading CS	92.3 - 94.7	5.3 - 7.7

⁽¹⁾ If the effective combined specific gravity of the aggregate exceeds 2.80, the Engineer may adjust the proportions specified.

In addition, combine the materials with the required amount of bitumen to meet the design properties specified in Table 307.03-2, except that on low volume roads (ADT 1,000 or below), the minimum stability shall be 1,500 pound-feet and the VMA and dust-asphalt ratio will be waived for 307-B, 307-BM, 307-BM2 and 307-C mixes.

Table 307.03-2: Mixture Design Properties

Mix ⁽¹⁾	Stability (minimum) lbf ⁽²⁾	Design Void Content % ⁽²⁾	Production Void Content, % ⁽²⁾	VMA (minimum) % ⁽²⁾	Dust- Asphalt Ratio ⁽³⁾
307-B	2,000	4.0±0.2	3-5.5	11.5	0.6-1.5
307-BM	2,000	4.0±0.2	3-5.5	13.5	0.6-1.5
307-BM2	2,000	4.0±0.2	3-5.5	13.5	0.6-1.5
307-C	2,000	4.0±0.2	3-5.5	13.0	0.6-1.5
307-CS	2,000	3.0±0.5	1-5	---	---
307-CW	1,500	4.0±0.2	3-5	13.0	0.6-1.5

⁽¹⁾ To identify critical mixes and make appropriate adjustments, the mix design shall meet these design properties for the bitumen content range of Optimum Asphalt Cement ±0.25%.

⁽²⁾ Tested according to AASHTO T 245 with 75 blows with the hammer on each end of the test specimen, using a Marshall Mechanical Compactor.

⁽³⁾ The dust-asphalt ratio is the percent of the total aggregate sample that passes the No. 200 sieve, as determined by AASHTO T 11, divided by the percent asphalt in the total mix.

If the materials proposed for use do not meet the design criteria specified in Table 307.03-2, find other suitable sources of materials. If the material at the asphalt plant will not combine within the tolerances of the Job Mix Formula (JMF), provide a new design.

B. Recycled Asphalt Pavement and Recycled Asphalt Shingles

- 1. Recycled Asphalt Pavement (RAP).** The Contractor may use asphaltic concrete removed from a Department project or other State Highway Agency project by an approved method and stored in a Department approved stockpile. RAP combined with the appropriate aggregate, asphalt cement, and anti-strip additive when required shall produce a mixture that meets **903.06** and **307**. The Contractor may incorporate RAP in the mixes specified in Table 307.03-3.

Table 307.03-3: Mixtures Using RAP

Mix Type	% RAP (Non-processed) ⁽¹⁾	Maximum % RAP (Processed) ⁽²⁾	Maximum % RAP Processed & Fractionated ⁽³⁾	Maximum Particle Size (inches)
307-ACRL	0	00	-	-
307-AS	0	10	10	-
307-A	15	20	35	1-1/2
307-B	15	30	35	1-1/2
307-BM	15	30	35	3/4
307-BM2	15	30	35	3/4
307-C	15	30	35	3/8
307-CW	15	30	35	1/2
307-CS	0	15	25	5/16

(1) “Non-processed” refers to RAP that has not been crushed and screened or otherwise sized prior to its use.

(2) “Processed” refers to RAP that has been crushed and screened or otherwise sized such that the maximum recycled material particle size is less than that listed in Table 307.03-3 prior to entering the dryer drum.

(3) “Fractionated” refers to RAP that has been processed over more than one screen, producing sources of various maximum particle sizes (e.g., 3/4 to 1/2 inch, 1/2 inch to #4, etc.). The Contractor may use the larger percentages of fractionated RAP specified only if individual fractions of two different maximum particle size are introduced into the plant as separate material sources for increased control.

All mixes shall contain at least 65% virgin asphalt.

The Contractor shall obtain a representative sample from the recycled material stockpile and shall establish a gradation and asphalt cement content. The Contractor shall determine the gradation and asphalt content of the recycled material at the beginning of a project and every 2,000 tons thereafter. The stockpile asphalt cement content for all recycled material shall not vary by more than 0.8%. The stockpile gradation tolerance for all recycled material on each sieve is specified in Table 307.03-4.

307.03

Table 307.03-4: Stockpile Gradation Tolerance

Sieve Size	Tolerance
3/8 inch and larger	± 10%
No. 4	± 8%
No. 8	± 6%
No. 30	± 5%
No. 200	± 4%

The Engineer will accept the mixture for aggregate gradation and asphalt content in accordance with **407.20.B**.

Provide a special mix design with asphalt content in the range of 5 to 7% where 307-C Mix is used as a surface on the shoulder.

Perform sampling and testing of the planings as well as new materials for bid purposes, and for the submission of the Job Mix Formula (JMF) as specified in **407.03**. Submit all additives to the Engineer for approval at the same time other materials are submitted for design verification.

After mixing, verify the moisture content of the total mix is no more than 0.1% as determined by oven drying. Provisions for lowering the temperature because of boiling or foaming shall not apply.

- 2. Recycled Asphalt Shingles (RAS).** RAS may be included to a maximum of 3% of the total weight of mixture. The percentage of RAS used will be considered part of the maximum allowable RAP percentage. The ratio of added new asphalt binder to total asphalt binder shall be 65% or greater for all 307 mixes. Either the mix producer or the RAS supplier shall obtain a representative sample from the recycled material stockpile and establish a gradation and asphalt cement content as required. Determine shingle asphalt binder content according to AASHTO T 164 Method A, with a minimum sample size of 500 grams. Determine the gradation and asphalt content of the recycled material at the beginning of the Project and every 2,000 tons of recycled material used thereafter. The stockpile asphalt cement content for all recycled material shall not vary by more than 0.8%. All RAS material shall be processed

to a minimum 100% passing the 3/8 inch sieve and a minimum 90% passing the No. 4 sieve.

To conduct the gradation testing, air dry a 500 to 700-gram sample of processed shingle material, dry sieve over the 3/8-inch and No. 4 sieves, and weigh. For mix design purposes, the Contractor may use the aggregate gradation specified in Table 307.03-5 as a standard gradation instead of determining the shingle gradation according to AASHTO T 30.

Table 307.03-5: Standard Gradation (for Mix Design Purposes)

Sieve Size	Total Percent Passing
3/8 inch	100
No. 4	97
No. 8	95
No. 16	80
No. 30	60
No. 50	50
No. 100	40
No. 200	30

An aggregate bulk specific gravity (G_{sb}) of 2.650 may be used instead of determining the shingle aggregate G_{sb} according to AASHTO T 84. In addition, the effective binder available for mixing with additional aggregates shall be considered as 75% of the total binder content as determined by AASHTO T 164 and shall be the value listed as the RAS binder content on the JMF.

Scrap asphalt shingle shall not contain extraneous waste materials. Extraneous materials including, but not limited to, asbestos, metals, glass, rubber, nails, soil, brick, tars, paper, wood, and plastics, shall not exceed 0.5% by weight as determined on material retained on the No. 4 sieve. To conduct deleterious material testing, take a representative 500 to 700-gram sample of processed shingle material, place over the No. 4 sieve, and pick and weigh all extraneous waste material retained on the No. 4 sieve. Base the percent of extraneous material on the total sample weight.

307.03

RAS shall contain less than the maximum percentage of asbestos fibers based on testing procedures established by the Department, or State or Federal environmental regulatory agencies. Analyze a minimum of one sample of processed asphalt roofing material for every 500 tons of material processed for the presence of asbestos.

Before a JMF for a particular design is approved, submit the following, along with the materials and information specified in **407.03**:

- a. Certification by the processor of the shingle scrap describing the shingle scrap content and source.
- b. A 1000-gram sample of the processed RAS material for inspection (new designs only).

Stockpile RAS separate from other salvage material. Do not blend RAS material in a stockpile with other salvage material. Do not blend Manufacture Waste Scrap Shingles (MWSS) and Tear-Off Scrap Shingles (TOSS). In addition, do not blend virgin sand material with the processed shingles, to minimize agglomeration of the shingle material.

All RAS supplied to a Department project shall come from a certified shingle processor/supplier approved by the Division of Materials and Tests.

C. Anti-Strip Additive

Check asphaltic concrete mixtures (Grading A, AS, ACRL, B, BM, BM2, C, CS, and CW) for stripping by the following methods:

1. The Ten Minute Boil test for dosage rate and the Root-Tunnecliff procedure (ASTM D4867) for moisture susceptibility.

Do not use the Root-Tunnecliff procedure (ASTM D4867) with the following mixtures: Grading A, AS, ACRL, and B.

2. For mixtures not requiring design, the Ten Minute Boil test for dosage rate and moisture susceptibility.

Mix an approved antistrip agent with the asphalt cement at the dosage as specified in **921.06.B**.

EQUIPMENT

307.04 Equipment

Provide equipment as specified in **407.04** through **407.08**.

If using recycled mix, modify the asphalt plant as approved by the Engineer to accommodate the addition of asphalt plantings. If using a batch plant to produce recycled mix, heat the aggregate to a temperature that will transfer sufficient heat to the cold plantings to produce a mix of uniform temperature within the specified range.

CONSTRUCTION REQUIREMENTS

307.05 General

Conform to the construction requirements specified in **407.09** and **407.11** through **407.17**.

307.06 Preparing the Subgrade, Sub-base, or Surface

The Plans will indicate whether the plant-mixed base is to be constructed on a treated or untreated subgrade or sub-base, on a granular base, or on an existing surface. Ensure that the surface upon which the plant mix base is to be constructed meets **205**, **207**, **302**, **303**, **304**, or **309**, whichever is applicable. If shown on the Plans, condition the surface as specified in **407.10**. Condition existing mineral aggregate base as specified in **310**. Construct prime coat or tack coat as specified in **402** or **403**, respectively.

Do not place AS/ACRL which cannot be covered by the next course of pavement within the same construction season.

Only place bituminous plant-mix base mixture on a surface that is dry and free of loose particles and other undesirable materials.

307.07

307.07 Thickness and Surface Requirement

Control thickness during the spreading operation by frequently measuring the freshly spread mixture to establish a relationship between the uncompacted mixture and the completed course. Thickness or spread rate in pounds per square yards shall be within reasonably close conformity with that shown on the Plans. Each course shall have a thickness after compaction of not more than 4 inches, unless otherwise approved by the Engineer.

The surface of the base shall meet the requirements specified in **407.18**, and when tested in accordance with **407.18**, the deviation of the surfaces from the testing edge of the straightedge shall not exceed the amounts specified in Table 307.07-1.

Table 307.07-1: Maximum Surface Deviation

Mixture	Maximum Deviation (inches)
Grading A, ACRL, and AS	1/2
Grading B, BM, BM2, C, CS, and CW	3/8

COMPENSATION

307.08 Method of Measurement

The Department will measure Mineral Aggregate, including Mineral Filler when required, and Asphalt Cement for Bituminous Plant Mix Base and other related items in accordance with **407.19**.

307.09 Basis of Payment

The Department will pay for accepted quantities at the contract prices in accordance with **407.20**.

For bidding purposes, use the asphalt cement content specified in Table 307.09-1 for the designated mix.

Table 307.09-1: Asphalt Cement Content

Mix Type	Asphalt Content
307 A	4.0%
307 AS	3.5%
307 ACRL	3.5%
307 B	4.3%
307 BM	5.0%
307 BM2	5.0%
307 C	5.0%
307 CW	6.0%
307 CS	6.5%

If the Engineer sets an asphalt content other than that specified in Table 307.09-1, the Department will calculate a price adjustment, based on the asphalt content set by the Engineer and the Monthly Bituminous Index for the specific grade asphalt on the mix design, in accordance with **407.20**.

309.01

**SECTION 309 – AGGREGATE-CEMENT BASE
COURSE**

309.01	Description	252
309.02	Materials	252
309.03	Equipment	253
309.04	Limitations	254
309.05	Preparing the Existing Subgrade	254
309.06	Cement Application, Mixing, and Spreading	254
309.07	Compaction	255
309.08	Finishing	256
309.09	Construction Joints.....	256
309.10	Thickness and Surface Tolerances	256
309.11	Curing	256
309.12	Traffic and Maintenance	256
309.13	Method of Measurement	257
309.14	Basis of Payment.....	257

DESCRIPTION

309.01 Description

This work consists of constructing a base of mineral aggregate and Portland cement on a prepared surface.

MATERIALS

309.02 Materials

Provide materials as specified in:

Water.....	302.03.B
Portland Cement, Type I.....	901.01
Portland-Pozzolan Cement, Type IP	901.01
Crushed Stone or Slag, Grading D	903.05
Aggregate, Crushed or Uncrushed Gravel or Chert	903.15

Recycled Concrete Aggregate.....	903.05.C
Bituminous Material for Curing, Emulsified Asphalt, Types allowed for Tack Coat in 403	904.03

Provide emulsified asphalt, of a type allowed for Tack Coat in **403**, meeting the test requirements specified in Table 904.03-1.

Submit a sample of the cement and aggregate to be used to the Materials and Tests Laboratory for approval at least 15 days before use.

EQUIPMENT

309.03 Equipment

Provide a stationary mixing plant or mechanical road mixer(s).

A. Stationary Mixing Plant

Provide an approved twin-shaft pugmill as specified in **303.06.A**.

The cement feeder shall include a surge tank between the cement supply and the pugmill. The feeder system shall be so designed that the aggregate feeder will not operate unless the cement feeder operates. During production of aggregate cement base, do not use the plant for other operations. The plant shall be capable of weighing each component and adjusting for moisture in the aggregates. Plants shall be calibrated annually and in the presence of the Engineer if requested.

B. Mechanical Mixer (for Road Mixing)

Provide pugmill or rotary type mechanical mixers capable of producing a uniform blend of all materials to the full depth of the course being placed. At least one mixer shall be capable of adding a regulated amount of water under pressure and uniformly mixing it with the aggregate and cement. The mixers may be either self-propelled or trailer type.

309.04

CONSTRUCTION REQUIREMENTS

309.04 Limitations

Only process the amount of aggregate-cement base that will be covered with the succeeding stage of base or pavement construction during the same construction season. Do not process aggregate-cement base unless the ambient air temperature is at least 40 °F in the shade and rising. Only add cement to aggregate that is free of frost, whether the aggregate is stockpiled for plant mixing or spread for roadway mixing.

For roadway mixing, limit application of cement to an area that will allow for continuous operations and for the completion of all but the final surface finish within 3 hours from the time cement is applied.

When using a stationary mixing plant, spread the material, using approved mechanical spreaders, within 1 hour after being discharged from the mixer. Complete all operations except final surface finishing within 3 hours after the material is discharged from the mixer.

Continue processing the uncompacted aggregate-cement mixture with no delay of more than 30 minutes. If the uncompacted aggregate-cement mixture is wetted by rain so that the average moisture content exceeds the specified tolerance, reconstruct the section as specified in **304.13**.

309.05 Preparing the Existing Subgrade

Before beginning other construction operations, prepare the subgrade as specified in **205**, **207**, or **302**, whichever is applicable.

309.06 Cement Application, Mixing, and Spreading

The quantity of cement to be added to the aggregate shall range between 3% and 5%, by weight, of the dry material. The Engineer will establish the exact percentage of cement within the above range based on test results, provided by the Contractor, of the aggregate selected for use on the project.

A. Roadway Mixing

Spread the aggregate on the subgrade to the required thickness, width, and cross-section using an approved mechanical spreader. Uniformly apply the specified quantity of Portland cement over the spread

aggregate using an approved mechanical cement spreader. Do not apply cement if the moisture content of the aggregate exceeds by more than 4% the optimum moisture content specified by the Engineer for the aggregate-cement mixture. Replace spread cement that has been lost due to the Contractor's negligence at no additional cost to the Department.

Perform road mixing using mechanical mixer(s). At least one pass of the mixer may be required before adding water. When required, add water through the mixer or by other approved methods to bring the mixture to the required moisture content. Continue mixing until a uniform mixture is obtained.

B. Stationary Mixing Plant

If using a stationary plant, continue mixing until a uniform and intimate mixture of cement, aggregate, and water has been obtained. All material fed into the plant shall travel the full length of the pugmill. Periodically check the quantity of cement expended by emptying the cement storage bin. Transport the mixture from the plant to the road in numbered trucks equipped with tight, metal, rear-end dump beds. Provide a sufficient number of trucks to ensure satisfactory progress of the construction operations. Use an approved mechanical spreader to spread the material. In mixing, handling, and placing the base material, take care to prevent segregation.

Place shoulder material for a width of at least 3 feet before spreading the base material in order to confine the base material and allow satisfactory compaction along the edges of the base.

309.07 Compaction

The Contractor may use any type of compacting equipment that will produce the required result. At the start of compaction, the percentage of moisture in the mixture based on oven dry weight shall not vary more than 3% above or 1% below the specified optimum moisture. Extend rolling over the edges of the base material onto the shoulders.

The Department will divide the completed base into lots of approximately 10,000 square yards for density testing purposes, and will perform five density tests on each lot. The average dry density of each lot shall be not less than 95% of maximum density as determined according to AASHTO T 134, and no individual test shall be less than 92% of maximum density. Rework or replace material not meeting the specified density at no additional cost to

309.08

the Department. At the beginning of a project or at any time it is deemed advisable, smaller lots may be considered to evaluate rolling procedures or for other reasons as approved or directed by the Engineer.

309.08 Finishing

Perform finishing operations in the same manner as specified for soil-cement base construction in **304.09**.

309.09 Construction Joints

At the beginning of each day's construction, form a straight transverse construction joint by cutting back into the completed work to form a true vertical face.

Build aggregate-cement base for large, wide areas in a series of parallel lanes of convenient length and width meeting the approval of the Engineer. Form straight longitudinal joints at the edge of each day's construction by cutting back into the completed work to form a true vertical face free of loose or shattered material.

309.10 Thickness and Surface Tolerances

The Department will determine the thickness of the base by measuring test holes dug at random locations. The measured thickness shall not deviate from that shown on the Plans by more than plus 1-1/2 inches or minus 1/2 inch. Reconstruct or replace work found not to be within this tolerance as specified in **304.13**.

The surface of the completed base shall be in reasonably close conformity to the lines, grades, and cross-section shown on the Plans or established by the Engineer and shall have a satisfactorily smooth riding quality.

309.11 Curing

Perform curing of the finished base in the same manner as specified for soil-cement base construction in **304.12**.

309.12 Traffic and Maintenance

The Contractor may open portions of completed base to traffic as specified in **304.14**.

Maintain the completed base as specified in **304.15**.

COMPENSATION

309.13 Method of Measurement

The Department will measure:

1. Mineral Aggregate for Aggregate-Cement Base Course by the ton in accordance with **109**.
2. Earth moved to prepare the existing subgrade, in accordance with **309.05**, as provided for under the appropriate provisions of **203** and **207**.
3. Portland Cement incorporated in the work by the ton in accordance with **109**.
4. Bituminous Material used for curing seal by the ton in accordance with **109**.
5. Water used in mixing and finishing operations by the M.G. (1,000 gallons) using calibrated tanks or distributors, or accurate meters.

The Department will deduct the weight of total moisture, as determined by dry weights, of the base material at the time of weighing in excess of 3% of optimum moisture content.

The Department will not measure or pay for water added to emulsified asphalt used for curing.

309.14 Basis of Payment

A. General

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Mineral Aggregate	Ton
Portland Cement	Ton

309.14

Bituminous Material	Ton
Water	MG

When mixing is performed in a stationary plant, the Department will not pay for water. When road mixing is performed, the Department will pay for water added to the material during mixing at the direction of the Engineer.

B. Adjustments

Specific Gravity. In cases where the Bulk SSD specific gravity of the mineral aggregate exceeds 2.85, the Department will adjust the tonnage of mineral aggregate for payment by multiplying the tonnage of mineral aggregate used by a specific gravity of 2.85 and dividing by the higher specific gravity.

**SECTION 310 – CONDITIONING MINERAL
AGGREGATE BASE**

310.01 Description	259
310.02 Materials	259
310.03 Equipment	259
310.04 Conditioning	260
310.05 Surface Requirements	260
310.06 Method of Measurement	260
310.07 Basis of Payment.....	261

DESCRIPTION

310.01 Description

This work consists of reshaping and compacting an existing mineral aggregate base or surface.

MATERIALS

310.02 Materials

Provide materials as specified in:

Aggregate for Conditioning Base	903.05
Calcium Chloride, Type 1, Type 2 or Calcium Chloride Liquor	921.02

EQUIPMENT

310.03 Equipment

Provide motor graders and water distributors in the number necessary for satisfactory prosecution and completion of the work, as well as one or more rollers of a type and sufficient weight to obtain the required density and to seal the surface of the base course.

310.04

CONSTRUCTION REQUIREMENTS

310.04 Conditioning

Condition the existing base by applying water, blading, and compacting as directed by the Engineer. Scarify sections of existing base that are pot-holed to the full depth of the potholes. Scarify and shape warped and distorted sections as directed by the Engineer. Moisten the material as necessary, and mix, shape, and roll until the base is uniformly and thoroughly compacted. Continue applying water, blading, and rolling until a smooth, dense, well-bonded surface is obtained that meets the Engineer's approval.

The Department will divide the completed base into lots of approximately 10,000 square yards for density testing purposes, and will perform five density tests in each lot. The average dry density shall be not less than 100% of maximum density as determined according to AASHTO T 99 Method D, and no individual test shall be less than 97% of maximum density. Smaller lots may be considered when approved or directed by the Engineer.

Distribute calcium chloride, when specified, at the approximate rate of 1 pound per square yard and incorporate it in the base material during blading and rolling operations as directed by the Engineer.

If additional material is to be added to the existing base, lightly scarify the existing base, add the material, and condition the base as specified above.

310.05 Surface Requirements

The surface of the conditioned base shall be in reasonably close conformity with the lines, grades, and cross-sections shown on the Plans or as directed by the Engineer and shall provide a satisfactory riding surface.

COMPENSATION

310.06 Method of Measurement

The Department will measure:

1. Conditioning Mineral Aggregate Base by the linear mile, based on a horizontal measurement made along the median centerline of the Project for divided sections and along the centerline of the pavement for two-lane sections, excluding bridges.

2. Calcium Chloride by the ton in accordance with **303.14.D**.
3. Water by M.G. (1,000 gallons) using calibrated tanks or distributors, or accurate water meters.

If the Contract requires the construction of a mineral aggregate base and a surface course, the Department will not directly measure or pay for conditioning of the base but will consider this work to be incidental to the unit price bid for the base material.

If the Contract requires the addition of base material to sections or the entire length of a previously constructed base, the Department will not directly measure or pay for conditioning of the base on the sections where base material is added. Sections where base material is not added will be measured for payment by the linear mile.

If the Contract requires a surface to be constructed on a previously constructed base and no additional material is added to the base, the Department will measure and pay for conditioning of the base by the linear mile.

310.07 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Conditioning Mineral Aggregate Base	Linear Mile
Calcium Chloride	Ton
Water	MG

Payment for Conditioning Mineral Aggregate Base is full compensation for conditioning all base on interchanges, approaches, service roads, ramps, frontage roads, roadside rest areas, and all other base within the limits of the Project that requires conditioning to receive a succeeding stage of construction under the Contract.

312.01

**SECTION 312 – AGGREGATE-LIME-FLY ASH
STABILIZED BASE COURSE**

312.01 Description	262
312.02 Materials	262
312.03 Proportioning	263
312.04 Equipment	264
312.05 Limitations	266
312.06 Subgrade Preparation	266
312.07 Mixing.....	266
312.08 Spreading	267
312.09 Compaction.....	267
312.10 Finishing	267
312.11 Construction Joints.....	268
312.12 Thickness and Surface Requirements.....	268
312.13 Curing	268
312.14 Traffic and Maintenance	268
312.15 Method of Measurement	268
312.16 Basis of Payment.....	269

DESCRIPTION

312.01 Description

This work consists of constructing a base of mineral aggregate, hydrated lime, and fly ash.

MATERIALS

312.02 Materials

Provide materials as specified in:

Crushed Limestone Aggregate Type A, Grading C	903.05
Bituminous Material for Curing Emulsified Asphalt, Types allowed for Tack Coat in 403	904.03

Water	921.01
Lime.....	921.04

Provide emulsified asphalt, of a type allowed for Tack Coat in **403**, meeting the test requirements specified in Table 904.03-1.

Fly Ash shall meet the requirements of **921.15**.

312.03 Proportioning

Proportion the lime, fly ash, and aggregate to meet the limits specified in Table 312.03-1.

Table 312.03-1: Proportioning of Lime, Fly Ash, and Aggregate Mix

Material	Range of Percent by Weight of Total Dry Mix
Lime	3.5
Fly Ash	11.0
Aggregate	85.5

The mixture shall be within plus or minus 2% of the optimum moisture of the mixture, as determined according to AASHTO T 99, Method C (with replacement).

Design the mixture so that when compacted into cylinders, cured and tested according to ASTM C593, the cylinders will have a minimum average compressive strength of 950 psi and no individual test is lower than 800 psi.

At least 45 days before producing the stabilized mixture, submit the following for the Engineer's approval:

1. Mix design,
2. Statement naming the source and percentage of each component, and
3. Report showing the results of the applicable tests meeting the above requirements.

For material testing and verification of the mix design, submit component materials in the quantities specified in Table 312.03-2.

312.04

Table 312.03-2: Material Quantities for Mix Verification Testing

Material	Quantity (pounds)
Hydrated Lime	25
Fly Ash	50
Aggregate	200

The Engineer may choose to verify the mix design on an annual basis provided the properties and proportions of the materials do not change appreciably. Adhere to the approved proportions of material during the progress of the work. Do not change the source or character of any material without the Engineer's approval, which will be based on verification of the new mix design.

EQUIPMENT

312.04 Equipment

A. Mixing Plant

Provide a stationary or portable batch or continuous mix type mixing plant that is equipped to allow the Engineer to verify the component percentages at any time.

- 1. Stationary or Portable Batch Type Plants.** Equip mixing plants with batching devices and scales to proportion the individual components by weight. Ensure that such devices have the accuracy needed to maintain the material percentages, based on total dry weight, within the tolerances specified in Table 312.04-1.

**Table 312.04-1: Tolerances for Mix Components
(based on dry weight)**

Material	Tolerance
Hydrated Lime	± 0.25%
Fly Ash	± 0.75%
Water	± 2.0%

Equip stationary or portable batch type plants with scales as specified in **501.04.A.3**. Use separate scales and hoppers for weighing the aggregate and the lime and the fly ash; however, the fly ash may be weighed cumulatively in the weigh hopper with the lime, provided the lime is added first.

- 2. Continuous Type Mixing Plants.** Equip continuous type mixing plants with:
1. Metering devices and scales for proportioning the lime and fly ash by weight to meet the tolerances specified in Table 312.04-1;
 2. An out-of-range alarm system that will sound an audible alarm when the lime or fly ash is not within the established tolerances;
 3. A meter or other approved regulating device to control the flow of water into the plant in a manner that positively maintains a uniform moisture content in the mixture; and
 4. A separate, quick, and automatically operating on-off device to shut the water off instantly when the mixer stops.

Maintain an approved method of checking and calibrating the weighing system in an easily accessible location on the plant.

B. Rollers

Provide either pneumatic tire or vibratory type rollers as specified in **407.07**.

312.05

C. Spreader

Provide either a self-propelled or tractor-drawn spreader that can maintain a uniform rate of travel while spreading and of laying a lift of uniform consistency and thickness with proper grade control.

D. Haul Trucks

Transport the mixture from the central plant in clean trucks equipped with tight metal rear-end dump beds having a cover of canvas, or other suitable material, securely fastened on all sides of the truck bed, and of such size as to maintain the moisture content and prevent the loss of fines.

CONSTRUCTION REQUIREMENTS

312.05 Limitations

The Contractor may perform stabilization from March 1 through September 30, and may continue this operation from October 1 through November 30 provided that Type I Portland cement is substituted for the lime on a pound for pound basis. Do not perform stabilization when the aggregate or the surface on which the base course is to be placed is wet or frozen, when it is raining, sleeting, or snowing, or when the temperature is 40 °F or less. Do not begin processing operations for this material unless the air temperature in the shade is at least 40 °F and rising. Cover the aggregate-lime-fly ash stabilized base course with the succeeding stage of base or pavement construction before December 15.

312.06 Subgrade Preparation

Prepare the subgrade as specified in **205**, **207**, or **302**, whichever is applicable.

312.07 Mixing

Mix the aggregate with the proper amount of lime, fly ash, and water in an approved mixer. Continue mixing until a thorough and uniform mixture is obtained. Handle the aggregate in a manner that will prevent contamination and segregation. Ensure that the plant will discharge the mixture without undue segregation.

312.08 Spreading

After mixing, transport the material to the site while it contains the proper moisture content, and spread the material to the required thickness and cross-section using an approved spreader. If the required compacted depth of the base exceeds 8 inches, construct the base in two or more approximately equal layers. The maximum compacted thickness of any one layer shall not exceed 8 inches.

312.09 Compaction

The Contractor may use any type of compacting equipment that will produce the required result. At the start of compaction, the percentage of moisture in the mixture based on oven dry weight shall not vary more than 3% above or 1% below the specified optimum moisture. Extend rolling over the edges of the base material onto the shoulders.

The Department will divide the completed base into lots of approximately 10,000 square yards for density testing purposes, and will perform five density tests on each lot. The average dry density of each lot shall be not less than 100% of the maximum density as determined according to AASHTO T 99, Method C (with replacement), and no individual test shall be less than 97% of the maximum density. If the specified density is not obtained, rework or replace the material to comply with the density requirement at no additional cost to the Department.

The Engineer may employ a control strip and random sampling to evaluate and adjust the Contractor's compaction procedure.

Provide a sufficient number of compaction and finishing units to ensure that the initial compaction of the processed section of the stabilized base course is completed within 4 hours from the time the water is added at the mixer. The final finishing and compaction shall be within 8 hours from the time of mixing. The Engineer may extend this time if the material has not reached an initial set. If, for any reason, construction operations are delayed or suspended and the Engineer requires the removal and disposal of loose or uncompacted material, the Contractor shall perform this work at no additional cost to the Department. No aggregate-lime-fly ash base course may be salvaged.

312.10 Finishing

Perform finishing operations as specified in **304.09**.

312.11

312.11 Construction Joints

Construct joints as specified in **309.09**.

312.12 Thickness and Surface Requirements

Meet the thickness and surface requirements specified in **309.10**.

312.13 Curing

After finishing the aggregate-lime-fly ash base, seal the surface with one of the bituminous materials specified in **312.02**, applied by a pressure distributor at the rate of 0.10 to 0.25 gallons per square yard or as directed by the Engineer. Heat or otherwise prepare the bituminous material to ensure uniform distribution. Apply the material no later than 24 hours after completing finishing operations unless the Engineer determines that application should be delayed. Keep the finished base continuously moist until the bituminous curing seal has been applied. Maintain the curing material during a 7-day protection period so that all the aggregate-lime-fly ash base course will be covered effectively during this period. Until the mixture has cured for 7 days, only allow on the base the pneumatic-tired equipment required for applying the curing seal. However, provide ingress and egress for property owners before the 7-day curing period.

312.14 Traffic and Maintenance

The Contractor may open portions of completed base to traffic as specified in **304.14**.

Maintain the completed base as specified in **304.15**.

COMPENSATION

312.15 Method of Measurement

The Department will measure bituminous material for curing seal and the mineral aggregate, lime, and fly ash mixture by the ton in accordance with **109**.

The Department will deduct the weight of total moisture in the aggregate, as determined by dry weights, of the base material at the time of weighing in excess of 3% of optimum moisture. The Department will not measure and

312.16

pay for mixing water; however, it will measure and pay for water added on the road at the direction of the Engineer by the M.G. (1,000 gallons) in accordance with **109**.

312.16 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Mineral Aggregate	Ton
Lime	Ton
Fly Ash	Ton
Bituminous Material	Ton
Water	MG

If fly ash is substituted with cement it will not result in additional cost to the Department.

313.01

SECTION 313 – TREATED PERMEABLE BASE

313.01 Description	270
313.02 Materials	270
313.03 Composition of Mixtures	271
313.04 Equipment	271
313.05 Construction Requirements	272
313.06 Limitations	273
313.07 Surface Requirements	273
313.08 Tolerance in Pavement Thickness	273
313.09 Method of Measurement	274
313.10 Basis of Payment	274

DESCRIPTION

313.01 Description

This work consists of constructing treated permeable base, composed of either a mixture of aggregate, Portland cement, and water, or a mixture of aggregate with asphalt binder, on a prepared sub-base. The Contractor may use either cement treated or asphalt treated permeable base.

MATERIALS

313.02 Materials

Provide materials as specified in:

Portland Cement, Type I	901.01
Aggregate for Portland Cement Treated Mixture	903.03
Aggregate for Bituminous Treated Mixture	903.06
Asphalt Cement, Grade PG 64-22, 70-22, 76-22, 82-22	904.01
Liquid Membrane – Forming Compounds	913.05
Water	921.01

313.03 Composition of Mixtures

A. Portland Cement Treated Permeable Base

In accordance with **604**, submit a concrete mix design, meeting the requirements specified in Table 313.03-1, to the Engineer for approval.

Table 313.03-1: Mix Design Properties

Property	Value
Water-Cement Ratio	0.43 (approximately)
Portland Cement Content	≥ 282 lbs/yd ³
Compressive Strength at 7 days (AASHTO T 22)	≥ 500 psi

B. Bituminous Treated Permeable Base

Asphalt treated permeable base shall be Bituminous Plant Mix Base (Hot Mix) as specified in **307** and **407**. Use liquid asphalt at the rate of 3% by weight of the total mixture. Asphalt content shall be such that all aggregate is visibly coated. Submit a mix design to the Engineer for approval as specified in **407.03**. Recycled Asphalt Pavement (RAP) meeting the requirements of **307.03.B** may be incorporated into asphalt treated permeable base up to 10% by weight of the aggregate. Treated permeable base mixtures containing RAP shall contain at least 65% virgin asphalt binder. For RAP containing gravel as a coarse aggregate, the maximum allowable RAP content shall be 10%.

Mix an approved antistrip agent with the asphalt cement at the dosage as specified in **921.06.B**.

EQUIPMENT

313.04 Equipment

To construct Portland cement treated base, provide equipment meeting **501.04.A** and **501.04.B**.

To construct bituminous treated base, provide equipment meeting **407.04** through **407.08**.

313.05

The spreading equipment shall meet either **501.04.D.11** or **407.06**.

CONSTRUCTION REQUIREMENTS

313.05 Construction Requirements

Construct cement treated permeable base and asphalt treated permeable base as specified in **309** and **307** respectively, unless otherwise specified below.

A. Cement Treated Permeable Base

- 1. Consolidation and Finishing.** Immediately after placing the cement treated permeable base, compact the mixture using a steel wheel roller weighing not less than 6 tons. Continue rolling until maximum densification is achieved; immediately cease rolling if aggregate breakage occurs. Do not use vibratory rollers. Instead of using a steel wheel roller, the Contractor may place the cement treated permeable base with a high-density screed with dual tamping bars.
- 2. Curing.** Immediately after spreading and compacting operations, cover the entire surface and exposed edges of the cement treated permeable base with transparent or white polyethylene sheeting as specified in **501.18**, or a white pigmented wax base curing compound meeting AASHTO M 148.

Use polyethylene sheeting having a thickness of at least 4 mils and hold the sheeting in place for a minimum of 7 days using a method approved by the Engineer. Before placing the sheeting, thoroughly wet the surface of the cement treated permeable base.

Place wax-based curing compound at a rate of 0.04 to 0.05 gallons per square yard.

B. Asphalt or Cement Treated Permeable Base

From the time of placement until placement of the following pavement layer, protect the treated permeable base from severe weather conditions, particularly freezing rain, snow, and icing, and from contamination by dust, dirt, mud, or other fine-grained material. Remove and replace, at no additional cost to the Department, all portion(s) of the treated

permeable base that become contaminated to the extent that drainage is reduced or inhibited.

Do not allow traffic on the treated permeable base, except for equipment required to place the following layer of pavement, provided that it enters and exits as near as possible to the paving operation. Repair damage to the treated permeable base caused by the Contractor's equipment at no additional cost to the Department.

313.06 Limitations

If using asphalt treated permeable base, adhere to the limitations specified in **407.09**. Do not place any treated permeable base that cannot be covered by the next course of pavement within the same construction season.

313.07 Surface Requirements

The Department will test the finished surface of the treated permeable base with a 12-foot straightedge in both transverse and longitudinal directions. The finished surface shall be uniform and shall not vary by more than ½ inch from the lower edge of the straightedge. If the tested surface varies by more than ½ inch, adjust the surface to a new grade, as established by the Engineer, as follows:

1. Fill the low areas with Portland cement concrete during the concrete paving operation, or
2. Apply emulsified asphalt, RS-2, at a rate not to exceed 0.2 gallons per square yard, as determined by the Engineer, over the specified low areas, and fill the low areas with No. 8 mineral aggregate. Seat the size No. 8 mineral aggregate with a pneumatic tire roller.

313.08 Tolerance in Pavement Thickness

Place treated permeable base to the thickness designated on the Plans. Before beginning any further work, take core samples from the treated permeable base, at locations established by the Engineer, in accordance with **501.24** for verification of base thickness. Take core samples at locations determined and witnessed by a Department representative, and document on the appropriate form.

The Department will adjust the contract unit price in accordance with **501.26** if the base thickness is determined by the Engineer to be deficient.

313.09

COMPENSATION

313.09 Method of Measurement

The Department will measure treated permeable base by the square yards complete in place for the width and thickness specified.

313.10 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Treated Permeable Base	Square Yard

The Department will adjust payment in accordance with **501.26.B** for all base found to be deficient in thickness by more than ¼ inch. The Department will not make additional payment over the contract unit price for base that has an average thickness in excess of that shown on the Plans.

The cost of antistripping additive used in Bituminous Plant Mix (Hot Mix) will be included in the price of Treated Permeable Base.

If the Department orders any increase or decrease in the cement content of the Cement Treated Base from the approved mix design, the measurement and payment for this change will be computed in accordance with **501.25** and **501.26**.

The Department will consider the cost of taking cores for verification of pavement thickness to be included in the contract unit price of treated permeable base.

The Department will not allow additional compensation for leveling of the treated permeable base except on ramps that contain 4,500 square yards or less of Portland cement concrete pavement. The Department will measure and pay for additional concrete used on these ramps in accordance with **501.25** and **501.26**.

PART 4 – FLEXIBLE SURFACES

SECTION 401 – MINERAL AGGREGATE SURFACE	276
SECTION 402 – PRIME COAT.....	279
SECTION 403 – TACK COAT	284
SECTION 405 – BITUMINOUS SEAL COAT	288
SECTION 407 – BITUMINOUS PLANT MIX PAVEMENTS (GENERAL).....	296
SECTION 410 – BITUMINOUS PLANT MIX SURFACE COURSE (COLD MIX).....	348
SECTION 411 – ASPHALTIC CONCRETE SURFACE (HOT MIX) ...	352
SECTION 414 – EMULSIFIED ASPHALT SLURRY SEAL AND MICRO-SURFACING	363
SECTION 415 – COLD PLANING OF BITUMINOUS PLANT MIX PAVEMENTS	381

401.01

SECTION 401 – MINERAL AGGREGATE SURFACE

401.01 Description	276
401.02 Materials	276
401.03 Equipment	276
401.04 Construction Methods	277
401.05 Thickness and Surface Requirements.....	278
401.06 Method of Measurement	278
401.07 Basis of Payment.....	278

DESCRIPTION

401.01 Description

This work consists of furnishing and placing one or more courses of aggregates, and an admixture if required, on a prepared surface.

MATERIALS

401.02 Materials

Provide materials as specified in:

Aggregate, Type B.....	903.05.B
Calcium Chloride, Type I, Type 2, or Calcium Chloride Liquor.....	921.02

The Engineer will accept aggregate for gradation as specified in **303.02**.

EQUIPMENT

401.03 Equipment

Provide equipment as specified in **303.06**.

CONSTRUCTION REQUIREMENTS

401.04 Construction Methods

Obtain the Engineer's approval of the completed roadbed before placing any surface material upon it.

On projects not requiring placement of surface material over the entire width of the roadbed, blade sufficient subgrade material from the subgrade, forming windrows on the shoulders from which to complete the compacted shoulders to the required cross-section after completing the surface course.

The surface course material may be spread with mechanical spreaders, dumped in windrows, or end dumped. Use approved machine methods to spread material dumped in windrows or end dumped, taking care to destroy all compaction planes caused by dumping or hauling over the material.

Construct the mineral aggregate surface in layers as shown on the Plans, with spreading, machining, sprinkling, and compaction operations progressing until the work is in reasonably close conformity to the lines, grades, and cross-sections shown on the Plans or established by the Engineer. Construct and maintain the surface of each layer to produce a uniform texture and to firmly key the aggregate. Uniformly apply water over the surface material during compaction in the amount necessary to ensure proper consolidation.

Roll each layer using approved rollers until the surface is thoroughly compacted and approved by the Engineer. If the required compacted depth of the surface course exceeds 6 inches, construct the surface course in two or more layers of approximately equal thickness. The maximum compacted thickness of any one layer shall not exceed 6 inches; however, if using vibrating or other approved types of special compacting equipment, the Contractor may increase the compacted depth of a single layer of the surface course to 8 inches with the Engineer's approval.

If two or more sizes or types of aggregates are to be blended on the road, spread the different aggregates separately using an approved mechanical spreader that can be adjusted to spread the materials in the proper proportions.

After spreading the material, and additive if specified, perform mixing using an approved mechanical mixer that is capable of producing a thorough and intimate mixture of aggregates, additive, and water.

Incorporate calcium chloride, if required, as specified in **303.08.B**.

401.05

401.05 Thickness and Surface Requirements

The thickness and surface of the completed Mineral Aggregate Surface shall meet **303.12** and **303.13**.

COMPENSATION

401.06 Method of Measurement

The Department will measure:

1. Mineral Aggregate Surface by the ton in accordance with **109**.
2. Water added to the materials at the direction of the Engineer by the M.G. (1,000 gallons) using calibrated tanks or distributors, or accurate water meters.
3. Calcium Chloride by the ton in accordance with **303.14.D**.

When measuring Mineral Aggregate Surface, the Department will deduct the weight of all surface moisture on the aggregate at the time of weighing in excess of 8%.

401.07 Basis of Payment

The Department will pay for accepted quantities of Mineral Aggregate Surface, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Mineral Aggregate	Ton
Calcium Chloride	Ton
Water	MG

SECTION 402 – PRIME COAT

402.01	Description.....	279
402.02	Materials	279
402.03	Equipment.....	280
402.04	Limitations	280
402.05	Preparing the Surface.....	280
402.06	Applying Priming Material	281
402.07	Applying Cover Material	281
402.08	Maintenance and Protection.....	281
402.09	Method of Measurement	282
402.10	Basis of Payment.....	282

DESCRIPTION

402.01 Description

This work consists of applying bituminous material, and cover material if required, on a designated base.

MATERIALS

402.02 Materials

Provide materials as specified in:

Aggregate for Cover Material, Size 7, 8, or 78.....	903.13
Emulsified Asphalt, Grade AE-P, CAE-P, or tack coats in 403.02	904.03

When prime coat quantity is 6 tons or more, AE-P or CAE-P will be applied unless otherwise directed by the Department.

Apply Emulsified Asphalt, Grade AE-P or CAE-P, at a temperature range of 60 to 140 °F.

402.03

When prime coat quantity is less than 6 tons, the use of emulsions for tack coat in **403.02** will be permitted. Dilute all tack coat emulsions with water at 1 part water to 1 part emulsion.

EQUIPMENT

402.03 Equipment

Provide a power broom or other mechanical sweeping equipment, bituminous heating equipment, a water sprinkler, a pressure distributor, and such other equipment and small tools as may be required to perform the work in a satisfactory manner.

The distributor shall be designed, equipped, maintained, and operated so that bituminous material at even heat may be applied uniformly on variable surface widths at readily determined and controlled rates from 0.05 to 0.5 gallons per square yard, with uniform pressure, and with an allowable variation from any specified rate of plus or minus 0.02 gallons per square yard.

Distributor equipment shall include: a tachometer, pressure gauges, accurate volume measuring devices, a calibrated tank, a thermometer for measuring the temperature of the material in the tank, a power unit for the pump, and full circulation spray bars that are adjustable laterally and vertically.

CONSTRUCTION REQUIREMENTS

402.04 Limitations

When applying bituminous prime coat, adhere to the same seasonal and temperature limitations as those specified for the succeeding stage of construction. The Contractor may apply the prime coat to a surface that is slightly damp, but never to a wet surface.

402.05 Preparing the Surface

Prepare the surface to be primed as specified in **303** or **310**, whichever is applicable.

If delays in the priming operation occur, maintain or rework the prepared surface to meet the requirements of **303** or **310**, whichever is applicable, before resuming the priming operation.

402.06 Applying Priming Material

Before applying the treatment, obtain the Engineer's approval of all areas to be treated. Apply and spread the bituminous material uniformly over the width of the section to be primed using a pressure distributor. The surface to be primed shall be damp. Do not apply prime coat if there is standing water on the surface or if it has dried. If there is delay between preparing the surface and priming operation occur, lightly rewet the surface.

If using AE-P or CAE-P, the Engineer will designate the application rate within the extreme limits shown on the Plans. If using emulsion other than AE-P or CAE-P diluted at 1:1, the Engineer will designate the application rate of application 1.5 times the rate specified for AE-P or CAE-P.

Maintain the application temperatures within the ranges specified in **402.02**.

To correct areas containing an excess or deficiency of priming material, add blotter material or bituminous material, as directed by the Engineer.

Protect all structures and concrete surfaces from the bituminous material during construction.

402.07 Applying Cover Material

If the bituminous material fails to penetrate before the time the roadway must be used by traffic, spread dry cover material at a rate established by the Engineer, between 8 and 12 pounds per square yard, to prevent damage to the primed surface. Avoid applying an excess of cover material.

402.08 Maintenance and Protection

Maintain the prime coat and the surface intact until it has been covered by the wearing surface or the project is completed. Do not place any succeeding stage of construction upon the prime coat until it has properly cured.

Repair spots where the prime coat may have failed, due to disintegration of the underlying surface material or other reasons, as follows:

402.09

1. Lightly dampen the exposed areas.
2. Refill such areas with approved material and thoroughly compact to conform with the surrounding surface.
3. Apply bituminous prime material to the surface with a hand spray.

If this method cannot produce satisfactory repairs, fill the depressions with approved mixtures of bituminous material and fine aggregate, and compact the mixture to conform to the surrounding surface.

COMPENSATION

402.09 Method of Measurement

The Department will measure:

1. Bituminous material and cover material by the ton in accordance with **109**.
2. Water used at the direction of the Engineer to dampen the base before applying bituminous materials by the M.G. (1,000 gallons), using calibrated tanks or distributors, or accurate water meters. Water used to dilute emulsified asphalt for tack coat will not be measured.

The Department may use net certified weights as a basis of measurement for cover material aggregate, subject to correction for aggregate that is lost, wasted, or otherwise not incorporated in the Work.

402.10 Basis of Payment

The Department will pay for accepted quantities of Prime Coat, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Bituminous Material	Ton
Cover Material	Ton
Water	MG

402.10

If using emulsion other than AE-P or CAE-P, payment will be based on the undiluted weight of the emulsified asphalt. No payment will be made for the water required to dilute of the tack coat.

If the prime coat is damaged due to causes beyond the Contractor's control, the Department will pay, at the contract unit prices, for mineral aggregate and bituminous material used to repair the damaged areas as specified in **402.08**.

403.01

SECTION 403 – TACK COAT

403.01 Description	284
403.02 Bituminous Materials	284
403.03 Equipment	285
403.04 Preparing the Surface	285
403.05 Applying Emulsified Asphalt.....	285
403.06 Method of Measurement	287
403.07 Basis of Payment.....	287

DESCRIPTION

403.01 Description

This work consists of furnishing and applying emulsified asphalt to a previously prepared base or surface course to provide bond for a superimposed course.

MATERIALS

403.02 Bituminous Materials

Provide materials as specified in:

Emulsified Asphalt, SS-1, SS-1h, CSS-1, CSS-1h, TST-1P, CQS-1h, CQS-1hp, RS-1, CRS-1.....	904.03
Approved Trackless Tack.....	QPL

Apply tack coat at the temperature ranges specified in Table 403.02-1.

Table 403.02-1: Tack Coat Application Temperatures

Material	Temperature Range
SS-1, SS-1h, CSS-1, TST-1P, CQS-1h, CQS-1hp, and CSS-1h	70 to 160 °F
Approved Trackless Tack from the QPL	Per Manufacturer's Recommendation

Dilution of asphalt emulsion used for tack coat on hot mix asphalt paving projects after leaving the terminal is not allowed. Apply the emulsion as delivered from the terminal.

EQUIPMENT

403.03 Equipment

Provide a power broom, equipment for heating bituminous material, a pressure distributor meeting the requirements of **402.03**, and such other equipment and small tools as may be required to perform the work in a satisfactory manner.

403.04 Preparing the Surface

Prepare the designated surface as specified in **404.05**. Ensure that the surface is dry when applying tack coat.

403.05 Applying Emulsified Asphalt

A. Emulsified Asphalt

Immediately after cleaning the surface, apply emulsified asphalt with the pressure distributor at a rate, established by the Engineer, within the range of 0.05 to 0.10 gallons per square yard of applied emulsion. If the bituminous material is to be placed upon a milled surface, apply at a rate, established by the Engineer, within the range of 0.08 to 0.12 gallons per square yard of applied emulsion. When applying tack coat on freshly-placed asphalt, lower application rates may be permitted, provided a full coverage application is still achieved.

For slurry seal and microsurface, apply a tack coat of SS-1h, CQS-1h, or CQS-1hp emulsion. The tack coat shall consist of one part emulsion and three parts water. The application rate shall be 0.10 to 0.15 gallons per

403.05

square yard of the diluted emulsion. The Engineer will determine the actual application rate.

Protect the surfaces of trees and structures adjacent to the area being treated to prevent their being splattered or marred.

Allow the emulsified asphalt to break prior to paving the next course. Apply tack coat only so far in advance of the paving operations as is necessary to obtain this proper condition of tackiness. Protect the tack coat from damage until the next course is placed.

B. Test Strip

When setting up an initial roller pattern and density test strip for the first layer of asphalt mixture, prepare a tack coat test strip to demonstrate that the proposed equipment and methods will achieve proper application of tack coat.

For the test strip, apply the tack material at a rate of between 0.05 and 0.10 gallons of applied emulsion per square yard. If placing the bituminous material upon a milled surface, apply the tack material at a rate of between 0.08 and 0.12 gallons applied emulsion per square yard.

In all cases, ensure that the application will result in a minimum double overlap of the actual tack spray as it lands on the surface. Adjustment of the spray-bar and the nozzles may be necessary to achieve this minimum double overlap. Corn-rows or any other pattern that would result in less than double overlap coverage of the tack coat is not acceptable for the tack application. The goal is to have a very thin but uniform coating of asphalt left on the surface when the emulsion has broken.

Once the test strip has been demonstrated and approved by the Engineer, use the same procedure and application rates for the entire project or until another design is proposed and accepted.

C. Fog Sealing

When the Contract requires bituminous material for fog sealing of shoulders, provide emulsified asphalt meeting **403.02** or an item from QPL 40A. Apply diluted emulsified asphalt at a rate of 0.10 to 0.15 gallons per square yard based on a dilution rate of one part emulsified asphalt to one part water. This application may require two equal increments if run-off occurs.

COMPENSATION

403.06 Method of Measurement

The Department will measure Emulsified Asphalt for Tack Coat and Fog Sealing by the ton, as delivered from the terminal, in accordance with **109**. The Department will make no direct payment for water used to dilute Emulsified Asphalt for Fog Sealing.

403.07 Basis of Payment

The Department will pay for accepted quantities, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Emulsified Asphalt for Tack Coat	Ton
Emulsified Asphalt for Fog Seal	Ton

The Department will measure and pay for the work required to prepare the designated surface, as provided for under **403.04**, in accordance with the applicable Section or Subsection under which the work is performed.

405.01

SECTION 405 – BITUMINOUS SEAL COAT

405.01	Description	288
405.02	Materials	288
405.03	Equipment	289
405.04	Limitations	289
405.05	Preparing the Designated Surface	289
405.06	Application.....	290
405.07	Spreading and Rolling Aggregate	293
405.08	Shoulders.....	294
405.09	Maintenance and Protection	294
405.10	Method of Measurement	295
405.11	Basis of Payment.....	295

DESCRIPTION

405.01 Description

This work consists of constructing a bituminous seal coat consisting of one or more applications each of bituminous material and cover aggregate.

MATERIALS

405.02 Materials

Provide materials as specified in:

Mineral Aggregate, Size Nos. 7, 8, 78, 89	903.13
Mineral Aggregate	903.14
Emulsified Asphalt, CRS-2p.....	904.03

Apply seal coat at a temperature range of 60 to 140 °F.

EQUIPMENT

405.03 Equipment

Provide a power broom or other mechanical sweeping equipment, equipment for heating bituminous material, a pressure distributor meeting the requirements of **402.03**, two pneumatic-tire rollers, self-propelled mechanical aggregate spreading equipment that can be adjusted to spread accurately at the specified rate, and such other equipment and small tools as may be required to perform the work in a satisfactory manner.

CONSTRUCTION REQUIREMENTS

405.04 Limitations

Only apply bituminous material:

1. When the designated surface is dry, firm, and properly cured;
2. Between April 15 and October 1; and, unless otherwise directed,
3. When the ambient temperature in the shade and away from artificial heat is 70 °F or more.

405.05 Preparing the Designated Surface

Before placing seal coat, clean all surfaces to be sealed by sweeping with a motorized broom to remove any loose material. Clean depressions and cracks not reached by the power broom using hand brooms or pressurized air.

Remove pavement markers and adhesives. Abrade all types of existing pavement markings. Work shall be accomplished without the pavement being gouged or damaged and in a manner which ensures the bituminous treatment will adhere in all areas applied. Work shall be performed to the satisfaction of the Engineer.

Cover any utility installations to prevent adherence of the bituminous mixture. Suitable covering includes plywood disks, sand, craft paper, roofing felt or other approved methods. Remove the protective coverings before opening the road to traffic. The cost for these adjustments shall be included in the bid price for other items.

405.06

The Plans will indicate whether the surface is to be constructed on a treated or untreated subbase, a granular base, an asphalt base, or on an existing surface. The surface of the base or sub-base upon which the construction is to be placed shall meet the requirements of the applicable Section of Part 3, Bases and Subgrade Treatments, of these Specifications.

Condition existing surface, if called for on the Plans, as specified in **407.10**.
Condition existing mineral aggregate base as specified in **310**.

Construct and maintain Prime Coat or Tack Coat, if shown on the Plans, as specified in **402** or **403**, respectively.

405.06 Application

A. Applying Bituminous Material

Have all equipment calibrated prior to starting work. The TDOT inspector shall be present during calibration to determine aggregate spread rate and distributor rates. Distributor trucks shall have proper calibration of spray equipment. Spray nozzles should be clean, properly angled, and appropriately sized for the desired application rate. Stop work if the distributor is not applying material properly, such as gaps in application or streaking.

Place a 500-foot test strip for the bituminous seal coat at the beginning of the project to assure proper coverage and proper equipment calibration. The test section is to verify break time of emulsion and chip retention. The test strip shall be able to carry normal traffic within 3 hours. If normal traffic cannot be carried, the emulsion shall be adjusted and another test strip is required.

At least 14 working days before the scheduled start of construction of any bituminous seal coat, submit a sample of aggregate intended for use for the determination of the appropriate application rates of bituminous material and aggregate. Apply emulsified asphalt by pressure distributor at a uniform rate in accordance with Table 405.06-1 below. The exact rate will be established by the Engineer.

Table 405.06-1: Application Rates for Bituminous Material

Aggregate Size (per 903.22)	Aggregate Spread Rate (lb/yd²)	Emulsion Shot Rate (gal/yd²)
7	25 – 30	0.30 – 0.45
78	22 – 28	0.28 – 0.38
8	20 – 25	0.20 – 0.35
89	17 – 23	0.17 – 0.28

Before beginning each spread, place building paper across the roadway surface with the forward edge exactly coinciding with the end of the preceding covered spread. Start distributors on the paper, the width of which shall allow the full force of all nozzles to be in effect before the forward edge of the paper is reached. If required by the Engineer, also stop the spread on building paper. Remove the paper immediately after its use, and dispose of properly. Immediately correct all defects in application.

The length of spread of bituminous material shall not exceed that which trucks loaded with cover material can immediately cover.

The spread of bituminous material shall not extend more than 6 inches wider than the width covered by the cover material. Do not allow the bituminous material to chill or otherwise impair retention of the cover material.

Do not allow traffic on the bituminous material until it has been covered with mineral aggregate.

Treat areas that are inaccessible to the distributor with either hand sprays or pouring pots as directed by the Engineer.

B. Application of Double Bituminous Surface Treatment

1. First Application

Apply the first application of emulsified asphalt using pressure distributors at a uniform rate established by the Engineer within the range of 0.30 to 0.38 gallons per square yard. Apply each spread of bituminous material to not be more than 6 inches wider than the

405.06

width covered by the immediate spread of cover aggregate. Each width of spread shall not be less than half the surface to be treated.

Before beginning each spread, place building paper across the roadway surface with the forward edge exactly coinciding with the end of the preceding covered spread. Start distributors on the paper, the width of which shall allow the full force of all nozzles to be in effect before the forward edge of the paper is reached. If required by the Engineer, also stop the spread on building paper. Remove the paper immediately after its use, and dispose of properly. Immediately correct all defects in application.

Treat areas that are inaccessible to the distributor with hand sprays or pouring pots as directed by the Engineer.

If treating less than the full width of the roadway, do not spread the aggregate on the inside 6 inches of either the first or second application until the adjacent lane has been treated. Immediately following each application, uniformly cover the applied bituminous material with Size No. 7 mineral aggregate that is reasonably free of surface moisture.

Spread the aggregate at a rate between 24 and 30 pounds per square yard, as established by the Engineer, using a self-propelled mechanical spreader; except on short projects of ½ mile in length or less, self-propelled mechanical spreading equipment will not be required. Back the truck on the aggregate being spread, without driving on or over uncovered bituminous material.

The length of bituminous material spread shall not exceed that which trucks loaded with cover material can immediately cover.

2. **Second Application**

Apply the second application of emulsified asphalt in the same manner as the first application, at a uniform rate established by the Engineer within the range of 0.20 and 0.35 gallons per square yard.

Spread mineral aggregate, Size No. 8, in the same manner as the first spread at a rate established by the Engineer within the range of 16 to 28 pounds per square yard.

Immediately after each spread of cover aggregate, broom to achieve uniform coverage. Use a power source, which is independent of the drive train that propels the equipment, to power the revolving brooms of mechanical sweeping equipment. Place additional aggregate by hand on thin or bare areas.

405.07 Spreading and Rolling Aggregate

A. Spreading

Immediately after bituminous material has been applied, no more than two minutes, spread and embed the mineral aggregate cover in the bituminous material. Spread the aggregate as close to the application of bituminous material as is practicable, and cover each distributor load applied immediately. Aggregates shall be moistened and visually damp at the time of placement.

Spread the aggregate in accordance with the rates specified in Table 405.06-1. The exact rate will be established by the Engineer. Back the truck on the aggregate being spread, without driving on or over uncovered bituminous material. If treating less than the full width of roadway, do not spread the aggregate on the inside 6 inches of the bituminous spread until the adjacent lane is treated. Immediately after spreading the aggregate, perform hand-brooming to achieve uniform coverage. Place additional aggregate by hand on thin or bare areas.

The speed of the spreader shall be such that the aggregates are not rolling over, and starting and stopping of the spreader is minimized. Use of previously used (swept) aggregates is not permitted.

B. Rolling – Bituminous Seal Coat

Immediately after distributing the aggregate, roll the entire surface by moving in a longitudinal direction, beginning at the outer edges and progressing toward the center of the roadway, with each trip of the roller overlapping the previous trip by half the width of the rear wheel. The amount and sequence of rolling shall be as directed by the Engineer. Complete the initial rolling of the aggregate within 1 hour after applying the bituminous material.

Use power brooms to correct irregularities by sweeping the aggregates from areas of thick or heavy distribution to areas of thin or light distribution. Then continue rolling until the aggregate is thoroughly

405.08

embedded in the bituminous material. The Engineer may require additional rolling at a later date. Redistribute excess or loose aggregate that was thrown out of place.

Slow moving traffic may use the section or roadway upon which the aggregate has been spread.

C. Rolling and Curing – Double Bituminous Seal Coat

Immediately after spreading and brooming the cover aggregate, roll the entire surface, beginning at the edges and progressing to the center. Begin rolling within 30 minutes after spreading the aggregate. The amount and sequence of rolling shall be as directed by the Engineer.

Allow the first application of bituminous material and aggregate to cure for as long as deemed necessary by the Engineer before beginning the second application.

For the second application of bituminous material and cover aggregate, repeat the same rolling and curing procedures as required for the first application.

The Contractor may allow slow-moving traffic to use sections of the roadway where the bituminous material has been covered with mineral aggregate.

405.08 Shoulders

Restore shoulders that have been disturbed by the Contractor's construction operations at no cost to the Department. Remove all objectionable material placed on the shoulders by the Contractor as directed by the Engineer.

Construct shoulders, when specified, as provided for under **208**.

405.09 Maintenance and Protection

Maintain in a satisfactory condition each completed section of seal coat until the entire Project is complete. Maintenance shall include making repairs where failures occur, and maintaining the seal coat in a smooth uniform condition; and brooming, dragging, and rolling when required.

After the final application, maintain the work in a satisfactory condition for at least 10 calendar days. If all other requirements of the Contract have been fulfilled, the Department will not charge working time during the 10-day maintenance period against the Contract time.

For final cleanup, sweep up all excessive quantities of loose, dislodged cover aggregate that may have collected along the edge of the completed seal coat, and dispose of this material as directed by the Engineer.

COMPENSATION

405.10 Method of Measurement

The Department will measure Mineral Aggregate and Bituminous Material by the ton in accordance with **109**. The Department may use net certified weights as a basis of measurement for mineral aggregate, subject to correction for aggregate that is lost, wasted, or otherwise not incorporated into the Work.

405.11 Basis of Payment

A. General

The Department will pay for accepted quantities of Bituminous Seal Coat, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Bituminous Material	Ton
Mineral Aggregate	Ton

The Department will measure and pay for the work required to prepare the designated surface, as provided for under **405.05**, in accordance with the applicable Section or Subsection under which the work is performed.

B. Adjustments

Specific Gravity. In cases where the Bulk SSD specific gravity of the mineral aggregate exceeds 2.80, the Department will adjust the tonnage of mineral aggregate for payment by multiplying the tonnage of mineral aggregate used by a specific gravity of 2.80 and dividing by the higher specific gravity

407.01

**SECTION 407 – BITUMINOUS PLANT MIX
PAVEMENTS (GENERAL)**

407.01	Description	296
407.02	Materials	297
407.03	Composition of Mixtures	298
407.04	Bituminous Mixing Plant	312
407.05	Hauling Equipment	323
407.06	Bituminous Pavers and Material Transfer Devices	323
407.07	Rollers	325
407.08	Small Tools	326
407.09	Weather Limitations.....	326
407.10	Conditioning the Existing Surface	328
407.11	Preparing the Bituminous Material	328
407.12	Preparation of Aggregates.....	330
407.13	Mixing.....	330
407.14	Spreading and Finishing.....	331
407.15	Compaction	333
407.16	Joints	338
407.17	Pavement Samples	338
407.18	Surface Requirements	339
407.19	Method of Measurement	339
407.20	Basis of Payment.....	341

DESCRIPTION

407.01 Description

This Section **407** is applicable to all types of bituminous pavements of the asphalt plant mix type as described in **307**, **313**, and **411**. Deviations from these general requirements will be indicated in the specific requirements for each pavement type.

This work consists of constructing one or more courses of bituminous mixture on a prepared foundation in accordance with this Section **407** and the specific requirements of the pavement type under contract.

MATERIALS

407.02 Materials

Provide materials as specified in:

Aggregates	903
Mineral Filler	903.16
Bituminous Materials.....	904
Chemical Admixtures and Additives	921.06.B

Separate aggregate into coarse and fine aggregate stockpiles. If stockpiling of coarse aggregate causes segregation, separate into coarse and medium coarse stockpiles.

Store each size and type of aggregate in a separate pile, bin, or stall. Maintain the storage yard in an orderly condition, clearing a walkway between stockpiles that are not separated by partitions. Make the stockpiles readily accessible for sampling.

The Engineer will conditionally accept the mineral aggregate for quality in the stockpile at the producer's site. The Engineer may conditionally accept the bituminous material at the asphalt terminal. The Engineer will accept for aggregate gradation and asphalt cement content from hot bin samples or sample(s) taken from the completed mix at the asphalt plant after it has been loaded onto the trucks for transport to the Project.

If anti-stripping additive, other than hydrated lime, meeting **921.06.B.1** is required, use approved in-line blending equipment, as specified in **407.04.A.6**, to add it at the mixing plant or inject it at the asphalt terminal. Manufacturer's documentation that asphalt binders will continue to meet requirements listed in **904** after the anti-stripping additive is added shall be provided by the contractor with the mix design submittal. For mix designs submitted more than six months in advance, the documentation shall be resubmitted prior to use of the mix design with updated test results.

If the resurfacing plans call for a Performance Grade (PG) asphalt mix with properties greater than that of PG 64-22 and this is the only asphalt grade on the Project, the Contractor may use either the asphalt grade shown on the Plans or an asphalt grade equal to or better than PG 64-22 for driveways and business entrances unless otherwise directed by the Engineer. The Department will pay for this material at the same unit price as bid for the

407.03

asphalt or asphalt mix. Mark the material tickets “**FOR DRIVEWAYS AND BUSINESS ENTRANCES ONLY**” at the point of delivery.

If using a warm mix asphalt additive meeting **921.06.B.3**, use approved blending equipment to add it at the mixing plant, or deliver it premixed with the asphalt cement.

For 411-OGFC mixtures, include a stabilizing additive listed on the Department’s Qualified Products List (QPL). Do not use fiber pellets. Slag wool fiber or cellulose fiber shall be blown into the asphalt plant measured by a flow meter or sensing device that is accurate to within plus or minus 10% of the amount required. For batch plants, add fibers in to the pugmill or weigh hopper. For drum plants, place the fiber line 1 foot upstream of the asphalt binder line so that the fibers are captured by the asphalt binder before being exposed to high-velocity gases in the drum. The minimum additive for a slag wool fiber shall be 0.4% and the minimum for a cellulose fiber shall be 0.3% of the total mix. The addition of a stabilizing additive material (fiber) shall be included in the cost of the asphalt cement.

407.03 Composition of Mixtures

A. General

Develop a bituminous mixture composed of aggregate (coarse, fine, or mixtures thereof), mineral filler if required, anti-strip additive if required, and bituminous material. Ensure that the aggregate fractions are sized, uniformly graded, and combined in such proportions so that the resulting mixture will meet the grading and physical properties of the approved Job Mix Formula (JMF).

B. Gradation and Bituminous Material Requirement

The requested aggregate gradation and bituminous material percentages shown on the JMF shall be within the design ranges specified in **903**, **307**, and **411**, respectively. Establish a recommended asphalt cement content for all mixes, with the final optimum asphalt cement content to be determined by the Engineer.

C. Job Mix Formula (JMF)

1. **General.** At least 14 working days before the scheduled start of production of any asphaltic paving mixture, submit a proposed Job Mix Formula (JMF) and Laboratory Design in electronic form,

where applicable, prepared in accordance with the Marshall Method of Mix Design (Asphalt Institute, MS-2), as modified by the Department, or by Gyrotory Compaction (AASHTO T 312). Regardless of which method is used, prepare trial blends with at least four different asphalt contents (at least two above the optimum and two below the optimum).

When using the Marshall method of compaction, compact the specimens to 75 blows per side. When using the gyrotory method of compaction, compact specimens to 65 gyrations.

All 411-OGFC design procedures shall follow the most current version of National Asphalt Pavement Association (NAPA) Publication IS-115, "Design, Construction and Maintenance of Open-Graded Friction Courses" except where modified herein. Design the OGFC using a Marshall compaction hammer at 50 blows or a standard gyrotory compactor at 50 gyrations.

Provide the following information with JMF submittals:

- a. The specific project on which the mixture will be used.
- b. The source and description of all materials to be used in the mix.
- c. The gradations and approximate proportions of the raw materials as intended to be combined in the paving mixture.
- d. A single percentage of the combined mineral aggregate passing each specified sieve. Plot the combined aggregate gradation on a gradation chart with sieve sizes raised to the 0.45 power to ensure a well graded mix.
- e. The Loss on Ignition (LOI) results on the combined aggregate of the mixture used as a wearing course.
- f. The Bulk Specific Gravity, Apparent Specific Gravity, and absorption on the combined mineral aggregate in the paving mixture (AASHTO T 84 and T 85).
- g. The fractured face count and glassy particle count of the plus No. 4 material, if applicable.

407.03

- h. A single percentage of asphalt by weight of total mix intended to be incorporated in the completed mixture.
- i. The dosage rate and source of anti-stripping additive, if required, meeting the requirements of **921.06.B.1**, to be added to the asphalt.
- j. The maximum specific gravity of the asphalt mixture (AASHTO T 209).
- k. A single temperature at which the mixture is intended to be discharged from the plant.
- l. Evidence that the completed mixture will conform to all physical requirements specified in **903.06** and **307.03.A** or **903.11** and **411.03.B**; however, for mixes designed according to AASHTO T 312, the stability and flow requirements will be waived and the resistance to rutting requirements for surface mixtures must be met.
- m. The tensile strength ratio (TSR) indicating the stripping and moisture susceptibility characteristics of the mix.
- n. To identify critical mixes and make appropriate adjustments, the mix design shall meet the required design properties for stability, flow, voids in mineral aggregate (VMA), and production void content as specified in **307.03** and **411.03** at the bitumen content range of Optimum Asphalt Cement plus or minus 0.25%.

Establish the laboratory mix and compaction temperatures for the JMF in accordance with Table 407.03-1.

Table 407.03-1: Laboratory Mix and Compaction Temperatures

PG Binder Grade	Lab Mix Temperature (°F)	Lab Compaction Temperature (°F)
64-22, 67-22	Per temp./visc. Chart	Per temp./visc. Chart
70-22	320 – 345	295 – 320
76-22	320 – 345	305 – 330
82-22	320 – 345	305 – 335

Perform any additional laboratory testing of the mix using the laboratory mix and compaction temperatures listed on the approved JMF, with a tolerance of plus or minus 5 °F for each temperature.

A Certified Laboratory Technician shall prepare and sign the Laboratory Design. To be certified, the technician shall have completed the Marshall Method of Mix Design School conducted by the Department, including the written and lab performance testing.

2. **Revision of Job Mix Formula.** The approved JMF shall remain in effect until the Engineer authorizes a change in writing. The Contractor, at any time after construction has started, may request that the JMF be revised, provided evidence is shown that the revision is necessary, and the revised aggregate gradation will meet all applicable gradation requirements.

Submit a revised JMF if, during the test strip construction and mix design/production verification procedure, changes are made to the mixture to comply with the specified criteria.

Provide a new design for any change in source of materials.

Submit all requests for design mix adjustments, redesigns, and new design mixes in writing to the Engineer for approval.

3. **Resistance to Plastic Flow.** Include, with the submitted JMF, test data showing that the material as produced will meet **307.03.A** or **411.03.B** when tested according to AASHTO T 245. Determine the bulk specific gravity of the laboratory compacted bituminous mixture (Marshall specimens) according to AASHTO T 166. Mixes

407.03

designed according to AASHTO T 312 are exempt from AASHTO T 245.

For surface mixtures used on roads with greater than 5,000 ADT, designed with the gyratory compactor (AASHTO T 312), include sufficient raw materials (aggregate and asphalt cement) with the submitted JMF so that the Central Laboratory may conduct rut testing in accordance with AASHTO T 340. The maximum allowable rut depth shall be 0.35 inches for roads with greater than or equal to 10,000 ADT and 0.40 inches for roads with 5,000 to 10,000 ADT.

Base the percent voids in the total mix on the maximum specific gravity of the bituminous mixture (Rice Gravity) according to AASHTO T 209. Calculate the voids in mineral aggregate (VMA) using the effective specific gravity of the aggregates.

D. Contractor's Quality Control

1. **General.** Assume responsibility for the quality of construction and materials incorporated in the Work. Provide and maintain a quality control system that will provide reasonable assurance that all materials conform to specification requirements.

Conduct all quality control sampling and testing according to the approved Quality Control Plan and the Department's Policies on Sampling and Testing Procedures and Sampling of Asphalt Mixes for Verification of Laboratory Design. The requirements for the Contractor's quality control sampling and testing will remain in effect until final Project acceptance.

2. **Contractor Quality Control System.** Develop, implement, and maintain a quality control system that will provide reasonable assurance that all materials and products submitted to the Department for acceptance conform to the specified requirements.
 - a. **Quality Control Technician.** Ensure that a Quality Control Technician, who is currently certified by the Department as a Certified Asphalt Plant Technician, is present at the asphalt plant during mix production. If the Department finds that the Quality Control Technician cannot perform as required by the position, the Department will revoke the certification and require replacement with a certified technician.

- b. **Documentation.** Document all quality control procedures, inspections, and tests and make this information available for review by the Department throughout the life of the Contract. Maintain adequate records of all inspections and tests. The records shall indicate the nature and number of tests performed, the number and type of deficiencies found, and the nature of corrective action taken as appropriate.

The Contractor's documentation procedures will be subject to the review and approval of the Department before the start of the work and to compliance checks during progress of the work. Provide copies of all charts and records documenting quality control tests and inspections to the Engineer on a daily basis.

- c. **Charts and Forms.** Record all conforming and nonconforming inspections and test results on approved forms and charts, and keep these records current and complete. Maintain test results at the Contractor's plant site laboratory and make such records available to the Engineer at all times during the performance of the work. Chart test results for the various materials and mixtures on forms that meet the Engineer's requirements. Provide an example of each proposed chart and form to the Engineer. Supply all charts and forms to be used to record results.
- d. **Corrective Actions.** Promptly correct all errors, equipment malfunctions, process changes, or other assignable causes that have resulted or could result in the submission of materials, products, and completed construction that do not conform to the specifications.

If the Engineer finds that the Contractor is not controlling its process and is making no effort to take corrective actions, the Engineer will require that plant operations be ceased until the Contractor can demonstrate that it can and will control the process.

- e. **Laboratories with Measuring and Testing Equipment.** Provide a fully equipped laboratory at the production site as specified in **106.06**. This facility may be permanent or portable. Furnish the laboratory with the necessary testing equipment and supplies for performing Contractor Quality Control sampling and testing as well as Department Acceptance sampling and

testing. To assure accuracy, the Department will check the testing equipment periodically according to the Department's Procedure for Qualified Laboratories.

- f. **Sampling and Testing.** Sampling and testing methods and procedures to determine quality conformance of the materials and products shall be in accordance with **106.04**. Address in the Quality Control Plan the taking of samples for material characteristics and the plotting of the test results on control charts.
- g. **Alternative Procedures.** The Engineer may approve the use of alternative sampling methods, procedures, and inspection equipment if such procedures and equipment provide, as a minimum, the quality assurance required by the Contract. Before applying such alternative procedures, describe them in a written proposal and demonstrate, for the Engineer's approval, that their effectiveness is equal to or better than the Contract requirements.
- h. **Minimum Mixture Quality Control Testing.** During production of the mixture, provide material that conforms to the approved JMF. Perform testing on mixtures to confirm conformance to the acceptance criteria and the JMF as follows. Mixes with a project total of less than 1,000 tons are exempt from all verification testing requirements unless deemed necessary by the Engineer.
 - 1) **Start Up Testing.** Produce 500 tons of mixture at the beginning of production of each mixture to confirm that the mixture meets the follow requirements:
 - a) All mix requirements are within the tolerance defined in Table 407.03-2.
 - b) Gradation and Asphalt Content are within the tolerance for a 1.00 pay factor based on a single test per Table 407.20-2.

- c) The average density on the test strip meets the requirements for 100% payment per Table 407.15-1.

Sample mixture for startup testing from one of the first ten trucks loaded of any mixture to complete this testing. Provide a technician certified by the Department in Asphalt Mix Design to perform all start up testing. All testing shall be done under the Department's supervision. Present all test results to the Department for approval of the mix verification.

If any of the above criteria fail verification, cease production. Make adjustments to the process and produce no more than 100 tons to retest the mixture. Once the mixture passes verification full production may proceed. If the retest fails, submit a modified JMF to the Engineer.

All nonconforming mix produced during the test strip construction is subject to acceptance and pay adjustment or removal per **407.20**.

Table 407.03-2: Mix Design Requirements

Property	Value
Maximum Theoretical Gravity	± 0.025 of Mix Design Value
Voids in Total Mix	As noted for production in 307.03 and 411.03
Voids in Mineral Aggregate	Minimum as noted in 307.03 and 411.03
Marshall Stability	Minimum as noted in 307.03 and 411.03
Dust/Asphalt Ratio	As noted in 307.03 and 411.03

- 2) Production Testing.** Sample and perform testing for conformance of the mix to the JMF within the tolerances defined in Table 407.20-2 on a 1000 ton maximum lot basis throughout production. Consider the process to be out of control and cease plant operations if test results from a single lot fall below the 0.90 pay factor limit or consecutive

407.03

tests fall below the 0.95 pay factor as specified in Table 407.20-2. Make adjustments to the process and produce no more than 100 tons for testing purposes. If the retest fails, submit a modified JMF to the Engineer. The Department will not allow the project to resume unless some corrective action has been taken and documented. Once test results show results compliant with the 1.00 pay factor range full production may resume.

- 3) **Volumetric Testing.** On any project using modified asphalt cement, test all the mix design requirements per Table 407.03-2 for each half day of production. Record all results on control charts made available to the department. If results fall outside the tolerance established in Table 407.03-2 then the following applies:
 - a) Resample and retest.
 - b) If the retest meets the criteria continue on without interruption.
 - c) If the retest fails to meet criteria, cease production. Make adjustments to the process and produce no more than 100 tons for testing purposes. If this retest fails, submit a modified JMF to the Engineer. The Department will not allow resumption of the project unless some corrective action has been taken and documented. Once compliance is achieved, resume full production.
3. **Quality Control Plan.** At the beginning of each paving season, submit in writing the proposed Quality Control Plan for the Engineer's approval. Include in this plan the sampling, testing, and inspection activities, and the anticipated frequencies of each, which the Contractor will follow to maintain process control. This Quality Control Plan shall apply to all Department contracts for the calendar year. If a change is made to the Quality Control Plan during the year, communicate such changes to the Regional Materials Supervisor. Refer to the recommended series of sampling, testing, and inspecting activities shown in Table 407.03-3.

Table 407.03-3: Recommended Items for a Contractor Quality Control Plan

A. All Types of Plants

1. Stockpiles
 - a) Determine gradation of all incoming aggregates.
 - b) Inspect stockpiles for separation, contamination, segregation, etc.
 - c) Conduct a fractured face count when gravel is used as coarse aggregate.
 - d) Determine the percent of glassy particles in slag coarse aggregate.
 - e) Determine gradation and asphalt content of recycled asphalt pavement when used as a component material.
2. Cold Bins
 - a) Calibrate the cold gate settings.
 - b) Observe operation of cold feed for uniformity.
 - c) Ensure that bins have proper dividers to prevent materials from spilling over into adjacent bins.
3. Dryer
 - a) Observe pyrometer for aggregate temperature control.
 - b) Observe efficiency of the burner.
 - c) Determine the percent dust coating on plus 4 material.
 - d) Check dried aggregate for contamination due to incomplete combustion of fuel.
4. Hot Bins
 - a) Determine gradation of aggregates in each bin.
 - b) Determine theoretical combined grading.
5. Bituminous Mixture
 - a) Determine percent bitumen.
 - b) Determine mix gradation.
 - c) Check mix temperature.
 - d) Determine percent moisture in mix when recycled asphalt pavement is a component material.
 - e) Determine Loss-On-Ignition (LOI) of aggregates in mix where applicable.
 - f) Check the mix for uncoated aggregate.
 - g) Ensure that handling procedures do not contribute to segregation of the mix.

B. Batch Plants

1. Batch Weights – Determine percent used and weight to be pulled from each bin to assure compliance with the JMF.
2. Check mixing time (both dry and wet).
3. Check operations of weigh bucket and scales.
4. Document accuracy of all weighing and metering devices for:
 - a) Asphalt cement
 - b) Aggregate
 - c) Anti-strip additive

C. Drum Mixer Plant

1. Calibrate the cold feed and prepare a calibration chart for each cold gate.
2. Develop information for the synchronization of the aggregate feed and the bituminous material feed.
3. Determine moisture content of aggregate being fed into dryer.
4. Determine the percent dust coating on dried plus 4 material.
5. Check dried aggregate for incomplete combustion of fuel.
6. Document accuracy of all weighing and metering devices for:
 - a) Asphalt cement
 - b) Aggregate
 - c) Anti-strip additive

Consider the activities identified in Table 407.03-3 to be normal activities necessary to control the production of asphalt concrete at an acceptable quality level. However, note that depending on the type of process or materials, some of the activities listed may not be necessary, and in other cases, additional activities may be required. The frequency of these activities will also vary with the process and the materials. When the process varies from the defined process average and variability targets, increase the frequency of these activities as necessary to restore proper conditions.

Plot and keep up-to-date control charts for all Quality Control Sampling and Testing. Provide control charts for the following:

- (a) Extracted asphalt content
- (b) Mix gradation
- (c) Dust to asphalt ratio
- (d) Maximum theoretical gravity (when required)
- (e) Voids in total mix (when required)
- (f) Stability (when required)

Post all current control charts in the asphalt lab where they can be seen.

The Contractor is responsible for formulating all design mixes with the exception of plant mix seal coat mixes. No lab design is required for **307** Grading A, AS, and ACRL mixes. However, establish the anti-strip additive dosage rate and verify compatibility of mixture materials by the ten minute boil test as specified in **407.03.E.2**. Submit all Contractor-furnished design mixes to the Department for approval prior to their use. Provide process control of all materials during handling, blending, mixing, and placing operations.

If recycled asphalt pavement (RAP) is approved for use as a component material in a hot bituminous mixture, the Contractor's Quality Control Plan shall include determination of the gradation and asphalt content of the RAP material at a minimum frequency of 1 stockpile sample per 2,000 tons used in the mixture.

E. Testing Procedures

Conduct the Tensile Strength Ratio (TSR), Stripping, and Loss on Ignition (LOI) testing in accordance with the following:

1. **Tensile Strength Ratio.** Perform testing for stripping and moisture susceptibility of the mixture according to ASTM D 4867, Standard Test Method for Effect of Moisture on Asphalt-Concrete Paving Mixtures. For all mixtures requiring design, except OGFC, follow ASTM D4867. For OGFC follow ASTM D4867 except as noted:
 - a. Modify step 8.6.1 so that the three conditioned samples are subjected to a partial vacuum of 26 inches Hg for 10 minutes to whatever degree of saturation achieved.
 - b. Subject the 3 conditioned samples to one freeze thaw cycle per note 6 listed in ASTM D4867 8.7. except as noted.

407.03

- c. After 15h in freezer, remove samples and immediately immerse the still wrapped specimen in 77 °F water for 2 hours.
- d. After 2 hours remove specimen from water bath and remove wrapping from specimen then immerse sample in 140 °F water bath for 24 hours.

All specimens tested for stripping and moisture susceptibility shall meet the criteria specified in Table 407.03-4.

Table 407.03-4: Criteria for Stripping and Moisture Susceptibility

Asphalt Cement	Minimum Tensile Strength	Minimum TSR
Polymer Modified	100 psi	80%
Non-Polymer Modified	80 psi	80%
411 OGFC	50 psi	80%

2. **Ten Minute Boil Test (Stripping)**

- a. **Field Test.** Test the completed mix for stripping at the asphalt plant as follows:
 - 1) From a sample of the completed mix, visually select a minimum of 50 grams of the plus No. 4 material and place immediately in boiling water.
 - 2) Continue to boil for 10 minutes, pour off water, and place coated aggregate on a paper towel.
 - 3) Perform a visual inspection to verify that the coated aggregate shows no evidence of stripping.
- b. **Laboratory Test.** Determine the dosage rate for anti-stripping additive in the laboratory as follows:
 - 1) Wash and surface dry 50 grams of the mineral aggregate passing the ½-inch sieve and retained on the No. 4 sieve.

- 2) Thoroughly coat the selected aggregate with the blend by stirring the mixture heated to 250° F.
 - 3) Immediately place the material in boiling water.
 - 4) Continue to boil for 10 minutes, pour off water, and place coated aggregate on a paper towel.
 - 5) Perform a visual inspection to verify that the coated aggregate shows no evidence of stripping.
3. **Test for Percent Loss on Ignition (LOI) of the Mineral Aggregate in an Asphalt Paving Mixture.** Conduct Loss on Ignition Testing as follows:
- a. Obtain a representative aggregate sample and weigh approximately 600 grams into an assayer's fire clay crucible that has been ignited to constant weight. Place a cover on the crucible to prevent pop-out of aggregate while heating.
 - b. Ignite the covered crucible and its contents in a muffle furnace at 1742° F to constant weight (minimum of 8 hours).
 - c. Cool the crucible and contents to room temperature and weigh.

If the aggregate sample is obtained by extraction with a vacuum extractor, correct the weights before and after ignition for filter aid using the following equation:

$$\text{Percent loss on ignition} = \frac{(A - B) \times 100}{A}$$

Where:

A = weight of sample before ignition (corrected for filter aid)
 B = weight of sample after ignition (corrected for filter aid)

407.04

EQUIPMENT

407.04 Bituminous Mixing Plant

Provide sufficient storage space for each size aggregate. Keep the different sizes separated until they have been delivered to the cold elevator or belt feeding the dryer. Maintain the storage yard in a neat and orderly condition and ensure that the separate stockpiles are readily accessible for sampling.

Plants used to prepare bituminous mixture shall meet all requirements specified in **407.04.A**. In addition, batch mixing plants shall meet **407.04.B**, continuous mixing plants shall meet **407.04.C**, and dryer-drum mixing plants shall meet **407.04.D**.

A. Requirements for All Plants

Mixing plants shall be of sufficient capacity and so coordinated to adequately handle the proposed bituminous construction.

1. **Equipment for Preparing Bituminous Material.** Provide tanks that are equipped to heat and hold bituminous material at the required temperatures. The circulating system for the bituminous material shall be designed to ensure proper and continuous circulation during the operating period. Make provisions for measuring and sampling the storage tanks' contents.
2. **Feeders for Dryer.** For each size aggregate, provide separate feeders that can deliver the aggregates onto the belt going to the dryer in proper proportions. Use mechanical feeders with separate adjustable gates to feed each size aggregate onto the belt.

Provide adequate means to ensure a constant and uniform flow of material from each bin. Equip bins containing fine aggregate with vibrators if necessary.

Do not blend or mix different aggregates, or different sizes of the same aggregates, with clam shells, bulldozers, high lifts, or similar equipment.

Feed the aggregate into the dryer to obtain a uniform production and uniform temperature.

3. **Dryer.** The plant shall include a dryer or dryers that are capable of:
- a. agitating the aggregate continuously during the heating and drying process;
 - b. heating and drying all aggregates to the temperature required; and
 - c. supplying the mixing unit continuously at its operating capacity.

Ensure that dryers are constructed and operated so that aggregates will not be contaminated with unburned fuel.

4. **Screens.** Provide plant screens, capable of screening all aggregates to the specified sizes and proportions and having normal capacities in excess of the mixer's full capacity.

The Contractor may allow a consistent carry-over, not to exceed 20%, on any screen. If any bin contains more than 20% of material that is undersized for that bin, empty the bin and correct the cause of this condition.

Provide approved scalping screens on all dryer-drum mixing plants; additional screens will not be required.

5. **Bins.** Provide storage bins of sufficient capacity to supply the mixer when it is operating at full capacity. Arrange bins to ensure separate and adequate storage of appropriate fractions of the mineral aggregates. For each bin, provide overflow pipes of the size and at the location needed to prevent material from backing up into other compartments or bins. Provide each compartment with an outlet gate constructed so that, when closed, no leakage occurs. The gates shall be cut off quickly and completely. The bins shall be constructed to provide adequate and convenient approved facilities for obtaining representative samples of aggregate from the full flow of each compartment. These bins are not required in an approved Dryer-Drum Mixing Plant. When using mineral filler, provide separate dry storage and equip the plant to uniformly and accurately feed the filler into the mixer.
6. **Bituminous Control Unit and Anti-Stripping Additive (ASA) Systems.** Provide means for weighing or metering the bituminous

407.04

material to ensure the proper amount of material is added to the mix within the tolerance specified. Provide means for checking the quantity or rate of flow of bituminous material into the mixer.

Where required, use approved in-line blending equipment to add anti-stripping additive, other than hydrated lime, meeting **921.06.B**. Provide a storage tank for the ASA that can maintain a constant temperature without overheating the additive. Store the additive according to the manufacturer's recommendations and at a temperature of 150 °F or less. The in-line blending equipment on drum plants shall have a totalizing "flow meter" capable of measuring the actual flow rate within the production range of 0.00 to 1.00 gallons per minute at increments of 0.05 gallons. Batch plants shall have a totalizing flow meter that displays the total gallons of material dispensed. The dispenser and/or pumps shall be capable of adding the heat stable ASA within a tolerance of 10% of the specified rate.

7. **Thermometric Equipment.** Fix an armored thermometer, capable of reading an adequate temperature range, in the bituminous feed line at a suitable location near the charging valve at the mixer unit.

At the discharge chute of the dryer, also place an approved thermometric instrument that can register automatically or indicate the temperature of the heated aggregates. With the Engineer's approval, the Contractor may place the thermometric instrument within the fines bin.

Equip the plant with an approved automatic recording and regulating apparatus to control the temperature of the aggregates.

8. **Dust Collector.** Equip the plant with a dust collector constructed to uniformly waste or return to the dried aggregate all or any part of the material collected. Handle collected baghouse fines intended for recirculation into the mix as if it were mineral filler or feed by another suitable method approved by the Engineer. Provide means to calibrate and adjust the dust fed from a baghouse.
9. **Safety Requirements.** Provide adequate and safe stairways to the mixer platform and sampling points. Place guarded ladders to other plant units at all points requiring access to plant operations. Provide access to the top of truck bodies by a platform or other suitable device to allow the Engineer to obtain samples and mixture

temperature data. Provide a hoist or pulley system to raise scale calibration equipment, sampling equipment, and other similar equipment from the ground to the mixer platform and return. Guard and protect all gears, pulleys, chains, sprockets, and other dangerous moving parts. Provide ample and unobstructed space on the mixing platform. Maintain a clear and unobstructed passage at all times in and around the truck loading area. Keep this area free of drippings from the mixing platform.

10. **Field Laboratory.** Provide a Type B field laboratory as specified in **106.06**.
11. **Surge and Storage Systems.** The Contractor may use surge and storage systems if the Department approves each system before use, and if the systems are designed to limit differences between material discharged from the bin or silo and material discharged directly from the plant.

Equip the surge bins and storage silos with low and high mix level indicators. Place the low level indicator at a location on the bin or silo that has been predetermined to prevent segregation of the mix.

Arrange the conveyor system used with the surge bins or storage silos so that samples of the mix or dry material may be conveniently taken.

Ensure that storage silos are closed, insulated, and heated to prevent localized heating. The storage silo shall be capable of being sealed to prevent oxidation of the mixture. Equip surge bins with a rain cover capable of preventing water from entering the mix in the bin.

The Engineer will base approval of a surge or storage system on inspection and tests that indicate that the system is capable of conveying, retaining, and delivering the bituminous mixture:

- a. Within the tolerance ranges as set forth on the JMF;
- b. Without segregation; and
- c. Without balling or hardening.

407.04

The Engineer may withdraw approval of a surge or storage system if tests, inspections, or both indicate that the system is having a detrimental effect on the bituminous mixture.

The Engineer will reject bituminous mix found to be damaged in any way by the use of a surge or storage system.

Mount, under the loading hopper, platform truck scales that meet the requirements of **109** and that are capable of recording tare and gross weights.

12. **Warm Mix Asphalt Process Equipment.** The Contractor may modify plants to reduce production and placement temperatures as specified in **407.11.B**. Obtain the Department's approval before making plant modifications for warm mix asphalt production temperatures. Modifications shall not impair the plant's ability to maintain temperature control or mixture proportions.

Ensure that modifications made to the plant to reduce mixing temperatures meet the requirements listed for warm mix asphalt additives in the Department's Qualified Products List (QPL).

B. Requirements for Batching Plants

1. **Plant Scales.** Provide dial scales for weighing of all aggregates and mineral filler, in the suspended weigh box. Dial scales shall be of a standard make and of sufficient size to allow the numerals on the dial to be read at a distance of 25 feet. The dials shall be of the compounding type having a full complement of index pointers. The value of the graduation of scales shall be as specified in Table 407.04-1.

Table 407.04-1: Graduation of Scales

Aggregate Amount (pounds)	Scale Graduation
< 5,000	≤ 5 pounds
5,000 to 10,000	≤ 10 pounds
> 10,000	≤ 0.1% scale capacity

Do not use pointers that give excessive parallax errors. Locate dial scales to be in plain view of the operator at all times. When

bituminous material is measured by weight, equip the asphalt weigh bucket with a separate dial scale with a minimum graduation not greater than 2 pounds. All dial scales shall be accurate within a tolerance of 0.5%. Eliminate vibration by setting the scales on a separate foundation, if required. Provide each installation of scales with ten standard 50-pound weights meeting the requirements of the U.S. Bureau of Standards for calibrating and testing weighing equipment. Inspect scales as often as the Engineer deems necessary to ensure their continued accuracy.

Provide an approved automatic printer system that will print the weights of the material delivered, when the system is used in conjunction with an approved automatic batching and mixing control system. Provide a weigh ticket for each load as evidence of such weights.

2. **Weigh Box or Hopper.** Provide means for accurately weighing each size of aggregate and mineral filler in a weigh box or hopper suspended on scales. The weigh box or hopper shall be of ample size to hold a full batch without hand raking or running over. The gate shall close tightly so that no material can leak into the mixer while a batch is being weighed.
3. **Bituminous Control.** Provide a bituminous material bucket of a non-tilting type. The length of the discharge opening or spray bar shall be not less than $\frac{3}{4}$ the length of the mixer, and it shall discharge directly into the mixer. The bituminous material bucket, its discharge valve or valves, and spray bar shall be adequately heated. Steam jackets, if used, shall be efficiently drainable and all connections shall be so constructed that they will not interfere with the efficient operation of the bituminous scales. The capacity of the bituminous material bucket shall be at least 15% in excess of the weight of bituminous material required in any batch. Provide the plant with an adequately heated, quick-acting, non-drip, charging valve located directly over the bituminous material bucket. If the bituminous material is metered, the indicator dial shall have a capacity of at least 15% in excess of the quantity of bituminous material used in a batch. The meter indicator dial shall have a scale with divisions measuring in gallons equivalent to a weight sensitivity of 0.04% of the total batch weight. The meter shall be accurate within a tolerance of 0.5%. The controls shall be capable of being locked at any dial setting and automatically resetting to that reading after the addition of bituminous material to each batch. The

407.04

dial shall be in full view of the mixer operator. Automatically control the flow of bituminous material so that it will begin when the dry-mixing period is over. All of the bituminous material required for one batch shall be discharged in not more than 15 seconds after the flow has started. The size and spacing of the spray bar openings shall provide a uniform application of bituminous material the full length of the mixer. Provide the section of the bituminous line between the charging valve and the spray bar with a valve, and provide the spray bar with a valve and outlet for checking the meter when a metering device is substituted for a bituminous material bucket.

4. **Mixer.** Provide an approved twin pugmill type mixer, steam or hot oil jacketed, that is capable of producing a uniform mixture within the job mix tolerances and that is constructed to prevent leakage of its contents. Equip the mixer with a sufficient number of paddles or blades set in the “run around” order, and operate at such speed as to produce a properly and uniformly mixed batch. The depth of the material in the pugmill shall not be above the tips of the paddles. If not enclosed, equip the mixer box with a dust hood to prevent loss of dust.

The clearance of blades from all fixed and moving parts shall not exceed 1 inch unless the maximum diameter of the aggregate in the mix exceeds 1-1/4 inches, in which case the clearance shall not exceed 1-1/2 inches.

5. **Control of Mixing Time.** Equip the mixer with an accurate time lock to control the operations of a complete mixing cycle. It shall lock the weigh box gate after the charging of the mixer until the closing of the mixer gate, at the completion of the cycle. It shall lock the bituminous material bucket throughout the dry-mixing period and shall lock the mixer gate throughout the dry and wet-mixing periods. The dry-mixing period is defined as the time interval between the opening of the weigh box gate and the start of introduction of bituminous material. The wet-mixing period is the time interval between the start of introduction of bituminous material and the opening of the mixer gate. The control of the timing shall be flexible and capable of being set at intervals of 5 seconds or less throughout a total cycle of up to 3 minutes. As a part of the timing device, install a mechanical batch counter that is designed to register only batches that have been mixed for the full time interval. Set the time intervals in the presence of and at the direction of the

Engineer, who will then lock the case covering the timing device until a change is needed in the timing periods.

6. **Operator's Platform Observation House.** Equip the plant with a scale observer's house, mounted on or near the weigh platform and situated so that the aggregate and asphalt scales, asphalt thermometer, and pyrometer are plainly visible from within the house.

Using approved materials, soundly construct the house to have at least 45 square feet of floor space and to be air conditioned by a unit of at least 12,000 Btu. The Contractor may install all batch controls in the house. However, do not use the house for storage or purposes other than to house the batch controls, plant operator, and Department Inspector. If choosing not to move the plant controls into the house, situate it to provide the scale inspector with a full view of the control panel.

If the scale-observer's house is located on the asphalt plant, provide an adequate secondary means of escape in the event of fire or explosion.

The Department will consider the house to be part of the plant and will not directly pay for its construction and maintenance.

C. Requirements for Continuous Mixing Plants

1. **Aggregate Proportioning.** Provide the plant with means for accurately proportioning each size of aggregate. The plant shall have a feeder mounted under each compartment bin. Each compartment bin shall have an accurately controlled individual gate to form an orifice for measuring volumetrically the material drawn from each compartment. Equip bins with adequate tell-tale devices to indicate the position of the aggregates in the bins at the lower quarter points.

The feeding orifice shall be rectangular with one dimension adjustable by positive mechanical means provided with a lock. Provide indicators for each gate to show the respective gate opening in inches.

407.04

Ensure that mineral filler can be fed into the mixer continuously and uniformly in the proportion set out in the JMF, and in a manner satisfactory to the Engineer.

2. **Weight Calibration of Aggregate Feed.** Equip the plant with an approved revolution counter that is in satisfactory working condition. Provide means to calibrate gate openings by weighing test samples. Make provisions so that materials fed out of individual orifices may be bypassed to individual test boxes. Equip the plants to handle individual test samples weighing not less than 200 pounds. Provide accurate scales to weigh such test samples.
3. **Synchronization of Aggregate Feed and Bituminous Material Feed.** Provide positive interlocking control between the flow of aggregate from the bins and the flow of bituminous material from the meter or other proportioning device. This control may be achieved using mechanical means or any other positive method satisfactory to the Engineer.
4. **Mixer.** Provide a continuous mixer of an approved twin pugmill type, which is adequately heated and capable of producing a uniform mixture within the job mix tolerances. The paddles shall be adjustable for angular position on the shafts and reversible to retard the flow of the mix. The mixer shall have a manufacturer's plate indicating the net volumetric contents of the mixer at the several heights inscribed on a permanent gauge. Provide charts showing the rate of feed of aggregate per minute for the aggregate being used. Determine the mixing time by the weight method, using the following formula (with weights determined for the job using tests conducted by the Engineer) where:

$$\text{Mixing time in seconds} = \frac{\text{Pugmill dead capacity in pounds}}{\text{Pugmill output in pounds per second}}$$

5. **Surge Hopper.** Equip the mixer with a discharge hopper with dump gates that will allow rapid and complete discharge of the mixture and of such size and design that no segregation of the mixture occurs.
6. **Platform Truck Scales.** Platform truck scales shall meet the requirements of 109.

D. Requirements for Dryer-Drum Mixing Plants

1. **Control of Aggregate.** Stockpile and handle aggregates to prevent any significant amount of segregation, contamination, or degradation. Construct stockpiles as specified in **903.20**.

Each aggregate shall have a separate feeder with a positive feed that can be easily and accurately calibrated. Provide a flow indicator and an audible warning device on each separate feeder to ensure a constant and uniform flow of aggregate from each bin onto the belt.

Feed mineral filler, if required, into the mixer continuously and uniformly in the proportion set out in the JMF and in a manner approved by the Engineer.

2. **Synchronization of Aggregate Feed and Bituminous Material Feed.** Provide satisfactory means to allow a positive interlocking control between cold aggregate feed and asphalt. Base the control setting for the asphalt flow on the dry weight of the aggregate. Provide an acceptable method for proportioning asphalt flow as variations in aggregate flow take place. Provide a metering system to measure the flow of asphalt into the drum, and locate an approved method of checking and calibrating the metering system in the control house. Provide an automatic interlock system that will shut off the asphalt flow and the burner when the aggregate flow ceases.
3. **Temperature Control.** Provide dryer-drum mixing plants equipped with a recording pyrometer or other approved thermometric instrument sensitive to a rate of temperature change of not less than 10 °F per minute. The system shall be equipped with automatic burner controls and shall provide for temperature sensing of the bituminous mixture at discharge from the drum.
4. **Scales and Metering Systems.** Provide weights and charts for checking the accuracy of the belt scales and the bituminous metering system. The scales and meters shall be accurate within a tolerance of 0.5%.

The belt scale that weighs the combined aggregate shall be in accordance with the National Institute of Standards and Technology Handbook 44.

407.04

5. **Sampling Devices.** Use an approved method for sampling individual cold feeds and sequential sampling of aggregate and asphalt under full scale production. The sampling device and procedures used shall be approved by the Engineer and shall not interrupt normal operation.
6. **Platform Scales.** Make certified platform scales available for checking the asphalt metering system and for weighing or checking loads of asphalt mix as specified in **109**.
7. **Silos or Surge Bins.** Provide surge bins or storage silos as specified in **407.04.A.11**. If a silo is not provided, use an approved surge bin capable of holding sufficient mix to allow the plant to operate at an efficient rate of production, and ensure the system is capable of conveying, retaining, and delivering the bituminous mixture so that it is within the JMF and without segregation. The Engineer will reject mix that is damaged in any way.

The surge bin may include an approved weighing system. If a weighing system is included in the surge system, provide approved weights for checking the weighing system. Check the system in maximum increments of 5,000 pounds and in a minimum of 3 increments. Check the system through its entire weighing range to or above the maximum weight that is expected to be applied. The system shall be accurate within a tolerance of 0.5%.

For surge bins that do not include a weighing system, mount platform truck scales meeting the requirements of **109** under the loading hopper.

8. **Aggregate Feed.** Proportion aggregate by feeding each size aggregate from a separate cold bin. The belt that delivers the aggregate shall have a load cell capable of registering the amount of flow from each individual bin on a readout in the control office; alternatively, the Contractor may proportion the aggregate by a linear system based on measured RPM of each feeder belt at a constant gate opening to feed aggregate at a predetermined rate that is set in the control office and that has a readout in the control office. Ensure that the rate of feed as determined from the bin settings agrees with the load cell on the collection belt feeding the dryer within a tolerance of plus or minus 10%. If the predetermined tolerance is exceeded, an alarm shall sound, and if corrections are not made within 60 seconds, the plant shall automatically shut down.

The aggregate feed system shall employ computer controlled adjustments to automatically produce mix of the correct proportions over the plant's entire range of production rates.

If the Engineer has previously calibrated and approved the plant for temporary manual operation, the plant may run for a period not to exceed 2 working days, or portions thereof, on manual should a computer breakdown occur.

9. **Electronic Data Retention.** The computer system and automatic weighing system shall include means to retain all electronic data during electrical power failures.

407.05 Hauling Equipment

Trucks used for hauling bituminous mixtures shall have tight, clean, smooth metal beds that have been thinly coated with a minimum amount of paraffin oil, hydrated-lime solution, or other approved material from the Department's QPL to prevent the mixture from adhering to the beds. Immediately after loading at the plant, cover each truck with a cover of canvas or other suitable material that is of sufficient size to protect the mixture from the weather. Allow the cover to lap down along the sides and rear of the truck bed a minimum of 6 inches, and use tie downs to secure the cover at a maximum of 5-foot spacing along the sides and rear of the truck bed. When necessary to ensure the mixture will be delivered on the road at the specified temperature, insulate truck beds and securely fasten the covers. Provide a 3/8-inch hole in both sides of each truck bed for inserting a thermometer.

407.06 Bituminous Pavers and Material Transfer Devices

A. Pavers

Bituminous pavers shall be self-contained, power-propelled units provided with an activated screed, equipped to be heated, and capable of spreading and finishing courses of bituminous plant mix material in lane widths applicable to the specified typical section and thickness shown on the Plans. All screed extensions shall be full assembly extensions, including activated and heated screeds. Pavers shall include throw-back blades, reverse augers, or equivalent to place mix beneath the auger gearbox. Auger extensions shall be incorporated in a manner such that the maximum distance from the augers to the end plate shall be 18 inches. Screed extensions may extend beyond the 18-inch maximum from auger extensions only when extending for short-term temporary deviations in

407.06

pavement width such as driveways. Do not use strike-off boxes, with the exception of sections with continuously varying width.

Equip the paver with a receiving hopper that has sufficient capacity for a uniform spreading operation. The hopper shall be equipped with a distribution system to place the mixture uniformly in front of the screed.

The screed or strike-off assembly shall produce a finished surface of the required evenness and texture without tearing, shoving, or gouging the mixture.

Equip all asphalt paving machines with automatic grade and slope controls. Both the grade and slope controls shall be in working order at all times; however, if the automatic controls fail, the Contractor may finish the day's work using manual controls, but shall not resume work the following day until both the grade and slope controls are in first class working order.

The Engineer may allow the Contractor to pave the inside shoulder concurrently with the inside traffic lane, subject to the Engineer's approval of the price adjustment for the mix used on the shoulder and of the paving and rolling equipment. In addition, the paver shall have an articulated screed that can be adjusted to fit the pavement cross-section and a power unit capable of handling the increased loading without undue stress.

B. Material Transfer Devices (MTDs)

Provide a Material Transfer Device (MTD) capable of transferring the asphalt from the truck or trailer to the asphalt paver without coming in contact with the asphalt paver. Use a MTD when placing all asphalt mixes, including shoulder mixes, with the exception that it will not be required when placing CS mix. An exception may be allowed due to lane width or safety issues if approved by the Engineer.

The MTD shall have a minimum storage capacity of 15 tons, and shall be equipped with mixing augers in the bottom of the storage hopper that are capable of remixing or re-blending the material as the material is removed from the storage hopper. The mixing augers shall be operational and used at all times during placement of the asphalt mixes. The MTD shall have a rear discharge conveyor that swivels a minimum of 150 degrees to allow feeding the paving machine from the front, side or rear.

Insert a stationary surge hopper into the paving hopper of the paver being fed by the MTD. The stationary surge hopper shall be considered as part of the MTD and shall have sloping sides (minimum of 60 degrees from horizontal) and a minimum storage capacity of 15 tons.

Obtain the Department's approval of models and manufacturers of MTDs before using on the Project. The Department will make no direct payment for use of an MTD and will consider all cost of furnishing and operating the MTD as incidental to the work.

407.07 Rollers

Provide self-propelled rollers, of steel-wheel, pneumatic tire, and/or vibratory type, which are in good condition and capable of reversing without backlash. Operate rollers at speeds slow enough to avoid displacement of the bituminous mixture. Equip rollers with a device for moistening and cleaning the wheels as required.

The required rollers shall be on the job, inspected, and approved before the start of paving operations.

Rollers shall meet the following additional requirements:

1. The steel-wheel roller shall weigh a minimum of 8 tons and may be either a three wheel or tandem type.
2. The pneumatic tire rollers shall have a minimum contact pressure of 85 pounds per square inch. The roller shall contain two axles upon which at least seven pneumatic-tire wheels are mounted to ensure the rear set of tires will not track the front set. The axles shall be mounted in a rigid frame provided with a loading platform or body suitable for ballast loading. Uniformly inflate the tires. Provide the Engineer with charts or tabulations of the contact area and contact pressures for the full range of tire inflation pressures and loadings for each size of roller tire provided. In place of a pneumatic tire roller, the Contractor may substitute a combination roller (pneumatic and steel wheel combination) of the make and model approved by the Department.
3. The Contractor may use vibratory rollers if the Engineer approves the particular roller proposed for use.

407.08

When paving the inside shoulder concurrently with the inside traffic lane, provide an additional roller, having a minimum width of 4 feet to a maximum width of 1 foot wider than the inside shoulder being paved, to compact the shoulder. Do not allow either the roller(s) on the inside traffic lane or the roller on the shoulder to traverse between the inside shoulder and the inside traffic lane.

407.08 Small Tools

Provide all necessary small tools, and keep them clean and free from accumulations of bituminous materials.

CONSTRUCTION REQUIREMENTS

407.09 Weather Limitations

The Contractor may place bituminous plant mix on properly constructed and accepted subgrade or previously applied layers if:

1. The subgrade and the surface upon which the bituminous plant mix is to be placed is free of excessive moisture, and
2. The bituminous plant mix is placed according to the temperature limitations specified in Table 407.09-1 and when weather conditions otherwise allow the pavement to be properly placed, compacted, and finished.

Table 407.09-1: Temperature Limitations

Compacted Thickness	Minimum Air or Surface Temperature (°F)	
	Unmodified mixes (PG 64, 67)	Modified mixes (PG 70, 76, 82)
≤ 1.5 inches	45	55
> 1.5 inches to < 3.0 inches	40	50
≥ 3.0 inches	35	45

3. Do not place bituminous plant mix, with a compacted thickness of 1.5 inches or less, between November 30 and April 1. Do not place

bituminous plant mix, with a compacted thickness greater than 1.5 inches, between December 15 and March 16. Only place 411-TL, 411-TLD, 411-TLE, and 411-OGFC mixtures when the pavement surface temperature and the ambient air temperature are a minimum of 55 °F and rising; limit placement to the period from April 1 to November 1. If the temperature meets the above requirements, outside of normal paving season, a request for a seasonal limitation waiver may be submitted for Departmental consideration. Requests shall be submitted in writing at least one week before the anticipated need.

4. If determined necessary by the Department, the Contractor may request a variance from the above required temperatures and seasonal limitations to pave at lower temperatures by submitting a Cold Weather Paving and Compaction Plan. All projects requiring a Cold Weather Paving and Compaction Plan shall utilize Intelligent Compaction to demonstrate proper coverage and compaction temperature at no additional cost to the Department; with the exception of small quantity projects, such as, but not limited to, bridge approaches, intersections, and temporary traffic shifts. Upon completion, the documentation showing appropriate coverage and compaction temperature shall be provided to the Department. Submit requests in writing at least one week before the anticipated need, and include a Cold Weather Paving and Compaction Plan that meets the Department's Procedure. The plan shall identify what practices and precautions the Contractor intends to use to ensure the mixture is placed and compacted to meet the specifications. The plan shall include compaction cooling curves estimating the time available for compaction, the intended production, haul, and compaction rates, with paver and roller speeds estimated. The Contractor may consider using such practices as the addition of rollers, reduced production and paving rates, insulated truck beds, and heating the existing surface.

In no cases will a Cold Weather Paving and Compaction Plan or seasonal limitation waiver be approved for 411-OGFC, 411-TL, 411-TLD, or 411-TLE.

If the specified densities are not obtained, stop all paving operations and develop a new plan. All mixture failing to meet specifications will be subject to price adjustments or removal and replacement at no cost to the Department.

407.10

407.10 Conditioning the Existing Surface

If bituminous mixes are to be placed upon an existing concrete pavement, with or without a bituminous overlay, remove all excess bituminous material from joints and cracks. Remove sections of existing pavement that are broken and pumping under traffic. Remove pavement where blowups have occurred at joints or cracks to provide a minimum opening of 1 foot for the full width of the pavement.

If the bituminous mixture is to be placed upon an existing bituminous pavement, remove areas containing excess bitumen and failures in the existing surface and base as directed by the Engineer.

Adjust all manholes and catch basin frames, which are associated with the storm sewer system, to the finished grades of the pavement. Unless otherwise specified, make such adjustments at no additional cost to the Department. The respective Utility Owner(s) will properly adjust all utility manholes, utility valve covers, and similar structures, to the finished grades of the pavement, unless otherwise shown on the Plans.

Remove unsatisfactory subgrade material encountered when removing the existing pavement and replace with approved material. Use overlay mixture or other approved material to fill openings left by the pavement and base removal to the full depth of the existing pavement, as directed by the Engineer, and compact the material in layers not to exceed 3 inches in thickness.

Paint contact surfaces of curbing, gutters, manholes, and other structures with a thin, uniform coating of bituminous material before placing the mixture against them.

When shown on the Plans, bring existing surfaces that are warped and irregular to uniform grade and cross-section using the leveling mixture specified in **307**.

407.11 Preparing the Bituminous Material

A. Hot Mix Asphalt (HMA)

Heat the bituminous materials for hot mixes to the required mixing temperature specified in Table 407.11-1.

Table 407.11-1: Mixing Temperatures

PG Binder Grade	Minimum Temperature (°F)	Maximum Temperature (°F)
PG 64-22, PG 67-22	270	310
PG 70-22	290	330
PG 76-22	290	330
PG82-22	290	330

Minimum temperature for OGFC mixes shall be 280°.

The temperature for Grading AS, Grading ACRL, and Grading TPB mixtures shall be between 225 and 275 °F, except when modified binders are used, and then the temperatures shall be between 250 and 310 °F. Aggregate should be coated, and no visible drain down should occur in storage silos or hauling equipment.

B. Warm Mix Asphalt (WMA)

The Contractor may subject the produced mixture to reduced production and placement temperatures by adding a chemical warm mix additive meeting **921.06.B.3** or by making plant modifications as specified in **407.04.A.12**.

When using either WMA technology, the maximum mixing temperature for any grade of asphalt cement shall be no more than 300 °F. At the beginning of a day's production, the producer may produce up to five truckloads at the temperatures specified in Table 407.11-1 to pre-heat placement equipment (pavers, transfer devices) before producing WMA. Indicate the laboratory mixing and compaction temperatures on the JMF during the mix design approval process. A tolerance of plus or minus 5.0 °F for each temperature will be allowed.

During test strip construction, ensure that all plant-produced WMA exhibits the ability to meet the test requirements for tensile strength ratio (TSR), conditioned tensile strength, Marshall Stability and flow, volumetrics, and boil test, as specified for HMA in specifications **307**, **407**, and **411**. Procedures for testing shall be in accordance with that which is defined for quality control and acceptance in **407.03.D.2.h** and **407.20.B.3**, respectively.

407.12

407.12 Preparation of Aggregates

Unless otherwise specified, dry and heat the aggregate for hot mixes to produce a completed mix of a uniform temperature as specified in Table 407.11-1. Adjust flames used for drying and heating to avoid damage to the aggregate and to avoid soot on the aggregate.

On all plants requiring screens, screen the hot dried aggregate into two or more fractions as specified. Convey the separated fractions into separate compartments ready for batching and mixing with bituminous material.

407.13 Mixing

Combine the dried aggregates within the mixer in the amount of each fraction of aggregates required to meet the JMF. Measure the bituminous material and introduce it into the mixer in the amount specified by the JMF.

After introducing the required amounts of aggregate and bituminous material into the mixer, mix the materials as long as necessary to obtain a complete and uniform coating of the particles and a thorough distribution of the bituminous material. The Engineer will determine wet-mixing time for each plant and for each type of aggregate used, but in no case shall the wet-mixing time be less than 25 seconds for batch type plants and 40 seconds for continuous mix plants.

The temperature of the completed mixture (determined at the time it is dumped from the mixer), made with aggregates containing absorbed moisture that causes foaming or boiling in the completed mix, shall be not less than 225 °F. The temperature of the mix when it is discharged from the mixer shall not deviate from that specified in **407.11.A**.

The Contractor may place hot-mixed bituminous mixtures in surge or storage silos if the mixture as used from the silos meets all the specification requirements for the particular mix involved.

When using surge or storage silos, as approved by the Engineer, meet the following additional requirements:

1. Provide a surge bin or storage silo system meeting **407.04.A.11**.
2. Empty the storage silos or surge bins when directed by the Engineer to check material quantities.

3. Limit hours of plant operation, whether for storage or direct shipment to the road, to reasonable working hours to allow normal inspection of plant operations.
4. Remove bituminous mixtures placed in a surge bin on the same day in which it is stored.
5. The Contractor may store bituminous mixtures of Gradings A, AS, ACRL, and B for up to 48 hours, and Gradings BM, BM2, C, CS, CW, D, E, and F for up to 96 hours, in a storage silo by complying with the following:
 - (a) Add an approved silicone additive to the asphalt cement for mixes to be stored beyond the day of mixing.
 - (b) Keep the stored bituminous mixture sealed at all times during storage.
 - (c) Fill the storage silo to at least 90% of capacity.
6. The Inspector will take samples of the stored material following the period of storage.
7. The stored material is subject to the same temperature, segregation, and laying requirements as required for unstored plant production.
8. The Engineer will reject mixtures having excessive segregation, lumpiness, or stiffness.
9. Locate the surge bins and storage silos in a position that enables the top of the truckload to be visible to the load operator during the loading operation.

407.14 Spreading and Finishing

For Contracts requiring night work, supply sufficient lighting and equipment as specified in **712.04.H**.

The temperature of the mixture at the time of depositing in the paver hopper shall be as specified in Table 407.11-1.

407.14

Place the mixture upon an approved surface, and spread and strike-off to the established lift thickness, line, grade, and elevation using approved asphalt paving machine(s). The Engineer may approve use of echelon or full-width paving if plant production is capable of supplying the paver so that a constant forward speed can be maintained. Use preset control string lines to control the alignment of the outside edge of the pavement. Where multi-course pavements are placed, offset the longitudinal joint in one layer from that in preceding layer by approximately 1 foot; however, construct the joint in the top layer at the centerline of the pavement if the roadway comprises two lane widths, or at lane lines if the roadway is more than two lanes in width. Pave in the direction of traffic.

Do not feed a paving machine from more than one asphalt plant. Coordinate plant production and paving operations to ensure constant forward movement of the pavers. The Engineer will consider repetitive interruptions or stopping of the paver as cause for stopping the work until the Contractor corrects the situation. If the paver must be stopped for a significant period of time, construct a joint and move the paver from the roadway before the bituminous mixture has cooled sufficiently to prevent proper compaction. If the bituminous mixture cools to the extent that the required density cannot be obtained, remove and replace the mixture at no cost to the Department.

Unevenness of texture, segregation (including end-of-load segregation) or tearing or shoving of bituminous mixture during the paving operation, shall be reason to stop the paving. Only resume paving operations when the condition is corrected. Immediately remove unacceptable mix and replace at no cost to the Department. The Department will not allow excessive throwing back of the bituminous mixture. Any amount of mixture not fully adhered to the roadway shall be repaired prior to completion of the project. If the failure is not repaired the same day as originally placed, the method of repair must be approved by the Engineer prior to beginning of the repair. The repairs will be no additional cost to the Department.

Provide automatic screed controls using either the string line, ski type grade reference system, or a non-contact averaging system on all work regardless of the paver width. The Engineer may require a string line reference system on new construction. If the base has been finished with equipment having automatic grade control or the Contractor demonstrates that an alternate method of spreading and finishing will result in a satisfactory riding surface, the Engineer may conditionally waive the string line requirement and authorize use of the ski type reference system. Regardless, the Engineer may at any time require the use of a string line reference system, even if previously waived, if in the Engineer's opinion, the use of the string line will result in a

superior riding surface. When the string line system is required on a multi-course pavement, use it on at least two courses exclusive of the surface course. When using the ski type system, the ski shall have the maximum practical length and in no case shall it be less than 40 feet in length. Pavement lanes previously placed with automatic controls or to form grade may serve as the longitudinal control reference for placing adjacent lanes by using a ski or joint matching shoe.

The string line reference system shall consist of suitable wire or twine supported by approved devices that are compatible with the type of automatic paver control system used. The string line and supports shall be capable of maintaining the line and grade shown on the Plans at the point of support while withstanding the tensioning necessary to prevent sag in excess of $\frac{1}{4}$ inches between supports spaced 50 feet apart. Install additional supports to provide a minimum spacing of 25 feet, or less as directed by the Engineer, to remove the apparent deviation of the string line from theoretical grade.

Provide all materials, equipment, labor, and incidentals necessary to construct the string line reference system, and maintain the system until its use is no longer required. Include the cost of erecting and maintaining the string line reference system in the unit price bid for other items of construction. Have the string line reference system be complete in place at least 300 feet in advance of the point where the pavement is being placed. Automatic screed controls are not required on sections of projects where service connections and other conditions interfere with their efficient operation.

On areas where irregularities or unavoidable obstacles make the use of mechanical spreading and finishing equipment impracticable, take the mixture from the hopper of the spreading machine and distribute it immediately into place using suitable shovels and other tools, and spread the mixture with rakes and lutes in a uniformly loose layer of such depth as will result in a completed course having the required thickness.

The Contractor and the Department will each be required to have an individual onsite that is certified by the Department through the HMA Roadway Certification Course.

407.15 Compaction

A. General

After spreading and striking-off the bituminous mixture and adjusting surface irregularities, thoroughly compact the mixture using methods

407.15

approved by the Engineer and that are capable of achieving the specified density while the material is in a workable condition. When no density requirements are specified, use a system of compaction for roadway pavements that has previously produced the required bituminous pavement densities. The Engineer may require a control strip and random density samples to evaluate the system.

In general, accomplish compaction using a combination of the equipment specified in **407.07**. As a minimum, meet the roller requirements in Table 407.15, but increase the number of rollers if the required results are not being obtained.

Table 407.15 – Roller Requirements by Mix Type

Mix Type	Roller Requirements
307-A, 307-B, 307-BM-2, 307-C, 307-CW (except surface)	3 Rollers (Intermediate roller shall be Pneumatic)
307-AS, 307-ACRL, 411-D, 411-E, 307-CW (surface), 313-Asphalt Treated Permeable Base	3 Rollers (unspecified)
411-TL, 411-TLD, 411-TLE, 307-CS (when paved as a continuous layer)	2 Rollers (unspecified)
411-OGFC	2 Rollers (both rollers shall be static steel double drum, 10 Ton minimum)
Any mix used for scratch paving	2 Rollers (breakdown shall be pneumatic)

1. If the compaction effort is detrimental to the quality of the mat, immediately stop and re-evaluate rolling patterns and equipment. To modify the roller train from that which is specified for the mix, submit to the engineer a written request of the rollers to be substituted and a narrative explanation of how the specified equipment has been detrimental to the quality of the pavement.
2. The Department will only consider requests for substitution of equipment when it is shown that best practices are being followed and that the problem is not due to improper operation or poor maintenance of the equipment. If this request is approved by the Engineer, a new test strip and roller pattern shall be established.
3. With the Engineer’s approval, the Contractor may reduce the minimum number of rollers listed above to one roller of either the

steel-wheel or vibratory type on the following types of construction and projects:

- a. Shoulder construction,
 - b. Incidental construction such as bridge approaches and driveways, and
 - c. Projects containing less than 1,000 tons of bituminous pavement.
4. Compaction of 411-OGFC mixtures shall consist of a minimum of two passes before the material temperature has fallen below 185 °F. Unless otherwise directed by the Engineer, begin rolling at the low side and proceed longitudinally parallel to the road centerline. When paving in echelon, or abutting a previously placed lane, roll the longitudinal joint first, followed by the regular rolling procedure. When paving in echelon, rollers shall not compact within 6 inches of an edge where an adjacent lane is to be placed. Operate rollers at a slow uniform speed with the drive wheels nearer the paver, and keep the rollers as nearly as possible in continuous operation. Continue rolling until all roller marks are eliminated. Do not park rollers on the bituminous pavement.

To prevent adhesion of the mixture to the rollers, keep the wheels properly moistened with water or water mixed with very small quantities of detergent or other approved material. Limit excess use of liquid.

Do not refuel rollers on bituminous pavements.

Along forms, curbs, headers, walls and other places not accessible to the rollers, compact the mixture thoroughly using hot hand tampers, smoothing irons, or with mechanical tampers. On depressed areas, the Contractor may use a trench roller to compact the mix.

B. Density Requirements

Meet the applicable density requirements specified in Table 407.15-1.

407.15

Table 407.15-1: Density Requirements for Bituminous Pavement

Mix Type	% of Maximum Theoretical Density (Lot Average)	No Single Test Less Than, % (Sub Lot)
Travel Lanes ADT <1,000 A, B, BM, BM-2, C, CW, D, E	90.0	87.0
Travel Lanes 1,000 <ADT <3,000 A, B, BM, BM-2, C, CW, D, E	91.0	89.0
Travel Lanes ADT >3,000 A, B, BM, BM-2, C, CW, D, E	92.0	90.0
Travel Lanes and Shoulders Any ADT CS, TL, TLD, TLE, OGFC	NA	NA
Shoulders B, BM, BM-2, D, E	88.0	85.0

Correct sublots that test below the minimum density so that the density of the area is equal to or above the minimum, at which point it can be used to determine the average density of the lot. Do not place any successive layers until the area has been corrected. As necessary to determine the classification of open graded or dense graded mixes and to measure segregation, use AASHTO T 269 or ASTM D3203.

Repair or replace defective mixture to the satisfaction of the Engineer and at no cost to the Department.

The Department will perform density testing in accordance with **407.20.B.5**.

C. Test Strips

Construct test strips for all A, B, BM, BM-2, C, CW, D, and E mixes to establish rolling patterns, to accommodate the Department to calibrate nuclear gauges, to verify that the base course or surface course mixture meets the density requirements of the specifications, and for mix design

and production verification as required. A test strip is not required for mixes AS, A-CRL, CS, TL, TLD, and TLE, but adjustments to the roller pattern may be made at the direction of the Engineer.

Before constructing the test strip, obtain the Engineer's approval of the underlying base or other pavement course. Compact the test strip using equipment as specified in this subsection and **407.07**.

Construct the test strip at the beginning of work on the pavement course. Prepare new test strips when:

1. A change in the JMF is necessary;
2. A change in the source of materials occurs;
3. A change in the material from the same source is observed;
4. There is reason to believe that the test strip density is not representative of the bituminous mixture being placed; and when
5. A change in paving or compaction equipment occurs.

With the approval of the Engineer, the Contractor may construct additional test strips.

Construct each test strip with approved bituminous mixture. The test strip shall remain in place as a section of the completed work. Construct each test strip to be 1 paver width wide, with an area of at least 400 square yards and of the depth specified for the pavement course concerned.

Immediately after placing the bituminous mixture, begin compacting the test strip. Perform compaction in a continuous and uniform manner over the entire test strip.

Continue compacting the test strip until additional roller coverage will produce no appreciable increase in density (1 pound per cubic foot), as measured using a nuclear gauge. Use the roller coverage necessary to obtain this maximum density as the rolling pattern for the remainder of the project.

Take cores on the test strip at ten locations as designated by the Engineer. Provide these cores to the Department for use in calibrating the nuclear

407.16

gauge and to verify that the average density of the test strip meets the density requirements of the specifications. The Department will report all densities using the corrected nuclear gauge readings. Correction factors are specific to the project, mix design and the nuclear gauges used during the test strip construction. If a different mix design or nuclear gauge needs to be used, it will be necessary to cut new cores from the ongoing pavement construction to establish a new nuclear gauge correction factor. Nuclear gauge correction factors determined for a mix design on another project shall not be used.

When testing test strip cores, the Department will determine density (bulk specific gravity) in accordance with AASHTO T 166, Method A only. All core samples shall be completely dry before testing. Air drying is permitted provided core samples are weighed at 2-hour intervals until dry in accordance with AASHTO T166, Section 6.1. Cores may also be dried in accordance with ASTM D7227.

If the density of the asphaltic concrete in the test strip does not meet specification requirements, make whatever changes are necessary to obtain the specified density. Use other sources and combinations of aggregates as necessary, subject to the Engineer's approval, to produce a mix meeting the required density.

407.16 Joints

Place bituminous paving as continuously as possible. Do not pass rollers over the unprotected end of a freshly laid mixture unless approved by the Engineer. Form transverse joints by cutting back on the previous run to expose the full depth of the course. Use a brush or sprayed coat of bituminous material on contact surfaces of longitudinal and transverse joints just before placing additional mixture against the previously rolled material.

407.17 Pavement Samples

When directed, cut samples from the compacted pavement for testing by the Engineer. Take samples of the mixture for the full depth of the course at locations selected by the Engineer. Cut the samples with a power saw or core drill. Samples shall have a top surface area of at least 10 inches.

Fill holes left by taking samples with the same type mixture that was used to construct the course sampled, and compact to conform to the surrounding pavement. Cut samples and repair sample holes at no cost to the Department.

407.18 Surface Requirements

Test the surface with a 12-foot straightedge applied parallel to the centerline of the pavement. The deviation of the surface from the testing edge of the straightedge shall not exceed that specified for the respective types of bituminous construction under the applicable Subsections of these Specifications.

Test the transverse slopes of tilted pavements with a string-line and string-level applied at right angles to the centerline of the pavement. The percent of slope, when computed for the full width of the pavement, shall not deviate more than 0.5 percentage points from that shown on the Plans.

Test the crown in crowned pavements with a string-line applied at right angles to the centerline of the pavement. The crown shall not deviate more than ½ inch from that shown on the Plans.

Correct deviations that exceed the specified tolerances. Remove and replace pavement that cannot be corrected to comply with the specified tolerances at no cost to the Department.

COMPENSATION**407.19 Method of Measurement**

The Department will measure:

1. Asphalt cement and mineral aggregate, including mineral filler when required, by the ton and as follows:
 - a. If the mix is loaded from a storage or surge bin, the Department will determine quantities by weighing the completed mix on truck scales meeting **109** and calculating the weight of asphalt cement and mineral aggregate based on the percentages measured into the mix by the appropriate scales or meters as specified in **407.04**.
 - b. If the mix is loaded directly into the hauling equipment from a batch plant, the Department will measure asphalt cement and mineral aggregate in batch quantities by scales or scales and meters as specified in **407.04.B**.

407.19

- c. If a continuous mix plant is used, the Department will measure Bituminous Material for Bituminous Plant Mix Pavement by the ton in accordance with **109**. The Department will determine quantities of mineral aggregate, including mineral filler when required, by weighing the bituminous pavement mixture on truck scales meeting **109**, and deducting the weight of the bituminous material from the weight of total mixture accepted.
 - d. If recycled mix is permitted, the Department will measure the completed mix, including new mineral aggregate, planings, asphalt cement, and additive, by the ton in accordance with **109**.
2. Removal and disposal of existing surface (concrete) by the square yards in accordance with **109**, if such work is required as specified in **407.10**. Such measurement will include the removal of bituminous overlay.
 3. Removal and Disposal of Existing Surface (Bituminous) by the square yards in accordance with **109**. Such measurement shall include the removal of base material, except concrete, as directed by the Engineer.
 4. Removal of unsatisfactory subgrade material where existing pavement has been removed by the cubic yard, in accordance with **203.09**. The Department will measure material used to replace such undercutting in accordance with the specification for the type of material used.
 5. Adjustment of catch basin grates and frames, water valve boxes, gas valve boxes and manhole covers and frames by each when required.
 6. Liquid anti-strip additive by the gallon.
 7. Hydrated lime by the ton.

The Department will measure bituminous mixtures used to fill openings left by pavement removal as specified in this Subsection **407.19**. The Department will measure base materials used to fill openings left by base removal as provided for in the respective Sections for each type specified.

The Department will not measure chemical additives or modifiers, when required, for payment, but will consider them incidental to asphalt cement.

The Department will not measure mineral filler separately for payment, but will consider it incidental to mineral aggregates.

407.20 Basis of Payment

A. General

The Department will pay for accepted quantities of Asphaltic Concrete (Hot Mix) with or without recycled material, at the contract prices, complete in place, as follows:

<i>Item</i>	<i>Pay Unit</i>
Bituminous Plant Mix Base (Hot Mix)	Ton

The Department will pay for liquid anti-strip additive and hydrated lime anti-strip additive based on certified documentation of material costs not to exceed \$15 per gallon and \$90 per ton, respectively.

The Department will pay for accepted quantities of Prime Coat or Tack Coat as specified in **402** or **403**, respectively.

The Department will pay for the work required to prepare the subgrade, sub-base, base, or surface in accordance with **307.06** and **411.06** as provided for in the applicable Section or Subsection under which the work is performed.

The Department will not make direct payment for polymer or other asphalt modifiers, but will consider such additives to be included in the price bid for the modified asphalt cement or modified mixture.

B. Acceptance of the Mixture

1. **General.** The Department will perform all necessary sampling and testing for acceptance purposes in strict conformance with the Department's Policies in addition to monitoring and observing the Contractor's quality control test procedures and results. However, the Engineer will reject for use in the work any load or loads of mixture which, in the Engineer's opinion, are unacceptable due to excessive segregation, improper coating of aggregates, or excessively high or low temperature.

407.20

The Engineer will accept bituminous mixture at the plant with respect to gradation and asphalt content, on a lot basis. A standard size lot at the asphalt plant will consist of a continuous shift's production that does not start over at Midnight. The number of sublots in a lot will vary according to Table 407.20-1.

Table 407.20-1: Sublot Requirements

Quantity (tons)	Number of Sublots
3001 – 4000	4 tests
2001 – 3000	3 tests
1001 – 2000	2 tests
Less than 1000	1 test

When the total plan quantity of any mix is less than 1,000 tons, the Department will accept the mix on the basis of visual inspection and Contractor Quality Control certification. If the daily production of any mix is less than 100 tons, no tests will be required for that quantity of mix. The Department may run extraction, gradation analysis, or other tests deemed necessary for acceptance purposes.

2. **Defective Materials**

- a. **Acceptance or Rejection.** Consider the Engineer's decision to be final as to the acceptance, rejection, or acceptance at an adjusted payment of the lots.

It is the intent of these specifications that each lot of material will meet specification requirements at the time of acceptance testing. The Department will not take check samples for acceptance purposes.

All acceptance samples will be split, and half of the sample will be retained by the Inspector. If the results of an acceptance test are questioned, the Central Laboratory will test the remaining half of the acceptance sample. The Department will use the results obtained by the Central Laboratory to evaluate the quality of the lot.

- b. **Disposition of Lots.** Remove and replace, at no cost to the Department, nonconforming lots of materials, products, or complete construction that cannot be corrected by reworking.

Alternatively, the Department may accept the nonconforming work at an adjusted payment as specified in these Specifications or as directed by the Engineer.

When a deficiency is determined, the Department will apply the applicable payment as specified in these Specifications to the entire lot. When multiple deficiencies occur, the Department will apply the applicable partial payments to the lot of material that is identified by each deficiency. The Department will apply the payment adjustment for each deficiency separately to not affect any other payment adjustment occurring for the same lot; however, if there are two or more deficiencies in the gradation acceptance tests, the Department will apply only the greater payment adjustment. When an area or linear measurement is used to specify lot size, the Department will determine the equivalent tons of mix placed in each lot by using the average calculated spread from the plant inspector's daily report for that day's production.

3. **Acceptance.** The Engineer will base acceptance of the mixture on test results of consecutive random samples taken from each lot. One random sample will be taken from each subplot. The bituminous mixture will be sampled at the plant according to AASHTO T 168. The percent bitumen content of the mixture will be determined according to AASHTO T 164 or by AASHTO T 308 except as herein revised.

The Contractor may use an approved ignition furnace instead of a vacuum extractor for the use in determining asphalt content and gradation. The method of calibration and test procedures shall comply with AASHTO T 308 Method A and the following.

Monthly, per mixture, the Engineer shall determine the correction factor for the ignition oven used for acceptance of the mixture per AASHTO T 308 and adjust the Asphalt Cement content for acceptance of the mixture accordingly. Keep records of all correction factors for all mixtures. Adjusted payment for asphalt content and gradation will be based on the ignition furnace results as specified in Table 407.20-2. Use of this alternative equipment shall be at no additional cost to the Department.

The percents passing the sieves will be determined in accordance with AASHTO T 30.

407.20

**Table 407.20-2: Acceptance Schedule of Payment
(Asphalt Plant Mix Characteristics)**

Characteristics	Pay Factor	Average Arithmetic Deviation of the Lot Acceptance Test from the JMF	
		1 Test	2 Tests or more
All mixes except 411-OGFC	1.00	0.00-0.30	0.00-0.25
Asphalt Cement Content ⁽¹⁾ (Extraction or ignition oven)	0.95 0.90 0.80 ⁽²⁾	0.31-0.35 0.36-0.40 over 0.40	0.26-0.30 0.31-0.35 over 0.35
411-OGFC only	1.00	0.00-0.30	0.00-0.25
Asphalt Cement Content (Extraction or ignition oven)	0.90 0.80 0.60 ⁽²⁾	0.31-0.35 0.36-0.40 over 0.40	0.26-0.30 0.31-0.35 over 0.35
Gradation 3/8 inch sieve and larger	1.00 0.95 0.90 0.80 ⁽²⁾	0.00-6.50 6.51-7.08 7.09-7.66 over 7.66	0.00-5.70 5.71-6.20 6.21-6.69 over 6.69
Gradation No. 4 sieve ⁽³⁾	1.00 0.95 0.90 0.80 ⁽²⁾	0.00-4.62 4.63-5.20 5.21-5.77 over 5.77	0.00-4.00 4.01-4.50 4.51-5.00 over 5.00
Gradation No. 8, 16, 30, & 50 sieves ⁽³⁾	1.00 0.95 0.90 0.80 ⁽²⁾	0.00-3.80 3.81-4.46 4.47-5.12 over 5.12	0.00-3.30 3.31-3.91 3.92-4.52 over 4.52
Gradation No. 100 & 200 sieves ⁽³⁾	1.00 0.95 0.90 0.80 ⁽²⁾	0.00-1.80 1.81-2.00 2.01-2.20 over 2.20	0.00-1.60 1.61-1.75 1.76-1.90 over 1.90

⁽¹⁾ Does not apply to 307 Grading A, AS, or ACRL mixes.

⁽²⁾ If approved by the Engineer, the Contractor may accept the indicated partial pay. The Department may require removal and replacement at no cost. The Contractor may remove and replace at no cost to the Department at any time.

⁽³⁾ When there is more than one reduced payment relating to gradation in 1 lot of material, only the greatest reduction in payment will be applied. Reductions applicable for any other reason will be cumulative.

Deduction for both asphalt content and gradation deficiencies will be cumulative. The Department will apply deductions to the total price of the mix (asphalt cement and aggregate combined) under the item for Asphalt Cement Content and Gradation Deduction.

4. **Additional Tests.** The Engineer may perform any test at any time to determine the effectiveness of the Contractor's quality control. In addition, the Department will conduct production verification tests parallel to that which is defined for quality control in **407.03.D.2.h**.
5. **Acceptance for Mix Density on the Roadway.** The Department will apply a deduction in payment, not as a penalty but as liquidated damages, for failure to meet the density requirements specified in **407.15**. As soon as practicable after the final rolling is completed on each lot, the Department will perform 5 density tests at locations determined by the Engineer, and will compute an average of all such tests. Deductions for failure to meet density requirements will be computed to the nearest 0.1% as a percentage of the total payment otherwise due for each lot. The percent of total payment to be deducted will be 5 times the percent the average in-place density for each lot that fails to meet **407.15**. The Department will make deductions in monies due the Contractor for failure to meet the density requirements under the item for Density Deduction. The Department will conduct acceptance testing for density in accordance with ASTM D2950 unless otherwise specified. For projects with total project tonnage per mix type less than 2,000 tons (not including small quantity jobs as defined in **407.20.B.1**) the Department may alternatively calculate in place density by cores (AASHTO T-166), in this case no cores will be taken for gauge correlation on the test strip. The Department inspector conducting the density tests shall be a certified Nuclear Gauge Field Technician.

For density testing purposes, the Department will divide the pavement into lots of 1,000 tons. Five density tests will be performed in each lot and the average results compared with the requirements specified in Table 407.15-1. At the beginning of a project or at any time it is deemed advisable, the Department may consider smaller lots to evaluate compaction methods or for other reasons as approved or directed by the Engineer.

The Department will randomly select acceptance test samples that are representative of the lot or subplot. Although performing compaction after the acceptance test is acceptable, the Department

407.20

will use the original test result to determine lot density. The Department may take information only samples to spot check compaction, but will not use these tests for acceptance testing.

C. Adjustments

1. **Asphalt Cement Adjustment.** If the Engineer sets an asphalt content other than that specified in Tables 307.09-1 and 411.09-1, the Department will calculate a price adjustment, based on the asphalt content set by the Engineer and the Monthly Bituminous Index for the specific grade asphalt on the mix design, according to the following formula:

$$PA = \frac{MBI \times (DA - BA) \times T}{100}$$

Where:

PA	=	Price Adjustment
MBI	=	Monthly Bituminous Index
DA	=	Percent asphalt set on the mix design
BA	=	Percent asphalt specified above to be used for bidding
T	=	Total tons asphalt mix for price adjustment

2. **Specific Gravity.** In cases where the effective combined specific gravity of the mineral aggregate exceeds 2.80, the Department will adjust the tonnage of mineral aggregate, or plant produced mixture, for payment by multiplying the tonnage of mineral aggregate, or plant produced mixture, used by a specific gravity of 2.80 and dividing by the higher specific gravity.
3. **Loss on Ignition (LOI).** If the approved JMF includes a surface mixture of limestone with gravel, granite, slag, quartzite or gneiss, perform tests for the percent LOI of the limestone aggregate in the asphalt paving mix as specified in **407.03.E.3**.

If the percent of LOI in the aggregate differs by plus or minus 2% from the LOI indicated in the JMF, the Department will make a payment deduction in the price bid for the mix, not as a penalty but as liquidated damages. The percent of total payment to be deducted will be 5 times the percent that the LOI exceeds the JMF tolerance of plus or minus 2%.

Replace or overlay all mix produced with aggregate tested and found to have a LOI that differs plus or minus 6% from the LOI indicated in the JMF at no additional cost to the Department.

To determine the deduction, the Department will use lots of approximately 5,000 square yards. The Department inspector will perform sampling and testing to establish the LOI according to the Department's sampling and testing procedures. If the initial tests indicate a variation in the LOI of plus or minus 2% than the value shown on the mix design, the Contractor shall perform the additional sampling necessary to establish the LOI of the aggregate in each lot, with the cost of the sampling being included in the contract unit prices bid for the paving items.

The Department will make deductions for excess variation in LOI under the item for Material Variation (Deduction).

410.01

SECTION 410 – BITUMINOUS PLANT MIX SURFACE COURSE (COLD MIX)

410.01	Description	348
410.02	Materials	348
410.03	Composition of Mixtures	349
410.04	Equipment	349
410.05	Limitations	349
410.06	Preparing Designated Surface	349
410.07	Mixing.....	350
410.08	Spreading and Finishing.....	350
410.09	Compaction	350
410.10	Surface Requirements	350
410.11	Maintenance	350
410.12	Method of Measurement	350
410.13	Basis of Payment.....	350

DESCRIPTION

410.01 Description

This work consists of constructing a Bituminous Plant-Mix Surface Course (Cold Mix), composed of aggregate and bituminous material, on a designated base in one or more layers and at the rate of application shown on the Plans or established by the Engineer.

MATERIALS

410.02 Materials

Provide materials as specified in:

Mineral Aggregate	903.10
Emulsified Asphalt, Grade AE-3	904.03

The Engineer will accept mineral aggregate for gradation in the stockpile at the paving plant site, and plant mixed material after being spread on the road. The Engineer may conditionally accept bituminous material at the source.

410.03 Composition of Mixtures

Combine the specified mineral aggregate and bituminous material in such proportions as to produce mixtures within the master composition limits specified in Table 410.03-1.

Table 410.03-1: Proportions of Total Mixture, Percent by Weight

Material Components	Percent by Weight
Mineral Aggregate	93.0 – 95.0%
Emulsified Asphalt	5.0 – 7.0%

EQUIPMENT

410.04 Equipment

Provide equipment as specified in **407.04** with the following modifications:

1. Automatic screed control devices will not be required on the bituminous pavers.
2. Plant equipment required for heating or drying materials and for blending different size aggregates will not be required.

CONSTRUCTION REQUIREMENTS

410.05 Limitations

Comply with the limitations specified in **407.09**.

410.06 Preparing Designated Surface

Prepare the designated surface upon which the material is to be placed as specified in **404.05**.

410.07

410.07 Mixing

Perform mixing as specified in **407.13**. The Contractor may either stockpile the mix or haul it directly from the mixer to the road. If stockpiled, ensure that the material shows no damage from weather or signs of stripping during handling.

410.08 Spreading and Finishing

Perform spreading and finishing and spreading choker aggregate as specified in **407.14**.

410.09 Compaction

Perform compaction operations as specified in **407.15**.

410.10 Surface Requirements

Comply with the surface and testing requirements specified in **407.18** to ensure that the deviation of the surface from the testing edge of the straightedge does not exceed ¼ inch.

410.11 Maintenance

Perform maintenance as specified in **404.09**.

COMPENSATION

410.12 Method of Measurement

The Department will measure Mineral Aggregate and Emulsified Asphalt for Bituminous Plant Mix Surface Course (Cold Mix) in accordance with **407.19**.

410.13 Basis of Payment

The Department will pay for accepted quantities of Bituminous Plant Mix Surface Course (Cold Mix) at the contract prices, complete in place, as follows:

<i>Item</i>	<i>Pay Unit</i>
Emulsified Asphalt	Ton
Mineral Aggregate (Including Choker)	Ton

410.13

The Department will measure and pay for the work required to prepare the designated surface, as provided for under **410.06**, in accordance with the applicable Section or Subsection under which the work is performed.

411.01

**SECTION 411 – ASPHALTIC CONCRETE SURFACE
(HOT MIX)**

411.01 Description	352
411.02 Materials	352
411.03 Composition of Mixtures	353
411.04 Equipment	361
411.05 General Requirements	361
411.06 Preparing the Designated Surface	361
411.07 Mixing	361
411.08 Surface Requirements	361
411.09 Method of Measurement	362
411.10 Basis of Payment	362

DESCRIPTION

411.01 Description

This work consists of constructing an asphaltic concrete pavement, composed of a mixture of coarse aggregate, fine aggregate, mineral filler if specified or required, and asphalt cement, on a prepared roadbed at the rate of application shown on the Plans or established by the Engineer.

The provisions of **407** shall apply to this work unless otherwise stipulated.

MATERIALS

411.02 Materials

Provide materials as specified in:

Mineral Aggregate	903.11
Mineral Filler	903.16
Asphalt Cement, PG 64-22, 70-22, 76-22, or 82-22	904.01
Chemical Additive	921.06.B

The Engineer will accept mineral aggregate, bituminous material, and plant mix in accordance with **407.02**.

411.03 Composition of Mixtures

A. General

Composition of mixtures shall be as specified in 407.03.

B. Proportioning

Combine the specified mineral aggregate and asphalt cement according to the proportions specified in Table 411.03-1.

Table 411.03-1: Proportions of Total Mixture, Percent by Weight

Surface Course	Effective Combined Mineral Aggregate	Asphalt Cement
Grading D	93.0 – 94.3	5.7 – 7.0 ⁽¹⁾
Grading E ⁽²⁾	93.0 – 94.3	5.7 – 7.0 ⁽¹⁾
Grading E (shoulders)	92.0 – 94.7	6.0 – 6.5 ⁽¹⁾
Grading TL	92.5 – 94.3	5.7 – 7.5 ⁽¹⁾
Grading TLD	93.0 – 94.3	5.7 – 7.0 ⁽¹⁾
Grading TLE	93.0 – 94.3	5.7 – 7.0 ⁽¹⁾
Grading OGFC	92.0 – 94.0	6.0 – 8.0 ⁽¹⁾

⁽¹⁾ If the effective combined specific gravity of the aggregate exceeds 2.80, the above proportions may be adjusted as directed by the Engineer. The upper limit for flow values shall not apply to mixes with modified asphalt liquids.

⁽²⁾ The minimum allowable asphalt cement content for 411E low volume mixtures is 5.3%.

1. **Grading D.** In addition to the other requirements of these Specifications, the composition of the mineral aggregate shall be such that when combined with the required amount of bitumen, the resultant mixture will meet Table 411.03-2.

411.03

Table 411.03-2: Mixture Properties (All Roads)

Mix ⁽¹⁾	Stability, Min. lb-ft ⁽²⁾	Flow 0.01 inch ⁽³⁾	Design Void Content % ⁽²⁾	Production Void Content % ⁽²⁾	VMA, Min. % ⁽²⁾	Dust- Asphalt Ratio ⁽⁴⁾
411D	2,000	8 – 16	4.0 ± 0.2	3 – 5.5	14	0.6 – 1.2

- (1) In order to identify critical mixes and make appropriate adjustments, the mix design shall have these required production properties for the bitumen content range of Optimum Asphalt Cement ±0.25%.
- (2) Tested in accordance with AASHTO T 245 with 75 blows of the hammer on each side of the test specimen, using a Marshall Mechanical Compactor.
- (3) Flow will only be required when using a non-modified binder (PG 64-22 or 67-22).
- (4) The dust to asphalt ratio is the percent of the total aggregate sample that passes the No. 200 sieve, as determined by AASHTO T 11, divided by the percent asphalt in the total mix.

2. **Grading E and TLE.** In addition to the other requirements of these Specifications, the composition of the mineral aggregate shall be such that, when combined with the required amount of bitumen, the resultant mixture will meet Table 411.03-3.

Table 411.03-3: Mixture Properties (High vs. Low Volume Roads)

Mix	Traffic Volume	Stability Minimum lb-ft ^(1, 3)	Flow 0.01 inch ⁽²⁾	Design Void Content % ⁽¹⁾	Production Void Content % ⁽¹⁾	VMA, Min % ⁽¹⁾
411E 411TLE	High Volume (ADT > 1,000)	2,000	8 – 16	4.0 ± 0.2	3 – 5.5	14
411E 411TLE	Low Volume (ADT ≤ 1,000)	1,500	8 – 16	3.5 ± 0.5	2 – 5	n/a

⁽¹⁾ Tested according to AASHTO T 245 with 75 blows of the hammer on each side of the test specimen, using a Marshall Mechanical Compactor.

⁽²⁾ Flow will only be required when using a non-modified binder (PG 64-22 or 67-22).

⁽³⁾ Minimum stability for shoulder mixes will be 1,500 lb-ft and optimum asphalt cement content for shoulder mixes shall be as directed by the Regional Materials Supervisor.

If the design criteria specified above cannot be obtained with the aggregate submitted to the laboratory for design, provide another source of aggregate.

3. **Gradings TL and TLD.** In addition to the other requirements of these specifications, the composition of the mineral aggregate shall be such that, when combined with the required amount of bitumen, the resultant mixture will meet Table 411.03-4.

411.03

Table 411.03-4: Mixture Properties (Gradings TL and TLD)

Mix	Stability, Min lb-ft ⁽¹⁾	Design Void Content % ⁽¹⁾	Production Void Content % ⁽¹⁾	Minimum VMA % ⁽¹⁾	Dust- Asphalt Ratio ⁽²⁾
411TL	2,000	4.0 ± 0.2	3 – 5.5	16	1.0 – 2.0
411TLD	2,000	3.8 ± 0.3	3 – 5.5	14	0.6 – 1.2

⁽¹⁾ Tested according to AASHTO T 245 with 75 blows of the hammer on each side of the test specimen, using a Marshall Mechanical Compactor.

⁽²⁾ The dust to asphalt ratio is the percent of the total aggregate sample that passes the No. 200 sieve, as determined by AASHTO T 11, divided by the percent asphalt in the total mix.

- Grading OGFC.** In addition to the other requirements of these specifications, the composition of the mineral aggregate shall be such that, when combined with the required amount of bitumen, the resultant mixture will meet Table 411.03-5.

Table 411.03-5: Mixture Properties (Grading OGFC)

Mix	Minimum Void Content %	Voids in Coarse Aggregate % ⁽¹⁾	Max. Cantabro Abrasion Loss (Non-Aged) % ⁽¹⁾	Drain Down Loss % ⁽²⁾
411OGFC	20	VCA _{DRC} > VCAMIX	20	<0.3%

⁽¹⁾ As described in National Asphalt Pavement Association (NAPA) Publication IS-115, "Design, Construction and Maintenance of Open-Graded Friction Courses."

⁽²⁾ Tested in accordance with AASHTO T 305.

C. Recycled Asphalt Pavement and Recycled Asphalt Shingles

- Recycled Asphalt Pavement.** The Contractor may use asphalt pavement that has been removed from a Department project or other State Highway Agency project by an approved method and stored in a Department approved stockpile. RAP combined with the appropriate aggregate, asphalt cement, and anti-strip additive when

required shall produce a mixture that will otherwise meet all the requirements specified in 903.11 and this Section 411. The Contractor may use RAP in each mix specified in Table 411.03-6.

Table 411.03-6: Use of Recycled Asphalt Pavement

Mix Type	% RAP (Non-processed) ⁽¹⁾	Maximum % RAP (Processed) ⁽²⁾	Maximum % RAP Processed and Fractionated ⁽³⁾	Maximum Particle Size (inch)
411D (PG64-22, PG67-22)	0	15	20	½
411D (PG70-22, PG76-22, PG82-22)	0	10	15	½
411E & 411TLE (Roadway)	0	15	20	½
411E & 411TLE (Shoulder)	15	30	35	½
411TL (PG64-22, PG67-22)	0	15	15	5/16
411TL (PG70-22, PG76-22, PG82-22)	0	10	10	5/16
411TLD (PG64-22, PG67-22)	0	15	15	5/16
411TLD (PG70-22, PG76-22, PG82-22)	0	10	10	5/16

(1) “Non-processed” refers to RAP that has not been crushed and screened or otherwise sized such that the maximum recycled material particle size is less than that listed above prior to entering the dryer drum.

(2) “Processed” refers to RAP that has been crushed and screened or otherwise sized such that the maximum recycled material particle size is less than that above prior to entering the dryer drum.

(3) “Fractionated” refers to RAP that has been processed over more than one screen, producing sources of various maximum particle sizes (e.g., ¾ to ½ inch, ½ inch to #4, etc.). The Contractor may use the larger percentages of fractionated RAP specified only if individual fractions of two different maximum particle size are introduced into the plant as separate material sources for increased control.

411.03

All mixes shall contain at least 80% virgin asphalt, except for 411E Shoulder Mix which shall have at least 65% virgin asphalt.

Obtain a representative sample from the recycled material stockpile and establish a gradation and asphalt cement content as required. Determine the gradation and asphalt content of the recycled material at the beginning of a project and every 2,000 tons thereafter. The stockpile asphalt cement content for all recycled material shall not vary from the JMF by plus or minus 0.8%. Table 411.03-7 specifies the stockpile gradation tolerance for all recycled material on each sieve.

Table 411.03-7: Stockpile Gradation Tolerances for Recycled Material

Size	Tolerance
3/8 inch sieve and larger	± 10%
No. 4 sieve	± 8%
No. 8 sieve	± 6%
No. 30 sieve	± 5%
No. 200 sieve	± 4%

The Contractor is responsible for its own sampling and testing of the RAP as well as new materials for bid purposes, and for submitting the JMF as specified in **407.03**. After mixing, the moisture content of the total mix shall be no more than 0.1% as determined by oven drying, and the provisions for lowering the temperature because of boiling or foaming shall not apply.

The Engineer will accept mixture for aggregate gradation and asphalt content based on extractions in accordance with AASHTO T 164 or in accordance with AASHTO T 308.

- 2. Recycled Asphalt Shingles (RAS).** Recycled Asphalt Shingles (RAS) may be included to a maximum of 3% of the total weight of mixture. The percentage of RAS used will be considered part of the maximum allowable RAP percentage. The ratio of added new asphalt binder to total asphalt binder shall be 80% or greater for all 411 mixes. Either the mix producer or the RAS supplier shall obtain a representative sample from the recycled material stockpile and establish a gradation and asphalt cement content as required.

Determine shingle asphalt binder content according to AASHTO T 164 Method A, with a minimum sample size of 500 grams. Determine the gradation and asphalt content of the recycled material at the beginning of the Project and every 2,000 tons of recycled material used thereafter. The stockpile asphalt cement content for all recycled material shall not vary by more than 0.8%. All RAS material shall be processed to a minimum 100% passing the 3/8 inch sieve and a minimum 90% passing the No. 4 sieve.

To conduct the gradation testing, air dry a 500 to 700-gram sample of processed shingle material, dry sieve over the 3/8-inch and No. 4 sieves, and weigh. For mix design purposes, the Contractor may use the aggregate gradation specified in Table 411.03-8 as a standard gradation instead of determining the shingle gradation according to AASHTO T 30.

Table 411.03-8: Standard Gradation (for Mix Design Purposes)

Sieve Size	Total Percent Passing
3/8 inch	100
No. 4	97
No. 8	95
No. 16	80
No. 30	60
No. 50	50
No. 100	40
No. 200	30

An aggregate bulk specific gravity (G_{sb}) of 2.650 may be used instead of determining the shingle aggregate G_{sb} according to AASHTO T 84. In addition, the effective binder available for mixing with additional aggregates shall be considered as 75% of the total binder content as determined by AASHTO T 164 and shall be the value listed as the RAS binder content on the JMF.

Scrap asphalt shingle shall not contain extraneous waste materials. Extraneous materials including, but not limited to, asbestos, metals, glass, rubber, nails, soil, brick, tars, paper, wood, and plastics, shall not exceed 0.5% by weight as determined on material retained on

411.03

the No. 4 sieve. To conduct deleterious material testing, take a representative 500 to 700-gram sample of processed shingle material, place over the No. 4 sieve, and pick and weigh all extraneous waste material retained on the No. 4 sieve. Base the percent of extraneous material on the total sample weight.

RAS shall contain less than the maximum percentage of asbestos fibers based on testing procedures established by the Department, or State or Federal environmental regulatory agencies. Analyze a minimum of one sample of processed asphalt roofing material for every 500 tons of material processed for the presence of asbestos.

Before a JMF for a particular design is approved, submit the following, along with the materials and information specified in **407.03**:

- a. Certification by the processor of the shingle scrap describing the shingle scrap content and source.
- b. A 1000-gram sample of the processed RAS material for inspection (new designs only).

Stockpile RAS separately from other salvage material. Do not blend RAS material in a stockpile with other salvage material. Do not blend Manufacture Waste Scrap Shingles (MWSS) and Tear-Off Scrap Shingles (TOSS). In addition, do not blend virgin sand material with the processed shingles, to minimize agglomeration of the shingle material.

All RAS supplied to a Department project shall come from a certified shingle processor/supplier approved by the Division of Materials and Tests.

D. Anti-Strip Additive

Check asphaltic concrete surface mixtures for stripping by the Ten Minute Boil test for dosage rate and ASTM D4867 (Root-Tunnecliff procedure) for moisture susceptibility.

Mix an approved anti-strip agent with the asphalt cement at the dosage specified in **921.06.B**.

EQUIPMENT

411.04 Equipment

Provide equipment as specified in **407.04** through **407.08**.

To construct shoulder mixes with recycled material, provide equipment that complies with **407**, except modify the asphalt plant as approved by the Engineer to accommodate the addition of asphalt planings. If using a batch plant to produce recycled mix, heat the aggregate to a temperature that will transfer sufficient heat to the cold planings to produce a mix of uniform temperature within the specified range.

CONSTRUCTION REQUIREMENTS

411.05 General Requirements

Construct the pavement as specified in **407.09**, **407.11**, **407.12**, and **407.14** through **407.17** and the following Subsections.

411.06 Preparing the Designated Surface

Prepare the designated surface upon which the material is to be placed as specified in **404.05**.

Ensure that loops used for traffic signals are installed before applying the final surface.

411.07 Mixing

Perform mixing as specified in **407.13**. In addition, the mixing cycle for surface course mixtures may require a dry-mixing period.

411.08 Surface Requirements

The surface shall meet the requirements specified in **407.18**, and when tested according to the provisions of that Subsection, the deviation of the surface from the testing edge of the straightedge shall not exceed $\frac{1}{4}$ inch.

411.09

COMPENSATION

411.09 Method of Measurement

The Department will measure Mineral Aggregate, including Mineral Filler when required, Asphalt Cement for Asphaltic Concrete Surface (Hot Mix), and other related items in accordance with **407.19**.

For bidding purposes, use the asphalt cement content specified in Table 411.09-1.

Table 411.09-1: Asphalt Cement Content

Mix Type	Asphalt Content, %
411-D	5.9
411-E Roadway	6.3
411-E Shoulder	6.3
411-TL	6.3
411-TLD	5.9
411-TLE Roadway	5.9
411-TLE Shoulder	5.9
411-OGFC	6.0

If the Engineer sets an asphalt content other than that specified above, the Department will make a price adjustment based on the asphalt content set by the Engineer and the Monthly Bituminous Index for the specific grade asphalt cement on the mix design. The Department will calculate a price adjustment in accordance with **407.20**.

411.10 Basis of Payment

The Department will pay for accepted quantities of Asphaltic Concrete Surface (Hot Mix) or asphaltic Concrete Surface (Hot Mix) (Shoulders) with or without recycled material, at the contract prices, complete in place, in accordance with **407.20**.

**SECTION 414 – EMULSIFIED ASPHALT SLURRY
SEAL AND MICRO-SURFACING**

414.01 Description.....	363
414.02 Materials	363
414.03 Composition of Mixture.....	364
414.04 Equipment.....	370
414.05 Preparing the Existing Surface.....	373
414.06 Applying Slurry Seal and Micro-Surfacing	374
414.07 Joints	377
414.08 Fog Seal Application.....	377
414.09 Weather Limitations.....	377
414.10 Opening to Traffic.....	378
414.11 Method of Measurement.....	378
414.12 Basis of Payment.....	379

DESCRIPTION

414.01 Description

This work consists of the design, testing, construction, and quality control required to apply an emulsified asphalt slurry seal surface (slurry seal) or micro-surface.

The slurry seal or micro-surface shall consist of a mixture of an approved emulsified asphalt, mineral aggregate, water, and specified additives or modifiers, properly proportioned, mixed, and uniformly spread over a prepared surface. The cured slurry or micro-surface shall have a homogeneous appearance, and adhere firmly to the surface.

MATERIALS

414.02 Materials

Provide materials as specified in:

Mineral Filler (Portland Cement)..... **901.01**

414.03

Mineral Aggregate (Slurry Seal).....	903.12.A
Mineral Aggregate (Micro-Surface)	903.12.B
Emulsified Asphalt	904.03
Water.....	921.01

For a slurry seal, use a Type CQS-1h emulsified asphalt. For micro-surfacing, use a Type CQS-1hp emulsified asphalt.

Ensure that no deleterious material is introduced into aggregate stockpiled at project site.

414.03 Composition of Mixture

At least 2 weeks before beginning work, submit a signed original of a mix design, performed by a qualified laboratory and covering the specific materials to be used on the Project, to the Materials and Tests Division for acceptance, together with representative samples of each ingredient to be used in the mixture. Identify the samples with information related to sources, type of materials, and project number.

Once the materials are approved, make no substitutions without first testing and obtaining the approval of the laboratory that prepared the mix design. Do not begin work until the Materials and Tests Division has evaluated and accepted the mix design.

Provide a laboratory report showing the results of tests performed on individual materials and comparing their values to those required by this specification. Use job aggregates in all laboratory design tests. Mixing tests shall pass at the maximum expected air temperature in ISSA T113.

A. Slurry Seal

1. **Testing.** The laboratory report shall provide the information specified in Table 414.03-1 for the slurry seal mixture.

Table 414.03-1: Quick-Set Emulsified Asphalt Slurry Seal

Test	Requirement
Mixing Time Test, seconds at 77 °F (TB-113)	120 min
Mix Time, at 50 and 100 °F	(informational)
<u>Set Time Tests:</u>	
30-Minutes-Blotter Test (TB-102)	no brown stain
Displacement Test	no displacement
Water Resistance Test, at 30 minutes (TB-102)	no discoloration
Wet Stripping Test, % coating (TB-114)	90% min
System Compatibility (TB-115)	Pass
Set Time Tests: 30 minutes (TB-139)	12 kg-cm min
Early Rolling Traffic Time: 2 hours (TB-139)	20 kg-cm min
Wet Track Abrasion Test, loss in g/ft ² (TB-100)	75 max, 6-day soak

For roadways having greater than 1,500 ADT, in addition to the tests specified in Table 414.03-1, the mixture shall also meet the requirements specified in Table 414.03-2 for the ISSA T109, Test Method for Measurement of Excess Asphalt in Bituminous Mixtures by Use of a Loaded Wheel Tester and Sand Adhesion.

Table 414.03-2: Excess Asphalt (for Roadways with > 1,500 ADT)

Roadway ADT	Requirement
1,500 – 3,000	Maximum: 55 grams/psf sand adhesion, 1,000 cycles @ 125 lbs
3,000+	Maximum: 50 grams/psf sand adhesion, 1,000 cycles @ 125 lbs

- Composition.** Emulsified asphalt slurry seal shall consist of a uniform mixture of aggregate, emulsified asphalt, latex solids when shown on the Plans, mineral filler, and water. The emulsified asphalt manufacturer shall certify the compatibility of all ingredients (including the mix set additive) of the mix.

414.03

The percent of residual asphalt based on the weight of the dry aggregate shall be between 7.5 and 13.5%, with a mixture control tolerance of plus or minus 0.50%.

Ensure that the aggregate gradation and percent residual asphalt, as provided in the slurry seal design accepted by the Engineer, is maintained within the mixture control tolerances stated herein.

The Contractor may add Portland cement to obtain the desired dispersion and working characteristics of the slurry provided that the addition of Portland cement is stated on the slurry seal design, does not exceed 3% of the weight of the aggregate, and has a mixture control tolerance of plus or minus 0.25%.

Portland cement added for dispersion of the slurry seal shall be a commercial quality, non-air entraining cement and shall not be considered as mineral filler for the purpose of satisfying the gradation requirements of the aggregate.

Pre-wet the aggregate with a minimum amount of water before blending with the emulsified asphalt to obtain a fluid, homogeneous slurry mixture of the proper consistency. Do not add to the mix any additional water above that quantity required by the slurry seal mix design to obtain a more workable mixture.

B. Micro-Surfacing

1. **Testing.** The laboratory report shall provide the information specified in Table 414.03-3 for the micro-surface mixture.

Table 414.03-3: Micro-Surfacing

Test	Requirement
Mixing Time Test, seconds at 77 °F (T-102)	120 min
Mix Time, at 50 and 100 °F	(informational)
Set Time Tests: 30 minutes (T-139)	12 kg-cm min
Early Rolling Traffic Time: 60 minutes (T-139)	20 kg-cm min
Wet Stripping Test, % coating (T-114)	90% min
Wet Track Abrasion Test, loss in g/ft ² (T-100)	75 max 6 days 50 max 1 hour
Measurement of Excess Asphalt (T-109)	50 grams/ft ² max Sand Adhesion, 1,000 Cycles at 125 lbs
Classification Compatibility (T-144)	11 pt. min
Loss on Ignition (LOI) Test, 407.03.E.3	(informational)

2. **Composition.** For the paving mixture, the design shall verify the functioning of the set regulating additives and shall present certified test results for the Engineer's approval. Aggregate in the mixture shall be representative of material to be used on the Project.

Obtain the Engineer's approval of the design before using. Proportions for the design shall be within the limits specified in Table 414.03-4.

414.03

Table 414.03-4: Micro-Surface Mixture Design Requirements

Material	Requirement
Modified Emulsified Asphalt Residue by Dry Weight of Aggregates	5.0-9.0%
Mineral Additive by Dry Weight of Aggregate	0.5%-3.0%
Latex or Polymer Based Modifier	3% minimum and as required to provide the specified properties
Mix Set Additive	As required to provide the specified properties
Water	As required to produce consistency

The Contractor may add Portland cement to obtain the desired dispersion and working characteristics of the mix, provided that the addition of Portland cement is stated on the micro-surface design, does not exceed 3% of the weight of the aggregate, and has a mixture control tolerance of plus or minus 0.25%.

Portland cement added for dispersion shall be a commercial quality, non-air entraining cement and shall not be considered as mineral filler for the purpose of satisfying the gradation requirements of the aggregate.

Proportion the mixture to achieve the test strip requirements specified in **414.06**.

C. Applicable Specifications

Consider the specifications and test methods identified in Table 414.03-5 to be part of this specification.

Table 414.03-5: Applicable Specifications

Title	Source
Mixing, Setting and Water Resistance Test to Identify “Quick-Set” Emulsified Asphalts	ISSA TB-102
Wet Track Abrasion of Micro Seals	ISSA TB-100
Measurement of Micro-Seal Consistency	ISSA TB-106
Test Method for Measurement of Excess Asphalt in Bituminous Mixtures by Use of a Loaded Wheel Tester	ISSA TB-109
Outline Guide Design Procedure for Slurry Seal	ISSA TB-111
Method to Estimate Micro-Seal Spread Rates and to Measure Pavement Macrotecture	ISSA TB-112
Trial Mix Procedure for Slurry -Seal Design	ISSA TB-113
Wet Stripping Test for Cured Slurry-Seal Mixes	ISSA TB-114
Test Method to Classify Emulsified Asphalt/Aggregate Mixture Systems by Modified Cohesion Tester. Measurement of Set and Cure Characteristics	ISSA TB-139
Classification Compatibility	ISSA TB-144
Design, Testing and Construction of Micro-Seal	ASTM D3910
Quantitative Extraction of Bitumen for Bituminous Paving Mixtures	ASTM D2172

The blended asphalt mixture, when combined with aggregate and mineral filler, shall have the following characteristics:

1. Be capable of filling up to ½-inch wheel ruts in one pass.
2. Be capable of field regulation of the setting time.
3. Be suitable for nighttime placement.

414.04

EQUIPMENT

414.04 Equipment

Maintain all equipment, tools, and machines used to perform this work in satisfactory working condition. Have available at all times a device capable of determining aggregate moisture within 3 minutes.

Immediately after loading, cover all trucks with a cover of canvas or other suitable material. Allow the cover to lap down along the sides and rear of the truck bed a minimum of 6 inches, and secure with tie downs at a maximum of 5-foot spacing along the sides and rear of the truck bed. Before starting hauling operations, ensure that all trucks are equipped to meet these requirements.

Provide power brooms, power blowers, air compressors, water flushing equipment, and hand brooms capable of thoroughly cleaning all cracks and the old surface. Provide hand squeegees, hand brooms, shovels, and other incidental equipment as necessary to perform work.

A. Mixing Equipment

The mixing equipment shall be re-supplied with all materials while depositing the mixture on the roadway to provide a continuous, non-stop surfacing operation. Produce the paving mixture in a self-propelled, front feed, continuous loading, mixing machine equipped with a positive, non-slipping aggregate delivery system and an interconnected, positive displacement water-jacketed gear pump to accurately proportion ingredients.

Equip the mixing machine with an approved fines feeder that has an accurate metering device or method to introduce a predetermined amount of mineral filler into the mixer at the same time and location as the mineral aggregate. Provide a spray bar to completely wet the aggregate dropping down to the pug mill with additive and water. The twin-shafted multi-blade pug mill shall be a continuous flow type and a minimum of 50 inches long. Introduce the emulsion above the third point of the mixer to ensure proper premixing of the aggregate, cement, additive, and water when the modified emulsified asphalt is added. Blade size and side clearances shall meet the equipment manufacturer's recommendations.

Perform mixing in a manner that does not cause premature breaking of the emulsified asphalt. The mixing unit of the mixing chamber shall be capable of thoroughly blending all ingredients.

Equip the mixer with a remote forward speed control at the back mixing platform so the back operator can control forward speed and level of mixture in paving or rut box.

Provide a computerized material monitoring system with integrated material control devices that are readily accessible and positioned so the amount of each material used can be determined at any time. Provide a back-up electronic materials counter that is capable of recording running count totals for each material being monitored. Equip the mixer with a radar ground measuring device. Calibrate each material control device before each mix application and as often thereafter as the Engineer deems necessary. The computer system shall have the capability to record, display and print the following information:

1. Individual sensor counts for emulsion, aggregate, cement, water, and additive
2. Aggregate, emulsion, and cement output in pounds per minute
3. Ground travel distance
4. Spread rate in pounds per square yard
5. Percentages of emulsion, cement, water, and additive
6. Cumulative totals of aggregate, emulsion, cement, water, and additive
7. Scale factor for all materials

Ensure the computer system is functional at the beginning of work and during each calibration.

Equip the mixing machine with a water pressure system and fog type spray bar, adequate for complete fogging of the surface ahead of the spreading equipment.

The mixing machine shall include controls for proportioning and calibrating the aggregate feed. The aggregate feed device shall have a revolution counter, so that the amount of aggregate used may be determined at any time, and a positive locking feed gate.

Provide an emulsion pump of the positive displacement type and equipped with a device that can be used to determine the amount of emulsion used at any time. Arrange the emulsion pump, meter, and

414.04

pipng to allow calibration of the meter by weighing a metered volume. The pump shall deliver the emulsion to the mixer box at a uniform rate, which shall not vary more than 2% from the required quantity.

Equip the water pump with a minimum of two valves. One valve shall establish the required water flow. The other valve shall be a quick acting valve to start and stop the water flow.

The mixing machine shall have sight gauges located at the material storage tanks for the asphalt emulsion and water.

Equip the mixing machine with approved metering devices that can be used for calibration purposes and for estimating the quantities of materials used during any one period. If the metering devices stop working properly, do not use the mixing machine until the necessary repairs have been made.

Provide satisfactory means to allow positive interlocking control between the flow of aggregate from the bins and the flow of emulsion from the pump. Calibrate each mixing unit in the Engineer's presence before starting construction. Document the individual calibration of each material at various settings, which can be related to the machine's metering devices. When calibrating the emulsion system, run a minimum of three tests, with each test run being a minimum of 40 gallons. To calibrate the aggregate delivery system, perform tests at three different gate settings, with two test runs at each gate setting and a minimum of 425 pounds per test run. To calibrate the filler (cement) delivery system, perform three tests at a minimum of 25 pounds per test. Use certified scales. Only use machines that have been calibrated and accepted by the Engineer to perform the work. The Engineer may require additional calibrations during the process of the work.

B. Spreading Equipment

Attach to the mixer a hydraulically adjustable (adjustable while applying mixture) type spreader box with a positive screed adjustment for yield control and a positive adjustment for the joint matcher. The box shall be equipped with the following: ribbon flights mounted on an adjustable shaft to continually agitate and distribute the materials throughout the box; curb bumpers and replaceable runners with a minimum of 5-foot long end runners; and a sufficient walkway to provide access to either side of the spreader box without walking through the freshly laid material.

The spreader box shall be heavy duty with cross bracing for rigidity and a manufacturer's weight of not less than 1,400 pounds at a width of 12 feet. The box shall be capable of laying mix to a width of 14 feet. The equipment shall provide sufficient turbulence to prevent the mix from setting in the box or causing excessive side build-up or lumps. To prevent loss of mixture from the box, attach flexible seals, front and rear, in contact with the road.

Equip the full width application box with a secondary strike-off located approximately 2 to 3 feet behind the primary strike-off to minimize transverse corrugations. The secondary strike-off shall have elevation and width adjustments similar to the primary strike-off. It shall have a pivot point where it can be tilted for texturing or raised completely off the surface. Rut filling shall require a steel or high density strike-off on the spreading equipment, as approved by the Engineer, or the use of a rut box. Use a rut box for filling ruts in excess of 3/8 inches unless otherwise shown on the Plans.

Operate the spreading equipment to prevent the loss of mixture on super-elevated curves. Spread mixture to fill cracks and minor surface irregularities and achieve a uniform skid-resistant surface without causing skips, lumps, or tears in the finished mat.

For slurry seals, the use of burlap drags or other drags necessary to obtain the desired finish requires the Engineer's approval. Replace drags having excessive build-up. Keep drags in a completely flexible condition at all times. Do not use drags on micro-surfacing.

CONSTRUCTION REQUIREMENTS

414.05 Preparing the Existing Surface

Immediately before applying the tack coat and mixture, remove all dust, dirt, vegetation, and other deleterious material from the existing surface by brooming, washing with water under high pressure, blowing with compressed air, or other approved methods. Obtain the Engineer's approval of the cleaned surface before applying the tack coat and mixture. Remove all thermoplastic pavement markings flush with the existing surface before applying the tack coat.

Establish stations at 1,000-foot intervals on the entire project before placing materials. Clearly identify and maintain the stations until project completion.

414.06

414.06 Applying Slurry Seal and Micro-Surfacing

A. Application

Before placing the mixture, apply a tack coat of SS-1h, CQS-1h, or CQS-1hp emulsion with an asphalt distributor. The tack coat shall consist of one part emulsion and three parts water. The application rate shall be 0.10 to 0.15 gallons per square yard of the diluted emulsion. The Engineer will determine the actual application rate. Apply the tack coat as specified in **403**.

Apply the emulsified asphalt slurry seal at a rate of 16 plus or minus 2 pounds per square yard based on dry aggregate weight unless otherwise shown on the Plans. Vary the rate of application within the range specified above as required by the condition of the pavement to obtain a minimum thickness of 1/8 inch above the high points of the milled areas and 1/4-inch thickness on unmilled areas.

Apply micro-surface as follows:

1. **Rut-fill Course.** If a rut-fill course is specified, apply enough material to fill the wheel paths without excess crowning (overfilling). An excess crown is defined as 1/8 inches after 24 hours of traffic compaction. Apply rut-fill courses in widths from 5 to 6 feet for each wheel path. Provide a smooth, neat seam where two rut-fill passes meet. Take care to restore the designed profile of the pavement cross-section. Feather the edges of the rut-fill course to minimize the use of excess material.
2. **Leveling Course.** If a leveling course is specified, apply at a rate of 14 plus or minus 2 pounds per square yard based on dry aggregate.
3. **Surface Course.** If a surface course is specified and it is placed over a leveling course, apply at a rate of 18 plus or minus 1 pounds per square yard based on dry aggregate. If a surface course is specified and it is not placed upon another micro-surfacing course, apply the paving mixture at a minimum rate of 22 pounds per square yard based on dry aggregate.

Apply micro-surface at the rates as shown on the Plans for leveling and surface courses.

Apply the mixture based on dry aggregate weight as shown on the Plans.

The maximum allowable speed of the machine shall be 130 feet per minute. The Engineer will determine the maximum allowable speed for rut filling. Place the final surface seal uniformly across the width of the traffic lane unless otherwise specified or directed. The action of the squeegee shall allow the mix to flow freely, leaving a smooth, uniformly textured surface.

Unless otherwise directed by the Engineer, pre-wet the surface with water by fogging ahead of the spreader box. Closely control pre-wetting to prevent water from accumulating to the point of running off or puddling.

As the aggregate and emulsion are being loaded into the aggregate/emulsion support trucks or mixing machine, perform a final screening of the aggregate by sieving it through screening equipment capable of removing random oversize material.

Ensure that the mixture is of the desired consistency when deposited on the surface. Add no additional elements to the mixture once placed. Ensure that a sufficient amount of mixture is carried in all parts of the spreader at all times to obtain complete coverage. Do not allow lumping, balling, or unmixed aggregate, or segregation of the emulsion and aggregate fines from the coarse aggregate. If the coarse aggregate settles to the bottom of the mix, remove the mix from the pavement. The mixture shall have proper consistency to avoid excessive splattering and excessive free water. Do not spray water into the spreader box during lay down operations. Use hand tools, lutes, and squeegees to spread mix on areas not accessible to the machine spreading equipment. After curing, perform rolling with a pneumatic-tired roller for sections of pavement not to be exposed to traffic. The roller shall be equipped with tires with a pressure of 40 to 60 pounds per square inch.

Demonstrate throughout the course of the Project that the number of trucking units being used is sufficient to ensure a continuous forward operation. Repeated stopping and starting of the machine will not be allowed.

B. Quality Control

Produce a mixture that complies with the mix design and the quality control tolerances. Apply the slurry seal or micro-surface at the rates

414.06

shown on the Plans. Use the methods described in this section to measure compliance. Maintain all quality control documentation and make it available to the Engineer upon request or at the completion of the work.

1. **Asphalt Content.** Calculate the percent asphalt content of the mixture by randomly reading the equipment computer display a minimum of three times a day. The quality control tolerances from the mix design is plus or minus 0.5%.
2. **Application Rate.** Calculate the yield of the course being placed by randomly reading the equipment computer display a minimum of three times a day. The quality control tolerance from the specified application rate is plus or minus 2 pounds per square yard.
3. **Documentation.** Maintain a lot sheet as follows:

Divide the Project into lots of each day's production. For each lot, maintain a lot sheet, providing the following information:

- (1) Contract Number, Route
- (2) Date, Air Temperature, Pavement Surface Temperature
- (3) Control Settings, Calibration Values, Unit Weight of Emulsion (pounds per gallon), Percent Residue in Emulsion
- (4) Beginning and Ending Log Miles
- (5) Computer display readings for material usage (Beginning, Ending, and Total)
- (6) Length, Width, Total Area (square yards) of the construction completed for the day
- (7) Aggregate used (dry ton), Asphalt Emulsion used (ton), additives (gallon), water (gallon), and/or Portland Cement (ton)

- (8) Application Rate of asphalt emulsion, Combined Application Rate (pounds per square yard)
- (9) Mix Design (Percent Portland Cement, Percent Emulsion, Percent Asphalt Cement)
- (10) Calibration Forms
- (11) Contractor's Authorized Signature

4. **Test Strip Construction.** Prior to production application, place a 1,000 plus or minus 50-foot test section. Place the test strip at the same time as paving is to take place, night or day, and under the same ambient conditions. Ensure the test strip is able to carry normal traffic within 60 minutes. If normal traffic cannot be carried, adjust the emulsion or mixture, and construct another test strip.

414.07 Joints

Prevent excessive build-up, uncovered areas, or unsightly appearance on longitudinal or transverse joints. Avoid excessive overlap on longitudinal joints. Provide spreading equipment of suitable width to produce a minimum number of longitudinal joints throughout the Project. When placing micro-surfacing, terminate the final center joint of the micro-surfacing at a point that will fall directly under the final permanent centerline. Before opening to traffic, apply pavement markings meeting **716.06**. Allow a maximum of 3 inches for overlap of the longitudinal lane line joints. Also, the joint shall have no more than ¼-inch difference in elevation when measured with a 10-foot straightedge over the joint. Extend final edge lines a minimum of 4 inches over the old longitudinal edge joint. Ensure straight lines along curbs and shoulders. Do not allow runoff on these areas. Keep lines at intersections straight to provide a neat appearance.

414.08 Fog Seal Application

Meet **403.05**.

414.09 Weather Limitations

Only place micro-surface and slurry seal when the pavement surface temperature and the ambient air temperature are a minimum of 50 °F and

414.10

rising. Do not apply micro-surface or slurry seal during foggy or rainy conditions. Limit placement to the period from April 1 to October 31.

414.10 Opening to Traffic

Micro-surface material shall cure sufficiently within 1 hour after application, and slurry seal material shall cure sufficiently within 2 hours after application, so that traffic can be allowed on the pavement without damaging the surface. Do not allow traffic on the mixture until it has cured sufficiently to prevent pickup by vehicle tires. Maintain traffic control as necessary to prevent damage to the mixture. Repair damage to the mixture caused by traffic at no cost to the Department.

COMPENSATION

414.11 Method of Measurement

The Department will measure:

1. Emulsified Asphalt Slurry Seal by the square yards complete in place and accepted.
2. Micro-Surfacing by:
 - a. The square yards complete in place and accepted; or by
 - b. The quantity in tons (dry) of aggregate, including mineral filler, and the quantity in tons of latex or polymer modified emulsion used in the accepted portion of the micro-surfacing, based on the calibrated metering device affixed to the micro-surface mixing machine.
3. Bituminous Materials for Tack Coat and for Fog Seal by the ton of undiluted emulsion.

The quantity for "Bituminous Material for Tack Coat", Item No. 403.01, should be $\frac{1}{4}$ of the estimated application rate. The Department will not directly pay for latex or polymer additives when used and will consider their cost to be included in the price bid for the respective items.

For bidding purposes, assume the emulsified asphalt content for the slurry mix design is 15%. When Micro-Surfacing is bid by the square yard, assume

the design asphalt content is 12%. If the Engineer sets an emulsified asphalt content for slurry seal other than that stated above, the Department will make a price adjustment based on the emulsified asphalt content set by the Engineer and the invoice price of the emulsified asphalt F.O.B. the project delivery point. The Department will calculate the price adjustment according to the following formula:

$$PA = \frac{[IP \times (DA - BA) \times T]}{100}$$

Where:

PA =	Price Adjustment
IP =	Invoice price of emulsified asphalt cement
DA =	Percent emulsified asphalt set on the mix design
BA =	Percent emulsified asphalt specified above to be used for bidding
T =	Total tons of aggregate for price adjustment as determined by the metering system on the mixing machine

The Department will make payment to the Contractor for additional emulsified asphalt as provided for above at the purchase price F.O.B. the project delivery point, as verified by invoice, with no compensation allowed for further handling or processing. The Department will be reimbursed from monies due the Contractor for a decrease in emulsified asphalt content in the amount equal to the purchase price F.O.B. the project delivery point.

414.12 Basis of Payment

A. General

The Department will pay for accepted quantities, determined in accordance with **414.11**, at the contract prices, complete in place, which payment shall be full compensation for all equipment, materials, labor and incidentals necessary to complete the work.

B. Adjustments

1. Loss on Ignition (LOI). A price adjustment for LOI shall be applied on a project basis per **407.20.C.3**.
2. Specific Gravity. In cases where the Bulk SSD specific gravity of the mineral aggregate exceeds 2.80, the Department will adjust the

414.12

tonnage of mineral aggregate for payment by multiplying the tonnage of mineral aggregate used by a specific gravity of 2.80 and dividing by the higher specific gravity.

**SECTION 415 – COLD PLANING OF BITUMINOUS
PLANT MIX PAVEMENTS**

415.01 Description.....	381
415.02 Equipment.....	381
415.03 General Requirements.....	382
415.04 Surface Requirements	383
415.05 Method of Measurement.....	383
415.06 Basis of Payment.....	384

DESCRIPTION

415.01 Description

This work consists of cold planing an existing bituminous plant mix pavement.

EQUIPMENT

415.02 Equipment

Provide a power broom, a water truck, and a planing machine, as well as equipment to remove the material planed from the pavement.

The planing machine shall be a power operated, self-propelled milling machine or grinder capable of removing bituminous concrete to the required width, depth, profile, cross-slope, and surface texture. The machine shall be capable of accurately establishing profile by referencing from either the existing pavement or from an independent grade control and shall have positive means for controlling cross-slope. The machine shall have a floating moldboard with sufficient down pressure to plane the milled surface. The machine shall have an effective means of removing cuttings from the pavement and for preventing dust from escaping into the air.

When milling the Interstate or controlled access freeways, the planing machine shall be capable of restoring pavement profile with a non-contact leveling system. The non-contact leveling system shall have a minimum of three sensors dispersed the length of the machine.

415.03

The maximum spacing between teeth on the cutter drum shall not exceed 5/8 inches. Provide supplemental equipment as necessary to remove material in areas that cannot be reached by the planing machine.

CONSTRUCTION REQUIREMENTS

415.03 General Requirements

Coordinate operations so that vertical longitudinal faces do not exceed 1-1/4 inches in height in areas to be used by public traffic. Taper transverse faces in a manner approved by the Engineer to avoid creating a traffic hazard. Perform cold planing in the direction of traffic.

When milling roadways for hot mix overlays, operate the planing machine at a consistent forward speed to provide an acceptable surface texture. The maximum allowable forward speed shall be 60 feet per minute when the teeth spacing is between 1/2 and 5/8 inches, and 80 feet per minute when the teeth spacing is less than 1/2 inch.

After planing, ensure that the finished surface provides a smooth riding surface free of scallops, scabs, gouges, ridges, oil film, and other imperfections of workmanship, has a uniform texture, and is true to the required grade and cross-section. The elevation of the longitudinal edges of adjacent cuts shall not differ more than 1/8 inch.

Do not begin milling unless the subsequent layer of pavement can be placed within the limitation specified in **407.09**.

Thoroughly sweep the planed pavement immediately behind the machine, and haul away all materials swept up. When the Engineer deems necessary, provide and use a water truck to control dust.

Where sound pavement has been gouged, torn, or otherwise damaged during the milling operations, or damage is done to any other property of any kind including utility frames, grates, and covers, make repairs at no cost to the Department. Take appropriate measures so that the cold planing operation does not trap water.

415.04 Surface Requirements

Where the planed pavement is not to be resurfaced, provide a uniform texture throughout the Project and a satisfactory riding surface. The average texture depth shall be no less than 0.20 inches.

The finished surface on the Interstate and controlled access freeways shall be of uniform profile throughout, without any scabbing, scallops, gouges, ridges, or other imperfections resulting from worn cutter teeth, improper operating speeds, poor equipment maintenance, or other instances of poor workmanship. The cross-slope shall be as shown on the Plans in the tangent, transition, and super-elevated curve sections.

The finished surface after the final cut shall not show a deviation greater than 1/8 inch from a 10-foot straightedge, and the cross-slope shall not deviate more than 3/8 inches in 10 feet. Correct all irregularities exceeding these limits.

Texture all approaches and tapers when required by the Engineer. Length, width, and depth of cut on approaches and tapers shall be as determined by the Engineer. Match the approaches and tapers to the finished cut on the main line, and transition to the existing surface to within plus or minus 1/8 inch.

When deemed necessary by the Engineer, transition private entrances to provide a smooth approach to the roadway.

Unless otherwise shown on the Plans, take ownership of the cuttings and remove them from the Project.

COMPENSATION**415.05 Method of Measurement**

The Department will measure Cold Planing of Bituminous Pavement by the quantity of material removed in tons or cubic yards, or by the square yard of planed pavement. The method of measurement will depend upon the pay item designated in the proposal.

Where payment is by the square yard, the Department will measure the pavement acceptably planed by the square yard in accordance with **109**.

415.06

Unless otherwise specified, the Department will not measure water used to control dust for separate payment but will consider it incidental to the planing operation.

415.06 Basis of Payment

The Department will pay for the accepted quantity of Cold Planed Bituminous Pavement at the contract unit price, which payment shall be full compensation for all labor, materials, equipment, hauling, and incidentals necessary to plane the pavement, control dust, and dispose of the cuttings.

PART 5 – RIGID PAVEMENT

SECTION 501 – PORTLAND CEMENT CONCRETE
PAVEMENT 386

**SECTION 501 – PORTLAND CEMENT CONCRETE
PAVEMENT**

501.01	Description	387
501.02	Materials	387
501.03	Proportioning and Quality Assurance of Concrete.....	387
501.04	Equipment	389
501.05	Subgrade Preparation	393
501.06	Construction of Base.....	393
501.07	Setting Forms	393
501.08	Conditioning of Base.....	394
501.09	Handling, Measuring, and Batching Material	394
501.10	Mixing Concrete	394
501.11	Mixing Limitations.....	395
501.12	Placing Concrete	395
501.13	Testing Concrete	398
501.14	Strike-Off of Concrete and Placement of Reinforcement	398
501.15	Joints	399
501.16	Final Strike-Off, Consolidation and Finishing	403
501.17	Surface Testing, Pay Factors, and Corrective Action.....	406
501.18	Curing	409
501.19	Removing Forms.....	411
501.20	Sealing Joints	412
501.21	Protection of Pavement	412
501.22	Opening to Traffic.....	413
501.23	Shoulders.....	413
501.24	Tolerance in Pavement Thickness.....	414
501.25	Method of Measurement	416
501.26	Basis of Payment.....	416

DESCRIPTION

501.01 Description

This work consists of constructing a pavement of Portland cement concrete, with or without reinforcement as specified, on a prepared surface.

MATERIALS

501.02 Materials

A. General

Provide materials as specified in:

Portland Cement	901.01
Fine Aggregate.....	903.01
Coarse Aggregate.....	903.03
Preformed Joint Fillers (Non-Extruding and Resilient Types).....	905.01
Joint Sealants	905.05
Reinforcing Steel and Dowel Bars.....	907
Curing Materials	913
Water	921.01
Air-Entraining Admixtures	921.06
Chemical Additives	921.06
Fly Ash	921.15
Slag Cement.....	921.16

B. Fly Ash and Slag Cement

Meet the requirements in **604.02**.

501.03 Proportioning and Quality Assurance of Concrete

A. Proportioning

- 1. Design and Production Parameters.** The concrete design shall be air entrained and produce a workable concrete mix meeting the design and production parameters specified in Table 501.03-1.

501.03

Table 501.03-1: Class CP – Paving Concrete

28 Day Compressive Strength, min (PSI)	Minimum Cementitious Content (pounds per cubic yard)	Maximum Water/Cement Ratio (pound/pound)	Air Content (%)	Slump (inch)
3000	526 ¹ 545 ²	0.45	5% design 3 – 8% production	0 – 2 ³ 3 ± 1 ⁴

(1) 526 pounds required when the coarse aggregate is crushed stone
 (2) 545 pounds required when the coarse aggregate is gravel
 (3) Allowable slump for slipform paving
 (4) Allowable slump for other than slipform paving

The fine aggregate shall not exceed 44% by volume calculation of the total aggregate.

Do not use sand manufactured from limestone or other polishing aggregates in the construction of traffic lanes.

The Contractor may include chemical admixtures in the concrete mixture based on the ambient air temperature and expected weather conditions.

Admixtures to be incorporated into the concrete shall be compatible and incorporated into the concrete in accordance with the manufacturer’s recommendations. Concrete mixtures utilizing multiple admixture manufacturers shall prove compatibility in accordance with Departmental procedures.

2. Mix Design Submittal

Submit in accordance with **604.03.A.2**, except that compressive strength specimens (7, 14, 28-day, etc.) shall be 6-inch by 12-inch due to the size of the coarse aggregate.

3. Partial Cement Replacement with Fly Ash or Slag Cement

Meet the requirements in **604.03.A.3**.

The Contractor may use ternary cementitious mixtures (mixtures with Portland cement, slag cement, and fly ash) for Class CP Concrete so long as the minimum Portland cement content is 50%. The maximum amount of fly ash substitution in a ternary blend shall be 20%. Substitution rates shall be at a 1:1 ratio.

4. **Use of Class A Concrete.** If approved by the Engineer, the Contractor may use Class A Concrete, as specified in **604** and modified herein, in variable width sections, ramps, and on projects containing 10,000 square yards of concrete pavement or less. The slump shall be modified to be a maximum of 3 inches, and the compressive strength of cylindrical specimens molded, cured and tested in an approved laboratory shall be not less than 3,000 psi at 28 days. The Department will not make additional payment to the Contractor for increased costs due to the use of this mixture.

B. Quality Control and Acceptance of Concrete

Meet the requirement of **604.03.B**.

EQUIPMENT

501.04 Equipment

Obtain the Engineer's approval as to the design, capacity, and mechanical condition of equipment and tools used to handle materials and perform all parts of the Work. Have the equipment at the jobsite sufficiently ahead of the start of construction operations to allow the Engineer to perform a thorough examination.

A. Batching Plant, Multi-Aggregate Feed System, and Equipment

Meet the requirements of **604.04.A**.

B. Mixers

Meet the requirements in **604.04.B**.

1. **Mixers at Site of Construction.** In addition to meeting the requirements of **604.04.B.1**, mixers at the site of construction, unless

501.04

otherwise stipulated, shall also meet **105.17** and shall be capable of discharging and distributing the mix without segregation on the prepared subgrade or sub-base.

- 2. Truck Mixers and Truck Agitators.** In addition to meeting the requirements of **604.04.B.3**, mixers or agitators used to mix and transport paving concrete shall be of the hydraulic drum lift type or other specially designed types that will discharge low slump concrete $\frac{1}{2}$ to 1-1/2 inches at a satisfactory rate without segregation. The Contractor may use approved conventional or standard truck mixers or truck agitators for mixing and hauling concrete under **604**, for projects that contain 10,000 square yards or less of concrete paving.
- 3. Non-agitator Trucks.** Bodies of non-agitator hauling equipment for concrete shall be smooth, mortar-tight, metal containers, and shall be capable of discharging the concrete at a satisfactorily controlled rate without segregation. Provide covers to protect the concrete.

C. Forms

Use straight side forms of metal having a thickness of not less than $\frac{7}{32}$ inch and furnished in sections not less than 10 feet in length. Forms shall have a depth at least equal to the required edge thickness of the concrete, without horizontal joint, and a base width equal to at least the depth of the forms. For curves of 100-foot radius or less, use flexible or curved forms of wood or metal, of the proper radius, and of a design acceptable to the Engineer. Provide forms with adequate devices for secure setting so that when in place they will withstand, without visible spring or settlement, the impact and vibration of the consolidating and finishing equipment. Flange braces shall extend outward on the base not less than $\frac{2}{3}$ the height of the form. Ensure that the top face of the form does not vary from a true plane by more than $\frac{1}{8}$ inch in 10 feet, and the face of the form does not vary more than $\frac{1}{4}$ inch. The forms shall contain provisions for locking the ends of abutting form sections together tightly, and for secure setting. Metal pins shall be of proper size and length to hold the forms rigidly and securely in place.

Do not use built-up forms except where the total area of pavement of any specified thickness on the Project is less than 10,000 square yards. Built-up forms shall have a minimum base width of 8 inches.

Remove forms with battered top surfaces and forms that are bent, twisted, or broken. Do not use repaired forms until inspected and approved by the Engineer.

Provide and maintain in satisfactory condition an adequate supply of forms to meet the needs of a full day's production.

D. Spreading and Finishing Equipment

Equipment shall include a paving machine designed to uniformly vibrate and finish the concrete full width and to its final grade.

- 1. Vibrators.** Vibrators for full-width and full-depth vibration of concrete paving slabs shall be multiple spuds or other types approved by the Engineer. Either attach the vibrators to the spreader or the finishing machine or mount them on a separate carriage. Operate the vibrators at the frequency recommended by the manufacturer, subject to approval of the Engineer. Submit to the Engineer the manufacturer's recommendations for installing and operating vibrators.
- 2. Longitudinal Floats.** Provide a mechanical longitudinal float, of a design approved by the Engineer, which is in good working condition and constructed to allow accurate adjustment to the required crown.
- 3. Bridges.** Furnish a minimum of two individual work bridges.
- 4. Finishing Straightedge.** Provide at least two straightedges, with handles at least 3 feet longer than half the width of the slab, constructed of light metal, and not less than 10 feet long. Ensure that the straightedges remain clean and straight.
- 5. Straightedge Templates.** Provide at least two straightedge templates for testing the completed surface. They may be of wood or metal; shall not be less than 12 feet long; and shall be clean, straight, and free from warp.
- 6. Water Supply Equipment.** Water supply equipment shall include pumps, or tanks mounted on trucks, of adequate capacity to furnish more than sufficient water to accommodate the construction and at the required and necessary pressure. A pipeline appropriate to the requirements of the construction may be used.

501.04

7. **Small Tools.** Provide edgers, trowels, hand floats, brushes, and other small tools necessary to produce the results required.
8. **Special Equipment and Tools.** Equipment and tools necessary to construct special features as shown on the Plans shall be able to produce the results required.
9. **Transverse Grooving Equipment.** Mechanical transverse grooving equipment shall consist of a steel tine comb with a minimum width of 6 feet, a vibrating beam roller, or other approved devices.
10. **Concrete Saw.** If sawed joints are elected or specified, provide sawing equipment adequate in number of units and power to complete the sawing to the required dimensions and at the required rate. The saws shall be equipped with water-cooled diamond edge blades. For sawing longitudinal joints, use saws equipped with guides to ensure proper alignment of the joints.

Provide at least one standby saw in good working order. Maintain an ample supply of saw blades onsite at all times during sawing operations. Provide adequate artificial lighting facilities for night sawing. Have all equipment onsite both before and continuously during concrete placement.

11. **Slip-form Paver.** Provide slip-form pavers designed to spread, consolidate, screed, and float-finish freshly placed concrete in one complete pass of the paver so that only a minimum of hand finishing will be necessary to provide a dense and homogeneous pavement that conforms with the Plans and Specifications. The slip-form paver shall be an approved self-propelled type, equipped with a crawler type track of sufficient area to prevent track slippage under load or sinking into the supporting subbase/subgrade. The length of ground contact per track and arrangement of track units shall be adequate to ensure the established straightedge tolerance. When using slip-form pavers, comply with all provisions and requirements of these Specifications that do not conflict with slip-form construction.

Control pavement alignment with an electronic sensing device in continuous contact with a sensing guide. Furnish equipment with electronic controls for vertically adjusting the paver strike-off and finishing components. Provide, install, and maintain electronic

controls, sensing devices, and sensing guides at no additional cost to the Department.

CONSTRUCTION REQUIREMENTS

501.05 Subgrade Preparation

Prepare the subgrade as provided for under 207.

501.06 Construction of Base

Construct the base as specified in the applicable Section of Part 3 – Bases and Subgrade Treatments, of these Specifications.

Construct the base to such grade tolerances as will ensure the required concrete pavement thickness is obtained.

Complete the base at least 500 feet in advance of paving.

Equip the base grading machine and slip-form paver with automatic line (guidance) and grade controls.

501.07 Setting Forms

A. Base Support

Ensure that the foundation under the forms is firm and true to grade so that each form, when set, will be firmly in contact for its whole length and at the specified grade. Fill all grade at the form line, which is found to be below established grade, up to grade with suitable material in lifts of ½ inch or less for a distance of 18 inches on each side of the base of the form, and thoroughly compact the material. Correct all grade at the form line found to be above grade by tamping or cutting as necessary. Do not rest the forms on pedestals of earth or other material to bring them to grade.

B. Form Setting

Set and obtain approval of forms a minimum of 500 feet in advance of the point where concrete is being placed. The Contractor may reduce this distance as approved by the Engineer when prevailing conditions justify a shorter distance. After setting the forms to the correct grade,

501.08

thoroughly tamp, mechanically or by hand, the material supporting the forms, at both the inside and outside edges of the base of the forms. Stake forms into place with not less than three pins for each 10-foot section. Place a pin at each side of every joint. Ensure that form sections are tightly locked and free from play or movement in any direction. Do not allow the forms to deviate from true line by more than ¼ inch at any point. Reset or remove as directed forms that settle or spring under the spreading and finishing equipment. Clean and oil the top and face of forms before placing concrete.

C. Grade and Alignment

Immediately before placing the concrete, check the alignment and grade elevations of the forms and correct as necessary. When a form has been disturbed or a grade has become unstable, reset and recheck the affected form.

501.08 Conditioning of Base

Check and correct the grade immediately ahead of concrete placing operations. Use an approved machine with automatic grade control to attain the final section. If the slip-form method of paving is used, place, compact, and finish the base to the proper grade to a width beyond the pavement limits sufficient to support all paving equipment.

Remove and replace high areas. The Contractor may fill low areas with base material and compact to correspond with the surrounding areas; except that for low areas in cement treated bases and bituminous bases, fill with concrete integral with the pavement. Repair low areas in lean concrete base as directed by the Engineer.

The base shall have been previously wetted and shall be in a moist condition at the time of placing concrete. If the base subsequently becomes dry before the actual placing of concrete, sprinkle it, while taking care to avoid forming pools of water. The base shall not be muddy or soft.

501.09 Handling, Measuring, and Batching Material

Meet the requirements in **604.11**.

501.10 Mixing Concrete

Meet the requirements in **604.13**.

Transport mixed concrete as required by **604.13** or in non-agitating trucks having special bodies. When truck mixers are used on hauls in excess of 1 hour, add the cement at the site of construction and perform mixing as specified under this Subsection.

From the time water is added to the mix to the time the concrete is deposited in place, no more than 30 minutes shall elapse for concrete hauled in non-agitating trucks, and no more than 60 minutes shall elapse for concrete hauled in truck mixers or truck agitators.

501.11 Mixing Limitations

Meet the requirements in **604.12**.

501.12 Placing Concrete

Either unload the concrete into an approved spreading device, or deposit it directly on the base, and mechanically spread the concrete in a manner that prevents segregation of the materials. When using central or transit mixed concrete, deposit it in an approved spreader. Place the mixture to minimize rehandling and relocation from point of placement. The mechanical spreader will not be required on areas too small to accommodate the paving equipment, projects that contain 10,000 square yards or less of concrete paving, and on variable width sections and ramps. Placing shall be continuous between transverse joints without the use of intermediate bulkheads. Do not place concrete on frozen grade.

Perform any necessary hand spreading with shovels or other approved tools. Do not allow workmen to walk in the freshly mixed concrete with boots or shoes coated with earth or other foreign substances.

If placing concrete adjacent to a previously constructed lane of pavement and mechanical equipment is to be operated on this existing lane of pavement, that lane shall meet the requirements for opening to traffic specified in **501.22**. If the existing lane is to only carry finishing equipment, the Contractor may begin paving the adjoining lanes after 7 days.

Deposit concrete as near to expansion and contraction joints as possible without disturbing them; do not dump concrete from the discharge bucket or hopper onto a joint assembly unless the hopper is well centered on the joint assembly.

501.12

Immediately remove all concrete materials that may fall on or be worked into the surface of a completed slab using approved methods.

When using the slip-form method of concrete paving, place the concrete with an approved slip-form paver meeting the requirements of **501.04.D.11**.

Ensure that the sliding forms are rigidly held together laterally to prevent spreading of the forms. The forms shall trail behind the paver for such a distance that no appreciable slumping of the concrete will occur and so that necessary finishing can be accomplished while the concrete is still within the forms. Before the concrete has hardened, correct any edge slump of the pavement, exclusive of edge rounding, in excess of $\frac{1}{4}$ inch.

Operate the slip-form paver with as nearly a continuous forward movement as possible, and coordinate all operations of mixing, delivering, and spreading of concrete to provide uniform progress while minimizing the stopping and starting of the paver. If, for any reason, it is necessary to stop the forward movement of the paver, also immediately stop the vibratory and tamping elements. Apply no tractive force to the machine, other than that which is controlled from the machine. Replace slabs with random cracks before completion of paving operations.

Contractor may choose to utilize a single lift or two lift paving process according to the following requirements.

A. Single Lift Pavement

Use vibrators to thoroughly consolidate the concrete against and along the faces of all forms and along the full length and on both sides of all joint assemblies. Do not allow vibrators to come in contact with a joint assembly, the grade, or a side form. Do not operate the vibrator for longer than 5 seconds in any one location.

The Contractor may only use hand-operated vibrators on projects containing 10,000 square yards or less of concrete paving and on variable width sections. Only operate vibrators mounted on a machine while the machine is in motion.

Equip the slip-form paver with vibrators meeting the applicable requirements of **501.04.D.1** to vibrate the concrete for the full width and depth of the strip of pavement being placed.

B. Two Lift Composite Pavement

When placing two lift composite pavements, the upper lift shall be of a lesser thickness as designated by contract design. It shall be placed such that the result is a wet-on-wet application. The lower lift will be one foot less in width than the upper lift.

Paving operations shall be adjusted and approved by the Engineer as necessary to assure a wet-on-wet monolithic pavement section. If the bonding between lifts or the consolidation of concrete is determined to be unsuitable by the Engineer, the lower lift shall be removed and replaced prior to the upper lift placement.

1. **Lower Lift.** Uniformly spread concrete with a spreader or slipform machine. Internal vibration will be required for the lower lift. Tie bars and dowel bars (with the use of dowel baskets) shall be placed in the lower lift at mid-depth of the finished concrete pavement thickness. The lower lift shall not require curing, texturing, or sawing before the upper lift is placed. The lower lift shall be struck off to provide a nominal lower lift thickness that complies with the pavement design. The upper lift shall be struck off to allow for the finished total pavement to conform to the cross section shown in the contract plans.
2. **Upper Lift.** Place the upper lift within 45 minutes following the placement of the lower lift. Placement of the upper lift shall be such that intermingling of the two concrete mixtures is minimal. External vibration for the upper lift will be allowed if proper consolidation and finishing can be demonstrated in accordance with **501.16**. Dowel bars can be inserted during the placement of the upper lift. Cure the upper lift only in accordance with **501.18**. At no time shall the total thickness be less than shown on the pavement design and the cross section shown in the contract plans.

Frequency of the vibrators shall be established based on the workability of the concrete mixture and past experiences. Electronic, internal, T-shaped, poker vibrators shall be used. Other types of vibrating equipment may be approved by the Engineer. Vibrator impulses shall be delivered directly to the concrete and the intensity of vibration shall be sufficient to consolidate the concrete thoroughly and uniformly throughout the depth and width of the lift. Increase in the speed of the vibrators will be allowed with the permission of the Engineer.

501.13

A paving plan shall be supplied to the Engineer for review and approval prior to pouring. The plan shall document procedures to ensure consistency of material properties during concrete placement and finishing, identify and eliminate potential for load misidentification, and maintain speed of production and paving. Concrete for each lift shall be produced from the same ready-mix facility.

501.13 Testing Concrete

All sampling and testing of materials will be performed in conformance with Departmental procedures. During the process of work if either the slump or air consistency tests give results outside the allowable specification range, do not place any additional concrete until the slump, air content, or both is brought within specification limits.

The Engineer will determine the 28-day compressive strength of the concrete under construction by conducting tests during the progress of work in accordance with **604.15**. The method of making and curing test specimens will be in accordance with AASHTO T 23. Furnish the concrete necessary for the Engineer to conduct the field tests and provide a storage facility with watertight tanks of satisfactory size and number to accommodate the cylinder specimens. The Engineer may allow concrete that fails to meet the specified strength to remain in place, but the Department will pay for such concrete at a reduced price as specified in **604.31** to compensate for the loss of strength. Any reduction in payment because of low strength will be in addition to any reduction in payment related to deficiencies in pavement thickness or rideability.

The Engineer will determine pavement thickness from test cores drilled by the Contractor from each unit of pavement in accordance with **501.24**.

501.14 Strike-Off of Concrete and Placement of Reinforcement

Following the placing of concrete, strike it off to conform to the cross-section shown on the Plans and to an elevation such that when the concrete is properly consolidated and finished, the surface of the pavement will be in reasonably close conformity with the elevation shown on the Plans or established by the Engineer. When reinforced concrete pavement is placed in two layers, strike off the entire width of the bottom layer to such length and depth that the sheet of fabric or bar mat may be laid full length on the concrete in its final position without further manipulation. When steel fabric is indicated, place it in strips transverse to the roadway at the depth and with the lap shown on the Plans. The fabric shall extend to within 2 inches of the

ends and sides of the slab. Place the reinforcement directly on the concrete, and then place, strike off, and screed the top layer of the concrete. Remove and replace with freshly mixed concrete, at no cost to the Department, all portions of the bottom layer of concrete left in place for more than 30 minutes without being covered with the top layer. When reinforced concrete is placed in one layer, the Contractor may position reinforcement in advance of concrete placement or place it after spreading the concrete by mechanical or vibratory means.

Ensure that reinforcing steel is free from dirt, oil, paint, grease, mill scale, and loose or thick rust that could impair the bond of the steel with the concrete.

501.15 Joints

Construct joints of the type and dimensions and at the locations shown on the Plans and in accordance with these Specifications.

Unless otherwise specified or directed, all contraction and construction joints shall be of the plain sawed groove type.

A. Longitudinal Joints

Install longitudinal joints perpendicular to the pavement surface and along or parallel to the centerline of the pavement, unless otherwise specified.

Place deformed steel tie bars of the specified length, size, spacing, and materials across and perpendicular to the longitudinal joints. Place the tie bars using approved mechanical equipment or rigidly secure them by chairs or other approved supports to prevent displacement. When using the slip-form method of paving, place the tie bars before vibrating.

To install tie bars in existing hardened concrete, pre-drill holes into the existing concrete slab to a minimum depth of half the tie-bar length and to a diameter of no more than 1/8 inch greater than the tie-bar. Thoroughly clean all pre-drilled holes using a wire brush and compressed air. Secure the tie bars using epoxy or adhesive material capable of withstanding minimum average pull-out resistance of 12,000 pounds or a maximum slippage of 1/32 inch. Provide jacking equipment or other suitable means to test the tie bars to meet the minimum pull-out resistance to the satisfaction of the Department.

501.15

A representative test section of a minimum of 15 tie bars or 2% of the total amount used on the Project shall be tested to determine if the installation method is acceptable. The Engineer will base acceptance on the pull-out data of this test section. The Engineer may require more than one test section if the Contractor's methods and procedures vary from the original procedure or there is reason to believe the installation is faulty.

Include all costs involved in the above procedure in the price bid for concrete pavement.

Cut longitudinal sawed joints with approved concrete saws to the depth, width, and line shown on the Plans, not later than 10 days after placing concrete and before any equipment or vehicles are allowed on the pavement.

Immediately after sawing, thoroughly clean all longitudinal contraction and construction joints of all residue by flushing with water under pressure.

B. Transverse Expansion Joints

Construct transverse joints to be straight, vertical to the pavement surface, and at the angle to the centerline of the pavement shown on the Plans.

Provide dowels across transverse expansion joints as shown on the Plans.

Secure dowels in position, parallel to the surface and centerline of the slab, with an approved metal device that is left in the slab. Unless otherwise specified, paint dowels with one coat of approved primer and thoroughly coat with a thin film of oil or approved bond breaker. If using oil, apply it after the paint has dried and immediately before placement. If corrosion resistant dowels are specified, use the bond breaker recommended by the dowel or coating manufacturer or as directed by the Engineer. Cover one end of each dowel with a close fitting, closed-end metal or plastic sleeve, not less than 4 inches long. Provide a flange or other approved device to separate the end of the sleeve and the end of the dowel during the placing of the concrete so that a space of not less than the proposed thickness of the joint plus ¼ inch will be provided for subsequent movement of the dowel in the sleeve. Use a sleeve type on the dowel bars that meets the Engineer's approval. Dowels shall have

ends free from burrs and distortions. Cut wires of dowel baskets before concrete placement.

To install premolded joint filler, if specified, the Contractor may use either of the alternate expansion joint and dowel assembly devices shown on the Plans or other approved expansion joint assemblies. The installing device shall have a length of $\frac{1}{2}$ inch less than the width of the slab. Assemblies shall be a rigid metal device capable of holding dowels and filler firmly in position during the entire construction operation and shall remain in place. Set the top of the filler below the surface of the proposed slab to accommodate the type of sealant specified, as shown on the Plans. When in position, the filler shall be perpendicular to the surface of the slab. While placing the concrete, protect the top edge of the filler with an approved metal channel cap. The Contractor may use an assembly device with a self-contained cap.

C. Transverse Contraction Joints

Place transverse contraction joints at the intervals specified and to result in the desired shape. Do not use formed contraction joints unless specified or required by the Engineer to control random cracking.

Place load transfer dowels at the intervals and depths shown on the Plans. Unless otherwise specified, paint dowels with one coat of approved primer and thoroughly coat with a thin film of oil or approved bond breaker. If using oil, apply it after the paint has dried and immediately before placement. If corrosion resistant dowels are specified, use the bond breaker recommended by the coating manufacturer or as directed by the Engineer.

Instead of using dowel assemblies at contraction joints, the Contractor may place dowel bars in the full width of pavement using a mechanical device approved by the Engineer. To use a dowel implanting device, first demonstrate accurate dowel placement and pavement finish.

- 1. Sawing.** Begin sawing the joints as soon as concrete has hardened sufficiently to allow sawing without excessive raveling. Once started, continue with the sawing operation until all transverse contraction joints are sawed. When necessary, provide for bad weather or nighttime operations. Omit the sawing of a joint if a crack occurs at or near the joint location before the time of sawing. Discontinue the sawing of a joint when a crack develops ahead of the saw. In general, saw all joints in sequence.

501.15

Saw all contraction joints in lanes adjacent to previously constructed lanes before uncontrolled or sympathy cracking occurs. If extreme conditions exist that make it impracticable to prevent erratic cracking by early sawing, form a contraction joint groove at intervals of every third or fourth joint or as often as required prior to initial set of concrete as provided for under paragraph (2) below. Immediately after sawing, thoroughly clean the joints of all residue by flushing with water under pressure.

Obtain the Engineer's approval of all sawing equipment as specified in **501.04.D.10**. Only use lightweight sawing equipment on the newly constructed pavement. The Contractor may use gang saw units or similar heavy equipment if the equipment is operated from a bridge or platform supported independently of the pavement.

2. **Formed Joints.** Construct formed contraction joints during the placing of the concrete. Form these joints by placing inserts in the plastic concrete, at the angle to the centerline of the pavement shown on the Plans and perpendicular to the surface. When the concrete has attained its initial set and after the joint has been carefully finished, remove the insert. Ensure that the groove so formed maintains its full width and depth as shown on the Plans, and the pavement at the joint meets surface requirements.

D. Transverse Construction Joints

Construct transverse construction joints to provide a uniform surface. Provide the surface texture as specified in **501.16.G** as needed. Install transverse construction joints when an interruption of more than 30 minutes occurs during the concreting operations. Do not construct transverse joints within 10 feet of an expansion joint, contraction joint, or plane of weakness. If sufficient concrete has not been mixed at the time of interruption to form a slab at least 10 feet long, remove the excess concrete back to the previous joint and dispose of as directed.

E. Expansion Joints at Structures

Place premolded joint filler against all structures and features projecting through, into, or against the slab to form expansion joints. Such joints shall extend the full depth of slab and, unless otherwise specified, shall be ½ inch in width.

501.16 Final Strike-Off, Consolidation and Finishing**A. Sequence**

Perform operations in the following sequence: strike-off and consolidation, floating and removal of laitance, straight-edging, and final surface finish.

B. Finishing at Joints

Consolidate concrete adjacent to joints to eliminate voids or segregation, against the joint material, under and around all load transfer devices, joint assembly units, and other features designed to extend into the pavement.

After the concrete has been placed and vibrated adjacent to the joints as specified in **501.12**, bring the finishing machine forward, operating it in a manner that will avoid damage or misalignment of joints.

C. Machine Finishing

Distribute or spread the concrete as soon as placed. Immediately after spreading, strike off and screed the concrete with an approved finishing machine that meets **501.04.D.1**. When the pan-float finisher combination machine is used for finishing the pavement, longitudinal floats are not necessary.

Vibrators, for full width and depth vibration of concrete paving slabs, shall meet **501.04.D.1**. If uniform and satisfactory consolidation of the concrete is not obtained by the vibratory method at joints, along forms, at structures, and throughout the pavement, furnish equipment and methods that will produce satisfactory work.

D. Hand Finishing

The Engineer may allow hand finishing methods in the following situations:

1. Mechanical equipment breaks down after concrete has already been deposited on the grade.

501.16

2. Variable width sections make the use of finishing machines impracticable.

When the Engineer allows hand finishing, strike-off and screed the concrete as soon as it is placed. Use a screed that is at least 2 feet longer than the maximum width of the slab to be struck off, of approved design, and sufficiently rigid to retain its shape. When reinforcement is used in the pavement, provide a strike-off template for striking off the bottom layer of concrete.

Consolidate the concrete using a suitable vibrator and other approved equipment.

Repeat screeding until the surface is of uniform appearance, true to grade and cross-section, and free from porous areas.

E. Floating

After the concrete has been struck off and consolidated, use one of the following methods to further smooth, true, and consolidate the concrete. Do not over-finish, or add water to the surface, under either of these methods.

1. **Hand Method.** If hand finishing is allowed as provided for under **501.16.D**, use equipment and methods approved by the Engineer.
2. **Mechanical Method.** Use the mechanical float described under **501.04.D.2** unless otherwise specified. Adjust the tracks from which the float operates to the required cross-section. Accurately adjust and coordinate the float with the adjustments of the transverse finishing machine so that a small amount of mortar is carried ahead of the float at all times. If excessive evaporation is occurring, the Contractor may apply a light fog spray of water. Adjust the forward speed so that the float will lap the distance directed by the Engineer on each transverse trip. Pass the float over each area of pavement at least two times, while preventing excessive operation over a given area. Waste excess water or soupy material over the side forms on each pass.

After floating, remove excess water and laitance from the surface of the pavement with a straightedge 10 feet or more in length. Lap successive drags one half the length of the blade.

F. Straightedge Testing and Surface Correction

After the floating has been completed and the excess water removed, but while the concrete is still plastic, test the concrete surface for trueness using an accurate metal straightedge, not less than 15 feet in length, swung from handles at least 3 feet longer than half the width of the slab. Hold the straightedge in contact with the surface in successive positions parallel to the road center-line, and go over the whole area from one side of the slab to the other as necessary. Advance the straightedge along the road in successive stages of no more than half the length of the straightedge. Immediately fill depressions found with freshly mixed concrete, and strike off, consolidate, and refinish the concrete. Cut down and refinish high areas. Ensure that the surface across joints meets these straightedge requirements. Continue to perform straightedge testing and surface corrections until the entire surface is free from observable departures from the straightedge and the slab conforms to the required grade and cross-section.

If the Engineer determines superficial water is needed to assist in finishing, apply such water by lightly fogging.

G. Surface Texturing

Texture the surface using a burlap drag, consisting of a seamless strip of damp burlap which, when dragged longitudinally along the full width of pavement, produces a uniform surface of gritty texture. Maintain the drag in such condition that the resultant surface is of uniform appearance and reasonably free from grooves over 1/16 inch in depth.

After finishing the pavement by the burlap drag, texture the surface by forming transverse grooves. Form the transverse grooves with mechanical equipment using a comb made of steel tines, vibrating beam roller, or other approved device. The Contractor may use manual tools, such as rakes with spring steel tines, on areas inaccessible to mechanical equipment, or areas of 1,000 square yards or less and variable width.

Form the grooves in the concrete at an appropriate time while the concrete is still in a plastic state, so that in the hardened concrete, the grooves will be between 0.09 and 0.13 inches in width, and between 0.12 and 0.19 inches in depth. Space the grooves at random intervals between 0.3 and 1.0 inches.

501.17

Regardless of the method used to form the grooves, ensure that the grooves are relatively smooth and uniform, and are formed without excessive tearing of the surface and without bringing pieces of the coarse aggregate to the top of the surface.

If the equipment breaks down or experiences mechanical failure, the Contractor may use manual tools for grooving, provided all mixing and placing operations cease until proper repairs are made.

Correct, at no expense to the Department, all individual areas of 50 square yards or larger of the hardened grooved concrete that do not conform to these requirements, by cutting acceptable grooves in the hardened surface with an approved cutting machine or by other approved methods.

H. Edging at Forms and Joints

After the final finish, but while the concrete is still in a plastic state, round the outside edges of the pavement to a $\frac{3}{4}$ -inch radius. When pavement is formed along a lane line, round the edges to a $\frac{1}{4}$ -inch radius. Round the edges of the pavement on each side of transverse expansion joints, formed joints, and transverse construction joints to a $\frac{1}{4}$ -inch radius. Perform edging with an approved edging tool that will produce a well-defined and continuous radius. Eliminate all tool marks formed by the edging tool by brushing to form a texture similar to the burlap drag finish.

501.17 Surface Testing, Pay Factors, and Corrective Action

All surface testing and any required corrective work shall be performed as soon as practicable and before sealing joints and opening to traffic.

A. Rideability Testing

The Department will conduct rideability testing using a roadway profiler to provide an International Roughness Index (IRI). Testing will be performed on each lane for mainline, auxiliary lanes, and ramps.

Schedule rideability testing at least seven days prior to need. Clean and clear the area to be tested of all obstructions. Wheel paths will be located 3 feet to each side of the centerline of each traffic lane.

For mainline, exit ramps, and auxiliary lanes, testing will begin 25 feet before the start of the concrete surface. Consider ramps between freeways that do not have stop or yield conditions to be mainline pavement. For exit ramps, test sections shall terminate 50 feet from a stop or yield condition. For entrance ramps, test will begin at the start of the new paved ramp.

To determine pavement rideability, the Department will evaluate the pavement using 0.1-mile Mean IRI (MRI) sections for overall roughness and IRI for individual continuous 25-foot sections for localized roughness in each wheel path. Mean IRI (MRI) shall be the average of each wheel path. Each 0.1-mile section will be considered a lot. IRI data will be calculated per ASTM E 1926. Each lot shall have a maximum Mean IRI value of 90 inches per mile. No individual continuous 25-foot section shall exceed an IRI of 175 inches per mile in either wheel path.

For low speed ramps with a posted speed of 40 MPH or less, each lot shall have a maximum Mean IRI value of 100 inches per mile. No individual continuous 25-foot section shall exceed an IRI of 220 inches per mile in either wheel path.

B. Pay Factor and Required Corrective Action

Perform corrective action to reduce the Mean IRI for each lot or IRI for any individual continuous 25-foot section that fails to meet the requirements specified. Perform corrective action to reduce the Mean IRI for each 0.1-mile lot with a Mean IRI above 90 inches per mile and 100 inches per mile for ramps with posted speed of 40 MPH or less. No more than 0.25 inches (two grinding passes) of material shall be removed by corrective diamond grinding without approval of the Engineer.

For lots exceeding a Mean IRI of 90 inches per mile or 100 inches per mile for (\leq 40 MPH) low speed ramps after corrective action is performed, a pay adjustment will be assessed in accordance with Figure 501.17-1.




Figure 501.17-1: Pay Factors and Corrective Action

Lots less than the 0.1 mile in length shall meet localized roughness requirements. The 25-foot continuous average sections of localized roughness must be corrected regardless of Mean IRI results.

A grinding strategy plan is required before any corrective action begins. Submit a copy of the grinding plan to the Engineer at least 5 days prior to starting any work. Perform required corrective work with approved grinding equipment or removing and replacing pavement as directed by the Engineer. Perform all corrective action at no cost to the department. Grinding equipment must meet **604.27.C**.

After Corrective action is complete, the Department will retest and evaluate the pavement. Seal all surfaces that are ground with an approved penetrating sealant listed on the Department's QPL.

Establish a positive means for removing grinding and grooving residue. Remove solid residue from pavement surface during the grinding or grooving operations. Do not allow residue to flow across lanes used by public traffic, into gutters, or drainage facilities. Dispose of residue in a manner that will prevent residue, whether in solid or slurry form, from reaching any waterway in a concentrated state.

After the Contractor performs corrective grinding, the Department will test the affected pavement for thickness in accordance with **501.24**.

501.18 Curing

Immediately after completing the finishing operations and as soon as marring of the concrete will not occur, cover and cure the entire surface of the newly placed concrete.

Where curing requires the use of water, ensure that sufficient water is available. Failure to provide a sufficient quantity of one of the curing materials specified in **913**, or lack of water for wet-curing methods, shall be cause for immediate suspension of concreting operations. Do not leave the concrete exposed for more than 30 minutes between stages of curing or during the curing period.

Perform curing according to one of the following methods:

501.18

A. Cotton or Burlap Mats

Entirely cover the surface of the pavement with cotton or burlap mats. The mats used shall be of such length (or width) that, as laid, they will extend at least twice the thickness of the pavement beyond the edges of the slab. Place the mats so that the entire surface and both edges of the slab are completely covered. Thoroughly saturate the mats with water prior to placement. Place and weight down the mats to ensure that they remain in intimate contact with the surface covered. Keep the covering fully saturated and in place for 72 hours after the concrete has been placed unless otherwise specified.

B. Waterproof Paper

Entirely cover the top surface and sides of the pavement with waterproof paper. Lap the units at least 18 inches. Place and weight down the paper to ensure it will remain in intimate contact with the surface covered. The paper shall have such dimensions that each unit as laid will extend beyond the edges of the slab at least twice the thickness of the pavement, or it shall be of pavement width with 3-foot strips of paper provided for the edges. If laid longitudinally, cement together paper not manufactured in sizes that provide this width in such a manner that the joints do not open up or separate during the curing period. Unless otherwise specified, keep the covering in place for 72 hours after the concrete has been placed. Thoroughly wet the surface of the pavement before placing the paper.

C. Impervious Membrane Method

Spray the entire pavement surface and edges uniformly with white pigmented curing compound immediately after finishing the surface and before concrete set has taken place, or, if the pavement is cured initially with jute or cotton mats, apply the curing compound upon removal of the mats. Do not apply curing compound during rainfall.

Apply curing compound under pressure by mechanical sprayers at the rate recommended by the manufacturer. Use spraying equipment of the fully atomizing type equipped with a tank agitator. At the time of use, the compound shall be in a thoroughly mixed condition with the pigment uniformly dispersed throughout the vehicle. During application, stir the compound continuously by effective mechanical means. The Contractor may hand spray odd widths or shapes and concrete surfaces exposed by the removal of forms. Do not apply curing compound to the inside faces

of joints to be sealed. Should the film become damaged from any cause within a 72-hour curing period, repair the damaged portions immediately with additional compound.

Upon removal of side forms, immediately protect the sides of the slabs exposed by applying curing treatment equal to that provided for the surface.

D. White Polyethylene Sheeting

Entirely cover the top surface and sides of the pavement with polyethylene sheeting. Lap the units at least 18 inches. Place and weight down the sheeting to ensure it remains in intimate contact with the surface covered. Use sheeting with such dimensions that each unit as laid will extend beyond the edges of the slab at least twice the thickness of the pavement. Thoroughly wet the surface of the pavement before placing the sheeting. Unless otherwise specified, keep the covering in place for 72 hours after the concrete has been placed.

E. Curing in Cold Weather

Meet the requirements in **604.24**.

When placing concrete in conditions where the air temperature is expected to drop below 35 °F, provide a sufficient supply of straw, hay, grass, or other suitable blanketing material along the work. At any time the temperature is expected to reach the freezing point during the day or night, spread such material over the pavement to a sufficient depth to prevent freezing of the concrete. Take care so as not to mar the concrete surface. Maintain such protection for not less than 5 days.

The Contractor is responsible for the quality and strength of concrete laid during cold weather. The Department reserves the right to require the Contractor to core the concrete to check for damage caused by freezing temperatures. Remove and replace concrete damaged by freezing action at no cost to the Department.

501.19 Removing Forms

The Contractor may remove forms once removal will not cause damage to the slab edges. Remove the forms carefully to avoid damaging the pavement. After the forms have been removed, cure the sides of the slab using one of the methods specified in **501.18**. The Engineer will consider honeycombed

501.20

areas to be defective work. Remove and replace all unsound material with satisfactory material at no cost to the Department.

501.20 Sealing Joints

Seal joints with one of the specified joint sealing materials before opening the pavement to traffic and as soon after completion of the curing period as is feasible. Select the sealant from the Department's QPL and apply it in strict accordance with the manufacturer's recommendations. Immediately before sealing, thoroughly clean each joint of all foreign material, including membrane curing compound, by sandblasting. Subject all joints to high-pressure air blowing prior to sealing. Ensure that the joint faces are clean and dry when applying the seal. Apply the sealant to the joint immediately after cleaning.

Apply the sealing material to each joint opening to conform to the details shown on the Plans or as directed by the Engineer. Perform sealing so as not to spill material on the exposed surface of the concrete. Immediately remove any excess material on the surface of the concrete pavement and clean the pavement surface.

Remove sealing material that does not bond to the concrete, and re-clean and reseal the joint at no expense to the Department.

Ream all random cracks with a suitable tool and fill with an approved joint sealant.

501.21 Protection of Pavement

Protect the pavement and its appurtenances against both public traffic and traffic caused by the Contractor's employees and agents. This shall include watchmen to direct traffic and the erection and maintenance of the warning signs, lights, pavement bridges, or crossovers.

Repair or replace all damage to the pavement prior to final acceptance at no cost to the Department.

Protect all concrete paving against the effects of rain before the concrete is sufficiently hardened; have available at all times materials to protect the edges and surface of plastic concrete. Such protective materials shall include standard metal forms or wood plank having a nominal thickness of not less than 2 inches and a nominal width of not less than the thickness of the pavement at its edge for the protection of the pavement edges, and covering

material such as burlap or cotton mats, curing paper, or plastic sheeting material for the protection of the surface of the pavement. When rain appears imminent, stop all paving operations and direct all available personnel to begin placing forms against the sides of the pavement and covering the surface of the plastic concrete with the protective covering.

501.22 Opening to Traffic

The Engineer will determine when the pavement will be opened to traffic. The Engineer will not allow traffic on the completed pavement until the concrete has attained a compressive strength of 3,000 pounds per square inch or until 14 days following concrete placement, whichever occurs first.

Remove and replace concrete that fails to develop a compressive strength of 3,000 pounds per square inch within 28 days at no cost to the Department, or accept reduced payment in accordance with **501.13**. Ensure pavement is free from construction debris, rocks, and other deleterious materials before opening to traffic. All other testing of the concrete pavement for smoothness and thickness shall be complete before opening to traffic.

501.23 Shoulders

Construct, shape, and dress shoulders according to the shoulder type shown on the Plans as soon as practicable following the completion of the pavement. Shoulders shall be one of the following types:

A. Base with Flexible Surface

Perform this work as specified in the applicable sections of Part 3 – Base and Subgrade Treatments and Part 4 – Flexible Surfaces.

Construct longitudinal joints between the concrete pavement and the asphalt shoulder by sawing, unless otherwise directed by the Engineer, to form an opening 1 inch wide by 1 inch deep, as measured from the lowest elevation. Install sealant with equipment recommended by the sealant manufacturer, which can maintain a uniform, homogeneous mixture throughout the sealing operation. Apply the sealant so that it flows into the joint without overlapping onto the pavement. Remove all sealant that overlaps onto the pavement at no cost to the Department.

501.24

B. Base with Rigid Surface

Perform this work in accordance with the applicable Sections of Part 3 – Base and Subgrade Treatments and Part 5 – Rigid Pavement.

Construct the longitudinal joint between the Portland cement concrete pavement and the Portland cement concrete shoulder in accordance with these Specifications and the details shown on the Plans. Use materials, including tie bars and joint sealant, that are of the same type as the Portland cement concrete mainline pavement.

Construct transverse joints in the Portland cement concrete shoulder to correspond to the transverse joints in the Portland cement concrete roadway and to be of the same type, material, and spacing. Both expansion and contraction joints shall include dowel assemblies of the same type specified for the roadway pavement.

501.24 Tolerance in Pavement Thickness

The Department will determine pavement thickness based on the average measurement of cores taken by the Contractor from each unit as defined in **501.24.A**. The Department will calculate the average thickness of each unit and determine the associated payment for the area represented in accordance with **501.24.B**.

A. Defining Units

For the purpose of determining the pavement thickness and for establishing an adjusted unit price for pavement that is deficient in thickness, the Department will define separate units as follows, unless otherwise specified:

1. Placement widths of 1,000 feet in length, starting at the end of the pavement bearing the smaller station number, will be considered separate units. The placement width is the width of a separately placed lane or lanes.
2. Last units having a length between 500 feet and 1,000 feet will be treated as separate units. The Department will include last units having a length not exceeding 500 feet in the last full unit.
3. Units on interchange ramps will be considered separately from units on the main line.

4. Each intersection will be considered as one unit.
5. Crossovers, entrances, and similar small areas may be combined to form a unit of 1,000 square yards or less. In each unit so established, the Department will make thickness measurements and apply price adjustments, if any, as specified in **501.24.B**, for pavement units on the main line and ramps, except the location and spacing of cores will be as designated by the Engineer.

B. Average Thickness Measurements and Payment Adjustments

Take core samples at locations determined and witnessed by a Department representative and documented on the appropriate form.

When the measurement of the core from a unit is within $\frac{1}{4}$ inch from the Plan thickness, the Department will make full payment for the pavement in the area represented.

When such measurement is deficient by more than $\frac{1}{4}$ inch but not more than 1 inch from the Plan thickness, the Department will direct two additional cores to be taken from within the unit at intervals of not less than 300 feet and will determine the average of the three cores. If the average measurement of these three cores is within $\frac{1}{4}$ inch of the Plan thickness, the Department will make full payment. If the average thickness of the three cores is deficient by more than $\frac{1}{4}$ inch but not more than 1 inch from the Plan thickness, the Department will pay an adjusted price, determined in accordance with **501.26.B**, for the area represented by these cores.

In calculating the average thickness of the pavement unit, the Department will consider measurements that exceed the average thickness by more than $\frac{1}{4}$ inch as the specified thickness plus $\frac{1}{4}$ inch, and will exclude from the average measurements that are less than the specified thickness by more than 1 inch.

When the measurement of any core is less than the specified thickness by more than 1 inch, the Department will determine the actual thickness of the pavement in this area from additional cores taken at not less than 10-foot intervals parallel to the centerline in each direction from the affected location until a core is found, in each direction, that is not deficient by more than 1 inch. The Engineer will evaluate areas found deficient in thickness by more than 1 inch, and if, in the Engineer's judgment, the deficient areas warrant removal, the Contractor shall

501.25

remove and replace them, at no additional cost to the Department, with concrete of the thickness shown on the Plans. The Department will not include exploratory cores for areas deficient by more than 1 inch in thickness when determining averages for adjusted unit prices.

COMPENSATION

501.25 Method of Measurement

The Department will measure Portland Cement Concrete Pavement (Plain) and Portland Cement Concrete Pavement (Reinforced) of the various thicknesses specified, by the square yard in accordance with **109**.

The Department will measure additional concrete required to level individual ramps, including acceleration and deceleration lanes, containing 4,500 square yards or less, by the cubic yard. Where a ramp becomes a traffic lane without a tapered acceleration lane, or a traffic lane becomes a ramp without a tapered deceleration lane, the Department will consider 300 feet of the lane, measured from the point of intersection with the adjoining lanes, as an acceleration or deceleration lane to be included in the ramp. To determine the number of cubic yards of additional concrete, the Department will deduct the theoretical quantity and all wasted concrete from the number of cubic yards used, as determined from invoices or conversion from batch weights.

The Department will not measure for payment additional concrete used for leveling on main line roadway or ramps that contain more than 4,500 square yards.

501.26 Basis of Payment

A. General

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Portland Cement Concrete Pavement (Plain) ___”	Square Yard
Portland Cement Concrete Pavement (Reinforced) ___”	Square Yard
Portland Cement Concrete Shoulders	Square Yard

Such payment is full compensation for furnishing all materials including reinforcing, dowels, and joint material.

Payment for Portland Cement Concrete Pavement, of the type and thickness shown on the Plans, also includes all labor, equipment, materials, and incidentals required to construct the longitudinal joint between the pavement and either flexible or rigid shoulders, and to texture the surface by forming transverse grooves.

Payment for Portland Cement Concrete Shoulders, of the type and thickness shown on the Plans, includes all labor, equipment, materials, and incidentals required to construct transverse joints in the Portland cement concrete shoulders.

For pavement found deficient in thickness by more than $\frac{1}{4}$ inch but not more than 1 inch, the Department will pay only the reduced price specified in **501.26.B**. No additional payment over the contract unit bid price will be made for pavement that has an average thickness in excess of that shown on the Plans.

The Department will pay for additional concrete used for leveling on ramps that contain 4,500 square yards or less based on the invoice price of the concrete when the concrete is purchased from a ready-mix producer. If the concrete is mixed on the Project by the Contractor, the price per cubic yard will be based on the invoice price of the materials plus 20%. The Department will make payment only on that portion of additional concrete that exceeds 4% of the theoretical quantity; no payment will be made for additional concrete exceeding 10% of the theoretical quantity.

The Department will pay for additional concrete, measured in accordance with **501.25**, at the purchase price, F.O.B. the unloading point, as verified by invoices, with no compensation allowed for further handling. The State will be reimbursed from monies due the Contractor for a decrease in concrete measured in accordance with **501.25** in an amount equal to the purchase price of the concrete F.O.B. the unloading point. No payment will be allowed for any changes in the proportions of the aggregates. No additional payment will be made if two-lift composite pavement alternate is selected.

B. Price Adjustments

- 1. Pavement Thickness.** Where the average thickness per unit of pavement is deficient in thickness by more than $\frac{1}{4}$ inch, but not more than 1 inch, the Department will pay an adjusted price as specified in Table 501.26-1.

501.26

Table 501.26-1: Price Adjustment for Concrete Pavement Deficiency

Deficiency in Thickness Determined by Cores (Inches)	Proportion of Contract Price Allowed
0 through 0.25	100%
0.26 through 0.50	75%
0.51 through 0.75	60%
0.76 through 1.00	50%

When the thickness of pavement is deficient by more than 1 inch and the judgment of the Engineer is that the area of such deficiency does not warrant removal and the Contractor elects not to remove the pavement, there will be no payment for the area retained.

- 2. Pavement Rideability.** The Department will adjust the unit price paid for Portland Cement Concrete Pavement in accordance with Figure 501.17-1.

The adjusted unit price will apply to the total area of the 0.1 mile-section for the lane width represented by the road profiler or profilograph.

PART 6 – STRUCTURES

SECTION 601 – TIMBER STRUCTURES	420
SECTION 602 – STEEL STRUCTURES	427
SECTION 603 – PAINTING.....	480
SECTION 604 – CONCRETE STRUCTURES	498
SECTION 606 – PILING.....	558
SECTION 607 – PIPE CULVERTS AND STORM SEWERS	578
SECTION 608 – SANITARY SEWERS.....	587
SECTION 609 – PIPE REMOVED AND RELAID.....	592
SECTION 610 – PIPE DRAINS.....	596
SECTION 611 – MANHOLES, CATCH BASINS, INLETS, AND PIPE END WALLS	600
SECTION 612 – STONE MASONRY	605
SECTION 613 – BRICK MASONRY	613
SECTION 615 – PRECAST/PRESTRESSED CONCRETE BRIDGE MEMBERS.....	618
SECTION 616 – POST-TENSIONED PRESTRESSED CONCRETE....	634
SECTION 617 – BRIDGE DECK SEALANT	646
SECTION 619 – POLYMER MODIFIED CONCRETE BRIDGE DECK OVERLAY FOR NEW AND EXISTING BRIDGES.....	650
SECTION 620 – BRIDGE RAILINGS	659
SECTION 621 – TEMPORARY STRUCTURES.....	661
SECTION 622 – SHOTCRETE.....	664
SECTION 623 – BRIDGE EXPANSION JOINTS	671

601.01

SECTION 601 – TIMBER STRUCTURES

601.01 Description	420
601.02 Materials	420
601.03 Reserved.....	421
601.04 Preliminary Work.....	421
601.05 Care and Protection of Timber	421
601.06 Components of Timber Structures	421
601.07 Erection	424
601.08 Paint and Painting	425
601.09 Final Cleanup	426
601.10 Method of Measurement	426
601.11 Basis of Payment.....	426

DESCRIPTION

601.01 Description

This work consists of constructing structures or parts of structures, other than piling, composed of timber, treated or untreated, or a combination of both, on prepared foundations at the locations shown on the Plans or as directed by the Engineer.

Construct those parts of timber structures to be constructed with materials other than timber, such as concrete and steel, as specified in the Sections pertaining to the respective types of structure.

MATERIALS

601.02 Materials

Provide materials as specified in:

Timber..... **911**

Provide timber of the dimensions shown on the Plans. The dimensions on the Plans are intended to represent the commercial product.

Untreated timber used for mud sills shall be heart cedar, heart cypress, redwood, or other durable timber.

Obtain the Engineer's approval of the design of ring or shear plate timber connectors. Provide connectors of galvanized metal meeting the appropriate ASTM standard.

Provide hardware for timber structures of the design, size, kind, and composition shown on the Plans or as directed by the Engineer.

601.03 Reserved

CONSTRUCTION REQUIREMENTS

601.04 Preliminary Work

Perform Clearing and Grubbing, Removal of Structures and Obstructions, Excavation and Undercutting, Structure Excavation, Foundation Preparation and Backfill, and Embankment Construction as specified in **201**, **202**, **203**, **204**, and **205**, respectively.

601.05 Care and Protection of Timber

Handle all timber with care, and store upon platforms, skids, or other supports at least 12 inches above the ground surface. Stack and strip timber to allow for the free circulation of air between the tiers and courses. Cover the stacked timber. Clear the ground underneath and in the vicinity of the timber of all weeds, rubbish, and other objectionable material, and shape to allow surface water flow to drain away from the stockpiled material.

601.06 Components of Timber Structures

A. Mud Sills

Firmly and evenly bed mud sills to a solid bearing and tamp in place.

B. Concrete Pedestals

Finish concrete pedestals for the support of framed bents so that the sills or posts will receive an even and uniform bearing. Slope the tops of pedestals projecting outside the bearing area downward to direct water away from the bearings. Set dowels, of not less than $\frac{3}{4}$ inches in

601.06

diameter and projecting the proper distance above the tops of the pedestals, 9 inches in the pedestal when they are being cast.

C. Sills

Secure sills with $\frac{3}{4}$ -inch diameter drift bolts extending into the mud sills, piles, or pedestals at least 9 inches. When possible, remove all earth from contact with sills to provide free circulation of air around the sills.

D. Caps

Set caps as shown on the Plans, to have full and even bearing on piles or other supports in the bent, and to provide even bearing and full contact with the stringers placed on the caps. Secure caps to each pile or post by a $\frac{3}{4}$ -inch drift bolt placed approximately at the center of the pile or post and extending through the cap and at least 9 inches into the pile or post. Secure caps to other supports as shown on the Plans.

E. Posts for Bents

Fasten posts to sills and pedestals with dowels of not less than $\frac{3}{4}$ inches in diameter extending into posts and sills as shown on the Plans.

F. Framing

Cut and frame truss and bent timbers to a close fit in such manner that they will have an even bearing over the entire contact surface of the joint. Do not perform any blocking or shimming when making joints. The Engineer will reject open joints.

Ensure that mortises are true to size for their full depth, and tenons make a snug fit therein. Mortises and tenons shall be draw-bored.

G. Stringers

Set and place all stringers to the required elevations to give flooring an even bearing at all contacts or intersections.

Size stringers at bearings and place in position so that knots near edges will be in the top portion of the stringer.

Unless otherwise specified, outside stringers shall have butt joints, but frame interior stringers to bear over the full width of floor beam or cap at each end of the stringer.

Separate the ends of untreated stringers at least $\frac{1}{2}$ inch to allow for air circulation, and securely fasten the ends to the timber upon which they rest.

Ensure that cross-bridging between stringers is neatly and accurately framed and securely toe-nailed with at least two nails in each end.

H. Flooring

Construct all flooring as shown on the Plans or as directed by the Engineer. Ensure that flooring has even, full, and uniform free bearing on each and all stringers, and is not pulled or warped to have such bearing. Only use shims and wedges with the Engineer's approval. When constructing timber flooring, take care to place flooring pieces of the same thickness adjacent to each other.

I. Wheel Guards

Construct wheel guards on each side of the roadway as shown on the Plans. Place the wheel guards in sections not less than 12 feet in length, unless otherwise shown on the Plans or directed by the Engineer.

Unless otherwise indicated, fasten wheel guards with $\frac{5}{8}$ -inch bolts not to exceed 5-foot 3-inch centers. Fasten the ends of all wheel guards sections. The bolts shall extend entirely through the riser blocks and floor plank.

J. Railing

Unless otherwise indicated or directed, provide railings of untreated, dressed lumber, constructed in a workmanlike and substantial manner. Construct the railings as shown on the Plans and to be reasonably true to line and grade. Paint the railings.

K. Bore Holes

Bore holes as follows:

601.07

1. **Round Bolts, Spikes, and Dowels.** Use a bit 1/16 inch less in diameter than the bolt, spike, or dowel to be used. The diameter of the holes for square bolts, spikes, or dowels shall be equal to the least dimension of the bolt or dowel.
2. **Machine Bolts.** Use a bit of the same diameter as the bolt.
3. **Rods.** Use a bit 1/16 inch greater in diameter than the rod.
4. **Screws.** Use a bit slightly smaller than the body of the screw at the base of the thread, but not to the full depth of the screw.

Re-treat all bolt holes bored after treatment with an approved treatment. Plug unfilled holes, after being treated, with treated plugs.

L. Bolts, Nuts, and Washers

Provide bolts, nuts, and washers of the kinds and sizes specified. Bolts shall have square heads and nuts. All bolts shall be galvanized. Vertical bolts shall have the nuts on the lower end.

Use a washer under the head or nut of all bolts or lag screws coming in contact with timber. Washers shall be of the same character as the bolt or screw with which they are used.

M. Countersinking

Countersink nuts and bolt heads as directed by the Engineer. Fill the recesses formed by countersinking with hot tar pitch.

N. Spiking

When using spikes to spike one member to another, with spikes 7 inches or longer as shown on the Plans, or when necessary in erection, drill holes through the member 1/16 inch less than the diameter of the spike that is to be driven. Drive spikes to the depth required to embed the full thickness of the head into the timber.

601.07 Erection

In erecting timber structures, or parts of structures, allow for the typical variations in Plans dimensions from commercial dimensions of timber to

obtain the required finished elevations and finished dimensions of the structure, without the use of shims or blocks.

Position and fasten timbers as shown on the Plans or as directed by the Engineer.

Perform all construction in a workmanlike manner and ensure that the structure presents a neat finish and appearance when completed.

Place planks with the heart side down, with ¼-inch openings between planks, unless otherwise shown on the Plans or directed by the Engineer. Fasten planks at each intersection to a nail strip or joist with two wire spikes of the size indicated or directed.

In structures constructed in whole or in part of treated timber, thoroughly coat with an approved treatment all areas, where the timber surface is broken after treatment. Completely fill holes in treated timber caused by withdrawing bolts, nails, spikes, or other causes with an approved treatment.

In structures constructed in whole or in part of untreated timber, thoroughly treat, as specified above, heads of piles not encased in concrete, ends, tops, and all contact surfaces of truss members, laterals, and braces, before assembling.

Thoroughly coat, as specified above, the back face of bulkheads and all other parts of timber in contact with earth.

For timber surfaces that are to be painted in the completed structure, paint those portions coming in contact with other timber or material before being fastened or placed, as specified for railings in **601.08**.

Remove and replace, at no cost to the Department, all damaged or unsatisfactory timber.

601.08 Paint and Painting

Paint railings, except those or parts of those constructed of treated timber, with three coats of paint applied as specified in **603**. Comply with the type, sequence, and colors shown on the Plans.

Paint all metals, unless otherwise shown or directed, as specified in **603**.

601.09

601.09 Final Cleanup

When finishing a structure, clean exposed timber of any discoloration caused by the construction operations.

Store all material becoming the property of the Department as directed by the Engineer.

Perform final cleanup as specified in **104.10**.

COMPENSATION

601.10 Method of Measurement

The Department will measure Untreated Timber and Treated Timber, complete in place and accepted, by the 1,000-board foot measure (MBFM) in accordance with **109**.

The Department will consider hardware used in a structure to be incidental to the Untreated Timber and Treated Timber bid items.

601.11 Basis of Payment

The Department will pay for accepted quantities of timber structures at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Treated Timber	MBFM
Untreated Timber	MBFM

SECTION 602 – STEEL STRUCTURES

602.01 Description.....	428
602.02 Materials	428
602.03 Reserved.....	429
602.04 Shop Inspection.....	429
602.05 General.....	430
602.06 Bolt Holes	435
602.07 Punched Holes	436
602.08 Reamed or Drilled Holes.....	436
602.09 Preparation of Field Connections.....	436
602.10 Accuracy of Punched and Drilled Holes	437
602.11 Accuracy of Reamed and Drilled Holes.....	437
602.12 Fitting for Bolting	438
602.13 Shop Assembling	438
602.14 Drifting of Holes	440
602.15 Match-Marking	440
602.16 Bolts and Bolted Connections.....	441
602.17 Connections Using High Strength Bolts	442
602.18 Plate Cut Edges	460
602.19 Welds	460
602.20 Facing of Bearing Surfaces	462
602.21 Abutting Joints	462
602.22 End Connection Angles	462
602.23 Lacing Bars	462
602.24 Fabrication of Members.....	463
602.25 Web Plates	463
602.26 Bent Plates	463
602.27 Fit of Stiffeners	464
602.28 Eyebars.....	464
602.29 Annealing and Stress Relieving	465
602.30 Pins and Rollers	465
602.31 Boring Pin Holes.....	466
602.32 Pin Clearances.....	466

602.01

602.33	Threads for Bolts and Pins	466
602.34	Pilot and Driving Nuts	466
602.35	Identification of Steels During Fabrication	466
602.36	Weighing of Members.....	467
602.37	Full Size Tests.....	467
602.38	Marking and Shipping.....	468
602.39	Erection	470
602.40	Handling and Storing Materials	470
602.41	Temporary Supports.....	471
602.42	Method and Equipment	471
602.43	Straightening Bent Material and Cambering	471
602.44	Misfits	472
602.45	Assembling.....	472
602.46	Pin Connections	473
602.47	Setting Shoes and Bearings	473
602.48	Painting	474
602.49	Method of Measurement	474
602.50	Basis of Payment.....	477

DESCRIPTION

602.01 Description

This work consists of furnishing the various materials for the fabrication, erection, and painting of bridges and such other parts of bridges that are composed of structural steel and miscellaneous metals, except steel piling or metal reinforcement for concrete.

MATERIALS

602.02 Materials

Provide materials as specified in:

Structural Steel and Appurtenant Materials	908
Paint	910

For materials not covered by these Specifications, comply with the AASHTO Bridge Specifications identified on the Plans. Refer to the Plans for testing requirements and dimensions of materials.

602.03 Reserved

CONSTRUCTION REQUIREMENTS – FABRICATION

602.04 Shop Inspection

A. AISC Certification for Steel Fabricators

Fabricators of steel bridges shall hold the following certifications in accordance with the AISC Certification Program for Structural Steel Fabricators – Standard for Steel Bridges:

1. As a minimum, all fabricators shall be certified in the category of intermediate bridges with applicable supplemental requirements.
2. Fabricators of advanced type bridges, as defined in the AISC Standard for Steel Bridges, shall be certified in the category of advanced bridges with applicable supplemental requirements.
3. Fabricators of diaphragms, cross-frames, floor beams, stringers (rolled beams) and laterals shall be certified in the category of Intermediate bridges, as a minimum.
4. Fabricators of bridge bearings, expansion joints, sign structures and other metal highway components as listed in the AISC standard shall hold certification under the AISC Certification Program – Standard for Bridge and Highway Metal Component Manufacturers. As an alternative, fabricators of bridge bearing or expansion joints may hold certification in the category of Intermediate bridges under the Standard for Steel Bridges.

B. Quality Assurance (QA) Shop Inspection

At least 6 weeks before starting shop fabrication, provide written notification to the Division of Structures, with a copy to the Engineer, as to the location and schedule of the fabrication of structural steel, so that the Department may arrange for QA shop inspection.

602.05

The Department will pay for the cost of this QA inspection, limited to the rates set forth in the Special Provisions for each weight range.

To establish the maximum inspection cost to be paid by the Department, the Department will multiply the per pound inspection cost for each specified weight range by the applicable steel poundage within its weight range. The Department will deduct the cost of all structural steel inspection (QA) in excess of this maximum cost from monies due the Contractor. The cost for structural steel inspection (QA) includes the cost of an inspection agency hired by the Department to perform shop inspection (QA) of steel fabrication. The Contractor may obtain a detailed description of the duties of an inspection agency from the Engineer.

The shop inspection performed by the inspection agency hired by the Department is intended as QA to assure to the Department that the fabricator is following all quality control requirements and is providing a product conforming to the Contract requirements. The inspection agency is not instructed or expected to replace the fabricator's quality control. The inspection and acceptance of the work performed by the Department's inspection agency does not relieve the fabricator of providing materials and finished products as specified. The Department may reject defective or non-conforming materials at any time. Replace rejected materials promptly at no additional cost to the Department.

Include the cost of nondestructive testing in the lump sum bid price for steel structures.

602.05 General

A. Type of Construction

The type of construction shall be welded or bolted, as shown on the Plans.

B. Workmanship and Finish

Workmanship and finish shall be in accordance with the American Institute of Steel Construction (AISC) best general practices in modern bridge shops. Provide a neat finish to portions of the work exposed to view.

C. Storage of Materials

Store material, either plain or fabricated, above the ground on platforms, skids, or other supports. Keep materials free from dirt, grease, or other foreign matter, and provide appropriate protection from corrosion.

D. Straightening Material

Ensure that rolled material, before being laid off or worked, is straight. If straightening is necessary, use methods that will not damage the metal.

Only perform heat straightening of ASTM A709, Grade 100W, 244 (ASTM A514) or ASTM A517 steel under rigidly controlled procedures, with each application subject to the Engineer's approval. Do not allow the maximum temperature of the steel to exceed 1100 °F as set forth in the *AASHTO Guide Specifications for Highway Bridge Fabrication with High Performance Steel*, current edition, and the *AASHTO Bridge Welding Code*, current edition. The Engineer will reject material with sharp kinks and bends.

To straighten plates, angles, other shapes, and built-up members when permitted by the Engineer, use methods that will not fracture or otherwise damage the metal.

Straighten distorted members by mechanical means or, if approved by the Engineer, by carefully planned procedures and supervised application of a limited amount of localized heat. However, to heat straighten AASHTO M 270 (ASTM A709) Grades HPS70W and 100W steel members, adhere to the *AASHTO Guide Specification for Highway Bridge Fabrication with High Performance Steel*, current edition, and the *AASHTO Bridge Welding Code*, current edition, with each application subject to the Engineer's approval. Do not exceed the maximum temperatures specified in Table 602.05-1.

602.05

Table 602.05-1: Heat Straightening

Grade	Maximum Temperature, degrees F
Grade HPS70W > 6 inches from weld	1100 °F
Grade HPS70W < 6 inches from weld	900 °F
Grade 100W > 6 inches from weld	1100 °F
Grade 100W < 6 inches from weld	950 °F

In all other steels, do not allow the temperature of the heated area to exceed 1200 °F, as controlled by temperature indicating crayons, liquids, or either contact or non-contact infrared thermometers. Heating in excess of the limits shown will be cause for rejection, unless the Engineer allows testing to verify material integrity.

Keep parts to be heat straightened substantially free of stress and from external forces, except stresses resulting from mechanical means used in conjunction with the application of heat.

The Engineer will reject pieces showing evidence of fracture following straightening of a bend or buckle.

E. Heat Curving Rolled Beams and Welded Girders

- 1. Materials.** Do not perform heat-curving in steels that are manufactured to a specified minimum yield point greater than 70,000 pounds per square inch.
- 2. Type of Heating.** Curve beams and girders by either continuous or V-type heating as approved by the Engineer.

- a. **Continuous Method.** For the continuous method, heat a strip along the edge of the top and bottom flanges simultaneously. Ensure that the strip is of sufficient width and temperature to obtain the required curvature.
- b. **V-type Heating.** For V-type heating, heat the top and bottom flanges at approximately the same rate and in regularly spaced truncated triangular or wedge-shaped areas having their base along the flange edge. Determine the spacing and temperature of areas necessary to obtain the required curvature. On the inside flange surface, terminate the apex of the truncated triangular area just before the juncture of the web and the flange. To avoid web distortion, take special care when heating the inside flange surfaces (the surfaces that intersect the web) so that heat is not applied directly to the web. When the radius of curvature is 1,000 feet or more, extend the apex of the truncated triangular heating pattern applied to the outside flange surface to the juncture of the flange and web. When the radius of curvature is less than 1,000 feet, extend the apex of the truncated triangular heating pattern applied to the outside flange surface past the web for a distance equal to 1/8 of the flange or 3 inches, whichever is less. The truncated triangular pattern shall have an included angle of approximately 15 to 30 degrees and a base of no greater than 10 inches. The Engineer may approve variations in these patterns.

For both types of heating, the flange edges to be heated are those that will be on the inside of the horizontal curve after cooling. Heating both inside and outside flange surfaces is only required when the flange thickness is 1-1/4 inches or greater, in which case, heat the two surfaces concurrently.

3. **Temperature.** Conduct the heat-curving operation so that the temperature of the steel does not exceed 1200 °F for Grades 36, 50, 50W, and HPS50W; and 1100 °F for Grades HPS70W and 100W, as measured by temperature-indicating crayons or other suitable means. Do not artificially cool the girder until after it has naturally cooled to 600 °F; the method of artificial cooling is subject to the Engineer's approval.
4. **Position for Heating.** The girder may be heat-curved with the web in either a vertical or a horizontal position.

602.05

When curving girders with the web in the vertical position, brace or support the girder to prevent it from overturning.

When curving with the web in the horizontal position, support the girder near its ends and at intermediate points, if required, to obtain uniform curvature. Do not allow the bending stress in the flanges due to the dead weight of the girder and externally applied loads to exceed the usual allowable design stress. During heating, maintain intermediate safety catch blocks at the mid-length of the girder within 2 inches of the flanges to avoid a sudden sag due to plastic flange buckling.

5. **Sequence of Operations.** Heat-curve the girder before painting, and either before or after completing all the required welding of transverse intermediate stiffeners. However, unless provisions are made for girder shrinkage, locate and attach connection plates and bearing stiffeners after heat curving. If longitudinal stiffeners are required, heat-curve or oxygen-cut them separately, and then weld them to the curved girder. When attaching cover plates to rolled beams, attach them before heat curving if the total thickness of one flange and cover plate is less than 2-1/2 inches and the radius of curvature is greater than 1,000 feet. For other rolled beams with cover plates, heat-curve the beams before attaching the cover plates. Either heat-curve or oxygen-cut cover plates separately, and then weld them to the curved beam.
6. **Camber.** Camber girders before heat curving. Camber rolled beams by heat-cambering methods approved by the Engineer. For plate girders, cut the web to the prescribed camber with suitable allowance for shrinkage due to cutting, welding, and heat curving. If necessary, correct moderate deviations from specified camber by a carefully supervised application of heat, as approved by the Engineer.
7. **Measurement of Curvature and Camber.** The Engineer will measure horizontal curvature and vertical camber for final acceptance after all welding and heating operations are completed and the flanges have cooled to a uniform temperature. The Engineer will check horizontal curvature with the girder in the vertical position.

- 8. Finish.** Provide a neat finish to exposed portions of the work. Perform shearing, flame cutting, and chipping carefully and accurately.

602.06 Bolt Holes

A. Holes for High Strength Bolts and Unfinished Bolts¹

Punch or drill all bolt holes. Material forming parts of a member composed of not more than five thicknesses of metal may be punched 1/16 inch larger than the nominal diameter of the bolts where the thickness of the material is not greater than 3/4 inch for structural steel, 5/8 inch for high-strength steel, or 1/2 inch for quenched and tempered alloy steel, unless sub-punching and reaming is required under **602.09**.

Where there are more than five thicknesses, or when any of the main material is thicker than 3/4 inch for structural steel, 5/8 inch for high-strength steel, or 1/2 inch for quenched and tempered alloy steel, either sub-drill and ream or drill holes full size.

If required under **602.09**, either sub-punch or sub-drill (sub-drill if thickness limitation governs) all holes 3/16 inch smaller, and, after assembling, ream 1/16 inch larger, or drill full size to 1/16 inch larger than the nominal diameter of the bolts.

The Department will only allow use of enlarged or slotted holes with high-strength bolts 5/8 inch or larger in diameter where shown on the design drawings.

B. Holes for Ribbed Bolts, Turned Bolts or other Approved Bearing Type Bolts

The Fabricator may either sub-punch or sub-drill all holes for ribbed bolts, turned bolts, or other approved bearing-type bolts 3/16 inches smaller than the nominal diameter of the bolt, and then ream, assemble or drill to a steel template or, after assembly, drill from the solid. In any case, ensure that the finished holes provide a driving fit as shown on the Plans or specified in the Special Provisions.

¹ See **602.16** for bolts included in designation "Unfinished Bolts."

602.07

602.07 Punched Holes

Use a die diameter that is not more than 1/16 inch larger than the punch diameter. Ream holes that must be enlarged to admit bolts. Ensure that holes are cleanly cut without torn or ragged edges. Poor matching of holes will be cause for rejection.

602.08 Reamed or Drilled Holes

Ream or drill holes so they are cylindrical and perpendicular to the member and sized to comply with **602.06**. Where practicable, direct reamers using mechanical means. Remove burrs on the outside surfaces. Poor matching of holes will be cause for rejection. Ream and drill holes with twist drills. If required by the Engineer, take apart assembled pieces to remove burrs caused by drilling. Assemble and securely hold together connecting parts that are being reamed or drilled and match-mark before disassembling.

602.09 Preparation of Field Connections

A. Sub-punching and Reaming of Field Connections

Unless otherwise specified in the Special Provisions or shown on the Plans, sub-punch (or sub-drill if sub-drilling is required) the holes in all field connections and field splices of main members of trusses, arches, continuous beam spans, bents, towers (each face), plate girders, and rigid frames, as specified in **602.06**, and subsequently ream while assembled or to a steel template, as specified in **602.13**. Sub-punch all holes for floor beam and stringer field connections, and ream to a steel template or while assembled.

When reaming or drilling full size field connection holes through a steel template, accurately locate and position the template and firmly bolt in place before drilling. Ensure that templates used for reaming matching members, or the opposite faces of a single member, are exact duplicates. Accurately locate templates used for connections on like parts or members so that the parts or members are duplicates and require no match-marking.

For any connection, instead of sub-punching and reaming or sub-drilling and reaming, the Fabricator may drill holes full size with all thicknesses of material assembled in proper position.

The Special Provisions or the Plans will identify if any additional sub-punching and reaming is required.

B. Numerically Controlled (N/C) Drilled Field Connections

1. **General.** For any connection or splice specified in **602.09.A**, instead of drilling undersized holes and reaming while assembled, or drilling holes full size while assembled, the Contractor may use N/C drilling equipment to drill bolt holes full-size in unassembled pieces and/or connections including templates for use with matching undersized and reamed holes.

If N/C drilling equipment is used, the Engineer, unless otherwise stated in the Special Provisions or shown on the Plans, may require the Contractor, by means of check assemblies, to demonstrate that this drilling procedure consistently produces holes and connections meeting **602.11** and **602.13**. Submit to the Engineer for approval a detailed outline of the proposed procedures for accomplishing the work, from initial drilling through check assembly, if required. Identify in the submittal the specific members of the structure that may be N/C drilled, the sizes of the holes, the location of common index and other reference points, composition of check assemblies, and all other pertinent information.

2. **Holes.** Ensure that holes drilled by N/C drilling equipment are drilled to appropriate size either through individual pieces or any combination of pieces held tightly together.

602.10 Accuracy of Punched and Drilled Holes

Punch holes so that, after assembling (before any reaming is done), a cylindrical pin 1/8 inch smaller in diameter than the nominal size of the punched hole may be entered perpendicular to the face of the member, without drifting, in at least 75% of the contiguous holes in the same plane. The Engineer will reject pieces that do not meet this requirement. The Engineer will also reject all holes that will not pass a pin 3/16 inch smaller in diameter than the nominal size of the punched holes.

602.11 Accuracy of Reamed and Drilled Holes

When holes are reamed or drilled, 85% of the holes in any contiguous group shall, after reaming or drilling, show no offset greater than 1/32 inch between adjacent thicknesses of metal. Use steel templates having hardened steel

602.12

bushings in holes accurately dimensioned from the center lines of the connection as inscribed on the template. Use the center lines when locating the templates from the milled or scribed ends of members.

602.12 Fitting for Bolting

Clean surfaces of metal in contact before assembling. Before reaming, ensure that the parts of a member are assembled, well pinned, and firmly drawn together with bolts. When necessary, take assembled pieces apart to remove burrs and shavings produced by the reaming operation. Ensure that members are free from twists, bends, and other deformation.

602.13 Shop Assembling

Assemble the field connections of main members of trusses, arches, continuous beam spans, bents, towers (each face), plate girders, and rigid frames in the shop with milled ends of compression members in full bearing, and then ream their sub-size holes to the specified size while the connections are assembled. Assembly may be full truss or girder assembly, progressive truss or girder assembly, full chord assembly, progressive chord assembly, or special complete structure assembly unless otherwise specified in the Special Provisions or shown on the Plans.

Fabricate check assemblies with numerically controlled (N/C) drilled field connections as specified in **602.13.F**.

Obtain the Engineer's approval of each assembly, including camber, alignment, accuracy of holes, and fit of milled joints, before starting reaming or before dismantling an N/C drilled check assembly.

The Fabricator shall submit to the Engineer a camber diagram showing the camber at each panel point for trusses or arch ribs and at the location of field splices and fractions of span length (1/4 points minimum, 1/20 points maximum) for continuous beam and girders or rigid frames. When the shop assembly is Full Truss or Girder Assembly or Special Complete Structure Assembly, the camber diagram shall show the camber measured in assembly. For the other shop assembly methods, the camber diagram shall show calculated camber.

A. Full Truss or Girder Assembly

Full Truss or Girder Assembly shall consist of assembling all members of each truss, arch rib, bent, tower face, continuous beam line, plate girder, or rigid frame at one time.

B. Progressive Truss or Girder Assembly

Progressive Truss or Girder Assembly shall consist of assembling initially for each truss, arch rib, bent, tower face, continuous beam line, plate girder, or rigid frame at least three contiguous shop sections or all members in at least three contiguous panels but not less than the number of panels associated with three contiguous chord lengths (i.e., length between field splices) and not less than 150 feet in the case of structures longer than 150 feet. Add at least one shop section or panel or as many panels as are associated with a chord length at the advancing end of the assembly before removing any member from the rearward end, so that the assembled portion of the structure is never less than that specified above.

C. Full Chord Assembly

Full Chord Assembly shall consist of assembling, with geometric angles at the joints, the full length of each chord of each truss or open spandrel arch, or each leg of each bent or tower, then reaming their field connection holes while the members are assembled and reaming the web member connections to steel templates set at geometric (not cambered) angular relation to the chord lines.

Ream field connection holes in web members to steel templates. Ensure that at least one end of each web member is milled or scribed normal to the longitudinal axis of the member. Accurately locate the templates at both ends of the member from one of the milled ends or scribed lines.

D. Progressive Chord Assembly

Progressive Chord Assembly shall consist of assembling contiguous chord members in the manner specified for Full Chord Assembly in **602.13.C** and in the number and length specified for Progressive Truss or Girder Assembly in **602.13.B**.

602.14

E. Special Complete Structure Assembly

Special Complete Structure Assembly shall consist of assembling the entire structure, including the floor system. (This procedure is ordinarily needed only for complicated structures such as those having curved girders or extreme skew in combination with severe grade or camber.)

F. Check Assemblies with Numerically Controlled (N/C) Drilled Field Connections

Fabricate a check assembly for each major structural type of each project, unless otherwise shown on the Plans or specified in the Special Provisions. The check assembly shall consist of at least three contiguous shop sections or, for a truss, all members in at least three contiguous panels but not less than the number of panels associated with three contiguous chord lengths (i.e., length between field splices). Base check assemblies on the proposed order of erection, joints in bearings, special complex points (such as portals of skewed trusses), and similar considerations.

Use geometric angles (giving theoretically zero secondary stresses under dead load conditions after erection) or cambered angles (giving theoretically zero secondary stresses under no load conditions) as shown on the Plans or specified in the Special Provisions.

For each major structural type to be fabricated, fabricate the check assemblies first. The Department does not require any matchmaking or shop assemblies other than the check assemblies.

If the check assembly fails to demonstrate that the required accuracy is being obtained, the Engineer may require the fabrication of additional check assemblies at no cost to the Department.

602.14 Drifting of Holes

Only drift holes during assembling to the extent that it brings the parts into position but does not enlarge the holes or distort the metal.

602.15 Match-Marking

Match-mark connecting parts preassembled in the shop to ensure proper fit in the field. Provide a diagram showing such match-marks to the Engineer.

602.16 Bolts and Bolted Connections

The requirements of this Subsection do not pertain to the use of high strength bolts. For bolted connections fabricated with high strength bolts, comply with **602.17**.

A. General

Use unfinished, turned, or ribbed bolts conforming to ASTM A307 for Grade A bolts for Low-Carbon Steel Externally and Internally Threaded Standard Fasteners. Only use bolted connections as shown on the Plans or specified in the Special Provisions. Use bolts with single self-locking nuts or double nuts unless otherwise shown on the Plans or specified in the Special Provisions. Use beveled washers where bearing faces have a slope of more than 1:20 with respect to a plane normal to the bolt axis.

B. Unfinished Bolts

Furnish unfinished bolts unless other types are specified.

C. Turned Bolts

Furnish turned bolts having a body surface that meets the ANSI roughness rating value of 125. Furnish hex headed bolts and nuts of the nominal size specified or the next larger nominal size. The thread diameter shall be equal to the body of the bolt or the nominal diameter of the bolt specified. Carefully ream holes for turned bolts with bolts furnished to provide for a light driving fit. Keep bolt threads entirely outside of the holes. Provide a washer under the nut.

D. Ribbed Bolts

The body of ribbed bolts shall be of an approved form with continuous longitudinal ribs. The diameter of the body measured on a circle through the points of the ribs shall be 5/64 inch greater than the nominal diameter specified for the bolts.

Furnish ribbed bolts with round heads conforming to ANSI B 18.5 unless otherwise specified. Furnish hexagonal nuts that are either recessed or have a washer of suitable thickness. Ribbed bolts shall have a driving fit when installed in the holes. The hardness of the ribs shall be such that the ribs do not compress, deform, or allow the bolts to turn in the holes

602.17

during tightening. If the bolt twists before drawing tight, ream the hole and provide an oversized replacement bolt.

602.17 Connections Using High Strength Bolts

A. General

All high strength bolts, or equivalent fasteners, tightened to a high tension shall be coated with permitted coatings in accordance with ASTM F3125 for their respective grade. Use the bolts in holes conforming to **602.06**, **602.07**, and **602.08**. All Grade A325 and A490 bolts, except Type 3 bolts used in weathering steel, shall be coated. Permitted coatings for Grade A325 and Grade A490 bolts are listed in ASTM F3125, Annex A1.

B. Bolts, Nuts, and Washers

The Department will pre-test bolts, nuts, and washers in accordance with **908.04**. Bolts used with weathering steel shall be ASTM F3125 Grade A325 Type 3, and all bolts, nuts and washers shall have the same weathering characteristics as the structural steel. Galvanized nuts shall be grade DH. Supply the Materials and Tests Division with samples of bolts, nuts, and washers used on the Project for purposes of testing (provide three per shipping lot).

Where the outer face of the bolted parts has a slope greater than 1:20 with respect to a plane normal to the bolt axis, use a hardened beveled washer to compensate for the lack of parallelism.

Use hardened beveled washers for American Standard Beams and Channels. The washers shall be square or rectangular, shall conform to the requirements of AASHTO M 293 (ASTM F436) and ASTM F3125 Grade A490, and shall taper in thickness.

Where necessary, washers may be clipped on one side from the center of the washer to a point not closer than 7/8 times the bolt diameter.

Hardened washers are not required for connections using ASTM F3125 Grade A325 and A490 bolts except as follows:

1. Use hardened washers under the turned element when tensioning is to be performed by the calibrated wrench method.

2. Regardless of the tensioning method, use hardened washers under both the head and the nut when ASTM F3125 Grade A490 bolts are to be installed in material having a specified yield point less than 40 kips per square inch. However, use of DTT's may replace a hardened washer provided a standard hole is used.
3. Where ASTM F3125 Grade A325 bolts of any diameter or ASTM F3215 Grade A490 bolts equal to or less than 1 inch in diameter are to be installed in oversize or short-slotted holes in an outer ply, use a hardened washer conforming to AASHTO M 293 (ASTM F436).
4. Where ASTM F3125 Grade A490 bolts over 1 inch in diameter are to be installed in an oversized or short-slotted hole in an outer ply, use a hardened washer conforming to AASHTO M 293 (ASTM F436).
5. Where ASTM F3125 Grade A490 bolts over 1 inch in diameter are to be installed in an oversized or short-slotted hole in an outer ply, use hardened washers conforming to AASHTO M 293 (ASTM F436) except with 5/16 inch minimum thickness under both the head and the nut instead of standard thickness hardened washers. Using multiple hardened washers with a combined thickness equal to or greater than 5/16 inch does not satisfy this requirement.
6. Where ASTM F3125, Grade A325 bolts of any diameter or ASTM F3125 Grade A490 bolts equal to or less than 1 inch in diameter are to be installed in a long slotted hole in an outer ply, use a plate washer or continuous bar of at least 5/16 inch thickness with standard holes. The washers or bars shall have a size sufficient to completely cover the slot after installation and shall be of structural grade material but need not be hardened except as follows. When ASTM F3125 Grade A490 bolts over 1 inch in diameter are to be used in long slotted holes in external plies, use a single hardened washer conforming to AASHTO M 293 (ASTM F436), but with 5/16 inch minimum thickness, instead of washers or bars of structural grade material. Using multiple hardened washers with combined thickness equal to or greater than 5/16 inch does not satisfy this requirement.

602.17

7. Alternate design fasteners conforming to Article 11.3.2.6, with a geometry that provides a bearing circle on the head or nut with a diameter equal to or greater than the diameter of hardened washers conforming to AASHTO M 293 (ASTM F436), satisfy the requirements for washers specified herein and may be used without washers.

C. Bolted Parts

Limit the maximum slope of surfaces of bolted parts in contact with the bolt head and nut to 1:20 with respect to a plane normal to the bolt axis. Ensure that bolted parts fit solidly together when assembled and are not separated by gaskets or any other interposed compressible material.

Ensure that, when assembled, all joint surfaces, including those adjacent to the bolt head, nuts, or washers, are free of loose scale, burrs, dirt, and other foreign material that would prevent solid seating of the parts. Paint is permitted unconditionally in bearing type connections.

Unless otherwise shown on the Plans, all contact surfaces of bolted parts shall be Class B as described in the AASHTO Bridge Specifications identified in the Plans.

D. Installation

Comply with the following when installing high strength bolts in the field or shop:

1. Install bolts to the minimum tensions specified in Table 602.17-1 and in accordance with the AASHTO LRFD Bridge Construction Specifications identified on the Plans. During installation, take particular care to achieve the snug tight condition as defined in Article 11.5.6.4.

Table 602.17-1: Minimum Bolt Tension ⁽¹⁾

Bolt Diameter (inches)	Bolt Tension (pounds)	
	(Grade A325)	Grade A490 Bolts
½	12,000	15,000
5/8	19,000	24,000
¾	28,000	35,000
7/8	39,000	49,000
1	51,000	64,000
1-1/8	64,000	80,000
1-1/4	81,000	102,000
1-3/8	97,000	121,000
1-1/2	118,000	148,000

⁽¹⁾ Equal to 70% of the specified minimum tensile strength of bolts.

2. Perform the rotational capacity test described in **602.17.E.1** and **602.17.E.2** on each rotational capacity lot before starting bolt installation. Provide hardened steel washers as part of the test.
3. Install bolt, nut, and washer combinations of the same rotational capacity lot together.
4. Un-galvanized bolts shall be “oily” to the touch when delivered and installed.
5. Clean and re-lubricate weathered or rusted bolts or nuts not satisfying the requirements of paragraph **D.2** above prior to installation. Test re-cleaned or re-lubricated bolt, nut, and washer assemblies in accordance with paragraph **D.2** above prior to installation.
6. Direct Tension Indicators (DTIs)
 - a. Use Direct Tension Indicators (DTIs) for each bolt. Do not use DTIs on weathering steel, and therefore all bolts shall be installed by either turn-of-nut tightening or calibrated wrench tightening in accordance with the construction specifications of the AASHTO Bridge Specifications

602.17

identified on the Plans. The load indicator average gap shall be 0.005 inch. After the joint has been properly pinned, tighten the joint to approximately half the specified tension to ensure firm contact of all plies, and then tighten the joint by systematically progressing from the center most rigid part to the free edges. Re-tightening may be necessary to restore tension if gaps increase from original measurements.

- b. Maintain a tension calibrator, such as a Skidmore Wilhelm, on the Project during all bolting operations. The Engineer will check the bolt tension versus the average gap of the DTI daily to ensure correct tension.
- c. Supply the Materials and Tests Division with samples of bolts, nuts, and washers used on the project for purposes of testing (provide three per shipping lot).
- d. Ship bolts, nuts, and washers in sealed containers, labeled with the supplier's name and lot identification. Ensure that the containers can protect the bolts from moisture and other contaminants until they are opened at the site. Damaged containers are cause for rejection.
- e. Verify the DTI's performance as specified in **602.17.E.3**.
- f. Install DTIs by one of the following three methods unless otherwise approved by the Engineer.
 - (1) Place the DTI under the bolt head and turn the nut to tighten. The protrusions on the DTI shall face the underside of the bolt head. Place the hardened flat washer under the nut and reduce the gap in the DTI to 0.005 inch.
 - (2) Place the DTI under the nut and turn the nut to tighten. Place the hardened flat washer between the nut and the DTI. The protrusions on the DTI shall face the underside of the hardened flat washer and nut and the gap in the DTI reduced to 0.005 inch. This method is suggested when it is too difficult to see the bolt head for inspection, or when the wrench operator wants to see the gap.

- (3) Place the DTI under the bolt head and turn the bolt head to tighten. Place the hardened flat washer between the bolt head and the DTI. The protrusions on the DTI shall face the underside of the hardened flat washer and bolt head and the gap in the DTI reduced to 0.005 inch. This method is suggested when it is too difficult to see the nut for inspection, or when the wrench operator wants to see the gap.

E. Inspection

In the presence of the Engineer, conduct the following tests to certify materials in accordance with **908.04** and prior to installation:

1. Rotational Capacity Tests on Long Bolts in Tension Calibrator

a. Equipment Required

1. Calibrated bolt tension measuring device of size required for bolts to be tested. Mark off a vertical line and lines 1/3 of a turn (120 degrees); and 2/3 of a turn (240 degrees), from vertical in a clockwise direction on the face plate of the calibrator.
2. Calibrated torque wrench.
3. Spacers and/or washers with hole size no larger than 1/16 inch greater than bolt to be tested.
4. Steel section to mount bolt calibrator. Flange of girder or cross frame accessible from the ground is satisfactory.

b. Procedure

1. Install nut on bolt and measure stick-out of bolt when three to five full threads of the bolt are located between the bearing face of the nut and the bolt head. Measure the bolt length, the distance from the end of the threaded shank to the underside of the bolt head.

602.17

2. Install the bolt into the tension calibrator and install the required number of shim plates and/or washer (one washer under the nut must always be used) to produce the thread stick-out measured in Step 1.
3. Tighten bolt using a hand wrench to the snug tensions specified in Table 602.17-2, -0 kips, +2 kips.

Table 602.17-2: Snug Tension

Bolt Diameter (inches)	Grade A325 Snug Tension (kips)	Grade A490 Snug Tension (kips)
½	1	1
5/8	2	2
¾	3	4
7/8	4	5
1	5	6
1-1/8	6	8
1-1/4	8	10
1-3/8	10	12
1-1/2	12	15

4. Match mark the nut to the vertical stripe on the face plate of the bolt calibrator.
5. Using the calibrated manual torque wrench, tighten the bolt to at least the tension specified in Table 602.17-3, and record the torque required to reach the tension and the value of the bolt tension. Measure torque with the nut in motion.

Table 602.17-3: Minimum Installation Tension

Bolt Diameter (inches)	Grade A325 Tension (kips)	Grade A490 Tension (kips)
½	12	15
5/8	19	24
¾	28	35
7/8	39	49
1	51	64
1-1/8	64	80
1-1/4	81	102
1-3/8	97	121
1-1/2	118	148

6. Further tighten the bolt to the rotation specified in Table 602.17-4. Measure the rotation from the initial marking in Step 4. Record the bolt tension. Assemblies that fail prior to this rotation either by stripping or fracture fail the test.

Table 602.17-4: Rotation from Snug Condition

Bolt Length (measured in Step 1)	Grade A325 Required Rotation	Grade A490 Required Rotation
Up to and including 4 diameters	2/3	2/3
Over 4 diameters, but not exceeding 8 diameters	1	5/6
Over 8 diameters to 12 diameters	1-1/6	1

7. The bolt tension measured in Step 6 after the required rotation must equal or exceed the values specified in Table 601.17-5. Assemblies that do not meet this tension have failed the test.

Table 602.17-5: Turn Test Tension

Bolt Diameter (inches)	Grade A325 Tension (kips)	Grade A490 Tension (kips)
½	14	17
5/8	22	28
¾	32	40
7/8	45	56
1	59	74
1-1/8	74	92
1-1/4	94	117
1-3/8	112	139
1-1/2	136	170

8. Loosen and remove the nut and examine the threads on the nut and bolt. No signs of thread shear failure, stripping, or torsional failure of the bolt should be evident. Assemblies that have evidence of stripping have failed the test.
9. Ensure that the torque measured in Step 5 does not exceed the maximum torque calculated as follows:

$$T_{\max} = 0.25 (P \times 1,000) \left(\frac{D}{12} \right)$$

Where:

- T_{\max} = maximum torque expressed in foot-pounds
- P = bolt tension measured in Step 5 expressed in kips
- D = bolt diameter expressed in inches

Assemblies with torque values exceeding this calculated value have failed the test.

2. Rotational Capacity Tests on Bolts too Short to fit Tension Calibrator

a. Equipment Required

1. Calibrated torque wrench and a spud wrench or equivalent.
2. Spacers and/or washers with hole size no larger than 1/16 inch greater than bolt to be tested.
3. Steel section with normal size hole to install bolt. Any available splice hole can be used with a plate thickness that will provide the number of threads under the nut required in Step 1 below. Mark off a vertical line and lines 1/3 of a turn (120 degrees); 1/2 of a turn (180 degrees); and 2/3 of a turn (240 degrees), from vertical in a clockwise direction on the plate.

b. Procedure

1. Install nut on bolt and measure stick-out of bolt when three to five full threads of the bolt are located between the bearing face of the nut and the bolt head. Measure the bolt length, the distance from the end of the threaded shank to the underside of the bolt head.
2. Install the bolt into the hole and install the required number of shim plates and/or washer (one washer under the nut must always be used) to produce the thread stick-out measured in Step 1.
3. Use a hand wrench to tighten the bolt to a snug condition. The snug condition is the normal effort applied to a 12-inch long wrench. The applied torque should not exceed 20% of the torque determined in Step 5.
4. Match mark the nut to the vertical stripe on the plate.
5. Tighten the bolt by turning the nut using the torque wrench to the rotation specified in Table 602.17-6. Use a second wrench to prevent rotation of the bolt

602.17

head during tightening. Record the torque required to reach this rotation. Measure torque with the nut in motion.

Table 602.17-6

Bolt Length (measured in Step 1)	Required Rotation (All Grades)
Up to and including 4 diameters	1/3
Over 4 diameters, but not exceeding 8 diameters	1/2

The measured torque should not exceed the values specified in Table 602.17-7. Assemblies that exceed the listed torques have failed the test.

Table 602.17-7

Bolt Diameter (inches)	Grade A325 Torque (ft-lbs)	Grade A490 Torque (ft-lbs)
1/2	150	180
5/8	290	370
3/4	500	630
7/8	820	1,020
1	1,230	1,540
1-1/8	1,730	2,160
1-1/4	2,450	3,050
1-3/8	3,210	3,980
1-1/2	4,250	5,310

6. Tighten the bolt further to the rotation specified in Table 602.17-8. The rotation is measured from the initial marking in Step 4. Assemblies that fail prior to this rotation either by stripping or fracture have failed the test.

Table 602.17-8

Bolt Length (measured in Step 1)	Additional Required Rotation Grade A325	Additional Required Rotation Grade A490
Up to and including 4 diameters	1/3	1/4
Over 4 diameters, but not exceeding 8 diameters	1/2	1/3

7. Loosen and remove the nut and examine the thread on the nut and bolt. No signs of thread shear failure, stripping, or torsional failure of the bolt should be evident. Assemblies that have evidence of stripping have failed the test.

3. Verification and Installation of High Strength Bolts with Direct Tension Indicators (DTIs)

- a. **Verification of DTI Performance.** If installing DTIs with high strength bolts to indicate bolt tension, perform the verification testing described below, and install the DTIs in accordance with the method specified below. Unless otherwise approved by the Engineer, install the DTIs under the head of the bolt and turn the nut to tighten the fastener. Follow the manufacturer's recommendations to properly orient the DTI and additional washers, if any, required for the correct use of the DTI.

In the presence of the Engineer, perform verification testing in a calibrated bolt tension measuring device. Use a special flat insert in place of the normal bolt head holding insert. Perform three verification tests for each combination of fastener rotational-capacity lot, DTI lot, and DTI position relative to the turned element (bolt head or nut) to be used on the project. Tighten the fastener by turning the element not against the DTI. Do not allow the element (bolt head or nut) against the DTI to rotate. The purpose of the verification testing is to ensure that the fastener will be at or above the desired installation tension when half or more of the spaces in the DTI have a gap of less

602.17

than 0.005 inch and that the fastener will not undergo excessive plastic deformation at the minimum gap allowed on the Project.

Conduct the verification test as follows:

1. Install the bolt, nut, and DTI assembly in a manner so that at least three and preferably not more than five threads are located between the bearing face of the nut and the bolt head.
2. Tighten the fastener first to the load equal to that specified in Tables 602.17-9 and 602.17-10 under Verification Tension for the grade and diameter of fastener. If an impact wrench is used, it is acceptable to tighten to a load slightly below that required and then use a manual wrench to attain the required tension.
3. Determine and record the number of refusals of a 0.005-inch tapered feeler gage in the spaces between the protrusions. The number of spaces between protrusions is listed below in Tables 602.17-9 and 602.17-10. The number of refusals shall not exceed the number listed under Maximum Verification Refusals in Tables 602.17-9 and 602.17-10 below for the grade and diameter of bolt for un-coated DTIs. The maximum number of refusals for coated DTIs (galvanized, painted or epoxy coated) used under the turned element shall not exceed the number of spaces on the DTI less one. The DTI lot is rejected if the number of refusals exceeds the values in the applicable table or, for coated DTIs, if the gage is refused in all spaces.
4. After the number of refusals is recorded at the verification load, further tighten the fastener until the 0.005-inch feeler gage is refused at all the spaces and a visible gap exists in at least one space.
5. Record the load at this condition and remove the fastener from the tension measuring device.

6. Ensure that the nut can be reassembled by hand for the complete thread length of the bolt excluding thread run-out. If the nut cannot be assembled for this thread length, the DTI lot is rejected unless the load recorded is less than 95% of the average load measured in the rotational capacity test of the fastener lot as specified in **908.04.C.3.g**.

If the bolt is too short to be tested in the calibration device, test the DTI on a long bolt in a calibrator to determine the number of refusals at the Verification Tension listed in Tables 602.17-9 and 602.17-10 below. The number of refusals shall not exceed the values listed under Maximum Verification Refusals. Then test another DTI from the same lot with the short bolt in a convenient hole in the work. Tighten the fastener assembly until the 0.005-inch feeler gage is refused in all spaces and a visible gap exists in at least one space. Disassemble the fastener. Ensure that the nut can be reassembled by hand for the complete thread length of the bolt excluding thread run-out. Reject the DTI lot if the nut cannot be assembled to this thread length.

- b. Installation.** Install fasteners using DTIs in two stages. Prevent rotation of the fastener element during each stage of the installation.
 1. First, snug the connection with bolts installed in all the holes of the connection. Then, tighten the bolts sufficiently to bring all the plies of the connection into firm contact. Ensure that the number of spaces in which a 0.005 inch-feeler gage is refused in the DTI after snug does not exceed those listed under Maximum Verification Refusals in Tables 602.17-9 and 602.17-10 for the grade and diameter of bolt. If the numbers exceed the values in the table, remove the fastener, install another DTI, and re-snug the fastener.
 2. Further tighten the connection until the number of refusals of the 0.005-inch feeler gage is equal to or greater than the number listed under Minimum Installation Refusals in Tables 602.17-9 and 602.17-10 for the grade and diameter of bolt. If the fastener is tightened so that no visible gap in any space

602.17

remains, remove the bolt and DTI, and replace with a new properly tightened fastener and DTI.

Table 602.17-9: DTI Requirements for Grade A325 Bolts

Bolt Diameter (inches)	Verification Tension (kips)	Maximum Verification Refusals	DTI Spaces	Minimum Installation Refusals
½	13	1	4	2
5/8	20	1	4	2
¾	29	2	5	3
7/8	41	2	5	3
1	54	2	6	3
1-1/8	67	2	6	3
1-1/4	85	3	7	4
1-3/8	102	3	7	4
1-1/2	124	3	8	4

Table 602.17-10: DTI Requirements for Grade A490 Bolts

Bolt Diameter (inches)	Verification Tension (kips)	Maximum Verification Refusals	DTI Spaces	Minimum Installation Refusals
½	16	2	5	3
5/8	25	2	5	3
¾	37	2	6	3
7/8	51	2	6	3
1	67	3	7	4
1-1/8	84	3	7	4
1-1/4	107	3	8	4
1-3/8	127	3	8	4
1-1/2	155	4	9	5

c. Equipment Required

1. Calibrated bolt tension measuring device with a special flat insert in place of normal bolt head holding insert. Special insert required to allow access to measure DTI gap.
2. Tapered leaf thickness (feeler) gage 0.005 inch. Same gage as to be used to inspect the bolts after installation.
3. Bolts, nuts, and standard washers to be used in the work with the DTIs.
4. Impact and manual wrench to tighten bolts. Equipment should be the same as to be used in the work.

d. Verification Test Procedure. Conduct three tests for each rotational-capacity lot and position of DTI.

1. Install bolt, nut, DTI, and standard washer (if used) into bolt tension measuring device. Assembly should match that to be used in the work.
2. Snug the bolt to no more than 50% of the required installation tension using the equipment that will be used in the work. Use another wrench on the bolt head to prevent rotation of the head against the DTI if the DTI is to be used under the unturned element.
3. Further tighten the bolt to tension specified in Table 602.17-11 (which is 1.05 times the required installation tension of the bolt). Use another wrench on the bolt head to prevent rotation of the head against the DTI if the DTI is to be used under the unturned element. If an impact wrench is used, tighten to a load slightly below the required load and use a manual wrench to attain the required tension. The load indicating needle of the bolt calibrator cannot be read accurately when an impact wrench is used.

602.17

Table 602.17-11

Bolt Diameter (inches)	Bolt Tension (kips)	
	Grade A325 Bolts	Grade A490 Bolts
½	13	16
5/8	20	25
¾	29	37
7/8	41	51
1	54	67
1-1/8	67	84
1-1/4	85	107
1-3/8	102	127
1-1/2	124	155

- Determine and record the number of spaces between the protrusions on the DTI that a 0.005-inch thickness gage is refused. The total number of spaces in the various sizes and grade of DTIs is listed in Table 602.17-12.

Table 602.17-12

Bolt Diameter (inches)	Number of Spaces	
	Grade A325 Bolts	Grade A490 Bolts
½	4	N/A
5/8	4	N/A
¾	5	6
7/8	5	6
1	6	7
1-1/8	6	7
1-1/4	7	8
1-3/8	7	8
1-1/2	8	N/A

5. The number of spaces that the 0.005-inch thickness gage is refused should not exceed the number specified in Table 602.17-13. If the number of spaces exceeds the number in the table, the DTI fails the verification test.

Table 602.17-13: Verification Criteria ⁽¹⁾

Number of Spaces in Washer	Maximum Number of Spaces Gage is Refused
4	1
5	2
6	2
7	3
8	3

⁽¹⁾ If the test is a coated DTI under the turned element, the maximum number of spaces the gage is refused is the number of spaces on the washer minus one.

6. Further tighten the bolt to the smallest gap to be allowed in the work. Normally, this smallest gap is defined as the gap at all the spaces less than 0.005 inch and not all gaps completely closed. Ensure that the 0.005-inch gage is refused at all spaces, but a visible gap exists in at least one space. The bolts in this test and in the actual installation should not be installed to a no visible gap condition. The load in the bolt becomes indeterminate when no gap exists. Failure of the bolt due to over-tightening may occur if the bolt is tightened beyond complete crushing of the DTI.
7. Remove the bolt from the calibrator and turn the nut on the threads of the bolt by hand. The nut should be able to be turned on the complete length of the threads, excluding the thread run-out. If the nut is unable to go the full thread length, the load required for the minimum gap in Step 6 is too large. The test must be repeated with a larger minimum gap, for example, one space that will accept a 0.005-inch feeler gage to

602.18

establish the smallest gap allowed in the work for the fastener rotational-capacity lot allowed in the work.

8. Bolts from rotational-capacity lots that are too short to fit in the tension measuring device shall be tested by tightening to the minimum gap in Step 6 and checked in accordance with Step 7. The DTI used with the short bolt should be checked in accordance with Steps 1 through 5 using a longer bolt in the tension measuring device.

602.18 Plate Cut Edges

A. Edge Planing

Remove to a depth of $\frac{1}{4}$ inch all sheared edges of plates that are thicker than $\frac{5}{8}$ inch and carry calculated stress. Fillet re-entrant corners to a minimum radius of $\frac{3}{4}$ inch before cutting.

B. Visual Inspection and Repair of Plate Cut Edges

Visually inspect and repair plate cut edges in accordance with Article 3.2.3 of the AASHTO/AWS *Bridge Welding Code*, D1.5, current edition.

602.19 Welds

Perform all welding in accordance with the AASHTO/AWS *Bridge Welding Code*, D1.5, current edition. Where conflicts occur, these Specifications shall govern.

All welders shall be qualified in accordance with the AASHTO/AWS D1.5, *Bridge Welding Code*, current edition. Welders shall be certified for each weld process and position which they will be using.

Grind all full penetration welds in webs and flanges flush with the base metal.

The following are revisions to the AASHTO/AWS *Bridge Welding Code*:

1. Add the following sentence to Article 6.1.1.1:

After fabrication, Quality Control (QC) shall mark each piece (girders, beams, diaphragms, X-frames, bearings, etc.) with the

fabricator's logo and the CWI Number of the QC Inspector accepting the piece. These stamps will signify that Quality Control (QC) has inspected the piece and that it meets the requirements of the plans and specifications.

2. Delete Article 6.1.3.1(3).
3. Delete Article 6.1.3.2.
4. Delete the last sentence in Article 6.1.3.4 and substitute the following:

Only individuals certified for NDT Level II may perform nondestructive testing.

5. Delete 6.1.3.4(1) and 6.1.3.4(2).
6. Delete the period at the end of Article 6.6.1 and add the following:

and access to all records necessary to verify conformance to plans and specifications.

7. Delete Article 6.7.1 and substitute the following:

Complete joint penetration groove welds in main members, as identified in the contract documents shall be QC tested by nondestructive testing.

Radiographic and ultrasonic testing shall both be performed in accordance with the requirements of Section 6.7.1.2:

8. Delete 6.7.1.2(2d) and substitute the following:

Longitudinal butt joints in beam or girder webs shall be 100% QC tested by nondestructive testing.

9. Add the following Article 6.17.5:

Each Ultrasonic Unit shall be certified for general operational performance at a minimum time interval of 12 months with a method approved by the instrument manufacturer.

602.20

602.20 Facing of Bearing Surfaces

Finish bearing and base plates and other bearing surfaces that will come in contact with each other or with concrete according to the ANSI surface roughness requirements defined in ANSI B46.1, *Surface Roughness, Waviness and Lay, Part I*, as specified in Table 602.20-1.

Table 602.20-1: Surface Roughness

Bearing Surface	ANSI Roughness Value
Steel Slabs	2000
Heavy plates in contact in shoes to be welded	1000
Milled ends of compression members, milled or round ends of stiffeners and fillers	500
Bridge rollers and rockers	250
Pins and pin holes	125
Sliding bearings	125

602.21 Abutting Joints

Face and bring abutting joints to an even bearing in compression members and girder flanges, and in tension members where so shown on the Plans and show working drawings. Where joints are not faced, the opening shall not exceed ¼ inch.

602.22 End Connection Angles

Build floor-beams, stringers, and girders having end connection angles to the exact length shown on the Plans, as measured between the heels of the connection angles, with a permissible tolerance of plus 0 inch to minus 1/16 inch. Where continuity is required, face end connections. The thickness of the connection angles shall not be less than 3/8 inch or less than that shown on the detail drawings, after facing.

602.23 Lacing Bars

Neatly round the ends of lacing bars unless another form is required.

602.24 Fabrication of Members

Unless otherwise shown on the Plans, cut and fabricate steel plates for main members and splice plates for flanges and main tension members, not secondary members, so that the primary direction of rolling is parallel to the direction of the main tensile and/or compressive stresses.

Ensure that fabricated members are true to line and free from twists, bends and open joints.

602.25 Web Plates

In built-up girders having no cover plates and that will not be encased in concrete, the top edge of the web plate shall not extend above the backs of the flange angles and shall not be more than 1/8 inch below at any point. Chip portions of the plate, projecting beyond the angles, flush with the backs of the angles. Web plates of girders having cover plates may be 1/2 inch less in width than the distance back to back of flange angles. Before painting, use silicone caulk to seal the top of splices of webs in girders without cover plates.

At web splices, the clearance between the ends of the web plates shall not exceed 3/8 inch. The clearance at the top and bottom ends of the web splice plates shall not exceed 3/4 inch.

602.26 Bent Plates

Furnish un-welded, cold bent, load carrying, rolled steel plates conforming to the following:

1. Take material from the stock plates so that the bend line will be at right angles to the direction of rolling, except that cold-bent ribs for orthotropic deck bridges may be bent in the direction of rolling if approved by the Engineer.
2. Before bending, round the corners of the plate to a radius of 1/16 inch throughout the portion of the plate where bending is to occur.
3. Cold bend so that no cracking of the plate occurs. Use the minimum bend radii, shown in Table 602.26-1, measured to the concave face of the metal.

602.27

Table 602.26-1: Minimum Cold-Bending Radii

Thickness (inches) ^(1,2)	Minimum Bending Radii (by Steel Grade)					
	36	50	50W	HPS70W	100	100W
$t \leq \frac{3}{4}$	1.5t	1.5t	1.5t	1.5t	1.75t	1.75t
$\frac{3}{4} < t \leq 1$	1.5t	1.5t	1.5t	1.5t	2.25t	2.25t
$1 < t \leq 2$	1.5t	2.0t	2.0t	2.5t	4.5t	4.5t
$t > 2$	2.0t	2.5t	2.5t	3.0t	5.5t	5.5t

(1) t = plate thickness
(2) Low alloy steel in thickness over ½ inch may require hot bending for small radii.

Allow for spring-back of ASTM A709 Grade 100 or 100W steels equal to about 3 times that for structural carbon steel. For break press forming, use a lower die span of at least 16 times the plate thickness. Multiple hits are advisable.

If a radius shorter than the minimum specified for cold bending is essential, hot bend the plates at a temperature not greater than 1200 °F, except for ASTM A709 Grade HPS70W steels. If ASTM A709 Grade HPS70W steel plates to be bent are heated to a temperature greater than 1100 °F, re-quench and temper according to the producing mill's standard practice. Hot bent plates shall conform to requirement (1) above.

602.27 Fit of Stiffeners

Fabricate (by milling, grinding, or welding, as shown on the Plans or otherwise specified) end-bearing stiffeners of girders and stiffeners intended as supports for concentrated loads to provide full bearing on the flanges to which they transmit load or from which they receive load. Stiffeners not intended to support concentrated loads shall, unless shown or specified otherwise, fit sufficiently tight to exclude water after being painted. Fillers under stiffeners shall fit within ¼ inch at each end.

602.28 Eyebars

Pin holes may be flame cut at least 2 inches smaller in diameter than the finished pin diameter. Securely fasten together, in the order that they will be

placed on the pin, all eyebars that are to be placed side by side in the structure and bore at both ends while so clamped. Pack and match-mark eyebars for shipment and erection. Stamp all identifying marks with steel stencils on the edge of one head of each member after fabrication is completed to be visible when the bars are nested in place on the structure. Ensure that the eyebars are straight and free from twists with pin holes accurately located on the centerline of the bar. The inclination of any bar to the plane of the truss shall not exceed 1/16 inch to a foot.

Simultaneously cut the edges of eyebars that lie between the transverse centerline of their pin holes with two mechanically operated torches abreast of each other, guided by a substantial template, to prevent distortion of the plates.

602.29 Annealing and Stress Relieving

Machine, finish bore, and straighten structural members, indicated in the Contract to be annealed or normalized, after heat treatment. Normalize and anneal (full annealing) according to ASTM A919. Maintain uniform temperatures throughout the furnace during the heating and cooling so that the temperature difference between any two points on the member does not exceed 100 °F at any one time.

Do not anneal or normalize members of ASTM A709 Grade 100W steels. Stress relieve these grades only with the Engineer's approval.

Maintain a record of each furnace charge, identifying the pieces in the charge and listing the temperatures and schedule used. Provide proper instruments, including recording pyrometers, for determining at any time the temperatures of members in the furnace. The records of the treatment operation shall be available to and meet the approval of the Engineer. The holding temperature for stress relieving ASTM A709 Grade HPS70W and 100W steels shall not exceed 1100 °F.

Stress relieve members, such as bridge shoes, pedestals, or other parts that are built up by welding sections of plate together, according to Section 4.4 of AASHTO/AWS *Bridge Welding Code* D1.5 when required by the Contract.

602.30 Pins and Rollers

Accurately fabricate pins and rollers to the dimensions shown on the Plans and working drawings and to be straight, smooth, and free from flaws. Forge and anneal pins and rollers more than 9 inches in diameter. Pins and rollers

602.31

9 inches or less in diameter may be either forged and annealed or cold-finished carbon steel shafting.

In pins larger than 9 inches in diameter, bore a hole not less than 2 inches in diameter full length along the axis after the forging has been allowed to cool to a temperature below the critical range, under suitable conditions to prevent damage by too rapid cooling, and before being annealed.

602.31 Boring Pin Holes

Bore pin holes true to the specified diameter, smooth and straight, at right angles with the axis of the member and parallel with each other unless otherwise required. Produce the final surface using a finishing cut.

The distance outside-to-outside of end holes in tension members and inside-to-inside of end holes in compression members shall not vary from that specified more than 1/32 inch.

602.32 Pin Clearances

The diameter of the pin hole shall not exceed that of the pin by more than 1/50 inch for pins 5 inches or less in diameter or by 1/32 inch for larger pins.

602.33 Threads for Bolts and Pins

Provide threads on all bolts and pins for structural steel construction that conform to the Unified Standard Series UNC-ANSI B 1.1, Class 2A for external threads and Class 2B for internal threads; but when pin ends have a diameter of 1-3/8 inches or more, provide 6 threads to the inch.

602.34 Pilot and Driving Nuts

Provide two pilot nuts and two driving nuts for each size of pin, unless otherwise specified.

602.35 Identification of Steels During Fabrication

A. Identification by Contractor

Provide the Engineer with complete certified mill test reports showing chemical analysis and physical tests for each heat of steel for all members

unless excepted by the Engineer. Properly identify for the Engineer each piece of steel to be fabricated.

Identify in the shop drawings each piece that is to be made of steel other than ASTM A709 Grade 36 steel. Ensure that pieces made of different grades of steel are not given the same assembling or erecting mark, even if they are of identical dimensions and detail.

Use a system of assembly-marking of individual pieces made of steel other than ASTM A709 Grade 36 steel and of issuing cutting instructions to the shop (generally by cross-referencing the assembly marks shown on the shop drawings with the corresponding item covered on the mill purchase order) that will maintain identity of the mill test report number.

The Contractor may furnish material from stock that can be identified by heat number and mill test report.

Mark any excess material placed in stock for later use with the mill test report number and with its AASHTO M 160 (ASTM A6) specification identification color code, if any, when separated from the full-size piece furnished by the supplier.

B. Certification of Identification

Upon request, furnish an affidavit certifying that throughout the fabrication, the identification of steel was maintained in accordance with this Specification.

602.36 Weighing of Members

If it is specified that any part of the material is to be paid for by actual weight, weigh the finished work in the presence of the Engineer, if practicable. In such case, supply satisfactory scales and perform all work involved in handling and weighing the various parts.

602.37 Full Size Tests

When the Contract requires full size tests of fabricated structural members or eyebars, the Plans or Specifications will state the number and nature of the tests, the results to be attained, and the measurements of strength, deformation or other performance parameters that are to be made. Provide suitable facilities, material, supervision, and labor necessary for making and recording the tests. The Department will pay for the testing of members in

602.38

accordance with the Contract as specified in **602.50**. Include the cost of testing, including equipment, handling, supervision, labor, and incidentals for making the tests, in the Contract price for the fabrication or fabrication and erection of structural steel, whichever is the applicable item in the Contract, unless otherwise specified.

602.38 Marking and Shipping

Paint or mark each member with an erection mark for identification. Provide an erection diagram that identifies the erection marks. Permanently stencil heat numbers on the main material so they will be identifiable in the field. Ensure that the steel fabricator submits three sketches identifying these heat numbers on 8-1/2 by 11-inch sheets to the Inspecting Agency and to the Engineer (see example shown in Figure 602.38-1).




Figure 602.38-1: Example Diagrams showing Heat Numbers

In addition to the heat number shown, the fabricator shall identify all high strength steels regardless of where it is used.

Provide as many copies of material orders, shipping statements, and erection diagrams as the Engineer may direct. Identify the weights of the individual members on the statements. Mark members weighing more than 3 tons with their weights. Load structural members on trucks or cars so that they may be transported and unloaded at their destination without being excessively stressed, deformed, or otherwise damaged.

602.39

Separately pack bolts of one length and diameter and loose nuts or washers of each size. Ship pins, small parts, and packages of bolts, washers, and nuts in boxes, crates, kegs, or barrels. Ensure that the gross weight of each package does not exceed 300 pounds. Plainly mark the outside of each shipping container with a list and description of the contained material.

CONSTRUCTION REQUIREMENTS – ERECTION – REMOVAL

602.39 Erection

Provide the falsework and all tools, machinery, and appliances, including drift-pins and fitting-up bolts, necessary for the expeditious performance of the work. Erect the metalwork, remove the temporary construction, and do all work necessary to complete the structure as required by the Contract.

Shear Stud Connectors

After erecting the beams, attach the shear stud connectors in compliance with OSHA standards. Install the studs in the locations shown on the Plans. Install and test shear studs in accordance with the latest version of AASHTO/AWS D1.5, Chapter 7 Stud Welding. Clean the surface receiving the studs by shot blasting or grinding to a bright metal surface immediately before welding. Weld studs using automatically timed stud welding equipment only. At the beginning of each day or shift, each individual welder/operator and equipment must complete the Production Control/Pre-production Testing described in paragraph 7.7.1 of AASHTO/AWS D1.5. Only allow individuals, who repeatedly demonstrate satisfactory installation, to install the shear studs. The Contractor is responsible for the quality of all welds.

The Department will inspect and randomly test the welds before any reinforcing steel is placed.

602.40 Handling and Storing Materials

Place material to be stored on the Project on skids above the ground. Keep material clean and properly drained. Place girders and beams upright and shore. Support long members, such as columns and chords, on skids placed near enough together to prevent damage due to deflection.

If the Contract is for erection only, check the material received against the shipping lists and report promptly in writing any shortage or damage

discovered. The Contractor is responsible for the loss of and damage to any material in its care.

602.41 Temporary Supports

Design, construct, and maintain temporary supports for steel beam erection to support the loads to which they will be subjected. Submit construction drawings for temporary supports and working drawings for changes in any existing structure necessary for safely maintaining traffic, in accordance with **105.02**. All drawings shall be stamped by a Professional Engineer licensed in the State of Tennessee.

602.42 Method and Equipment

All contractors and subcontractors directly engaged in the erection or removal of structural steel, precast prestressed or mild steel reinforced concrete bridge beams or girders over active highway traffic lanes, on any route, railroad or any stream deemed navigable to commercial or pleasure water craft, shall submit an erection or removal plan prepared and stamped by a Professional Engineer licensed in the State of Tennessee. Include the following in these plans: the sequences of erection or removal, the generalized location of all pick points, and the plan to adequately stabilize the structure throughout the erection or removal process. Submit this plan to the Engineer at least 30 days before starting erection or removal. At each stopping point in the erection or removal sequence, have a competent contractor's representative inspect the beams to ensure adequate stability.

Do not begin any erection or removal work without the Engineer's approval. The Engineer's approval does not relieve the Contractor of the responsibility for the safety of its method or equipment or from carrying out the work in accordance with the Plans and Specifications.

602.43 Straightening Bent Material and Cambering

A. Straightening Bent Material

Straighten plates, angles, other shapes, and built-up members, when permitted by the Engineer, using methods that will not produce fracture or other damage. Straighten distorted members by mechanical means or, if approved by the Engineer, by the careful planned and supervised application of a limited amount of localized heat, except that heat straightening of ASTM A709 Grade 100W or ASTM A517 steel members shall be done only under rigidly controlled procedures, each

602.44

application subject to the approval of the Engineer. Ensure that the maximum temperature of the ASTM A709 Grade 100W and the HPS70W steels does not exceed 1100 °F. Do not apply heat directly on weld metal. In all other steels, do not allow the temperature of the heated area to exceed 1200 °F as determined by temperature indicating crayons, liquids, bimetal thermometers, or infrared thermometers (conductor or non-conductor).

Keep parts to be heat straightened substantially free of stress and from external forces, except stresses resulting from mechanical means used in conjunction with the application of heat.

Following the straightening of a bend or buckle, carefully inspect the surface of the metal for evidence of fracture. Fractured material will be rejected.

B. Cambering

Correct errors in camber in welded beams and girders of ASTM A709 Grade HPS70W and 100W material under rigidly controlled procedures, with each application subject to the Engineer's approval.

602.44 Misfits

Assume responsibility for all misfits, errors, and damage, and make the necessary corrections and replacements. The Engineer will allow the correction of minor misfits using small amounts of reaming, cutting, and chipping. However, immediately report any error in the shop fabrication or deformation resulting from handling and transportation that prevents the proper assembling and fitting up of parts by moderate use of drift pins or by a moderate amount of reaming and slight chipping or cutting. Obtain the Engineer's approval of the proposed method of correction. Perform the correction in the Engineer's presence.

602.45 Assembling

Accurately assemble parts as shown on the working drawings and follow all match-marks. Carefully handle the material so that no parts will be bent, broken, or otherwise damaged. Do not perform any hammering that will damage or distort the members. Clean bearing surfaces and surfaces to be in permanent contact before assembling the members. Unless erected by the cantilever method, erect truss spans on blocking that is placed to give the trusses proper camber. Leave the blocking in place until the tension chord

splices are fully connected with permanent fasteners and all other truss connections pinned and erection bolted. Do not permanently fasten splices of butt joints of compression members and railing until the span has been swung. For splices and field connections, fill one-half of the holes with erection bolts and cylindrical erection pins (half erection bolts and half pins) before placing permanent fasteners.

Use fitting-up bolts that are of the same nominal diameter as the permanent fasteners and cylindrical erection pins that are 1/32 inch larger.

602.46 Pin Connections

Furnish pilot and driving nuts for use in driving pins at no cost to the Department. Drive pins so that the members fully bear on the pins. Screw pin nuts tight and burr the threads at the face of the nut with a pointed tool.

602.47 Setting Shoes and Bearings

Do not place shoes and bearing plates on bridge seat bearing areas that are improperly finished, deformed, or irregular. Set shoes and bearing plates level in exact position and to have full and even bearing. Unless otherwise specified, the Contractor may use any of the following methods to set shoes and bearing plates:

1. A preformed fabric pad composed of multiple layers of 8-ounce duck impregnated and bound with high quality natural rubber or of equivalent and equally suitable materials compressed into resilient pads of uniform thickness. The number of plies shall be such as to produce a thickness of 1/8 inch after compression and vulcanizing. The finished pads shall withstand compression loads perpendicular to the plane of the laminations of not less than 10,000 pounds per square inch without detrimental reduction in thickness or extension.
2. Elastomeric Bearing Pads.
3. Grouted Bearing Plate.

Do not place any load on them until the grout has set for at least 96 hours. Take adequate provisions to keep the grout well moistened during this period. The grout shall consist of one part Portland cement to one part mortar sand.

Unless otherwise shown on the Plans or conditionally approved by the Engineer, cast anchor bolts into the masonry. If the Engineer approves the

602.48

drilling of holes for setting anchor bolts, set the bolts accurately, and completely fill the holes with grout meeting the requirements of **921.09**. The location of the anchor bolts in relation to the slotted holes in the expansion shoes shall correspond with the temperature at the time of erection. Adjust the nuts on anchor bolts at the expansion ends of spans to allow the free movement of the span.

602.48 Painting

Unless otherwise shown on the Plans or specified in the Contract, perform shop and field painting in accordance with the **603**. Pay special attention to **603.06**.

Grease rollers, when not painted, with hard grease that will readily adhere to the metal in cold and hot weather. Paint the ends of rollers with the same kind and type of paint as the rest of the structure.

COMPENSATION

602.49 Method of Measurement

The Department will measure metal in a structure by the unit, lump sum, when the item is designated "Steel Structures" and by the pound when the item is designated "Structural Steel."

The Department will calculate weight for Structural Steel on the following bases:

A. Unit Weights (pound per cubic foot)

The Department will use the material unit weights specified in Table 602.49-1.

Table 602.49-1: Material Unit Weights

Materials	Unit Weight (pound per cubic foot)
Aluminum, cast or wrought	173.0
Bronze	536.0
Copper-Alloy	536.0
Copper-Sheet	558.0
Iron, cast	445.0
Iron, malleable	470.0
Iron, wrought	487.0
Lead, sheet	707.0
Steel, rolled, cast, copper bearing, silicon, nickel and stainless	490.0
Zinc	450.0

B. Shapes and Plates

The Department will compute the weight of rolled shapes, and of plates up to and including 36 inches in width, on the basis of their nominal weights and dimensions, as shown on the Plans, deducting for cuts, and open holes.

The Department will compute weights of plates wider than 36 inches on the basis of their dimensions as shown on the Plans, deducting for cuts and holes. To this will be added one-half of the "Permissible Variation in Thickness and Weight," as tabulated in ASTM A6, General Requirements for Delivery of Rolled Steel Plates, Shapes and Bars for Structural Use.

C. Castings

The Department will compute the weight of castings from the dimensions shown on the approved shop drawings, deducting for open holes. To this weight will be added 5% allowance for fillets and overrun. Scale weights may be substituted for computed weights of castings or of small complex parts for which accurate computations of weight would be difficult.

602.49

D. High Strength Bolts

The Department will include the weight of heads, nuts, single washers, and threaded stick-through of all high tensile strength shop bolts on the basis of the weights shown in Table 602.49-2.

Table 602.49-2: Weight of High Strength Bolts

Diameter of Bolt (inches)	Weight per 100 Bolts (pounds)
½	19.7
5/8	31.7
¾	52.4
7/8	80.4
1	116.7
1-1/8	165.1
1-1/4	212.0
1-3/8	280.0
1-1/2	340.0

E. Welds

The Department will base the weight of shop and field fillet welds on the weights shown in Table 602.49-3.

Table 602.49-3: Weight of Shop and Field Fillet Welds

Size of Weld (inches)	Pounds per Linear Foot
¼	0.20
5/16	0.25
3/8	0.35
½	0.55
5/8	0.80
¾	1.10
7/8	1.50
1	2.00

F. Shear Connectors

The Department will compute weights of shapes for shear connectors on the basis of their nominal weights per foot as shown on the approved shop drawings.

The Department will compute weights of spirals for shear connectors on the basis of the weights per foot as shown on the approved shop drawings.

The weight of stud bar shear connectors will be based on Table 602.49-4.

Table 602.49-4: Weight of Stud Bars

Diameter of Shank (inches)	Weight per inch of Shank (pounds)	Weight of Head (pounds)
3/4	0.125	0.174
7/8	0.170	0.210
1	0.223	0.250

G. Miscellaneous

The Department will not include the weight of temporary erection bolts, shop and field paint, boxes, crates, and other containers used for shipping, and materials used for supporting members during transportation and erection.

H. Other Items

The Department will measure quantities of other Contract items that enter into the completed and accepted structure for payment in the manner prescribed for the items involved.

602.50 Basis of Payment

The Department will pay for accepted quantities on a unit price per pound or on a lump sum basis, as required by the Contract and as follows:

602.50

A. Structural Steel – Per Pound

Under Contracts containing an item for Structural Steel, all metal parts, other than metal reinforcement for concrete and metal piling, such as anchor bolts and nuts, shoes, rockers, rollers, bearing and slab plates, pins and nuts, expansion dams, weld metal, bolts embedded in concrete, and cradles and brackets, will be considered as structural steel, unless otherwise specified. The Department will pay for accepted quantities of structural steel at the contract unit price per pound for Structural Steel.

B. Steel Structures – Lump Sum

When the bid schedule calls for a lump sum price for Steel Structures, the Department will pay for the item at the contract lump sum price, complete in place and accepted.

The Department will not pay for materials used in standard tests, unless otherwise indicated on the Plans or in the Special Provisions.

The Department will pay for full size fabricated structural members or eye-bars that are tested in accordance with the Specifications, when such tests are indicated on the Plans or in the Special Provisions, at the same rate as for comparable members in the structure. The Department will not pay for members that fail to meet Contract requirements and members that are rejected as the result of tests.

The cost of drilling anchor bolt holes is incidental to other pay items.

The estimate of the weight for steel structures shown on the Plans is approximate only, and no guarantee is made that it is the correct weight to be furnished. The Department will not adjust the contract price if the weight furnished is more or less than the estimated weight.

If the Engineer directs changes in the work that modify the weight of steel to be furnished, the Department will adjust the lump sum payment as follows:

1. The Department will determine the value per pound of the increase or decrease in the weight of structural steel involved in the change by dividing the contract lump sum amount by the weight of steel in the original structure(s).
2. To determine the adjusted contract lump sum payment, the Department will take the contract lump sum amount, plus or minus

602.50

the value of the steel involved in the change. The Department will not allow any additional compensation for such change.

603.01

SECTION 603 – PAINTING

603.01	Description	480
603.02	Materials	481
603.03	Reserved.....	482
603.04	Clearing and Removing Obstructions	482
603.05	Preparing Surfaces	482
603.06	Schedule of Painting	483
603.07	Weather Conditions.....	485
603.08	Storing Paint.....	486
603.09	Mixing Paint.....	486
603.10	Applying Paint	486
603.11	Shop Painting	489
603.12	Field Painting	490
603.13	Repainting Existing Steel Structures.....	491
603.14	Protection of Traffic.....	495
603.15	Protection of Structures and Surfaces	495
603.16	Final Cleanup	495
603.17	Method of Measurement	496
603.18	Basis of Payment.....	496

DESCRIPTION

603.01 Description

A. General

This work consists of surface preparation, paint application, furnishing protection from paint spatter and disfigurement, and final cleanup. The type, color, and number of paint coats shall be as specified in **603.06** and as shown on the Plans.

Each coat, for all systems, shall have a contrasting tint to aid in even application and inspection.

B. Certification Requirements

All contractors or subcontractors involved in field surface preparation or coating application shall be certified according to the Society for Protective Coatings (SSPC) Painting Contractor Certification Program (PCCP) or NACE International Institute Contractor Accreditation Program (NIICAP).

Contractors or subcontractors performing field coating application shall be certified according to SSPC QP1, Field Application or equivalent, including NIICAP AS-1 Field.

Contractors and subcontractors performing field surface preparation of existing structures shall be certified according to SSPC QP2, Field Removal of Hazardous Coatings or equivalent, including NIICAP AS-2 Hazard Waste Removal.

Ensure that all contractors and subcontractors that perform field surface preparation or field coating application are certified to the requirements of SSPC; QP1 or QP2, or NIICAP; AS-1 Field or AS-2 before Contract award and remain certified for the duration of the Project. If a contractor’s or subcontractor’s certification expires or is suspended, do not allow that contractor to perform any work until the certification is reissued or reinstated. The Department will not consider any requests for time extensions for any delay in the completion of the Project due to an inactive certification and may apply liquidated damages. Provide a copy of the certifications to the Engineer before beginning work and notify the Engineer of all changes in certification status.

MATERIALS

603.02 Materials

Provide materials as specified in:

Paint..... **910**

Unless otherwise specified, use paint manufactured and prepared to comply with the applicable specifications including those included by reference.

603.03

603.03 Reserved

CONSTRUCTION REQUIREMENTS

603.04 Clearing and Removing Obstructions

Cut or clear trees, limbs, bushes, grass, and other items that will damage or prevent satisfactory painting. Remove and replace as directed by the Engineer all obstructions or other items that will prevent proper paint application. Take care in removing the obstructions so as not to impair their usefulness when replaced. Replace damaged items at no cost to the Department.

603.05 Preparing Surfaces

A. New Structures

Prepare all metal surfaces to a condition equivalent to SSPC SP10/NACE 2 (Near White Blast Clean).

Prepare the fabricated steel to have a surface profile of 1 mil minimum to 2.5 mils maximum before applying the shop coat. Verify the surface profile obtained on the prepared surface according to ASTM D4417, Method A, B, or C.

B. Existing Structures

Prepare metal surfaces for painting as shown on the Plans and in accordance with these Specifications.

Unless otherwise specified, the Contractor may use any of the following methods to clean the metal:

1. **Hand (SSPC-SP2) or Power Tool (SSPC-SP3) Cleaning.** Use bristle or wood fiber brushes to remove loose dust. Remove oil and grease with solvents according to SSPC SP1. Use solvents that are safe and biodegradable.
2. **Blast Cleaning.** Use SSPC-SP10/NACE 2 for System A, or as shown on the Plans for Systems B and C. Blast cleaning shall leave a surface profile acceptable to the paint manufacturer.

For dry-blasted surfaces, remove all traces of blast products from the surface and abrasive from pockets and corners by brushing the surface with clean brushes made of hair, bristle, or fiber, using compressed air (from which detrimental oil and water have been removed) to blow off such residue, or cleaning with a vacuum.

For wet-abrasive-blasted surfaces, clean by rinsing with fresh water, to which sufficient corrosion inhibitor has been added to prevent rusting, or with fresh water, followed immediately by an inhibitive treatment approved by the paint manufacturer. Supplement this cleansing by brushing if necessary to remove residue.

Ensure that the compressed air used for nozzle blasting is free of detrimental amounts of water or oil. Provide adequate separators and traps. In the presence of the Engineer, test for the presence of oil or water in the compressed air in accordance with ASTM D4285.

Perform blast cleaning operations so that no damage is done to partially or entirely completed portions of the Work.

Remove all traces of oil, grease, or smudges deposited in the cleaning operations from blast-cleaned surfaces. Obtain the Engineer's approval of the cleaning before painting.

Ensure that the appearance of the surface after blast cleaning corresponds with the pictorial standards A SP-10, B SP-10, C SP-10, or D SP-10 of SSPC-VIS 1.

3. **Water Washing.** Use a high pressure water wash to remove all chalk, loose coatings, and other contaminants. High pressure water wash is defined as using pressure from 3,000 to 4,000 pounds per square inch at 8 to 10 gallons per minute.

603.06 Schedule of Painting

A. New Structures

Unless otherwise specified, paint all structural steel and other exposed metal by the paint systems specified in Table 603.06-1.

603.06

Table 603.06-1: System A – Inorganic Zinc

Paint System	Specification	Minimum Dry Film Thickness (mils)	Maximum Dry Film Thickness (mils)
Primer (shop coat)	Inorganic Zinc Silicate Paint, 910.03	2.5	5.0
Intermediate Tie Coat	910.03 , as modified below	2.0	5.0
Finish Coat (color coat)	Urethane Finish, 910.03 (match color shown on the Plans)	2.0	5.0

Only apply primer in the fabrication shop. Apply the intermediate tie coat and finish coat in the field. To ensure compatibility between coats, obtain all paint (primer, intermediate tie coat, and finish coat) from the same manufacturer.

B. Existing Structures

Unless otherwise shown on the Plans, paint all metal surfaces of existing structures with one of the systems specified in Tables 603.06-2 or 603.06-3, or System A, as specified in **603.06.A**. To ensure compatibility between coats, obtain all paint (spot primer, primer, and finish coat) from the same manufacturer.

Table 603.06-2: System B

Paint System	Specification	Minimum Dry Film Thickness (mils) ⁽²⁾	Maximum Dry Film Thickness (mils) ⁽²⁾
Spot Primer	Epoxy Mastic ⁽¹⁾	2.0	5.0
Primer	Epoxy Mastic ⁽¹⁾	3.0	5.0
Finish Coat (color coat)	Urethane Finish, 910.03 (match color shown on the Plans)	2.0	5.0

⁽¹⁾ Material to be on Qualified Products List maintained by the Division of Materials and Tests.

⁽²⁾ The primer dry film thickness is measured above the surface profile.

Table 603.06-3: System C

Paint System	Specification	Minimum Dry Film Thickness (mils) ⁽²⁾	Maximum Dry Film Thickness (mils) ⁽²⁾
Spot Primer	Universal ⁽¹⁾	2.0	5.0
Primer	Universal ⁽¹⁾	3.0	5.0
Finish Coat (color coat)	Urethane Finish, 910.03 (match color shown on the Plans)	2.0	5.0

⁽¹⁾ Material to be on Qualified Products List maintained by the Division of Materials and Tests.

⁽²⁾ The primer dry film thickness is measured above the surface profile.

603.07 Weather Conditions

Do not apply paint:

1. When either the ambient or steel surface temperature exceeds 100 °F or is below 40 °F, unless the Engineer approves otherwise in writing.

603.08

2. To steel that is at a temperature that will cause blistering or porosity, or otherwise will be detrimental to the life of the paint.
3. When the relative humidity exceeds 85%.
4. During rain, snow, fog, or misty conditions, or when the steel surface temperature is less than 5 °F above the dew point.

603.08 Storing Paint

If paint is to remain in storage for a considerable length of time, turn the containers end for end at least once a week. The Engineer will re-inspect paint that has been in storage for longer than 6 months before approving its use. Store paint according to the manufacturer's recommendations. Do not allow the paint to freeze.

603.09 Mixing Paint

Thoroughly mix paint before applying. Ensure that the pigments remain in uniform suspension during application. Perform mixing by mechanical methods, except that hand mixing will be permitted for containers less than 5 gallons in size. When special paint is specified, mix it according to the manufacturer's recommendation.

603.10 Applying Paint

A. General

Submit the manufacturer's current printed instructions for applying the paint system specified to the Engineer for approval. Follow the instructions, as approved, unless otherwise directed by the Engineer.

Apply paint by brushing, spraying, or a combination of these methods. The Contractor may use daubers or sheepskins if no other method is practicable to properly apply paint in places of difficult access. Only use dipping, roller coating, or flow coating when specifically authorized.

To the maximum extent practicable, apply each coat of paint as a continuous film of uniform thickness free of pores. Repaint all thin spots or areas missed in the application and allow to cure before applying the next coat of paint.

Ensure that each coat of paint is in a proper state of cure before applying the succeeding coat.

B. Spray Application

Spray application of paint, whether air spray, airless spray, hot air spray, or hot airless spray, shall be in accordance with the following:

Use equipment suitable for the intended purpose, that is capable of properly atomizing the paint to be applied, and that is equipped with suitable pressure regulators and gauges. Maintain the equipment in proper working condition. Keep spray equipment so that dirt, dried paint, and other foreign materials are not deposited in the paint film. Remove solvents left in the equipment before using.

- 1. Air Spray.** Use the air caps, nozzles, and needles recommended by the manufacturers of the material being sprayed and the equipment being used.

Provide adequately sized traps or separators to remove oil and condensed water from the air. Periodically drain the traps or separators during operations. Ensure that the air from the spray gun impinging against a clean surface shows no sign of condensed water or oil. Adjust the pressure on the material in the pot when necessary for changes in elevation of the gun above the pot. The atomizing air pressure at the gun shall be high enough to properly atomize the paint, but not so high as to cause excessive fogging of paint, excessive evaporation of solvent, or loss by over-spray.

- 2. Airless Spray.** Use fluid tips of proper orifice and fan angle, and a fluid control gun of proper construction, as recommended by the manufacturer of the material being sprayed and the equipment being used. Fluid tips shall be of the safety type with shields.

Adjust the air pressure to the paint pump so that the paint pressure to the gun is proper for optimum spraying effectiveness. This pressure shall be sufficiently high to properly atomize the paint. Do not use pressures considerably higher than that necessary to properly atomize the paint.

Keep spraying equipment clean and use proper filters in the high pressure line so that dirt, dry paint, and other foreign materials are

603.10

not deposited in the paint film. Remove all solvent left in the equipment before applying paint.

Provide airless paint spray equipment with an electric ground wire in the high-pressure line between the gun and the pumping equipment. Ensure that the pumping equipment is suitably grounded to avoid the build-up of any electrostatic charge on the gun.

C. Brush Application

Use brushes of a style and quality that will enable proper application of paint. Round or oval brushes are generally considered most suitable for bolts, irregular surfaces, and rough or pitted steel. Wide, flat brushes are suitable for large flat areas, but they should not have a width over 5 inches. Length of the bristles should be equal to or exceed the brush width.

Brush to obtain a smooth coat, as nearly uniform in thickness as possible. Brush subsequent coats in a direction perpendicular to that of the previous coat. Typically, brushed coats are thinner than sprayed coats and additional brushed coats may be needed to achieve the proper film thickness. Work paint into all crevices and corners. Use spray, daubers, or sheepskins to paint surfaces not accessible to brushes. Brush out all runs or sags.

D. Roller Application

The Contractor may use rollers to apply paint on flat or slightly curved surfaces. Roller application shall be in accordance with the recommendations of the paint manufacturer and roller manufacturer. Use paint rollers of a style and quality that will allow proper application of paint having the continuity and thickness required in Sections 6.7 and 6.8 of SSPC-PA 1. The coating shall not contain any nap from the roller.

Do not apply paint using rollers on irregular surfaces such as bolts, crevices, welds, corners, or edges, unless otherwise specified. When permitted, however, subsequently brush out the paint applied by roller on these irregular surfaces to form a continuous and unbroken film.

603.11 Shop Painting

Unless otherwise specified, apply one coat of primer paint to steelwork after it has been accepted by the inspector and before it is shipped from the plant. The shop coat of paint shall meet the dry film thickness specified in **603.06** for the paint system being supplied.

Paint surfaces that are not in contact, but inaccessible after assembly, with three coats of shop paint. The shop contact surfaces and field contact surfaces within friction type joints shall be free of oil, paint, lacquer, galvanizing, or rust inhibitor. Apply a coat of shop paint to other field contact surfaces, except for main splices for chords of trusses and large girder splices involving multiple thicknesses of material where a shop coat of paint would make erection difficult.

Do not paint structural steel that is to be welded before welding is complete. If it is to be welded only in the fabricating shop and subsequently erected by bolting, apply one coat of paint after shop welding is finished. Do not apply shop paint to steel in the area where field welding will be performed.

Coat machine-finished surfaces for sliding contact with an approved lubricant, as soon as practicable after being accepted and before removal from the shop.

Paint erection marks for field identification of members and weight marks on surface areas previously painted with the shop coat. Do not load material for shipment until it is thoroughly dry, and in no case, less than 24 hours after applying the paint.

Design bolted faying surfaces for a Class B surface. Ensure the faying surfaces are prepared to provide a slip coefficient at least equal to that required for a Class B surface. Provide a certification that the paint used will provide the required resistance at the proposed thickness.

Do not move or handle painted steel until sufficient cure time has elapsed to ensure no damage is done to the fresh coating. Insulate the steel from the binding chains by softeners approved by the Engineer. Provide padding for hooks and slings used to hoist steel. Space diaphragms and similar pieces in such a way that no rubbing will occur during shipment that may damage the coatings. Store the steel on pallets at the jobsite, or by other means approved by the Engineer, so that it does not rest on the dirt and so that components do not fall or rest on each other.

603.12

603.12 Field Painting

Apply the intermediate coat and finish coat for steel structures in the field, after erection is complete, except as specified in **603.11**.

Before painting operations begin:

1. Obtain the Engineer's approval of a containment system designed to prevent release of surface preparation debris, dust, drippings, and over-spray into the environment.
2. Develop a contingency plan for cleanup of inadvertent spills of paint.
3. Submit a copy of the contingency plan to the Engineer, along with a list of the equipment and personnel that will implement the plan.
4. Have on the jobsite, and approved, the personnel, equipment, and material necessary to contain both spillage and over-spray. Keep onsite the following items, as a minimum:
 - a. 55-gallon drum of sand,
 - b. Biodegradable cleaners and degreasers, and
 - c. Boom skimmer collector and boat with motor for over water work.

Limit and contain over-spray by following prudent application procedures in accordance with the specifications, taking into account the ambient climatic conditions. Use drop-cloths, screens, and similar measures to prevent contamination of the soil, adjacent properties, and streams or ponded surface water.

Immediately clean up spills or over-spray and concurrently report the occurrence to the Tennessee Department of Environment and Conservation (TDEC) and the Engineer. Also notify the Tennessee Emergency Management Agency (TEMA) where deemed appropriate.

Prominently display a copy of the contingency plan, including emergency phone numbers, at the jobsite.

For each field coat of paint, apply the dry film thickness specified in **603.06** for the paint system being used. Where measurement of dry film thickness

may become difficult or dangerous, the Engineer may allow wet film measurement. In such cases, the Engineer will predetermine and notify the Contractor of the required wet film thickness, for each type of paint, to comply with the dry film thickness specified.

Sand to remove excessive thickness from areas of each coat that have dry film thickness over the maximum specified or that have runs and sags. Touch up areas of the finish coat after sanding to provide a uniform appearance.

Touch up metal that has been shop coated with the same paint as the shop coat. This touch-up shall include cleaning and painting of field connections, welds, and all damaged or defective paint and rusted areas. The Contractor may apply an overall coat of primer in place of touch-up or spot painting.

Before erection, apply all field coats of paint to surfaces (other than contact surfaces) that will be inaccessible after erection. Only apply shop primer to surfaces that will be in contact with concrete.

If concreting or other operations damage paint, clean and repaint the surface. Before applying any paint, remove all cement or concrete spatter, drippings, and other debris that would interfere with repainting the damaged area.

When traffic produces an objectionable amount of dust, allow the dust for the necessary distance on each side of the bridge, and take all other precautions necessary to prevent dust and dirt from coming in contact with freshly painted surfaces or with surfaces before the paint is applied, at no cost to the Department.

603.13 Repainting Existing Steel Structures

Clean and prepare all metal surfaces to be repainted as specified in **603.05.B**, unless otherwise specified, and repaint with the paint system shown on the Plans. Apply paint as specified in **603.12**. Unless otherwise shown on the Plans, take the following precautions to remove, contain, and dispose of the surface preparation waste and paint removal media.

A. General

Before starting surface preparation, take soil and water samples at the bridge site. Have the samples analyzed by EPA Test Method 1311, Toxicity Characteristic Leaching Procedure (TCLP), to determine existing metal and organic content.

603.13

Contain all waste debris in an enclosed system using air moving equipment capable of creating a negative pressure inside the enclosure to prevent release of debris or dust into the environment, with the following exception: equipment capable of creating a negative pressure will not be required when surface preparation is performed using high pressure water or when paint removal is confined to localized surface areas such as bearings and beam ends and where removal of the paint is accomplished by a containment means, approved by the Engineer, that precludes the release of removal waste into the environment. Do not perform any surface preparation activities when weather conditions, as determined by the Engineer, preclude effective containment of waste debris and dust.

When a high pressure water wash is specified, perform a preliminary wash test on a representative area of 50 square feet of the structural steel that is to be cleaned and painted, in order to collect a minimum of two samples of the debris in the used wash water. Take the samples in the presence of a Department representative and have them analyzed for metal and organic content using the TCLP test method. If samples do not exceed threshold values for a characteristic waste, provide containment consisting of screens, water permeable tarps, or both. Place these screens or tarps around the work area to contain all paint chips or other solid wastes generated by the water wash operations. If samples exceed threshold values for a characteristic waste, use as containment water impermeable material capable of containing all waste including the wash water.

Before starting the work, obtain all required permits and supply copies to the Engineer.

B. Containment

1. **General.** Before starting surface preparation at each bridge, submit the design drawings of the containment system for surface preparations to the Engineer for review. See SSPC Guide 6, *Guide for Containing Surface Preparation Debris Generated During Paint Removal Operations*. There shall be no visible emissions from the containment.

From SSPC Guide 6:

- a. Blast clean: minimum Class 2A, visual negative pressure verification

- b. Water wash: Class 2W
- c. Hand and power tool clean with vacuum shroud: Class 3P
- d. Hand and power tool clean without vacuum shroud: Class 2P

2. **Submittal Requirements.** Include the following in the submittal:

- a. Provide an analysis of the load that will be added to the existing structure by the containment system and waste materials. The load analysis shall ensure that the system will not induce a load on the bridge that will create an overstress condition or otherwise affect the structural integrity of the bridge. Retain a civil engineer licensed by the State of Tennessee to prepare and seal the analysis. The containment system or equipment shall not encroach upon the minimum bridge clearances shown on the Plans, unless otherwise approved by the Engineer.

The Engineer's review and acceptance of the load analysis in no way relieves the Contractor of responsibility for the structural safety of the containment system.

- b. Provide a work phase diagram describing how the debris is to be contained and collected during surface preparation operations, including material specifications and details for containment structures (connections, frame, supports, enclosure sheeting, etc.) and type of blast media. Properly maintain the containment system while work is in progress and do not deviate from the approved working drawings without the Engineer's prior approval. Deny public access to rigging, scaffolding, and containment systems.
- c. Provide a contingency plan for environmental cleanup of a containment system failure or spill that releases surface preparation debris into the environment. Maintain a copy of the contingency plan and all materials and equipment required to implement the cleanup at the jobsite at all times during surface preparation and containment operations.

If a containment system fails or a spill occurs, immediately notify the Tennessee Department of Environment and Conservation (TDEC). Suspend all operations except those activities required to implement the contingency plan for cleanup. Do not resume surface preparation operations until

603.13

modifications have been made to correct the cause of the failure or spill.

- d. Identify the location and type of temporary storage area for contaminated debris pending its final disposition.

C. Storage and Disposal

Place all waste collected in the containment system in approved containers, tagged with the bridge number, contract number, Contractor's name, contents, and the date. Haul the containers daily, or as directed by the Engineer, to a storage area that will prevent spillage and migration of the waste into the environment. The storage area shall provide protection from vandalism and unauthorized access by the general public and shall be approved by the Engineer.

Collect a representative, composite sample for each 10 cubic yards, or portion thereof, of all waste as it is generated. Retain an approved independent testing laboratory to analyze all samples for metals and organic content using EPA Test Method 1311, Toxicity Characteristic Leaching Procedure (TCLP).

The TCLP test report for each composite sample shall show the percentage of the toxic metals and their respective threshold values. Waste not exceeding the threshold for a characteristic waste may be disposed of as an industrial waste in any landfill permitted to handle this material.

Handle all waste that exceeds the threshold for a characteristic waste as a hazardous waste. Comply with all hazardous waste rules and regulations of the EPA and the Tennessee Department of Environment and Conservation (TDEC).

Do not store any hazardous waste at the temporary storage site for more than 90 days after the date of generation. Transport all hazardous waste using a permitted transporter and dispose of this waste in an authorized hazardous waste facility. As the co-generator of the waste, the Contractor shall sign the manifests and other required documents.

Provide a copy of all test reports, transportation manifests, and confirmation of disposal to the Engineer before acceptance of the Project.

D. Worker and Public Safety

Ensure that all personnel involved in the generation and handling of the waste are trained in accordance with EPA/Occupational Safety and Health Administration (OSHA) directives. Comply fully with 29 CFR 1926.62 for worker and public safety protection. Provide adequate respiratory protection and protective clothing to all exposed workers, including Department employees when their inspection duties subject them to exposure. The protection provided shall meet OSHA requirements.

Contain all waste generated by surface preparation to not cause a public hazard.

After metal surfaces have been cleaned and prepared, paint existing steel structures in accordance with **603.06** or as otherwise specified.

603.14 Protection of Traffic

Protect the environment and the traveling public, both vehicular and pedestrian, from injury or damage during the progress of painting. These precautions may include, but are not limited to, erecting suitable coverings, protective screens, warning signs, and barricades. The Contractor shall be directly and solely responsible for injury and damage incurred and hereby agrees to hold the Department and its employees harmless therefrom.

603.15 Protection of Structures and Surfaces

Protect all portions of the structure against damage by splatter of paint or paint materials. Clean and restore to original condition all surfaces damaged by paint splatter at no cost to the Department.

603.16 Final Cleanup

Perform final cleanup as specified in **104.10**.

603.17

COMPENSATION

603.17 Method of Measurement

A. Painting Steel Structures

Unless otherwise specified, the Department will consider the painting of steel structures to be incidental to the price bid for Structural Steel.

When the Contract includes an item for Painting Steel Structures on a lump sum basis, the Department will measure painting a structure or structures, as shown on the Plans, as one unit.

B. Repainting Existing Steel Structures

The Department will measure Repainting Existing Steel Structures for payment on a lump sum basis for each unit. The repainting of a structure or structures as shown on the Plans will be considered as one unit.

C. Containment and Disposal of Waste

The Department will measure Containment and Disposal of Waste for payment on a lump sum basis for each unit. The containment and disposal of surface preparation wastes for a structure or structures as shown on the Plans will be considered one unit.

When the Contract does not include pay items for containment and disposal of waste, consider such work to be incidental to other items of construction.

603.18 Basis of Payment

When provided for in the Contract, the Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Painting Steel Structures (Location and Description)	Lump Sum
Repainting Existing Steel Structures (Location and Description)	Lump Sum
Containment and Disposal of Waste (Location and Description)	Lump Sum

When the Contract includes an item for Painting Steel Structures, such payment is full compensation for preparing the surface and furnishing and applying the paint.

Payment for Repainting Existing Steel Structures is full compensation for obtaining all permits and preparing the surface, including removing paint and furnishing and applying the paint.

Payment for Containment and Disposal of Waste is full compensation for obtaining all permits, including all fees and costs thereof, containing surface preparation waste, furnishing containers and placing waste therein, and testing, transporting, and disposing of all surface preparation waste.

The Department will deduct fines incurred by the State as a result of the Contractor's operation from monies due to the Contractor.

SECTION 604 – CONCRETE STRUCTURES

604.01	Description	499
604.02	Materials	499
604.03	Classification, Proportioning and Quality Assurance of Concrete.....	501
604.04	Equipment	510
604.05	Forms	516
604.06	Falsework	522
604.07	Camber	523
604.08	Reinforcement.....	524
604.09	Drainage and Weep Holes.....	527
604.10	Placing Pipes, Conduits, Anchors, Casting, and other Appurtenances	527
604.11	Handling, Measuring, and Batching Materials.....	527
604.12	Mixing Limitations.....	530
604.13	Mixing Concrete	530
604.14	Consistency of Concrete	532
604.15	Compressive Strength Tests of Concrete	532
604.16	Placing Concrete	534
604.17	Bonding Construction Joints	539
604.18	Depositing Concrete Under Water	539
604.19	Removal of Forms and Falsework	541
604.20	Defective Concrete.....	541
604.21	Finishing Concrete Surfaces.....	542
604.22	Finishing Slab Surfaces for Pavements or Bases	545
604.23	Curing Concrete	547
604.24	Protection of Concrete in Cold Weather	549
604.25	Painting Metals	549
604.26	Waterproofing and Waterstops.....	549
604.27	Rideability of New or Resurfaced Bridge Decks and Roadway Approaches	550
604.28	Loading and Opening to Traffic.....	552
604.29	Final Cleanup.....	553

604.30 Method of Measurement.....	553
604.31 Basis of Payment.....	556

DESCRIPTION

604.01 Description

This work consists of constructing all structures or parts of structures composed of Portland cement concrete, whether plain, reinforced, or a combination of both, on prepared foundations, at the locations shown on the Plans or as directed by the Engineer.

Use concrete consisting of a mixture or mixtures of Portland cement, aggregates, air-entraining agents, water, and chemical additives when approved, combined by the methods specified herein and in the proportions specified for the designated class of concrete.

Construct parts of a structure, or structures, which are to be constructed with materials other than Portland cement concrete and concrete reinforcement steel, as specified in the Section of these Specifications covering the particular type of construction.

MATERIALS

604.02 Materials

A. General

Provide materials as specified in:

Hydraulic cement.....	901.01
Fine Aggregate, (all Classes of concrete)	903.01
Coarse Aggregate.....	903.03
Lightweight Aggregate	903.19
Joint Filler, Preformed Type.....	905.01
Steel Bar Reinforcement.....	907.01
Welded Steel Wire Fabric.....	907.03
Structural Steel.....	908.01
Permanent Steel Bridge Deck Forms.....	908.03
Steel Castings	908.05
Gray Iron Castings.....	908.07

604.02

Bronze Bearing Plates, Plain.....	908.09
Bronze Bearing Plates, Self-Lubricating.....	908.10
Elastomeric Bearing Pads	908.12
Paints.....	910
Cement Concrete Curing Materials.....	913
Precast Concrete Box Culverts	914.08
Water.....	921.01
Chemical Admixtures and Additives	921.06
Air-Entraining Admixtures	921.06
Waterstops	921.08
Precast Prestressed Bridge Deck Panels	921.13
Applied Texture Finish	921.14
Fly Ash.....	921.15
Slag Cement.....	921.16

B. Fly Ash and Slag Cement

Do not use fly ash or slag cement of different classes or sources as partial replacement for Portland cement in concrete mixes.

C. Precast Box Sections

Unless otherwise shown on the Plans, for fill heights less than or equal to those shown in the standard box culvert drawings for cast-in-place concrete box sections, the Contractor may substitute precast reinforced box sections meeting **914.08** and the standard box culvert drawings for precast box culverts.

Submit shop drawings of the proposed precast box section and design calculations for approval before construction. As a minimum, the shop drawings shall include a plan and elevation view of the box culvert showing all precast sections, a typical precast box section showing dimensions and reinforcing, and notes and details required for construction. After obtaining the necessary approval from Structures Division, furnish the Structures Division a reproducible design file. The Department will pay the Contractor for the precast box based on the price bid for the quantity of the items in the cast-in-place structure it replaces. Manufacture the precast reinforced box sections in accordance with Departmental procedures.

For fill heights greater than those shown in the standard box culvert drawings for cast-in-place concrete box sections or other non-standard

designs, the Contractor may submit for consideration a value engineering change proposal in accordance with **104.11**.

604.03 Classification, Proportioning and Quality Assurance of Concrete

A. Classification and Proportioning

1. Classification and Design Parameters

- a. **Design and Production Parameters.** Proportion the concrete based on a pre-determined minimum cementitious content, and a water-cement ratio that does not exceed the maximum shown in Table 604.03-1. Below this limit, adjust the quantity of water to meet the slump requirements. The fine aggregate shall not exceed 44% by volume calculation of the total aggregate. For slip formed Class A concrete incorporated into parapets and median barriers, the maximum percent by volume of fine aggregate shall not exceed 46%.

Document mixture adjustments, for moisture corrections, on the daily report. Ensure that the adjusted mix complies with all the performance criteria specified in Table 604.03-1.

604.03

Table 604.03-1: Composition of Various Classes of Concrete

Class of Concrete	Min 28-Day Compressive Strength (psi)	Min Cement Content (pound per cubic yard)	Maximum Water/Cement Ratio (pound/pound)	Air Content % (Design \pm production tolerance)	Slump (inches)
A	3,000	564	0.45	6 \pm 2	3 \pm 1 ⁽¹⁾
D, DS ^(2,3)	4,000	620	0.40	7 ⁽³⁾	8 max ⁽⁴⁾
L ^(3,5)	4,000	620	0.40	7 ⁽³⁾	8 max ⁽⁴⁾
S (Seal)	3,000	682	0.47	6 \pm 2	6 \pm 2
X ⁽⁶⁾					

- ⁽¹⁾ For slip forming, the slump shall range from 0 to 3 inches.
- ⁽²⁾ Use Class D concrete in all bridge decks except box and slab type structures unless otherwise shown on the Plans. Use Class DS concrete in bridge decks with polish-resistant aggregate described in **903.03** and **903.24**.
- ⁽³⁾ Design Class D, Class DS, and Class L concrete at 7% air content. Acceptance range for pumping and other methods of placement is 4.5-7.5%. Sampling will be at the truck chute.
- ⁽⁴⁾ Water reducing admixtures are acceptable; however, do not exceed the maximum water/cement ratio in order to achieve the required slump.
- ⁽⁵⁾ The unit weight of air dried Class L concrete (lightweight concrete) shall not exceed 115 pounds per cubic foot as determined according to ASTM C567.
- ⁽⁶⁾ Plan specific requirements

Include chemical admixtures in the concrete mixture based on the ambient air temperature and expected weather conditions.

If using a Type A, F, or G water reducer, then the allowable slump shall be a maximum of 8 inches.

Admixtures to be incorporated into the concrete shall be compatible and incorporated into the concrete in accordance with the manufacturer's recommendations. Concrete mixtures utilizing multiple admixture manufacturers shall prove compatibility in accordance with the Departmental procedures.

Do not use fine aggregate manufactured from limestone or other polishing aggregates in concrete to be used as a riding surface in traffic lanes.

b. Self-Consolidating Concrete (SCC) Design and Production Parameters

Proportion the concrete based on a pre-determined minimum cementitious content, and a water-cement ratio that does not exceed the maximum shown in Table 604.03-2. The fine aggregate shall not exceed 50% by volume calculation of the total aggregate volume. Maximum size of coarse aggregate shall not exceed a No. 67 stone. The Contractor may elect to use SCC as an alternate/option in replacement of Class A concrete.

Document mixture adjustments, for moisture corrections, on the daily concrete report. Ensure that the adjusted mix complies with all the performance criteria specified in Table 604.03-2.

Table 604.03-2: Composition of Self-Consolidating Concrete

Class of Concrete	Min 28-Day Compressive Strength (psi)	Min Cement Content (pound per cubic yard)	Maximum Water/Cement Ratio (pound/pound)	Air Content % (Design \pm production tolerance)	Slump Flow (inches)
SCC ^(2,3,4,5)	3,000 ⁽¹⁾	564	0.45	6 \pm 2	26 \pm 5
SH-SCC ^(2,3,4,5,6)	4,500	620	0.45	6 \pm 2	26 \pm 5

⁽¹⁾ Or as shown on the Plans or approved shop drawings.

⁽²⁾ Acceptance range for the T50 test in accordance with ASTM C1611 shall be between 2-7 seconds.

⁽³⁾ Passing ability in accordance with ASTM C1621 shall be equal to or less than 2 inches for acceptance.

⁽⁴⁾ Visual Stability Index (VSI) shall not exceed 1 as per ASTM C1611 for acceptance.

⁽⁵⁾ Static segregation as measured by ASTM C1610 shall not exceed 20%.

⁽⁶⁾ Air Content may be reduced if placed under water or underground if approved by the Engineer.

Include chemical admixtures in the self-consolidating concrete mixture based on the ambient air temperature and expected weather conditions. Approved viscosity modifying admixtures (VMA) may be used as part of the chemical admixtures if they are shown in the approved mixture design.

Dosage rates for any admixtures incorporated into the concrete shall be stated during the mix design submittal process. All

604.03

admixtures shall be compatible and incorporated into the concrete in accordance with the manufacturer's recommendations. Concrete mixtures utilizing multiple admixture manufacturers shall prove compatibility in accordance with the Departmental procedures.

c. **Class X and High Early Strength**

When the Plans for structural or pavement repairs, or other type work, require high early strength concrete, a Class X design approval is required. The Contractor may use Type I, Type IL, or Type III cement. If Type I or Type IL cement is used, the minimum cement content shall be 714 pounds per cubic yard. If Type III cement is used, the minimum cement content shall be 620 pounds per cubic yard.

The Contractor may substitute high early strength concrete, meeting these requirements, for Class A concrete when approved in writing by the Engineer at no additional cost to the Department. When electing to use high early strength concrete, use the same source and gradation of fine and coarse aggregates as that specified for the concrete being substituted.

2. **Mix Design Submittal.** Submit, for approval, the proposed design in accordance with Departmental procedures at least 14 days prior to use. Develop the design using saturated surface dry aggregate weights. The design shall be prepared in an approved testing laboratory by a TDOT Certified Concrete Mix Design Technician or a Professional Engineer licensed by the State of Tennessee. The TDOT Certified Concrete Mix Design Technician or Professional Engineer licensed by the State of Tennessee shall certify that the information contained on the design submittal is correct and is the result of information gained from the actual trial batch. Build trial batches for design no more than 90 days before submitting the design. The trial batch shall produce an average compressive strength to indicate that the specified 28-day strength can be obtained in the field. Make all strength determinations using equipment meeting the requirements of, and in the manner prescribed by, AASHTO T 22. The design shall provide concrete of the strength specified in all applicable Special Provisions, Plans, and Specifications. The approved mix design will expire at the end of each calendar year or if it does not meet the minimum 28-day

strength requirements. Assume responsibility for all costs of concrete design, preparation, and submittal.

Submit a complete concrete mix design using the current template in accordance with Departmental procedures.

Self-consolidating concrete (Classes SCC, SH-SCC, and P-SCC) shall be verified prior to placement either at the ready mix, precast, or prestressed facility. The concrete producer shall perform a trial batch verification of the submitted design in the presence of Regional Materials and Tests. The trial batch will ensure that all batched quantities and target admixture dosage rates are acceptable and meet specification prior to design approval. All quantities and identified admixture target dosage rates shall meet the tolerances specified in **604.11**.

Instead of the above design submittal, an existing design may be submitted for approval provided the design has been approved by the Department within the current calendar year. The approval of this design submittal will not relieve the Contractor of the responsibility of providing concrete meeting the requirements of these Specifications. A temporary design may be submitted, on the Department's template, for approval once compressive strength test results meet or exceed the 28-day strength requirement (as determined by the Plans, Specifications, or Standard Drawings). The temporary design will be reissued for the calendar year once acceptable 28-day compressive strength data is submitted.

If proposing to use materials or admixtures from sources other than those shown on the approved design a new mix design approval shall be developed in accordance with Departmental procedures. Concrete shall not be placed until the new design is approved.

- 3. Partial Cement Replacement with Fly Ash or Slag Cement.** Do not use concrete with fly ash or slag cement as a partial cement replacement in concrete when high early strength is specified. Only use fly ash or slag cement as a partial cement replacement of Type I or Type II Portland cement.

When choosing to replace a portion of Type I or Type II cement with fly ash or slag cement, ensure that the following requirements will be met before producing any concrete:

604.03

1. Store fly ash or slag cement in silos separate from each other and separate from the hydraulic cement.
2. Add the fly ash or slag cement to the concrete using methods and equipment that are approved by the Engineer and capable of uniformly distributing the materials throughout the mix.
3. The fly ash or slag cement may be weighed cumulatively in the weigh hopper with the cement, provided the cement is added first. The temperature of the fly ash or the slag cement shall not exceed 160 °F at the time of introduction to the mix.

When designing Portland cement concrete with Type I or Type II cement modified by the addition of fly ash and/or slag cement, meet the maximum cement replacement rates (by weight) and minimum substitution ratios (by weight) specified in Table 604.03-3 for the applicable type of modifier.

Table 604.03-3: Type I or Type II Cement Modified by Fly Ash or Slag Cement

Modifier	Maximum Cement Replacement Rate % (by weight)	Minimum Modifier Cement Substitution Rates (by weight)
Slag Cement (Grade 100 or 120)	35.0	1:1
Class "F" Fly Ash	25.0	1:1
Class "C" Fly Ash	25.0	1:1

The Contractor may use ternary cementitious mixtures (mixtures with Portland cement, slag cement, and fly ash) for Class A, Class D, and Class DS concrete provided that the minimum Portland cement content is 50%. The maximum amount of fly ash substitution in a ternary cementitious mixture shall be 20%. The Department will allow Type IS cement with ternary cementitious mixtures. When using a Type IS cement, do not use any additional slag cement as a partial replacement for the hydraulic cement. The Department will allow a maximum of 20% fly ash as a partial hydraulic cement replacement in Class A concrete using only Type IS cement.

B. Quality Control and Acceptance of Concrete

Determine and measure the batch quantities of all ingredients (including all water and specified or approved admixtures) for all concrete produced for the Project, and to mix, deliver, and place the concrete so that the concrete meets the requirements of these Specifications. The Contractor may withhold some of the water from the mix at the facility provided the delivery ticket indicates the amount of water withheld. If a portion of the water is withheld at the facility, the Contractor may add additional water at the work site provided the design water-cementitious material ratio of the mix is not exceeded.

The minimum size of a batch shall be 2.5 cubic yards.

Provide qualified technicians to perform sampling, testing, and inspection for process control. A TDOT Certified Concrete Plant Quality Control Technician shall provide process control of the concrete at the facility. This technician shall be present at the facility during all batching operations for the Project and shall have the primary responsibility during production of performing process control. A TDOT Certified Concrete Field Testing Technician or ACI equivalent shall provide process control of the concrete at the placement site and shall be present during all concrete placement. For placement of concrete for minor structures as noted in **604.03.B**, a TDOT Certified Field Testing Technician or ACI equivalent is not required unless process controls or acceptance testing are performed in accordance with Departmental procedures.

Provide the necessary equipment to perform process control at the plant and at the placement site during times of concrete placement.

The concrete producer shall develop for the Engineer's approval and maintain at the plant a plant-specific Process Control Plan that shall apply to all Department contracts for the calendar year. Communicate all changes made to the Process Control Plan during the year to the Regional Materials Supervisor. Develop for the Engineer's approval a placement site Process Control Plan stating the procedures for sampling, testing, and inspection of the concrete. Maintain a record of all tests and inspections performed at the facility and placement site. Provide these documents to the Engineer upon completion of the Project for inclusion in the Project records. Keep records current and make them available to the Engineer for review at any time.

604.03

For process control, perform the following as a minimum:

1. Test to determine aggregate gradations (AASHTO T 27 with AASHTO T 11 when required). Conduct a combined belt gradation before work starts and at least daily to verify consistency if using a dynamic, multi-aggregate feed system.
2. Inspect the stockpiles to ensure they remain uncontaminated and unsegregated. Maintain a current aggregate quality report at the plant.
3. Calibrate the weighing systems, aggregate feed flow rate and weigh bridges, water meters, and admixture dispensing systems before starting production.
4. Ensure accurate weighing or flow rate of the aggregates and cement, the proper metering of water and admixtures, and the quality of water.
5. Ensure mixing equipment is in proper working condition and the proper mixing speeds and revolutions are controlled as required.
6. Adjust mix proportions due to actual moisture content of both coarse and fine aggregates, with moisture content determined according to AASHTO T 255. If using a dynamic aggregate weighing system, multi-aggregate proportioning adjustments are to be made by using an in-bin moisture sensor.
7. Conduct slump (AASHTO T 119) or slump flow (ASTM C1611) and air tests (AASHTO T 152).
8. Conduct yield tests (AASHTO T 121). If yield varies more than plus or minus 2% from that shown on the design, stop all batching operations until the problem has been identified and corrected or a new concrete design has been obtained.
9. Prepare quality control cylinders and early break cylinders for compression tests performed according AASHTO T 22.
10. Conduct tests for concrete and ambient air temperatures.

11. Provide a daily report to the Engineer that identifies the date, Contract and Project, Item number(s), batch weights, moisture corrections, admixtures, slump, air content, temperatures, and similar pertinent information.
12. A concrete delivery ticket shall accompany each load to the placement site. The ticket shall include as a minimum the following:
 - a. Date
 - b. Contract number
 - c. County
 - d. Class of concrete
 - e. Approved TDOT concrete mix design number
 - f. Number of cubic yards
 - g. Load number
 - h. Truck number
 - i. Maximum water allowed by design
 - j. Total water added at the plant
 - k. Maximum water allowed to be added on the project
 - l. Water-Cementitious material ratio
 - m. Number of revolutions at mixing speed at plant
 - n. Time loaded
 - o. Actual and target batch weights of each component including each aggregate, chemical admixture and mineral admixture used. Include the difference (%) between the actual batch weights and the target weights.
 - p. Signature of producer's TDOT Certified Concrete Plant Quality Control Technician

The concrete delivery ticket shall be delivered to the Engineer at the site of the Work. Loads that do not carry such information or do not arrive in satisfactory condition shall not be used.

Make, cure, and transport all early break cylinders in accordance with **604.15.C**, and deliver to the regional laboratory or other established satellite laboratories for testing. Make all early break cylinders for self-consolidating concrete according to ASTM C1758, and deliver to the regional laboratory or other established satellite laboratories for testing.

The Department or its representative will be responsible for performing all acceptance tests. A TDOT Concrete Field Testing Technician or ACI equivalent will sample and test in accordance with Departmental

604.04

procedures. The Department will also be responsible for properly curing and transporting all acceptance cylinders according to AASHTO T 23.

The Department will perform all independent assurance sampling and testing. All sampling and testing for acceptance and independent assurance will be at the frequencies established in Departmental procedures. The Department will determine the time and location for obtaining all acceptance and independent assurance samples.

Provide cylinder molds, a wheelbarrow, and a level site to perform testing. Provide a secure location for the initial curing of the concrete acceptance cylinders as specified in **722.09**.

In addition, the Department will require an approved concrete design for minor structures. The Contractor may use pre-approved, pre-packaged concrete mixtures listed in the Department's QPL 15 for these applications if the quantity does not exceed 2 cubic yards per day, in which case no design will be required. If the quantity exceeds 2 cubic yards, prior approval must be obtained from the Engineer prior to placement. All pre-packaged concrete mixtures are required to be mixed in a mechanical concrete mixing machine and in accordance with manufacturer's recommendations.

The following are considered minor structures. See each Section for additional details:

- 611** Manholes, catch basins, inlets, and pipe end walls
- 701** Cement concrete sidewalks, driveways and median pavement
- 702** Cement concrete curb, gutter, and combined curb and gutter
- 703** Cement concrete ditch paving
- 705** Guard rail
- 707** Fences
- 709** Rip-rap slope paving
- 713** Highway signing
- 714** Roadway and structure lighting

EQUIPMENT

604.04 Equipment

Obtain the Engineer's approval as to the design, capacity, and mechanical condition of equipment and tools used to handle materials and perform the

work. Have the equipment on the jobsite sufficiently ahead of the start of construction operations to be examined and approved by the Engineer. Use equipment and construction processes that have sufficient capacity to accomplish the maximum continuous concrete placement, as governed by the construction joints shown on the Plans or as directed by the Engineer.

A. Batching Plant, Multi-Aggregate Feed System, and Equipment

- 1. General.** The batching plant shall include bins, weighing hoppers, or belt feeds with weigh bridges and load cells, and scales. If using cement in bulk, include a bin, hopper, and separate scale for cement. Provide adequate means for cement cut off checks. Ensure that the weighing hoppers are properly sealed and vented to preclude dusting during operation. Provide adequate means to sample the cement stored in the bulk cement as specified in Departmental procedures.

All producers of concrete shall be on the Department's Producer List and be actively certified by the National Ready Mixed Concrete Association (NRMCA) Plant Certification Program.

- 2. Bins and Hoppers.** Provide bins with adequate separate compartments for fine aggregates, each size of coarse aggregate, and cement in the batching plant. Ensure that each compartment discharges efficiently and freely into the weighing hopper. Provide controls so that as the quantity desired in the weighing hopper is being approached, the material may be added slowly and shut off with precision. Provide a port or other opening for removing overloaded material from the hopper. Provide weighing hoppers that are constructed to eliminate accumulations of tare materials and to discharge fully without jarring the scales. Ensure that the partitions between compartments, both in bins and in hoppers, are sufficiently ample to prevent spilling under any working conditions.

For multi-aggregate feed systems, provide bins as noted with variable size openings and variable speed belts. Each bin must have a calibrated moisture sensor to adjust aggregate feed flow rates. Assure consistent, uninterrupted aggregate flow and consistent belt speeds once aggregate feed system is calibrated.

- 3. Scales.** Provide scales of the beam type, springless, dial type or load cell type to weigh aggregates, cement, and pozzolans. Scales shall be accurate within 0.5% throughout the range of use. Scale dial

604.04

faces or digital readouts are to be graduated to indicate loads of 0.1% or less of scale capacity.

When using beam type scales, provide an indicator such as a “tell-tale” dial to inform the operator that the required load in the weighing hopper is being approached. The “tell-tale” device on weighing beams shall clearly indicate the critical position. Poises shall be designed so that they cannot be easily removed from the beam and can be held firmly in place. Ensure that the weigh beams and “tell-tale” device are in full view of the operator while charging the hopper and that the operator has convenient access to all controls.

Inspect and check the scales as often as the Engineer deems necessary to assure their continued accuracy. Scales shall be calibrated by a certified scale company every 6 months.

For multi-aggregate feed systems, provide a dual idler weight bridge with load cells to accurately weigh the actual aggregate flow rate.

B. Mixers

- 1. General.** The Contractor may mix concrete at the site of construction or at a central point or wholly or in part in truck mixers. Each mixer shall have attached in a prominent place a manufacturer’s plate showing the capacity of the drum, in terms of mixing and agitating capacity, and the speed of rotation of the mixing drum or blades for both mixing and agitation.

Mixers shall be capable of combining the aggregates, cement, water and admixtures, when specified, into a thoroughly mixed and uniform mass within the specified mixing period. They shall have sufficient capacity to comply with minimum production requirements.

Equip mixers with an approved device for accurately measuring water within a range of error of not more than 1%. Provide an accurately calibrated and easily read indicator to show the amount of water used in each batch.

All mixers shall have blade wear indicators. Repair the pick-up and throw-over blades in the drum or drums once the blade wear reaches the blade wear indicator or when holes are worn through the blades.

Place the top of the blade wear indicator at 90% of the total height of the radial part of the blade. Retain at the jobsite or central plant a copy of the manufacturer's design showing dimensions and arrangements of blades. The blade wear indicator shall be a minimum of ¼ inch thick steel, 2 inches wide by 6 inches long.

2. **Mixers at Site of Construction.** In addition to the above requirements, mixers at the site of construction, unless otherwise stipulated, shall also meet **105.17** and shall be capable of discharging and distributing the mix without segregation.
3. **Truck Mixers and Truck Agitators.** Truck mixers shall be certified by the National Ready Mix Concrete Association (NRMCA) Delivery Vehicle Certification Program Option A or Option B. Each truck shall display the NRMCA certification card. Ensure that truck mixers used for mixing and hauling concrete, as well as the truck agitators used for hauling central-mixed concrete, meet all the applicable requirements specified in **604.04.B.1**. Truck mixers shall have a manufacturer's plate indicating the various uses for which the equipment is designed, the gross volume of the drum, and the minimum and maximum speed of rotation of the drum or blades for charging, mixing and agitating. Equip truck mixers with an approved device for recording the number of revolutions of the drum or blades.

Provide ample and satisfactory equipment for conveying concrete from the mixer to final position in the forms. Use closed chutes or pipes when concrete is to be dumped or dropped for a distance greater than 5 feet. Where steep slopes are required, equip the chutes with baffle boards, or use chutes in short lengths that will allow the direction of movement to be reversed.

Use vibrators of an approved type and operate them under load at the rate recommended by the manufacturer and approved by the Engineer.

When placing concrete by pumping, do not use aluminum conduit.

Do not pour any concrete for bridge decks or slabs above grade before verifying the availability and operability of all necessary equipment approved by the Engineer, including finishing machines, continuous water source or portable tanks, water distribution equipment, two work bridges, vibrators, sprayers, a 12-foot straightedge, and appropriate backup items.

604.04

Provide at every concrete deck pour a portable, cold fogger capable of changing humidity and cooling air above fresh concrete. The fogger shall be designed to provide a maximum VMD (volume mean diameter) of 15 microns, and a throw distance of 60 feet.

C. Volumetric Continuous Mixers

Produce concrete specified in Table 604.03-1 in accordance with **604.03**, in a volumetric continuous mixing plant provided that the manufacturer's equipment meets the tolerance requirements of Table 604.11-1. Use a volumetric continuous mixing plant that conforms to the following:

1. The unit shall be equipped with:
 - a. Calibrated proportioning devices for each ingredient added to the concrete mix and perform mixing by a continuous auger and/or paddles.
 - b. Equipped with proportioning controls that may be set and secured for different materials and mixes.
 - c. A working recording meter that is visible at all times and furnishes a ticket printout with the calibrated measurement of the mix being produced.
 - d. Separate bins and gate openings for each type of material, including a watertight storage bin for cement. Cover the aggregate bins with tarpaulins or by other approved methods when required.
2. The unit shall have a stamped plate from the Volumetric Mixer Manufacturers Bureau (VMMB) stating the equipment conforms to ASTM C685. The plate shall be attached in a prominent place and indicate the gross volume of the transportation unit.
3. The volumetric mixing plant shall be operated and calibrated by a Volumetric Mixer Operator certified by VMMB and holds a TDOT Concrete Field Testing Technician Certification or equivalent. Perform the calibration of gate settings according to the manufacturer's recommendations for the mix design to be used before starting work. The calibration procedure shall account for the moisture content of the aggregates. The yield shall be maintained within a tolerance of plus or minus 1% and verified, in

the presence of the Engineer, using a minimum of a 0.25 cubic yard container every 500 cubic yards or a minimum of once per week. Recalibrations shall be necessary when indicated by the yield checks, every 6 months, every 2,500 cubic yards, or at any time the Engineer deems necessary to ensure proper proportioning of the materials.

4. Tests for aggregate moisture contents and gradations shall be performed by a TDOT Concrete Plant Quality Control Technician or a TDOT Aggregate Certified Testing Technician.
5. Concrete mix design submittal shall be in accordance with **604.03.A.2.**

If the mixer fails to discharge a uniform mix at any time, production of concrete shall halt until any problems are corrected and approved by the Engineer.

A volumetric continuous mixing plant shall provide a concrete delivery ticket for each load. The ticket shall include as a minimum the following:

- a. Date
- b. Contract number
- c. County
- d. Class of concrete
- e. Approved TDOT concrete mix design number
- f. Number of cubic yards
- g. Truck number
- h. Maximum water allowed by design
- i. Total water added
- j. Water-cementitious materials ratio
- k. Time discharged
- l. Signature of producer's VMMB Certified Volumetric Mixer Operator

Provide the concrete delivery ticket to the Inspector at the site of the Work. Loads that do not carry such information or do not arrive in satisfactory condition shall not be used.

604.05

CONSTRUCTION REQUIREMENTS

604.05 Forms

A. Construction

Forms shall be mortar-tight and sufficiently rigid to prevent distortion due to the pressure of the concrete and other stresses incidental to the construction operations, including vibration. Construct and maintain forms to prevent the opening of joints due to shrinkage of the lumber.

Build the forms true to line and grade. Hold the forms in place with studs or uprights, and waling, which shall be sufficiently and substantially braced and tied.

Cut off and cap all forms and studding with not less than a 2 x 4-inch piece.

Chamfer all exposed edges with $\frac{3}{4}$ -inch material, unless otherwise specified. All chamfer strips shall be straight, of uniform width, and dressed.

Remove wood devices used to separate forms before placing concrete within 4 inches of such devices.

B. Form Lumber

Dress form lumber for all exposed concrete surfaces on at least one side and two edges, and construct to produce mortar-tight joints and smooth, even concrete surfaces.

The Contractor may use plywood forms, or forms face-lined with plywood, masonite, or other approved similar material, provided the plywood forms and form linings are substantial, of uniform thickness, and are mortar-tight when in position.

C. Metal Ties

Construct metal ties or anchorages within the forms to allow their removal to a depth of at least 1 inch from the face without damaging the concrete. If wire ties are permitted, cut the wires back at least $\frac{1}{4}$ inch

from the surface of the concrete, and ensure that the surface is left sound, smooth, even, and uniform in color.

D. Walls

Provide sufficient openings at intervals along the bottom of wall forms to allow thorough cleaning before concrete placement. Close such openings before placing concrete in the forms.

E. Surface Treatment

Before placing reinforcement, treat all forms to prevent the adherence of concrete. Treat forms, which are not provided with a special treatment, with an approved oil. Do not use any material that will adhere to or discolor the concrete.

F. Metal Forms

Ensure that metal forms comply with all requirements for forms, as regards design, mortar tightness, filleted corners, beveled projections, bracing, alignment, removal, reuse, and oiling. Construct forms using metal of sufficient thickness to ensure that the forms will remain true to shape. Countersink all bolt heads on the face forming the concrete surface. Use clamps, pins, or other connecting devices designed to hold the forms rigidly together and to allow removal without damaging the concrete. Do not use metal forms that do not present a smooth surface or do not line up properly. Keep metal forms free from rust, grease, or other foreign matter.

G. Permanent Steel Bridge Deck Forms

The Contractor may use permanent steel forms to construct bridge deck forms for concrete deck slabs of bridges. Do not use permanent steel bridge deck forms for the overhang portions of the slab.

The following criteria shall govern the design of permanent steel bridge deck forms:

1. Design the steel forms on the basis of dead load of form, reinforcement, and plastic concrete plus 50 pounds per square foot for construction loads. The unit working stress in the steel sheet shall not exceed 0.725 of the specified minimum yield

604.05

strength of the material furnished, or 36,000 pounds per square inch, whichever is less.

2. Deflection under the weight of the forms, the plastic concrete, and reinforcement shall not exceed $1/180$ of the form span or $1/2$ inch, whichever is less, but in no case shall this loading be less than 120 pounds per square foot total. The permissible form camber shall be based on the actual dead load condition. Do not use camber to compensate for deflection in excess of these limits. Laminations may be used to satisfy design criteria.
3. If the design span of the form sheets is less than the clear distance between top girder flanges minus 2 inches, include the design for the support system with the shop drawing submittal.
4. Compute physical design properties according to the American Iron and Steel Institute Specification for the Design of Cold Formed Steel Structural Members, latest published edition.
5. Provide a minimum concrete cover of 1 inch over all reinforcement, both transverse and longitudinal in the bottom mat.
6. Maintain the plan dimensions of both layers of primary deck reinforcement from the top surface of the concrete deck.
7. Do not consider permanent steel bridge deck form as lateral bracing for compression flanges of supporting structural members.
8. Do not use permanent steel bridge deck forms in panels where open longitudinal deck joints are located between stringers.
9. Submit the fabricator's shop and erection drawings to the Engineer of Structures for approval. These drawings shall indicate the grade of steel, the physical and section properties for all permanent steel bridge deck form sheets, and the method of attaching the forms and form supports to the main structural members. All drawings shall be stamped by a Professional Engineer licensed in the State of Tennessee. Review and approval of shop drawings by the Engineer of Structures will extend only to general details of forms and attachments. As this forming system is not an integral load-carrying member of the

completed slab, the Engineer of Structures will not review the design. The Contractor shall assume sole responsibility for ensuring the safe design of the metal decking system and its installation.

10. Do not rest form sheets directly on the top of the stringer or floor beam flanges. Securely fasten each flute of each sheet to form supports and to have a minimum bearing length of 1 inch at each end.
11. Place form supports in direct contact with the flange of either the stringers or floor beams. Make all attachments by bolts, clips, or other approved means. Do not weld form supports to main structural members.
12. If permanently exposed form metal contains areas of damaged galvanized coating, thoroughly clean and wire brush such areas, and apply two coats of zinc-oxide powder primer, Federal Specification TT-P-641d, Type II, no color added, to the satisfaction of the Engineer. It is not necessary to touch up minor heat discoloration in areas of welds.
13. Locate transverse construction joints at the bottom of a flute, and field drill $\frac{1}{4}$ -inch weep holes at not more than 12 inches on center along the line of the joint.
14. Ensure that the concrete is properly vibrated to avoid honeycomb and voids at construction joints, expansion joints, valleys, and ends of form sheets. Obtain the Engineer's approval of pouring sequences, procedures, and mixes. Do not use calcium chloride or other admixtures containing chloride salts in the concrete placed on permanent steel bridge deck forms.
15. After the deck concrete has been in place for a minimum period of 2 days, test the concrete for soundness and bonding of the forms by sounding with a hammer. If this procedure reveals areas of doubtful soundness, remove the forms from such areas for visual inspection after the pour has attained adequate strength.
16. Where sections of the forms are removed, the Engineer will not require the Contractor to replace the forms, but the Contractor

604.05

shall repair the adjacent metal forms and supports to present a neat appearance and to ensure their satisfactory retention. Remove or repair all unsatisfactory concrete as directed by the Engineer. Repair, at no cost to the Department, all damage to the concrete, reinforcing steel, or both caused by the inspection process.

17. As permanent steel deck forms are not a structural component of the bridge or deck system, the Contractor shall assume responsibility for determining the structural adequacy of the deck forms to support the wet concrete and specified construction load allowance. It is also the Contractor's responsibility to verify that the deck system meets all the requirements set forth in this section.
18. The Department will not pay for, and will instead consider incidental to the forming system, all overruns in deck concrete attributable to deflections or distortions in the deck form.

H. Special Forming Systems

The use of precast bridge deck panels eliminates the bottom reinforcing mat used in cast-in-place bridge decks; therefore, it is not possible to make all of the ties needed to maintain the rigidity of the reinforcing mat, deck form, and girder system. To enhance the stability of this system during construction, provide additional reinforcing, ties, temporary erection diaphragms, and permanent diaphragms as shown on the Plans and as specified below. Include the cost associated with these requirements in the unit price of items bid.

1. Tie the strands projecting from the ends of deck panels to the upper mat of reinforcing steel at 2-foot maximum spacing. Tie the upper mat to projecting shear reinforcement or stud shear connectors at maximum 2-foot spacing along the beam.
2. For precast, prestressed I-beams and bulb-tee beams, construct additional permanent diaphragms or additional temporary erection diaphragms as shown on the Plans between all girders at substructures and at intermediate points such that the spacing between diaphragms does not exceed that shown on the Plans.
3. For precast, prestressed box beams, construct additional permanent diaphragms or additional temporary erection

diaphragms as shown on the Plans between all girders at substructures and at intermediate points such that the spacing between diaphragms does not exceed that shown on the Plans.

4. For prestressed I-beams, bulb-tee beams, and box beams, form and pour the bottom 15 inches of diaphragms at bents as soon as possible after setting beams, using Class A concrete (3,000 psi). Pour the remaining portion of the diaphragms at substructures concurrently with the bridge deck. Provide temporary erection diaphragms as shown on the Plans at the ends of girders where the end diaphragms are to be poured concurrently with the bridge deck. The Contractor may also submit alternate temporary diaphragm details to the Engineer for approval.
5. For prestressed beams, do not pour any part of integral abutment backwalls prior to, or concurrently with, placement of the slab until at least half of the slab in the end span has been poured. Pour a minimum of the top 12 inches of the abutment backwall concurrently with the slab. Provide temporary erection diaphragms as shown on the Plans at the ends of girders. The Contractor may also submit alternate temporary diaphragm details to the Engineer for approval. Support the beams to prevent damage due to twisting or overturning during all phases of construction.
6. Place form supports for precast bridge deck panels in direct contact with the flange of the girders or beams. Make all attachments by bolts, clips, or other approved means. Do not weld form supports to the main structural members.

To request use of a special forming system not specifically authorized in this Specification, submit the design and calculations to the Engineer of Structures for review and approval.

I. Global Stability of Exterior Girders during Slab Overhang Pours

Ensure the stability of the exterior girder(s) against twisting, overturning, and web buckling during slab pouring operations. This may require supplemental bracing. When the width of the slab overhang exceeds the depth of the exterior girder, submit details and design calculations for the cantilever support (including deflections caused by the mechanical screed) to the Engineer for approval.

604.06

J. Other Considerations

If the deck slab thickness is increased more than 1-1/2 inches due to the use of permanent deck forms or precast deck panels, redesign the girders for the entire change in thickness, and bear all costs incidental to the increased depth of slab thickness and girder redesign, if required.

All bridge beams and girders shall be erected and the grade of the roadway established on the bridge before forming is started for the bridge deck, unless otherwise shown on the Plans or approved by the Engineer.

604.06 Falsework

Support falsework, used to support the forms and concrete for concrete structures, on sills resting on rigid foundations composed of solid rock, piles driven until the bearing capacity of each pile is sufficient to support the required loading, or earth borne footings as specified in this Subsection **604.06**.

The Department will only allow earth borne footings when, in the Engineer's opinion, the soil can adequately support the superimposed loads and the following conditions are met:

1. Only use spread footings on stable ground that is capable of supporting the superimposed load.
2. Grade and maintain the site to prevent ponding of water, or erosion of soil in the proximity of the spread footings.
3. Design and construct the falsework system to not exceed the bearing capacity of the soil, and in no case to exceed 3,000 pounds per square foot.
4. Design and construct the footings to carry the superimposed loads.
5. Construct all footings on a level plane.

The bearing value of piles will be calculated according to the formulas given in **606.14**.

Design and construct the falsework to support the required loading without distortion or settlement of the forms.

Place “tell-tales” to allow for observation of the amount of falsework settlement at locations designated by the Engineer.

The Engineer may require the Contractor to submit detailed falsework plans, together with a soils report, design calculations, and other information necessary for a thorough review. The Contractor is responsible for the design and construction of the falsework system and shall repair, or remove and replace, as directed and at no cost to the Department, all concrete, other material, or portions of the structure that are damaged or destroyed due to failure of the falsework.

Have all plans for falsework and formwork for cast-in-place structures over navigable waters or pedestrian or vehicular traffic stamped by a Professional Engineer licensed in the State of Tennessee.

Before placing any superstructure concrete, furnish to the Engineer a certification similar to the following:

CERTIFICATION

I hereby certify that the plans for falsework and formwork on (Structure Identification) have been prepared by me in accordance with accepted structural engineering practice. I further certify that said falsework has been erected in full compliance with said plans.

_____, P.E.

Tennessee License Number _____

604.07 Camber

Construct structures of any type or size to a permanent camber only when shown on the Plans. Provide sufficient camber in the falsework and forms for each span to allow for the tightening of joints in the forms and supporting falsework.

604.08

604.08 Reinforcement

A. General

All reinforcement shall consist of deformed steel bars meeting the requirements of ASTM A615 Grade 60, unless otherwise shown on the Plans or directed by the Engineer. Use standard CRSI hook details unless otherwise specified. Reinforcing steel designated with the suffix E shall be epoxy coated as specified in **907.01**. Deformed steel bars shall have a net area at all sections equivalent to that of plain round or square bars of the corresponding nominal size.

Steel wire fabric, meeting **907.03**, may be furnished in rolls or sheets.

B. Protection of Material

Store reinforcing steel above the ground surface on platforms, skids, or other supports located outside the scope of the active construction operations. Protect the reinforcing steel from physical damage, rust, and other surface deterioration. Remove all brush and weeds from the storage area immediately before storing reinforcing steel in the area.

C. Bending

Cold bend reinforcing steel, where indicated, to the forms and dimensions shown on the Plans. Unless otherwise indicated, ensure that all bends are in one plane. Uncoated bars of $\frac{3}{4}$ inch or less that have only hooks or a single bend may be bent in the field, provided satisfactory equipment for proper and accurate work is used, and provided the bending is accomplished true to form and dimensions without damage to the bars. Perform all other bending in the shop before shipment.

D. Substitution

The Contractor may substitute bars of different sizes from those shown on the Plans only with the Engineer's written permission. If substitution is allowed, comply with the following:

1. Do not reduce the total area of steel in any 1 foot in each direction.

2. For cast-in-place concrete, the clear distance between parallel bars in a layer shall not be less than 1.5 bar diameters, 1.5 times the maximum size of the coarse aggregate, or 1-1/2 inches.
3. Where positive or negative reinforcement is placed in two or more layers, place bars in the upper layers directly above those in the bottom layer with the clear distance between layers not less than 1 inch.
4. Clear distance limitation between bars shall also apply to the clear distance between a contact lap splice and adjacent splices or bars. Limit groups of parallel reinforcing bars bundled in contact to act as a unit to four in any one bundle. Limit bars larger than No. 11 to two in any one bundle in beams. Locate bundled bars within stirrups or ties. Individual bars in a bundle cut off within the span of a member shall terminate at different points with at least 40 bar diameters stagger. Where spacing limitations are based on bar diameter, treat a unit of bundled bars as a single bar of a diameter derived from the equivalent total area.
5. In walls and slabs, space the primary flexural reinforcement no farther apart than 1.5 times the wall or slab thickness, or 18 inches.

E. Splicing

Furnish all reinforcement in the full length shown on the Plans, unless otherwise approved in writing by the Engineer. The Contractor may splice temperature reinforcement at no additional cost to the Department. Splicing may occur once per bar in the end sections of box and slab type culverts that are on a skew other than 90 degrees and in box and slab type culverts that require no contraction joints due to their length. In end sections of 90 degree skewed structures and in interior sections of all box and slab type culverts, furnish temperature reinforcement in the full length required, with no splices. Do not make any splices, unless shown on the Plans or authorized by the Engineer of Structures.

Do not splice tension reinforcement at points of maximum stress. Rigidly clamp the members at all splices with at least two approved metal clips located approximately 3 inches from the ends of the bars and bolted around them, or secure with wire in a manner satisfactory to the Engineer.

604.08

Splice steel shapes only as shown on the Plans.

Splice steel fabric by overlapping the sheets by not less than 12 inches, matching at least three transverse members, and by securely wiring the overlapped sections in a manner satisfactory to the Engineer.

F. Placing and Fastening

Before placing reinforcing steel, thoroughly clean it of mill scale, rust, dirt, paint, oil, or other foreign substances or coating of any character that will reduce the bond. Once in-place, if reinforcement becomes dirty, rusty, or spattered with mortar that dries before concrete is placed around it, thoroughly clean such reinforcement, or the part affected, before covering it with concrete.

Accurately place and firmly hold in position all reinforcement as shown on the Plans or as directed by the Engineer. Fasten uncoated steel bars together with metal clips or wire at each intersection. Fasten coated steel bars with coated wire ties or coated clips. Where spacing is less than 1 foot in each direction, fasten alternate intersections. Securely space all reinforcing steel from the forms and between adjacent reinforcement with approved metal spacers, concrete blocks, or other approved devices or methods, except only use metal spacers in slabs of bridges and top slabs of box type structures. Where possible, arrange spacer devices so that their use cannot be detected in the completed structure. Mix concrete for spacer block construction in the same proportions as that used in the concrete mixture. Construct the blocks to be rectangular in shape with uniform surfaces and with no dimension greater than the depth required for proper spacing from the forms or between adjacent reinforcement. Do not use gravel, brick, or wooden blocks.

Before depositing concrete, ensure that all reinforcing steel in the section of the concrete pour is accurately and securely placed and the Engineer has approved the placement. Do not disturb the spacers during concrete placement.

All dimensions relating to the spacing or cover of reinforcing bars are to the centers of the bars or the clear distance respectively, unless otherwise indicated. Tolerances for placement shall be plus or minus ½ inches for spacing and minus 1/8 inch or plus 3/8 inch for cover.

604.09 Drainage and Weep Holes

Construct drainage openings and weep holes using materials in the manner and at the locations shown on the Plans or established by the Engineer. Place ports or vents for equalizing hydrostatic pressure, when required, as directed by the Engineer.

Where structures are to be backfilled, protect weep holes or openings by placing a wire basket, with dimensions of 1 foot x 1 foot x 1 foot and filled with coarse aggregate of size 7, 8, 57, 67, 68, or 78, immediately over or behind the holes or openings, as directed by the Engineer. After all finished grading is complete, clean weep holes of all dirt and debris, and ensure that they are free draining.

604.10 Placing Pipes, Conduits, Anchors, Casting, and other Appurtenances

As directed by the Engineer, place, during construction, all pipes, conduits, anchors, castings, bolts, plates, grillages, and other appurtenances that are necessary or desirable to be placed in the concrete of a structure, whether shown on the Plans or not. Unless otherwise specified, assume that such pipes and conduits will be delivered to the site of the structure by the Department or by other parties for whose use the pipes and conduits are intended.

The Department will not pay for placing such pipes, conduits, and other appurtenances; however, it will not make any deductions for the volume of concrete displaced by those items.

604.11 Handling, Measuring, and Batching Materials

Ensure that the batch plant site, layout, equipment, and provisions for transporting material will provide a continuous supply of material to the work. Build and maintain aggregate stockpiles as specified in **903.20**. A concrete delivery ticket shall accompany each load to the placement site and shall include, as a minimum, the information specified in **604.03.B.12**.

Handle and transport aggregates from stockpiles or other sources to the batching plant in such a manner as to maintain a uniform grading of the material. Do not use aggregates that have become segregated or mixed with earth or foreign material. Stockpile or bin all aggregates produced or handled by hydraulic methods at least 12 hours before being batched to allow for drainage. Consider rail shipment requiring more than 12 hours as adequate

604.11

binning only if the car bodies allow free drainage. If the aggregates contain high or non-uniform moisture content, the Engineer may require storage or stockpile periods in excess of 12 hours, or sprinkling of aggregate to achieve uniform moisture content.

Separately weigh the fine aggregate and each size of coarse aggregate into the hopper or hoppers in the respective amounts set by the Engineer.

Measure cement by weight, using separate scales and hoppers. The scales shall be equipped with a device to indicate positively the complete discharge of the batch of cement into the batch box or container.

The Contractor may use batching plants equipped to proportion aggregates and bulk cement by weight by means of automatic and interlocked proportioning devices of the approved type.

Individual materials shall be batched within the tolerances specified in Table 604.11-1.

Table 604.11-1: Concrete Batching Tolerances

Size	Tolerance
Cementitious Materials	-1% to +4%
Aggregates	± 1.5%

When mixing is at the site of construction, transport aggregates from the batching plant to the mixer in batch boxes, vehicle bodies, or other containers of adequate capacity and construction to properly carry the volume required. Ensure that partitions separating batches are adequate and effective to prevent spilling from one compartment to another while in transit or being dumped.

For bulk cement, use a suitable method of handling the cement, from weighing hopper to transporting container, for transportation to the mixer, with chute, boot, or other approved device, to prevent loss of cement and to provide positive assurance of the actual presence in each batch of the entire amount specified.

Transport bulk cement to the mixer in weatherproof compartments carrying the full amount of cement required for the batch. The Contractor may transport cement in original shipping packages on top of the aggregates, with each batch containing the proportion required by the job mix.

Deliver batches to the mixer separate and intact. Dump each batch into the mixer without loss of any material, and when more than one batch is carried on the truck, without spilling of material from one batch compartment to another.

Water shall be measured by either volume or weight. The accuracy of measuring the water shall be within a range of error of not more than 1%. Unless otherwise allowed, calibrated tanks for measuring water shall include an auxiliary tank from which the measuring tank shall be filled. The measuring tank shall be equipped with an outside tap and valve to check the setting unless other means are provided for readily and accurately determining the amount of water in the tank. The volume of the auxiliary tank shall be at least equal to that of the measuring tank.

Use chemical admixtures as specified in **604.03**, and add them to the mix using the manner and method recommended by the manufacturer, subject to the Engineer's approval. Add air-entraining agents to the mix using an approved procedure and an approved dispenser to ensure accurate proportioning of the agent. Measure all admixtures to an accuracy of plus or minus 3%.

When using lightweight aggregates, uniformly pre-saturate the aggregates and allow to drain. At time of use, ensure that the aggregates are in a saturated surface dry condition to minimize water absorption.

When placing concrete during hot weather, take appropriate measures to reduce the hazards of increased rate of cement hydration and high concrete temperatures.

The temperature of the concrete at point of discharge shall not exceed 90 °F. Reduce the temperature of the concrete using one or any combination of the following methods:

1. Sprinkle coarse aggregate stockpiles to distribute the water evenly and to prevent moisture variation within the stockpile.
2. Use crushed or chipped ice as a portion of the mixing water, or use water cooled by refrigeration or other means. If using ice, substitute it on a pound for pound basis for water and ensure that it is completely melted before the concrete is discharged from the mixer.
3. The Contractor may employ other means as approved by the Engineer.

604.12

Unless otherwise specified, to use additives or admixtures, submit a revised mix design for the Engineer's review and approval. Unless specifically provided in the Contract, the Department will consider the furnishing and use of approved additives or admixtures and the other precautions necessary to provide satisfactory concrete and concrete products to be incidental to the furnishing and placement of the concrete, and the Contractor shall bear all additional costs and risks.

Do not mix different types of cement, and do not use them alternately. Where it is necessary for the color of the concrete to be uniform, only those cements that will produce similar color in concrete may be used alternately.

604.12 Mixing Limitations

Stop mixing concrete in time to allow finishing to be completed in daylight hours, unless an adequate and approved artificial lighting system is provided and operated.

Unless authorized in writing by the Engineer, discontinue mixing and concreting operations when falling air temperature in the shade and away from artificial heat reaches 40 °F. Do not resume operations until rising air temperature in the shade and away from artificial heat reaches 35 °F.

When concreting at temperatures above 35 °F, heat or cool the aggregates or water as necessary before placing in the mixer so that the temperature of the resultant mixture will be no less than 50 °F and no more than 90 °F at the time of placement. If heating is required, use an apparatus that will heat the mass uniformly and that will prevent the possible occurrence of overheated areas that might damage the concrete. Do not use frozen aggregates in the concrete.

When concreting is authorized at temperatures of 35 °F or less, heat the water or the aggregates or both to no less than 70 °F and no more than 150 °F. Ensure that the temperature of the heated mixture is no less than 60 °F and no more than 100 °F at the time of placement on the road.

604.13 Mixing Concrete

The Contractor may mix concrete in a central-mix plant or in truck mixers. The mixer shall be of an approved type and capacity, and shall comply with the applicable requirements of **604.04.B**. Clean mixers at suitable intervals

to prevent buildup of hardened concrete that could affect the mixer's capacity and mixing ability.

Dump the batch into the drum so that a portion of the mixing water enters in advance of the cement and aggregates. Measure mixing time from the time all materials, except water, are in the drum. Ensure that the flow of water is uniform, and that all water is in the drum by the end of the first 15 seconds of the mixing period. Keep the throat of the drum free of accumulations that may restrict the flow of materials into the drum.

When mixed in a central mixing plant, ensure that the mixing time is no less than 60 seconds and no more than 90 seconds. Mixing time ends when the discharge chute opens. Include transfer time in multiple drum mixers in the mixing time. Remove the contents of an individual mixer before a succeeding batch is emptied therein.

Operate the mixer at the speed recommended by the manufacturer. Dispose of concrete mixed less than the specified time at no additional cost to the Department. Do not operate mixers for central mix plants at a capacity greater than the manufacturer's guaranteed mixing capacity.

Transport mixed concrete from the central mixing plant in truck mixers or truck agitators. Truck mixers and truck agitators used to transport concrete from a central mixing plant and truck mixers used to mix concrete in transit from a central batching plant shall meet all applicable requirements of **604.04.B.3**, and in addition, the mixing speed and agitating speed shall be those recommended by the manufacturer of the mixer, and the total revolutions at mixing speed shall be within the range of 70 to 100 for drum mixers. Operate truck mixers and truck agitators within the capacity recommended by the manufacturer.

When the concrete is mixed and transported in truck mixers; no more than 90 minutes shall elapse from when the water is added to the mix until the concrete is deposited in place at the site of the work. When the ambient air temperature exceeds 90 °F, no more than 60 minutes shall elapse for concrete placed in bridge decks.

Do not retemper concrete by adding water or by other means. However, the Contractor may withhold a portion of the mixing water or chemical admixtures from transit mixers and add at the work site if all requirements of the approved concrete mix design is met, provided the delivery ticket indicates the amount of water withheld. The total amount of water in the mix shall not exceed the maximum in the approved concrete mix design. To

604.14

achieve additional slump, use a water reducing admixture. If water, air entrainers, or chemical admixtures are added at the placement site, mix the concrete a minimum of 30 revolutions at mixing speed after making the additions. Do not use concrete that is not within the specified slump limits, air content limits, temperature limits, or time limits at the time of placement.

For the items of construction identified in **604.03.B**, the Contractor may perform concrete mixing using mobile volumetric measuring and mixing equipment as specified in **604.04**.

604.14 Consistency of Concrete

The slump of the concrete when measured according to AASHTO T 119 shall meet **604.03.A.1.a**. The slump flow of self-consolidating concrete when measured according to ASTM C1611 shall meet **604.03.A.1.b**.

604.15 Compressive Strength Tests of Concrete

A. General

The Engineer will determine concrete strength by tests performed during the progress of the work and will use these tests to determine the strength of the concrete for acceptance and pay purposes. The frequency of testing will be as specified in the sampling and testing schedule of Departmental procedures.

The frequency of testing for compressive strength to determine when forms may be removed, or when a structure may be put into service, shall be as requested by the Contractor or as deemed necessary by the Engineer in accordance with **604.15.C**.

B. Concrete Acceptance Cylinders

The Department will test the specimens for compressive strength according to AASHTO T 22. Provide the necessary concrete for making test specimens and adequate curing and storage facilities at no additional cost to the Department.

Concrete cylinders submitted for testing beyond 28 days shall comply with the design strength requirements specified in **604.03** or the Plans.

If the acceptance cylinders fail to meet the specified strengths, the Contractor must provide QC data from companion cylinders that meet or exceed the required strength, and TDOT Materials and Test shall perform a nondestructive test using a Swiss Hammer on the concrete to prove required strength is achieved, and then the Contractor may drill core samples from the hardened concrete as verification of concrete strength instead of using the concrete cylinders. Companion cylinders shall be made from the same sample as the acceptance cylinders. If these requirements are met, the Contractor may then elect to drill a maximum of three concrete core samples per set of cylinders from the hardened concrete. The Contractor shall obtain the cores in accordance with Departmental procedures. Obtaining the concrete cores and repairing the concrete core holes shall be at no cost to the Department.

The compressive strength of concrete cores submitted beyond 28-days from the placement date will be adjusted using the following equation:

$$A = [(4.1 + (0.85 * B))/B] * C$$

Where:

A = the Calculated Result of the Compressive Strength of the Concrete at 28 days (psi)

B = the Age of the Concrete (days)

C = the Compressive Strength Result of the Concrete Core (psi)

The Engineer will not accept concrete cylinders and cores submitted for testing beyond 56 days.

The average compressive strength of the two cores taken to represent the failing concrete cylinders will be considered to be the acceptance strength of record for the in-place concrete. In accordance with **604.31**, the Engineer will accept at a reduced pay concrete that meets the required strengths specified in **604.03** or the Plans for the respective class.

All concrete used shall undergo acceptance testing. The Department will determine the method to formally accept in-place concrete that is represented by acceptance cylinders that have been lost, damaged, or destroyed. These methods may include coring or non-destructive testing.

604.16

C. Early Break Cylinders

Make and cure all test specimens according to AASHTO T 23, and the applicable procedures therein defined for Field Cured Specimens, unless otherwise specified by the Engineer. The Department will test the specimens for compressive strength according to AASHTO T 22. Provide the necessary concrete for making test specimens at no additional charge to the Department.

Cylinders shall be representative of the concrete placed and shall be cured in the same manner and method as the placed concrete. Specimens shall be protected from the elements in the same manner as the formed work. If specimens are to be used for determining when a structure is capable of being put into service the specimens should be removed from the molds at the time of removal of the form work.

604.16 Placing Concrete

A. General

Do not place concrete until the Engineer has checked and approved forms and reinforcing steel. Ensure that the forms are clean of all debris and are kept wet immediately before concrete is placed. Obtain the Engineer's approval of the method and sequence of placing concrete. Unless otherwise allowed, place all concrete in daylight. Do not start placing concrete in any portion of a structure unless it can be entirely completed in daylight. When the placing of concrete is allowed during other than daylight hours, provide and operate an adequate and approved artificial lighting system. Plans for nighttime operations, including adequate lighting, shall be acceptable to the Engineer.

Use tools of an approved type to thoroughly work concrete during placing operations. The working shall be such as to force all coarse aggregate from the surface and to bring mortar against the forms to produce a smooth finish, substantially free from water and air pockets, or honeycomb.

If the forms show bulging or settlement while concrete is being placed, stop placing until a correction has been made.

Construct T-beam girders, slabs, arch rings, and all horizontal sections, except curbs and sidewalks, monolithically and continuously, unless otherwise allowed by the Engineer.

Construct curbs and sidewalks after the bridge deck is completed, unless otherwise shown on the Plans.

After initial set and before final set of the concrete, do not jar forms or place any strain on the ends of projecting reinforcement. Drive piles no closer than 20 feet to footings that are less than 7 days old and to foundations supporting concrete that is less than 7 days old.

Unless otherwise specified, before placing a bridge deck overlay of Class D, Class DS, or Class L concrete, machine scarify the surface to be covered to a minimum depth of 1 inch. In areas inaccessible to machine scarifying, and in areas of spalling where steel reinforcement is exposed, remove deteriorated concrete using hand tools or other methods approved by the Engineer. After scarifying, clean the deck of all deleterious material. Do not allow traffic on the scarified deck.

Take care to avoid contaminating the surface of the bridge deck after scarification. Remove all contaminants from the deck to the Engineer's satisfaction before placing the concrete overlay.

When placing concrete in bridge decks when the rate of moisture evaporation may be excessive as determined by the Engineer, comply with the following additional requirements.

1. Do not start any concrete deck pours until the mandatory Bridge Deck Construction Pre-pour Meeting is conducted and all pertinent considerations covered by the Pre-Pour Check List are resolved.
2. Protect the concrete to prevent rapid drying due to high temperature, low humidity, high winds, or combinations thereof. Do not place any concrete when the rate of moisture evaporation from the freshly placed concrete exceeds 0.2 pounds per square foot per hour as determined by Figure 604.16-1 below. Provide the Engineer appropriate measuring devices meeting industry standards to establish the temperature of the concrete and ambient air, relative humidity, and wind velocity adjacent to the concrete surface.

604.16




Figure 604.16-1: ACI nomograph for estimating rate of evaporation of surface moisture from concrete

3. If data collected during the 24 hours prior to the pour, or predictions from the National Weather Service indicate that the moisture evaporation rate of 0.2 pounds per square foot per hour may be exceeded, limit concrete placement to hours when the evaporation rate is less than 0.2 pounds per square foot per hour. An exception to this requirement would be if the

Contractor demonstrates to the Engineer's satisfaction before the pour that protection can be provided, or other actions taken, to maintain an acceptable moisture evaporation rate. Schedule placement of bridge deck concrete accordingly. Notwithstanding all precautions, if during concrete placement, the evaporation rate of 0.2 pounds per square foot per hour is exceeded, terminate the pour as directed by the Engineer.

In hot weather (generally 90°F and greater or as determined by the Engineer), apply a certified dry fog with a maximum volume mean diameter (VMD) of 15 microns with a throw distance of 60 feet above the concrete surface during placement and finishing operations. Furnish a certification to the Engineer verifying the VMD.

In addition, immediately before placing the concrete, cool the forms and reinforcing steel to 90 °F or less by using a fine spray of water, leaving no puddles or pockets of water. Sprinkle trucks or keep them in the shade when not being unloaded to help reduce the temperature of the concrete.

Use one of the four following methods at the discharge point when pumping concrete:

1. A metal loop consisting of four 90-degree elbows shall be placed in the line just before the rubber discharge hose.
2. A minimum of 10 feet of line lying horizontally just before the discharge point.
3. A rubber discharge hose configured into a "j" shape or loop, either of which prevents a loss in the pressure of the discharge line.
4. A rubber discharge hose, 10 to 12 feet in length, that reduces in diameter from 5 to 4 inches over its length.

B. Railings and Curbing

When constructing curb, take care in installing railing steel or anchoring devices.

Do not construct concrete railings on any structure until the falsework has been struck.

604.16

C. Chutes and Troughs

Place concrete to prevent segregation of materials and displacement of reinforcement.

Keep all chutes, troughs, and pipes clean and free from coatings of hardened concrete by thoroughly flushing with water after each run. Discharge the water used for flushing clear of the concrete already in place.

Take care to fill each part of the form by depositing the concrete as near final position as possible. Work the coarse aggregate back from the forms and around the reinforcement without displacing the bars.

D. Vibrating

Unless otherwise directed, compact the concrete with suitable mechanical vibrators operating within the concrete. When required, in addition to vibrating, also hand spade with suitable tools to ensure proper and adequate compaction.

Manipulate vibrators to work the concrete thoroughly around the reinforcement and embedded fixtures and into corners and angles of the forms. Do not use vibrators to cause concrete to flow or run into position. The vibration at any point shall be of sufficient duration to accomplish compaction without causing segregation.

Have at least one additional stand-by vibrating unit available for all individual pours in excess of 10 cubic yards.

E. Joints

Do not produce a featheredge at construction joints. Do not construct transverse or longitudinal joints through spans, unless otherwise specified.

Placement of bridge deck concrete between specified transverse construction joints shall be continuous unless otherwise approved in writing by the Engineer. If the Contractor fails to maintain a rate of placement of 20 feet per hour in the longitudinal direction as specified in **604.22**, or if, in the Engineer's judgment, placement is interrupted unduly because of failure or repositioning of equipment or any other cause, the Engineer may direct that all placement be stopped and a

transverse construction joint be formed in the deck as shown on the Plans or as directed by the Engineer.

Clean layers completing a day's work, or placed just before temporarily discontinuing operations, of all laitance or other objectionable material as soon as the surface has become sufficiently firm to retain its form.

To construct box culverts 6 feet or less in height, the Contractor may construct the side walls and top slab as a monolith. When using this method of construction, construct any necessary construction joints vertical and at right angles to the axis of the culvert.

To construct box culverts more than 6 feet in height, place the concrete in the walls and allow to set at least 4 hours before constructing the top slab. Leave appropriate keys in the side walls for anchoring the top slabs.

Unless otherwise shown on the Plans, transverse contraction joints in box culverts shall be plain butt joints and longitudinal reinforcement shall not extend across the joint. Space contraction joints at intervals of 30 to 40 feet. Predetermine the location of joints, and when practicable, place them at changes in the box section. Locate these joints parallel to the main reinforcing steel in the slab and not necessarily perpendicular to the axis of the box or slab type culverts.

604.17 Bonding Construction Joints

Where dowels, reinforcing bars, or other adequate ties are not shown on the Plans, form keys of a directed size by constructing projections above the concrete and monolithically with the concrete.

In resuming work, draw the forms tightly against the face of the concrete. Thoroughly clean the entire surface of the concrete to be bonded and roughen with a steel tool. Before proceeding with concreting, soak the surface with clean water.

604.18 Depositing Concrete Under Water

Do not deposit any concrete, except for cofferdam seals and drilled shafts, under water. Perform the work specified in **204.10** to prepare foundations before placing concrete foundation seals. It is necessary to inspect foundations for seal concrete. Provide an experienced diver equipped with a diving suit, two-way telephonic and other appurtenant equipment necessary for performing underwater inspections.

604.18

Place concrete for seals only in still water and ensure that the cofferdams or cribs meet the requirements specified in **204.09**. Regulate the method of depositing concrete to maintain the surface of the concrete as nearly horizontal as practicable throughout the operation. Place the concrete in a compact mass in its final position using a tremie, unless otherwise approved by the Engineer. Do not disturb the concrete after depositing, and do not expose it to the action of water before final setting.

Obtain cores for each seal footing. However, the Engineer will waive the inspection and coring of the seal footing if the seal footing is founded on piles and the encased piling projects above the seal footing and embeds into the structural footing a minimum length as shown on the Plans.

Obtain four cores, size N, as described by the Diamond Core Drill Association, or larger, representing 80% of the depth of the seal footing as directed by the Engineer unless otherwise noted on the Plans. Should the cores or other inspection indicate an inferior seal, perform corrective measures at no cost to the Department. Unless otherwise noted, consider the costs for coring the seal to be incidental to other work items.

Mix all concrete deposited under water in the proportions designated for Class S concrete. No additional compensation will be allowed for the additional cement. Regulate the consistency of concrete to prevent segregation of material during placement. Place underwater concrete continuously until the work is completed.

The tremie shall consist of a metal tube and suitable hopper of sufficient strength to withstand the stresses to which it is subjected. The tube shall have a minimum inside diameter of not less than 10 inches and shall be constructed in sections having flanged couplings fitted with gaskets. Support the tremie to allow free movement of the discharge end over the entire top surface of the work and to allow the tremie to be rapidly lowered when necessary to reduce or stop the flow of concrete. Equip the lower or discharge end of the tremie with a suitable valve or device that shall be tightly closed while the tremie is being charged and lowered into position, and that can be fully opened in the lower position. Keep the discharge end closed until the tube is filled with concrete to prevent water from entering. Induce concrete flow by raising the tremie, but always keep the discharge end in the deposited concrete.

After removal of cofferdam sheeting, provide an underwater diver and camera to perform a tactile inspection of the concrete seal exposed faces and provide a video to document the condition of the exposed seal footing surfaces.

604.19 Removal of Forms and Falsework

The Contractor may remove forms for ornamental work, railings, parapets, columns, and vertical surfaces that do not carry loads within 12 to 48 hours, unless otherwise directed by the Engineer. In cold, damp, or freezing weather, all vertical forms shall remain in place until the concrete has set sufficiently to withstand damage when the forms are removed. When removing forms, take care not to mar the concrete surface or to subject it to any undue pressure.

Remove or cut, as specified in **604.05.C**, projecting wires or other metal devices used for holding forms in place and that pass through the body of the concrete. Fill the holes or depressions thus made, and all other holes, depressions, and small voids that show upon the removal of the forms, with cement mortar mixed in the same proportions as that used in the body of the concrete being repaired.

The Contractor may release and remove falsework and supports under concrete structures when the following conditions are met:

1. Representative specimens of the concrete, made and cured in accordance with **604.15.C**, attain a compressive strength of 3,000 pounds per square inch.
2. The concrete has been in place a minimum of 7 days, not counting days of 24 hours each in which the temperature falls below 40 °F, or 21 calendar days, whichever occurs first.

After the above conditions have been met, the Contractor may proceed with placing further concrete pours or erecting precast or fabricated members. Allow other loadings as specified in **604.28**.

For continuous concrete girder or slab units, do not release or remove the falsework and supports from any span in the continuous unit until the concrete in all spans has been placed a sufficient length of time to meet all requirements for the removal of falsework and supports specified above.

604.20 Defective Concrete

Remove and replace defective concrete upon discovery. If the surface of the concrete is bulged, uneven or has honeycombing that cannot be repaired satisfactorily, remove and replace the entire section or unit. The extent of the removal shall be as determined by the Engineer.

604.21

Concrete having an acceptance compressive strength less than the minimum specified shall be removed, disposed of, and replaced by the Contractor at no cost to the Department, unless specifically authorized by the Engineer, in writing, to be included in the permanent work. Remove and dispose of nonconforming concrete in a manner that will not damage existing construction or other facilities and property.

The Engineer may allow concrete that fails to meet the strength specified to remain in the permanent construction, provided the durability is acceptable; but the Department will pay for this concrete at a reduced price. The Department will adjust the bid price for concrete that fails to meet the specified strength, but is considered structurally adequate for inclusion in the permanent construction, in accordance with **604.31**. The Department will base any adjustment in bid price due to low strength concrete on the acceptance compressive strength of record for the concrete, as determined in accordance with **604.15**.

604.21 Finishing Concrete Surfaces

Unless otherwise authorized, finish the surface of the concrete immediately after removing forms.

Give all concrete surfaces a Class I finish.

Give the following surfaces of all structures a Class II or Applied Texture Finish: roadway face and top of curbs, vertical outside face of curb overhang or sidewalks slab, bottom surface of slab overhang, bridge railings, barrier railings, all vertical surfaces of the superstructure of dual bridges exposed to view from either structure, and all surfaces of retaining walls, wing walls, and end walls that are visible from passing vehicles.

Give all surfaces of structures over a highway or another structure exposed to general view a Class II or Applied Texture Finish. Such surfaces, in addition to those specified above, will usually include all parapets, copings, columns, piers, bents, sides and ends of caps, the outside of all fascia beams, the ends of arch rings, outer surfaces of spandrel walls, the exposed surfaces of wing walls, and the faces of abutments. The Plans will show if additional surfaces, other than those already indicated, are to receive a Class II or Applied Texture Finish. If an Applied Texture Finish is used, the color of the finish shall be similar to Mountain Gray, Federal Specification No. 36440, Federal Color Standard 595b, except that the inside face and the top of the parapet or rail shall be White, Federal Specification No. 37886. Submit a color sample to the Engineer for approval.

Do not combine the Class II and Applied Texture Finish. If the Plans show an Applied Texture Finish, do not use a Class II finish.

The Plans may show other finish classes for designated surfaces.

A. Class I, Ordinary Surface Finish

Begin finishing as soon as forms are removed. Remove all fins and irregular projections from surfaces that are to be exposed or waterproofed. On all surfaces, ensure that the cavities produced by form ties and all other holes, honeycomb spots, broken corners or edges, and other defects, are thoroughly cleaned, saturated with water, and carefully pointed and trued with a mortar of cement and fine aggregate mixed in the proportions used in the class of the concrete being finished. Mortar used in pointing shall not be more than 30 minutes old. Leave all construction and expansion joints in the completed work carefully tooled and free of all mortar and concrete. Leave the joint filler exposed for its full length with clean and true edges.

On all surfaces that cannot be repaired to the Engineer's satisfaction, rub as specified for a Class II finish.

B. Class II, Rubbed Finish

Complete a Class I finish. Saturate the concrete with water. Ensure that sufficient time has elapsed before the wetting down to allow the mortar used in the pointing to thoroughly set. Rub the surfaces to be finished with a wetted wooden block or a medium coarse carborundum stone. Do not use the carborundum stone until the concrete has hardened to the state where the sand will grind, rather than ravel or roll. Continue rubbing until all form marks, projections, and irregularities have been removed, all voids filled, and a uniform surface has been obtained. Leave the paste produced by this rubbing in place. The Engineer will not allow a brush finish or painting with grout.

After all concrete above the surface being finished has been cast, obtain the final finish by rubbing with a fine carborundum stone and water. Continue this rubbing until the entire surface is of a smooth texture and uniform color.

After the final rubbing is completed and the surface has dried, rub it with burlap to remove loose powder and ensure it is free from all unsound patches, paste, powder, and objectionable marks.

604.21

C. Class III, Float Finish

For unformed surfaces, except slab surfaces for pavements or bases, achieve a Class III finish by placing an excess of material in the form and removing or striking off the excess with a template, forcing the coarse aggregate below the mortar surface. Avoid creating concave surfaces. After the concrete has been struck off, thoroughly work the surface and float with a suitable floating tool of wood, canvas, or cork. Before the finish has set, remove the surface cement film with a fine brush to produce a fine-grained, smooth but sanded texture.

D. Applied Texture Finish

To prepare the surface for a textured finish, first provide a Class 1 Ordinary Surface Finish. Allow the concrete to set for a minimum of 28 days to allow for ample cure time and weathering of curing compounds before applying the textured finish. Pressure wash all surfaces just before application. Remove from surfaces to be coated all efflorescence, flaking, coating, rust, dirt, oil, and other foreign substances. Apply coatings only to surfaces that are free of surface moisture as determined by sight and touch. Shield and mask surfaces that are not to receive a Coated Finish. Vee out cracks over 1/8-inch wide and fill with an approved product from the Department's QPL. Obtain the Engineer's approval of the surface preparation immediately before starting the work.

Apply the textured finish in the number of coats as recommended by the manufacturer and as posted on the Department's QPL to achieve a total application rate of 1 gallon per 45 square feet. If using a two-coat system, apply a base coat similar in color to Mountain Gray, Federal Specification No. 36440, when the final coat is White, Federal Specification No. 37886. When the final coat is similar in color to Mountain Gray, Federal Specification No. 36440, use a base coat of White, Federal Specification No. 37886. Provide advance notice to the Engineer of the date(s) and time(s) the texture coating is to be applied.

Apply the textured finish with rollers or brushes to provide a consistent and uniform coverage. As an alternative, the Contractor may spray the textured finish if using a containment system meeting the Engineer's approval. Regardless of the method of application, prevent drippings and overspray from the texturing process or otherwise contain in a manner that will not contaminate the environment.

Submit to the Engineer certification of the following:

1. Brand name,
2. Production batch or lot number,
3. Qualified Products List Evaluation Number,
4. Manufacturers recommended rate of application,
5. Safety Data Sheet,
6. Materials Data Sheet, and
7. Shipping date.

Submit a color sample to the Engineer for approval.

604.22 Finishing Slab Surfaces for Pavements or Bases

Use approved mechanical finishing machines to finish bridge floors or top slabs of structures serving as finished pavements or bases. In extreme cases where mechanical finishing machines cannot be used, such as narrow widths due to phase construction, the Engineer may allow hand finishing or other methods.

Mechanical finishing machines shall be approved power driven machines, traveling on rails adjusted to conform to the profile of the roadway. Equip the machines with oscillating or vibrating transverse or longitudinal screeds that may be adjusted to conform to the profile or the required cross-section of the roadway. The screed shall have sufficient strength to retain their shape after adjustment. Pass over each area of the bridge floor with the finishing machine as many times as necessary to obtain the required profile and cross-section.

When using longitudinal screeds, comply with the following restrictions:

1. The span length of the slab section to be poured shall be 70 feet or less.
2. Place sufficient concrete ahead of the strike-off to fully load the beam or girder prior to strike-off.
3. Control the rate of placement to ensure that the concrete will not take its initial set before the entire placement is complete.
4. The slab to be poured shall be in a tangent section.

604.22

5. Assume responsibility for damage to the structure caused by using this method. Do not change the sequence of construction, as shown on the Plans, without the Engineer's written approval.

When using the hand method, strike off the bridge floors or slabs with a screed that is parallel to the centerline of the roadway resting on bulkheads or screed strips cut or set to the required cross-section of the roadway. This screed shall have sufficient strength to retain its shape and a cutting edge that may be adjusted to conform to the profile of the roadway. Screeds shall be of sufficient length to finish the full length of spans 40 feet or less in length. Finish spans over 40 feet in length in two or more sections, but no section shall be less than 20 feet in length. Set screed strips or headers to the specified grades, and check and adjust as necessary before the final screeding operation. Work the screed back and forth over the surface until the proper profile and cross-section is obtained.

Maintain a minimum placement rate of 20 feet of deck per hour when placing concrete in a longitudinal direction.

For bases, finish the surface by grooving lightly with a wire broom at an angle of 60 degrees with the centerline. Begin all strokes at the center and end at the edge.

Finish and texture the surface of bridge approach slabs, bridge decks, and top slabs of other structures serving as roadway pavements by Method 3 below, except Method 1 or 2 may be used where shown on the Plans and/or where the design speed of the roadway on which the structure is located is less than 40 miles per hour.

1. Finish the surface by dragging a seamless strip of damp burlap over the full width of the surface. Use a burlap drag consisting of sufficient layers of burlap to slightly groove the surface and move it forward with a minimum bow of the lead edge. Keep the drag damp, clean, and free of particles of hardened concrete. When allowed by the Engineer, the Contractor may use a light broom or brush herringbone finish that leaves a texture similar to that obtained by the burlap drag.
2. Finish the surface with a burlap drag as noted in Method 1 above. Then, at an appropriate time during the stiffening of the concrete, form transverse grooves in the surface so that in the hardened concrete the grooves will be between 0.09 and 0.13 inches in width; between 0.12 and 0.19 inches in depth; and spaced at random

intervals between 0.3 and 1.0 inches. The grooves shall be relatively smooth and uniform. Form the grooves without tearing the surface or bringing pieces of coarse aggregate to the surface, and to drain transversely.

3. Finish the surface with a burlap drag as noted in Method 1 above. Then, after allowing the concrete to cure as specified in **604.23** and to harden sufficiently to support the necessary equipment, groove the surface transversely using a mechanical saw device that will leave grooves 0.125 inches wide, 0.125 inches deep, and randomly spaced from 0.75 to 1.125 inches apart center to center. Perform any corrective grinding for smoothness before transverse grinding, otherwise it will be necessary to re-groove.

Establish positive means for removing grooving residue as specified in **604.27.C**.

Terminate the grooves formed by Method 2 or 3 approximately 12 inches from curbs, parapets, barrier walls, and other vertical walls.

Include all costs for finishing and texturing in the unit price bid for the concrete being placed. As soon as the surface has set sufficiently to withstand damage when walking on it, and not later than the morning following the placing of the concrete, apply a 12-foot straightedge and mark all variations exceeding 1/8 inch. Correct and seal such variations in the same manner as specified in **604.27.C**.

604.23 Curing Concrete

Cure all concrete surfaces as specified below, except those surfaces protected by forms that remain in place 7 days or longer as specified in **604.19**. Use curing materials that meet the requirements of **913**. Begin curing on unformed surfaces immediately after the water sheen disappears and the surface finish is applied. On formed surfaces, begin curing immediately after removing forms.

When the temperature is expected to fall below 35 °F, protect the concrete as specified in **604.24**.

Cure bridge decks and the top slabs of other structures located above the roadway subgrade elevation by using both the Membrane-Forming Compound Method and the Water Method. Use new burlap for each pour, except burlap may be reused on the same project if it is undamaged and

604.23

deemed acceptable by the Engineer. The Contractor may cure all other concrete surfaces by either of the following methods.

A. Membrane-Forming Compound Method

Give all surfaces the required surface finish and keep it moist before applying the curing compound. Apply the burlap drag finish on bridge decks, and on the top slabs of other structures that also serve as the roadway surface, as soon as practicable after screeding the surface, and then immediately apply the membrane curing compound.

Apply the curing compound at the manufacturer's recommended rate. Apply the curing compound under pressure. Only use hand sprays in areas that are inaccessible to pressure equipment. At the time of application of the curing compound, the concrete shall be thoroughly moist but without surface water.

At the time of use, ensure that the compound is in a thoroughly mixed condition with the pigment or dye uniformly dispersed throughout the vehicle. If the application of the compound results in a streaked or blotchy appearance, take corrective action at once to obtain a well-dispersed mixture of uniform appearance. For concrete surfaces that are not protected by burlap curing covers, use other means to protect against marring for a period of 5 days from the date of application. Immediately replace membrane coating marred within the 5-day period on an otherwise unprotected surface.

B. Water Method

As soon as possible after applying curing compound to bridge decks and to other top slabs located above subgrade elevation, apply either a combination of damp burlap and white polyethylene sheeting or a white, co-polymer coated, absorbent, non-woven synthetic fabric, from a work bridge, taking care not to mar the surface of the deck. The sheeting material shall meet the performance requirements of ASTM C171. Immediately cover all other concrete slabs with materials suitable for use with the water cure. After placing the protective cover, immediately apply a mist spray and keep the cover thoroughly wet with a continuously fed soaker hose system for 120 hours.

Keep all surfaces other than slabs protected from the sun and wet for a period of at least 72 hours from the beginning of the initial curing period. For finishing, the Contractor may temporarily remove the covering from

curbs, walls, handrails and other surfaces requiring a Class II finish, but shall restore the covering as soon as possible.

604.24 Protection of Concrete in Cold Weather

If, after the concrete has been placed, the ambient temperature is expected to drop below 35 °F, provide insulation blankets, sufficient canvas, and framework, or other types of housing, to enclose and protect the structure in such a way that the air surrounding the fresh concrete can be maintained at a temperature of at least 45 °F and the surface temperature of the concrete will not exceed 80 °F. Maintain the above conditions for a period of 120 hours after the concrete is placed. Furnish a maximum-minimum thermometer to the Engineer for temperature documentation.

604.25 Painting Metals

Paint, as specified in **603**, all exposed surfaces of all metals that are not lubricated or that do not have a bituminous coating, unless otherwise indicated or directed.

Clean the surface of metals having a bituminous coating and treat with two coats of bitumen to present a smooth finished surface that is tough and tenacious when cold but not tacky when warm. The bituminous coating shall have no tendency to scale off.

Exposed surfaces, as used above, shall include the inside of cast iron drainpipes or weep holes.

604.26 Waterproofing and Waterstops

Perform waterproofing, where shown on the Plans or directed by the Engineer, as specified in **605**.

Install waterstops, as specified, as shown on the Plans and in conformity with the requirements of these Specifications.

Install waterstops in continuous strips without splices, except that splices will be allowed at changes in direction when necessary to avoid buckling or distortion of the web or flange. Perform all splices of waterstops in accordance with the manufacturer's recommendations. For polyvinyl chloride waterstops, the heat used shall be sufficient to melt but not char the plastic.

604.27

Ensure that the waterstops are supported during the progress of work and are properly embedded in the concrete. Work the concrete in the vicinity of the joints to ensure maximum density and imperviousness. Use forms that can be removed without damaging the waterstops. Provide suitable guards to protect exposed projecting edges and ends of partially embedded waterstops from mechanical damage.

604.27 Rideability of New or Resurfaced Bridge Decks and Roadway Approaches

A. General

The rideability requirements shall apply to all new or resurfaced bridge decks and roadway approaches. Bridge decks resurfaced with bituminous material shall meet the respective rideability requirements for the bituminous material as specified in **407.18** or in the contract.

Set all asphalt paving in each 150-foot approach area to grade by using string lines. Set all concrete paving in each 150-foot approach area to grade by using string lines or side forms set to grade. Assume responsibility for the final adjustment of the string lines in the approach area.

Fabricate and install all expansion joints in accordance with **623**, Standard Drawings, and approved shop drawings. Form the recess for the expansion device to the proper dimensions to allow placement of the expansion device.

B. Rideability Testing

After the bridge deck, approach slabs, and roadway pavement tie-ins are completed, the Department will conduct rideability tests using a roadway profiler to provide an International Roughness Index (IRI) for each wheel path and Mean IRI (MRI) for overall roughness. A lot is considered each lane for the length of the bridge and 150 feet before and 150 feet after each end of the bridge, unless a shorter distance is specified by the Engineer or shown on the Plans. Each lot shall be tested.

Schedule rideability testing at least seven days prior to need. Clean and clear the area to be tested of all obstructions. Wheel paths will be located 3 feet each side of the centerline of each traffic lane.

To determine pavement rideability, the Department will evaluate the pavement using Mean IRI for the lot and IRI for individual continuous 25-foot sections for localized roughness in each wheel path. Mean IRI shall be the average of each wheel path. IRI data shall be calculated per ASTM E1926. Each lot shall have a maximum Mean IRI value of 130 inches per mile.

For bridges with a posted speed limit of 45 mph or greater no individual continuous 25-foot section shall exceed an IRI of 190 inches per mile in either wheel path, except sections which include an expansion joint.

For bridges with a posted speed limit of 40 mph or less, no individual continuous 25-foot section shall exceed an IRI of 250 inches per mile in either wheel path, except sections which include an expansion joint.

For sections with an expansion joint, no individual continuous 25-foot section shall exceed an IRI of 350 inches per mile in either wheel path.

C. Pay Factor and Required Corrective Action

Perform corrective action to reduce the Mean IRI for each lot or IRI for all individual continuous 25-foot section that fails to meet the requirements specified. Perform corrective action to reduce the Mean IRI for each lot to 130 inches per mile or less. No more than 0.25 inches (two grinding passes) of material shall be removed by corrective diamond grinding without approval of the Engineer.

The individual continuous 25-foot sections with localized roughness exceeding the limits specified for each wheel path must be corrected regardless of Mean IRI results.

A grinding strategy plan is required before any corrective action begins. Submit a copy of the grinding plan to the Engineer at least 5 days prior to starting any work. Perform corrective action, including grinding of bridge decks and approach slabs, removal of pavement tie-ins, resurfacing, and application of sealants, at no additional cost to the Department.

Grinding shall be performed by a power driven, self-propelled grinding machine that is specifically designed to smooth and texture Portland cement concrete surface using diamond blades. The effective base of the machine shall not be less than 12 feet. The equipment shall be of a size that will cut or plane at least 3 feet wide. The equipment shall be capable

604.28

of grinding the surface without causing spalls at cracks, joints, or other locations.

Do not use asphalt milling or cold planing machines to perform grinding work on Portland cement concrete bridge deck surfaces. Do not grind Portland cement concrete bridge deck surface within 2.25 inches of reinforcing steel.

Establish a positive means for removing grinding and grooving residue. Remove solid residue from pavement surface during the grinding or grooving operations. Do not allow residue to flow across lanes used by public traffic, into gutters, or drainage facilities. Dispose of residue in a manner that will prevent residue, whether in solid or slurry form, from reaching any waterway in a concentrated state.

Perform all corrective action on bridge decks before final surface grooving. Seal all surfaces that are ground with an approved penetrating sealant listed on the QPL.

The Department will retest corrected surfaces with the roadway profiler to ensure that the IRI does not exceed the maximum requirements.

After corrective action is complete, lots that do not meet an MRI of 130 inches per mile or less, a pay adjustment will be assessed by using the following equation.

$$\text{Pay Adjustment} = \frac{130 - \text{MRI}}{130} \times \$9,000$$

604.28 Loading and Opening to Traffic

Do not allow any traffic, heavy equipment, storage of materials, or other loading on a structure or any part thereof, except as noted in **604.19**, until all forms and falsework have been removed and 10 calendar days have elapsed thereafter, unless otherwise noted in the Plans.

Construction loads on bridges applied anytime subsequent to the placement of girders shall not exceed 50 pounds per square foot based on a uniform distribution of load. Reconcile loads characterized as non-uniform in nature either by analysis equating the load to an effective uniform load or by the use of timbers or other means approved by Engineer to distribute construction loads. The length of load distribution may be taken as the bridge beam spacing (or slab span between walls for concrete culverts) occurring at the

location of load application. Submit all analysis and supplementary support details required to ensure proper construction load distribution. If concrete is mounded ahead of the screed machine during placement of the deck, consider that portion extending above the screed elevation as a construction load. Place construction loads as optimally as reasonable to minimize loads on the structure. When the area occupied by construction loads in any structure span exceeds 25% of the area of that span, submit a diagram detailing the location, character, sequence, and weight of all construction loads applied to the structure to the Division of Structures for approval. Submit this diagram at least 30 days in advance of the planned operation.

604.29 Final Cleanup

Perform final cleanup as specified in **104.10**.

COMPENSATION

604.30 Method of Measurement

A. Concrete for Structures

The Department will measure concrete for concrete structures, unless otherwise specified, by the cubic yard for payment purposes. The volume will be computed from the dimensions shown on the Plans or directed in writing by the Engineer, except for the concrete fillet above fabricated bridge girders. This fillet, as shown on the Plans, is intended to allow for adjustment due to the imprecise methods of predicting camber development of structural members. At the time of construction, the fillet used to compensate for grade changes due to camber development, super-elevation, or other factors beyond the Contractor's control will be field measured for payment by profiling of the bridge members.

The Department will make no allowances for:

1. Furnishing the material and constructing drainage openings and weep holes as shown on the Plans or as directed by the Engineer, provided such openings are 6 inches in diameter or less, except that no deduction will be made for such openings in the computation of concrete quantities. Allowance will be made for other openings as indicated.

604.30

2. Additional cement used in depositing concrete under water; for use of chemical admixtures, for fillers, sealers, and tar paper used in expansion joints; for dowels or other materials used in bonding construction joints; for waterstops; and for painting metals.
3. Concrete placed below the foundation elevation shown on the Plans, unless directed by the Engineer. When approved by the Engineer, the Department will measure concrete used for leveling structure footings by the cubic yard using the average end area method or other approved methods.

Unless otherwise indicated, the Department will deduct the volume of concrete displaced by pile heads.

The Department will make no additional compensation for high early strength concrete substituted by the Contractor for other classes of concrete. The unit price for the class of concrete for which the substitution was made shall be full compensation for the concrete.

The Department will measure by the square yard any hydro-blasting of the bridge deck performed before placing a bridge deck overlay.

B. Structure Excavation and Foundation Preparation

The Department will measure and pay for Structure Excavation, Foundation Preparation and Backfill in accordance with **204**, except when the Plans indicate that no payment will be made for excavation and foundation preparation, then the Department will not measure excavation and will consider it incidental to other items of construction.

When, under **204.10.A**, the Contractor places a foundation seal that is not included in the Plans, the Department will not measure and pay for furnishing the concrete and placing the seal, unless the following requirements and conditions are complied with before placing the foundation seal:

1. Cofferdams in which seals are requested shall have been constructed in strict compliance with **204.09**.
2. After investigation, the Engineer determines that conditions have been encountered that make it impracticable to de-water the foundation before placing the footing.

3. The Contractor requests and receives approval for the construction of the seal in writing.
4. The Department and the Contractor execute a Change Order to establish a unit price per cubic yard and the method of measurement for the concrete to be used in the seal.

When the above conditions have been met, the Department will measure and pay for the Concrete Foundation Seal in accordance with the terms of the Change Order.

C. Reinforcement

The Department will measure and pay for steel bar reinforcement used in concrete structures, unless otherwise specified, by the pound, as computed from the dimensions shown on the Plans, or directed in writing by the Engineer, and the weights specified in Tables 604.30-1 and 604.30-2.

Table 604.30-1: Steel Bar Reinforcement

Bar Designation No.	Weight (pounds per foot)
3	0.376
4	0.668
5	1.043
6	1.502
7	2.044
8	2.670
9	3.400
10	4.303
11	5.313

604.31

Table 604.30-2: Large Bar Sizes

Bar Designation No.	Weight (pounds per foot)
14S	7.650
18S	13.600

The bar numbers designate the number of 1/8 of an inch increments in the nominal diameter of the bars. The nominal diameter of a deformed bar is equivalent to the diameter of a plain bar having the same weight per foot as the deformed bar.

The Department will make no allowance for any device for splicing, clamping, tying, or positioning the reinforcement.

D. Applied Texture Finish

The Department will measure Applied Texture Finish by the square yard of concrete surface treated, as determined in accordance with **109**.

604.31 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Class A Concrete (Description)	Cubic Yard
Class D Concrete (Description)	Cubic Yard
Class DS Concrete (Description)	Cubic Yard
Class L Concrete (Description)	Cubic Yard
Class S Concrete (Description)	Cubic Yard
Steel Bar Reinforcement	Pound
Epoxy Coated Reinforcing	Pound
Scarifying	Square Yard
Applied Texture Finish	Square Yard
Hydro-demolition	Square Yard

The Department will pay for the concrete fillet above fabricated bridge girders as bridge deck concrete with the quantities based on the fillet required for a conventional deck forming system and measured as specified in **604.30.A**. The Department will not pay for increases in the fillet depth needed to accommodate the Contractor's chosen deck forming system (e.g.

precast deck panels) and will consider this increase to be incidental to other items bid.

The Department will pay for accepted quantities of leveling concrete at 40% of the price bid for the concrete used in the footing as approved by the Engineer.

If the Contractor does not meet the surface rideability requirements specified in **604.27**, the Department will make deductions in monies due to the Contractor on a lump sum basis.

When field conditions result in the construction of a different type of box culvert or box bridge from that shown on the Plans (box type to slab type or vice versa), the Department will increase the respective bid price per cubic yard for Class A concrete by 15% for constructing a slab type instead of box type and will decrease the bid price by 13% for constructing box type instead of slab type. The Department will not adjust the Steel Bar Reinforcement unit bid price for the change in box culvert or box bridge type.

Where concrete does not meet the specified strength but is allowed to be included in the permanent construction as specified in **604.20** or cores fail to meet the strengths specified in **604.15**, the Department will use the following equation to determine percent payment of contract bid price.

$$PP = 100 - (3 \times Ds)$$

Where:

PP = Percent Payment

Ds = Percent Below Specified Strength

$$Ds = \left[\frac{(\text{Specified Strength} - \text{Actual Strength})}{\text{Specified Strength}} \right] \times 100$$

The Department will base the percent payment on the unit price of the item as bid, i.e., volume [cubic yards], length [feet], each, or other designated bid unit. Payment of the calculated percentage includes cost of incidental items such as reinforcing steel when included in the price bid for the item.

Defective concrete greater than 25% below specified strength may remain in place at no cost to the Department if approved by the Department of Structures, or the Contractor may remove and replace the defective concrete.

606.01

SECTION 606 – PILING

606.01	Description	558
606.02	Classification.....	559
606.03	Materials	559
606.04	Equipment	559
606.05	Preliminary Work.....	562
606.06	Precast Concrete Piles	562
606.07	Cast-in-Place Concrete Piles	564
606.08	Test Piles	565
606.09	Calibration Tests	568
606.10	Order Lists for Piles	568
606.11	Storage and Handling.....	569
606.12	Driving Piles	569
606.13	Bearing Value and Penetration.....	571
606.14	Determination of Bearing Value	571
606.15	Inspection of Shells for Cast-in-Place Piling	573
606.16	Extensions and Splices	573
606.17	Cutoffs and Treatment of Pile Heads	574
606.18	Conditioning of Treated Timber Piles after Driving	574
606.19	Painting Steel Piles and Steel Shells	574
606.20	Final Cleanup	574
606.21	Method of Measurement	575
606.22	Basis of Payment.....	577

DESCRIPTION

606.01 Description

This work consists of furnishing and driving or placing piling. This work also includes the furnishing and driving of test piling and production piling and conducting load tests, when shown on the Plans or included in the Contract.

606.02 Classification

The Department will classify piling according to the following designations:

1. Steel "H" Piling, 8, 10, 12, and 14 inches;
2. Steel Pipe Piling, as designated on the Contract Plans;
3. Timber Piling (Untreated), Sizes 1 and 2;
4. Timber Piling (Treated), Sizes 1 and 2;
5. Precast Prestressed Concrete Piling, 14, 16 and 18 inches; and
6. Cast-in-Place Concrete Piling.

Refer to the Plans for the designation and size of piling to be used in the construction.

MATERIALS**606.03 Materials**

Provide materials as specified in:

Materials for Concrete	604.02
Reinforcement for Concrete Piles	907.01
Pre-Stressing Reinforcement Steel and Anchorages.....	907.04
Steel Piles	908.15
Steel Shells	908.16
Steel Pipes.....	908.17
Paint.....	910.03
Timber Piles.....	911.03

EQUIPMENT**606.04 Equipment**

Have all equipment required for handling and driving steel piling, timber piling, precast concrete piling, steel shells or steel pipe on the Project and approved by the Engineer before beginning work.

Use pile driver leads that are straight and allow freedom of movement of the hammer. Hold the leads in position with guys or braces to support the pile during driving. Except where driving piles through water, use leads of

606.04

sufficient length to make the use of a follower unnecessary, unless otherwise approved by the Engineer.

Provide equipment and tools to manufacture concrete for piles, whether precast or cast-in-place, which meet **604.04** and the Engineer's approval.

Provide forms for precast concrete piles that meet the applicable requirements of **604.05**.

The plant and equipment furnished for steam and air driven hammers shall have sufficient capacity to maintain, under working conditions, the pressure at the hammer specified by the manufacturer. Equip the boiler or tank with an accurate pressure gauge. Also install a gauge that will accurately measure the pressure at the hammer intake, unless another approved method is provided to furnish the data necessary to determine the energy delivered by the hammer.

Operate diesel hammers with a wide open throttle when blows are being counted to determine the average penetration to use in the safe load formula, except that in the case of diesel hammers with enclosed rams, the throttle settings shall be just short of the settings that would cause non-striking parts of the hammer to rise off the piles as the ram piston travels upward.

Equip diesel hammers that have an enclosed ram with an accurate gauge and charts that will evaluate the equivalent energy being produced under any driving condition.

If the Engineer finds the size or type of hammer used to be unsatisfactory, replace it with another size or type of hammer, or use other corrective measures as required to produce satisfactory results.

A. Hammers for Timber Piles

Drive timber piles with an approved steam, air, diesel, or gravity hammer.

1. Steam, air, or diesel hammers shall develop an energy of not less than 6,000 foot-pounds per blow.
2. Gravity hammers shall weigh at least 2,000 pounds and not less than the weight of the driving head and pile. Regulate the height of fall to avoid damage to the pile. The height of fall shall not exceed 20 feet.

B. Hammers for Steel Piles

Drive all steel type piles with an approved steam, air, or diesel hammer. Only use gravity hammers with the Engineer's written approval. If the Engineer approves the use of gravity hammers, meet the requirements specified under paragraph 3 below.

1. Steam, air, or diesel driven hammers shall:
 - (a) Develop at least 7,000 foot-pounds of energy.
 - (b) Except as provided in paragraph 2(b) below, develop an energy per blow in foot-pounds not less than 250 multiplied by R, where R is the required minimum bearing resistance of the pile in tons.
 - (c) Have a gross energy in foot-pounds of not less than 2.5 times the weight of the pile in pounds.
2. The following additional requirements apply to diesel driven pile hammers:
 - (a) Hammers that do not restrict the rebound of the ram shall have a ram weighing at least 2,000 pounds.
 - (b) Hammers that have an enclosed ram shall have a rated equivalent energy in foot-pounds of not less than 250 multiplied by R, where R is the required minimum bearing resistance of the pile in tons.
3. When approved by the Engineer, the Contractor may use gravity hammers to drive steel piling provided that:
 - (a) The weight of the pile is no more than the weight of the hammer.
 - (b) The steel piling will be driven to refusal on rock, and the overburden is relatively free of boulders.
 - (c) The hammer weighs at least 3,000 pounds and not more than 5,000 pounds. Regulate the height of fall to obtain a minimum energy per blow of 12,000 foot-pounds and to

606.05

avoid damage to the pile. The height of fall shall not exceed 10 feet.

C. Hammers for Precast Concrete Piles

Drive precast concrete piles with a steam, air, or diesel hammer that develops an energy per blow at each full stroke of the piston of at least 12,000 foot-pounds and not less than 1 foot-pound per each pound weight of the pile being driven. Limit the maximum hammer energy such that no damage occurs to the pile during driving.

The following additional requirements also apply to diesel powered pile hammers:

1. Hammers that do not restrict the rebound of the ram shall have a ram weighing not less than 2,750 pounds and not less than $\frac{1}{4}$ the weight of the pile.
2. Hammers that have an enclosed ram shall have a rated equivalent energy of at least 15,000 foot-pounds per blow.

D. Hammers for Steel Shells or Steel Pipe

Drive steel shells or steel pipe for cast-in-place piles with hammers that meet **606.04.C**.

CONSTRUCTION REQUIREMENTS

606.05 Preliminary Work

Perform Clearing and Grubbing, Removal of Structures and Obstructions, Excavation and Undercutting, Structure Excavation, Foundation Preparation and Backfill, and Embankment Construction as specified in **201**, **202**, **203**, **204**, and **205**, respectively. In areas where piles are to be driven and excavation or embankment construction is to be performed, complete the excavation or embankment before driving piles.

606.06 Precast Concrete Piles

Construct precast concrete piles as shown on the Plans and according to these Specifications. Construct precast concrete piles of either air-entrained or non-air-entrained Class P concrete that is proportioned and mixed as

specified in **615.09**. Submit to the Department for approval a concrete design, indicating the proportions, the source or brand of all materials, and the type of cement to be used. Prepare and place the concrete as specified in **604** with the revisions and additions stipulated herein.

Assemble and place the reinforcement as shown on the Plans.

Stress cables for precast prestressed concrete piles as specified in **615.07** and **615.08**.

Cast piles in a horizontal position. Do not cast in tiers. Place the concrete continuously in each pile and consolidate by mechanically vibrating and spading. Take care to avoid horizontal or diagonal cleavage planes, and to ensure that the reinforcement is properly embedded in the concrete and not displaced. Overfill the forms, screed off the surplus concrete, and finish the top surface to a uniform, even texture similar to that produced by the forms.

Side forms may be removed as soon as their removal will not cause distortion to the hardened concrete. As soon as the forms are removed, repair surface irregularities, and unless otherwise specified, give the piles a Class I finish as specified in **604.21.A**.

Cure the precast concrete piles by the water method as specified in **604.23.B**, or by steam curing as specified in **615.11.C.2**

Do not move piles from the bottom supporting forms, or release the stressing force on prestressed piles, until the concrete has attained a compressive strength of at least 3,500 pounds per square inch, as evidenced by test specimens made and cured in the same manner as the piles.

Ensure that the concrete in precast and precast prestressed piles have developed a compressive strength of at least 5,000 pounds per square inch and have reached a minimum age of 7 days before driving the piles.

Make, cure, and perform testing of test specimens as specified in **615.09**.

When handling or hauling precast concrete piles, support them at the points shown on the Plans, or, if not so shown, support the piles at the quarter points. The Engineer will make a final inspection as to condition after delivery to the site.

606.07

606.07 Cast-in-Place Concrete Piles

A. General

Construct cast-in-place concrete piles of the design shown on the Plans and that consist of concrete cast in drilled holes or in steel shells or pipes driven to the required bearing. Use Class A concrete meeting **604**, or use Class X concrete, as required by design, meeting 604. Provide and place suitable casing when required to prevent caving of the hole before concrete is placed.

B. Drilled Holes

Dry drill all holes for cast-in-place piles to the tip elevations shown on the Plans. The Engineer will examine all holes for straightness and will reject holes that on visual inspection from the top show less than half of the diameter of the hole at the bottom. Provide and place suitable casings when required to prevent caving of the hole before concrete is placed.

After drilling operations have been completed, but before placing concrete, remove all loose material at the bottom of the hole.

Do not use water for drilling operations or for any other purpose that may cause it to enter the hole. Take all necessary action to prevent surface water from entering the hole.

C. Casing

If using casing in drilling operations, remove it from the hole as concrete is placed. Maintain the bottom of the casing not more than 5 feet nor less than 1 foot below the top of the concrete during withdrawal and placing operations, unless otherwise allowed by the Engineer. Prevent separation of the concrete during withdrawal operations by hammering or otherwise vibrating the casing.

D. Steel Shells and Pipes

Inspect the inside of shells and pipes as specified in **606.15**. Remove all loose material before placing concrete. Place the concrete in one continuous operation from tip to cutoff elevation and to avoid segregation. Consolidate the concrete in the upper 25 feet of shell or pipe piles by using vibrators.

Do not fill any shell or pipe with concrete until all adjacent shells, pipes, or piles within a radius of 5 feet or 4-1/2 times the average pile diameter, whichever is greater, have been driven to the required resistance.

After a shell or pipe has been filled with concrete, do not drive a shell, pipe, or pile within 20 feet of it until at least 7 days have elapsed.

606.08 Test Piles

When called for in the Bid Schedule, furnish and drive test piles of the dimensions, at the locations, and to the minimum tip elevations, shown on the Plans or as designated by the Engineer.

When approved by the Engineer, the Contractor may drive test piles to be load tested through the existing overburden, without excavating to the bottom of the footing elevation and by predrilling when required by the Engineer, provided that the additional length of test pile necessary to obtain the requirements specified below is furnished at no additional cost to the Department.

Before driving any other test or foundation piles, excavate the ground at each test pile to the elevation of the bottom of the footing.

Drive test piles to be load tested full length or to the specified bearing indicated on the Plans as determined by the applicable specification equation in **606.14**, whichever occurs first. Drive all other test piles full length or to 1.5 times the specified bearing indicated on the Plans, whichever occurs first. However, the tip elevation for all piles shall be either a minimum of 10 feet below ground elevation or the minimum tip elevation when specified on the Plans. If the test pile has been driven to 1.5 times the specified bearing but has not reached the minimum tip elevation, continue to drive the test pile until the required penetration is obtained or practical refusal occurs, whichever occurs first. When the required pile penetration cannot be achieved by driving without exceeding practical pile refusal, use other penetration aids such as jetting or preformed pile holes. Practical refusal shall be defined as 15 blows per inch for 2 consecutive inches of driving or when 2 times the minimum required bearing is achieved based on the last 6 inches of driving. Use pile driving equipment capable of driving to 1.5 times the specified bearings indicated on the Plans at a driving rate not to exceed 15 blows per inch.

Perform a load test on one or more of the test piles as shown on the Plans or as designated by the Engineer. From driving logs for test piles and hold-

606.08

down piles, load tests, and other available subsoil information, the Engineer will determine the number and length of piles to be used and the minimum required bearing.

The Engineer may require a test pile to be left in place for use, cut off, spliced, or removed.

Load tests shall consist of a test load accomplished by loading weights on a platform or by jacking against hold-down piles with a suitable apparatus for accurately measuring the test load and the pile settlement under each increment of load. The pile load test apparatus for applying loads and measuring movement shall meet the requirements of ASTM D1143. Apply the load to not exert any undue bending stresses or damage to the pile. The loading and calibration system shall be capable of applying and recording loads up to 200% of the pile bearing values shown on the Plans. Materials used in performing load tests shall remain the property of the Contractor. Unless otherwise shown on the Plans, wait a minimum of 3 days between installing the load test pile and starting the test.

The Engineer may direct that load tests be added, deleted, or repeated, and will make payment for such testing in accordance with **606.22**.

The Department based the number of load tests and test piles shown on the Plans on the assumption that the Contractor will drive all tests piles with the same pile driver as was used for the load test pile. If choosing to drive some test piles with a different pile driver, furnish the necessary additional load tests at no additional cost to the Department.

After the Engineer establishes the number and length of piles to be used, the Contractor may drive regular piles with a different pile driver from that used for driving test piles, provided it notifies the Structures Division before pile lengths are established and uses a pile driver that conforms to the specified requirements.

Before driving a pile to be load tested, submit to the Engineer written details outlining the method of applying, measuring, and recording test loads along with sufficient sketches to fully illustrate the method, procedure, and arrangements proposed. For the jacks to be used in the tests, submit to the Engineer calibration certificates from a laboratory approved by the Engineer. Ensure that the certificates are no more than 6 months old.

The following are the two methods for performing pile load tests. Perform the quick load test unless directed otherwise on the Plans.

A. Quick Load Test

The full test load shall be 200% of the pile load shown on the Plans. Apply the load in approximately equal increments of 10 to 20% of the pile load as shown on the Plans, and at intervals of 5 minutes throughout the load test. Take and record readings of time, load, and movement immediately before and after applying each load.

Apply the load until either a plunging failure occurs, or the full test load is reached. Plunging failure occurs when continuous jacking is required to maintain the test load. After the final holding time, or immediately after plunging failure occurs, remove the applied load in five approximately equal decrements with intervals of 5 minutes between decrements. Take readings after removing each decrement and 5 minutes after the complete removal of the test load.

B. Maintained Load Test

The full test load shall be 150% of the pile load as shown on the Plans. Apply the test load in maximum increments of 25% of the pile load as shown on the Plans and at time intervals such that the rate of settlement does not exceed 0.12 inch per hour per load increment for a minimum interval of 2 hours. Take and record readings of time, load, and movement immediately before and after applying each load increment.

The failing load is defined as the minimum load that produces one of the following conditions:

1. Rate of settlement exceeding 0.12 inch per hour for a 2-hour period.
2. Settlement occurring during the last 12 hours of the full load test period.
3. Permanent net settlement after rebound in excess of $\frac{1}{4}$ inch.

When failure occurs under condition 1, decrease the applied load as necessary until the rate of settlement is within the allowable limits to establish the failing load. Take a final reading 1 hour after complete removal of the load, and accurately record the failing load. The Department will pay the full value of the unit price bid for load tests. The Engineer will decide to what extent, if any, the test pile will be considered as contributing to the support of the structure.

606.09

Should failure not occur due to condition 1, carry the load test to completion with the full test load remaining on the pile for 48 hours and then removed in six equal increments at 1-hour intervals with readings taken after the removal of each increment and 1 hour after the complete removal of the test load.

Although the terminology in this Subsection is related to driven piles, it shall also apply to cast-in-place piles if so designated on the Plans.

After performing the load tests shown on the Plans, the Contractor may choose to substitute piling of a different material or configuration from that shown on the Plans provided they meet the minimum design standards and specifications and are approved by the Engineer. The required length of the substituted piling will be determined by additional load test(s) conducted at no cost to the Department. The basis of payment for the piling shall be in accordance with **606.22**, except the total linear feet shall not exceed that established by load tests for the piles shown on the Plans. When additional test piles that are load tested and deemed usable are made at plan location using the substituted material, the Department will make payment at the unit bid price for regular piling.

606.09 Calibration Tests

When diesel or other types of hammers requiring calibration are to be used, calibrate the hammers by performing load tests, as directed by the Engineer, even if no load tests are called for in the Bid Schedule. The Department will not require such calibrations if the hammer is to be used only for driving piles to rock or a fixed tip elevation, or when the hammer is of a type and model that has previously been calibrated by sources acceptable to the Engineer, for similar type, size, and length of pile, and foundation material.

606.10 Order Lists for Piles

The Engineer will furnish the Contractor with an itemized list showing the number and length, as determined by tests, of all required piles, complete in place. The Engineer will not prepare the list of piling for any portion of the foundation area until the required test data representative of that portion has been determined. The Engineer will base the lengths given in the order list on the lengths that are assumed to remain in the completed structure.

Furnish the piles in accordance with the itemized list, except, at no additional cost to the Department, increase the lengths to provide for fresh heading and

for such additional length as may be necessary to suit the Contractor's method of operation.

If during pile driving, the conditions encountered require a change in lengths, make such changes by cutting off piling if it is too long, by furnishing new piling, or by splicing as specified in **606.16** if the piling is too short.

The Department will make no allowance for delays caused by the procedure of determining pile lengths.

606.11 Storage and Handling

Store and handle piles to avoid damaging them and as follows:

1. Store steel piles above ground, and keep them free of dirt and grease and, insofar as practicable, corrosion.
2. To handle timber piles, do not use hooks, dogs, pike poles, or similar pointed tools, and take care to avoid breaking their surface.
3. Lift precast concrete piles by attaching a suitable bridle or sling to the pile at the points shown on the Plans.

606.12 Driving Piles

Drive piles at the locations shown on the Plans or as directed in writing by the Engineer, and to within an allowed variation as to direction of pile of not more than $\frac{1}{4}$ inch per foot of pile length, with a maximum variation at the head of the pile from the position shown on the Plans of not more than 3 inches. To ensure proper positioning of each pile, use templates constructed of heavy timbers or steel, which are accurately positioned, securely held in place, and approved by the Engineer. When using water jets, ensure that the number of jets and the nozzle volume and pressure is sufficient to erode the material adjacent to the piling freely. The pump shall always have sufficient capacity to deliver a pressure of at least 100 pounds per square inch at two $\frac{3}{4}$ -inch jet nozzles. Before the required penetration is reached, shut off the jets and drive the piles by hammer to final penetration.

When preformed pile holes are used, construct them by drilling or driving and withdrawing a suitable punch or chisel at or near the locations of the piles. If preformed pile holes are so oversized that the sides of a round pile or the corners of a square pile are not in contact with the soil, restore lateral stability by filling the space between the pile and the sides of the hole with

606.12

approved clean sand, at no cost to the Department. Terminate preformed holes before the required penetration is reached and drive the pile by hammer to the final tip elevation to seat the pile and secure the minimum required bearing.

Except when the pile head is fitted into a steel head block, provide every timber pile with a metal collar or wire wrapping. Protect the heads of all concrete piles, and the heads of all other piles when the nature of the driving is such that piles may be unduly damaged, with caps of approved design, having a plywood cushion next to the pile head and fitting into a casting, which, in turn, supports a hammer cushion made from durable, manufactured material. Do not use wire rope and other materials of limited durability. Use an approved pile cushion of sufficient thickness to prevent damage to the pile during driving. Use a minimum initial dimension of 4-inch thick plywood pile cushion for concrete piles. Replace the pile cushion before excessive compression (more than $\frac{1}{2}$ the original thickness), burning, or charring takes place. During hard driving, several pile cushions may be necessary for a single pile. Use a new pile cushion for each pile.

For special types of piling, provide driving heads, mandrels, or other devices in accordance with the manufacturer's recommendations so that the pile may be driven without damage.

For steel piling, squarely cut the heads and provide a driving cap to align the axis of the pile with the axis of the hammer. When shown on the Plans, cap steel piles with steel plates or other devices.

Use full length piles where practicable. In exceptional circumstances, the Engineer may allow splicing of piles. Splice as specified in **606.16**.

Install production piles full length, except terminate driving when practical refusal as defined in **606.08** has been reached. If production piles do not achieve the minimum required bearing when driven full length, the Engineer will determine if additional piles are required.

The tip elevation for all production piles shall be equal to or below the minimum pile tip elevation shown on the Plans. When the required pile penetration cannot be achieved by driving without exceeding practical refusal, use other penetration aids such as jetting or preformed pile holes.

If piles are raised during driving of other piles, or by any other cause, drive them down again at no cost to the Department.

606.13 Bearing Value and Penetration

When the Bid Schedule provides for load tests, the Engineer will determine the minimum number of hammer blows per unit of pile penetration needed to obtain the specified bearing value based on load tests performed as specified in **606.08** and **606.09**. In the absence of load tests, the Engineer will determine the safe bearing value based on test pile data.

Each driven pile or shell shall have a minimum bearing value as shown on the Plans or as specified by the Engineer given the results of the load test or test pile data. Drive piles with the same driving system (fuel setting, hammer cushion, and pile cushion) as the test piles, or the pile that was load tested.

Piles used to penetrate a very soft upper stratum overlying a hard stratum shall penetrate the hard material a sufficient distance to fix the pile rigidly.

606.14 Determination of Bearing Value

In the absence of load tests, the Engineer will determine the safe bearing value by one of the following formulas:

1. Gravity Hammers:

$$P = \frac{2WH}{S + 1}$$

2. Single Acting Steam or Air Hammers and Diesel Hammers with Unrestricted Rebound:

$$P = \frac{2WH}{S + 0.1}$$

3. Double Acting Steam or Air Hammers:

$$P = \frac{2H(W + Ap)}{S + 0.1}$$

4. Double Acting Steam or Air Hammers and Diesel Hammers Having Enclosed Rams:

$$P = \frac{2E}{S + 0.1}$$

606.14

Where:

- P = Safe load per pile in pounds;
- W = Weight of the striking part of the hammer in pounds;
- A = Area of piston in square inches;
- p = Steam pressure in pounds per square inch at hammer;
- H = Height of fall in feet for gravity, steam, and air hammers, and observed average height of fall, in feet, of blows used to determine penetration for diesel hammers with unrestricted rebound of ram;
- S = Average penetration per blow in inches for the last 5 to 10 blows of a gravity hammer or the last 10 to 20 blows of a steam, air, or diesel hammer; and
- E = Manufacturer's rating for foot-pounds of energy developed by double acting steam or air hammers, and 90% of the average equivalent energy in foot-pounds, as determined by a gauge attached to the pile hammer and recorded during the period when the average penetration per blow is recorded for diesel hammers having enclosed rams. Hammers of this type shall be equipped with a gauge and applicable charts supplied that will evaluate the equivalent energy being produced under any driving condition.

The above formulas are applicable only when:

1. The hammer has a free fall;
2. The head of the pile is free from broomed or crushed wood fiber or other serious impairment;
3. The penetration is at a reasonably quick and uniform rate;
4. There is no appreciable bounce after the blow;
5. The weight of pile is no more than the weight of hammer used, if hammer is of the gravity type; and
6. A follower is not used.

If there is an appreciable bounce, twice the height of bounce will be deducted from H to determine its value in the formula.

The bearing power, as determined by the appropriate formula in the list above, will be considered effective only when it is less than the crushing strength of the pile.

Other recognized formulas for determining pile-bearing power may be used if fully detailed in the Special Provisions.

When the safe bearing value of any pile is found by test or computation to be less than the design load, drive longer piles or additional piles as directed in writing by the Engineer.

606.15 Inspection of Shells for Cast-in-Place Piling

After the shell has been driven, and the core withdrawn, obtain the Engineer's approval of the shell before placing any concrete. Remove and replace shells that have been improperly driven, do not hold their proper form and dimensions, or are broken or otherwise defective.

606.16 Extensions and Splices

A. Steel and Timber Piles

Use full length steel or timber piles where practicable. If splices cannot be avoided, use a method of splicing as shown on the Plans. Spliced piles shall have a full, true, and even bearing at the joint. Do not splice timber piles in abutments.

B. Precast Concrete Piles

Extend precast concrete piles by removing the concrete at the end of the pile and leaving the reinforcement steel exposed for a length of 30 diameters.

Securely brace the pile to prevent it from vibrating during the cutting or building up operation. Remove the concrete to produce a face at right angles to the axis of the pile.

Securely fasten reinforcement similar to that used in the pile to the projecting steel. Place the necessary forms to prevent leakage along the pile.

Immediately before placing concrete, clean the top of the pile of all loose particles, wet it thoroughly, and cover with a thin coating of cement grout. Use Class P or Class X (high early strength) concrete meeting the applicable requirements of **604** and **615.09**.

Extend precast prestressed concrete piling as shown on the Plans. Use reinforcement similar to that used for precast concrete piling, Size 1.

606.17

Remove forms as specified in **604.19**. After the forms have been removed, give the concrete the required finish.

Do not construct caps to be supported by built-up precast concrete piles until test specimens representing the concrete in the buildups attain a compressive strength of at least 3,000 pounds per square inch.

606.17 Cutoffs and Treatment of Pile Heads

Drive or cut the tops of all piles to a true plane at the elevation shown on the Plans or established by the Engineer.

Saw timber piles that support timber caps to the plane of the superimposed cap, and ensure they fit snugly. Treat untreated timber pile heads as specified in **601.07** before they are to receive caps.

After treatment, place a covering of 20-gauge galvanized iron on each timber pile and fold it down neatly over the side and fasten to shed water.

No treatment or covering of pile heads will be required if they are to be encased in concrete.

606.18 Conditioning of Treated Timber Piles after Driving

Thoroughly treat all places where the surface of timber piles is broken as specified in **601.07**. Treat bored holes and holes caused by withdrawing bolts and spikes as specified in **601.06.K**.

606.19 Painting Steel Piles and Steel Shells

Unless otherwise specified, paint steel piles or steel pile shells that extend above the ground or water surface. Extend the paint from 2 feet below the low water or ground surface elevation to the top of the exposed steel. Unless otherwise indicated, use painting System A, as specified in **603.06**, except apply the shop coat in the field. Perform painting as specified in **603**.

606.20 Final Cleanup

After driving and completing the piling, clean the piles of undue discoloration caused by construction operations. Give those areas of concrete piles that will be exposed the applicable finish, as specified in **604.22**.

Perform final cleanup as specified in **104.10**.

COMPENSATION

606.21 Method of Measurement

A. Test Piles

The Department will compute the length of test piles for payment as the total length in linear feet of test piles shown on the Plans or as required by the Engineer; or if the penetration for any one test pile is greater than the length of the pile shown on the Plans or directed by the Engineer, then the linear feet of actual penetration of such test pile will be the linear feet of test pile measured for payment.

Where a buildup or extension is placed on a test pile to be left in place, the Department will compute the actual linear feet of buildup or extension for payment for the size of pile used as the test pile. The Department will make no allowance for splicing, cutoffs, or cutting off a test pile in order to construct an extension or buildup upon the test pile. No payment will be made for cutting off or removing test piles not to remain in place.

B. Loading Tests

The Department will measure pile loading tests by the unit per each, which will be determined by the number of load tests performed.

C. Piles

The Department will measure piles of the sizes shown on the Plans or as directed by the Engineer, complete in place, including buildups or extensions, by the linear foot. Measurement will not include the part cut off after driving.

Piles spliced, built up, or cut off to such an extent as to change the length of the completed piling from one size to the other size will be computed for payment in the size originally intended.

No measurement for payment will be made for digging or drilling holes, or for jetting piling, to obtain the required penetration.

606.21

If, in accordance with **606.08**, the Contractor chooses to substitute piling of a different material or configuration from that shown on the Plans, the total linear feet to be paid will not exceed that established by load tests for the piles shown on the Plans.

D. Splices

The Department will measure splices for timber and steel piles by allowing 3 feet of piling, complete in place, for each splice made, except measurement for payment of splices for steel will be made only for splicing performed within the limits specified in Table 606.21-1.

Table 606.21-1: Payment of Splices for Steel Piles

In-Place Length	Maximum Pay Splices
40 feet or less	None
> 40 feet ≤ 80 feet	1
> 80 feet ≤ 120 feet	2
> 120 feet	3

No allowance will be made for splicing shells or pipe for cast-in-place piling. The Department will not measure splices caused by damage to a pile.

E. Pile Cutoffs

No allowance will be made for cutting off cast-in-place piles.

The Department will measure for payment the actual length of pile cutoff, to the nearest 0.1 foot, for precast concrete, precast prestressed concrete, steel, steel shell, and steel pipe piles.

The Department will not measure for payment steel, steel shell, and steel pipe pile cutoffs having a length of 10 feet or greater. For precast prestressed concrete piles, the 2 feet of piling required for seismic attachment, when the Contractor chooses this option, will not be included in the measurement for cutoff.

Take ownership of unused lengths of piles and pile cutoffs and remove from the Project. The Department will not measure cutoffs caused by damage to the pile.

606.22 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Test Piles (Description)	Linear Feet
Load Test (Description)	Each
Steel Piles (Size)	Linear Feet
Steel Pipe Piles (Size)	Linear Feet
Untreated Timber Piles (Size)	Linear Feet
Treated Timber Piles (Size)	Linear Feet
Precast Concrete Pile (Size)	Linear Feet
Precast Prestressed Concrete Pile (Size)	Linear Feet
Cast-in-Place Concrete Pile (Size)	Linear Feet
Pile Tips (Description)	Linear Feet

Such payment is full compensation for providing all materials, equipment, labor, and incidentals to complete the work as specified.

The Department will pay for each load test performed as specified in **606.08** at the unit price bid for load tests, except that a load test repeated for any given test pile from the same setup will be paid for at one-half the unit price bid for load tests.

The Department will pay for pile cutoffs at the invoice price of the pile per foot. The Department will not directly pay for the costs of preparing precast prestressed concrete piles for buildups but will consider this work to be incidental to building up the pile.

The Department will not make additional payment if the Contractor chooses to use high-early-strength concrete.

If test piles and load tests indicate that piling will not be necessary or pile lengths shorter than those shown in the Plans will be acceptable, the price per linear foot for these test piles shall be full compensation for furnishing and removing all equipment for driving piling, and the Department will not compensate the Contractor for any loss or anticipated profits for failure to use piling as shown. If the Engineer directs the use of individual concrete production piling that is longer by more than 16 feet than that shown in the Plans, the Department will pay for that concrete piling at a rate equal to 1.15 times the contract unit price per linear foot for that size concrete pile.

607.01

SECTION 607 – PIPE CULVERTS AND STORM SEWERS

607.01	Description	578
607.02	Materials	578
607.03	Equipment	580
607.04	Preliminary Work.....	581
607.05	Structure Excavation and Foundation Preparation	581
607.06	Laying Pipe Culverts.....	581
607.07	Joining Pipe.....	581
607.08	Field Strutting	582
607.09	Backfilling and Post Installation Inspection.....	582
607.10	Disposal of Excess or Unsuitable Material	584
607.11	Final Cleanup	584
607.12	Method of Measurement	584
607.13	Basis of Payment.....	585

DESCRIPTION

607.01 Description

This work consists of constructing pipe culverts, side drains, slope drains, and storm sewers of the kinds and dimensions shown on the Plans or specified in the Contract. The work also includes all labor, materials, and equipment as may be necessary to make connections with other drainage structures as shown on the Plans or as directed by the Engineer.

MATERIALS

607.02 Materials

A. General

Provide materials as specified in:

Joint Mortar	905.02
Rubber Gaskets	905.03

Reinforced Concrete Pipe (RCP).....	914.02
Polyvinyl Chloride (PVC) Pipe	914.09
High Density Polyethylene (HDPE) Plastic Pipe.....	914.10
Steel Reinforced Thermoplastic Ribbed Pipe (SRTRP)	914.11
Polypropylene (PP) Pipe.....	914.12
Corrugated Metal Pipe (CMP).....	915.02

Materials for special end connections to pipes or structures, required to complete the work as shown on the Plans or directed by the Engineer, shall conform to **914** and **915**, unless otherwise specified.

Reinforced concrete pipe shall be, round, arch or elliptical, as shown on the Plans.

The sizes of pipe shall be identified by the nominal inside diameter. Provide pipe of the sizes and classes or gauges specified in the Contract, shown on the Plans, or established by the Engineer.

For corrugated metal pipe, and pipe arches, the Contractor may use corrugated steel, provided different corrugations are not mixed in a single line of pipe.

Aluminum coated corrugated metal pipe shall conform to the requirements of AASHTO M 274 and the Department's Drainage Manual for pipe culvert gauge.

Furnish coupling bands and all hardware, except nuts, bolts, and washers, of the same material and coating as the pipe.

When corrugated metal pipe arches are specified as "size equivalent round," the dimensions shall be as shown on the Plans.

B. Pipe Culverts Cross Drains, Side Drains, & Storm Drains

Where Pipe Culverts (Cross Drains & Median Drains) are specified, provide them in accordance with the following:

1. Pipe Diameters from 18 through 36 inches. Provide materials meeting one of the following:

1. RCP Class III, IV, or V meeting **914.02** or AASHTO M 170, M 206, or M 207.

607.03

2. CMP meeting **915.02** or AASHTO M 274.
3. HDPE pipe meeting **914.10** or AASHTO M 294.
4. PVC pipe meeting **914.09** or AASHTO M 304.
5. PP pipe meeting **914.12** or AASHTO M 330.
6. SRTRP meeting **914.11** or AASHTO M 335.

2. Pipe Diameters Larger than 36 inches through 60 inches.

Provide materials meeting one of the following:

1. RCP Class III, IV, or V meeting **914.02** or AASHTO M 170, M 206, or M 207.
2. CMP meeting **915.02** or AASHTO M 274.
3. HDPE pipe meeting **914.10** or AASHTO M 294.
4. PP pipe meeting **914.12** or AASHTO M 330.
5. SRTRP meeting **914.11** or AASHTO M 335.

3. Pipe Diameters Larger than 60 inches. Provide materials meeting the following:

1. RCP Class III, IV, or V meeting **914.02** or AASHTO M 170, M 206, or M 207.
2. CMP meeting **915.02** or AASHTO M 274.

C. Slope Drains

Where Slope Drains are specified, provide materials in accordance with one of the following:

1. CMP meeting **915.02** or AASHTO M 274.
2. HDPE pipe meeting **914.10** or AASHTO M 294.
3. PVC pipe meeting **914.09** or AASHTO M 304.
4. PP pipe meeting **914.02** or AASHTO M 330.
5. SRTRP meeting **914.11** or AASHTO M 335.

EQUIPMENT

607.03 Equipment

Provide hoisting equipment capable of handling and placing the pipe culvert in final position without damaging the pipe. Include mechanical tamps.

CONSTRUCTION REQUIREMENTS

607.04 Preliminary Work

Perform Clearing and Grubbing, Removal of Structures and Obstructions, Excavation and Undercutting, and Embankment Construction as specified in **201, 202, 203, and 205**, respectively.

607.05 Structure Excavation and Foundation Preparation

Perform Structure Excavation and Foundation Preparation as specified in **204**.

Provide bedding for pipe culverts that conforms to the requirements of **204** or the Standard Drawings.

When excavating to install pipe culverts across private property, salvage and replace in its original position, all topsoil and sod disturbed by the excavation operations, unless otherwise specified. Consider all costs of restoring the area to its original condition as incidental to other items of construction.

607.06 Laying Pipe Culverts

Lay pipe culverts beginning at the downstream end of the pipe line. Ensure that the lower segment of the pipe is in contact with the shaped bedding throughout its full length. Place bell or groove ends of RCP and outside circumferential laps of flexible pipe facing upstream. Place CMP, HDPE, PP, SRTRP, and PVC pipe with longitudinal laps or seams at the sides.

Lay paved invert pipe so that the longitudinal centerline of the paved segment coincides with the flow line. Place reinforced elliptical concrete pipe with the major axis of the reinforcement less than 5 degrees departure from a vertical plane through the longitudinal axis of the pipe.

607.07 Joining Pipe

RCP may be of bell and spigot or tongue and groove design, unless one type is specified. Join pipe sections so that the ends are fully entered and the inner surfaces are reasonably flush and even.

Use rubber gaskets or other types of joints recommended by the pipe manufacturer and approved by the Engineer.

607.08

To form gasket joints for concrete pipe, install rubber ring gaskets meeting ASTM C443 for round pipe.

Join CMP with approved coupling bands in accordance with ASTM D3212.

HDPE, PP, SRTRP, and PVC pipe shall be joined in accordance with ASTM D3212 and meet the performance requirement for soil-tightness, unless water-tightness is specified. Install joints so that the connection of pipe sections, for a continuous line, will be free from irregularities in the flow line.

If the Engineer approves use of other joint types, install or construct them in accordance with the manufacturer's recommendations.

Inspect the pipe culvert before placing any backfill, and remove and re-lay or replace pipe found to be out of alignment, unduly settled, or damaged.

607.08 Field Strutting

If required, perform strutting or vertical elongation as shown on the Standard Drawing.

Leave ties and struts in place until the embankment is completed, unless otherwise specified.

607.09 Backfilling and Post Installation Inspection

After the pipe culvert is installed, backfill the trench as specified in **204** and the Standard Drawings. Visually inspect all pipe culverts during and after installation to ensure conformance to these Specifications. Conduct the final visual inspections for all pipe culverts no sooner than 30 days after completing installation and final fill. Conduct final visual inspections from the inlet and outlet ends of all pipe culverts, providing sufficient hand-held lighting to observe any defects. In addition to visual inspection, perform the testing described below not less than 30 days after completing pipe culvert installation and final fill placement. Perform all post installation inspections and testing in the presence of the Engineer as follows:

A. Flexible Pipes: HDPE, PVC, SRTRP, PP, and CMP

Conduct a deflection test (mandrel, laser, video, or manual) on at least 10% of the total number of pipe culvert runs, representing a minimum 10% of the total project footage including a minimum of one run of each

pipe culvert diameter. The Engineer will randomly select installations to be tested to determine whether the pipe culvert diameter has been reduced greater than 5% of the actual diameter. At any location of a pipe culvert run, if the deflection is greater than 5% but less than 7.5%, further evaluate all pipe culvert installations to identify excessive deflections. Provide documentation with pipe culvert station, material type, diameter, deflection location, and length results to the Engineer and Design Engineer for evaluation of excessive deflections based on material type, diameter, deflection location, pipe culvert structural integrity, and effects to pavement stability and drainage.

Replace, at no cost to the Department, all pipe culverts with deflections greater than 7.5% of the actual pipe diameter, undue misalignment, or poor joint construction. Perform all excavation, removal and replacement of pipe culverts with same or different material and all additional work including, but not limited to, bedding, backfill, base stone or asphalt removal and repaving, required to correct the pipe installation due to poor construction techniques at no cost to the Department.

B. Rigid Pipe: RCP

Visually inspect all RCP for alignment, cracking, undue misalignment, abrupt slope changes and joint gasket installation between pipes at headwalls, catch basins, manholes, etc., for continuity, improper backfill or bedding during and after installation; inspect according to Section 27 of AASHTO Standard Specifications for Highway and Bridges or per ASTM C1840. If found, further evaluate installations where visual inspections detect poor construction techniques as directed by the Engineer, at no additional cost to the Department.

Based on the evaluations, the Engineer and Design Engineer may allow the pipe culvert to remain in place if remediations are made according to an approved remediation plan submitted by the producer. The Contractor shall have full understanding of the remediation process prescribed and how to perform the remediation. All remediation work shall be at no cost to the Department.

The Engineer shall inspect pipe culverts for poor installation practices, undue misalignment, abrupt slope changes, joint gasket installation between headwalls, catch basins, manholes, etc., continuity, and improper backfill or bedding. Based on unsatisfactory results of inspection or deflection testing, the Engineer may request additional inspections at no cost to the Department

607.10

607.10 Disposal of Excess or Unsuitable Material

Dispose of excess or unsuitable excavated material as directed by the Engineer. Use excavated material as specified in **204.08.C**.

607.11 Final Cleanup

Perform final cleanup as specified in **104.10**.

COMPENSATION

607.12 Method of Measurement

A. Reinforced Concrete Pipe Culverts

The Department will measure reinforced concrete pipe culverts of the different classes, shapes, and sizes specified, by the linear foot of pipe installed and accepted. The Department will pay for the quantity of pipe cut off, not to exceed 2 feet, at the contract bid price for pipe in place.

B. Corrugated Metal Pipe Culverts

The Department will measure corrugated metal pipe by the linear foot of pipe installed and accepted. The Department will make measurements as follows:

1. Corrugated Metal pipe with square and vertical ends or with skewed and vertical ends will be measured, in place, end to end of the metal on the centerline of the structure.
2. Corrugated Metal pipe with square ends beveled, and with ends skewed and beveled, except arch pipe, will be measured, in place, by averaging the end-to-end distances at the top and bottom of the pipe, measured parallel to the centerline of the structure.
3. Corrugated Metal arch pipe with square ends beveled, and with ends skewed and beveled, will be measured, in place, end to end of the metal along the invert of the structure.

C. HDPE Pipe, PP Pipe, SRTRP, and PVC Pipe Culverts

The Department will measure HDPE, PP, SRTRP, and PVC pipe by the linear foot of pipe installed and accepted. The quantity of pipe cut off, not to exceed 2 feet, will be paid for at the contract bid price for pipe in place.

D. Slope Drains

The Department will measure Slope Drains in the same manner as specified for corrugated metal pipe in **607.12.B**.

E. Side Drains

The Department will measure Pipe Culverts (Side Drains) of the different sizes specified by the linear foot along the centerline of the installed pipe, not to exceed the ordered length of the pipe. Order Pipe Culverts (Side Drains) in increments of 2 feet.

F. Incidentals

Unless otherwise shown on the Plans, the Department will not measure structure excavation, and will consider such work incidental to other items of construction. When the Plans provide for direct payment for structure excavation, the Department will make measurement and payment in accordance with **204**.

The Department will not pay for labor and materials used in making branch connections. The length of pipe in the branch connection will be measured and included in the quantity of pipe culvert installed in the branch line.

The Department will not separately measure strutting of flexible pipe culverts but will consider such costs as included in the unit price bid per linear foot of pipe.

607.13 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

607.13

<i>Item</i>	<i>Pay Unit</i>
___" (Type) Pipe Culvert (Description)	Linear Feet
(Type) Pipe Arch (Size)	Linear Feet
___" Slope Drain Pipe	Linear Feet
___" Crossdrain Pipe Culvert	Linear Feet
Box Culvert (Size)	Linear Feet
___" Slotted Drain Pipe	Linear Feet

Such payment is full compensation for all labor and materials used in making joints and connections to other structures; for strutting, when required; excavation, bedding, and backfill, unless otherwise provided for in the Contract, and for completing all incidentals necessary to complete the item.

SECTION 608 – SANITARY SEWERS

608.01 Description.....	587
608.02 Materials	587
608.03 Equipment.....	588
608.04 Preliminary Work.....	588
608.05 Structure Excavation and Foundation Preparation.....	588
608.06 Laying Pipe.....	588
608.07 Constructing Joints.....	589
608.08 Connections	589
608.09 Test for Watertightness	590
608.10 Backfilling	590
608.11 Method of Measurement.....	590
608.12 Basis of Payment.....	591

DESCRIPTION

608.01 Description

This work consists of constructing sanitary sewers, or parts of sewers, composed of the kinds and dimensions of pipe shown on the Plans or established by the Engineer. The work also includes such incidentals, materials, and labor as may be necessary to make connections with other structures, as shown on the Plans or as directed by the Engineer.

MATERIALS

608.02 Materials

Provide materials as specified in:

Joint Mortar	905.02
Rubber Gaskets.....	905.03
Hemp or Oakum Gaskets.....	905.04
Concrete Pipe, Non-Reinforced.....	914.01
Concrete Pipe, Reinforced	914.02
Vitrified Clay Pipe.....	914.06

608.03

Polyvinyl Chloride (PVC) Pipe.....	914.09
Cast Iron Pipe.....	915.01

EQUIPMENT

608.03 Equipment

Provide equipment as specified in **607.03**.

CONSTRUCTION REQUIREMENTS

608.04 Preliminary Work

Perform Clearing and Grubbing, Removal of Structures and Obstructions, Excavation and Undercutting, and Embankment Construction as specified in **201, 202, 203, and 205**.

608.05 Structure Excavation and Foundation Preparation

Perform Structure Excavation and Foundation Preparation as specified for pipe culverts in **204**.

Provide bedding for sanitary sewers that conforms to the requirements of **204.10.B** for Class A, Class B, or Class C. If no bedding class is specified, comply with the requirements for Class C bedding.

608.06 Laying Pipe

If new facilities or other construction interfere with the existing flow of sewage, provide satisfactory by-pass facilities. Do not divert sewage into an open ditch at any time. Unless otherwise specified, the Department will not directly pay for the costs incurred in providing by-pass facilities but will consider this work to be incidental to other items of construction.

Lay pipe without break in grade from structure to structure and with the bell or groove end upgrade. Ensure that each section has firm bearing throughout its length and forms a close concentric joint with the adjoining pipe. Make junctions and turns with standard or special fittings.

Do not allow water to run or stand in the trench while pipe laying is in progress, before the joint has completely set, or before the trench has been

backfilled. Do not open up more trench at any time than the available pumping facilities are able to dewater.

If the work ceases for any reason, securely close the end of the pipe with a tight fitting plug or cover. For all branch openings or service connections provided for future use, securely close with a tight fitting plug and seal to prevent leakage. Plug open ends of pipe to be abandoned, and seal in a manner approved by the Engineer.

When the pipe connects with structures, place or cut off the exposed ends to be flush with the interior face of the structure and make satisfactory connections.

Take up and relay, at no cost to the Department, pipe that is not in good alignment, shows undue settlement, or is damaged.

608.07 Constructing Joints

Lay pipe and seal joints in a continuous operation. Seal all joints during the same day in which the sections of pipe are laid. Construct the joints to be watertight, using a method of connection that meets the Engineer's approval.

Clean the joints of cast iron pipe, and then joint and seal with materials recommended by the pipe manufacturer.

Make joints in concrete or clay pipe with hemp or oakum gaskets impregnated with hot asphalt and sealed with hot poured sewer joint sealing compound, hemp or oakum gaskets impregnated with neat cement grout and sealed with mortar, rubber gaskets, mastic compound, or other elastic material, or other types of joint recommended by the pipe manufacturer.

As the work progresses, clean the interior of all pipe in place.

608.08 Connections

Make connections by constructing manholes or other structures or installing wyes or tees as shown on the Plans or directed by the Engineer. Install wyes and tees for future connections as shown or directed.

Make connections to existing structures and sanitary sewer house service connections as shown on the Plans or directed by the Engineer.

608.09

Include the cost of temporary connections and disinfecting and deodorizing excavation or sewage in the unit price bid for other items of construction.

608.09 Test for Watertightness

When required, perform tests for watertightness at no cost to the Department. Conduct the tests in the presence of the Engineer and in accordance with the established procedures prescribed by the local municipality, utility, or owner.

Rebuild or repair, as required and at no cost to the Department, all sanitary sewers and connections showing leakage in excess of that allowed by the local codes or established regulations. The Engineer will only accept rebuilt or repaired sewers that pass the above test.

608.10 Backfilling

After the pipe is installed, backfill the trench as specified in **204**.

COMPENSATION

608.11 Method of Measurement

The Department will measure pipe for sanitary sewers, of the various kinds, types, and sizes, by the linear foot of pipe installed and accepted. The length will be determined by measuring along the centerline of the pipe from center to center of structures, or junction fittings. An allowance of 2 feet of the kind and size of pipe in the sewer line will be made for each wye or tee required in the line. The Department will measure each kind, type, and size, determined by the nominal inside diameter of the pipe, separately.

The Department will measure sanitary sewer house service connections per each.

The Department will not directly pay for the labor and materials used in making branch connections and will consider this incidental to the work.

Unless otherwise shown on the Plans, the Department will not measure structure excavation, and will consider such work to be incidental to other items of construction. When the Plans provide for direct payment for Structure Excavation, the Department will measure and pay for this work in accordance with **204**.

608.12 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
<u> </u> ” Sanitary Sewer Pipe	Linear Feet
Sanitary Sewer House Service Connections	Each

Such payment is full compensation for all labor, materials, and incidentals necessary to complete the items.

609.01

SECTION 609 – PIPE REMOVED AND RELAID

609.01 Description	592
609.02 Materials	592
609.03 Equipment	593
609.04 Preliminary Work.....	593
609.05 Removing Pipe	593
609.06 Preparing Pipe for Relaying	593
609.07 Structure Excavation and Foundation Preparation	593
609.08 Relaying or Placing Pipe.....	594
609.09 Backfilling.....	594
609.10 Final Cleanup	594
609.11 Method of Measurement	594
609.12 Basis of Payment.....	595

DESCRIPTION

609.01 Description

This work consists of removing and relaying pipe culverts and storm sewers or sanitary sewers as shown on the Plans, specified in the Contract, or directed by the Engineer. The work also includes all labor and materials as may be necessary to make connections with other drainage structures as shown on the Plans or as directed by the Engineer.

This item does not include pipes that are to be removed but not to be incorporated into the Work.

MATERIALS

609.02 Materials

Provide materials as specified in:

Joint Mortar	905.02
Rubber Gaskets	905.03
Hemp or Oakum Gaskets	905.04

Obtain the Engineer's approval of all materials and devices to be used in making connections before using them in the work.

EQUIPMENT

609.03 Equipment

Provide equipment as specified in **607.03**.

CONSTRUCTION REQUIREMENTS

609.04 Preliminary Work

Perform Clearing and Grubbing, Removal of Structures and Obstructions, and Excavation and Undercutting as specified in **201**, **202**, and **203**, respectively.

609.05 Removing Pipe

Carefully remove the pipe and handle so as not to damage or cause the pipe to be unfit for relaying.

Replace pipe damaged as a result of negligence or inefficient handling or any other action under the Contractor's control, with pipe of the same kind and quality at no cost to the Department.

609.06 Preparing Pipe for Relaying

Clean the pipe, inside and outside, of all dirt, debris, mortar, and other foreign matter.

Cut salvaged pipe to obtain the required lengths, and furnish coupling bands, gaskets, and other jointing materials necessary to make all connections.

Ensure that all pipe to be relaid is sound and in good condition. Do not use broken or deteriorated sections of pipe or connections.

609.07 Structure Excavation and Foundation Preparation

Perform Structure Excavation and Foundation Preparation as specified in **607.05**.

609.08

609.08 Relaying or Placing Pipe

Relay or place pipe of the various types specified as prescribed for the respective types in **607.06**, **607.07**, **607.08**, **608.06**, and **608.07**.

609.09 Backfilling

Perform backfilling as specified in **204** for pipe culverts.

609.10 Final Cleanup

Dispose of all excess or unsuitable material as directed by the Engineer.

Perform final cleanup as specified in **104.10**.

Store all material that is to become the Department's property as directed by the Engineer.

COMPENSATION

609.11 Method of Measurement

The Department will measure pipe removed and relaid, of the various kinds, by the linear foot along the centerline of the pipe and from end to end of the pipe, complete in place, including incidentals, after relaying.

The Department will not measure pipe removed but not relaid. Excavation, including the volume occupied by the pipe, performed to remove pipe under this Section will be measured for payment in accordance with **204.12**, for Culvert Excavation (Unclassified).

Unless otherwise shown on the Plans, the Department will not measure structure excavation, and will consider such work to be incidental to other items of construction. When the Plans provide for direct payment of Structure Excavation, the Department will measure and pay for this work in accordance with **204.12** for Culvert Excavation (Unclassified), and the volume occupied by the pipe will be included in the measurement for payment.

609.12 Basis of Payment

The Department will pay for accepted quantities of pipe removed and relaid at the contract unit price per linear foot for each type of pipe, complete in place.

With the exception of pipe to be replaced at the Contractor's expense, the Department will pay for pipe used to replace rejected pipe under the Section covering the type and kind of pipe being replaced.

610.01

SECTION 610 – PIPE DRAINS

610.01 Description	596
610.02 Materials	596
610.03 Reserved.....	597
610.04 Preliminary Work.....	597
610.05 Structure Excavation and Foundation Preparation	597
610.06 Backfill.....	597
610.07 Suspending Pipe Drains	597
610.08 Placing and Joining Pipe	597
610.09 Painting Pipe Drains.....	598
610.10 Finishing and Final Cleanup	598
610.11 Method of Measurement	598
610.12 Basis of Payment.....	599

DESCRIPTION

610.01 Description

This work consists of furnishing and constructing or placing pipe drains not classified as pipe culverts or storm sewers in **607**, sanitary sewers in **608**, or underdrains in **710**. Construct pipe drains of the kinds and sizes of pipe shown on the Plans, specified in the Contract, or established by the Engineer.

MATERIALS

610.02 Materials

Provide materials as specified in:

Joint Mortar	905.02
Rubber Gaskets.....	905.03
Paint.....	910
Non-Reinforced Concrete Pipe	914.01
Vitrified Clay Pipe	914.06
Plastic and Polyethylene Corrugated Tubing.....	914.07
Cast Iron Pipe.....	915.01

610.03

Corrugated Metal Pipe (Non-Perforated).....	915.02
Corrugated Aluminum Pipe (Non-Perforated).....	915.02

Use the paint system shown on the Plans.

Where Pipe Drains (Bridge Drains) are specified, provide metal pipe meeting **915.02**, or polyethylene pipe meeting AASHTO M 294.

610.03 Reserved

CONSTRUCTION REQUIREMENTS

610.04 Preliminary Work

Perform Clearing and Grubbing, Removal of Structures and Obstructions, and Excavation and Undercutting as specified in **201**, **202**, and **203**, respectively.

610.05 Structure Excavation and Foundation Preparation

Perform Structure Excavation and Foundation Preparation as specified in **204**.

For pipe drains, unless otherwise shown on the Plans or directed by the Engineer, cut a shallow trench in natural ground or compacted embankment to a depth of not less than 10% of the outside vertical pipe diameter and shape to fit the lower pipe exterior for the specified embankment.

610.06 Backfill

Backfill trenches as specified in **204** for pipe culverts.

610.07 Suspending Pipe Drains

Where pipe drains are to be placed above the ground surface, suspend them as shown on the Plans or as directed by the Engineer, and ensure that they are securely and rigidly held in place.

610.08 Placing and Joining Pipe

Place pipe for drains as specified in **607.06**. Make joints in concrete, clay, and corrugated metal drain pipe as specified in **607.07**.

610.09

Form joints in cast iron pipe in accordance with the manufacturer's recommendations, using the recommended fittings and methods.

610.09 Painting Pipe Drains

Do not paint concrete, vitrified clay, and corrugated metal pipe drains, even if they are to be exposed, unless otherwise shown on the Plans.

Paint cast iron drains that are to be exposed and do not have a bituminous coating in accordance with the applicable requirements of **603**. Clean cast iron pipe drains that have a bituminous coating and treat with two coats of bituminous material of such kind and grade that the finished coating will be tough when cold and not tacky during hot weather.

Painting shall include all hangers, braces, and other appurtenances.

610.10 Finishing and Final Cleanup

Dispose of all excess or unsuitable material as directed by the Engineer.

Perform final cleanup as specified in **104.10**.

COMPENSATION

610.11 Method of Measurement

The Department will measure pipe drains, of the various kinds and diameters, for payment by the linear foot along the centerline of the pipe, and from end to end of the pipe, including incidentals, complete in place. The Department will measure each kind and diameter of pipe separately.

The Department will not measure excavation, foundation preparation, or backfilling associated with the construction of pipe drains for payment.

The Department will not measure hangers, braces, and similar supports for suspending or hanging pipe drains.

Pipe used in weep holes and drainage openings 6 inches in diameter or less, through concrete abutments, decks, slabs, floors, walls, or similar features will not be paid for directly or under the pay items of this Section, but will be handled in accordance with **604.30.A**.

610.12

610.12 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
<u> </u> " Pipe Drain (Bridge Drain)	Linear Feet
Plastic Pipe Drains (<u> </u> "	Linear Feet

611.01

**SECTION 611 – MANHOLES, CATCH BASINS, INLETS,
AND PIPE END WALLS**

611.01	Description	600
611.02	Materials	600
611.03	Reserved.....	601
611.04	Preliminary Work.....	601
611.05	Structure Excavation, Foundation Preparation, and Backfill	601
611.06	Concrete Construction.....	601
611.07	Inverts	602
611.08	Reserved.....	602
611.09	Inlet and Outlet Pipes.....	602
611.10	Castings and Fittings.....	602
611.11	Final Cleanup	603
611.12	Method of Measurement	603
611.13	Basis of Payment.....	604

DESCRIPTION

611.01 Description

This work consists of constructing manholes, catch basins, inlets, and pipe end walls at the locations shown on the Plans. The work includes furnishing and installing incidental appurtenances and connections to pipe and other structures as may be necessary to complete the construction as shown on the Plans or as directed by the Engineer.

MATERIALS

611.02 Materials

Provide materials as specified in:

Steel Bar Reinforcement	907.01
Structural Steel.....	908.01
Gray Iron Castings	908.07
Precast Manholes and Catch Basins.....	921.10

Manhole Steps **921.11**

For cast-in-place Portland cement concrete, use Class A or when a higher strength concrete is specified in the Standard Drawings use Class X concrete. Manufacture, place, and cure structural concrete as specified in **604**.

Use bolts, anchors, frames, and hangers for castings and plates as approved by the Engineer.

The Contractor may use either the manhole and catch basin sections detailed on the Plans or may substitute comparable sections of cast-in-place concrete or precast reinforced concrete, as may be applicable. When a substitution is proposed for a manhole or catch basin section detailed on the Plans, construct the substitute section in accordance with the applicable Standard Drawing as approved by the Engineer. If the Department has no Standard Drawing of the substitute section, submit shop drawings of the revised section to the Engineer for approval prior to construction. After obtaining the necessary approval, furnish the Engineer an electronic reproducible design file.

611.03 Reserved

CONSTRUCTION REQUIREMENTS

611.04 Preliminary Work

Perform Clearing and Grubbing, Removal of Structures and Obstructions, Excavation and Undercutting, and Embankment Construction as specified in **201**, **202**, **203**, and **205**, respectively.

611.05 Structure Excavation, Foundation Preparation, and Backfill

Perform Structure Excavation, Foundation Preparation, and Backfill as specified in **204**. Do not backfill or allow traffic on cast-in-place sections until 7 calendar days after the representative test specimens reached the required compressive strength.

611.06 Concrete Construction

Perform all concrete construction as specified in **604**.

611.07

611.07 Inverts

Construct inverts of Class A, or when a higher strength concrete is specified in the Standard Drawings use Class X concrete, to conform to the shapes shown on the Plans and to cause the least possible resistance to flow. The shape of the inverts shall conform uniformly to inlet and outlet pipes. Provide a smooth and uniform finish.

611.08 Reserved

611.09 Inlet and Outlet Pipes

Extend inlet and outlet pipes through the walls of manholes, catch basins, and inlets for a sufficient distance beyond the outside surface to allow for connections, but cut the pipes off flush with the wall on the inside surface, unless otherwise directed.

Construct the concrete or brick and mortar around the pipes to prevent leakage and to form a neat connection.

611.10 Castings and Fittings

Handle castings and fittings in a manner that will prevent damage. The Engineer will reject damaged castings and fittings.

Place all castings and fittings in the positions shown on the Plans or as directed by the Engineer and set true to line and grade.

If castings are to be set in concrete or cement mortar, place all anchors or bolts in position before placing the concrete or mortar. Ensure that the casting will not be disturbed until the mortar or concrete has set.

When castings are to be placed upon previously constructed masonry, bring the bearing surface of masonry true to line and grade to present an even bearing surface that will allow the entire face or back of the casting to come in contact with the masonry. Set castings in mortar beds or anchor to the masonry as shown on the Plans or as directed by the Engineer.

Set castings to be firm and snug and to not rattle.

611.11 Final Cleanup

Dispose of all excess or unsuitable material as directed by the Engineer.

Perform final cleanup as specified in **104.10**.

COMPENSATION**611.12 Method of Measurement****A. Manholes, Catch Basins, and Inlets**

When the Bid Schedule indicates that manholes, catch basins, and inlets will be measured by the unit (per each), the Department will measure as follows:

1. Manholes will be measured by the unit, per each, for the various types, diameters, and ranges of depth as shown on the Plans.
2. Catch basins will be measured by the unit, per each, for the various types and ranges of depth as shown on the Plans.
3. Inlets will be measured by the unit, per each, for the various types shown on the Plans.

B. Components of Manholes, Catch Basins, Inlets, and End Walls

When the Bid Schedule contains items for various components of manholes, catch basins, inlets, and end walls, the Department will measure as follows:

1. Portland cement concrete and steel bar reinforcement will be measured in accordance with **604.30**.
2. Structural steel and gray iron castings will be measured by the computed weight based on the dimensions shown on the Plans and deducting for open holes. To this weight the Department will add 5% allowance for fillets and overruns. The Department may substitute scale weights for computed weights of small complex parts for which accurate computations would be difficult.

611.13

3. Steps will not be measured and paid for directly but will be considered incidental to the pay items of other materials with which the structure is constructed.
4. Unless otherwise shown on the Plans, the Department will not measure structure excavation and will consider it incidental to other items of construction. When the Plans provide for direct payment for Structure Excavation, the Department will measure and pay in accordance with **204**.

611.13 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Manholes __' to __' Depth	Each
Junction Box (Description)	Each
Catch Basins, Type __, __' to __' Depth	Each
Spring Drain Box (Description)	Each
Bridge Edge Drain (Size)	Each

Such payment is full compensation for furnishing all materials, equipment, tools, labor, and incidentals necessary to complete the item.

When the Contractor makes approved substitutions for the manhole and catch basin sections detailed on the Plans, the Department will pay for accepted quantities based on the prices bid for the quantities of the items replaced by the substitute sections.

SECTION 612 – STONE MASONRY

612.01 Description.....	605
612.02 Materials	605
612.03 Classification	605
612.04 Reserved.....	606
612.05 Preliminary Work.....	606
612.06 Structure Excavation, Foundation Preparation, and Backfill	606
612.07 Preparing Stone.....	606
612.08 Laying Stone	607
612.09 Pointing.....	609
612.10 Arch Rings	610
612.11 Copings, Top Walls, Bridge Seats, and Back Walls	611
612.12 Finishing and Final Cleanup	611
612.13 Method of Measurement.....	612
612.14 Basis of Payment.....	612

DESCRIPTION

612.01 Description

This work consists of constructing stone masonry structures and stone masonry portions of concrete, steel, timber, and composite structures, at the locations shown on the Plans or as directed by the Engineer.

MATERIALS

612.02 Materials

Provide materials as specified in:

Masonry Mortar.....	912.03
Masonry Stone.....	921.07

612.03 Classification

Stone Masonry will be classified under the following designations:

612.04

1. Uniform-Course Stone Masonry shall consist of masonry constructed with roughly squared stones laid in uniform courses, and in which all courses have approximately the same thickness.
2. Nonuniform-Course Stone Masonry shall consist of masonry constructed with roughly squared stones laid in uniform courses, and in which the courses may have different thicknesses.
3. Uncoursed Stone Masonry shall consist of masonry constructed with roughly squared stones of varying thicknesses and not constructed in courses.
4. Rustic Stone Masonry shall consist of masonry constructed with stones broken to various shapes and sizes.

612.04 Reserved

CONSTRUCTION REQUIREMENTS

612.05 Preliminary Work

Before beginning work on stone masonry, perform all necessary Clearing and Grubbing, Removal of Structures and Obstructions, Excavation and Undercutting, and Embankment Construction as specified in **201, 202, 203,** and **205,** respectively.

612.06 Structure Excavation, Foundation Preparation, and Backfill

Perform Structure Excavation, Foundation Preparation, and Backfill as specified in **204.**

The foundation for this type of construction shall present a uniform bearing surface. If a reinforced foundation is necessary, construct it of Class A concrete as specified in **604** or as directed by the Engineer.

612.07 Preparing Stone

Complete all shaping and dressing of stone before the stone is placed. For angles, ends of walls, copings, and similar features, use selected stone that is squared and pitched to line. The exposed faces of stones shall not show tool marks.

Uniform-coursed masonry stone shall be of the thickness shown on the Plans. In any one course of nonuniform-coursed masonry, use stone of the same thickness, with a minimum thickness of 5 inches. In uncoursed masonry, not more than 10% of the stone shall be of the same thickness, with a minimum thickness of 5 inches.

Stone for uniform-coursed masonry, nonuniform-coursed masonry, and uncoursed masonry shall have a width not less than 1-1/2 times the thickness with a minimum of 12 inches, and a length not less than 1-1/2 times the width, unless otherwise shown on the Plans or directed by the Engineer. Headers shall have a width not less than the thickness, with a minimum of 12 inches, and a length sufficient to extend entirely through walls of 2 feet or less in thickness, and at least 1 foot into the core of the wall for walls more than 2 feet thick. Dress the beds and sides of all stone so that adjacent stones will not touch and so that the face joint will not exceed 1-1/2 inches. The face protrusions shall not exceed 2 inches.

Rustic masonry stone shall consist of stone broken to various shapes and sizes and roughly squared back from the face not less than 3 inches. At least 80% of the stone shall have a minimum face dimension (rise) of not less than 6 inches. The other face dimension at right angles to the rise shall not exceed 2 times the rise, or 2 feet, whichever is smaller. The third dimension shall be at least 1-1/2 times the rise with a minimum of 12 inches. Not more than 10% of the stones shall be of the same face dimensions. Headers shall be of such length as to extend entirely through walls of 2 feet or less in thickness, and at least 1 foot into the core of walls more than 2 feet in thickness. Dress the beds and sides of all stones so that the adjacent stones will not touch and so the face joints will not exceed 1-1/2 inches. The face protrusions shall not exceed 2 inches.

612.08 Laying Stone

When shown on the Plans, build, at a site designated by the Engineer, an L-shaped sample section of wall not less than 5 feet high and 8 feet long, showing an example of face wall, end wall, top wall, method of turning corners, and method of forming joints. Do not lay any masonry, other than the foundation bed, before obtaining the Engineer's approval of the sample walls.

Do not construct stone masonry in freezing weather, or when the stone contains frost.

612.08

Construct the bottom of the foundation course of large, selected stones that are laid on bearing beds parallel to the natural bed of the material.

Use larger stones in the bottom courses, and then gradually decrease stone size from the bottom to the top of the wall; however, uniformly distribute stones of various sizes throughout the wall. Prevent small stones or stones of the same size from meeting or bunching.

Use selected large stones, roughly pitched to lines, at all corners and ends of walls.

Uniformly distribute unweathered stones and stones of the same color throughout the exposed faces of the wall to avoid the appearance of patches. Thoroughly clean each stone and moisten with water before setting. Clean and moisten the bed that is to receive the stone before spreading the mortar.

Embed stones in freshly made mortar. The joints shall be full and the stones carefully settled in place before the mortar is set. Stones shall not contact adjacent stones but shall be suspended in the mortar. Do not set the four corners of adjacent stones to be contiguous unless otherwise indicated or directed.

Build the backing chiefly of large stones laid in full mortar beds, well bonded with each other and interlocked and bonded with the face stones. Completely fill all spaces and interstices with mortar, or with spalls surrounded completely with mortar.

Do not jar or displace stones already set. Do not roll or turn stones on the wall.

If a stone is moved or the joint broken after setting, remove the stone, clean off the mortar from the stone bed and joints, and reset the stones in fresh mortar.

Headers shall hold in the heart of the wall, the same size shown in the face, and shall extend not less than 12 inches into the core or backing, unless otherwise indicated. Uniformly distribute headers throughout the walls of structures to occupy at least 1/5 of the wall faces. In walls 2 feet or less in thickness, extend headers entirely through the walls.

Except in rustic masonry, spalls will not be permitted in the beds or face joints. The bed joints and beds shall have an average thickness of not more than 1 inch. Horizontal face joints shall be not less than 1/2 inch nor more than

1 inch and shall be approximately uniform in thickness. Vertical face joints shall be not less than $\frac{1}{2}$ inch nor more than 1-1/2 inches in thickness.

Lay uniform-course and non-uniform-course masonry to line and grade, and in courses that are roughly leveled up. Break vertical joints in coursed masonry with those in adjoining courses at approximately the middle of the stones.

Lay uncoursed stone masonry to line and with the bed of the stone approximately parallel and level. Do not extend horizontal face joints through more than four stones, and vertical face joints through more than two stones. Break all joints approximately at the middle of the adjacent stones.

Construct rustic stone masonry so that the stone of the various face sizes will be well and uniformly distributed throughout the face of the wall. Prevent small stones or stones of the same size from meeting or bunching. Spalls may be used but shall not be segregated. Construct the joints along the face to be not less than $\frac{1}{2}$ inch nor more than 1-1/2 inches in thickness, to have an approximately uniform width, and to not extend in a straight line through more than two stones. Form face joints to run in all directions and at various angles with each other. In general, bed surfaces shall be practically perpendicular to the face of the wall for not less than 3 inches, from which point they may be irregular and fall off not to exceed 3 inches in 12 inches, and shall be free from depressions or projections that will impair the strength of the masonry or hinder the securing of full bearing on the mortar.

Construct weep holes of such shape and size as indicated or directed. Unless otherwise shown on the Plans or directed by the Engineer, space weep holes not over 10 feet center to center and locate them at the lowest point where free outlet may be obtained. Protect the inlet end of weep holes by placing a wire basket of 1 foot by 1 foot by 1 foot, filled with coarse aggregate, size 7, 8, 57 or 68 immediately over or behind the holes as directed.

Take care at all times to keep the surface free from mortar stains. Immediately after laying and while the mortar is fresh, clean face stones of all mortar stains and keep in a clean condition.

Finish the top edge or course to a true line with a uniform surface on top of the wall.

612.09 Pointing

Properly point face joints before the mortar in the joints sets.

612.10

Where raked joints are required, squarely rake all mortar in exposed face joints to a depth of approximately 2 inches before the mortar has set. Use clean water to thoroughly wet joints that are not pointed at the time the stone is laid, and fill with mortar. Ensure that the mortar is well driven into the joints, and then finish with an approved pointing tool.

Where weather joints are required, the bed shall be weather struck. Slightly rake the joints to conform to the bed weather joints. Do not leave the mortar flush with the stone faces. If required by the Engineer, wet the joints and point with mortar.

Rake out joints on top surfaces to a depth of approximately 1 inch at the edges and crown the mortar to drain.

Keep the walls upon which pointing is being performed moist for a period of at least 72 hours after completion. In hot, dry weather, protect the pointed masonry from the sun during this period.

Do not smear the face surfaces of stone with the mortar forced out of the joints or mortar used in pointing.

After the pointing is completed and the mortar has set, thoroughly clean the stone and leave it in a neat and workmanlike condition.

612.10 Arch Rings

Lay out a full-size template of the arch ring near the quarry site, showing face dimensions of each ring stone and thickness of joints. Obtain the Engineer's approval of the template before starting the shaping of any ring stone. Place no ring stone in the structure until all ring stones have been shaped, dressed, and approved.

Construct arch centering in accordance with construction drawings submitted by the Contractor in accordance with **105.02**. Provide suitable wedges for adjusting the elevation of the forms and for taking up any settlement occurring during loading. Lower the centering gradually and symmetrically to avoid overstresses in the arch.

When directed by the Engineer, support centering with approved jacks to take up and correct any slight settlement that may occur after masonry placement begins. In general, strike centering and make the arch self-supporting before placing railing or coping.

Construct, in a manner satisfactory to the Engineer, any additional falsework or bracing needed to hold the stones in position.

Furnish arch ring stones of the size shown on the Plans and dress them to form radial joints not more than 1-inch in width. On the face and soffit, the joints shall be cut hard for a distance of at least 3 inches, from which point, they may fall off not to exceed 1 inch in 1 foot. Completely fill the joints with mortar, and grout if necessary. Point or finish the joints while the mortar is fresh.

Place an anchor composed of ½-inch steel bar bent into an elongated letter S in each voussoir joint extending at least 1 foot into the backing and to within 3 inches of the face of the stone.

612.11 Copings, Top Walls, Bridge Seats, and Back Walls

Construct copings, tops of walls, bridge seats, back walls, and similar features to the lines, grades, and cross-sections, and of the material, shown on the Plans or as directed by the Engineer.

For copings, tops of wall, bridge seats, back walls, and similar features to be constructed of concrete, use Class A concrete conforming to the applicable requirements of **604**, unless otherwise shown on the Plans or directed by the Engineer. Construct concrete copings in sections from 5 to 10 feet long and of the width and thickness shown on the Plans.

Construct stone copings of carefully selected stones of the length, width, and thickness shown on the Plans. Construct copings to have a uniform surface and to be pitched to line along the top and bottom edge.

612.12 Finishing and Final Cleanup

Clean exposed surfaces of stone masonry of all mortar, scars, and blemishes to provide a surface having a natural color of stones. Use wire brushes and acid that will not mar or damage the stone or mortar when required.

Perform final cleanup as specified in **104.10**.

612.13

COMPENSATION

612.13 Method of Measurement

The Department will measure stone masonry, complete in place, by the cubic yard. The volume will include the cubic yards placed within the lines shown on the Plans and typical cross-sections, or as directed by the Engineer. The different classifications of mortar stone masonry will be measured separately. Arch rings will be included in the measurements of the classifications of masonry in connection with which they are constructed, unless otherwise indicated.

The Department will measure concrete used in reinforcing foundations and in copings, tops of walls, bridge seats, and back walls in accordance with **604.30**.

The Department will include copings, tops of walls, bridge seats, and back walls constructed of stone in the measurements of the classification of masonry in connection with which they are constructed.

Unless otherwise shown on the Plans, the Department will not measure structure excavation, and will consider this work incidental to other items of construction. When the Plans provide for direct payment for Structure Excavation, the Department will measure and pay for this work in accordance with **204**.

612.14 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Uniform-Course Stone Masonry	Cubic Yard
Non-uniform Course Stone Masonry	Cubic Yard
Uncoursed Stone Masonry	Cubic Yard
Rustic Stone Masonry	Square Yard

SECTION 613 – BRICK MASONRY

613.01	Description.....	613
613.02	Materials	613
613.03	Reserved.....	614
613.04	Preliminary Work.....	614
613.05	Structure Excavation, Foundation Preparation, and Backfill	614
613.06	Mortar	614
613.07	Laying Brick	614
613.08	Copings, Tops of Walls, Bridge Seats, and Back Walls	615
613.09	Finishing and Final Cleanup	616
613.10	Method of Measurement.....	616
613.11	Basis of Payment.....	617

DESCRIPTION

613.01 Description

This work consists of constructing brick masonry structures, and the brick masonry portions of concrete, steel, timber, and composite structures, at the locations shown on the Plans.

MATERIALS

613.02 Materials

Provide materials as specified in:

Building Brick (Kind and Grade as Specified)	912.01
Sewer Brick	912.02
Masonry Mortar	912.03
Brick Paving Units.....	912.05

613.03

613.03 Reserved

CONSTRUCTION REQUIREMENTS

613.04 Preliminary Work

Before beginning work on brick masonry, perform all necessary Clearing and Grubbing, Removal of Structures and Obstructions, Excavation and Undercutting, and Embankment Construction as specified in **201, 202, 203,** and **205,** respectively.

613.05 Structure Excavation, Foundation Preparation, and Backfill

Perform Structure Excavation, Foundation Preparation, and Backfill as specified in **612.06.**

613.06 Mortar

Mortar for brick masonry shall meet **912.03.**

613.07 Laying Brick

Do not construct brick masonry in freezing weather or when the bricks contain frost.

For exposed surfaces, corners, and similar areas, use brick selected from brick that has been approved for color and uniformity.

Immediately before laying brick, thoroughly clean and moisten with water both the bricks and the bed that is to receive the brick.

Lay brick in freshly made mortar, true to the lines and grades shown on the Plans or as directed by the Engineer. Arrange headers and stretchers to thoroughly bond the masonry and, unless otherwise indicated or directed, alternate headers and stretchers with consecutive courses breaking joints.

Lay brick in courses to be thoroughly bonded with the joints completely filled with mortar.

Lay the courses continuously, and with consecutive courses breaking joints. Neatly strike face joints, using a weather joint. Finish all joints properly as

the laying of brick progresses and to be not less than $\frac{1}{4}$ inch nor more than $\frac{1}{2}$ inch in thickness.

Do not use spalls or bats except for shaping around irregular openings or when unavoidable to finish out a course, in which case, place a full brick at the corner and the bat in the interior of the course. Use filling materials for the interior of the walls that are of the same quality as used in the face of the unit, unless otherwise shown on the Plans or directed by the Engineer.

Neatly plaster the surface of brick masonry, against which embankment or backfill is to be placed, with mortar to a thickness of not less than $\frac{1}{2}$ inch, and finish the mortar to a true and uniform surface. Protect the mortar and keep it wet for 48 hours after completion.

Keep the exposed surface of brick free from mortar stains. Immediately after laying, thoroughly clean face brick of all mortar stains.

Construct weep holes of such shape and size as shown on the Plans or as directed by the Engineer. Space weep holes not over 10 feet center to center and locate them at the lowest point where free outlet may be obtained, unless otherwise directed by the Engineer. Protect the inlet end of weep holes by placing a wire basket 1 foot by 1 foot by 1 foot filled with coarse aggregate size 7, 8, 57, or 68 immediately over or behind the holes as directed.

In case any brick is moved, or the joints break after laying, remove the brick, clean off the mortar from the brick, bed, and joints, and relay the brick in fresh mortar.

Protect brick masonry and keep it wet for a period of 48 hours after laying brick.

Ensure that all brick masonry presents an even, uniform, neat, and workmanlike appearance.

613.08 Copings, Tops of Walls, Bridge Seats, and Back Walls

Construct copings, tops of walls, bridge seats, back walls, and similar features to the lines, grades, cross-sections, and of the material shown on the Plans or as directed by the Engineer.

For copings, tops of walls, bridge seats, back walls, and similar features, to be constructed of concrete, use Class A concrete conforming to the requirements of **604**, unless otherwise shown on the Plans or directed by the

613.09

Engineer. Construct concrete copings and similar features in sections from 5 to 10 feet long and of such widths and thicknesses as shown on the Plans or as directed by the Engineer. The sections may be cast-in-place or precast and set in place in full mortar beds. Finish concrete as specified in **604.22**.

For copings, tops of walls, bridge seats, back walls, and similar features to be constructed of stone, use stone masonry of the classifications shown on the Plans or as directed by the Engineer. Construct stone copings of the design and thickness shown on the Plans, using carefully selected large stones of the length, width, and thickness shown on the Plans. The stone shall have a uniform surface and be pitched to line along the top and bottom edge. For all stone, comply with the requirements specified in **612**.

613.09 Finishing and Final Cleanup

Clean brick masonry that is to be exposed in the completed construction of all mortar, scars, and blemishes. The exposed surface shall present a surface having the natural color of the brick.

Perform final cleanup as specified in **104.10**.

COMPENSATION

613.10 Method of Measurement

The Department will measure brick masonry by the 1,000 brick, as indicated on the Plans, placed within the lines shown on the Plans and typical cross-sections or as established by the Engineer.

When the Department measures brick masonry by the cubic yard, the volume will include the mortar.

When the Department measures brick masonry by the 1,000 brick, the mortar will not be considered. If fractional parts of brick, of $\frac{1}{2}$ brick or greater, are used, the Department will include these parts in the measurements; if less than $\frac{1}{2}$ brick, they will not be included.

The Department will measure concrete used in reinforcing foundations and in copings, tops of walls, bridge seats, and back walls in accordance with **604.30**.

613.11

The Department will measure copings, tops of walls, bridge seats, and back walls constructed of stone masonry in accordance with **612.13**.

Unless otherwise shown on the Plans, the Department will not measure structure excavation, and will consider the work incidental to other items of construction. When the Plans provide for direct payment for Structure Excavation, the Department will make measurement and payment in accordance with **204**.

613.11 Basis of Payment

The Department will pay for accepted quantities of Brick Masonry at the contract unit price per 1,000 brick, whichever unit is called for on the Plans or in the Contract, complete in place.

615.01

**SECTION 615 – PRECAST/PRESTRESSED CONCRETE
BRIDGE MEMBERS**

615.01	Description	618
615.02	Prestressing Methods	619
615.03	Materials	619
615.04	Equipment	620
615.05	General	620
615.06	Forms	620
615.07	Stressing Requirements – General	621
615.08	Pretensioning Procedure.....	622
615.09	Proportioning and Mixing of Concrete	623
615.10	Handling, Placing, and Consolidating Concrete.....	625
615.11	Removing Forms, Finishing, and Curing	626
615.12	Post-Tensioning Procedure	628
615.13	Combined Prestressing and Post-tensioning	629
615.14	Transfer of Stress	629
615.15	Handling and Installation	630
615.16	Grouting	631
615.17	Tolerances	631
615.18	Method of Measurement	632
615.19	Basis of Payment.....	633

DESCRIPTION

615.01 Description

This work consists of manufacturing precast/prestressed structural concrete members and hauling, storing, and placing the precast/prestressed members on a prepared substructure.

Fabricate these items in plants that have been certified by the Precast/Prestressed Concrete Institute (PCI). The fabricator shall be certified by PCI for the product that it will be manufacturing and supplying to the State or the Contractor.

615.02 Prestressing Methods

Prestress the individual bridge members by pretensioning, post tensioning, or a combination of both methods. Plans for prestressed members will fully detail at least one of these methods. The Contractor may use a prestressing method other than that shown on the Plans if approved by the Engineer.

Fabricate precast/prestressed concrete members in a PCI Category B3 certified plant. Have at each fabrication site a technician skilled in the approved prestressing method. This technician shall give specialized aid and instruction in the use of the prestressing equipment and installation of materials as may be necessary to achieve the required results. The fabricator of precast/prestressed concrete members shall also have at each fabrication site a quality control technician capable of performing all necessary quality control inspection and testing to ensure that the precast/prestressed member is applicable for its intended use. The quality control technician shall have direct lines of communication to engineering, production, and management with responsibility only to management and shall not be subject to control by production (plant superintendent). Quality Control personnel shall meet the training requirements as specified in the Departmental procedures.

MATERIALS

615.03 Materials

Provide materials as specified in:

Portland Cement	901.01
Fine Aggregate.....	903.01
Coarse Aggregate.....	903.03
Joint Filler, Preformed Type.....	905.01
Steel Bar Reinforcement.....	907.01
Prestressing Reinforcement Steel and Anchorages.....	907.04
Structural Steel.....	908.01
Elastomeric Bearing Pads	908.12
Paints	910
Cement Concrete Curing Materials	913
Water	921.01
Air-Entraining Admixtures	921.06
Chemical Admixtures and Additives	921.06
Grout, Type 1	921.09

615.04

EQUIPMENT

615.04 Equipment

Provide equipment as specified in **604.04**. Also provide a Type A field laboratory as specified in **106.06**.

CONSTRUCTION REQUIREMENTS

615.05 General

Construct the substructure for the precast/prestressed structural concrete members as shown on the Plans and as specified in these Specifications.

Fabricate the panels in a PCI Category B3 certified plant.

Construct the precast/prestressed structural concrete members in an approved plant under plant control conditions and place them upon the substructure to the established lines and grades as shown on the Plans.

Ensure that each plant has a quality control plan as specified in **604.03.B**.

615.06 Forms

Unless otherwise allowed, for external forms, provide metal forms that are mortar-tight and sufficiently rigid to prevent distortion due to pressure of the concrete and other stresses incident to the construction operations. The forms shall be substantial and unyielding, and designed, set, and maintained so that the finished concrete will conform to the proper dimensions and contours. Provide forms that are filleted at sharp corners and that have a bevel or draft in the case of projections to allow for easy removal. Wooden bulkheads may be used.

Treat forms with oil immediately before placing the concrete. Do not use any material that will adhere to or discolor the concrete.

Internal forms may be of cellular polystyrene, meeting the requirements specified in Table 615.06-1, or reinforced cardboard.

Table 615.06-1: Cellular Polystyrene

Property	Value
Density (ASTM D1622)	0.90 pounds per cubic foot
Compressive Strength @ 10% Deformation (ASTM D1621)	10 psi minimum
Absorption (ASTM C272)	3% (vol.) maximum

Each individual form shall have a cross-sectional area, equal to the cross-sectional area of the beam void, and a minimum length of 5 feet. When individual forms are constructed by gluing pieces together, use an approved glue. The Engineer will reject forms that show signs of glued joint separations.

615.07 Stressing Requirements – General

Calibrate all jacks, together with their gauges before using in the manufacture of prestressed members. When required by the Department, perform calibrations using proving rings or other acceptable methods performed by an approved testing laboratory at the Contractor's expense. Have a calibration chart for each device readily available on site and furnish such charts to the Department. Recalibrate jacks and gauges at least once every 6 months. Provide means for measuring the elongation of reinforcement to at least the nearest 1/16-inch.

For all methods of tensioning, determine the force in the tendons by monitoring either the applied force or the elongation, and then independently checking by measuring the other. At the completion of tensioning operations, the two control measurements, force and elongation, shall agree within 5% of the computed theoretical values. If discrepancies exceed 5%, suspend the tensioning operation and use qualified personnel to determine and evaluate the source of error before proceeding. If the source of the discrepancy cannot be determined, recalibrate the devices. Additionally, ensure that the control measurements of force and elongation algebraically agree with each other within 5%. If the measurements do not agree within 5%, the Contractor may add a load cell at the "dead end," and if force measurements agree within 5% between the gauge at the live end and the load cell at the dead end, the Department will waive the requirement for elongation agreement.

When taking elongation and gauge readings, include appropriate allowances for chuck seating, bed shortening under load, abutment rotation, thermal

615.08

effects, gauge correction based on calibration data, friction, and any other compensation for the setup.

To measure the tensioning force, use one or more of the following methods:

1. Pressure gauges to measure force from the pressure applied to hydraulic jacks.
2. Dynamometers connected in tension into the tensioning system.
3. Load cells connected into the tensioning system, so the action of the tensioning operation imparts a compressive force to the sensing element.
4. Digital readouts connected to a pressure transducer to measure force from the pressure applied to the hydraulic jack.
5. Force computed from the actual elongation of the strand based on its physical properties and compensation adjustments.

For pretensioned members, establish independent references adjacent to each anchorage to indicate any yielding or slippage that may occur between the time of initial stressing and final release of the cables.

Stressing of strands for pretensioned members or tendons for post-tensioned members may be from one end, unless otherwise indicated. However, if there is a discrepancy of more than 5% between stresses in the strand or tendon, as computed from the elongation measurement and those indicated by gauge readings, perform jacking from both ends.

615.08 Pretensioning Procedure

Apply to each cable the amount of stress shown on the Plans. Perform pretensioning by either the single strand or multi-strand jacking method.

When prestressing is performed by the multi-strand jacking method, bring the cables to a uniform initial tension of approximately 5,000 pounds before applying the full pretensioning stress. Measure the initial tension of each cable by a dynamometer or other approved means.

After the initial tensioning, stress the cables until the required elongation and jacking pressure are attained and reconciled within the limits specified in **615.07**.

Tension the deflected pretensioned strands by either partially jacking at the end of the bed followed by raising or lowering the strands to their final position, or entirely by jacking, with the strands being held in their final position during the jacking operation.

Tension the deflected strands so that the final tension in all parts of the strand is uniform and provide means to reduce frictional forces at the bend points to a minimum.

When strands are deflected after partial tensioning, raise or depress the strands simultaneously at all points or in an approved specific sequence.

Obtain the Engineer's approval of strand splicing methods and devices. When using single strand jacking, provide only one splice per strand. When using multi-strand jacking, either splice all strands or no more than 10% of the strands. Spliced strands shall be similar in physical properties, from the same source, and shall have the same "twist" or lay. Locate all splices outside of the prestressed units.

The Engineer may accept wire failures, provided not more than one wire in any strand is broken and the area of broken wires does not exceed 2% of the total area of the strands.

After final stressing, all strands shall be positioned as shown on the Plans, and the stress in the strands shall be uniformly distributed throughout the bed length.

With the cables stressed in accordance with the Plan requirements and the foregoing Specifications, and with all other reinforcing in place, cast the members to the lengths specified. Maintain cable stress between anchorages until the concrete reaches the compressive strength specified in **615.09**.

615.09 Proportioning and Mixing of Concrete

Proportion Class P concrete as specified in Table 615.09-1.

615.09

Table 615.09-1: Class P Concrete

Class of Concrete	Minimum 28-Day Compressive Strength (psi)	Minimum Cement Content (pound per cubic yard)	Maximum Water/Cement Ratio (pound/pound)	Air Content % (Design ± production tolerance)	Slump or Slump Flow (inches)
P	5,000 ⁽¹⁾	658	0.45	0-8 ⁽²⁾	2 ± 1 ⁽³⁾
P-SCC ⁽⁴⁾	5,000 ⁽¹⁾	658	0.45	0-6 ⁽²⁾	26 ± 5

⁽¹⁾ Or as shown on the Plans or approved shop drawings.

⁽²⁾ Air entraining is optional with the Contractor, unless otherwise shown on the Plans or shop drawings.

⁽³⁾ Not to exceed 3 inches before the addition of high range admixtures, and not to exceed 10 inches after the addition of high range admixtures. If water-cement ratio is equal to or less than 0.35 then the maximum slump is 10 inches. If the water-cement ratio is 0.36 – 0.45, the maximum slump is 8 inches.

⁽⁴⁾ Maximum coarse aggregate size of a No. 67 stone.

Comply with all applicable provisions of **604.03** except as modified herein.

Submit a concrete mix design template in accordance with Departmental procedures for review and approval. Do not use calcium chloride.

Handle, measure, and batch materials; mix concrete; and comply with the limitations of mixing as specified in **604**.

Make concrete test specimens for Class P and Class P-SCC, in accordance with AASHTO T 23 and ASTM C1758 respectively, to determine the adequacy of the concrete design and the minimum time at which the stress may be applied to the concrete. Cure the test specimens used to determine the time at which stress may be applied in the same manner and under the same conditions as the bridge members. The initial curing of specimens to determine the design strength of the concrete shall be as specified above with additional curing water, as provided in AASHTO T 23. The compressive strength of the concrete will be determined from the average strength of at least two representative test specimens made and cured as specified above and tested in accordance with AASHTO T 22. The frequency of sampling and testing will be in accordance with Departmental procedures.

615.10 Handling, Placing, and Consolidating Concrete

A. Handling and Placement

Handle and place concrete for prestressed bridge members as follows:

1. Before placing any concrete, clean the forms of construction debris and other extraneous matter. Place and secure the reinforcing bars, of the size and type specified, as shown on the Plans.
2. Place concrete in the forms immediately after mixing. Do not use any concrete that does not reach its final position in the forms within 30 minutes after adding the cement to the mix. Place the concrete to prevent segregation of the materials and displacement of the reinforcement.
3. Use metal or metal-lined open troughs and chutes and keep them clean and free from hardened concrete. Discharge water used in flushing clear of the forms.
4. Keep the temperature of forms, headers, cables, reinforcing bars, or other steel that comes in contact with freshly placed concrete to below 110 °F during casting operation, except keep forms for deck panels below 90 °F.
5. Do not begin to place concrete if the ambient temperature is below 26 °F; and if the ambient temperature falls below 26 °F during the placement of concrete, discontinue the placement as soon as practicable.
6. Do not begin placing concrete during precipitating weather; and if precipitating weather occurs during the pouring operation, only leave the area where the concrete is being placed uncovered. Limit this uncovered area to no more than 10 feet of bed length.
7. Do not deposit any concrete until the Engineer has inspected and approved the placement of the reinforcement, conduits, anchorages, and prestressing steel. Clean all exposed steel of all concrete, other than light deposits of cement paste, immediately after placing and consolidation is completed.

615.11

B. Consolidation

During and immediately after the placing operation, consolidate the concrete with vibrators and suitable spading tools. Apply vibration at the point of deposit and in the area of freshly deposited concrete. The vibrators used may be internal or external or a combination of both. Vibrate for a sufficient duration and intensity to compact the concrete thoroughly, but so as not to cause segregation. Place concrete in the precast units in one continuous operation for each unit, except for the minimum delay required for installing voids.

Deposit and consolidate the concrete so that the concrete will be smooth and dense and free from honeycomb and pockets of segregated aggregates.

615.11 Removing Forms, Finishing, and Curing

A. Removing Forms

The Contractor may remove side forms after 6 hours, where the removal of forms will not cause distortion of the hardened concrete. Do not remove the members from the bottom forms until they have been stressed sufficiently to sustain all forces and bending moments that may be applied during handling.

B. Finishing

Finish all formed surfaces of the bridge members as specified in **604.22** or other methods when approved by the Engineer. Finish roadway surfaces of the members as specified in **604.21.C**. Transversely score the top surface of members that will not become a part of the roadway surface with a stiff wire brush, or by other approved methods. After removing hold down devices from the bottom of the beams, coat the resulting holes with an approved bonding compound and plug with mortar.

C. Curing

Cure the bridge members by the water method or by steam curing as specified below. The Contractor may use other methods, provided the details of the proposed methods are submitted to the Engineer and approved.

1. **Water Curing.** As soon as the concrete has hardened to a degree that the finish will not be harmed, perform water curing as follows:
 - a. Cover the member with a pre-dampened material suitable for use with the water cure.
 - b. Keep continuously and thoroughly wet until the member has attained the strength required for stress transfer with a minimum curing time of 24 hours.

Do not cure using the water method when the ambient temperature is expected to drop below 45 °F.

2. **Steam Curing.** Perform steam curing as follows:
 - a. After placing and vibrating the concrete, wait until the member attains initial set, 2 to 4 hours, or 4 to 6 hours if a set retarder has been used, before applying steam. If the ambient air temperature is below 50 °F, apply enough steam during the delay period to hold the air surrounding the member at a minimum temperature of 50 °F and a maximum of 10 °F greater than the temperature of the concrete at placement.
 - b. To prevent moisture loss on exposed surfaces during the delay period, cover members as soon as possible after casting or keep the exposed surfaces wet by fog spray or wet blankets.
 - c. Perform steam curing beneath suitable enclosures that will allow free circulation of steam about the sides, ends, and tops of members, and that will contain the live steam with a minimum moisture loss. The Contractor may use tarpaulins or similar flexible covers, provided they are kept in good repair and secured in a manner that will prevent the loss of significant steam and moisture.
 - d. Steam at the jets shall be low pressure and in a saturated condition. Steam jets shall not impinge directly on the concrete, test cylinders, or forms. During application of the steam, the temperature rise within the enclosure shall not exceed 50 °F per hour. The curing temperature throughout the enclosure shall be not less than 90 °F nor more than 160 °F, and the relative humidity shall be not less than 95%. The difference in the

615.12

temperature adjacent to the concrete at different locations within the enclosure shall not exceed 20 °F at any time. Continue steam curing until the concrete has reached the required transfer strength. In discontinuing the steam, do not reduce the temperature within the enclosure more than 50 °F per hour until the temperature inside is within 10 °F of the temperature outside. The minimum time from the end of placement and finishing operations to the removal of required covers shall not be less than 12 hours.

- e. When curing has been done at elevated temperatures, begin to transfer the prestressing load after releasing the forms and discontinuing the steam and while the concrete is still hot in order to prevent cooling shrinking and cracking. If directed by the Engineer, cover members or otherwise protect them to cool the concrete slowly after release in order to prevent thermal shock and the evaporation of moisture in the members.
- f. Provide temperature recording devices that will provide an accurate continuous permanent record of the curing temperature. Provide a minimum of one recording device per 200 feet of continuous bed length with a minimum of two devices per bed.
- g. Leave side forms in place a minimum of 6 hours after the concrete is cast or until the concrete has set sufficiently to withstand damage when the forms are removed. When the side forms are removed during the curing cycle, only remove the minimum area of the curing enclosure that is necessary to remove each individual form section area in the enclosure. Immediately close the open area in the enclosure as each form section is removed.
- h. When the temperature is not expected to rise above 32 °F, protect the beams from freezing temperatures until the design strength is reached.

615.12 Post-Tensioning Procedure

When post-tensioning, set the anchor plates normal in all directions to the axis of the steel. In all stressing operations, keep the stressing forces symmetrical about the vertical axis of the member. Do not begin tensioning

until the concrete has reached a compressive strength of at least 3,500 pounds per square inch, unless otherwise shown on the Plans.

The amount of tensioning to be retained in each post-tensioned unit after anchorage shall be as shown on the Plans. Apply a slight overstress, as determined in the field, to overcome friction between steel and enclosure and to allow for relaxation of the anchorage.

Tension the units until the required elongations and jacking pressures are attained and reconciled within the limits specified in **615.07**, with such overstress as approved by the Engineer for anchorage relaxation. Then allow the male anchorage element to be driven home by the jack action.

Conduct the tensioning process so that the tension being applied, and the elongation of the prestressing elements may be measured at all times. Determine the friction loss in the element, i.e., the difference between the tension at the jack and the minimum tension, in accordance with the current edition of AASHTO Standard Specification for Highway Bridges.

615.13 Combined Prestressing and Post-tensioning

If the members are manufactured with part of the reinforcement pre-tensioned and part post-tensioned, comply with the applicable portions of the requirements specified above for each part.

615.14 Transfer of Stress

Do not transfer the stress to the bridge members until the compressive strength of the test specimens is 4,000 psi or greater, unless otherwise shown on the Plans.

Before transferring any stress to the bridge members, obtain the Engineer's approval of the pattern and schedule for releasing the strands. Strip or loosen forms that tend to restrict the horizontal or vertical movement of the member prior to stress transfer.

Transfer stress by either the multiple strand release method or the single strand release method.

When the multiple strand method of release is used, gradually and simultaneously release either a symmetrical group of strands or all the strands. Remove the load on the strands from the anchorage and place on the

615.15

jacking system. Gradually release the jack or jacks until the strands are relaxed.

When the single strand release method is used, heat strands with a low oxygen flame played along the strand for a minimum of 3 inches until the metal gradually loses its strength and allows the strand to slowly pull itself apart. Apply heat at such a rate that failure of the first wire in each strand will not occur until at least 5 seconds after heat is first applied. Release the strands in the sequence of the approved pattern and schedule of release.

615.15 Handling and Installation

Prepare an erection plan in accordance with **602.42** and with the requirements of this Subsection.

The Contractor may handle all members immediately after completion of stressing. If the stressing is not done in a continuous operation, do not handle members before they are sufficiently stressed, as determined by the Engineer, to sustain all forces and bending moments due to handling. When handling members, maintain them in an upright position at all times and pick them up from the points designated on the Plans.

The Contractor may incorporate the members into the bridge structure at any time after completion of stressing and grouting, provided representative test specimens indicate that the concrete in the members has attained the design strength specified in **615.09**, unless a minimum beam age is shown on the Plans.

Do not ship any beams from the fabrication plant for incorporation into a structure until the Department has formally accepted the beams in accordance with Departmental procedures.

Erect all prestressed beam members and establish the grade of the roadway on the bridge before starting to form for the bridge deck, unless otherwise shown on the Plans or approved by the Engineer.

If the Contractor wishes to start forming for the bridge deck before all beams have been erected, and the Plans do not preclude this practice, first obtain written approval from the Structures Division before constructing any forms.

615.16 Grouting

Equip conduit, used for installing the bars or cables through post-tensioned members, with approved grouting vents. After completion of stressing, grout the space between sides of bar or cable and sides of conduit as specified in **616.09**.

Clean recesses in girders at the ends of diaphragm bars, holes left by form ties, or all other surface irregularities, and patch with an approved epoxy grout.

615.17 Tolerances

Unless otherwise specified, standard sections shall meet the manufacturing tolerances specified in Table 615.17-1. Any variation beyond these tolerances will be subject to the Engineer's approval.

615.18

Table 615.17-1: Manufacturing Tolerances in Standard Sections

Description	Tolerance	
	I-Sections	Box Sections
Nominal Depth	± ½-inch	± ½-inch
Nominal Width	± ½-inch	± ½-inch
Nominal Length	Computed Elastic Shortening ±1/2-inch	Computed Elastic Shortening ±1/2-inch
Variation in Straightness, inches	¼-inch x (Total Length in feet)/10	¼-inch x (Total Length in feet)/10
Variation in Camber, inches	Beams in any 1 span not more than: 1/8-inch x (Total Length in feet)/10	Beams in any 1 span not more than: 1/8-inch x (Total Length in feet)/10
Location of Voids	-----	Length ± ½-in Wall Thickness ± ½-in
Bearing	Full Bearing – Full Width of Beam	Full Bearing on at Least 2/3 of Width of Beam
Tendon Placement	± ½-inch	± ½-inch
Reinforcing Steel Placement	± ½-inch	± ½-inch
Reinforcing Steel Concrete Cover	± ½-inch	± ½-inch
Reinforcing Steel Splice Lengths	Minus 1-1/2-inches	Minus 1-1/2-inches

COMPENSATION

615.18 Method of Measurement

The Department will measure structural members by the linear foot of precast/prestressed concrete structural members of the several types and sizes installed, complete in place. The Department will determine the linear measurement from the nominal lengths shown on the Plans.

615.19 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Prestressed Concrete I-Beam (Type)	Linear Feet
Prestressed Concrete Bulb Tee Beam (Size)	Linear Feet
Precast Concrete Beam (Description)	Linear Feet
Prestressed Concrete Box Beam (Size)	Linear Feet
Prestressed Concrete Beam (Size, Description)	Linear Feet
Concrete Channel (Size)	Linear Feet

If the Engineer allows concrete that does not meet the specified strength to remain in the permanent construction, the Department will adjust the bid price in accordance with **604.31**.

616.01

SECTION 616 – POST-TENSIONED PRESTRESSED CONCRETE

616.01 Description	634
616.02 Prestressing Methods	634
616.03 Materials	635
616.04 Reserved.....	635
616.05 Protection and Installation of Prestressing Steel	635
616.06 Anchorages and Distribution.....	637
616.07 Ducts	638
616.08 Prestressing	639
616.09 Bonding and Grouting.....	641
616.10 Form Work	644
616.11 Sampling and Testing.....	644
616.12 Method of Measurement	644
616.13 Basis of Payment.....	644

DESCRIPTION

616.01 Description

This work consists of prestressing cast-in-place concrete by furnishing, placing, and tensioning prestressing steel in accordance with the Plans and these Specifications, and furnishing and installing all appurtenant items necessary for the particular prestressing system to be used, including ducts, anchorage assemblies, prestressing steel, and grout.

616.02 Prestressing Methods

Perform prestressing using post-tensioning methods.

Submit to the Engineer for review and approval complete details of the proposed method, materials, and equipment to use in the prestressing operations, including any additions or rearrangement of reinforcing steel from that shown on the Plans. Such details shall outline the method and sequence of stressing and shall include complete specifications and details of the prestressing steel and anchoring devices, working stresses, bursting stresses, anchoring stresses, type of ducts, and all other data pertaining to the

prestressing operation, including the proposed arrangement of the prestressing steel in the members, pressure grouting materials, and equipment. Do not cast any member to be prestressed until the Engineer approves the shop detail drawings.

MATERIALS

616.03 Materials

Provide materials as specified in:

Portland Cement (Type I or III)	901.01
Prestressing Reinforcement Steel and Anchorages	907.04
Water	921.01

All components of the post-tensioning system shall be certified to meet the Post-Tensioning Institute (PTI) *Acceptance Standards for Post-Tensioning Systems*.

616.04 Reserved

CONSTRUCTION REQUIREMENTS

616.05 Protection and Installation of Prestressing Steel

Locate the prestressing steel in the girder stems with an equal force in each stem. At the Contractor's option, the prestressing force may vary 5% from the theoretical equal force per girder provided the required total force is obtained and the force is distributed symmetrically about the centerline of the typical section. Tension stressing units a few at a time in each girder to minimize stress differentials. Obtain the Engineer's approval of the stressing sequence.

Protect prestressing steel against physical damage and rust or other results of corrosion at all times. Do not use prestressing steel that is physically damaged. Light surface rust is not a cause for rejection.

Package prestressing steel in containers or other shipping forms to protect the steel against physical damage and corrosion during shipping and storage. Place an approved corrosion inhibitor in the package or form. Alternatively, the Contractor may use a corrosion inhibitor carrier type packaging material

616.05

or, when allowed by the Engineer, may apply corrosion inhibitor directly to the steel. Ensure that the corrosion inhibitor will have no deleterious effect on the steel or concrete or bond strength of steel to concrete. Immediately replace or restore to original condition all damaged packaging or forms.

If choosing to use a corrosion inhibitor carrier type packaging material, ensure that the material conforms to Federal Specification MIL-P-3420.

Mark the shipping package or form with a statement that the package contains high-strength prestressing steel that should be handled with care. Also identify the type, kind, and amount of corrosion inhibitor used, including the date when placed, safety regulations, and instructions for use.

Submit the following for the corrosion inhibitor:

1. A sample, a list of chemicals and their proportions, and instructions for use.
2. Evidence that the prestressing steel will be protected from rust and other results of corrosion.
3. A certificate of compliance.

When acceptable prestressing steel for post-tensioning is installed in ducts after completion of concrete curing, complete the stressing and grouting within 10 calendar days after installing the prestressing steel. Rust that may form during these 10 days will not be cause for rejection of the steel. If prestressing steel is installed, tensioned, and grouted within 10 calendar days after concrete curing, it is not necessary to use a corrosion inhibitor in the duct following installation of the prestressing steel. If prestressing steel is installed as specified above but is not grouted within 10 calendar days, use an approved corrosion inhibitor in the duct. Ensure that the corrosion inhibitor is maintained at an effective level until grouting is complete.

Do not make any welds or grounds for welding equipment on the forms or on the steel in the member after the prestressing steel has been installed.

Place tendons in rigid ducts after completing concrete placement. Provide ducts as shown on the Plans and as specified in **616.07**.

616.06 Anchorages and Distribution

Anchor post-tensioned prestressing steel at the ends using approved permanent type anchoring devices capable of producing a stress of not less than 95% of the guaranteed minimum tensile strength of the prestressing steel.

Distribute the load from the anchoring device to the concrete using approved devices.

Place bearing plates normal to the tendon path and tight against forms. Brace and anchor forms to support the weight of the bearing plates.

Use approved plates and assemblies that conform to the following requirements:

1. The final unit compressive stress on the concrete directly underneath the plate or assembly shall not exceed 3,000 pounds per square inch.
2. Bending stresses in the plates or assemblies induced by the pull of the prestressing shall not exceed the yield point of the material or cause visible distortion in the anchorage plate when 100% of the ultimate tensile strength is applied as determined by the Engineer.

If the anchoring device is sufficiently large and is used in conjunction with a steel grillage embedded in the concrete that effectively distributes the compressive stresses to the concrete, the Contractor may omit steel distribution plates or assemblies.

Where the end of a post-tensioned assembly will not be covered by concrete, recess the anchoring devices so that the ends of the prestressing steel and all parts of the anchoring devices will be at least 2 inches inside of the end surface of the members, unless a greater embedment is shown on the Plans. Following post-tensioning, fill the recesses with grout, and finish flush. Use a suitable corrosion inhibitor to protect exposed anchorage hardware before final embedment in concrete.

Include complete details of jacking chairs in fabrication drawings to allow verification of proper reinforcement clearances.

616.07

616.07 Ducts

Use mortar-tight ducts that are sufficiently rigid to maintain their shape and alignment during concrete placement and grout installation. Ducts shall remain water tight. Use ducts having the following minimum wall thicknesses:

1. High Density Polyethylene (HPDE): 2.0 millimeter
2. High Density Polypropylene (HDPP): 2.0 millimeter

For tendons composed of single prestressing bars, provide ducts with a minimum internal duct diameter of at least $\frac{1}{4}$ inch larger than the outside diameter of the prestressing bar. For multiple wire, bar, or strand tendons, provide a duct nominal internal cross-sectional area of at least 2.25 times the net area of the prestressing steel.

Make positive joints between duct sections. Do not make angles at the joints. Use waterproof tape at the joints. Bend ducts without crimping or flattening. Use ferrous metal or polyethylene couplings to connect ducts to anchoring devices.

Protect ducts against crushing, excessive bending, dirt contamination, and corrosive elements, during transport, storage, and handling of ducts.

In case of damage to a duct, seal it with tape, or splice a duct coupler over the damaged section to form a seal that prevents cement paste from entering the duct during the placement of concrete and that prevents leakage during grouting operations.

Provide all ducts and anchorage assemblies with inlets for the injection of grout into the duct after prestressing according to the *PTI Guide Specification for Grouting of Post-Tensioned Structures*.

Provide all ducts with outlets to allow the escape of air, water, grout, and bleed water according to the *PTI Guide Specification for Grouting of Post-Tensioned Structures*.

Provide inlets and outlets with an inner diameter of at least $\frac{3}{4}$ -inch for strand tendons and of at least $\frac{3}{8}$ inch for single bar tendons. Extend the length of outlets a sufficient distance out of the concrete member to allow for the proper closing of the outlets.

Place inlets and outlets, at a minimum, in the following locations:

1. The anchorage area of the tendon;
2. All high points of the duct, when the vertical distance between the highest and lowest point is more than 2 feet; and
3. At major changes in the cross-section of the duct, such as couplers and anchorages.

In addition, place:

1. An inlet at or near the lowest point of the tendon;
2. A free draining outlet at all low points of the duct; and
3. An outlet at a distance less than 3 feet downstream from high point outlets.

Show all inlet and outlet locations on drawings.

Provide positive mechanical shut-off valves for all inlets and outlets. Provide inlets and outlets with valves, caps, or other devices capable of withstanding the grouting pressure.

Securely fasten ducts in place to prevent movement. Maintain distances from the forms by stays, blocks, ties, hangers, or other approved supports. Use precast blocks. Space all duct supports in accordance with the *PTI Guide Specification for Grouting of Post-Tensioned Structures*. Cover the ends of ducts to prevent the entry of water or debris.

Connect inlets and outlets to the duct with metallic or plastic structural fasteners. Do not use components that react with the concrete, cause corrosion of the prestressing steel, or contain water-soluble chlorides.

616.08 Prestressing

Tension prestressing steel using hydraulic jacks so that the force in the prestressing steel is not less than the value shown on the Plans. Do not perform stressing on a single strand pull. Use a jack that is capable of making a multiple pull on all strands in a tendon.

616.08

Unless otherwise specified or shown on the Plans, the stress in the prestressing steel after all losses shall not exceed 80% of the yield point stress of the prestressing steel. The maximum temporary tensile stress (jacking stress) in the prestressing steel shall not exceed 90% of the yield point stress of the prestressing steel. Anchor the prestressing steel at stresses (initial stress) that will result in the ultimate retention of working forces of not less than those shown on the Plans, but in no case shall the initial stress at the anchor exceed 70% of the specified minimum ultimate tensile strength of the prestressing steel.

Working force and working stress will be considered as the force and stress remaining in the prestressing steel after all losses, including creep and shrinkage of concrete, elastic compression of concrete, relaxation of steel, losses in post-tensioned prestressing steel due to sequence of stressing, friction and take up of anchorages, and all other losses peculiar to the method or system of prestressing have taken place or have been provided for.

The loss in stress due to all causes in post-tensioned prestressing steel shall be in accordance with the AASHTO LRFD Bridge Design Specifications designated on the Plans.

Equip each jack used to stress tendons with either a pressure gauge or a load cell for determining the jacking stress. Use a pressure gauge that has an accurately reading dial at least 8-inches in diameter. Calibrate each jack and its gauge as a unit with the cylinder extension in the approximate position that it will be at final jacking force. Keep a certified calibration chart with each gauge. Ensure that each gauge is capable of reading loads directly in pounds or is accompanied by a chart from which the dial reading can be converted to pounds.

If a load cell is used, calibrate it and provide it with an indicator that will allow determination of the prestressing force in the tendon. Do not use the lower 10% of the manufacturer's rated capacity of the load cell to determine the jacking stress.

Provide means for measuring the elongation of reinforcement to at least the nearest 1/16-inch.

The Engineer may check the certified calibration charts for the hydraulic jacks, pressure gauges, or load cells used for tensioning prestressing steel before and during tensioning operations.

Prior to placing forms for closing slabs of box girder cells, demonstrate to the satisfaction of the Engineer that all ducts are unobstructed.

Except as herein provided, do not prestress cast-in-place concrete until at least 10 days after the last concrete has been placed in the member to be prestressed and until the compressive strength of the last placed concrete has reached the strength specified for the concrete at the time of stressing.

Conduct the tensioning process so that the tension being applied, and the elongation of the prestressing steel may be measured at all times. Keep a record of gauge pressures or load cell readings and elongations for each tendon stressed.

Use elongation measurements as the primary control of the stressing operation; however, ensure that the hydraulic pressure gauge readings or the load cell readings at the time of the measured net elongation are within 5% of the calculated gauge or load cell reading for that particular elongation. If the gauge or load cell pressure readings vary by more than 5% from their calculated reading, stop all work and correct the defect before proceeding. A variance of more than 5% may be cause for jacking at both ends.

Tension prestressing tendons in continuous post-tensioned members by jacking at each end of the tendon unless otherwise shown on the Plans. Such jacking of both ends need not be done simultaneously. When approved by the Engineer, the Contractor may tension bent cap tendons by jacking from one end only.

The Contractor may tension prestressing tendons in single span post-tensioned members by jacking from one end only. When tensioning is done from one end only, tension half of the prestressing steel in each member from one end of the span and the other half from the opposite end, unless otherwise allowed by the Engineer.

616.09 Bonding and Grouting

Provide Class A, B, C, or D grout as specified in the *PTI Guide Specifications for Grouting of Post-Tensioned Structures*. Bond all post-tensioned prestressing steel to the concrete by filling the void space between the duct and tendon with grout according to the PTI Guide.

Provide prestressing steel that is free of dirt, loose rust, grease, or other deleterious substances.

616.09

Perform all grouting operations using staff with grouting experience on projects of a similar type and magnitude. Perform grouting operations under the immediate supervision of an individual skilled in various aspects of grouting and who is certified by the American Segmental Bridge Institute (ASBI) Grouting Certification or equivalent certification program, approved by the Engineer. Furnish the name of the grouting operations supervisor and proof of their ASBI certification and grouting experience to the Engineer before beginning grouting operations.

Make available on-site, before beginning grouting operations, all the required testing equipment for checking grout workability (flow-cone), temperatures, and other specified tests.

Provide written certification that all ingredients used in the grout meet the ASTM requirements contained in the *PTI Guide Specification for Grouting of Post-Tensioned Structures*. This includes, but is not limited to, the following:

- Cement mill test reports;
- Mineral additives test reports;
- Chemical admixtures reports; and
- Test reports for any other ingredients used in the grout.

For prepackaged grouts, provide the manufacturer's current certified mill test reports for the product.

Use grouting equipment capable of continuous operation with little variation of pressure, which includes a system for recirculating the grout while actual grouting is not in progress. Use grouting equipment capable of maintaining a pressure on completely grouted ducts and fitted with a valve that can be locked off without loss of pressure in the duct.

Do not use compressed air to aid in the pumping of grout.

Provide grout pumps of a positive displacement type, capable of providing a continuous flow of grout, and capable of maintaining an outlet pressure of at least 150 pounds per square inch and with a pressure gauge having a full-scale reading of not more than 300 pounds per square inch.

Determine the flowability of the grout according to ASTM C939. The efflux time of a grout sample immediately after mixing shall be between 11 and 30 seconds. Do not begin grouting until this test is passed. When hot weather

conditions may cause quick setting of the grout, cool the grout by approved methods, as necessary, to prevent blockages during pumping operations. When freezing weather conditions are possible during and following placement of grout, protect the grout from damage by freezing according to the *PTI Guide Specification for Grouting of Post-Tensioned Structures*.

Provide a supply of potable water and standby flushing equipment capable of developing a pumping pressure of 250 pounds per square inch and of sufficient capacity to flush out any partially grouted ducts.

Clean ducts of all material that would impair bonding of the grout or interfere with grouting procedures. Blow out each duct with compressed, oil-free air. Check all inlets and outlets for their capacity to accept injection of grout by blowing compressed, oil-free air through the system, and proving each inlet and outlet in turn.

Pass all grout through a screen with 1/8-inch maximum clear openings before entering the grout pump. Open all grout vents before the start of grouting. Completely fill the duct by injecting grout from the lowest end of the tendon in an uphill direction. Pump grout continuously through the duct and waste at the outlet until no visible slugs of water or air are ejected, and the efflux time of the ejected grout is between 11 and 30 seconds. Maintain a continuous, one-way flow of grout within a grouting stage.

Close all outlets in a similar manner one after the other in the direction of the flow. For outlets placed a short distance downstream from a high point, close that outlet before its associated high point outlet. Increase the grouting pressure at the injection end to at least 100 pounds per square inch and hold for at least 10 seconds. Do not remove or open valves and caps until the grout has set.

Abrasive blast-clean the concrete surface of recessed anchorage assemblies. Fill anchor recesses with concrete conforming to the requirements for the structure, and finish flush.

Remove ends of vents 1 inch below the roadway surface after grouting has been completed. Permanently seal all recess areas.

Do not release the falsework under the bottom slab supporting the superstructure until at least 48 hours after grouting of the post-tension prestressing steel or until the grout strength is obtained.

616.10

616.10 Form Work

Do not remove falsework until all prestressing is complete and the structure has been post-tensioned to the Engineer's satisfaction.

616.11 Sampling and Testing

Provide the following to the Engineer well in advance of anticipated use:

1. Furnish one sample of each size strand for each reel in accordance with Departmental procedures.
2. Test one completely fabricated tendon at a laboratory approved by the Department and furnish a notarized letter to the Division of Materials and Tests from the laboratory stating that no deformation has occurred in the anchor head and no slippage of strand has occurred at the wedges.

When prestressing systems have been previously tested and approved for similar projects by an agency acceptable to the Department, testing will not be required, provided the Contractor furnishes the Engineer with a notarized letter stating that the system is the same as a previously tested system.

COMPENSATION

616.12 Method of Measurement

The Department will measure prestressing of cast-in-place concrete by the lump sum as shown on the Plans.

The Department will not measure, and will consider incidental to the work, the furnishing and placing of additional deformed bar reinforcing steel required by the particular system used; ducts, anchoring devices, distribution plates or assemblies, and incidental parts; and the grouting of recesses and pressure grouting of ducts.

616.13 Basis of Payment

The Department will pay for prestressing cast-in-place concrete by the lump sum.

616.13

Such payment is full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all work involved in furnishing, placing, and tensioning the prestressing steel in cast-in-place concrete structures, complete in place, as shown on the Plans, as specified in these Specifications, and as directed by the Engineer.

If the Engineer allows the concrete that does not meet the specified strength to remain in the permanent construction, the Department will adjust the bid price in accordance with **604.31**.

617.01

SECTION 617 – BRIDGE DECK SEALANT

617.01 Description	646
617.02 Materials	646
617.03 Reserved.....	646
617.04 General.....	646
617.05 Weather Limitations.....	647
617.06 Membrane Application.....	647
617.07 Method of Measurement	649
617.08 Basis of Payment.....	649

DESCRIPTION

617.01 Description

This work consists of furnishing and placing a waterproofing system over a properly prepared concrete bridge deck for the purpose of protecting structural concrete from the deterioration caused by absorption of deicing salts and water.

MATERIAL

617.02 Materials

Provide materials as specified in:

Bridge Deck Sealant, System A or B..... **906.04**

617.03 Reserved

CONSTRUCTION REQUIREMENTS

617.04 General

To minimize the amount of construction traffic on the bridge deck seal after placement, do not install the seal until all major phases of roadway construction have been completed. Complete the roadway base and pavement up to the surface course before beginning installation of the bridge

deck seal. The construction of the bridge deck sealant and overlay may be performed concurrently with or after the roadway surface course.

Obtain the Engineer's approval of all methods used in performing the work before the work is started. If, at any time, the Engineer finds the methods to be unsatisfactory, make changes and improvements as required.

Protect concrete surfaces, structural steel, railing, passing vehicles, and similar surfaces from being defaced by sealant. Should defacement occur, clean surfaces on the structure to the Engineer's satisfaction. Assume sole responsibility and liability for damage to passing vehicles.

Limit traffic on the area being treated to the necessary workers and equipment to perform the work required. Maintain all other traffic on portions of the structure that are not being given the membrane protective coating. At all times, keep traffic off the membrane, and protect the membrane from damage. Repair damage that may occur by patching in a manner satisfactory to the Engineer.

617.05 Weather Limitations

Do not apply sealant during wet weather conditions, when the relative humidity exceeds 85%, or when the surface upon which the sealant is being placed or the ambient air temperature is below 50 °F. Ensure that the surface upon which the sealant is being placed is dry at the time of application.

617.06 Membrane Application

Before applying the membrane, ensure the bridge deck is clean from all debris that would interfere with the membrane adhering to the deck. Check the manufacturer's recommendations about tack/primer coat between the deck and membrane.

Apply the waterproofing membrane to form a butt joint with the face of the curbs. Place the membrane to achieve a shingling effect that will allow any accumulated water to drain toward the low curb or the drainpipes. Overlap each strip longitudinally and transversely a minimum of 4 inches or as recommended by the manufacturer. In all cases, begin the waterproofing at the low point of the surface to be waterproofed so that water will run over and not against the laps.

Operate the paving equipment in the direction of the transverse lap of the membrane.

617.06

Apply the prefabricated membrane to the bridge deck by either hand methods or mechanical applicators.

Use a wide tipped torch to cause tackiness or an adhesive if necessary, to ensure a good seal of the joints. Use hand rollers or other satisfactory pressure apparatus on the applied membrane to ensure firm and uniform contact with the bituminous overlay. Take special care at the curb face to ensure that the membrane uniformly adheres to the concrete. Apply a mastic, of the type specified by the manufacturer, to the butt joints at face of the curb as shown on the Plans. At all open joints, expansion joints, and at other joints as directed by the Engineer, apply the membrane to form a butt joint with the face of the joint, and apply mastic as shown on the Plans.

Ensure that the entire membrane is free of placement defects such as wrinkles, air bubbles, and fishmouths. Patch all torn or cut areas, or narrow overlaps, using a satisfactory adhesive and by placing sections of the membrane over the defective area so that the patch extends at least 6 inches beyond the defect. Roll or firmly press the patch onto the surface. Remove air bubbles, caused by the formation of vapor pressure or out-gassing under the membrane after placement, by puncturing the membrane and repairing the defective area in the manner specified above for cut and torn areas.

After completing the membrane waterproofing, cut the membrane with two right angle cuts at all deck drain pipes. Make the cuts to the inside diameter of the drain pipes, and then turn down the corners of the membrane waterproofing into the drains and lay them in a coating of mastic.

Begin applying the bituminous overlay immediately after completing the membrane placement.

Apply a bond coat of an acceptable adhesive to the surface of prefabricated membranes, if required, according to the membrane manufacturer's recommendations before placing the overlay.

Overlay the waterproofing system with asphaltic concrete of the type and in the quantity shown on the Plans.

All requirements of **Part 4** of these Specifications shall apply to this construction with the following revisions and additions:

1. The paving operation shall be in the same direction as the end laps of the membrane.

2. The requirements for automatic grade and slope controls on the paver will be waived.
3. The density requirements will be waived; however, all other applicable compaction requirements in **407.15** will apply. Give the first asphalt concrete lift a breakdown roll as soon as possible after the paving machine has passed.

Deposit, spread, and roll the overlay so as not to damage the membrane.

COMPENSATION

617.07 Method of Measurement

The Department will measure and pay for bridge deck sealant, complete in place, by the number of square yards of bridge deck and approach slabs covered.

The Department will measure and pay for tack coat, when used, and bituminous layers as provided for in **403**.

617.08 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Bridge Deck Sealant	Square Yard

Such payment is full compensation for the preparation of surfaces and furnishing and applying the waterproofing system complete in place.

619.01

**SECTION 619 – POLYMER MODIFIED CONCRETE
BRIDGE DECK OVERLAY FOR NEW AND EXISTING
BRIDGES**

619.01 Description	650
619.02 Materials	650
619.03 Proportioning	651
619.04 Equipment	651
619.05 Limitations	654
619.06 Hydro-Demolition	655
619.07 Cleaning	655
619.08 Mixing	655
619.09 Placing, Consolidating, and Finishing	656
619.10 Texturing	656
619.11 Curing	656
619.12 Reconstruction	657
619.13 Traffic Loading	657
619.14 Method of Measurement	658
619.15 Basis of Payment	658

DESCRIPTION

619.01 Description

This work consists of constructing a polymer modified concrete (PMC) bridge deck overlay for the purpose of protecting structural concrete from the deterioration caused by absorption of deicing salts and water.

MATERIALS

619.02 Materials

Provide materials as specified in:

Portland Cement (Type I or Type III)	901.01
Fine Aggregate (Natural Sand)	903.01

Coarse Aggregate (Size 7)	903.03
Water	921.01

Use a polymer that appears on the Department's QPL.

619.03 Proportioning

Proportion the polymer modified concrete mixture to meet the requirements in Table 619.03-1 and the following pre-determined proportioning values. Polymer admixture shall be at least 24.5 gallons per cubic yard. Fine aggregate shall be natural sand and proportioned within the range of 1505 to 1785 pounds per cubic yard. The coarse aggregate shall be proportioned within the range of 1176 to 1456 pound per cubic yard. Water, including free moisture on the sand and coarse aggregate, shall be proportioned within the range of 56 to 154 pounds per cubic yard.

Table 619.03-1: Composition of Polymer Modified Concrete Mixtures

Class of Concrete	Min 28-Day Compressive Strength (psi)	Min Cement Content (pound per cubic yard)	Maximum Water/Cement Ratio (pound/pound)	Air Content % (Design \pm production tolerance)	Slump (inches)
PMC	4,000 ⁽¹⁾	658 ⁽²⁾	0.40 ⁽³⁾	0-8	4-6 ⁽⁴⁾

⁽¹⁾ Or as shown on Plans

⁽²⁾ Use Type I or Type III Portland Cement

⁽³⁾ Considering all the non-solids as part of the water.

⁽⁴⁾ Slump shall be measured 4 to 5 minutes after discharge from a continuous mixer.

The polymer admixture shall contain a minimum of 46% solids. A concrete mix design is required for identifying constituent materials. Concrete shall not be placed until the mix design is approved. Do not change materials without the Engineer's written approval.

EQUIPMENT

619.04 Equipment

Obtain the Engineer's approval as to the design, capacity, and mechanical condition of all equipment and tools necessary for handling materials and

619.04

performing all parts of the work. Have the equipment onsite sufficiently ahead of the start of construction operations to allow for the Engineer's examination and approval.

A. Volumetric Continuous Mixers

Produce PMC overlay in a volumetric continuous mixing plant provided that the manufacturer's equipment meets the tolerance requirements of **604.11**. Use a volumetric continuous mixing plant that conforms to the following:

1. The unit shall be equipped with:
 - a) Calibrated proportioning devices for each material added to the concrete mix and perform mixing by a continuous auger and/or paddles.
 - b) Proportioning controls that may be set and secured for different materials and mixes.
 - c) Recording meter that is visible at all times and furnishes a ticket printout with the calibrated measurement of the mix being produced.
 - d) Separate bins and gate openings for each type of material, including a watertight storage bin for cement. Cover the aggregate bins with tarpaulins or by other approved methods when required.
2. The unit shall have a stamped plate from the Volumetric Mixer Manufacturers Bureau (VMMB) stating the equipment conforms to ASTM C685. The plate shall be attached in a prominent place and have the following plainly marked: the gross volume of the transportation unit in terms of mixed concrete, the discharge speed, and the mass calibrated constant of the machine in terms of volume.
3. The volumetric mixing plant shall be operated and calibrated by a Volumetric Mixer Operator certified by VMMB and holds a TDOT Concrete Field Testing Technician Certification or equivalent. In the presence of the Engineer, perform the calibration of gate settings according to the manufacturer's recommendations for the mix design to be used before starting work. The calibration procedure shall account for the moisture content of the aggregates. The yield

shall be maintained within a tolerance of plus or minus 1% and verified using a minimum 2 cubic feet container every 50 cubic yards. Recalibrations will be necessary when indicated by the yield checks, and at any other times the Engineer deems necessary to ensure proper proportioning of the materials.

4. Provide equipment necessary for TDOT to perform tests to determine moisture and gradations of aggregates in accordance with SOP 1-1. If gradations are out of tolerance or aggregate moisture content varies by 5% or more, additional yield checks and/or calibration will be required.

If the mixer fails to discharge a uniform mix at any time, production of concrete shall cease until any problems are corrected.

Each load of concrete produced by a volumetric continuous mixing plant shall be accompanied by a Concrete Delivery Ticket. The ticket shall include as a minimum the following:

- a. Date
- b. Contract number
- c. County
- d. Class of concrete
- e. Concrete design number
- f. Number of cubic yards
- g. Load number
- h. Truck number
- i. Maximum water allowed by design
- j. Total water added
- k. Water-cementitious materials ratio
- l. Time loaded
- m. Time discharged
- n. Signature of producer's VMMB Certified Volumetric Mixer Operator

B. Placing and Finishing Equipment

Provide hand tools for placing and brushing-in freshly mixed polymer modified concrete and for distributing it to approximately the correct level for striking-off with the screed.

Use an approved finishing machine complying with the following requirements for finishing large areas of work.

619.05

1. Use a self-propelled finishing machine capable of forward and reverse movement under positive control. Provision shall be made for raising all screeds to clear the screeded surface for traveling in reverse.
2. The Contractor may use a self-propelled finishing machine equipped with one or more rotating rollers, augers, and 1,500 to 2,500-vpm vibratory pans.
3. The machine shall be of the vibrating-screed type designed to consolidate the modified composition by vibration. Vibration frequency shall be variable with positive control between 3,000 and 11,000 vibrations per minute. The bottom face of the screeds shall be not less than 4 inches wide and shall be metal covered. The screeds shall have positive control of the vertical position.
4. Provide and use a suitable portable lightweight or wheeled work bridge behind the finishing operation.

CONSTRUCTION REQUIREMENTS

619.05 Limitations

On new structures, deck concrete shall be in place and properly cured before starting overlay operations. Overlay operations may begin as soon as the concrete has gained sufficient strength to resist damage from the blast cleaning.

Construct the overlay during favorable weather conditions. Place the mixture when the atmospheric temperature is between 55 and 75 °F. Place concrete in accordance with **604.16**. In all instances, place and keep the PMC overlay at a temperature above 45 °F for at least 96 hours after placement. Provide approved housing, heating, insulation methods, or some combination thereof, during cold weather. Do not place the mixture when the temperature is 85 °F or higher; when the wind velocity is high; when the relative humidity is extremely low; when rain is expected within the working period; or when any other atmospheric conditions cause difficulty in the satisfactory finishing, texturing, or curing of the overlay. This may require night work or other limited work periods. Keep PMC overlay aggregate and sand as cool as possible at the storage site during high temperatures to help prevent cracking in the new overlay.

619.06 Hydro-Demolition

Before placing the overlay, hydro-blast the concrete surface to be covered to the depth shown on the Plans. In areas where machine hydro-blasting cannot reach, in areas of spalling, and where steel reinforcement is exposed, remove deteriorated concrete to sound material using hand tools. Do not use pneumatic hammers heavier than a nominal 45 pounds.

After hydro-blasting, clear the deck of all debris. Do not allow traffic on the cleaned portion of the deck.

619.07 Cleaning

After hydro-blasting but before placing the overlay, power wash the entire area of the deck surface with a minimum 10,000-pound per square inch washing system to provide a bright, clean appearance that is free from laitance, dust, dirt, oil, grease, bituminous material, paint, and all other foreign matter. Perform the hydro-demolition of an area of the deck within the 24-hour period preceding the placement of the overlay on the area. Clean the existing deck using a process that will ensure conformance with the air and water pollution regulations applicable to the county or city where the site of work is located and with applicable safety and health regulations. Discontinue use of any method that does not consistently produce satisfactory work and conform to the above requirements and replace with an acceptable method. While cleaning, reasonably confine all debris of every type, including dirty water, resulting from the cleaning operation. Immediately and thoroughly clean such debris from the blast-cleaned surfaces and all other areas where any escaped debris may have accumulated.

Protect the cleaned areas, as necessary, against contamination before placing the overlay. Cover cleaned areas with a plastic cover that will be rolled up as the placement equipment passes over it so that the cleaned surface is not exposed to wheels, dirt, oil, grease, or any other contaminants. Re-clean contaminated areas and areas exposed more than 36 hours as directed by the Engineer at no cost to the Department.

619.08 Mixing

Mix concrete at the work site, where PMC is to be placed, in accordance with the specified requirement for the equipment used. Do not allow more than 5 minutes to elapse between the completion of mixing and the start of placement operations. Mixing capability shall be such that finishing

619.09

operations can proceed at a steady pace with final finishing completed before the formation of the plastic surface film.

619.09 Placing, Consolidating, and Finishing

The Contractor may vibrate and finish using approved hand methods in areas that are not accessible to the finishing machine.

Place and fasten screed rails in position to ensure the new surface will be finished to the required profile. Anchorage for supporting rails shall provide horizontal and vertical stability. Do not treat screed rails with parting compound to facilitate their removal.

While placing the PMC, have two water vacuums present for removing excessive water.

Finished surface smoothness shall comply with **604.27**.

619.10 Texturing

Form transverse grooves in the concrete overlay by mechanical texturing. Form the grooves at an appropriate time during the stiffening of the concrete mixture so that in the hardened concrete, the grooves will be between 0.09 and 0.13 inches in width; between 0.12 to 0.19 inches in depth; and will be spaced at random intervals between 0.3 and 1 inch. The grooves shall terminate approximately 18 inches from curbs, concrete parapets, barrier walls, or other vertical walls. The grooves shall be relatively smooth and uniform. Form the grooves without tearing the surface or without bringing pieces of the coarse aggregate to the top of the surface. Form grooves to drain transversely. Correct areas that do not conform to these requirements using approved methods at no cost to the Department.

619.11 Curing

Promptly cover the overlay surface with a single layer of wet burlap. Avoid using new burlap, as even when pre-soaked, it can dry out quickly. It may be necessary, at the Engineer's request, to wet the burlap and let it dry out, and then repeat this procedure several times to allow for total absorption. Use white plastic to cover the wet burlap.

Consistently spray a mist of water over the burlap before covering it with white plastic; however, ensure that the amount of water sprayed is not so excessive as to damage the fresh overlay surface.

Pull, place, and keep the white plastic within 10 to 30 feet of the front cover of burlap. Adjust these distances based on the weather conditions at the time of placement. Secure the plastic so that it will not blow off the burlap during the wet cure. Minimize the number of seams in the plastic.

Secure the plastic by using the rails, rolling over the edges of wet burlap onto the plastic, laying folded wet burlap transversely across the deck, or by keeping water on the surface of the plastic. Seal the plastic to prevent the wind from puffing up the plastic during the wet cure. Exercise caution when wetting down the surface of the plastic to prevent the water from running into the overlay being placed.

Place soaker hoses under the plastic once the overlay has set long enough to support the weight of the soaker hoses and after the overlay placement is completed. In hot weather, use cold water to enhance these procedures.

Place a plastic cover over the deck area after the deck has received hydro-demolition and the deck area has been cleaned. Remove the plastic as the PMC is being placed.

619.12 Reconstruction

Remove all areas of the overlay that either display a significant number of cracks or that are not intimately bonded to the underlying deck and replace with acceptable concrete at no cost to the Department. Seal all small cracks, which are not significant enough to require removal of the overlay, with a high molecular weight methacrylate sealant at no cost to the Department.

619.13 Traffic Loading

When Type I cement is used, do not allow traffic loading on the new PMC overlaid surface until it has undergone a 24-hour wet cure and 24-hour dry cure and has attained a compressive strength of 3,000 pounds per square inch.

When Type III cement is used, do not allow traffic loading on the new PMC overlaid surface until it has undergone a 12-hour wet cure and a 12-hour dry cure and has attained a compressive strength of 3,000 pounds per square inch.

619.14

COMPENSATION

619.14 Method of Measurement

The Department will measure PMC by the square yards in accordance with **109**.

The Department will measure PMC Variable Depth by the cubic yard complete in place, as determined by deducting the theoretical volume of Bridge Deck Overlay (PMC) from the total volume of PMC required to obtain the finished grade shown on the Plans or established by the Engineer.

619.15 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Bridge Deck Overlay (PMC)	Square Yard
Polymer Modified Concrete (Variable Depth)	Cubic Yard

Payment for Bridge Deck Overlay (PMC) is full compensation for placing and finishing the overlay, including providing all tools, labor, equipment, and incidentals for such placement. This item includes only the PMC for the theoretical plan depth of the overlay.

The Department will pay for accepted quantities of Polymer Modified Concrete (Variable Depth) at the invoice price of the materials delivered to the Project plus 5%. The invoice provided to the Department must reflect the producer's price used to establish the bid price for PMC and the total quantity of PMC purchased by the Contractor for the entire Project. All other costs associated with placing Polymer Modified Concrete (Variable Depth) are incidental to the price bid for Bridge Deck Overlay (PMC).

SECTION 620 – BRIDGE RAILINGS

620.01	Description.....	659
620.02	Materials	659
620.03	Reserved.....	659
620.04	Construction Methods	659
620.05	Method of Measurement	660
620.06	Basis of Payment.....	660

DESCRIPTION

620.01 Description

This work consists of furnishing and placing railings for bridges as covered by standard designs or as specially detailed, and includes all reinforcing steel, anchor bolts, or insert sleeves as detailed to support the railing.

MATERIALS

620.02 Materials

For the respective type of railing, provide materials as follows:

Concrete Parapet with Structural Tubing.....	STD-11-1
Concrete Parapet.....	STD-1-1 or STD-1-1SS
Concrete Rail	STD-7-1, STD-11-2

620.03 Reserved

CONSTRUCTION REQUIREMENTS

620.04 Construction Methods

A. Metal Railing

Construct steel or aluminum tubing according to the details shown on the Plans and the requirements specified in **602**. Where painting is required, meet the requirements of **603.06**, unless otherwise specified. No

620.05

painting will be required for aluminum or galvanized railing. Carefully adjust metal railing before bolting connections to ensure proper matching at abutting joints and correct alignment throughout the railing length. Set rail posts plumb, unless otherwise shown on the Plans.

B. Concrete Parapet and Concrete Railings

After all falsework has been struck, construct concrete parapet and concrete railings as specified in **604**. Exercise care to secure smooth and tight-fitting forms that can be rigidly held to line and grade and removed without damaging the concrete. Construct all moldings, panel work, and bevel strips as shown on the Plans with neatly mitered joints. All corners in the finished work shall be true, sharp, and clean-cut and shall be free from cracks, spalls, or other defects. Give all exposed surfaces a Class II or Applied Textured Finish as specified in **604.21**.

COMPENSATION

620.05 Method of Measurement

The Department will measure bridge railing of the type specified, in place, by the linear foot, overall dimensions.

620.06 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Aluminum Railing (Description)	Linear Feet
Steel Railing (Description)	Linear Feet
Concrete Parapet (Description)	Linear Feet
Concrete Parapet with Structural Tubing	Linear Feet
Timber Railing (Description)	Linear Feet
Concrete Railing	Linear Feet

Such payment is full compensation for furnishing all materials and constructing the railing of the type specified complete in place.

SECTION 621 – TEMPORARY STRUCTURES

621.01 Description.....	661
621.02 Construction.....	661
621.03 Method of Measurement.....	662
621.04 Basis of Payment.....	662

DESCRIPTION

621.01 Description

This work consists of constructing, maintaining, removing, and disposing of temporary structures and temporary shoring.

CONSTRUCTION REQUIREMENTS

621.02 Construction

Construct all temporary structures at the location and to the dimensions, grades, and load capacity shown on the Plans or in the Contract, or in accordance with drawings prepared by the Contractor and approved by the Engineer. Alternate design and details prepared by the Contractor must be equivalent to the design and details furnished by the Department. Prepare and submit alternate designs and details as specified in **105.02**.

Unless otherwise provided on the Plans or in the Contract, maintain temporary structures until the completion of the Contract or the opening of the permanent structure.

The maintenance of all temporary structures shall include their replacement in case of partial or complete failure. The Department reserves the right, in case of the Contractor's delay or inadequate progress in making repairs and replacement, to furnish such labor, materials and supervision of the work as may be necessary to restore the structure for proper movement of traffic. The Department will consider the entire expense of such restoration and repairs a part of the cost of the temporary structure and, where such expenditures are incurred by the Department, will charge them to the Contractor.

621.03

Unless otherwise noted on the Plans or in the Contract, upon completion and opening to traffic of the permanent construction, remove and dispose of the temporary structure, restore the area as nearly as possible to its original condition, and leave the area in a neat condition satisfactory to the Engineer.

Use temporary shoring to retain earth during grading operations and bridge construction to maintain traffic. Install temporary shoring at the locations shown on the Plans or as directed by the Engineer. The Department will not make payment for this item when used for the installation of drainage structures and utilities, to meet OSHA regulations, or for the Contractor's convenience, unless these locations are specifically shown on the Plans. Design the temporary shoring for the specific locations and in-situ soil types. The submittal shall be in accordance with **105.02**, shall be stamped by a Professional Engineer, licensed in the State of Tennessee, and shall include detailed drawings, design calculations, and shoring material requirements. Temporary shoring may consist of sheet piling, piling/lagging walls, tie back walls, and similar structures.

COMPENSATION

621.03 Method of Measurement

The Department will measure temporary structures by the unit (per each), completed, accepted, and satisfactorily removed at the designated time.

The Department will measure and pay for temporary shoring by the square foot of exposed vertical face area. The bottom of shoring for payment will be where the exposed face intersects the existing or specified grade. The top of shoring for payment will be the actual shoring top, but not more than 1 foot above where the back of shoring intersects the existing or specified grade.

621.04 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Temporary Structure (Description – Station)	Lump Sum (per Each)
Temporary Shoring	Square Feet

621.04

Such payment is full compensation for all designs, submittals, labor, tools, equipment, materials, and all other incidentals necessary to install and remove temporary structures and temporary shoring.

Unless otherwise indicated, all salvageable material obtained from the removal and reconditioning work shall remain the property of the Contractor.

622.01

SECTION 622 – SHOTCRETE

622.01 Description	664
622.02 Materials	664
622.03 Proportioning and Quality Assurance of Shotcrete	664
622.04 Preconstruction Test Panels	667
622.05 Production Test Panels	668
622.06 Test Panel Curing and Testing	668
622.07 Mixing and Batching Shotcrete	669
622.08 Equipment	669
622.09 Method of Measurement	669
622.10 Basis of Payment	670

DESCRIPTION

622.01 Description

This work consists of constructing shotcrete in reasonably close conformance with the Plans or as established by the Engineer.

MATERIALS

622.02 Materials

Provide materials as specified in:

Portland Cement, Type I	901.01
Fine Aggregate	903.01
Coarse Aggregate	903.22
Water	921.01
Fly Ash	921.15

622.03 Proportioning and Quality Assurance of Shotcrete

A. Proportioning

Submit the proposed shotcrete design to the Engineer for approval. Establish the design using saturated surface dry aggregate weights and

trial batches meeting the specified performance requirements. Make all strength determinations on equipment meeting the requirements of and in the manner prescribed by AASHTO T 22. Build trial batches and preconstruction test panels no more than 60 days prior to the design submittal. Assume responsibility for all costs related to concrete design, preparation, and submittal.

Include the following, as a minimum, in the proposed shotcrete design submittal:

1. Source of all aggregates
2. Brand and type of cement
3. Source and class of fly ash (if used)
4. Specific gravity of cement
5. Specific gravity of fly ash (if used)
6. Admixtures (if used)
7. Gradations of aggregates
8. Specific gravity of aggregates (saturated surface dry)
9. Percentage of fine aggregate of total aggregate (by volume)
10. Water-cement ratio (w/c)
11. Weights of each material required to produce a cubic yard of concrete
12. 3-day compressive strength (three 3-inch diameter cores taken from test panel or wall face)
13. 28-day compressive strength (three 3-inch diameter cores taken from test panel or wall face)
14. 7-day absorption (three 3-inch diameter cores taken from test panel or wall face)

Shotcrete shall meet the performance requirements specified in Table 622.03-1.

622.03

Table 622.03-1: Shotcrete Performance Requirements

Parameter	Value
3-Day Compressive Strength (psi)	2000
28-Day Compressive Strength (psi)	4000
Minimum Cementitious per cubic yard	660
Maximum Water/Cement (pound/pound)	0.45
Air Content (%)	7-10 ⁽¹⁾
7-Day Maximum Absorption (%)	8

⁽¹⁾ Air content acceptance range shall be between 7-10%, with sampling at the truck chute. Air entrainment is required for wet-mix shotcrete but not for dry-mix shotcrete.

Aggregate for shotcrete shall meet the strength and durability requirements of AASHTO M 6/M 80 and the gradation requirements specified in Table 622.03-2. An intermediate size aggregate may also be used as an additional component if needed to meet gradation. Aggregates failing to comply with Table 622.03-2 may be used if preconstruction testing as specified in **622.04** proves satisfactory results.

Table 622.03-2: Gradation Requirements

Sieve Size	Percent Passing by Weight
¾ inch	100
½ inch	98-100
3/8 inch	90-100
No. 4	70-85
No. 8	50-70
No. 16	35-60
No. 30	20-50
No. 50	8-20
No. 100	0-10

Chemical admixtures to be incorporated into the shotcrete shall be compatible and incorporated into the concrete in accordance with the manufacturer's recommendations. Concrete mixtures utilizing multiple

admixture manufacturers shall prove compatibility in accordance with Departmental procedures. Ensure that accelerators (if used) are compatible with the cement used, are non-corrosive to steel, and will not promote other detrimental effects such as cracking and excessive shrinkage.

B. Quality Control and Acceptance of Shotcrete

It is the Contractor's responsibility to determine and measure the batch quantities of all ingredients (including all water and specified or approved admixtures) for all shotcrete so that the shotcrete meets the specified requirements. During all batching operations, provide at the concrete plant a TDOT Concrete Plant Quality Control Technician, who shall have the primary responsibility of process control, including all sampling, testing, and inspection of the aggregate and shotcrete.

The average compressive strength of each set of three test cores extracted from test panels or wall facing shall equal or exceed 85% of the specified compressive strength, with no individual core less than 75% of the specified compressive strength, as determined according to ACI 506.2. Do not take cores from the outer 6 inches of test panels, measured in from the top outside edges of the panel form. Trim the ends of compressive strength cores to provide test cylinders that are at least 3 inches long. Do not trim ends for absorption cores.

Provide all equipment, materials, and personnel necessary to obtain shotcrete cores for testing, including constructing test panel boxes, field curing, and coring. The Engineer will perform compressive strength and boiled absorption testing and will base shotcrete final acceptance on 28-day compressive strength.

C. Placement of Shotcrete

An ACI-certified Shotcrete Nozzleman shall be utilized to properly place shotcrete.

622.04 Preconstruction Test Panels

Furnish two preconstruction test panels for each proposed mixture being considered and for each shooting position to be encountered on the Project. Make preconstruction test panels prior to production and as part of the mix design submittal process, using the same equipment, materials, mixture, proportions, and procedures proposed for the work.

622.05

Construct the preconstruction test panels with minimum dimensions of 30 x 30 inches square and at least 4 inches thick. Slope the sides at 45 degrees over the full panel thickness of release rebound.

Construct one preconstruction test panel to include the maximum anticipated reinforcing congestion shown on the Plans. Cores extracted from the test panel shall demonstrate encapsulation of the reinforcement in accordance with ACI 506.2 equal to core Grade 2 or better.

Construct the second preconstruction test panel without reinforcement and extract nine 3-inch diameter cores for absorption and compressive strength testing.

622.05 Production Test Panels

Provide nine 3-inch diameter cores from a minimum of one production test panel or, instead of production test panels, taken from the shotcrete facing during the first production application of shotcrete and henceforth for every 5,000 square feet of shotcrete placed. Cut at least nine 3-inch diameter core samples from each production test panel for absorption and compressive strength testing.

If choosing to take cores from the wall face instead of making production test panels, take cores at the locations designated by the Engineer. Fill core holes in the wall facing by dry packing with non-shrink patching mortar after cleaning and dampening the holes. Do not fill core holes with shotcrete.

Construct production test panels simultaneously with the shotcrete facing installation at times designated by the Engineer. Production test panels shall be a minimum full thickness of 18 x 18 inches square and at least 4 inches thick.

The Contractor may extract test specimens from test panels in the field or may transport them to another location for extraction. Keep panels in their forms during transport.

622.06 Test Panel Curing and Testing

Immediately after shooting the test panels, field moist cure the panels by covering and tightly wrapping with a sheet of material meeting ASTM C171 until they are delivered to the testing lab or test specimens are extracted. Do not immerse test panels in water. Do not further disturb test panels for the first 24 hours after shooting.

Clearly mark preconstruction/production cores and containers to identify core locations. If for production testing, mark the section of the wall represented by the cores on the cores and container. Immediately wrap cores in wet burlap or material meeting ASTM C171, and seal in a plastic bag. Deliver cores to the Engineer or testing lab, as directed by the Engineer, within 48 hours of shooting the panels. When the test length of a core is less than twice the diameter, the correction factors given in AASHTO T 24 will be applied to obtain the compressive strength of individual cores. The remainders of the panels shall become the property of the Contractor.

622.07 Mixing and Batching Shotcrete

Aggregate and cement may be batched by weight or by volume in accordance with AASHTO M 241 (ASTM C685). Ready mix shotcrete shall comply with AASHTO M 157. Batch, deliver, and place shotcrete within 90 minutes of mixing. The use of retarding admixtures may extend application time beyond 90 minutes if approved by the Engineer.

Premixed and packaged shotcrete mix may be provided for on-site mixing. The packages shall contain materials conforming to **622.02** and be from a source on the Department's Producer List. Place the material within the time limit following mixing recommended by the manufacturer.

EQUIPMENT

622.08 Equipment

Use mixing equipment that thoroughly blends the materials in sufficient quality to maintain placing continuity.

COMPENSATION

622.09 Method of Measurement

The Department will measure completed and accepted quantities of shotcrete in square feet, by taking measurements over and parallel to the actual area of the applied shotcrete.

622.10

622.10 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Shotcrete	Square Feet

Such payment is full compensation for furnishing all labor, materials, tools, equipment, and incidentals required to place the shotcrete, including surface preparation.

SECTION 623 – BRIDGE EXPANSION JOINTS

623.01 Scope of Work	671
623.02 Modular Roadway Expansion Joints.....	671
623.03 Strip Seal Expansion Joints.....	675
623.04 Method of Measurement	678
623.05 Basis of Payment.....	678

DESCRIPTION

623.01 Scope of Work

This work consists of fabricating and installing shop fabricated bridge expansion joint systems, of the general size, configuration, and joint movement specified.

623.02 Modular Roadway Expansion Joints

This Subsection is applicable to expansion joints having a required movement in excess of 4 inches.

A. Fatigue Design

Provide certification that all proposed modular expansion devices have been tested in accordance with the National Research Program Report 467 *Performance Testing for Modular Bridge Joint Systems*.

B. Materials

1. **General.** All parts and elements shall be of the material and design indicated in the manufacturer's catalog, except as otherwise specified in the Contract or shown on the Plans.
2. **Steel Plates, Bars, Rolled Shapes, and Extrusions.** All steel plates, bars, rolled shapes, and extrusions shall be fabricated from high-strength, low alloy grade 50S, HPS50W steel, conforming to the requirements of ASTM A709 grade 50 or 50W, as shown on approved shop drawings. Anchor bars may be A36 steel. All membrane retainers shall have a 3/8-inch minimum thickness.

Stainless steel sheets for the sliding surfaces of the support bars shall conform to the requirements of ASTM A167, alloy 304, 20 micro-inch RMS finish.

Anchor bolts, bolts, nuts, and washers shall conform to the requirements of ASTM F1554, as shown on the Plans.

3. **Preformed Elastomeric Seals.** The elastomeric sealing element shall be a polychloroprene (neoprene) seal that is resistant to heat, oil, jet fuel, and ozone. The seal shall be one-piece full length of the expansion joint, including curb and parapet face projections.

In addition, the sealing elements shall conform to ASTM D2628, modified to omit the recovery test and to meet the requirements specified in Table 623.02-1.

Table 623.02-1: Elastomeric Sealing Element Hardness

Property	Requirement	ASTM Method
Hardness	60 +/- 7	D2240
Type A	Durometer	Modified

To install the preformed elastomeric elements in place, use as a lubricant/adhesive a one-part moisture-curing, polyurethane and hydrocarbon solvent mixture or as recommended by the manufacturer and approved by the Engineer.

4. **Support Bar Bearings.** Use support bar bearings fabricated from polyurethane compound with polytetrafluorethylene (PTFE) self-lubricating surfaces having engineering properties equivalent to adiprene, teflon or cast nylon w/MDS (molybdenum disulfide) (i.e., high-load bearing and high-impact resistance characteristics plus low coefficient of friction).
5. **Joint Control Mechanism.** To ensure equal distribution of the total joint opening, provide suitable equilibrium type springs that operate counter to compression forces of the sealing elements and co-linear with the axis of structure movement.
6. **Support Bars.** Provide support bars that as a minimum:

- a. Incorporate stainless steel sliding surfaces to minimize resistance to joint movements.
- b. Provide support above, below, and laterally as required to prevent lifting, transmit bearing loads, and maintain positioning of the bar. Place support bars at right angles to each transverse rail.
- c. Are at least 2 inches in width and 3 inches in height, and that will ensure that each transverse rail (separation beam) will rest on a separate support bar at each support assembly.

7. Separation Beams/Transverse Dividers. Separation beams/transverse dividers shall be at least 2-1/2 inches in top width and 4 inches in height and shall be designed for the design live load (AASHTO HS 20-44 minimum plus 50% for impact), using working stress limits. Analyze support bars and transverse rails using both vertical and horizontal live load components.

8. Miscellaneous Hardware. Provide miscellaneous hardware as described in the manufacturer's literature.

C. Fabrication and Construction

The manufacturer of the prefabricated expansion joint assembly shall prepare shop drawings showing details of the assembly and installation. Installation drawings shall include concrete, reinforcing steel and/or anchorage details falling within the respective modular joint stress zones.

- 1. Construct the expansion joint systems as shown on the shop drawings. Meet the tolerance requirements included in AASHTO specifications. Perform all welding according to AWS specifications and by certified welders only. Ensure that fabricators are certified under the AISC Quality Certification, Category I, Simple Steel Bridges, SBR-1B.
- 2. Shop drawings shall also supply information regarding material specifications, geometry, a table of variable temperature and dimensions, and a bill of material. The maximum joint opening for a single modular unit shall be 4 inches measured at right angles to the rails.

623.02

3. With the exception of the stainless steel elements, either paint all steel in accordance with System A as specified in **603.06**, or galvanize it, unless otherwise shown on the Plans.
4. Ensure that the profile of the joint in the pavement area conforms to the roadway cross-section, slope, skew, and grade. Provide slider plates at curbs, walkways, and parapets, as part of the completed joint assembly, in accordance with details shown on the Plans and Standard Drawings.
5. Preset the modular expansion joint assembly in accordance with approved shop drawings, joint setting data, and specifications. Secure the assembly for shipping. Provide the assembly with temporary self-aligning guide angles or other structural members to span over the block-out for joints and allow for proper grade and elevation adjustment between the bridge deck and approach roadway. Make final adjustment at the discretion of the Engineer. Account for all movements due to factors such as shrinkage, creep, and mid-slab deflection, before making this final adjustment. Obtain the permission of the joint manufacturer's technical representative to make any adjustments other than for temperature settings.
6. Properly position and attach the prefabricated joint assembly to the superstructure using the anchorages provided with the assembly.
7. Do not use drilled and grouted or cast-in-place inserts to anchor the expansion device to the structure. Accomplish anchorage by attachment to each longitudinal bridge girder, supplemented by 2-inch wide straps, providing no less than 1.25 square inches of cross-sectional area per linear foot of expansion joint between direct connections at girders. The straps shall be a minimum length of 1 foot with a 2-inch, 90-degree bend at the free end.
8. Ensure that girder attachments provide a means of adjustment so that the expansion device can be installed to line and grade in conformance with approved shop drawings, the Plans, and the manufacturer's recommendations.
9. Use a similar configuration for the backwall anchorage.

10. Coordinate with the joint supplier, remain-in-place form supplier, and/or beam fabricator to ensure that all details impacting the acceptable installation of the expansion joint are in harmony.
11. Clean formed recesses of foreign material and prepare by an approved method. Ensure that deck concrete is well consolidated behind and around both sides of the joint edge rails and support boxes.

D. Installation Supervision and Certification

A manufacturer's representative shall be present at the time of installation to assist the Contractor in the proper setting of the joint. If the individual representing the manufacturer is not a full-time employee of the manufacturer, provide written certification that the individual is a duly authorized agent of the manufacturer before beginning joint installation. After installation, the representative shall inspect and certify to the Engineer that the joint has been installed in accordance with the manufacturer's recommendations, and that it is water tight. The Engineer will not accept joints for which such certifications are not provided.

The Contractor and the manufacturer's representative shall conduct tests for water-tightness in the presence of the Engineer by ponding water upon the joint for a period of 15 minutes. Take corrective measures to eliminate all leaks.

623.03 Strip Seal Expansion Joints

A. Description of Work

This Subsection is applicable to expansion joints having a required movement of 4 inches or less.

B. Materials

1. **General.** All parts and elements shall be of the material and design indicated in the manufacturer's catalog, except as otherwise specified in these provisions or shown on the Plans.
2. **Steel Plates, Bars, Rolled Shapes, and Extrusions.** All steel plates, bars and shapes shall be fabricated from high-strength, low

623.03

alloy Grade 50 steel, conforming to the requirements of ASTM A709 Grade 50 or 50W, as shown on approved shop drawings. Anchor bars and plates may be A36 steel. The membrane retainer may be either an extrusion or rolled shape.

Anchor bolts, bolts, nuts, and washers shall conform to the requirements of ASTM A307, as shown on the Plans.

3. **Preformed Elastomeric Seals.** The elastomeric sealing element shall be EPDM or a polychloroprene (neoprene) seal that is resistant to heat, oil, jet fuel, and ozone. The seal shall be one piece full length of the expansion joint including curb and parapet face projections. The seal shall be a mechanically locked seal element placed in a solid steel extrusion or rolled shape conforming to the Plans dimensions.

In addition, the sealing elements shall conform to ASTM D2628, modified to omit the recovery test and to meet the requirements specified in Table 623.02-1 above.

To install preformed elastomeric elements in place, use as a lubricant/adhesive a one-part moisture-curing, polyurethane and hydrocarbon solvent mixture or as recommended by the manufacturer and approved by the Engineer.

4. **Miscellaneous Hardware.** Provide miscellaneous hardware as described in the manufacturer's literature.

C. Fabrication and Construction

1. The manufacturer of the prefabricated expansion joint assembly shall prepare shop drawings showing details of the assembly and installation. Installation drawings shall include concrete, reinforcing steel and/or anchorage details falling within the respective joint zones. The shop drawings shall also show any changes to the reinforcing steel or concrete limits from the Plans due to the type joint being used.
2. Shop drawings shall also supply information regarding material specifications, geometry, a table of variable temperature and dimensions, and a bill of material. The maximum joint opening shall be 4 inches. Construct the expansion joint systems in accordance with the details shown on the shop drawings. Tolerance

requirements shall be in accordance with AASHTO Specifications. Perform all welding in accordance with AWS specifications and by certified welders only. Ensure that fabricators are certified under the AISC Quality Certification, Category I, Conventional Steel Structures.

3. Ensure that the profile of the joint conforms to the roadway cross-section, slope, skew, and grade.
4. Either paint all steel that is part of the joint assembly in accordance with System A as specified in **603.06**, or galvanize in accordance with ASTM A123, unless shown otherwise on the Plans.
5. Properly position and attach the prefabricated joint assembly to the superstructure using the anchorages provided with the assembly.
6. Do not use drilled and grouted or cast-in-place inserts to anchor the expansion device to the structure on new construction. Accomplish anchorage by attachment to each longitudinal bridge girder, supplemented by 2-inch wide straps, providing no less than 1.25 square inches of cross-sectional area per linear foot of expansion joint between direct connections at girders. The straps shall be a minimum length of 1 foot with a 2-inch, 90-degree bend at the free end.
7. Anchorage details for repair of expansion joints on existing structures shall be as shown on the Contract drawings and/or approved shop drawings.
8. Ensure that girder attachments provide a means of adjustment so that the expansion device can be installed to line and grade in conformance with approved shop drawings, the Plans, and the manufacturer's recommendations.
9. Use a similar configuration for the backwall anchorage.
10. Coordinate with the joint supplier, remain-in-place form supplier, and/or beam fabricator to ensure that all details impacting the acceptable installation of the expansion joint are in harmony.
11. Clean formed recesses of foreign material and prepare by an approved method. Ensure that deck concrete is well consolidated behind and around both sides of the joint steel.

623.04

COMPENSATION

623.04 Method of Measurement

The Department will measure expansion joints of each kind horizontally by the linear foot along the center of the joint from outer face to outer face of the concrete superstructure of the bridge.

The Department will consider slider plate assemblies at curbs, walkways, medians, median barriers, and parapets to be incidental to the items for the expansion joint systems and will not measure and pay for them directly.

623.05 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Modular Roadway Expansion Joints	Linear Feet
Strip Seal Expansion Joints	Linear Feet

A. Modular Roadway Expansion Joints

Payment for Modular Roadway Expansion Joints is full compensation for furnishing and installing the device complete in place, including all labor, materials, equipment, and other incidentals necessary to complete the work.

The Department will pay for the deck concrete placed within the limits of the expansion joint block-outs at the applicable contract unit price per cubic yard. Otherwise, the cost of all modifications of bridge details, including parapet and/or median slider plate assemblies, forming for adequate block-outs of the concrete deck slab, and any additional reinforcing steel required in the concrete deck slab block-outs, necessary to properly install the roadway expansion joint shall be included in the price bid for the joint.

B. Strip Seal Expansion Joints

Payment for Strip Seal Expansion Joints is full compensation for furnishing and installing the device complete in place, including all

623.05

labor, materials, equipment, and other incidentals necessary to complete the work.

Modifications of bridge details including parapet and/or median slider plate assemblies that are necessary to properly install the roadway expansion joint shall be included in the price bid for the joint.

PART 7 – INCIDENTAL CONSTRUCTION AND SERVICES

SECTION 701 – CEMENT CONCRETE SIDEWALKS, DRIVEWAYS AND MEDIAN PAVEMENT	681
SECTION 702 – CEMENT CONCRETE CURB, GUTTER, AND COMBINED CURB AND GUTTER.....	687
SECTION 703 – CEMENT CONCRETE DITCH PAVING	692
SECTION 705 – GUARDRAIL	696
SECTION 706 – GUARDRAIL ADJUSTED, REMOVED AND RESET	701
SECTION 707 – FENCES	705
SECTION 708 – MONUMENTS AND MARKERS	710
SECTION 709 – RIPRAP AND SLOPE PAVEMENT.....	714
SECTION 710 – UNDERDRAINS	722
SECTION 711 – CONCRETE MEDIAN BARRIER.....	728
SECTION 712 – TEMPORARY TRAFFIC CONTROL	731
SECTION 713 – HIGHWAY SIGNING	748
SECTION 714 – ROADWAY AND STRUCTURE LIGHTING	756
SECTION 715 – ASPHALTIC CONCRETE CURB (HOT MIX).....	780
SECTION 716 – PAVEMENT MARKINGS	784
SECTION 717 – MOBILIZATION OF FORCES, SUPPLIES AND EQUIPMENT	799
SECTION 722 – FIELD OFFICE.....	801
SECTION 730 – TRAFFIC SIGNALS.....	807
SECTION 740 – GEOSYNTHETICS	866

**SECTION 701 – CEMENT CONCRETE SIDEWALKS,
DRIVEWAYS
AND MEDIAN PAVEMENT**

701.01 Description.....	681
701.02 Materials	681
701.03 Equipment.....	682
701.04 Preliminary Work.....	682
701.05 Subgrade Preparation	682
701.06 Expansion Joints	683
701.07 Limitations on Mixing	683
701.08 Mixing and Placing Concrete.....	683
701.09 Finishing	683
701.10 Protection and Curing	684
701.11 Backfilling	685
701.12 Final Cleanup	685
701.13 Method of Measurement	685
701.14 Basis of Payment.....	686

DESCRIPTION

701.01 Description

This work consists of constructing, on a prepared subgrade, Portland cement concrete Sidewalks, Driveways, and Median Pavement, excluding those Sidewalks, Driveways, and Median Pavement that are integrally part of structures.

MATERIALS

701.02 Materials

Provide materials as specified in:

Preformed Joint Filler	905.01
Cement Concrete Curing Materials	913
Drain Pipe, Standard Strength	914.04

701.03

To construct sidewalks, driveways, and median pavement, use Class A concrete meeting the requirements of **604**.

EQUIPMENT

701.03 Equipment

A. Forms

Use forms of wood, metal, or other suitable material. Extend forms for the full depth of the concrete. Only use forms that are true to line, free from warp, and of sufficient strength to resist the pressure of the concrete without springing. On all radial sections, use curved forms of proper radius and that are of a design acceptable to the Engineer. Brace and stake forms to ensure that they will remain in both horizontal and vertical alignment until their removal.

B. Mixing and Finishing Equipment

Use mixers that meet **501.04.B**.

Furnish satisfactory floats, templates, straightedges, edgers, spades, and tamps. Compact the subgrade using tamping or rolling equipment that will produce the desired results.

Instead of using forms, the Contractor may use a slip form paver that will produce the required results.

CONSTRUCTION REQUIREMENTS

701.04 Preliminary Work

Perform Clearing and Grubbing, Removal of Structures and Obstructions, Excavation and Undercutting, and Embankment Construction as specified in **201**, **202**, **203**, and **205**, respectively.

701.05 Subgrade Preparation

Prepare subgrade for sidewalks, driveways, and median pavement to the required depth and to a width that will allow for the installation and bracing of the forms. Shape and compact the subgrade to a firm, even surface in

reasonably close conformity with the grade and cross-section shown on the Plans. Remove all soft and yielding material, replace it with acceptable material, and compact it as directed by the Engineer.

701.06 Expansion Joints

Unless otherwise shown on the Plans or directed by the Engineer, place premolded expansion joint filler, 1 inch in thickness, at the locations and in line with expansion joints in the adjoining pavement, gutter, or curb. Cut all premolded expansion joint filler to the full width or length of the proposed construction and extend it to within 1 inch of the top or finished surface. Place all longitudinal expansion joints as shown on the Plans or as directed by the Engineer. Ensure that all expansion joints are true, even, and present a satisfactory appearance.

Form construction joints around all appurtenances, such as manholes and utility poles, that extend into and through the sidewalk or median area. Install 1-inch thick premolded expansion joint filler in these joints. Install expansion joint filler, of the thickness shown on the Plans, between concrete sidewalks and any fixed structure, such as a building or bridge. Install 1-inch thick expansion joint filler between concrete curb and median pavement and, unless otherwise specified, between concrete curb and sidewalk. This expansion joint material shall extend for the full depth of the walk or median pavement.

701.07 Limitations on Mixing

Comply with **604.12**.

701.08 Mixing and Placing Concrete

Mix concrete as specified in **604.14**.

Place concrete as specified in **501.12**, except that mechanical spreaders will not be required. Immediately before placing the concrete, thoroughly wet the subgrade, and give the forms a coating of light oil. Thoroughly clean and oil the forms before each use.

701.09 Finishing

Strike-off the concrete with a transverse template resting upon the side forms. After striking-off the concrete to the required cross-section, finish it with

701.10

floats and straightedges until the required surface requirements have been obtained.

When the concrete surface is free from water and just before the concrete obtains its initial set, finish and lightly sweep the surface with a broom to produce a sandy texture. The longitudinal surface variations shall not exceed $\frac{1}{4}$ inch under a 12-foot straightedge, or $\frac{1}{8}$ inch on a 5-foot transverse section. Ensure that the finished concrete surface will drain completely at all times.

Carefully finish the edges of the sidewalks, driveways, and median pavement, and round with an edging tool having a $\frac{1}{2}$ -inch radius.

Divide the surface of sidewalks into blocks using a grooving tool. Space the grooves approximately 5 feet apart to produce rectangular blocks unless otherwise directed by the Engineer. Cut the grooves to a depth of not less than 1 inch. Shape the edges of the grooves with an edging tool having a $\frac{1}{4}$ -inch radius.

Place grooves in median pavement to be in line with corresponding joints in adjoining construction or as directed by the Engineer.

Unless otherwise shown on the Plans, place marks or grooves at right angles to the centerline of driveways and approximately 8 inches apart. Using a suitable marking tool, make these markings to be between $\frac{1}{8}$ and $\frac{1}{4}$ inch in depth. A grooving tool, of 6 to 8 inches in width, with multiple grooves for grooving alternate strips 8 inches apart, may be used for this purpose. Remove irregularities caused by the edges of the marking tool using a wetted brush or wooden float. Round all marking edges.

Do not place grooves in the surface of sidewalks or driveways reinforced for beam action where the full thickness of concrete is required for strength.

Round the edges of the concrete at expansion joints with an edging tool having a $\frac{1}{4}$ -inch radius. Remove all marks caused by edging. Clean the top and ends of expansion joint material of all concrete and trim the expansion joint material to be slightly below the surface of the concrete.

701.10 Protection and Curing

Forms may be removed as soon as their removal will not damage the concrete. Do not exert pressure upon the concrete when removing forms.

Perform curing and provide cold weather protection as specified in **501.18**.

Do not allow pedestrians on concrete sidewalks, driveways, or medians until 12 hours after finishing the concrete. Do not allow vehicles or loads on any sidewalk, driveway, or median until the Engineer has determined that the concrete has attained sufficient strength for such loads.

Construct and place barricades and protection devices as necessary to keep pedestrians and other traffic off the sidewalk, driveway, or median.

Repair all sidewalks, driveways, or paved medians damaged prior to final acceptance of the Project, at no cost to the Department, by removing concrete within groove limits and replacing it with concrete of the same type and finish as used in the original construction.

701.11 Backfilling

Immediately after removing the side forms, fill the spaces along the edges of the sidewalk or driveway with suitable material, placed in layers not exceeding 4 inches in loose thickness, and compact this material until firm and stable.

701.12 Final Cleanup

Perform final cleanup as specified in **104.10**.

COMPENSATION

701.13 Method of Measurement

The Department will measure Concrete Sidewalks and Concrete Driveways by the square foot, complete in place, based on surface area measurements. Where standard widths are constructed, the measurements shall not exceed the standard widths shown on the Plans without the Engineer's written approval. The Department will measure Concrete Sidewalks of each thickness, and Concrete Driveways, separately.

The Department will measure Concrete Median Pavement by the volume in cubic yards, complete in place, as obtained from the specified thickness shown on the Plans and surface measurements for width and length.

701.14

The Department will measure Concrete Curb Ramps and Concrete Curb Ramps (Retrofit) by the area in square feet, complete in place, as obtained from surface measurements. Where standard widths are constructed, the measurements shall not exceed the standard widths shown on the Plans, unless approved in writing by the Engineer.

Unless otherwise shown on the Plans, the Department will consider subgrade preparation, backfill, expansion joint materials, and drain pipe to be incidental to the work.

701.14 Basis of Payment

The Department will pay for accepted quantities, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Concrete Sidewalk (__ “)	Square Feet
Concrete Driveway (__ “)	Square Feet
Concrete Median Pavement	Cubic Yard
Concrete Curb Ramp	Square Feet
Concrete Curb Ramp (Retrofit)	Square Feet

Such payment is full compensation for all subgrade preparation, backfill, and all other incidentals necessary to complete the work.

**SECTION 702 – CEMENT CONCRETE CURB,
GUTTER, AND COMBINED CURB AND GUTTER**

702.01 Description.....	687
702.02 Materials	687
702.03 Equipment.....	688
702.04 Preliminary Work.....	689
702.05 Subgrade Preparation	689
702.06 Expansion Joints	689
702.07 Limitations on Mixing	689
702.08 Mixing, Placing, and Finishing Concrete.....	689
702.09 Protection and Curing	690
702.10 Backfilling	691
702.11 Final Cleanup.....	691
702.12 Method of Measurement.....	691
702.13 Basis of Payment.....	691

DESCRIPTION

702.01 Description

This work consists of constructing Curb, Gutter, or Combined Curb and Gutter of Portland cement concrete.

MATERIALS

702.02 Materials

Provide materials that meet the applicable requirements of **604** and **913**, and as specified in:

Preformed Joint Filler	905.01
Drain Pipe, Standard Strength	914.04

To construct curb, gutter, and combined curb and gutter, use Class A concrete meeting the requirements of **604**, with the following exception: when placing

702.03

concrete with a curb extruding machine, the slump shall range from 0 to 3 inches.

The Contractor may adjust water and percentages of fine and coarse aggregate within the limits specified (fine aggregate may range from 40 to 65%) to allow satisfactory placement.

The Department will make compressive strength test specimens in accordance with AASHTO T 23.

EQUIPMENT

702.03 Equipment

A. Forms

Except for the templates between 10-foot sections, use either wood or metal forms that meet **701.03.A**. For the templates, use 1/8-inch thick metal, of the same width as that of the curb, gutter, or combination curb and gutter, and that is not less than ¼ inch more in depth than the respective depth of the type curb and gutter being constructed. The templates shall have lugs or other devices to hold them in position during concrete placement and shall be of a design that will allow their removal without damaging the concrete. For gutters, use a strike-off template, of the form and shape of the gutter, to shape the top surface of the gutter.

B. Compaction Equipment

Compact the subgrade using tamping or rolling equipment that will produce the desired results.

C. Mixing and Finishing Equipment

Use mixers that meet **604.04**. With the Engineer's approval, the Contractor may use a curb machine that will place the concrete in a satisfactory manner. Provide finishing equipment, including satisfactory floats, edgers, spades, and tamps.

CONSTRUCTION REQUIREMENTS

702.04 Preliminary Work

Perform Clearing and Grubbing, Removal of Structures and Obstructions, Excavation and Undercutting, and Embankment Construction as specified in **201**, **202**, **203**, and **205**, respectively.

702.05 Subgrade Preparation

Perform subgrade preparation for curb, gutter, and combined curb and gutter to the required depth, and to a width that will allow the installation and bracing of the forms. Shape and compact the subgrade to a firm, even surface, in reasonably close conformity with the grade and section shown on the Plans. Remove all soft and yielding material, replace it with acceptable material, and compact as directed by the Engineer.

702.06 Expansion Joints

Form expansion joints at the intervals and locations shown on the Plans, using 1-inch thick preformed joint filler, unless otherwise specified. Place expansion joints in line with corresponding expansion joints in adjoining pavement or other construction. Cut joint filler to the full cross-section of the curb, gutter, or curb and gutter.

702.07 Limitations on Mixing

Comply with **604.12**.

702.08 Mixing, Placing, and Finishing Concrete

Mix concrete as specified in **604.13**.

Immediately before placing the concrete, thoroughly wet the subgrade, and apply a coating of light oil to the forms. Thoroughly clean and oil the forms before each use.

Place concrete as specified in **501.12**, except that the mechanical spreader will not be required.

Place the concrete immediately after mixing. Spade and vibrate the edges, sides, or faces to thoroughly consolidate the concrete and bring the mortar to

702.09

the surface. After vibrating, use a wooden float to give the surface a smooth and even finish.

Construct concrete curb, gutter, or combined curb and gutter, to be reasonably true to line, grade, and cross-section, and, unless otherwise shown on the Plans, in sections having uniform lengths of 10 feet. The length of these sections may be reduced to no less than 6 feet where necessary for closures. Carefully set the templates before placing the concrete and keep them in place until the concrete has set sufficiently to hold its shape. Remove templates while the forms are still in place. Remove the forms on the face of all curbs as soon as the concrete will hold its shape, and then use a wooden float on the surface to provide a smooth and even finish. No plastering is permitted. Unless otherwise specified, round the top edges of the curb and the edge of the gutter to a radius of $\frac{3}{4}$ inch. Finish the edges on each side of templates and expansion joint material with an edging tool having a radius of not over $\frac{1}{4}$ inch, and then remove all lines or marks with a wet brush. Finish the back of curbs not less than 3 inches below the top of backfill against the curb. Leave all exposed surfaces, against which some rigid type of construction is to be made, smooth and uniform to allow free movement of the curb, gutter, or combined curb and gutter.

Remove all tool marks with a wetted brush or wooden float and ensure that the finished surface presents a uniform and pleasing appearance.

If the Engineer allows use of curb machines, perform finishing as specified above, except that instead of constructing the curbs in sections, contraction joints may be sawed a minimum depth of $\frac{1}{4}$ the thickness of the section, at intervals of 6 to 10 feet.

Place weep holes or drainage openings through curbs as shown on the Plans or as directed by the Engineer. Place coarse aggregate behind each opening as needed.

702.09 Protection and Curing

Immediately after finishing the concrete, provide protection and perform curing as specified in **501.18**.

Protect the curb, gutter, and combined curb and gutter until final acceptance. Repair concrete that is damaged before final acceptance by removing and reconstructing each 10-foot section that has been damaged at no cost to the Department.

702.10 Backfilling

Immediately after the concrete has set sufficiently and the forms have been removed, fill the space behind the curb or combined curb and gutter with suitable material, placed in layers not exceeding 4 inches in loose thickness, and compact until firm and stable.

702.11 Final Cleanup

Perform final cleanup as specified in **104.10**.

COMPENSATION**702.12 Method of Measurement**

The Department will measure Concrete Curb, Concrete Gutter, and Concrete Combined Curb and Gutter for payment by the cubic yard, complete in place. The volume, per linear foot of length, will be obtained from the dimensions shown on the Plans. Linear measurements will be surface measurements taken along the center of gravity of the section.

Unless otherwise shown on the Plans, the Department will consider subgrade preparation, backfill, expansion joint materials, and drain pipe to be incidental to the work.

The Department will not measure or make payment under this Section for curb integral with concrete pavement or concrete base unless otherwise shown on the Plans or specified in the Contract.

702.13 Basis of Payment

The Department will pay for accepted quantities, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Concrete Curb	Cubic Yard
Concrete Gutter	Cubic Yard
Concrete Combined Curb and Gutter	Cubic Yard

Such payment is full compensation for all subgrade preparation, backfill, and all other incidentals necessary to complete the work.

703.01

SECTION 703 – CEMENT CONCRETE DITCH PAVING

703.01 Description	692
703.02 Materials	692
703.03 Equipment	693
703.04 Preliminary Work.....	693
703.05 Subgrade Preparation	693
703.06 Joints	694
703.07 Limitations on Mixing.....	694
703.08 Mixing, Placing, and Finishing Concrete.....	694
703.09 Protection and Curing	694
703.10 Backfilling.....	694
703.11 Final Cleanup	694
703.12 Method of Measurement	695
703.13 Basis of Payment.....	695

DESCRIPTION

703.01 Description

This work consists of constructing paved ditches of Portland cement concrete on a prepared subgrade.

MATERIALS

703.02 Materials

Provide materials that meet the applicable requirements of **604**.

For Portland cement concrete ditch paving, use Class A concrete meeting the requirements of **604**.

EQUIPMENT

703.03 Equipment

A. Forms

Use forms of either wood or metal that meet **701.03.A**. To shape the top surface of the paved ditch, use a strikeoff template having the same form and shape as the ditch section.

B. Compaction Equipment

Compact the subgrade using tamping or rolling equipment that will produce the required compaction and shape.

C. Mixing and Finishing Equipment

Use mixers that meet **604.04**. Mechanical ditch paving machines may be used when approved by the Engineer.

Provide finishing equipment, including satisfactory floats, edgers, spades, and tamps.

CONSTRUCTION REQUIREMENTS

703.04 Preliminary Work

Perform Clearing and Grubbing, Removal of Structures and Obstructions, Excavation and Undercutting, and Embankment Construction as specified in **201**, **202**, **203**, and **205**, respectively.

703.05 Subgrade Preparation

Prepare subgrade for ditch paving to the required depth and to a width that will allow the installation and bracing of forms. Shape and compact the subgrade to a firm, even surface, in reasonably close conformity with the grade and section shown on the Plans or as directed by the Engineer. Remove all soft and yielding material, replace it with acceptable material, and compact as directed by the Engineer.

703.06

703.06 Joints

Form joints at the intervals and locations shown on the Plans. Cut joint filler for expansion joints to the full depth of the ditch pavement.

703.07 Limitations on Mixing

Comply with **604.12**.

703.08 Mixing, Placing, and Finishing Concrete

Mix concrete as specified in **604.13**.

Before placing concrete, prepare the subgrade and forms as specified in **701.05**.

Place the concrete immediately after mixing. After spading the edges and allowing the concrete to thoroughly consolidate, use a wooden float to give the surface a smooth and even finish.

Round the edges of the paved ditch to a radius of ½ inch, and finish edges along expansion and contraction joints with an edging tool having a radius of not over ¼ inch. Remove all edging tool marks with a float and brush.

703.09 Protection and Curing

Immediately after finishing the concrete, cure it as specified in **501.18**.

Protect the ditch paving until final acceptance of the Project. Remove concrete that is damaged prior to acceptance by removing and reconstructing the damaged sections at no cost to the Department.

703.10 Backfilling

Immediately after the concrete has set sufficiently and the forms have been removed, fill the spaces on each side of the ditch paving with suitable material and compact thoroughly; or, if sod is specified, lay it in accordance with **803**.

703.11 Final Cleanup

Perform final cleanup as specified in **104.10**.

COMPENSATION

703.12 Method of Measurement

The Department will measure Portland Cement Concrete Ditch Paving for payment by the cubic yard, complete in place. The volume per linear foot of length will be obtained from the dimensions shown on the Plans. Linear measurements will be surface measurements taken along the centerline of the paved ditch.

Unless otherwise shown on the Plans, the Department will consider subgrade preparation, backfill, and expansion joint materials to be incidental to the work.

703.13 Basis of Payment

The Department will pay for accepted quantities, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Portland Cement Concrete Ditch Paving	Cubic Yard

Such payment is full compensation for all subgrade preparation, backfill, and all other incidentals necessary to complete the work.

705.01

SECTION 705 – GUARDRAIL

705.01 Description	696
705.02 Materials	696
705.03 Reserved.....	697
705.04 Preliminary Work.....	697
705.05 Posts	697
705.06 Installation of Posts	697
705.07 Erection	699
705.08 Final Cleanup	699
705.09 Method of Measurement	699
705.10 Basis of Payment.....	700

DESCRIPTION

705.01 Description

This work consists of furnishing and erecting guardrail, and constructing anchor blocks and approach ends, of the specified kind and dimensions.

Guardrail includes appurtenant materials and work required to make connections with other guardrail or structures, as may be required to complete the Work shown on the Plans.

MATERIALS

705.02 Materials

Provide materials as specified in:

Metal Beam Guardrail.....	909.05
Guardrail Posts.....	909.07
Guardrail Hardware	909.08

Use Class A Portland cement concrete. Mix, place, finish, and cure concrete as specified in **604**.

For all guardrail safety end treatment systems, provide certification from the supplier that the device meets the requirements of and is listed on the Department's QPL or Standard Drawings. In addition, submit detailed shop drawings for the QPL or Standard Drawing approved devices to the Engineer, and utilize a copy onsite during installation.

705.03 Reserved

CONSTRUCTION REQUIREMENTS

705.04 Preliminary Work

Perform Clearing and Grubbing, Removal of Structures and Obstructions, Excavation and Undercutting, and Embankment Construction as specified in **201**, **202**, **203**, and **205**, respectively.

705.05 Posts

Provide posts of the shape, size, and dimensions shown on the Plans and/or the approved Shop Drawings. Set posts reasonably true to the lines and grades shown on the Plans or established by the Engineer.

705.06 Installation of Posts

Before beginning any excavation or driving any guardrail post, determine the location of all underground electrical, drainage, and utility lines in the vicinity, and conduct work so as to avoid damaging these facilities. Dig or drill holes to the depth shown on the Plans and/or the approved Shop Drawings and to a size that will allow proper setting of the posts and sufficient room for backfilling and tamping. Alternatively, the Contractor may drive posts using approved methods and equipment, provided the posts are erected in the proper position and are free of distortion, burring, or other damage.

If solid rock is encountered while drilling post holes:

1. Within 18 inches of the ground surface, drill an oversized or elongated hole 24 inches into the rock. Set the post at the roadside edge of the hole, and backfill the hole with the cutting spoils.

705.06

- a. If using wooden posts, either drill a single oversized hole 23 inches in diameter, or three overlapping holes 10 inches in diameter, to a length of 23 inches.
 - b. For steel posts, drill a single oversized hole, 20 inches in diameter, or three overlapping holes 8 inches in diameter, to a length of 20 inches.
2. Below 18 inches of the ground surface, drill holes 12 inches into the rock or to the depth shown on the Plans. The holes shall be 8 inches in diameter for steel posts, and 12 inches in diameter for wood posts.
 3. When installing end terminals using tubes, install posts 1 and 2 to full depth or a minimum of 36 inches into the solid rock. Backfill the holes around the steel tube with the cutting spoils.
 4. See approved shop drawings for additional information concerning post depth and hole size.

To validate proper installation of posts, for each guardrail contractor/installer doing work for the Department, the Regional Operations and Materials and Tests offices may select any post for verification. If the posts are found to be in accordance with the Plans and Specifications, the Contractor may re-install the posts if they were not damaged during the pulling process. If the post length is found to be deficient, the Department will require the contractor/installer to remove the entire run of guardrail or end terminal and replace it properly at no cost to the Department.

Backfill holes with selected earth or other suitable materials in layers not to exceed 4 inches in thickness. Thoroughly tamp each layer. After backfilling and tamping is complete, hold the posts or anchors securely in place.

For metal divider guardrail on bridges, bolt posts to the structure as shown on the Plans. Set the anchor bolts to the proper location and elevation, with templates, and carefully check after the median is placed and before the concrete has set.

Set anchor bolts for metal divider guardrail, to be placed on a previously constructed bridge, by drilling holes in the proper locations and anchoring the bolts as shown on the Plans.

Repair damaged coating on galvanized steel posts as specified in **713.04.B**, or replace the posts, at the Engineer's direction, at no cost to the Department.

705.07 Erection

Set guardrail anchors, and make and place attachments as shown on the Plans and/or approved Shop Drawings, or as directed by the Engineer. Guardrail installed on new alignments is to be complete in place before the mainline roadway is opened to traffic unless otherwise directed by the Engineer. On roadways open to traffic, install each section of guardrail complete in place including end sections in a continuous operation.

Draw up tightly all bolts or clips used for fastening the guardrail or fittings to the posts. End bolts shall have sufficient length to extend at least $\frac{1}{4}$ inch through and beyond the full nut, except where such extension might interfere with or endanger traffic, in which case, cut off the bolt flush with the nut.

Erect, draw, and adjust all railings so that the longitudinal tension will be uniform throughout the entire length of the rail.

Shop curve Metal Deep Beam Single Guardrail and Protective Guardrail at Bridge Ends that are installed on a curve with a radius of 150 feet or less.

705.08 Final Cleanup

Perform final cleanup as specified in **104.10**.

COMPENSATION**705.09 Method of Measurement**

The Department will measure Guardrail of the various classes and dimensions in accordance with the Plans.

The Department will measure Terminal Anchors of the various types for payment by the unit within the limits shown on the Plans.

The Department will not measure projections or anchors beyond the end post for payment, except as noted.

The Department will consider excavation and backfilling, and the furnishing and placing of anchor bolts and devices for guardrail posts on bridges, to be incidental to the work.

705.10

705.10 Basis of Payment

The Department will pay for accepted quantities, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Guardrail (Class)	Linear Feet
Guardrail End Terminal (Type)	Each
Single Guardrail (Type)	Linear Feet
Guardrail at _____	Linear Feet

The Department will make no payment for a section of guardrail, including end terminals, until it is complete in place. Payment is full compensation for all posts, blocks, rail elements, terminal sections, fittings, hardware, labor and equipment, and all incidentals necessary to complete the work.

When no contract unit price has been established for Shop Curved Metal Deep Beam Single Guardrail, payment will be made at a rate equal to 1.5 times the contract unit price for Metal Deep Beam Single Guardrail with corresponding post spacing. When no unit price has been established for Shop Curved Protective Guardrail at Bridge Ends, payment will be made at a rate equal to 1.25 times the contract unit price of Guardrail at Bridge Ends.

No additional payment will be made for shop curving the guardrail in the Guardrail End Terminal units.

When no contract unit price has been established for drilling or boring in solid rock for posts while placing Single Guardrail or End Terminal Posts, the Department will pay for each hole at a rate equal to 2.0 times the contract unit price for Single Guardrail. When no pay item for Single Guardrail exists in the Contract, payment will be made at a rate of 2.0 times the current yearly State average.

While drilling or boring into solid rock for posts placed in conjunction with Guardrail at Bridge Ends, Parapets, Piers, Concrete Endposts, and other similar edifice, payment will be made at a rate equal to 1.25 times the contract unit price per applicable end device.

No additional payment will be made for drilling or boring for the placement of posts, unless posts are driven to refusal in solid rock.

**SECTION 706 – GUARDRAIL ADJUSTED, REMOVED
AND RESET**

706.01 Description.....	701
706.02 Materials	701
706.03 Reserved.....	702
706.04 Preliminary Work.....	702
706.05 Dismantling or Removing Guardrail.....	702
706.06 Installation of Posts.....	703
706.07 Erection.....	703
706.08 Guardrail Adjustment.....	703
706.09 Final Cleanup.....	703
706.10 Method of Measurement.....	703
706.11 Basis of Payment.....	704

DESCRIPTION

706.01 Description

Guardrail Adjusted or Removed and Reset consists of dismantling, removing, salvaging, resetting, or adjusting existing guardrail, as shown on the Plans or as directed by the Engineer. The work includes the furnishing of all necessary hardware, anchors, and other appurtenances required to replace those that are not suitable for reuse.

Posts Furnished and Guardrail Furnished consists of furnishing and setting guardrail and posts to replace rail and posts that are unsuitable for resetting, as shown on the Plans or as directed by the Engineer. Guardrail removed and reset shall comply with the Department's Standard Drawings and/or approved Shop Drawings, as applicable for the type of installation.

MATERIALS

706.02 Materials

Provide materials as specified in:

Guardrail Posts.....	909.07
----------------------	---------------

706.03

Remove, dismantle, reshape, repair, and reset all materials that can be reused.

For the reset rail, use salvaged material for posts, rails, cables, wire, metal sheets or plates, and similar features, but furnish whatever additional bolts, clips, and other appurtenances of the kind and quality used in the original guardrail as may be required to complete the guardrail.

Posts, rail and hardware furnished and set shall be of the size and type used in the original guardrail, or as shown on the Plans, and/or approved Shop Drawings, and shall meet the requirements of **909.05**, **909.07**, and **909.08**.

706.03 Reserved

CONSTRUCTION REQUIREMENTS

706.04 Preliminary Work

Perform Clearing and Grubbing, Removal of Structures and Obstructions, Excavation and Undercutting, and Embankment Construction as specified in **201**, **202**, **203**, and **205**, respectively.

706.05 Dismantling or Removing Guardrail

Carefully dismantle and detach railings, anchors, fittings, and all other material suitable for reuse from the posts, and neatly store and protect from damage.

Do not remove any sections of existing guardrail until the Engineer concurs the removal is necessary and the appropriate warning devices are installed. Promptly install the proposed guardrail, including any anchor system, to minimize traffic exposure to hazards.

Excavate or pull all posts so as not to damage the posts for further use.

Inventory, clean, and store all salvaged material until it is reset.

Replace, at no cost to the Department and with material of the same type and kind, all material damaged or lost on account of carelessness, negligence, or failure to properly protect the material and perform the work.

Remove broken posts or stubs and dispose of as directed by the Engineer.

706.06 Installation of Posts

Install posts as specified in **705.06**.

The Engineer will designate which posts are to be reused.

706.07 Erection

Thoroughly clean all posts and guardrail to be reset.

Space posts as originally spaced, unless otherwise shown on the Plans. Set posts vertically, and to the depth shown on the Plans or as established by the Engineer.

For all other details of erection, comply with **705.07**.

706.08 Guardrail Adjustment

Perform guardrail adjustment or realignment as shown on the Plans and in accordance with these Specifications and the following definitions:

- A. Realigned Guardrail:** Sections of guardrail that may be realigned without removal or disassembly and are not out of line horizontally plus or minus 6 inches or vertically plus or minus 2 inches.
- B. Adjusted Guardrail:** Guardrail that may be repositioned by the vertical adjustment of the block.
- C. Resetting Guardrail:** Entire sections of guardrail that require removal as directed by the Engineer.

706.09 Final Cleanup

Perform final cleanup as specified in **104.10**.

COMPENSATION

706.10 Method of Measurement

The Department will measure for payment:

706.11

1. Guardrail Removed, Guardrail Reset, and Guardrail Adjustment by the linear foot along the centerline of the guardrail, and from center of end post to center of end post.
2. Guardrail Furnished by the linear foot along the centerline of the rail before installations.
3. Posts Furnished by the individual unit.
4. End terminals in accordance with **705.09** and **705.10**.

The Department will not measure projections or end terminals beyond the end post, or any excavation or backfilling performed in connection with this construction.

706.11 Basis of Payment

The Department will pay for accepted quantities, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Guardrail Removed	Linear Feet
Guardrail Reset	Linear Feet
Guardrail Removed and Reset	Linear Feet
Guardrail Adjustment	Linear Feet
Posts Furnished	Each
Guardrail Furnished	Linear Feet

Payment for Guardrail Adjustment, Guardrail Removed, and Guardrail Reset is full compensation for all additional bolts, clips, and other incidentals required to complete the work.

SECTION 707 – FENCES

707.01 Description.....	705
707.02 Materials	705
707.03 Reserved.....	706
707.04 Preliminary Work.....	706
707.05 Setting Posts and Backfilling	706
707.06 Erecting Fence	707
707.07 Final Finishing and Cleanup	708
707.08 Method of Measurement	708
707.09 Basis of Payment.....	709

DESCRIPTION

707.01 Description

This work consists of constructing fences, gates, and water crossings.

MATERIALS

707.02 Materials

Provide materials of the kind, size, and type shown on the Plans, including all necessary posts, fittings, and appurtenances.

Provide materials as specified in:

Portland Cement Concrete, Class A.....	604
Stock Fence.....	909.01
Chain-Link Fence	909.02
Fence Gates.....	909.03
Water Gates and Water Crossings	909.04

The Engineer will reject galvanized material that is damaged. With the Engineer's approval, the Contractor may repair damaged galvanized material as specified in **713.04.B**.

707.03

707.03 Reserved

CONSTRUCTION REQUIREMENTS

707.04 Preliminary Work

Before beginning construction or placing of fences, perform all necessary Clearing and Grubbing and Removal of Structures and Obstructions as specified in **201** and **202**, respectively. Clearing for fence construction shall not extend beyond the right-of-way line. Do not disturb living trees and shrubs 1 foot or more on each side of the fence line unless otherwise directed by the Engineer. Locate the fence 1 foot inside the right-of-way unless otherwise shown on the Plans. Remove rock, which protrudes above the ground surface and is in the line of the fence, to the ground surface.

Turn fences in at drainage structures, cattle passes, and bridges where directed by the Engineer so as to abut wingwalls and abutments.

Provide two weeks notice to affected property owners before cutting existing fences. Install access control fences before cutting existing fences in areas used by domestic livestock or other areas as directed by the Engineer.

707.05 Setting Posts and Backfilling

Set line posts for stock fence at intervals not to exceed 10 feet. Erect braced line posts at intervals of 330 feet between end or corner posts, and, when necessary due to terrain features, install additional braced line posts at locations designated by the Engineer. Measure the interval between posts parallel to the bottom of the fabric of the proposed fence and in line of fence from center to center of post.

Set posts for chain-link fence at intervals not to exceed 10 feet. Measure the intervals between posts as specified above for stock fence.

Install posts, shown on the Plans to be set in concrete, in dug or drilled holes of the size and to the depth shown on the Plans or directed by the Engineer. For embedment of posts and for anchors, use Class A concrete meeting the requirements of **604**. Construct the concrete embedment and anchors with a crown at the top to shed water.

If ground conditions allow, the Contractor may drive posts that do not require embedment to the required depth using approved methods, or otherwise shall

install such posts in holes dug or drilled to the specified depth and to a size that will allow sufficient room for proper backfilling.

If solid rock is encountered, install posts by drilling the rock to the required depth and grouting the post therein with Portland cement grout composed of one part cement to three parts sand.

Backfill post holes for posts not requiring concrete embedment with selected earth or other approved material. Place backfill material in layers not exceeding 6 inches, and thoroughly tamp each layer. When backfilling and tamping is completed, secure the posts and anchors in the proper position.

Do not apply pull to posts set in concrete until the concrete has cured a minimum of 72 hours.

707.06 Erecting Fence

At certain locations along the right-of-way, the Engineer will direct the Contractor to construct chain-link fence or stock fence prior to the removal of existing fences.

When fences are constructed 1 foot inside the right-of-way, landowners may join these fences by setting posts adjacent to them.

A. Stock Fences

Place fabric by securing or fastening one end and applying sufficient tension to remove approximately one-half of the tension curve in the wire before making permanent attachment elsewhere. Fasten the fabric and barbed wire to the posts as shown on the Plans. Tightly draw up all bolts and clips or ties used to fasten wire or fittings to the posts. Use bolts of sufficient length to extend at least $\frac{1}{4}$ inch through and beyond the full nut; however, where such extension might constitute a safety hazard, cut the bolt off flush with the nut.

B. Chain-Link Fence

Place the fabric by securing one end and applying sufficient tension to remove all slack before making attachment elsewhere. Fasten the fabric to the posts at intervals not exceeding 14 inches. When specified, connect the top rail with expansion sleeves to form a continuous rail, and fasten the fabric to the rail at intervals not exceeding 2 feet. When using aluminum-alloy fabric, attach a tension wire to the bottom of the fabric

707.07

by means of a hog-ring type fastener at a maximum of 2-foot intervals, and secure the wire at the terminal posts with brace bands.

Pull barbed wire taut before permanently attaching to a post or extension arm.

When chain-link or stock fences cross short depressions or ditches, construct water crossings or water gates of the type, at the locations, and in accordance with the Plans or as directed by the Engineer.

Construct and install fence gates as shown on the Plans or as directed by the Engineer.

707.07 Final Finishing and Cleanup

The Engineer will inspect fences after they have been placed in final position. Dispose of all excess or unsuitable material as directed by the Engineer.

Perform final cleanup as specified in **104.10**.

COMPENSATION

707.08 Method of Measurement

The Department will measure:

1. Fences by the linear foot along the bottom of the fabric and from end to end of the fence, complete in place, deducting the width of openings.
2. Gates by the unit, per each, complete in place, for the kinds and dimensions as shown on the Plans.
3. Water Crossings, complete in place, by the length in linear feet, as determined in accordance with the details shown on the Plans.
4. Water Gates, complete in place, by the area in square feet, as determined in accordance with the details shown on the Plans.
5. End, braced line, and corner post assemblies as determined in accordance with the details shown on the Plans and the following:

- a. Chain Link Fence: The Department will measure each assembly consisting of one post and one or more horizontal rails and one or more truss rods, as detailed on the Plans by the unit.
- b. Stock Fences: The Department will measure each assembly consisting of one post, diagonal or horizontal braces and tie wires as detailed on the Plans, by the unit.

The Department will consider excavation, backfilling, and concrete for anchors and post embedment to be incidental to the work.

The Department will not measure projections or anchors beyond the end posts for payment.

707.09 Basis of Payment

The Department will pay for accepted quantities, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Fence (Description)	Linear Feet
Gate (Description)	Each
End, Braced Line, and Corner Post Assemblies (Description)	Each
Water Crossings	Linear Feet
Water Gates	Square Feet

Such payment is full compensation for all excavation, backfill, and all other incidentals necessary to complete the work.

708.01

SECTION 708 – MONUMENTS AND MARKERS

708.01 Description	710
708.02 Materials	710
708.03 Equipment	711
708.04 Foundation Preparation	711
708.05 Manufacture and Erection of Monuments and Markers	711
708.06 Final Finishing and Cleanup	712
708.07 Method of Measurement	712
708.08 Basis of Payment.....	713

DESCRIPTION

708.01 Description

This work consists of furnishing and erecting monuments or markers composed of Portland cement concrete or other materials approved by the Engineer. Monuments and Markers shall be of the kind, size, dimensions, shapes, and markings as shown on the Plans.

MATERIALS

708.02 Materials

Furnish monuments and markers manufactured of Class A concrete, composed of materials including reinforcement meeting **604.02**.

Provide concrete right-of-way markers that have a smooth finish and are fabricated as shown on the Plans.

Stone for monuments and markers shall meet **921.07**.

Metal materials shall conform to the requirements shown on the Plans or specified in the Special Provisions.

Provide paint, if required, that meets **910** for the kind and type of paint called for on the Plans.

EQUIPMENT

708.03 Equipment

Provide hoisting equipment, rollers, skids, protecting mats, and other equipment necessary to handle monuments or markers without damage.

CONSTRUCTION REQUIREMENTS

708.04 Foundation Preparation

A. Monuments

Unless otherwise shown on the Plans, excavate for monuments to not less than 6 inches larger on all sides than the base of the monument, and to a depth of not less than 6 inches below the grade of the base of the monument, unless solid rock is encountered. Remove all soft or yielding material in the foundation to such depth as directed by the Engineer, and refill and tamp in 6-inch layers with material satisfactory to the Engineer.

If solid rock is encountered, excavate to below the grade of the base, remove soft or flaky material, and bring to a true even grade.

Ensure that the foundations for all monuments are of such character as will hold the monument in place and in its intended position. Obtain the Engineer's approval of the foundation.

B. Markers

Prepare the excavation for markers by digging holes to the depth shown on the Plans or as directed by the Engineer, and of such size as will allow satisfactory backfilling and tamping. If rock is encountered above the grade of the base of the marker, the Contractor may cut off the marker, provided it is set 1 foot in solid rock and the area around the marker is filled with Class A concrete or mortar meeting **905.02**. Place the backfill in 6-inch layers. Thoroughly tamp each layer, and when the backfilling is completed, ensure that the marker is substantial and unyielding.

708.05 Manufacture and Erection of Monuments and Markers

Concrete monuments and markers may be precast or cast-in-place. The concrete shall meet the requirements of **604.03** for Class A concrete.

708.06

Manufacture monuments and markers in accordance with the applicable provisions of **604**.

Cut stone monuments and markers from stone conforming to **921.07** and to be of the size and shape and to contain such other details as shown on the Plans or as directed by the Engineer.

Place markers in the prepared excavation, and hold firmly in place, true to line and grade, until backfilled. Place backfill in 6-inch layers, and thoroughly tamp each layer.

Install or erect stone or precast monuments on the prepared foundation, set accurately at the proper elevation, and in a manner that will ensure they will remain firmly in place. Set the monuments on blocks or shims to line and grade. Fill the excavation below the bottom of the monument with Class A concrete. Work the concrete in, under, and around the base of the monument until all voids are filled. After the concrete has set, backfill the remainder of the excavation to the natural ground line with suitable material.

Perform painting, if called for on the Plans, as specified in **603**.

708.06 Final Finishing and Cleanup

The Engineer will inspect monuments or markers after they have been placed in their final position. Remove all defects and scars.

Neatly shape the surface of the ground immediately around each installation to the established grade. Dispose of all excess material as directed by the Engineer.

Perform final cleanup as specified in **104.10**.

COMPENSATION

708.07 Method of Measurement

The Department will measure Monuments and Markers for payment by the number of individual units furnished, placed, and accepted, complete in place.

708.08

The Department will consider excavation and foundation preparation, and the backfill material and concrete used in preparing foundations or backfilling the excavation, to be incidental to the work.

708.08 Basis of Payment

The Department will pay for accepted quantities, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Monuments (Description)	Each
Markers (Description)	Each

Such payment is full compensation for all labor, materials, equipment, and all other incidentals necessary to complete the work.

709.01

SECTION 709 – RIPRAP AND SLOPE PAVEMENT

709.01 Description	714
709.02 Materials	714
709.03 Classification.....	716
709.04 Equipment	717
709.05 Foundation Preparation	717
709.06 Rubble-Stone Riprap (Grouted)	717
709.07 Sacked Sand-Cement Riprap.....	719
709.08 Reinforced Concrete Slope Pavement.....	719
709.09 Machined Riprap.....	720
709.10 Final Cleanup	720
709.11 Method of Measurement	721
709.12 Basis of Payment.....	721

DESCRIPTION

709.01 Description

Riprap consists of furnishing and setting or placing rubble stones, crushed stone, sacked sand-cement, machined riprap, and embedded riprap.

Slope Pavement consists of constructing a reinforced concrete mat on prepared slopes.

MATERIALS

709.02 Materials

To construct riprap and slope pavement, provide materials that meet the following:

A. Rubble-Stone Riprap

For Rubble-Stone Riprap, provide stone or broken Class A or paving concrete meeting the requirements of **921.07**. Ensure that at least 80% of the stone have a minimum dimension of 10 inches. The remainder

shall be 2 to 4 inches and shall be approximately rectangular or trapezoidal in shape. Broken Class A or paving concrete shall be free of steel and wire fabric reinforcement.

For Rubble-Stone Riprap (Grouted), provide sand meeting **903.01** or **903.02** and cement meeting **901.01**.

B. Sacked Sand-Cement Riprap

For Sacked Sand-Cement Riprap, provide manufactured or natural sand meeting the quality requirements of **903.01** or **903.02** and cement meeting **901.01**.

Use sacks of either cotton or jute, standard grade of cloth, that will hold the sand-cement mixture without leakage during handling and tamping. Sacks shall be strong and sized to hold approximately 1 cubic foot.

C. Reinforced Concrete Slope Pavement

Construct reinforced concrete slope pavement of Class A concrete meeting **604.03** and steel reinforcement meeting **907.01** or **907.03**, whichever is specified.

Preformed expansion joint filler shall meet **905.01**.

D. Curing Materials

Provide materials meeting **913**.

E. Machined Riprap

For Machined Riprap, provide clean shot rock that is essentially free of sand, dust, and organic materials, and that is of the size designated for the class specified. The stone shall be uniformly distributed throughout the size range. Construct the stone layer to the thickness designated for the specified class, as defined in **709.03**, unless otherwise noted on the Plans.

Provide washed or clean rock, at no additional cost to the Department, for sensitive areas of the Project, as shown on the Plans, described in permits, or designated by the Engineer. Obtain the Engineer's approval

709.03

of washed or clean rock before placing in environmentally sensitive areas.

When using rock or stone as riprap, ensure that the material meets the quality requirements in **903.25**. Obtain the Engineer's approval of the material before using.

709.03 Classification

Riprap is classified according to the following designations:

1. Rubble-Stone Riprap (Grouted)
2. Sacked Sand-Cement Riprap
3. Machined Riprap
 - a. Machined Riprap (Class A-1) shall vary in size from 2 inches to 1.25 feet with no more than 20% by weight being less than 4 inches. The thickness of the stone layer shall be 1.5 foot with a tolerance of 3 inches.
 - b. Machined Riprap (Class A-2) shall be identical to Class A-1 except that the Contractor may substitute hand placed rubble stone riprap placed 1 foot thick in accordance with **709.11** for 1.5 feet of machined riprap.
 - c. Machined Riprap (Class A-3) shall vary in size from 2 to 6 inches with no more than 20% by weight being less than 4 inches. The thickness of the 4-inch stone layer shall be as shown on the Plans.
 - d. Machined Riprap (Class B) shall vary in size 3 inches to 2.25 feet with no more than 20% by weight being less than 6 inches. The thickness of the layer shall be 2.5 feet with a tolerance of 4 inches.
 - e. Machined Riprap (Class C) shall vary in size from 5 inches to 3 feet with no more than 20% by weight being less than 9 inches. The thickness of the layer shall be 3.5 feet with a tolerance of 6 inches.

EQUIPMENT

709.04 Equipment

Provide wooden or metal tamps of sufficient weight and number to properly compact the slopes on which the riprap or slope pavement is to be placed.

When using sacked sand-cement, furnish wooden hand tamps, having a tamping face not greater than 1 square foot, and of sufficient weight and number to properly tamp the riprap.

Provide a mechanical mixer to mix concrete, cement grout, or sand-cement.

Provide all necessary small tools or implements to perform the work.

CONSTRUCTION REQUIREMENTS

709.05 Foundation Preparation

Immediately before constructing riprap or slope pavement, trim the slopes or ground surface within reasonably close conformity to the lines and grades shown on the Plans or as directed by the Engineer, and thoroughly compact the slopes or ground surface using hand or mechanical tamps.

On slopes, place the bottom of the riprap at least 2 feet below the natural ground surface, unless otherwise directed by the Engineer.

709.06 Rubble-Stone Riprap (Grouted)

A. Placing Stone

Construct Rubble-Stone Riprap (Grouted) by hand on the prepared foundation. Place the stones as close together as is practicable to minimize voids.

When constructing rubble-stone riprap in layers, tie the layers together using large stones protruding from one layer into the other.

Construct rubble-stone riprap to a standard depth of 12 inches, unless otherwise shown on the Plans or directed by the Engineer, but in no case to less than 10 inches in depth. Ensure that, for each 25 square feet of surface, Rubble-Stone Riprap has an average depth of not less than the

709.06

depth shown on the Plans or as directed by the Engineer, or the standard depth required in these Specifications.

Place each stone with the larger dimension parallel to the surface upon which it is set, except as set forth above to provide keys between layers. Place the length as directed by the Engineer, and set each main stone against the adjoining stones to provide close contact. Place stone so as to equally distribute the large stones to the extent possible.

After a workable area of the riprap has been set, shape the stones by knapping to a uniform surface. Thoroughly chink the voids and fill with the smaller stones and spalls. Continue this work as construction progresses.

B. Grouting

After chinking and filling, fill the voids between the stones with grout. Take care to prevent earth or sand from filling the spaces between the stones before the grout is poured.

To fill the voids, use grout composed of one part Portland cement and four parts sand, measured by volume, and mixed thoroughly with sufficient water to make a grout of a consistency that will flow into and completely fill the voids.

Mix this grout either in a one-bag mixer or larger for not less than 1-1/2 minutes.

Immediately before pouring the grout, sprinkle the stones with water. Pour the grout carefully into the voids between the stones, beginning at the lower portions of the riprap and progressing upward. Ensure that the entire bottom line of voids is filled with grout before pouring the line of voids next above. To pour the grout, use vessels of adequate size and shape. Broadcasting, slopping, or spilling of grout from the vessels on the surface of the riprap will not be permitted. Progress of pouring shall be sufficiently slow to prevent the grout from oozing from the voids and flowing over the surface. During the pouring operations and continuing until the grout has reached its initial set, use fiber brooms to maintain a uniform distribution. Continue the grouting operations until all the voids have been completely filled and the grout has set even with the surface of the riprap.

C. Curing

As soon as any section of the grouted riprap has hardened sufficiently, sprinkle it with water until the riprap has been covered with burlap, cotton, or jute mats, earth, or liquid membrane-forming compound. Maintain the mats or earth by soaking with water for a period of not less than 72 hours. The water used for wetting and curing the grouted riprap shall be free from salt or alkali.

709.07 Sacked Sand-Cement Riprap

Construct Sacked Sand-Cement Riprap by placing sacks, filled approximately $\frac{3}{4}$ full of a mixture of sand and cement, on the prepared foundation.

Mix the sand and cement dry, with a mechanical mixer, in the proportion of 94 pounds of cement to 5 cubic feet of dry sand, until the mixture is uniform in color. After the mixing has been completed, pour the sand-cement mixture into sacks, of approximately 1-cubic foot capacity, until they are approximately $\frac{3}{4}$ filled. Securely fasten the sacks with hog rings, by sewing, or by using other suitable methods that prevent leakage of the mixture from the bags.

Bed the sacks of sand-cement, by hand, on the prepared grade with all the fastened ends on the grade and with the joints broken. The completed riprap shall have a minimum thickness of 10 inches, measured perpendicular to the slope. The surface shall not vary more than 3 inches above or below the desired theoretical plane.

Ram and pack the sacks against each other and tamp on the surface to form close contact and to ensure a uniform surface. Immediately after placing and tamping the sacks of sand-cement, thoroughly soak them by sprinkling with water. Do not apply water under high pressure.

Before soaking with water, remove and replace sacks of sand-cement that were ripped or broken during placing.

709.08 Reinforced Concrete Slope Pavement

Construct Reinforced Concrete Slope Pavement as shown on the Plans and in accordance with the applicable requirements of **604**, except that the concrete shall be of such consistency that it will not flow on the slope and that will allow finishing to the thickness shown on the Plans.

709.09

Score or saw the slope pavement for a depth of 1 inch on 6-foot centers, both ways, or as directed by the Engineer. Use a ½-inch preformed expansion joint filler wherever the slope pavement abuts a portion of the bridge sub-structure.

Remove forms, which may be of wood or metal, after the concrete has set. Cure the concrete as specified in **501.18**.

709.09 Machined Riprap

Take care in preparing the riprap subgrade to ensure that no reduction in the design waterway occurs. Do not place any riprap until the final subgrade elevation has been verified by the Engineer. When directed by the Engineer, roll the riprap down with metal tracked equipment to provide a more dense stone mass with final contours in reasonable conformance to the Plans. Do not begin to place the super-structure until the Engineer has accepted the final elevation of the riprap.

Upon completion of the work, visually inspect to ensure that approximately 50% of the surface area consists of stones no smaller than half of the maximum size specified.

Dump and place the material using appropriate power equipment in a manner that will produce a uniform surface appearance. Hand work may be required to correct irregularities.

When preparing the site, adhere to the provisions for erosion control specified in **209** and for channel excavation specified in **203.02.C**.

When required by the Plans or permits, or as directed by the Engineer, properly tamp into the subsurface, or otherwise blend into the substrate, embedded riprap in streams, conveyances, diversions, or other sensitive areas. Ensure that water will flow over the embedded riprap and that flow is not lost below or within the rock. If clean rock is required by the Plans or permit, or as directed by the Engineer, provide rock that meets the provisions of **709.02** for clean rock.

709.10 Final Cleanup

Perform final cleanup as specified in **104.10**.

COMPENSATION

709.11 Method of Measurement

The Department will measure Rubble-Stone Riprap (Grouted), Concrete Block Riprap, and Reinforced Concrete Slope Pavement by the volume in cubic yard, complete in place, as obtained from the thickness shown on the Plans and surface measurements. Unless otherwise specified, the Department will not measure or pay for reinforcement in slope pavement but will consider the costs thereof as included in the price bid for slope pavement.

The Department will measure Machined Riprap by the ton or the cubic yard for the respective items in accordance with **109**, complete in place. However, where Machined Riprap (Class A-2) is specified and the Contractor selects the hand placed rubble stone riprap option, the Department will increase actual tonnage measured and accepted by 50% for payment purposes.

No measurement for payment will be made for excavation or for preparing the foundation for riprap, and filter blanket where specified.

709.12 Basis of Payment

The Department will pay for accepted quantities, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Rubble-Stone Riprap	Cubic Yard or Ton
Rubble-Stone Riprap (Grouted)	Cubic Yard
Concrete Block Riprap	Cubic Yard
Reinforced Concrete Slope Pavement	Cubic Yard
Machined Riprap (Class __)	Cubic Yard or Ton

710.01

SECTION 710 – UNDERDRAINS

710.01 Description	722
710.02 Materials	722
710.03 Kinds and Sizes of Underdrains	723
710.04 Reserved.....	723
710.05 Aggregate Underdrains	723
710.06 Aggregate Underdrains (with Pipe).....	723
710.07 Filter Cloth and Aggregate Underdrain (with and without Pipe) .	724
710.08 Final Cleanup	725
710.09 Method of Measurement	725
710.10 Basis of Payment.....	726

DESCRIPTION

710.01 Description

This work consists of constructing underdrains composed of stone, gravel, slag, sand, or any one of these materials and perforated pipe, semi-circular drain pipe (with connections), or filter cloth, on prepared foundations at the locations shown on the Plans or as directed by the Engineer. The work shall include all necessary excavation and backfill, together with such work and materials as may be necessary to make connections with other drainage structures, as shown on the Plans.

MATERIALS

710.02 Materials

Provide materials as specified in:

Aggregate for Underdrains	903.17
Joint Mortar	905.02
Pipe (Size shown on the Plans).....	914.03, 914.07, 915.02, 915.03
Polyvinyl Chloride (PVC) Underdrain Pipe	914.09
Geotextile.....	921.12

710.03 Kinds and Sizes of Underdrains

Construct underdrains of the kinds specified. Unless otherwise specified, circular pipe for underdrains shall have a diameter of 4 inches. Semi-circular pipe for underdrains shall have a diameter of 4-5/8 inches. In the case of pipe, consider the size to mean the nominal inside diameter.

710.04 Reserved**CONSTRUCTION REQUIREMENTS****710.05 Aggregate Underdrains**

Excavate trenches to receive the aggregate at the locations and to the dimensions shown on the Plans or as directed by the Engineer. Make the trench deep enough to intercept the water-bearing strata and provide it with a smooth and uniform finish.

Place aggregate meeting the requirements of **903.17** in the trench in 6-inch layers to the depth shown on the Plans. Tamp each layer with an approved tamp.

Do not construct any underdrains that will not be paved over during the same construction season.

710.06 Aggregate Underdrains (with Pipe)

Excavate the trench to receive the pipe at the locations shown on the Plans or as directed by the Engineer. If the Plans do not show dimensions, construct the width of the trench to be not less than the outside diameter of the pipe plus 12 inches. Make the trench deep enough to intercept the water-bearing strata and to allow installation of the pipe and cover material. Unless otherwise shown on the Plans, spread a 2-inch layer of aggregate on the bottom of the trench, compact it, and bring to a uniform grade.

Ensure that the pipe is firmly embedded in the layer of aggregate. Lay perforated pipe with the flow sector and perforations at the bottom.

If an underdrain is extended through a dry fill or other section where perforated pipe is undesirable, construct the underdrain with the pipe specified, and join sections by forming mortar joints or approved manufactured joints, or by using connecting bands.

710.07

After the pipe has been laid and approved, carefully backfill around the pipe with the specified aggregate in a manner that will not displace the pipe. Place the aggregate around and over the pipe in 6-inch layers. Thoroughly tamp each layer with a vibratory compactor.

Make lateral and other connections where shown on the Plans or as directed by the Engineer.

710.07 Filter Cloth and Aggregate Underdrain (with and without Pipe)

A. Trench Excavation

Excavate trenches at the locations and to the depth and width shown on the Plans. Prepare the sides and bottom of the trenches to a relatively smooth condition, free of sharp objects, obstructions, depressions, and debris that might damage the filter cloth during installation.

Dispose of material removed from the trench outside of the right-of-way at locations obtained by the Contractor unless the Engineer authorizes its disposal within designated locations.

B. Filter Cloth

Place geotextile meeting **921.12** with the long dimension parallel to the centerline of the channel, laying it loosely without wrinkles or creases. When more than one width of filter cloth is necessary, overlap the joints a minimum of 12 inches. Insert securing pins with washers through both strips of overlapped material and into the material beneath, until the washer bears against the cloth and secures it firmly to the base material. Insert these securing pins through the overlapped cloth at not greater than 2-foot intervals along a line through the midpoint of the overlap.

Protect the cloth at all times during construction to prevent contamination by surface runoff. Remove contaminated cloth and replace with uncontaminated cloth at no cost to the Department. Replace cloth damaged during installation at no cost to the Department. Drop stone for overlaying on the cloth from a height no greater than 3 feet. Place the cloth so that the downstream edges overlap the upstream edges.

Install the filter cloth so that all splice joints are provided with a minimum overlap of 3 feet. Overlap the closure at the top of the trench as shown on the Plans, and secure with mechanical ties. Where outlet pipe passes through the fabric, use a separate piece of fabric of sufficient

size to be wrapped around the pipe and flared against the side of the filled drain fabric.

Anchor field splices of filter cloth with securing pins as directed to maintain the required overlap. Take care when placing the aggregate filler and installing the pipe (when specified) to prevent damage to the filter cloth. To repair a torn, punctured, or otherwise damaged section, cut a piece of filter cloth large enough to cover the damaged area and overlap all around the damaged area a minimum of 12 inches.

C. Aggregate Underdrain

Place the aggregate in 6-inch layers, and compact each layer using a vibratory compactor to the satisfaction of the Engineer before making the filter cloth closure at the top of the trench. Protect the exposed end of the outfall pipe by an endwall matching the existing slope.

Bevel the end of the outfall pipe to fit the slope of the endwall. Should the outlet end of the pipe or the endwall fall within the limits of ditch paving, remove to neat lines that portion of the ditch paving within the endwall limits necessary to provide a connection with the new endwall, and make the endwall blend with the ditch paving.

710.08 Final Cleanup

Dispose of all excess or unsuitable material as directed by the Engineer. Perform final cleanup as specified in **104.10**.

COMPENSATION

710.09 Method of Measurement

The Department will measure for payment:

1. Aggregate Underdrains by the linear foot along the centerline of the underdrains, and from end to end of the underdrains, complete in place.
2. Filter Cloth Underdrains and Filter Cloth Underdrains (With Pipe) by the linear foot along the centerline of each type of Underdrain (with or without pipe) installed.

710.10

3. Lateral Underdrain by the linear foot, as measured along the center of the outfall pipe from the center of the Filter Cloth Underdrain to the centroid of the beveled outfall end.
4. Lateral Endwalls by the unit, per each, for the type and size as indicated on the Plans.
5. 6-inch Perforated Pipe with Vertical Drain System by the linear foot along the centerline of the underdrains, and from end to end of the underdrains, complete in place.

710.10 Basis of Payment

The Department will pay for accepted quantities of underdrains of the various kinds and sizes installed, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Aggregate Underdrains (With Pipe)	Linear Feet
Filter Cloth Underdrain	Linear Feet
Filter Cloth Underdrain (With Pipe)	Linear Feet
Lateral Underdrain	Linear Feet
Lateral Endwall	Each
Perforated Pipe with Vertical Drain System	Linear Feet

Such payment is full compensation for all excavation, backfill, connections, specials, and all other incidentals necessary to complete the work.

Payment for Filter Cloth Underdrain is full compensation for furnishing and installing the 4-inch perforated underdrain pipe and pipe elbow when an underdrain outlet is required.

Payment for Lateral Underdrain is full compensation for excavating the trench, furnishing and installing the outlet pipe and all materials, backfilling and compacting the trench, disposing of excess materials, returning the shoulder and slope to the previously existing normal condition, and for providing all tools, equipment, labor, and incidentals necessary to complete this item of work.

Payment for Lateral Endwalls is full compensation for excavation, concrete, backfill, compaction, disposal of excess material, and for all tools, equipment, labor, and incidentals necessary to complete this item of work.

710.10

Payment for 6-inch Perforated Pipe with Vertical Drain System is full compensation for the pipe and pipe elbows, the installation of the materials including the polyethylene sheeting, and for all tools, equipment, labor, and incidentals necessary to complete this item of work.

In cases where the Bulk SSD specific gravity of the mineral aggregate exceeds 2.85, the Department will adjust the tonnage of mineral aggregate for payment by multiplying the tonnage of mineral aggregate used by a specific gravity of 2.85 and dividing by the higher specific gravity.

711.01

SECTION 711 – CONCRETE MEDIAN BARRIER

711.01 Description	728
711.02 Materials	728
711.03 Equipment	729
711.04 General	729
711.05 Finishing	729
711.06 Curing	730
711.07 Method of Measurement	730
711.08 Basis of Payment.....	730

DESCRIPTION

711.01 Description

This work consists of constructing cement concrete median barriers on a prepared subgrade.

MATERIALS

711.02 Materials

Provide materials as specified in:

Portland Cement	901.01
Fine Aggregate for Concrete.....	903.01
Coarse Aggregate for Class A Concrete:	
Size No. 467, 57 or 67	903.03
Joint Filler, Preformed Type	905.01
Steel Bar Reinforcement	907.01
Welded Steel Wire Fabric	907.03
Cement Concrete Curing Materials.....	913.05
Water.....	921.01
Air-Entraining Admixtures	921.06

For Portland cement concrete median barriers, use Class A concrete, meeting **604**.

EQUIPMENT

711.03 Equipment

Provide the applicable equipment specified in **604.04**.

CONSTRUCTION REQUIREMENTS

711.04 General

Construct concrete median barriers as shown on the Plans by fixed-form, slip-form, or precast methods.

Perform all necessary excavation and backfilling for the barriers, and satisfactorily dispose of all excess excavated material. Thoroughly compact the material adjacent to the median barrier base as directed by the Engineer.

Place slip-formed concrete with an approved slip-form placing machine designed to vibrate, consolidate, and finish the concrete in one pass of the machine so that a minimum of hand finishing will be necessary to provide a dense, homogeneous unit. Hold the sliding forms rigidly together to prevent spreading of forms and ensure after passing there is no noticeable slumping of concrete. Hold the concrete at a uniform consistency.

Where the median is concrete, form transverse contraction joints in the base and barrier to match the adjacent concrete median. Where the median is asphalt, construct transverse contraction joints in the base and barrier at a uniform spacing of 15 to 20-foot intervals. Construct joints in the barrier directly over the joints in the base. Construct transverse contraction joints as shown on the Plans. Where concrete median barrier is installed on concrete pavement, the joints in the barrier and pavement shall coincide.

Construct expansion joints in accordance with Plan details. Form expansion joints about all bridge piers, drainage inlets, concrete gutters, and other features projecting through, into, or against the barrier curb and base. Chamfer joints as specified in **604**.

711.05 Finishing

Concrete median barriers shall present a smooth, uniform appearance in their final position, conforming to the horizontal and vertical lines shown on the Plans or as directed by the Engineer. Ensure the top surface and the top

711.06

6 inches of the barrier, when checked with a 12-foot straight-edge, do not vary more than 1/8 inch from the testing edge of the straight-edge when placed parallel to the centerline. Correct deviations in excess of this requirement.

Do not begin corrective work on extruded median barriers until the barrier surfaces have set sufficiently to withstand further damage that could be caused by making corrections. Give the exposed surface of the median barrier a Class II finish or applied texture finish as specified in **604.21**. However, should the median barrier abut a similar barrier on a bridge, give the roadway barrier the same finish as that required on the bridge median barrier.

711.06 Curing

Perform curing as specified in **604.23**.

COMPENSATION

711.07 Method of Measurement

The Department will determine quantities of concrete median barrier, of the type specified, by measuring the length in linear feet, parallel to the centerline of the barrier, and including the joints but excluding all other openings in the barrier.

711.08 Basis of Payment

The Department will pay for accepted quantities, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Concrete Median Barrier (Description)	Linear Feet

Unless otherwise provided, such payment is full compensation for all required excavation, backfill, disposal of excess excavated material, reinforcement, joint materials, drilling and grouting, and all other incidentals necessary for the complete construction of concrete median barriers.

SECTION 712 – TEMPORARY TRAFFIC CONTROL

712.01 Description.....	731
712.02 Materials	731
712.03 Reserved.....	734
712.04 General.....	734
712.05 Pavement Marking Removal.....	742
712.06 Temporary Centerline and Lane Marking.....	743
712.07 Maintenance.....	743
712.08 Adjustment to Plans	744
712.09 Method of Measurement	744
712.10 Basis of Payment.....	746

DESCRIPTION

712.01 Description

This work consists of furnishing, erecting, and maintaining all construction warning signs, barricades, flexible drum channelizing units, temporary pavement markings, and other traffic control devices in accordance with the provisions of the current edition of the MUTCD, including all addenda, or as shown on the Plans or as directed by the Engineer for the purpose of safely directing traffic through construction zones. This work shall include installing additional devices as necessary in construction work zones.

MATERIALS

712.02 Materials

Provide traffic control and marking devices in accordance with the current edition of the MUTCD, except as herein modified.

Provide materials as specified in:

Signs:

Aluminum.....	916.02
Reflective Sheeting.....	916.06
Paint.....	916.09

712.02

Cold Rolled Carbon Steel -16 gauge	ASTM A1008
Non-metallic Drums and Barricades.....	QPL
Reflective Sheeting.....	916.06

A. Sign Sheeting Material

Sign sheeting material for all temporary construction signing shall be Type B or better, Fluorescent Orange color meeting the requirements of AASHTO M 268 and **916.06**. For all interstate projects, provide new fluorescent orange sign sheeting material; for all other construction projects, provide new or previously used sign sheeting that is in good condition.

B. Temporary Pavement Marking Material

Unless otherwise specified, the material for pavement marking line shall be either temporary pavement marking tape, or reflectorized paint with raised reflective pavement markers placed as shown on the Plans.

Where Removable Pavement Markings are specified, provide materials listed on the Department's QPL. Before use, the manufacturer shall certify to the Department that the removable tape is identical to that listed on the Department's QPL. Failure of the removable tape to perform satisfactorily with regard to installation or removability is cause for rejection of the material.

C. Cones

Cones shall be a minimum of 28 inches high and weighted at the base.

D. Portable Barrier Rail

Portable barrier rail shall meet the requirements of and be listed on the Department's QPL or Standard Drawings.

Provide certification from the supplier that the proposed portable barrier meets the requirements of and is listed on the Department's QPL or Standard Drawings. Submit all certification documents to the Engineer before delivery to the Project. Do not use different shapes, lengths, or connections of rail in the same continuous run.

E. Portable Impact Attenuators

Portable impact attenuators shall be in accordance with the Plans and Specifications, meet the requirements for the appropriate test level, and meet the requirements of and be listed on the Department's QPL or Standard Drawings.

F. Sign Supports

Stationary sign supports shall be steel posts meeting **916**. Do not use wood for stationary or portable sign supports. Provide portable sign supports that meet the requirements of and are listed on the Department's QPL or Standard Drawings. In splicing supports, use 5/16-inch diameter galvanized ASTM A449 (SAE J429 Grade 5) or galvanized ASTM F3125 Grade A325 bolts.

G. Vertical Panels

The substrate material for vertical panels shall be aluminum, meeting the requirements of **916.02**, or a high density copolymer polyethylene. The high density copolymer polyethylene shall be flexible and shatterproof for temperatures to -50 °F (ASTM D746). The reflective sheeting shall be AASHTO M 268 Type B or better, meeting the requirements for Fluorescent Orange material as specified in **916.06**. Attach the vertical panel (aluminum or copolymer) to a steel "U" post (weight 2.0 pounds per foot) meeting the requirements of **916.03**.

H. Flexible Drums, Flashing Arrow Boards, and Changeable Message Signs

Select Flexible Drums, Flashing Arrow Boards, and Changeable Message Signs that meet the requirements of and are listed on the Department's QPL or Standard Drawings.

Traffic control devices defined by the FHWA as Work Zone Category 1 and Category 2 devices weighing less than 100 pounds. Select all Category 1 and Category 2 devices that meet the requirements of and are listed on the Department's QPL or Standard Drawings. Alternatively, the Contractor may submit a notarized letter, along with documentation from the FHWA Office of Safety, certifying that Category 1 devices and Category 2 devices weighing less than 100 pounds meet the requirements of the Department's QPL and Standard Drawings.

712.03

Submit all certification documents to the Engineer before delivering these traffic control devices to the Project.

712.03 Reserved

CONSTRUCTION REQUIREMENTS

712.04 General

At the pre-construction conference, designate a responsible person who will be assigned to the Project to supervise traffic control.

Erect signs in a workmanlike manner such that all supports are plumb, sign panels are generally perpendicular to the travelway, and legends are horizontal so that they effectively convey the intended message. Do not display advanced warning signs more than 48 hours before physical construction begins. The Contractor may erect signs up to one week before needed, if the sign face is fully covered in a manner approved by the Engineer. Ensure that the sign sheeting is free of any damage that would reduce the reflectivity. Do not use overlay plates on signs. Mount signs on stationary or portable supports dependent on the type work being performed. Drive sign supports a minimum of 3.5 feet into soil or 1 foot into solid rock. Where soil and solid rock are both encountered, the depth of the sign support in the ground shall be:

$$d_1 + 3.5d_2 = 42$$

where

d_1 = depth in inches of support in soil

d_2 = depth in inches of support in solid rock

The Contractor may splice stationary U-Post sign supports that are 3 lbs/ft or less, provided the splice is a minimum of 18 inches. In addition, drive the stubs for the splice as required above and so as not to extend above 18 inches from ground level. A splice is only allowable with U-Posts and shall not be permitted for any other post types (square tube, round post, I-beam, etc.). Fasten the splice with four bolts, two placed at each end of the splice. In general, work being performed at spot locations and of short duration will necessitate the use of portable supports properly weighted for stability.

During periods of non-use, remove warning signs and other devices from the work area, and cover or otherwise position them so they do not convey their

message to the traveling public and do not present a safety hazard to drivers. If covered, maintain the covering material in a neat and workmanlike manner during its use. The method of covering the sign face shall not deface or damage the sheeting of the sign.

Use flashing or steady burning lights to light barricades and other devices that require lighting, as shown on the Plan details or as directed by the Engineer. Procure and bear the expense of a continuous power source.

A. Flaggers

Provide flaggers with proper attire and paddle when necessary to safely handle traffic through the construction zone. Ensure that flaggers are trained and certified in flagging operations by one of the following training programs:

1. American Traffic Safety Services Association (ATSSA)
2. National Safety Council (NSC)
3. Tennessee Transportation Assistance Program (TTAP)
4. ABET Accredited University Programs

The Department will accept flagger training programs developed and conducted by construction industry associations, consultant organizations, and contractors if they have an established, written program that meets all MUTCD requirements and Department Policy.

The Department will review and determine if an alternative training program is acceptable prior to use. Alternative training programs shall meet all MUTCD requirements and follow FHWA guidance.

The Department will consider flaggers to be a general requirement of traffic control and will not make direct payment for such.

Coordinate flagging operations in a manner that causes as little delay to the traveling public as possible. Delays shall be kept within 2 minutes or ¼ mile, but shall not exceed 5 minutes or a 1 mile maximum, unless prior authorization is granted by the Department.

B. THP Troopers and Uniformed Law Enforcement Officers

When requested by the Engineer or the Contractor and approved by the Regional Safety Coordinator or Regional Operations Office, a Tennessee Highway Patrol (THP) Trooper may be provided to enforce motor

712.04

vehicle laws and otherwise assist in securing the public safety. Submit requests for the THP at least 48 hours in advance of the requested time of service. If the THP is scheduled to work and the work is canceled, or the schedule is changed, notify the THP and the Engineer at least 2 hours before the scheduled start of work.

When a THP Trooper is not available, the Contractor may provide a Uniformed Law Enforcement Officer if approved by the Engineer and the Regional Safety Coordinator or Regional Operations Office. All Uniformed Law Enforcement Officers shall provide marked law enforcement vehicle equipped with blue lights and have the authority to write traffic tickets and make arrests within the project site. The Uniformed Law Enforcement Officer shall maintain a detailed written log of enforcement activities and shall submit the log to the Engineer for verification each month.

All Uniformed Law Enforcement Officers working on Department projects shall have training from a Peace Officer Standards and Training (POST) certified police training academy in the State of Tennessee and an additional 4 hours of FHWA approved work zone training. Submit records of this training to the Engineer.

C. Flashing Arrow Board

Install Flashing Arrow Board(s), meeting all requirements of the MUTCD, at the locations shown on the Plans or as directed by the Engineer. Ensure that the Flashing Arrow Board(s) will perform as specified herein. Correct or immediately replace all Flashing Arrow Boards that exhibit any type of malfunction, including improper dimming.

The Flashing Arrow Board shall be capable of displaying the following configurations:

1. Right Arrow – ten lamps flashing in unison forming an arrow
2. Left Arrow – ten lamps flashing in unison forming an arrow
3. Double Arrow – five lamps in each arrow head and three lamps in a common shaft all flashing in unison
4. Four Point Caution – four outermost corner lamps flashing in unison

Use the Flashing Arrow Board(s) in the single arrow mode for lane closure only, and situate and align them so that the flashing arrow is

clearly visible and legible. The single arrow mode display shall have ten lamps flashing in unison. Do not use the sequential arrow configuration, chevron arrow configuration, and horizontal bar configuration. The flash rate shall not be less than 25 flashes per minute or more than 40 flashes per minute. Minimum lamp “on-time” shall be 50% of the cycle.

Mount the Flashing Arrow Board(s) so as to provide a minimum of 7 feet between the bottom of the panel and the roadway.

D. Signs

Portable signs may be used when the duration of the work is less than 3 days or as allowed by other conditions in the proposal. Ensure that all portable signs and sign mounting devices used in work meet the requirements of and are listed on the Department’s QPL or Standard Drawings. When not being used, remove portable signs from the clear zone. Do not turn signs sideways or backwards while the signs are in the clear zone. Mount portable interim signs a minimum of 1 foot above the level of the edge of traveled way and at the height recommended by the manufacturer’s crashworthy testing requirements.

All regulatory sign blanks shall be rigid.

Make every effort to eliminate the use of interim signs as soon as the Work allows for the installation of permanent signs.

Maintain existing street name signs at street intersections.

Cover all signs or portions of a sign(s) that are not applicable to the Traffic Control Plan so as not to be visible to traffic, or remove such sign(s) from the roadway when not in use.

Do not remove existing signs and supports without the Engineer’s prior approval. Store and protect all existing signs and supports that are to be removed if this material will be required later in the Work.

Furnish, install, reuse, and maintain interim guide, warning, or regulatory signs required to direct traffic in accordance with the MUTCD. Mount the bottom of all interim signs at least 7 feet above the level of the pavement edge when the signs are used for long-term stationary operations as defined in the MUTCD.

712.04

Maintain existing guide and exit directional signs on the Project until conditions require a change in location or legend content. When change is required, the signs shall be in accordance with the Traffic Control Plan. When an existing guide and exit directional sign is in conflict with work to be performed, remove the conflicting sign and reset it in a new, non-conflicting location that has been approved by the Engineer.

When it is not possible to use existing signs, either in place or relocated, furnish, erect, maintain, modify, relocate, and remove new interim guide and exit directional signs as shown on the Plans or as directed by the Engineer.

Complete the installation of new permanent guide and exit directional signs, and the permanent modification or resetting of existing guide and exit directional signs, when included in the Contract, as soon as practicable to minimize the use of interim guide and exit directional signs.

E. Worker Visibility and Safety

Ensure that all workers within the Project's right-of-way, who are exposed to either vehicular traffic or to construction equipment in the work area, wear high-visibility safety apparel. Consider high-visibility apparel to be personal protective clothing that meets performance Class 2 or Class 3 of the ANSI/ISEA 107 publication. Provide Class 3 apparel for night work.

F. Portable Barrier Rail

Place all portable barrier rail as far away from the travel lanes as possible while serving the intended purpose. Move or remove all portable barrier as directed by the Engineer. The Department will make no additional payment for removing barrier that is no longer required.

G. Lane Closures

Hold the length of a lane closure to the minimum length required to accomplish the Work. Locate advanced warning signs for the Project so as to not overlap with the advanced warning signs for lane shifts and lane closures.

Use drums in all transition tapers for lane closures on multi-lane roads.

Contractor's Staff performing a lane closure shall have certifications that meet the requirements in Table 712.04-1 to close lanes on TDOT facilities and shall be onsite during each lane closure performed.

Table 712.04-1: Lane Closure Certification Requirements

Type of Facility	Requirement
Two Lane	Flagging Operations Certification (Shall comply with 712.04.A)
Multi-Lane	*ATSSA Traffic Control Technician Training or equivalent
Controlled Access Freeways & Expressways	*ATSSA Traffic Control Technician Training or equivalent

* Proof of certification shall be provided to the Engineer at the Pre-Construction Meeting.

H. Night Work Lighting

When the Contract requires night work, supply sufficient lighting and equipment as specified herein.

1. **Lighting Plan.** Submit the following information regarding the lighting plan to the Engineer:
 - a. Descriptions and sketches of the layout of lighting devices including spacing, luminary height, lateral placement, and anticipated illuminance provided.
 - b. Photometric and physical specifications of all lighting equipment.
 - c. Detailed description of all lighting to be used on construction equipment.
 - d. Methods to be employed to reduce glare.
 - e. Contractor's frequency and procedure for checking illumination levels.
2. **Protective Equipment and Lighting.** In addition to their standard protective equipment, equip construction personnel and equipment as follows:

712.04

- a. Traffic Control Persons, all equipment operators, and all other workers shall:
 - (1) Wear high-visibility apparel that meets performance Class 2 or Class 3 of the ANSI/ISEA 107 publication. Class 3 apparel shall be required for night work.
 - (2) Have a minimum of 12 square inches of reflective material added to their hard hats that is visible from all sides.
- b. Also equip Traffic Control Persons with:
 - (1) A flashlight complete with semi-transparent red cone, and
 - (2) Radios or cell phones so that they may communicate with each other.
- c. All workers shall receive specific training on night work operations.
- d. All vehicles in the work area must operate rotating or flashing incandescent amber lights visible in 360 degrees around the vehicle.
- e. All work vehicles including trucks must have red and white reflective tape applied to all sides such that it defines the outline of the vehicle.

Provide the equipment specified in Table 712.04-2 with non-glare balloon style lights or equivalent. The lights will be required on each piece of equipment in operation.

Table 712.04-2: Night Work Lighting Requirements

Equipment Type	Illuminance Requirement
Paver, Milling Machine, Material Transfer Devices	One 4000-watt assembly or two 2000-watt assemblies
Grader, Roller, Rumble Strip Machine, Shoulder Machine	One 400-watt assembly
Paint truck	One 400-watt assembly or a non-glare 300-watt floodlight assembly
Guardrail driver, stationary operation	One 4000-watt assembly or two 2000-watt assemblies or equipment light plant
Trail Vehicle	One 4000-watt assembly or two 2000-watt assemblies

A trail vehicle will be required to follow the last piece of equipment in a mobile operation (i.e. finish roller, pavement marking, etc.) depicting the beginning of the working area. In addition, ensure that portable lighting of at least 400 watts is available for the density testing inspector. The Engineer will determine the illuminance requirement for other vehicles not listed in Table 712.04-2. The Contractor may substitute a 400-watt metal halide lamp or equal approved by the Engineer for a 2000 or 400-watt balloon light assembly.

Locate and direct all luminaries in such a way to minimize glare to both motorists and work vehicles. If glare is noted from any travel path, adjust the lighting to reduce the glare to a level acceptable to the Engineer.

Replace non-functioning lamps immediately. Check the luminary aiming daily. Regularly clean the luminaries.

I. Specification Compliance

The Engineer will notify the Contractor of failure to comply with this Specification or the Plans. The safe passage of pedestrians and traffic through and around the temporary traffic control zone, while minimizing confusion and disruption to traffic flow, shall have priority over all other Contractor activities. Continued failure of the Contractor to comply with the requirements of the Traffic Control Standard Specification or Special

712.05

Provisions will result in non-refundable deductions of monies from the Contract for non-performance of Work as long as the deficiency remains.

Failure of the Contractor to comply with this Specification or take immediate correction actions required within 48 hours of written notice shall be reason for the Engineer to suspend all other work on the Project, except erosion prevention and sediment control and traffic control, to apply non-refundable deductions of monies from the Contract at a rate of \$2,500 per calendar day per notice, and to withhold payment of monies due to the Contractor for any work on the Project until traffic control deficiencies are corrected. These other actions shall be in addition to the deductions for non-performance of traffic control.

712.05 Pavement Marking Removal

Remove conflicting pavement markings, in a manner acceptable to the Engineer, to prevent confusion to vehicle operators.

Remove final surface pavement markings by sand blasting, water blasting, or acceptable grinding methods that will cause the least possible damage to the pavement.

Remove intermediate surface pavement markings by sand blasting or water blasting, or other approved methods that will cause the least possible damage to the pavement. The following methods are acceptable for removing intermediate surface pavement markings: sand blasting using air or water, high pressure water, steam or superheated water, or mechanical devices such as grinders, sanders, scrapers, scarifiers, and wire brushes.

At no cost to the Department, repair damage to the pavement or surface resulting from pavement marking removal using methods and materials acceptable to the Engineer. The removal shall not result in what appears to be a line that conflicts with the current markings.

Accomplish traffic shifts on the final surface using interim traffic marking tape unless otherwise shown on the Plans.

Do not remove an existing pavement marking by painting over with black paint or asphalt.

When the method of removal causes sand or other material to accumulate on the pavement, remove the residue as the work progresses.

712.06 Temporary Centerline and Lane Marking

Unless otherwise specified, install temporary pavement marking as follows:

1. Provide 4-inch wide pavement marking line as shown on the Plans for projects that will have traffic maintained overnight. For temporary pavement line markings on intermediate layers of pavement, use reflective tape, reflectorized paint, and raised pavement markers, or a combination thereof as shown on the Plans or as required by the Engineer, and install to permanent standards before dark hours. Short, unmarked sections will not be allowed. The Department will measure and pay for these markings as Painted Pavement Marking (Line) in accordance with **716.08** and **716.09**. Preserve established no-passing zones, if any, on the existing pavement; if no-passing zones have not previously been established, establish them before beginning the work. Mark two-lane, two-way highways with 10-foot long center lines applied on 40-foot centers and appropriate no-passing barrier lines.
2. Where required on the completed permanent surface, for 10-foot lane lines, no-passing barrier line, and edge line, use reflectorized paint applied as specified in **716**.
3. Maintain pavement markings at no additional cost to the Department until they are covered by the subsequent paving course or the Project is accepted.
4. It will not be necessary to remove pavement markings except for markings that convey conflicting or incorrect information to the traveling public.

712.07 Maintenance

Assume full responsibility for the continuous and expeditious maintenance of all signs, barricades, temporary impact attenuators, and all other traffic control devices to meet the “acceptable” category as described in *Quality Guidelines for Temporary Traffic Control Devices and Features* published by ATSSA. Such maintenance will be considered a part of the original installation cost. Failure to maintain all traffic control devices so as to provide continuous safety to the public will be cause for suspension of construction operations until proper traffic control is re-established.

712.08

712.08 Adjustment to Plans

Maintain traffic through the Project in accordance with the traffic control plan and the MUTCD. To request a change to the traffic control plan, submit a plan revision request in writing to the Engineer for approval, with the requested change marked in red on the traffic control plans sheets. The Engineer may adjust the traffic control plan as deemed necessary to ensure the safety of the workmen and traveling public.

COMPENSATION

712.09 Method of Measurement

The Department will measure the following for payment:

1. Signs, including Vertical Panels, erected on suitable supports by the actual area in square feet installed, with no deductions made for corner radii.
2. Flexible Drums for channelizing traffic by the unit, per each, as determined by counting the maximum number of drums on a jobsite and in use at any one time. This shall be designated by making a notation such as "On October 29, 2013, there were 242 Flexible Drums in use. Pay quantity is 242 Each." This will not apply to phase construction projects. On phase construction projects, each phase is treated as a separate project to arrive at a final pay quantity. The highest number used on Phase I, plus the highest number used on subsequent phases, will constitute the final pay quantity.
3. Barricades by the linear foot for the type designated.
4. Delineators and Temporary Flexible Tubular Delineators by the unit, per each.
5. Warning Lights and Flashing Arrow Boards by the unit, per each for the type designated. Payment will be based on the maximum number in place at one time.
6. Portable Barrier Rail by the linear foot. Separate measurement will be made for the initial installation of portable barrier rail at each site that the rail is used on the Project as shown on the Plans or approved by the Engineer. No separate measurement will be made for

removing and resetting portable barrier rail on new alignment at the same site to provide for changes in traffic control required by the different phases of construction. The following conditions apply to measurements of portable barrier rail:

- a. The sites on one directional roadway of a divided highway will be considered independently of the sites on the other directional roadway.
 - b. Each bridge for which portable barrier rail is shown on the Plans or approved by the Engineer will be a separate site.
 - c. Additional relocations of barrier rail due to safety of work zone or traffic, as established in the traffic control plans or as directed by the Engineer laterally up to 10 feet, will be paid at 10% of the interconnected portable barrier bid amount unless a separate item is in the proposal.
7. Portable Impact Attenuators based on the initial installation of each portable impact attenuator. No additional payment will be made for removal, moving, and reinstalling impact attenuators at other locations on the Project as directed by the Engineer. Payment will be based on the maximum number of portable impact attenuators in place at one time.
 8. Temporary pavement marking line as described for Painted Pavement Marking Line in **716.07** regardless of whether the lines are painted, taped markings, or raised pavement markers, or a combination of the above as shown on the Plans or as required by the Engineer, except that Removable Pavement Marking (Line) will be measured by the linear foot of installed line.

Unless otherwise specified, the Department will not separately measure or pay for traffic cones, removal of pavement marking, and flaggers, as these items will be considered incidental to the lump sum item Traffic Control.

The Department will pay for THPs, but the Contractor is responsible for notifying the THP and the Engineer when work has been canceled within 2 hours of the scheduled start of work. If the THP is not notified of work cancellation and the THP elects to monitor/patrol the project for a maximum of 2 hours, the Department will deduct from the monies owed the Contractor an amount equaling the THP pay rate for 2 hours of work.

712.10

The Department will pay for Uniformed Law Enforcement Officers provided by the Contractor at the per hour invoice price of the officer's work plus 5%, not to exceed \$60 per hour for the total hours present on the Project. No compensation will be made for drive time.

712.10 Basis of Payment

The Department will pay for accepted quantities, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Traffic Control	Lump Sum
Portable Barrier Rail	Linear Feet
Portable Impact Attenuator	Each
Signs	Square Feet
Vertical Panels	Square Feet
Flexible Drums	Each
Temporary Barricades (Type)	Linear Feet
Removable Pavement Marking (Description)	Linear Feet

The lump sum payment for Traffic Control is full compensation for providing Temporary Workzone Lighting and all equipment, labor, and materials, and for furnishing flaggers and traffic cones, and for removing conflicting and incorrect pavement markings, as required, until Project completion.

Payment for Portable Barrier Rail is full compensation for all materials, installation, maintenance, and all incidentals necessary to complete the work.

Payment for Portable Energy Absorbing Terminals will be made at the contract price per Portable Energy Absorbing terminal, complete in place, with total payment based on the maximum number of portable energy absorbing terminals in place at one time as specified in **712.09**.

Payment for Signs and Vertical Panels is full compensation for providing sign panels with proper sheeting and legend, erecting on proper supports, furnishing all mounting hardware, covering when not in use, relocating, handling, and maintaining until Project completion.

Payment for Barricades is full compensation for materials, equipment, relocating, handling, maintaining, and all incidentals of the work.

Unless otherwise designated, all signs, barricades, and other traffic control devices covered by this section shall become the property of the Contractor

712.10

at the completion of the Project. The salvage value for these items shall be reflected in the contract unit price bid.

The Department will pay for 10-foot lane line/center line and solid barrier line as Painted Pavement Marking (Line) in accordance with **716.08**.

Payment for Removable Pavement Marking Line, 8-inch Barrier Line, Channelization Striping or Stop Line, is full compensation for the installation, maintenance, and removal of the marking line when it is no longer required.

Payment for Uniformed Police Officers is full compensation for providing the Officer, official law enforcement vehicle, all necessary equipment, and administrative costs associated therewith.

713.01

SECTION 713 – HIGHWAY SIGNING

713.01 Description	748
713.02 Materials	748
713.03 Reserved.....	749
713.04 Construction Methods and Requirements	749
713.05 Final Cleanup	753
713.06 Method of Measurement	754
713.07 Basis of Payment.....	755

DESCRIPTION

713.01 Description

This work consists of constructing foundations and supports, fabricating, furnishing, assembling, and erecting traffic signs on the supports, including delineators when specified, for a section of highway, its interchanges, frontage roads, and roads or streets affording immediate access to the highway.

Construct and erect highway signs and devices in accordance with these Specifications and the MUTCD, latest edition.

The Plans will show the extent and general arrangement of the signs. Refer to the Plans for general guidance. If departures from the Plans and Specifications are deemed necessary by the Contractor, submit the reasons for and details of such departures to the Engineer for approval. Do not make any departure without the Engineer's prior written approval. For departures from the Plans, submit for the Engineer's approval eight copies of drawings showing the complete design of the proposed departure and all other information necessary to complete the sign assembly.

MATERIALS

713.02 Materials

Provide materials as specified in:

Portland Cement Concrete, Class A.....	604
--	-----

Highway Signing Material.....	916
-------------------------------	-----

713.03 Reserved**CONSTRUCTION REQUIREMENTS****713.04 Construction Methods and Requirements**

Before beginning any excavation or driving any sign posts, determine the location of all underground electrical, drainage, and utility lines in the vicinity, and perform work so as to avoid damaging these facilities.

All signs are numbered or otherwise identified. Locate signs as shown on the Plans. Obtain the Engineer's approval for all changes in locations before erection.

Locate delineators as shown on the Plans and in accordance with the MUTCD.

Place the top of all sign footings level with the ground line. Remove the existing footings of signs to be eliminated to 6 inches below ground line.

The Engineer, or Contractor when required, will stake the location of all sign supports and delineators and mark the location of each sign with the number of the sign. After the sign locations have been staked, but before ordering any material for the supports, allow for a field inspection and approval by the Engineer. Construct the signs at the approved locations.

Ensure steel meets all specifications in **602.04**.

A. Flexible Delineator Posts

Drive the flexible delineator posts or anchors into the ground with equipment that does not damage the posts, anchors, or the reflective sheeting. Drill or form pilot holes where necessary to obtain the embedment shown on the Plans.

B. Post Supports for Ground Mounted Signs

Furnish and erect post supports consisting of one or more posts of the type shown on the Plans.

713.04

Drive all posts into the ground, or bolt to a stub in the concrete foundation. Plumb, align, and orient posts as shown on the Plans. To drive posts, use a method that will not damage or deface the top of the post.

For sign posts that are to be bolted to or stubbed in a concrete foundation, excavate as nearly to neat lines as possible and generally pour all parts of the sign post foundation against the soil or rock face. Use forming below ground level in sandy soils or when directed by the Engineer. Forming will be required for all concrete work above the finished ground level and the top 12 inches of all concrete work. Provide necessary braces to keep anchor bolts and stubs in proper position. For foundations, use Class A concrete, meeting the requirements of **604.03**. Perform forming and concrete work as specified in **604**. Remove and dispose of all surplus excavated material.

Repair all cracked, chipped, or scratched galvanized steel members by “touching-up” with an approved zinc powder, wire, stick, or spray manufactured especially for this purpose. The zinc powder, wire, or stick shall become completely liquid at a temperature no greater than 475 °F. Thoroughly clean the area to be regalvanized, including removing slag on welds, and repair according to the recommendations of the manufacturer of the material being used.

C. Foundations for Sign Supports

Furnish all materials and labor, and perform all necessary construction to complete the foundations upon which the sign supports will be erected.

1. **Excavation and Backfill.** Excavate and backfill as specified in **204**.
2. **Disposing of Surplus or Unsuitable Material.** Dispose of surplus or unsuitable material as specified in **203.07**.
3. **Forms.** Construct forms as specified in **604.05**.
4. **Steel Reinforcement.** Provide steel reinforcement as specified in **604.08**.
5. **Electrical Conduit.** Install electrical conduit, when specified, in the foundations as shown on the Plans.

6. **Concrete.** Use either (1) Class A concrete meeting **604.03** or (2) Class X concrete with a f'_c as identified in the plans or required by the design. If Class X concrete is required, use a mix meeting the minimum requirements of **604.03** for Class A concrete, but with a cementitious material quantity necessary to produce the specified strength.
7. **Placing Concrete.** Place concrete as specified in **604.16**.
8. **Setting Anchor Bolts and Stubs.** Set anchor bolts and stubs for sign supports to proper locations and elevations with templates, and carefully check them after constructing the sign foundation and before the concrete has set. Anchor rods shall conform to the requirements of **730.11**.
9. **Surface Finish.** Perform finishing as specified in **604.21**.
10. **Curing.** Cure concrete as specified in **604.23**.

D. Column Supports for Cantilever Structures

Fabricate and erect supports and horizontal arms constructed of galvanized steel. The supports shall consist of one or more vertical poles, one or more horizontal arms, and all necessary fastenings for assembling the units and anchoring the supports to a foundation.

Use leveling nuts to plumb supports. Erect cantilever supports so that the arms are horizontal.

Assemble all high strength bolt connections as specified in **602.17**.

Perform all welding as specified in **602.19**.

The Engineer will reject supports on which galvanizing has been damaged in transportation, handling, and erection. With the Engineer's approval, the Contractor may replace such damaged supports in the field as specified in **713.04.B**. The repaired area shall be similar in appearance and in coating thickness to the original coating. The Engineer will reject supports that are not coated satisfactorily.

713.04

E. Supports for Overhead Sign Structures

Fabricate and erect truss sign supports constructed of aluminum or galvanized steel.

Erect the structures with the specified camber and so as to prevent excessive stresses, damage, or defacement.

Provide brackets for mounting signs (including future signs) of the type to be supported by the structure. They shall be adjustable to allow mounting of the sign faces at any angle between a truly vertical position and 3 degrees from vertical. Obtain this angle by tilting the top of the sign toward traffic. All brackets shall be of a length equal to the heights of the signs being supported.

Before erecting aluminum end supports, protect the bottom of each base plate with an approved material that will adequately prevent any harmful reaction between the plate and the concrete.

Use leveling nuts to plumb the end supports. Do not fill the space between the base plate and the foundation with grout.

Tighten all nuts on aluminum trusses, except those used on the flanges, only until they are snug. This includes the nuts on the anchor bolts. Use a thread lubricant with each aluminum nut.

Tighten all nuts on galvanized steel trusses, with the exception of high strength bolt connections, only to a snug condition. Assemble all high strength bolt connections as specified in **602.17**.

Repair galvanizing on steel trusses as specified in **713.04.B**.

Field welding will not be permitted.

F. Signs

Furnish, fabricate, and erect signs on their supports.

When alternates are allowed, all legends, borders, and accessories for an entire project shall conform to the requirements of one and only one of the alternates.

Mechanically apply the reflective sheeting to the properly prepared aluminum with the equipment and in the manner prescribed by the sheeting manufacturer.

All completed signs shall be free from defects in materials and workmanship and shall effectively present the specified message under conditions of both day and night viewing. Reflectorized sign surfaces shall exhibit uniform color and brightness over the entire background surface and shall not appear mottled, streaked, or stained when viewed either in ordinary daylight or in the incident beam of an automobile headlamp.

The reflectorized legend optical performance shall uniformly reflect incident light from motor vehicle headlamps back to the eyes of the operator at entrance angles up to 30 degrees without gaps or irregularities.

Position signs on, and fasten them to, the support as shown on the Plans or as directed by the Engineer. All signs, once erected, shall be clean and free of substances that would hide or otherwise obscure any portion of the sign face. Attach flat sheet signs to the posts with tamper resistant fasteners.

After the sheeting is thoroughly attached to the sign face, attach demountable letters, digits, borders, shields, and alphabet accessories flush against sign faces, with corrosive resistant fasteners as recommended by the manufacturer. Use a sufficient number of fasteners to securely fasten demountable legends and borders to sign panels.

Provide demountable borders of the width shown on the Plans. Place demountable borders as shown on the Plans. Spacing of all legends shall meet the FHWA Standard Alphabets for Highway Signs. Any improper size or spacing of legends and borders shall be cause for rejection of the entire sign.

713.05 Final Cleanup

Before final inspection, clean exposed sign and support surfaces, and level and repair the site as directed by the Engineer to ensure the effectiveness and neat appearance of the work. Perform final cleanup as specified in **104.10**.

713.06

COMPENSATION

713.06 Method of Measurement

The Department will measure:

1. Class A Concrete and Steel Bar Reinforcement for embedment of sign supports, and for foundations for sign supports and overhead sign structures, in accordance with **604.30**.
2. Mile Marker and Steel Posts by the unit, per each, complete in place.
3. Flexible delineator posts with reflective sheeting, anchors, and all material necessary for erection of this item payment by the unit, per each, in place.
4. Aluminum or Steel Hollow Square Posts for sign supports, Aluminum or Steel I-Beams and WF-Beams for sign supports, Structural Steel Hollow Square Posts (Break-Away) for sign supports, and Structural Steel I-Beams and WF-Beams (Break Away) for sign supports by the pound based on the nominal weight per foot listed on the sign schedule, for the various sizes and weights used, complete in place.
5. Aluminum or Steel Overhead Sign Structures and Steel Cantilever Sign Structures by the unit, per each, complete in place, including the footings and all incidentals necessary to construct these items.
6. "U" Section Steel Posts by the pound, based on the nominal weight per foot listed on the sign schedule, for the various sizes and weights used, complete in place.
7. Flat Sheet Signs by the square foot for each thickness, complete in place.
8. Extruded Aluminum Panel Signs for payment by the square foot complete in place, except that the measurement will be made only for the actual dimensions of the extruded panels. No payment will be allowed for any space between panels.

The Department will consider conduit, excavation, and backfilling to be incidental to the associated items.

713.07 Basis of Payment

The Department will pay for accepted quantities, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Class A Concrete (Foundation for Sign Supports)	Cubic Yard
Steel Bar Reinforcement (Foundation for Sign Supports)	Pound
Mile Marker & Steel Post	Each
Flexible Delineator (Description)	Each
(Description) Sign Supports	Pound
Steel Overhead Sign Structure (Span ____)	Each
Steel Cantilever Sign Structure (Sign No.)	Each
“U” Section Steel Posts	Pound
Flat Sheet Aluminum Sign (____ ” thick)	Square Feet
Extruded Aluminum Panel Sign	Square Feet

Such payment is full compensation for furnishing all materials, equipment, tools, labor, and incidentals necessary to complete the work.

714.01

**SECTION 714 – ROADWAY AND STRUCTURE
LIGHTING**

714.01 Description	756
714.02 Materials	757
714.03 Codes.....	758
714.04 Reserved.....	759
714.05 Conduit.....	759
714.06 Pull Boxes	762
714.07 Underground Cable for Lighting Circuits	763
714.08 Light Standards	765
714.09 Bracket Arms	767
714.10 Luminaires	767
714.11 Lamps.....	770
714.12 Installation of Overhead Wires	770
714.13 Cable Markers	770
714.14 Control Center.....	770
714.15 Field Painting	771
714.16 Testing After Installation	771
714.17 Repair of Seeded and Sodded Areas	773
714.18 Disposal of Excess or Unsuitable Material	773
714.19 Final Cleanup	773
714.20 Method of Measurement	773
714.21 Basis of Payment.....	776

DESCRIPTION

714.01 Description

This work consists of furnishing and installing roadway and structure lighting systems complete or to the extent shown on the Plans.

MATERIALS

714.02 Materials

Provide materials as specified in **917** and as follows:

Portland Cement Concrete, Class A.....	604
Crushed Stone Grading D.....	903.05
Steel Bar Reinforcement for Concrete Structures.....	907.01
Welded Steel Wire Fabric.....	907.03
Gray Iron Castings.....	908.07
Inorganic Zinc Paint	910.03
Cement Concrete Curing Materials	913
Conduit	917.05 or 917.07

Within 30 days after the issuance of the work order, submit to the Engineer, four collated sets of the manufacturer's descriptive literature and technical data, fully describing the types of lighting equipment proposed for use. In the descriptive literature, identify the manufacturer and model, and include sufficient information for the Engineer to determine if the equipment or material meets the requirements of the Plans and these Specifications. Include with these sets of submittal data a list of the materials submitted along with descriptive material for, but not limited to, the following items when applicable:

1. Complete photometric data of luminaires as published by the manufacturer with independent testing laboratory results.
2. Computer printouts showing illumination levels throughout each interchange area where high mast luminaires are to be installed.
3. General details of light standards, breakaway bases, and bracket arms. For light standards taller than 30 feet, submit one set of design calculations and six prints of "Design" or "Shop" drawings to the Division of Structures for approval purposes. The Department will review these drawings at the earliest possible date, and will return two prints marked "Approved for Fabrication," or "Returned for Revisions as Noted." Respond by taking appropriate action to ensure the earliest possible correction of these items so as not to delay the installation.
4. Highmast tower details with a set of design calculations for each height including access hole, base, anchorage, head frame, and

714.03

lowering device. Include specification references for materials and location, type, size, and extent of welds. In addition to the set of design calculations, submit six prints of "Design" or "Shop" drawings for each highmast tower height to the Division of Structures for approval purposes, in a manner similar to that specified in Item 3 above for light standards taller than 30 feet.

5. Dimension sheets and performance data on all related equipment.

The Engineer will retain one copy and forward one copy each to the local entity (city or county engineer) and the Traffic Operations Division for their review.

Also include with the submittal sets detailed scale drawings of all non-standard or special equipment and of all proposed deviations from the Plans. Deviations from the Plans or Specifications require approval from the Traffic Operations Division. Include a letter requesting deviations or alternate materials in the submittal for Traffic Operations Division approval. Upon request, submit for approval sample articles of materials proposed for use. The Department will not be liable for any materials purchased, labor performed, or delay to the Work prior to such approval.

In addition to the above, include with each submittal a notarized letter certifying that all lighting system materials listed in the submittal conform to the Plans and Specifications. Also submit to the Engineer a statement from the Maintaining Agency that all lighting system materials listed in the submittal are acceptable to the Agency.

714.03 Codes

Furnish material and perform all work in strict accordance with the latest revision of the National Electrical Code, the National Electrical Safety Code, the Illuminating Engineering Society (IES) publications, ANSI standards, and the codes, regulations, and rules prevailing in the area in which the Work is being performed, as applicable.

714.04 Reserved**CONSTRUCTION REQUIREMENTS****714.05 Conduit**

Install conduit of the type and size specified at the locations shown on the Plans, or as directed by the Engineer. Install pull or drag wires of the type and size specified in conduit at the locations shown on the Plans.

A. Underground Conduit

1. **General.** Underground conduit shall consist of encased or direct burial conduit. Install conduit in a trench excavated to the dimensions and lines specified.

Before beginning any excavation, determine the location of all electrical, drainage, and utility lines in the vicinity, and perform work so as to avoid damaging these facilities. Ensure that the conduit will be located so as to avoid conflict with proposed guardrail, sign posts, and other features.

Build conduit runs in straight lines where possible. Where sweeps are necessary, use standard long sweep conduit bends when feasible, and meet the minimum radius required by the National Electric Code. Install pull boxes at intervals so that the tensile strength of the conductors will not be exceeded.

Obstructions encountered when excavating trenches for underground conduit may require minor changes, such as in locations of conduit runs and pull boxes. Obtain the Engineer's approval before making such changes. Where possible, provide a minimum of 12 inches between the finished lines of conduit runs and utility facilities, such as gas lines, water mains, and other underground facilities not associated with the electrical system. Where the conduit run is adjacent to concrete walls, piers, footings, and similar structures, maintain a minimum of 4 inches of undisturbed earth or firmly compacted soil between the conduit and the adjacent concrete or, when the conduit is encased, between the encasement and the adjacent concrete.

714.05

Unless shown on the Plans, do not excavate trenches in existing pavement or surfaced shoulders to install conduit. If it is necessary to place a conduit under an existing pavement, install the conduit by jacking or other approved means with galvanized rigid steel conduit or schedule 80 PVC conduit.

Keep jacking and drilling pits at least 10 feet from the edge of the paved shoulder or sidewalk unless otherwise directed by the Engineer. When the Plans specifically allow excavation of a trench through an existing pavement or surfaced shoulder, restore the pavement and/or surface and base to their original condition. Do not leave boring pits open for extended periods of time.

Unless otherwise specified, cut trenches for conduit on a slight grade for drainage, and make the walls of the trench essentially vertical. Tamp the bottom of the trench as necessary to produce a firm foundation for the conduit.

Excavate trenches for rigid metallic conduit, with or without encasement, to a minimum depth of 18 inches, plus conduit diameter, measured from the finished subgrade.

Sheet and brace the trenches as required, and adequately support all pipe and other structures exposed in trenches as necessary to prevent damage.

Ream metallic conduit after threads are cut. Ream other conduit as necessary. Cut all ends square and to butt solidly in the joints to form a smooth raceway for cables.

Ensure that conduit joints form a water-tight seal. Coat metallic conduit threads with pipe compound and then securely connect. Make conduit joints with the materials and in the manner recommended by the conduit manufacturer and as approved by the Engineer.

Install conduit bushings in conduit where necessary and required for protection of the conductors. When the conduit is installed for future use, ensure that the ends of metallic conduit runs are properly threaded and capped, and that the ends of non-metallic conduit runs are satisfactorily plugged or capped to prevent water or other foreign matter from entering the conduit system.

- a. **Encased Conduit.** Place encased conduit under roadway and paved shoulders unless trenching is required for installation at the locations shown on the Plans. Unless otherwise specified, construct encasement as follows:
- (1) Construct the encasement of Class A concrete meeting the requirements of **604**.
 - (2) Extend the encasement of conduit under roadway pavements or surfaces to the outer edges of the surfaced or paved shoulders, or 1 foot beyond the outer edge of the sidewalk, or 1 foot beyond the outer edge of the curb when no shoulder or sidewalk is indicated.
 - (3) Extend the conduit at least 6 inches beyond the encasement.
 - (4) Encase the pipe with a minimum of 3 inches of concrete.
 - (5) Plug the ends of the conduit temporarily to prevent the entrance of concrete or other foreign material.
 - (6) Do not encase any conduit with concrete until inspected and approved by the Engineer.
 - (7) Cure concrete encasement as specified in **604.23**, except that the curing period may be reduced to 24 hours if backfilling is to proceed at the time specified in **714.05.A.2**.
- b. **Direct Burial Conduit.** When rock is encountered in the bottom of the trench, install the conduit on a bed of well compacted fine grain soil at least 4 inches thick.
2. **Backfilling Conduit.** Do not backfill encased conduit until the concrete encasement has cured a minimum of 24 hours. After the Engineer has inspected and approved the installation of direct burial conduit, promptly backfill to the required grade with approved material in layers not exceeding 6 inches in loose depth and compact each layer as directed by the Engineer.

714.06

B. Conduit on Structures

Install conduits, conduit fittings, hangers, expansion fittings, and accessories as shown on the Plans and, unless otherwise specified, in accordance with the following:

1. Run conduit parallel to beams, trusses, supports, pier caps, and similar features in the most direct manner.
2. Install horizontal runs on a slight grade, without forming low spots, to ensure proper drainage.
3. Run conduits with smooth, easy bends.
4. Hold conduits in boxes with locknuts and provide bushings for protection of the conductors.

C. Testing Conduit

After completing the installation of conduit, test it with a metallic mandrel in the presence of the Engineer. Use a mandrel having a diameter $\frac{1}{4}$ inch smaller than the conduit, and a length of 2 inches. Repair, to the Engineer's satisfaction, all conduits that will not allow passage of the mandrel. If repairs cannot be accomplished, remove and replace the conduit at no additional cost to the Department.

After the mandrel test, scour all conduits with a stiff wire brush having a slightly larger diameter than the conduit.

Test conduits that have been installed under a previous contract with a mandrel and clean as described above before installing the cables.

714.06 Pull Boxes

Construct pull boxes in accordance with the design, dimensions, and at the locations shown on the Plans. Construct concrete pull boxes of Class A concrete meeting the requirements of **604**. Place non-metallic pull boxes only in non-traffic bearing locations and not in paved areas.

Provide a cast iron frame and cover or reinforced concrete cover, as shown on the Plans, with each pull box.

Plug unused conduit entrance holes and openings for conduit to be extended by others with suitable plugs of plastic, bituminous fiber, or other approved material to prevent the entrance of foreign matter.

714.07 Underground Cable for Lighting Circuits

Underground cable for lighting circuits shall consist of direct burial cable, preassembled cable in duct, or cable in conduit, as shown on the Plans.

If it is necessary to install a cable under an existing pavement or surfaced shoulder, install conduit, when specified, in accordance with the applicable provisions of **714.05**, and place the cable within the conduit.

Construct walls of trenches for cables to be essentially vertical. Unless otherwise specified, install underground cable as follows:

1. Excavate trenches for direct burial cable to a minimum depth of 24 inches plus the cable diameter as measured from finished subgrade.
2. In general, locate the trenches to avoid conflict with proposed guardrail, sign posts, and other features.
3. Protect direct burial cable, and preassembled cable in duct, in trenches by cushioning with sand or earth that passes a ¼-inch screen. Place the cable, or preassembled cable in duct, and sand or earth in the trench so that a minimum 3-inch thickness of the cushion material will surround each cable.

A. Direct Burial Cable

Do not unreel cables and pull into the trench from one end. Unreel the cables, lay them alongside the trench, and then lay in the trench. Allow the cables to “snake” slightly in the trench to provide adequate slack for settling of earth. Ensure that there are no crossovers of cable in the trench. Where cable is brought up into the base of the lighting standard, leave sufficient slack for making the connections inside the standard.

B. Preassembled Cable in Duct

When installing in the trench, do not pull preassembled cable in duct taut, but allow it to “snake” in the ditch to provide not less than 18 inches

714.07

slack per 100 feet of trench. The minimum bending radius on the cable duct shall be 18 inches. Where the duct is brought into the base of the lighting standard or into a pull box, leave sufficient length for trimming the duct to expose enough cable to allow for the connections to be made inside the standard or pull box.

C. Cable in Conduit

Carefully pull cables in conduits into place using approved methods so that the cable will be installed without electrical or mechanical damage. Pull all cables within a single conduit at the same time. If necessary, to ease the pulling, use a lubricant of the type recommended by the cable manufacturer. When cables are pulled through hand holes in pole shafts, place a pad of firm rubber or other suitable material between the cable and the edges of the opening to prevent cable damage.

After the cable has been installed in the conduit, seal the ends of buried conduit with approved pliable and non-hardening material to prevent the entrance of dirt, moisture, or other foreign material.

D. Splices

Splice conductors as shown on the Plans. Only make splices at accessible points, such as handholes and pull boxes, unless otherwise shown on the Plans. After making a conductor splice, insulate it with heat-shrinkable tubing, supplied by the manufacturer, with an adhesive coating on the inner wall.

E. Ground Wire

Install ground conductors of the type and size shown on the Plans, and to be continuous in trenches with direct burial cable, and continuous inside preassembled cable in duct, and in conduit. Connect the ground conductors to the ground rod at all control points, to the ground lug in pole foundations, and to all metallic conduit runs using a grounding bushing, except that the connections to conduit in pole foundations may be omitted. Make all connections as shown on the Plans.

F. Backfilling Underground Cable

Backfill cable as specified in **714.05**.

G. Cable Identification

To assist in the identification of circuits at the pull boxes, mark the phase conductors with colored rubber-based, or equivalent, paint. When final connections are made, provide permanent tape wire markers to identify the branch circuit conductors (X1A, X1B, etc.), neutral (X1N, etc.), and the ground (g).

714.08 Light Standards

Install light standards of the designated design, kind, size, and class in accordance with and at the locations shown on the Plans. Ensure that the installed standards, complete with the bracket arm(s) and luminaire(s) as specified, provide the mounting height shown on the Plans. Determine the pole height as required by bracket arm upsweep, slope conditions, and similar characteristics.

A. Foundations for Light Standards

Consider transformer bases to be an integral part of the lighting standard unless otherwise specified.

1. Bolt-Down Base Pole Foundations

- a. **Concrete Foundations.** Excavate a hole of the size and depth shown on the Plans. Remove and dispose of all excavated material as directed by the Engineer. Place anchor bolts of the type and size specified according to the pole manufacturer's recommendations, and securely hold to ensure proper position in the completed foundation. Ensure that no realignment of anchor bolts will occur after the foundation is poured. Accurately place reinforcing steel and securely hold to avoid displacement.

Accurately place conduits in foundations, orient them in the proper direction to accommodate service cables, and securely hold to avoid displacement.

Place Class A concrete in the excavated area against undisturbed earth to an elevation 4 inches below the finished ground line, and in an approved form from 4 inches below said ground line to the finished top of foundation elevation, as specified. Construct the foundation with a continuous concrete

714.08

pour. Chamfer the edges of the top and formed portion of the foundation. Apply a Class II finish, as specified in **604.21.B**, to the portion of the foundation above grade and within 4 inches of grade.

- b. **Metal Foundations.** Install metal foundations where shown on the Plans and, if desired, at locations where installation is possible without predrilling the hole.
2. **Prestressed Concrete Butt Base Pole Foundations.** Excavate prestressed concrete butt base lighting standard foundations using manual or mechanical methods. Dig or drill the holes to the depth and the diameter shown on the Plans. Place and compact in the bottom of the hole 6 inches of crushed stone, meeting the requirements of **903.05**, Grading D.
3. **Wood Poles.** Excavate for wood poles as specified for prestressed concrete butt base pole foundations in **714.08.A.2**. Dig or drill the holes to the depth shown on the Plans and in such diameter to allow satisfactory use of mechanical tamping equipment.

B. Light Standard Installation

Handle the standards or poles as recommended by the manufacturer and approved by the Engineer. Accomplish erection without marring the finish or otherwise damaging the standard. Ground the light standards as shown on the Plans. When installing lighting on a bridge, review the proposed bridge plans or the completed structure before ordering the standards.

1. **Bolt-Down Base Poles.** Set standards with bolt-down bases on foundations constructed as specified in **714.08.A.1**. Use metal shims supplied with the poles to plumb the pole, if the twin bracket arm type is used; and, unless otherwise specified, to rake or lean the pole backward 4 inches, if the single bracket arm type is used.
2. **Prestressed Concrete Butt Base Poles.** Place prestressed concrete butt base lighting standards in the hole and on the layer of crushed stone prepared as specified in **714.08.A.2**. Position the pole in the center of the hole at grade and hold in place. Rake the lighting standards with single bracket arms as specified for poles with bolt-down bases in **714.08.B.1**. Set lighting standards with two bracket arms plumb. Fill the space surrounding the pole butt-base with

crushed stone, applied in 6-inch layers. The crushed stone shall meet the same requirements specified for the stone foundation in **714.08.A.2**. Moisten the stone backfill material as necessary, and thoroughly compact each layer with mechanical tamping equipment. Continue the backfill with crushed stone to the depth of the bottom edge of the cable entrance in the butt base. After completing the installation of the electrical cable, continue placing the crushed stone backfill in 6-inch layers, and compact to a depth of 1 foot below grade. Backfill the remaining 12 inches with soil in two equal layers, and thoroughly compact each layer.

3. **Wood Poles.** Place wood poles in holes excavated as specified in **714.08.A.2**. Set the pole in the center of the hole, with any vertical curvature of the pole located in the plane of the lines, and rake in a direction opposite that of the unbalanced stress where a guy or underbrace is specified. Backfill the hole with approved material applied in 6-inch layers, and thoroughly compact each layer with mechanical tamping equipment. Install cross arms and guying components, when specified, as shown on the Plans.

C. Highmast Tower Installation

Install standards with lowering devices on foundations constructed as shown on the Plans. Ensure that the standards are plumb. Assemble the shaft in the Engineer's presence. Do not perform any field welding between sections of the shaft. Erect the tower according to the manufacturer's recommended procedures and under the manufacturer's supervision. Make adjustments to align all parts and ensure operation. Arrange for the manufacturer or its representative to instruct the local utility in the proper operation of the lowering device.

714.09 Bracket Arms

Install, on the lighting standards, bracket arms of the specified type, design, kind, dimensions, and number as shown on the Plans.

714.10 Luminaires

Use the following luminaire types on the roads and bridges: High Intensity Discharge (HID) which includes High Pressure Sodium (HPS) and Metal Halide (MH); Fluorescent and Induction lamps; and Light Emitting Diode (LED).

714.10

Install luminaires of the design and size shown on the Plans, and level according to the manufacturer's recommendations, as shown on the Plans and as approved by the Engineer. Provide glare shields on luminaires when shown on the Plans.

Clamp the pole and bracket cable in the proper terminals on the terminal board in the luminaire, and then splice the cable to the proper phase and neutral conductors outside of the handhole in the pole base. After other required circuit splices are made outside of the handhole, place all of the wire inside the handhole. Leave slack in all cables for future maintenance. Attach a suitable identification tag to each of the phase cables.

Clean luminaire reflector surfaces and glassware after installation. Perform cleaning, if required, according to the luminaire manufacturer's recommendations.

Ensure that luminaires for sign lighting are adjustable both horizontally and vertically.

A. High Intensity Discharge (HID)

High Intensity Discharge (HID) luminaires shall meet IES standards from LM-51-00 to LM-35-02. The HID luminaire shall be covered by a one-year written warranty starting from the system acceptance date. All the other electrical and mechanical component parts of the HID shall be covered by a five-year written warranty starting from the system acceptance date. The signed warranty certificate shall be submitted prior to final payment.

B. Light Emitting Diode (LED)

Light Emitting Diode (LED) luminaires shall be manufactured in accordance with ANSI C136.37-2011 (or recent version). All testing and data sheets for proposed LEDs shall be included in the submittal package and shall include, but not limited to, the following: Illuminating Engineering Society of North America (IESNA): LM-79-08, LM-80-08, RP-8-14, TM-3-95, and TM-15-07 (all should be up-to-date versions). In addition to these requirements, the LEDs shall meet the following requirements:

1. **Finished surface.** Furnish luminaires with the color mentioned in the plans. The surface of luminaire housing shall meet UL-1598

listed for wet locations, ASTM B117 for salt chamber exposure, and ASTM D1654 for rust creepage.

2. **Thermal Management.** The luminaire shall start and operate in the ambient temperature range of -25C to +25C.
3. **Optical Assembly.** The LED optical assembly package shall have a minimum Ingress Protection rating of IP 66 according to ANSI/IEC 60529. The luminaire shall have a standardized refractor/reflector to meet the required optical distribution as required by the plans. The optical assembly shall utilize high brightness, long life, minimum 70 color rendering index (CRI), (3000 K-5700 K) color temperature (+/-300 K) LEDs binned according to ANSI C78.377. Lenses shall be UV-stabilized acrylic or glass. Provisions for house-side shielding shall be provided when specified.
4. Prevent the entrance of wildlife by limiting openings around the pipe tenon mounting area.
5. Electrical Parts (including Safety Testing) shall comply with an ANSI C136.41 with 7-pin receptacle that is fully pre-wire for LED driver's control.
6. Documents for the materials submitted need a certification from a National Voluntary Laboratory Accreditation Program (NVLAP) and that lab must be recognized by the U.S. Department of Energy.
7. The entire LED luminaire and all of its component parts shall be covered by a 10 year written warranty covering materials, fixture finish, and workmanship. Failure is when one or more of the following occur:
 - a. Negligible light output from more than 10 percent of the LED packages.
 - b. Condensed moisture inside the optical assembly.
 - c. Driver that continues to operate at a reduced output below 15 percent of the rated nominal output. The warranty period shall start from the system acceptance date. The signed warranty certificate shall be submitted prior to final payment.

714.11

714.11 Lamps

Install lamps of the design, type, and size, and at the locations shown on the Plans.

714.12 Installation of Overhead Wires

Install overhead wiring, when specified, as shown on the Plans.

714.13 Cable Markers

When shown on the Plans, place precast or cast-in-place concrete cable markers, of the dimensions indicated, at all locations where lighting cables make an abrupt change in direction. Construct the markers of Class A concrete meeting **604**. Imprint an arrow on each marker to indicate the direction of the cable run as it approaches and leaves the marker. Also imprint the circuit number on the marker.

Recess the markers into the ground approximately 3 inches, unless otherwise specified.

714.14 Control Center

Furnish and install a service pole or poles of the design, type, size, and class, and at the locations shown on the Plans. Install the service pole(s) as specified in **714.08** and as shown on the Plans. Set the service pole(s) plumb.

Notify the power company, at least 30 days before connection, of the need to furnish power to operate the lighting system.

Unless otherwise specified, furnish and install all the control center equipment and electrical supply facilities. The electrical supply facilities shall include the necessary service conduit from the control cabinet to the delivery point designated on the Plans.

Construct a concrete slab, of the dimensions and thickness indicated, around the service pole foundation. Construct the slab of Class A concrete meeting the requirements of **604**, and reinforce the slab, if specified, as shown on the Plans.

Construct a 6-foot chain-link fence and gate of the size specified around the control center as shown on the Plans and as specified in **707**.

714.15 Field Painting

After erection is completed, thoroughly clean steel standards that are not galvanized, and then apply two coats of inorganic zinc paint meeting the requirements of **910.03**. Perform painting as specified in **603**.

If the shop coat of prime paint is damaged, cover the damaged areas with a coat of the same type of paint as used for the original primer coat, and allow it to completely dry before applying the first coat of aluminum paint.

If the finish on galvanized steel materials is scratched, chipped, or otherwise damaged, the Engineer will reject the material, or may allow it to be repaired as specified in **713.04.B**.

714.16 Testing After Installation

Install all materials and equipment to form a complete installation ready for operation, unless otherwise specified.

After the installation is completed, test the lighting system in the presence of a Department representative and the Maintaining Agency. Tests shall include insulation resistance, voltage, current, and performance tests. Unless otherwise specified, perform the tests in accordance with the following:

A. Voltage Tests

Take a voltage reading at the control center at the load side of the circuit protection device and the last lighting standard served in each branch circuit. In cases where the circuit feeds in two or more directions, take the voltage reading at the light most remote from the control point or as directed by the Engineer. Unless otherwise specified, with the complete lighting system energized and all lamps operating, the voltage of this last standard shall not be less than 90% of the nominal rated voltage of the luminaire supply circuit, and the voltage at the last underpass luminaire in each branch circuit shall not be less than the minimum operating voltage recommended by the manufacturer of the luminaire ballast.

714.16

B. Current Test

Conduct current tests at each control center at the load side of each circuit protection device, using a clamp-on type ammeter. Current, in amperes, in each supply conductor shall not be greater than the rated current of a luminaire times the number of luminaires in the circuit.

C. Grounding Resistance Test

Conduct ground resistance tests with a “megger,” manufactured by the James H. Biddle Company, or a “vibraground” manufactured by Associated Research Incorporated or approved equal.

Adhere to the following when conducting this test:

1. Ensure that no equipment, such as ballast or oil switches, is connected at the time of the test.
2. Test only one conductor at a time.
3. Isolate the conductor being tested from ground.
4. Ensure that the other phase conductor and the neutral are grounded during each test.

D. Performance Tests

Prior to acceptance and after all faults have been corrected, operate the lighting system, including automatic control equipment and other specified apparatus, for a continuous 48-hour period without interruption or failure attributable to poor workmanship or defective material. After the 48 hours of continuous operation, the Engineer will inspect all lights and equipment for normal operation. Make all necessary repairs or replacements to the Engineer’s satisfaction.

Make arrangements with the Servicing Agency to purchase the electric power necessary to conduct all tests.

Furnish the Engineer five copies of the test results, together with five copies of a statement from the Maintaining Agency that the system is acceptable to the Agency.

714.17 Repair of Seeded and Sodded Areas

If areas previously seeded or sodded are disturbed during the performance of the work described in this Section, reseed (with mulch) or re-sod such areas as specified in **801** or **803**, respectively. Perform these repairs as the work progresses to minimize erosion of disturbed areas.

714.18 Disposal of Excess or Unsuitable Material

Dispose of excess or unsuitable material as specified in **203.07**.

714.19 Final Cleanup

Perform final cleanup as specified in **104.10**. Remove existing foundations, designated for removal, to a minimum of 6 inches below grade. Before final inspection, touch-up finishes, clean surfaces including signs that are lighted, and perform such other work as directed by the Engineer to ensure the effectiveness and neat appearance of the work.

COMPENSATION**714.20 Method of Measurement**

When the bid schedule contains an item for Roadway and Structure Lighting on a lump sum basis, measurement will be for the sum of all items to be furnished and installed.

When the bid schedule contains items for various elements of Roadway and Structure Lighting, the Department will make measurement for payment as follows:

A. Conduit

The Department will measure:

1. Encased Conduit and Direct Burial Conduit by the linear foot of conduit for each kind, number, and size installed as indicated, and
2. Conduit (Structures) of the kind and size specified by the linear foot of each individual kind and size of conduit placed.

714.20

B. Pull Boxes

The Department will measure Pull Boxes by the unit, per each.

C. Cable

The Department will measure Cable of the type, and number and size of conductors specified, by the linear foot from the center to center of pull boxes, light standards, and similar features, for each type and number and size of conductors. No additional allowance will be made for slack length, length inside equipment or standards, and similar instances requiring additional length of wire.

D. Preassembled Cable in Duct

The Department will measure Preassembled Cable in Duct by the linear foot from the center to center of pull boxes, light standards, and similar features. No additional allowance will be made for slack length.

E. Light Standards

The Department will measure Light Standards of the kind and design specified by the unit, per each.

F. Luminaires

The Department will measure Luminaires of the size, type, and design specified by the unit, per each, regardless of their classifications (i.e. LED, HID).

G. Overhead Conductors

The Department will measure Overhead Conductors of the gauge, type, and kind specified by the linear foot between supports. No allowance will be made for slack length.

H. Cable Markers

The Department will measure Cable Markers by the unit, per each.

I. Control Center

The Department will measure the Control Center on a lump sum basis. Such measurement will be for the sum total of all items to be furnished and installed at the control center, except as specified in **714.20.J** and **714.20.K**.

J. Class A Concrete

The Department will measure Class A Concrete used to construct the concrete slab around the service pole at the control center by the volume in cubic yards, as determined from the specified thickness shown on the Plans and surface measurements for width and length. The Department will not measure reinforcement for the concrete slab for payment but will consider the costs thereof as incidental to the item for Class A Concrete.

K. Chain-Link Fence and Gate

The Department will measure and pay for Fence and Gates in accordance with **707.08** and **707.09**, respectively.

L. Navigational Lighting and Overhead Sign Lighting

The Department will measure Navigational Lighting and Overhead Sign Lighting furnished and installed in accordance with the Plans on a lump sum basis.

M. Incidental Items

The Department will consider incidental, and will not directly measure, the following:

1. Excavation and backfilling performed in connection with this construction.
2. The removal and satisfactory disposal of existing pavement, surface, and base required to install conduit, and for restoring the base, pavement, and surface to their original condition.
3. Furnishing, installing, and subsequently removing sheeting, bracing, and supports needed to install conduit.

714.21

4. Labor, materials, equipment, electrical energy, and incidentals required to conduct the performance tests specified in **714.16.D**.
5. Reseeding, resodding, and otherwise restoring to their original condition areas that were disturbed during the performance of the work described in this Section.

714.21 Basis of Payment

When the bid schedule indicates payment will be made for Roadway and Structure Lighting on a lump sum basis, such payment is full compensation for all materials, labor, equipment, and incidentals necessary to produce a completely integrated, operative, and finished installation of a Roadway and Structure Lighting System, as shown on the Plans.

When the bid schedule contains items for various elements of Roadway and Structure Lighting, the Department will make payment as follows:

A. Conduit

1. **Encased Conduit.** The Department will pay for Encased Conduit at the contract unit price per linear foot, complete in place, for each kind, number, and size installed as indicated. Such payment is full compensation for all excavation, sheeting when required, backfilling, disposal of excess or unsuitable material, furnishing and placing or installing all materials and accessories, including grounding materials, concrete, and reinforcement when specified, all bends, joints, fittings and appurtenances, and installing the encased conduit complete.
2. **Direct Burial Conduit.** The Department will pay for Direct Burial Conduit of the kind, number, and size specified at the contract unit price per linear foot, complete in place. Such payment is full compensation for all excavation, sheeting when required, backfilling, jacking of conduit, disposal of excess or unsuitable material, furnishing and placing or installing all materials and accessories, including grounding materials, bedding materials when required, all bends, joints, fittings and appurtenances, and installing the conduit complete.
3. **Conduit (Structures).** The Department will pay for Conduit (Structures) of the kind and size specified at the contract unit price per linear foot, complete in place. Such payment is full

compensation for furnishing and installing all materials, including conduits, hangers, expansion fittings, grounding materials, and associated hardware and accessories, and installing the conduit complete.

B. Pull Boxes

The Department will pay for Pull Boxes at the unit price per each, complete in place. Such payment is full compensation for furnishing and installing or constructing pull boxes and for all excavation, backfilling, and other work connected therewith.

C. Cable

The Department will pay for Cable of the type, and number and size of conductors, as specified, at the contract unit price per linear foot, complete in place. Such payment is full compensation for furnishing and installing the cable and grounding materials, making splices, joints and connections, and for trenching, furnishing, and placing cushion and backfill material, and disposing of excess or unsuitable excavated material.

D. Preassembled Cable in Duct

Preassembled Cable in Duct of the kind and size specified will be paid for at the contract unit price per linear foot, complete in place. Such payment is full compensation for furnishing and installing the cable duct, grounding materials, making splices and connections, and for trenching, furnishing, and placing cushion and backfill material, and disposing of excess or unsuitable excavated material.

E. Light Standards

The Department will pay for Light Standards of the type specified at the contract unit price per each, complete in place. Such payment is full compensation for furnishing and installing the complete light standards, including the foundation, standard, bracket arm or arms, associated hardware and wiring, grounding materials, excavation, backfilling materials, and backfilling. The Department will measure foundations for high mast towers separately.

714.21

F. Luminaires

The Department will pay for Luminaires of the size and type specified at the contract unit price per each, regardless of their classifications (i.e. LED, HID), complete in place. Such payment is full compensation for furnishing and installing the complete luminaire, including the ballast(s), lamp(s), glare shields where required, and associated hardware and wiring.

G. Overhead Conductors

The Department will pay for Overhead Conductors of the gauge, type, and kind specified at the contract unit price per linear foot, complete in place.

H. Cable Markers

The Department will pay for Cable Markers of the design specified at the contract unit price per each, complete in place. Such payment is full compensation for furnishing and installing the marker complete, including the excavation, backfilling, and removal and disposal of excess or unsuitable excavated materials.

I. Control Center

The Department will pay for the Control Center at the contract unit price per lump sum, complete in place. Such payment is full compensation for furnishing and installing all equipment and materials, including service pole(s) when specified, and photoelectric relays, relay cabinets, multiple relays, lightning arrestors, fuse cutouts, and all other equipment, materials, associated hardware, and accessories, as shown on the Plans. Payment for the Control Center is full compensation for furnishing and installing all electrical supply facilities from the delivery point for electrical energy, as shown on the Plans, to the control center.

J. Class A Concrete

The Department will pay for Class A Concrete, measured as specified in **714.20.J**, at the contract unit price per cubic yard, complete in place.

714.21

K. Navigational Lighting and Overhead Structure Lighting

The Department will pay for Navigational Lighting and Overhead Structure Lighting by the lump sum complete in place including all materials and labor.

715.01

SECTION 715 – ASPHALTIC CONCRETE CURB (HOT MIX)

715.01	Description	780
715.02	Materials	780
715.03	Composition of Mixture	780
715.04	Equipment	781
715.05	Limitations	782
715.06	Preparing the Curb Foundation	782
715.07	Preparing the Mixture	782
715.08	Hauling and Placing Mixture	782
715.09	Curing and Protection	783
715.10	Method of Measurement	783
715.11	Basis of Payment.....	783

DESCRIPTION

715.01 Description

This work consists of constructing an asphaltic concrete curb composed of a mixture of coarse aggregate, fine aggregate, mineral filler (if specified or required), and asphalt cement, on a prepared foundation.

MATERIALS

715.02 Materials

Provide materials meeting **411.02**, except that commercially available stabilizing material may be added with the Engineer’s approval.

715.03 Composition of Mixture

The composition of the mixture shall conform to the requirements of **411.03** with the following additions and revisions:

A. Proportioning

Combine the mineral aggregate and asphalt cement as specified in Table 715.03-1.

Table 715.03-1: Proportioning

Combined Mineral Aggregate	Asphalt Cement
90-94%	6-10%

B. Mineral Aggregate

Use mineral aggregate of Grading E, except that other gradings that have a history of satisfactory performance may be used when approved by the Engineer.

C. Job Mix Formula

Use a job mix formula that will provide sufficient workability during placing and that will ensure a finished curb of adequate stability and the desired surface texture.

EQUIPMENT

715.04 Equipment

Use mixing and hauling equipment that meet **407.04** and **407.05**.

To place the curb, use an approved self-propelled automatic curb machine capable of producing a smooth, well-compacted finished curb. Equip the machine with a hopper sufficient in capacity to ensure a continuous operation, and a power driven screw or other device that forces the mixture through a tube and then through a die or mold attached to the tube. Ensure that the mold will produce the desired cross-section of the curb. The machine shall be so constructed that the thrust against the asphaltic mixture will eliminate objectionable surface voids as the mixture passes through the mold.

715.05

CONSTRUCTION REQUIREMENTS

715.05 Limitations

Comply with **407.09**.

715.06 Preparing the Curb Foundation

When the curb is to be placed on a granular base, remove all soft or otherwise unsuitable material and replace with suitable material. Thoroughly compact the finished base, and shape to the required line, grade, and cross-section, and prime in accordance with the applicable provisions of **402**.

When the curb is to be placed on an existing pavement, thoroughly clean the area receiving the curb of all dirt and other objectionable matter. Apply a tack coat to this area in accordance with the applicable provisions of **403**.

715.07 Preparing the Mixture

Prepare the asphaltic concrete curb mixture as specified in **407.11**, **407.12**, and **407.13**.

715.08 Hauling and Placing Mixture

Use hauling equipment of an approved type, and schedule hauls so that the temperature of mixture when deposited is not more than 25 °F lower than when it left the mixing plant.

Place the curb in position on the tacked or primed surface using an approved automatic curb machine that shapes and compacts the mixture to the designated cross-section. No side forms will be required for machine placed curb, but where the curb is laid on an existing pavement that does not have a smooth grade, the Engineer may require use of a 2 x 2 inch angle iron or other approved apparatus as a track so that the finished curb will have a smooth and true line and grade.

Where the curb is to abut an existing structure-wall or is placed at the extreme edge of pavement, use a machine that is capable of placing the curb within 1 inch of the structure-wall or pavement edge. Only use hand methods adjacent to structures that preclude machine placing.

On grades greater than 3%, place the curb with the machine traveling uphill. If, in the Engineer's opinion, the curb is not being adequately compacted, take corrective action. Corrective measures may include adjusting the mix, loading the machine with additional weight, retarding forward movement of the machine by braking, or other measures that will ensure adequate compaction.

Carefully construct required joints so as to ensure a continuous bond between the old and the new sections of the curb.

715.09 Curing and Protection

Protect the newly laid curb from traffic by barricades or other suitable methods until the asphaltic mixture has cooled to air temperature.

Remove and replace curb or sections of curb that are displaced, destroyed, or otherwise damaged before final acceptance.

715.10 Method of Measurement

The Department will measure Asphalt Concrete Curb for payment by the linear foot, complete in place.

715.11 Basis of Payment

The Department will pay for accepted quantities, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Asphaltic Concrete Curb (__ inches)	Linear Feet

716.01

SECTION 716 – PAVEMENT MARKINGS

716.01 Description	784
716.02 Materials	784
716.03 Thermoplastic Pavement Marking	785
716.04 Raised Reflective Pavement Markers.....	790
716.05 Snowplowable Reflective Pavement Marker	791
716.06 Preformed Plastic Pavement Markings	792
716.07 Paint	793
716.08 Method of Measurement	796
716.09 Basis of Payment.....	797

DESCRIPTION

716.01 Description

This work consists of furnishing and supplying pavement markings in accordance with these Specifications and the latest revision of the MUTCD, including establishing and locating non-passing zones as well as providing the layout of paint striping, preformed plastic pavement markings, raised reflective pavement markers, snowplowable reflective pavement markers, and thermoplastic pavement markings.

MATERIALS

716.02 Materials

Provide materials as specified in:

Paint	910
Thermoplastic Pavement Markings	919.01
Spray Thermoplastic Pavement Marking.....	919.02
Preformed Plastic Pavement Marking.....	919.03
Raised Reflective Pavement Markers	919.04
Snowplowable Reflective Pavement Markers	919.05

Plastic pavement markings may be either preformed or thermoplastic unless otherwise specified.

CONSTRUCTION REQUIREMENTS

716.03 Thermoplastic Pavement Marking

Furnish and apply thermoplastic pavement marking material meeting **919.01** by the screed extrusion or ribbon dispenser methods, or spray thermoplastic pavement marking material meeting **919.02**.

As an alternate, the Contractor may apply preformed thermoplastic marking material for stop bars, crosswalks, legends, or directional arrows. The preformed thermoplastic material shall have a minimum thickness of 0.090 inches and be fused to the pavement by the heat of a torch.

A. Equipment

Provide special kettle(s) for melting and heating the thermoplastic material. Equip the kettle(s) with automatic thermostatic control devices so that heating can be done by controlled heat transfer rather than by direct flame, to provide positive temperature control and prevent overheating of the material.

Provide equipment that will continuously mix and agitate the material. Conveying parts of the equipment shall prevent accumulation and clogging. All parts of the equipment that come in contact with the material shall be easily accessible for cleaning and maintenance. All mixing and conveying parts of the equipment, including the shaping die (or spray nozzle in the case of spray thermoplastic marking material), shall maintain the material at the plastic temperature with heat transfer oil or electrical element controlled heat. Direct fire heat transfer will not be allowed.

The equipment shall ensure continuous uniformity in the dimensions of the stripe. The applicator equipment shall be mobile and maneuverable to the extent the straight line can be followed and normal curves can be made in a true arc. The applicator equipment shall provide a method of applying "skip" lines. Calibrate the equipment, and check it periodically by marking over a metal plate. The equipment shall provide for varying widths to produce varying widths of traffic markings.

1. **Extruded or Ribbon-Dispensed Thermoplastic Marking.** Apply the material to the pavement by either the screed extrusion method or the ribbon dispenser method.

716.03

The screed extrusion device shall have one side of the shaping die open with the other three sides contained by, or part of, suitable equipment for heating and controlling the flow of material. Do not use pans, aprons, or similar appliances that the die overruns.

Ribbon dispensers shall be heated, suspended above the road surface, and shall apply the material to the width and thickness specified.

Apply glass spheres to the surface of the completed stripe by an automatic bead dispenser attached to the striping machine in such a manner that the beads are dispensed almost instantaneously upon the installed line. The glass sphere dispenser shall be capable of applying glass spheres to the surface of the completed stripe by a double drop application for initial traffic striping and marking. Attach the bead dispenser for the first bead drop to the striping machine so that the beads are dispensed closely behind with the thermoplastic material. Attach the second bead dispenser to the striping machine so that the beads are dispensed immediately after the first bead drop application. Equip glass sphere dispensers with an automatic cut-off control that is synchronized with the cut-off of the thermoplastic material and applies the glass spheres so that the spheres appear uniform on the entire traffic stripes and markings surface with 50 to 60% embedment.

The applicator equipment to be used on roadway installations may consist of either hand equipment or truck mounted units depending on the type of marking required.

The hand equipment shall have sufficient capacity to hold 150 pounds of molten material and shall be sufficiently maneuverable to install crosswalks, lane, edge, and center lines, arrows, and legends. The truck mounted unit for lane, edge, and center lines shall consist of a mobile self-contained unit carrying its own material capable of operating at a minimum speed of 5 miles per hour continuously during an 8-hour period while installing striping.

Hand equipment used for stop bars, crosswalks, legends, directional arrows and other specialty markings shall use the same thermoplastic formulation as described above with the exception of placing the marking at a minimum thickness of 0.090 inches and a

single drop of AASHTO M 247, Type 1 bead at the rate of 8 to 10 pounds per 100 square feet of stripe.

2. **Spray Thermoplastic Marking.** For lane, edge, and center lines, use truck-mounted applicator equipment consisting of a mobile self-contained unit carrying its own material capable of operating at a minimum speed of 5 miles per hour continuously during an 8-hour period while installing striping.

Each application machine must be equipped with an automatic counting mechanism capable of recording the number of linear feet of material applied to the roadway surface with an accuracy of 0.50%, to be checked by the Engineer.

Apply glass spheres to the surface of the completed stripe by an automatic bead dispenser attached to the striping machine in such a manner that the beads are dispensed almost instantaneously upon the installed line. The glass sphere dispenser cut-off shall be synchronized with automatic cut-off of the thermoplastic material.

B. Application

1. **Contractor's Responsibility for Notification.** Notify the Engineer before placing the thermoplastic materials. Furnish the Engineer with the manufacturer's name and batch numbers of the thermoplastic materials and glass spheres to be used. Ensure that the approved batch numbers appear on the thermoplastic materials and glass spheres packages.
2. **Application.** Before beginning application, ensure that the pavement temperature is a minimum of 50 °F and rising. Suspend application if the pavement temperature falls below 50 °F. Thoroughly clean all surfaces to be marked of all dust, dirt, grease, oil, and all other foreign matter before applying the striping.

The pavement marking material, when formed into traffic stripes, shall be readily renewable by placing an overlay of new material directly over old markings of the same material. Such new material shall bond itself to the old markings in a manner that will ensure no splitting or separation will take place.

Offset longitudinal lines at least 2 inches from longitudinal joints of Portland cement concrete pavements.

716.03

a. **Extruded or Ribbon-Dispensed Thermoplastic Marking.**

To ensure optimum adhesion of thermoplastic applied on all Portland cement concrete pavements, apply a binder-sealer material as recommended by the thermoplastic manufacturer. To ensure optimum adhesion, install the thermoplastic material in a melted state at a temperature of 400 to 450 °F.

Unless otherwise shown on the Plans, maintain a minimum average film thickness of 0.100 inch for lane and edge lines on all markings. Compute this thickness on the basis of the amount of material used each day. The film thickness shall be uniform in appearance throughout its application. Apply the glass sphere top coating with a pressure type spray gun designed specifically for this purpose, and that will embed the spheres into the line surface to at least one-half their diameter.

Place Drop on Glass Beads of AASHTO M 247 Type 1 and Type 4 on the thermoplastic stripe at a rate of 8 to 10 pounds per 100 square feet of stripe.

Place the AASHTO M 247 Type 4 glass beads immediately after the first bead drop application of AASHTO M 247 Type 1 beads.

Regardless of the application methods and procedures, or pavement types, replace all pavement markings that fail to comply with these Specifications, or fail to adhere to the pavement for one year after installation, at no cost to the Department.

b. **Spray Thermoplastic Marking.** Before applying the pavement-marking material, remove all dirt, glaze, grease, and all other material that would reduce the adhesion of the paint to the pavement. Open-graded roadways, such as double-bituminous surface treatment (DBST), require sweeping (brooming) to ensure cleanliness.

Remove all existing material that might cause premature failure of the new material.

To ensure optimum adhesion of spray thermoplastic applied to Portland cement concrete surfaces, apply a binder-sealer material as recommended by the thermoplastic manufacturer.

The binder-sealer material shall form, when applied with conventional mobile paint spraying equipment, a continuous film over the pavement surface that will dry rapidly and adhere to the pavement surface. The binder-sealer shall be that product currently in use and recommended by the thermoplastic material manufacturer. Include all costs, including materials, associated with application of the binder-sealer, in the unit bid price for the spray thermoplastic pavement markings.

Install the pavement-marking material in a molten state, by the spray method, at a minimum temperature of 350 °F and a maximum temperature of 425 °F. Scorching or discoloration of material is cause for rejection by the Engineer. Use equipment constructed so that all mixing and conveying parts, up to and including the spray gun, maintain the material in the molten state.

Do not apply the pavement-marking materials when air and pavement surface temperatures are below 40 °F or when the surface of the pavement contains evidence of moisture.

When the plans specify 60-mil markings, apply the pavement-marking material at a thickness of not less than 0.060 inch for all roads except open-graded roadways such as DBST. For such surfaces, apply material at a thickness of not less than 0.065 inch. In no case shall the applied thickness exceed 0.075 inch.

Place the pavement-markings with adequate drop-on glass spheres in accordance with the above requirements, uniformly applied to ensure adequate nighttime reflectivity. Use a compatible combination of marking material and spheres to preclude the surface spheres from sinking deeply into the marking, or from being prematurely lost from the surface of the marking.

The producers of the thermoplastic compound and glass spheres shall furnish to the Department three copies of certified tests reports showing results of all tests specified therein and shall further certify that the materials meet all requirements.

716.04

The Department will randomly sample molten thermoplastic material for verification testing in accordance with AASHTO T 250.

3. **Temporary Marking.** When thermoplastic is used on the final surface, the Contractor may use reflectorized paint installed to permanent standards at the end of each day's work and then install the permanent marking after the paving operation is completed. Short, unmarked sections are not allowed. The Department will not directly measure and pay for temporary markings for the final surface, and will consider the costs thereof to be incidental to the item for permanent markings.
4. **Protection of Newly Applied Traffic Stripes and Markings.** Do not allow traffic onto or allow vehicles to cross newly applied pavement markings until they are sufficiently dry. Remove and replace portions of the pavement markings damaged by passing traffic or from any other cause, at no additional cost to the Department.

716.04 Raised Reflective Pavement Markers

To bond markers to the pavement, use an epoxy listed on the Department's QPL and that is approved by the marker manufacturer or a hot bituminous adhesive conforming to the requirements specified below. Do not use markers manufactured with a self-adhesive backing. Space markers as shown on the Plans. Do not install markers over joints in rigid pavements.

Furnish pavement markers of a type listed on the Department's QPL. Install the markers when the pavement is dry and the pavement temperature is no less than 50 °F.

Clean the portion of the highway surface, to which the marker is to be bonded by the adhesive, of all dirt, curing compound, grease, oil, moisture, loose or unsound layers, paint, and all other material that would adversely affect the bond of the adhesive. Perform cleaning by blast cleaning on Portland cement concrete and old bituminous pavements. Blast clean new bituminous pavement where, in the Engineer's judgment, the surface contains an abnormal amount of asphalt or the surface is contaminated with dirt, grease, paint, oil, or other material that would adversely affect the bond of the adhesive.

Melt and heat the bituminous adhesive in either thermostatically controlled double boiler type units using heat transfer oil or thermostatically controlled electric heating pots. Do not use direct flame melting units. Use a melter/applicator unit that is suited for both melting and pumping application through heated applicator hoses.

Heat the adhesive to between 375 and 425 °F, and apply it directly to the pavement surface from the melter/applicator by either pumping or pouring. Maintain the application temperature between 375 and 425 °F, as lower temperatures may result in decreased adhesion while higher temperatures may damage the adhesive.

Apply the adhesive in a puddle approximately $\frac{2}{3}$ to $\frac{3}{4}$ the diameter of the marker. Apply markers to the adhesive immediately (within 10 seconds) to ensure bonding. Place the marker in position by applying downward pressure until the marker is firmly seated with the required adhesive thickness and squeeze out. Remove excessive adhesive squeeze out from the pavement, and immediately remove adhesive on the exposed surfaces of the markers. Remove adhesive from exposed faces of pavement markers according to manufacturer's recommendations.

Install reflective markers so that the reflective face of the marker is perpendicular to a line parallel to the roadway centerline. Protect the markers against impact until the adhesive has hardened to the degree designated by the Engineer.

The Contractor may reheat and reuse adhesive, provided the manufacturer's recommendations regarding the pot life at application temperatures are not exceeded.

Clean out equipment and tanks using petroleum solvents such as diesel fuel or similar materials. Turn off all heating equipment before beginning cleaning operations. Remove all solvent from the equipment tanks and lines before the next use of the melter.

716.05 Snowplowable Reflective Pavement Marker

Contour the pavement at each snowplowable marker location to match the bottom of the marker casting. Install markers according to the manufacturer's recommendations. For asphalt surfaces, only use the dry saw method to apply snowplowable reflective pavement markers. When using the dry saw method, provide a vacuum system to contain the dust. For other surfaces, regardless of the saw method used, ensure that the saw cut is clean, dry, and

716.06

free of all dust or residue before applying the adhesive. Accompany each shipment of adhesive with a written statement from the adhesive manufacturer certifying that the material furnished conforms to the recommendations of the marker manufacturer and stating the minimum temperature at which the adhesive can be satisfactorily mixed and applied.

716.06 Preformed Plastic Pavement Markings

Apply preformed plastic pavement markings on clean, dry surfaces free of dirt and foreign matter. Only apply markings when the pavement temperature is at least 60 °F. Should the plastic require activators for the adhesive or various special coatings for different pavement surfaces, include the cost of the activator or special coatings in the unit price of plastic.

Furnish with each package of reflectorized pavement marking materials complete instructions and specifications for applying pavement marking materials to pavement surface. Install the reflectorized pavement marking materials according to the vendor's specifications. Any adhesion used in the installation shall be as specified by the manufacturer. Use an adhesion-promoting primer when recommended by the pavement marking manufacturer.

Establish guides to mark the lateral location of pavement markings as shown on the Plans or as directed by the Engineer. The Engineer will verify the location of the guides. Place markings in proper alignment with the guides. The deviation rate in alignment shall not exceed 1 inch per 200 feet of roadway. The maximum deviation shall not exceed 2 inches, and there shall be no abrupt deviations.

Remove and replace, at no cost to the Department, markings placed that are not in the alignment or sequence as shown on the Plans or as specified herein. Remove such markings as specified in **712.05**. Guides placed on the roadway for alignment purposes shall not establish a permanent marking on the roadway in the opinion of the Engineer.

When specified in the Contract, place markings for newly paved asphalt concrete surfaces immediately after final rolling of the mat. Use a rubber tired roller cart with a minimum weight of 200 pounds or a truck operated at no more than 3 miles per hour to ensure proper adhesion when the markings are in place. Do not use steel wheel rollers for this purpose.

716.07 Paint**A. Application of Painted Pavement Markings**

Apply paint with a spray-type machine capable of satisfactorily applying the paint under pressure through a nozzle that sprays directly upon the pavement at a rate not to exceed 880 feet per minute. Equip the machine with:

1. Air blast device for cleaning the pavement ahead of the painting operation;
2. Guide pointer to keep the machine on an accurate line;
3. Device to agitate the paint;
4. Device to maintain a uniform flow and application of the paint;
5. Automatic device to provide a broken or skip line of the length required;
6. At least two spray guns capable of being operated either individually or together;
7. Automatic counting mechanism capable of recording the number of linear feet of material applied to the roadway surface with an accuracy of 0.50%, to be checked by the Engineer; and
8. Accurate meters that register quantities for both white and yellow applied paint to the nearest gallon.

When using waterborne paint, ensure the equipment can heat the material from ambient air temperature to 123 °F. Equip the machine with a bead or sphere dispenser that can be regulated to dispense the spheres automatically at the uniform rate required. The equipment shall be designed and operated so as to allow traffic to safely pass on the roadbed.

Do not apply paint unless the ambient air temperature is at least 45 °F. However, if the Engineer directs that paint be applied when air temperatures are below 45 °F, heat the paint according to the manufacturer's recommendations.

716.07

For the following operations, the Engineer will not require large automatic spray application machinery meeting the preceding requirements, provided the Contractor selects pavement marking equipment capable of producing a uniform, acceptable finished product consistent with the Plans and Specifications:

1. Installation of temporary pavement markings.
2. Installation of permanent pavement markings on projects having a total length of 1,000 feet or less.
3. Installation of permanent pavement markings on an individual project segment having a total length of 1,000 feet or less on an intermittent project.

Clean the pavement surface before placing any pavement marking material.

Locate and place temporary markings on final pavement surfaces to underlie or coincide with the permanent pavement markings.

Perform cleaning and painting using equipment of the kind and in the manner provided by previously specified equipment. On sections where no previously applied line is available to serve as a guide or if the line is to be re-located, spot the proposed location of the new line with paint in advance of the application. On tangent sections, space the control points no more than 500 feet apart and on curves at intervals that will ensure the accurate location of the line. Leave gaps in all lines at intersections in accordance with the MUTCD or as directed by the Engineer.

Do not apply any paint over a chalk line, wire, or cord, and instead offset such guide marks from the paint line to be placed. On sections where previously applied lines are visible, use the old lines unless otherwise directed. Do not apply any paint to areas of pavement when moisture remains on the surface, or when wind conditions may cause a film of dust to be deposited on the line areas after these areas have been prepared for painting.

Apply drop-on type glass beads uniformly to the painted surface at a uniform rate of not less than 6 pounds per gallon of paint applied.

Apply paint so as to deposit a uniform final film thickness of 0.015 inch (within a reasonable tolerance) and at a speed not to exceed 880 feet per

minute. Use this rate of application for all types of paint, making proper adjustments in gallons for an intermittent line or wider lines. Ensure that the quantity of paint does not under-run the designated amount by more than 5%. If a check of the rate of application indicates a greater variation, stop the work until the paint machine is properly adjusted or replaced. This percent of variation is set out to give the Contractor some leeway in starting the job and in getting the machine in adjustment; it is not expected that there will be either a continuous overrun or under-run, but that the final average rate of application will closely approach the rate established above.

When reflectorized paint is required for temporary or final marking, install the paint to permanent standards at the end of each day's work. Do not leave any short, unmarked sections.

Protect traffic lines and markings. Place warning and directional signs as shown on the Plans or as directed by the Engineer to control traffic in the marking area. If the drying time of the material being used exceeds 60 seconds, protect the newly applied markings by placing traffic cones or other approved warning devices at frequent intervals as directed. Leave these devices on the line until the material is dry or firm enough not to track or receive impressions from normal traffic. Remove these devices as soon as possible to prevent a traffic hazard. Do not leave such devices in the roadway overnight. If so directed, provide flaggers to direct traffic.

Apply paint to appear as clearly delineated lines with minimal crookedness and waviness, giving due consideration to the contours and roughness of the pavement. Segments of broken line stripe shall square off positively at each end. The paint lines shall be without mist, drip, or splatter. Remove and/or correct, to the Engineer's satisfaction and at no additional cost to the Department, lines that do not meet these requirements when placed.

Operate the paint equipment so that it will be unnecessary for traffic to cross the newly painted line behind the equipment in order to safely pass the painting machine, and to allow traffic to keep moving at all times.

B. Removal of Painted Markings

Remove painted pavement markings where specified or directed by the Engineer. Obtain the Engineer's approval of the paint removal method

716.08

before beginning the work. Do not remove existing painted pavement markings by painting over them with black paint or asphalt.

When the method of removal causes sand or other material to accumulate on the pavement, remove the residue as the work progresses. Remove painted markings by methods that cause the least possible damage to the pavement. Repair damage to the pavement or surface caused by pavement marking removal as directed by the Engineer and at no cost to the Department.

Where a plastic marking will replace the painted marking and paint removal is specified in the Contract, remove enough of the paint to ensure proper installation of the plastic. The paint removal shall be uniform and shall expose a minimum of 75% of the surface area that is to receive the plastic materials.

COMPENSATION

716.08 Method of Measurement

A. Pavement Marking (Broken lane lines), Pavement Marking (Dotted line), and Pavement Marking (Transverse Shoulder)

The Department will measure the length of each of these markings, complete in place and accepted, as listed in the bid schedule, along the center of each line. Only the marked line will be measured for payment.

B. Pavement Marking (Solid barrier line)

The Department will measure the length of solid barrier line, complete in place and accepted, along the center of each line. Where double solid barrier lines are used, each solid barrier line will be measured separately for payment.

C. Pavement Marking (Crosswalk Striping)

The Department will measure the length of crosswalk striping, complete in place and accepted, along the centerline of the crosswalk. The Department will not separately measure boundary lines on crosswalk.

D. Pavement Marking (Channelization Striping)

The Department will measure Channelization Striping, including the boundary lines, complete in place and accepted, by the square yard.

E. Pavement Marking (Stop line)

The Department will measure the length of stop lines, complete in place and accepted, in linear feet to the nearest foot along the centerline of the stop line.

F. Pavement Marking (Designs)

The Department will measure designs or lettering by the unit, per each, complete in place or as stipulated in the Contract and shown on the Plans.

G. Raised Reflective Pavement Markers and Snowplowable Reflective Pavement Markers

The Department will count the number of each type of pavement markers installed as directed and accepted.

H. Removal of Existing Painted Line

The Department will measure the removal of broken lane line and solid barrier line along the center of each line. Only the painted line will be measured for payment.

Adhesives will be considered incidental to the installation of raised reflective pavement markers and snowplowable reflective pavement markers.

716.09 Basis of Payment

The Department will pay for accepted quantities, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Plastic Pavement Marking (__ ” Dotted Line)	Linear Feet
Plastic Pavement Marking (Transverse Shoulder)	Linear Feet
Plastic Pavement Marking (__ ” Barrier Line)	Linear Feet
Plastic Pavement Marking (Cross-Walk)	Linear Feet
Plastic Pavement Marking (Stop Line)	Linear Feet

716.09

Plastic Pavement Marking (Channelization Striping)	Square Yard
Painted Pavement Marking (__” Barrier Line)	Linear Feet
Painted Pavement Marking (Cross-Walk)	Linear Feet
Painted Pavement Marking (Stop Line)	Linear Feet
Painted Pavement Marking (Channelization Striping)	Square Yard
Plastic Pavement Marking (Word or Design)	Each
Raised Pavement Marker (Description)	Each
Snowplowable Pavement Marker (Description)	Each
Removal of:	
Pavement Marking (Dotted Line)	Linear Feet
Pavement Marking (Transverse Shoulder)	Linear Feet
Pavement Marking (__” Barrier Line)	Linear Feet
Pavement Marking (Cross-Walk)	Linear Feet
Pavement Marking (Stop Line)	Linear Feet
Pavement Marking (Channelization Striping)	Square Yard
Pavement Marking (Word or Design)	Each

Such payment is full compensation for layout, materials, labor, equipment, tools, royalties, and all other incidentals necessary to complete the work.

**SECTION 717 – MOBILIZATION OF FORCES,
SUPPLIES AND EQUIPMENT**

717.01 Description.....	799
717.02 Method of Measurement.....	799
717.03 Basis of Payment.....	799

DESCRIPTION

717.01 Description

This work consists of mobilizing and demobilizing the Contractor's and all Subcontractors' forces, supplies, equipment, and incidentals at the Project site. It shall include all Contractor and Subcontractor costs associated with obtaining performance bonds, insurance required by railroads, and other preconstruction costs incurred after Contract award that are necessary costs to the Project and are of a general nature rather than directly attributable to other pay items. Include all necessary preconstruction costs not attributable to a specific pay item in the lump sum price for Mobilization and not in any other pay item.

COMPENSATION

717.02 Method of Measurement

The Department will measure Mobilization by the unit for the completion of the work described in **717.01**.

717.03 Basis of Payment

The Department will pay for Mobilization on a lump sum basis.

The Department will make partial payments for Mobilization with the first and second partial pay estimates paid on the Contract. Payment will be made at the rate of 50% of lump sum price for Mobilization on each of these partial pay estimates provided the amount bid for Mobilization does not exceed 5% of the total amount bid for the Contract. If the amount bid for the item of Mobilization exceeds 5% of the total amount bid for the Contract, the Department will pay 2-1/2% of the total amount bid on each of the first partial

717.03

payment estimates, and that portion exceeding 5% on the last partial pay estimate.

As an exception to the above, where the Work covered by the Contract is limited exclusively to the resurfacing of an existing pavement, including projects involving the milling off of a portion of the existing pavement prior to the laying down of new asphalt cement concrete layer(s), the Department will pay the entire lump sum price for the item of Mobilization, less the retainage provided for in Title 54-5-121, TCA, with the first partial pay estimate paid on the Contract, provided the amount bid for Mobilization does not exceed 5% of the total amount bid for the Contract. If the amount bid for the item of Mobilization exceeds 5% of the total amount bid for the Contract, the Department will pay 5% of the total amount bid for the Contract on the first partial pay estimate, and the portion exceeding 5% on the last partial pay estimate.

SECTION 722 – FIELD OFFICE

722.01	Description.....	801
722.02	Location	801
722.03	Minimum Spatial Requirements	801
722.04	Other Requirements	802
722.05	Outside Utilities	802
722.06	Interior Utility Services.....	802
722.07	Doors and Windows.....	803
722.08	Furnishings and Equipment	803
722.09	Concrete Cylinder Storage	805
722.10	Maintenance and Custodial Service	805
722.11	Project Sign.....	805
722.12	Basis of Pavement.....	806

DESCRIPTION

722.01 Description

This work consists of providing and maintaining an adequate, weatherproof field office for the exclusive use of the Engineer and Department staff during both the Contract period and for a maximum of 60 days thereafter.

GENERAL REQUIREMENTS

722.02 Location

Locate the field office or materials laboratory on a site that is both satisfactory to the Engineer and convenient to the Project site.

722.03 Minimum Spatial Requirements

Unless otherwise specified in the Special Provisions, the Engineer's field office shall meet the minimum floor area and headroom requirements specified Table 722.03-1. It shall contain a sufficient number of windows to provide at least 27 square feet of natural light. Existing building structures meeting these minimum requirements are acceptable.

722.04

Table 722.03-1: Field Office Spatial Requirements

Building Type	Width (feet)	Length (feet)	Headroom (feet)	Windows Required
Type 1	10	30	8	6
Type 2	12	50	8	10

722.04 Other Requirements

Arrange for and comply with all necessary local and State regulatory permits and inspections, including all costs associated therewith.

Fully equip the Engineer's field office and have it ready for occupancy at least 2 days before the start of actual construction operations.

Protect the field office against fire, flooding, and theft throughout the 24 hours of every day the unit is in service. Assume responsibility for Department property housed in the field office that is lost due to theft, fire, or natural causes.

722.05 Outside Utilities

A. Electrical Power

Arrange for electrical service for the field office. The power supply shall be 115-volt, 60-cycle current of sufficient amperage to provide for heat, interior and exterior lighting, operating office equipment, and air conditioning.

B. Sanitary Sewer Outfall

Provide an adequate temporary outfall into either the municipal sanitary sewer system or an approved individual sewage disposal system. Dispose of sanitary wastes in accordance with the applicable requirements of the municipal regulations.

722.06 Interior Utility Services

A. Lighting

Furnish lighting fixtures as required to provide minimum illumination of 70 foot-candles in all areas.

B. Electrical Receptacles

Provide six duplex convenience electrical receptacles throughout the field office as directed by the Engineer. At least two of these receptacles shall be 20-amp capacity.

C. Heating and Air Conditioning

Provide heating and air conditioning equipment capable of maintaining a year-round temperature between 70 °F and 78 °F.

D. Sanitary Facilities

Provide a water closet, lavatory, slop sink, vent fan, and a hot water heater having a minimum 5-gallon capacity.

E. Telephone, Answering Machine, and Facsimile Machine

Provide telephone service with an answering machine, a facsimile machine, and two incoming phone lines.

722.07 Doors and Windows

Provide doors of stock sizes and that have a key-in-knob lock of an approved manufacturer. Key all doors similarly. Provide operative windows except for picture windows. Operative windows shall be either double hung or casement type equipped with adequate locks. Provide all windows with either shades or Venetian blinds. Provide adequate screens for all window openings. Provide frosted glass for windows in sanitary areas.

722.08 Furnishings and Equipment

Provide the field office with the following:

A. Furnishings

1. Three office type desks, minimum top dimensions 32 x 60 inches, with two or more drawers on each side.
2. Three swivel desk chairs.

722.08

3. One work table, 30 inches high, with a minimum of 24 square feet of work area.
4. One drafting stool.
5. Two folding-type chairs.
6. One fire resistant drawer-type safe, legal size, with combination or key lock.
7. One four-drawer legal size metal filing cabinet equipped with lock.
8. Two two-drawer (14-1/2 x 16 inches) metal filing cabinets.
9. Two round wastebaskets.
10. One plan rack of an approved design to be equipped with ten rods.

B. Equipment

1. Two fully automatic electronic calculators with tape.
2. One office type copying machine.
3. One pencil sharpener.
4. One 5-pound CO₂ fire extinguisher of approved manufacture for each 200 square feet of floor area.
5. One first-aid kit.
6. One electric sanitary water cooler with refrigerated storage compartment, with a continuous supply of paper cups.
7. Toilet paper holders, paper towel dispensers, and soap dispensers in the toilet rooms, with a continuous supply of each.

722.09 Concrete Cylinder Storage

Provide a storage shed/building for temporary storage of concrete acceptance cylinders. The storage facility shall be of sufficient size and construction to protect the concrete cylinders from the elements and damage. Obtain the Engineer's approval of the storage facility location. Department personnel will control access to the storage shed/building. Equip the storage shed with a concrete curing box or water curing tank with a heating/circulating system of sufficient size to properly cure all acceptance cylinders before transferring for final storage and testing. The curing box or curing tank and heater/circulator shall comply with AASHTO M 201, and proper curing of the cylinders shall be in accordance with AASHTO T 23. The storage facility shall be equipped with a measuring device that will record the minimum and maximum temperatures inside of the curing area.

722.10 Maintenance and Custodial Service

Provide the following maintenance and custodial services:

A. Maintenance

Perform all necessary repairs of damaged, defective, or vandalized parts of the field office and associated furnishings and equipment. Continue maintenance operations as long as the Engineer occupies the field office.

B. Custodial

1. Weekly trash removal.
2. A broom and dust pan or bi-monthly floor cleaning service.
3. Cleaning supplies or bi-monthly window and sanitary facility cleaning.
4. Replacement of supplies as required to maintain office equipment and sanitary facilities.

722.11 Project Sign

Equip the field office with a sign that identifies both the use of the structure and provides notice against trespassing.

722.12

COMPENSATION

722.12 Basis of Pavement

The Department will pay for accepted quantities, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Field Office (Type __)	Lump Sum

Such payment is full compensation for providing all that is specified in this Section **722** for the duration of the Project.

SECTION 730 – TRAFFIC SIGNALS

730.01 Description of Work	808
730.02 Regulations and Code	808
730.03 Submittal Data Requirements	809
730.04 Mill Test Reports and Certification.....	810
730.05 Working Drawings.....	811
730.06 Guarantee	811
730.07 Training.....	811
730.08 Excavating and Backfilling	812
730.09 Removing and Replacing Improvements	813
730.10 Foundations.....	813
730.11 Anchor Rods	814
730.12 Pull Boxes	814
730.13 Transformer Base.....	815
730.14 Conduit.....	816
730.15 Conductors	818
730.16 Cable	818
730.17 Wiring	819
730.18 Service Connection	819
730.19 Sealant.....	819
730.20 Strand Cable.....	819
730.21 Bonding and Grounding.....	820
730.22 Field Test	820
730.23 Inspection.....	821
730.24 Signal Heads	822
730.25 Controllers	825
730.26 Cabinets	827
730.27 Auxiliary Equipment for Traffic Signal Controllers	834
730.28 Miscellaneous Traffic Signals	837
730.29 Detectors	845
730.30 Reserved.....	851
730.31 Reserved.....	851
730.32 Cantilever Signal Supports.....	851

730.01

730.33 Steel Strain Poles	853
730.34 Pedestal Support Signal Poles	854
730.35 Wooden Pole Signal Supports.....	855
730.36 Pole Location	856
730.37 Method of Measurement	856
730.38 Basis of Payment.....	864

DESCRIPTION

730.01 Description of Work

This work consists of furnishing and installing all necessary materials and equipment to complete in-place traffic signal systems, modify existing systems, or both, all as shown on the Plans or the Standard or Special Details, and as specified in these Specifications. Unless otherwise shown on the Plans or specified in the Special Provisions, all materials shall be new.

Where existing systems are to be modified, incorporate the existing material into the revised system, salvage it, or abandon it as specified or as directed by the Engineer.

Furnish and install all incidental parts that are not shown on the Plans or specified herein, but that are necessary to complete the traffic signal or other electrical systems, or that are required for modifying existing systems, as though such parts were shown on the Plans or specified herein. Include the costs of such incidentals in bid price for other items. All systems shall be complete and in operation to the Engineer's satisfaction at the time of completion of the work.

GENERAL REQUIREMENTS

730.02 Regulations and Code

Ensure that all equipment provided conforms to NEMA Standards Publication, Traffic Control Systems, latest revision, or the Radio Manufacturers Association, whichever is applicable. In addition to the requirements of these Specifications, the Plans, and the Special Provisions, all material and work shall conform to the requirements of the NEC and the NESC; the Standards of ASTM, ANSI, ITE, and IMSA; the MUTCD; and other applicable local ordinances.

Wherever reference is made to the NEC, or the Standards mentioned above, consider the reference to mean the code or standard that is in effect on the date of advertising the bids or authorization for force account.

730.03 Submittal Data Requirements

Within 30 days after the issuance of the work order, submit to the Engineer, the Traffic Operations Division, and the local entity (city or county engineer), one collated set of the manufacturer's descriptive literature and technical data that fully describes the types of signal equipment proposed for use. In the descriptive literature, identify the manufacturer and models and include sufficient information for the Engineer to determine if the equipment or material meets the requirements of the Plans and these Specifications. Include with these sets of submittal data a list of the materials submitted along with descriptive material for, but not limited to, the following items:

1. Controller
2. Cabinet and Exhaust Fan
3. Detectors
4. Signal Heads including Lamp Information and Mounting Hardware
5. Loop Wire and Loop Sealant
6. Shielded Detector Cable
7. Signal Cable
8. Cable for Span Wire, Guys, and similar features
9. Pull Boxes
10. Conduit
11. Coordination Equipment

Also include in the submittal sets detailed scale drawings of all non-standard or special equipment and of all proposed deviations from the Plans. Upon request, submit for approval sample articles of materials proposed for use. The Department will not be liable for any materials purchased, labor performed, or delay to the Work prior to such approval.

In addition to the above, submit to the Engineer a notarized letter certifying that all traffic signal materials listed in the submittal conform to the Plans and Specifications along with a copy of a statement from the maintaining agency that the system is acceptable to the agency. Any material substitutions requested by the maintaining agency shall meet minimum Department standards and shall be approved by the Department in writing prior to purchase or installation. The Department will not be liable for any materials purchased, labor performed, or delay to the Work regarding such approval.

730.04

Submit an electronic copy in PDF format of “Design” or “Shop” drawings, indicating the proposed dimensions and material specification for each of the supports and mast arms involved, to the Division of Structures for approval purposes within 30 days after the work order is issued. The Department will review these drawings at the earliest possible date, and will return the electronic copy marked “Approved for Fabrication,” or “Returned for Revisions as Noted.” Respond by taking appropriate action to ensure the earliest possible correction of these items so as not to delay the installation.

730.04 Mill Test Reports and Certification

Provide Mill Test Reports (MTR) or Certifications of Conformance to the Specifications for Materials and Design for all materials incorporated into the Work. Supply the following prior to acceptance of the structures:

1. MTRs for MAJOR structural items only, as identified in Table 730.04-1, shall include both physical and chemical descriptions of the material as supplied to the fabricator. When physical properties are altered during the fabrication, supplement the MTR covering chemical composition with certified test reports indicating the physical properties of this material after fabrication.
2. Certifications of Conformance to the Specifications for all remaining material not covered by MTR as identified in Table 730.04-1.
3. Certification that all welding was performed by operators qualified as follows: Steel welders to AWS and aluminum welders to ASME.
4. Certification of Conformance to the Specification for the Design of all components not completely dimensioned and detailed on the Standard Drawing.

Table 730.04-1: Required Mill Test Reports and Certifications

Component Materials	MTR	Certification
Tubes for arms and poles	X	
Base Castings	X	
Anchor Bolts	X	
Pole tops, misc. fittings, and hardware		X
Fabricated or cast-type arm connections		X
Galvanizing		X

730.05 Working Drawings

Provide within the controller cabinet and to the local maintaining agency an electrical schematic diagram of the cabinet and system wiring. Submit manufacturer's instructions for installation, maintenance, and operation of all equipment to the local maintaining agency and also place a copy within the controller cabinet. Place all such materials inside a plastic envelope mounted in the cabinet.

730.06 Guarantee

Guarantee the Traffic Signal System(s) installed under these Specifications, including all equipment, parts, and appurtenances in connection therewith, to the City or County and State against defective workmanship and materials for a period of not less than 1 year following the date the signal system is installed and made operational, except in no case shall this guarantee expire prior to 3 months after the final acceptance of the Project. Upon completion of the Project, turn over to the government agency responsible for maintaining the signal installation all warranties or guarantees on equipment and materials that are offered by the manufacturers as normal trade practice.

730.07 Training

Provide to the maintaining agency and/or the Department a training session on the controller and associated cabinet equipment to be supplied on the Project. The training session shall last for a minimum 4 hours unless the maintaining agency and/or the Department determines a lesser time is adequate. Train the user in the complete operation and programming features of all controllers. Provide this training prior to the acceptance of the Project at a facility agreed upon by the maintaining agency.

730.08

After the required training, certify to the Engineer that training has been completed.

This training requirement shall not apply if a training program meeting these criteria has been provided to the maintaining agency by this vendor and/or manufacturer on the equipment being bid within 18 months prior to the date of the invitation to bid. This requirement shall apply if the bidder is proposing new, upgraded, or modified equipment not covered in the previous training program.

MATERIALS AND INSTALLATION

730.08 Excavating and Backfilling

Perform excavation needed to install conduit, foundations, and other equipment, so as to cause the least possible damage to the streets, sidewalks, and other improvements. Excavate trenches no wider than necessary to properly install the electrical equipment and foundations. Do not begin excavating until immediately before installing conduit and other equipment. Place the material from the excavation where it will cause the least disruption and obstruction to vehicular and pedestrian traffic and the least interference with the surface drainage.

Backfill the excavations and compact to at least the density of the surrounding material. Remove all surplus excavation material and dispose of outside the highway right-of-way, in accordance with **203.07**, or as directed by the Engineer.

After backfilling, keep excavations well-filled, and maintain in a smooth and well-drained condition until permanent repairs can be made.

At the end of each day's work, and at all other times when construction operations are suspended, remove all equipment and other obstructions from that portion of the roadway used by public traffic, and park a minimum of 30 feet from the edge of pavement unless otherwise protected by guardrail, bridge rail, or barriers installed for other purposes.

Perform excavation in the street or highway so as to restrict no more than one traffic lane in either direction at any time. Do not obstruct traffic during hours of peak flow unless otherwise approved by the Engineer. Incorporate construction signing in accordance with the MUTCD.

730.09 Removing and Replacing Improvements

Replace or reconstruct, with the same kind of materials as found on the Work, improvements, such as sidewalks, curbs, gutters, Portland cement concrete and asphalt concrete pavement, bituminous surfacing, base material, and all other improvements removed, broken, or damaged by the Contractor.

Before removing the sidewalk and pavement material, use an abrasive type saw to cut, to a minimum depth of 2 inches, the outline of all areas to be removed in Portland cement concrete sidewalks and in all pavements. Use any method satisfactory to the Engineer to cut the remainder of the required depth. Make cuts neat and true with no shatter outside the removal area.

Whenever a part of a square or slab of existing concrete sidewalk or driveway is broken or damaged, remove the entire square or slab and reconstruct the concrete as specified above.

Perform all work in accordance with these Specifications, or the applicable local ordinance, whichever is of a higher standard. Consider this removal and replacement work to be incidental to other items.

730.10 Foundations

Construct foundations for posts, standards, and cabinets of Class A Portland cement concrete.

Pour foundations for posts, standards, and pedestals after the post, standard, pedestal, or anchor bolts or reinforcing steel is in proper position. Form the exposed portions to present a neat appearance. Rest the bottom of concrete foundations on firm undisturbed ground.

Construct forms to be true to line and grade. Finish tops of footings for posts and standards, except special foundations, to curb or sidewalk grade or as ordered by the Engineer. Use rigid forms, securely braced in place. Place conduit ends and anchor bolts by means of a template until the concrete sets. Moisten both the forms and the ground that will be in contact with the concrete before placing concrete. Do not remove forms until the concrete has cured for at least 12 hours and hardened sufficiently to allow form removal without causing damage to the concrete.

Apply an ordinary surface finish to exposed surfaces of concrete. Wherever the edge of a concrete foundation or sidewalk section is within 18 inches of

730.11

any existing concrete improvement, extend the sidewalk section to meet the existing improvement.

Where obstructions prevent the construction of planned foundations, construct a foundation satisfactory to the Engineer.

730.11 Anchor Rods

Furnish, with anchor-base type rods, anchor bolts meeting the requirements of ASTM F1554, grade as required by design. Fit each anchor bolt with two heavy hex nuts. Hot-dip galvanize all nuts and not less than 10 inches of the threaded ends of anchor bolts according to ASTM A153. The anchor bolts shall be capable of resisting at yield strength stress the bending moment of the shaft at its yield strength stress.

Set standards, posts, and pedestals plumb by adjusting the nuts before the foundation is finished to final grade. Do not use shims or similar devices for plumbing or raking. After plumbing or raking has been completed, cut off anchor bolts $\frac{1}{4}$ inch above the top nut, and paint the exposed surface with rust protective paint.

Furnish all anchor bolts and nuts required for relocating existing standards and posts.

730.12 Pull Boxes

Construct and install pull boxes as shown on the Plans and the Standard Drawings or as directed by the Engineer. Additional pull boxes may be required where conduit runs are more than 150 feet long. The maximum spacing between pull boxes shall be 150 feet, unless otherwise directed by the Engineer. Install pull boxes wherever practicable out of the line of traffic. Set covers level with the pavement, or with the curb or sidewalk grade, or with the surrounding ground as required.

Place electrical conductors within pull boxes to be clear of the metal frame and cover.

Rest the bottom of the pull box firmly on a bed of crushed stone with a minimum depth of 12 inches below the bottom and extending 6 inches beyond the outside edge of the pull box, unless otherwise directed by the Engineer.

A. Concrete Pull Boxes

Construct concrete pull boxes of a mixture of one part cement, two parts sand, and four parts gravel or 1-inch crushed stone with reinforcement placed as shown on the Standard Drawings. Reinforcement shall consist of welded wire reinforcement, 4 x 4 inches – No. 4/4 at 85 pounds per 100 square feet, meeting the requirements of **907.03**. Pull boxes may be poured in place or precast. The color of the pull box concrete material shall match the surrounding concrete color.

Install a cast iron frame and cover of the dimensions shown on the Drawings in each pull box. Provide castings of Class 30, meeting the requirements of **908.07**. The covers shall have a roughened top surface of 1/8 inch in relief. Provide notches for removing the cover. Inscribe the words “TRAFFIC SIGNALS” on top of the covers with letters 1-1/2 inches high and 1/8 inch in relief as shown on the Drawings.

The frame shall have a minimum weight of 42 pounds. The cover shall be of the “Extra Heavy” type with a minimum weight of 54 pounds.

B. Reinforced Plastic or Epoxy Mortar Pull Boxes

Ensure that pull boxes composed of reinforced plastic or epoxy mortar are designed and tested to temperatures of -50 °F and meet the requirements of the following: ASTM D543, ASTM D570, ASTM D790, and ASTM D635, and are based on a 30,000-pound single axle load over a 10 x 20 inch area. The top of the pull box shall consist of a concrete frame (ring) and cover. The color of the pull box concrete material shall match the surrounding concrete color. Inscribe the words “TRAFFIC SIGNALS” on top of the covers.

730.13 Transformer Base

Fabricate the transformer base from steel plate and sheet, and design it to harmonize with the shaft. Provide each transformer base with:

1. One 7-1/2 x 9 inch minimum handhole, with a cover secured with stainless steel fastening screws;
2. Four galvanized steel bearing plates to fasten the base to the anchor bolts;

730.14

3. Four galvanized steel bolts, nuts, and washers to fasten base and standard; and
4. One ½-inch, 13 UNC grounding nut welded to the inside of the base opposite the handhole opening.

Ensure that the strength of the transformer base is comparable with that of the shaft.

When a transformer base is required, no handhole will be required in the shaft.

730.14 Conduit

Furnish and install plastic and steel conduit in accordance with these Specifications and close conformity with the lines shown on the Plans or as established by the Engineer.

Threads shall be clean cut, straight, and true and of sufficient length to allow proper coupling. Do not use long running threads on any part of the Work. Protect threads in transit and during installation and provide conduit with proper supports and protection during construction to prevent damage. Properly thread, ream, and cap all ends of pipe installed for future connections to prevent water and foreign matter from entering the conduit system. Provide threaded ends with approved conduit bushings.

Signal conduit shall be a minimum 2 inches in diameter, and detector conduit a minimum 1 inch in diameter, unless otherwise specified or directed by the Engineer. Conduit for service connections shall be 1 inch in diameter. Do not use conduits smaller than 1 inch in diameter unless otherwise specified, except grounding conductors at service points shall be enclosed in ¾-inch diameter conduit. Larger-sized conduit may be used, at no additional cost to the Department, in which case it shall be for the entire length of the run with no reducing couplings allowed.

A. Materials

Provide conduits and fittings of the type as shown in the construction plans or as directed by the Engineer and as follows:

1. **Steel Conduit**

- a. Rigid conduit and fittings shall be heavy-wall, hot dipped galvanized steel conforming to Federal Specification WW-C-581-d(3) and ANSI C80.1. It shall be galvanized inside and out and shall meet the requirements of ASTM A53. Each length shall bear the label of Underwriters Laboratories, Inc.
 - b. Flexible conduit shall be galvanized flexible steel meeting Federal Specification WW-C-581-d(3), ANSI C80.1, and UL Standard 6 with a minimum 40-mil thickness of polyvinyl chloride (PVC) coating conforming to ASTM D746.
2. **Plastic Conduit.** For plastic conduit, provide high impact PVC, Schedule 40 or Schedule 80.
 3. **High-Density Polyethylene (HDPE).** Materials used for the manufacture of HDPE conduit and fittings shall be per ASTM F2160 and consist of a Standard Dimension Ratio (SDR) 9-11. No other substitutions shall be allowed unless directed by the Engineer. HDPE conduit can be used with preassembled cable and rope-in-conduit.

B. Installation

All bends shall be in strict compliance with the NEC.

Lay conduits to a minimum depth of 6 inches below subgrade but not less than 24 inches below pavement grade except when approved by the Engineer; conduit may be laid at a depth of not less than 24 inches below top of curb when placed in back of the curb. Place conduit runs for detectors parallel to existing or proposed curbs and not more than 18 inches behind the curb face unless other specified. Place steel conduit or Schedule 80 PVC conduit under existing pavements by approved jacking or drilling methods. Do not disturb pavements without the Engineer's approval. Where trenching is allowed in a traffic bearing area, use PVC conduit (Schedule 40) encased in concrete.

Conduits shall be continuous and extend from end point (i.e. pull box, foundation signal pole, pedestal pole, etc.) to another end point, or as directed by the Engineer. Conduit splicing shall not be permitted between end points.

After completing the installation of the conduit, test all conduits installed under the Contract with a mandrel having a diameter $\frac{1}{4}$ -inch smaller than

730.15

the conduit and a length of 2 inches. Repair, to the Engineer's satisfaction, all conduits that will not allow passage of the mandrel; if repairs cannot be accomplished, remove and replace the conduit at no additional cost to the Department. After the mandrel test, scour all conduits with a stiff wire brush slightly larger in diameter than the conduit. Clear all conduits in the Engineer's presence.

Extend conduits terminating in anchor base standards and pedestals approximately 2 inches above the foundation and slope them toward the hand-hole opening. Conduits shall enter concrete pull boxes from the bottom and shall terminate not less than 2 inches nor more than 4 inches above the bottom of the box and near the box walls to leave the major portion of the box clear.

Clean existing underground conduit to be incorporated into a new system by blowing with compressed air, or by other means approved by the Engineer.

730.15 Conductors

Furnish and install conductors in accordance with these Specifications and close conformity as shown on the Plans, or as directed by the Engineer.

Traffic Control Conductors shall be rated at 600 volts. Run all conductors, except loop conductors and cables run along messengers, in conduit, except where run inside poles. Where signal conductors are run in lighting standards containing high voltage street lighting conductors, encase the signal conductors in flexible or rigid metal conduit. Where telephone circuits are introduced into controller foundations, encase the telephone conductors in flexible metal conduit and in conformance with the NEC.

Conductors for traffic loops shall be continuous AWG No. 14 XLP stranded wire to the detector terminals or spliced with shielded detector cable within a pull box, conduit, or pole base.

Detector cable shall be two conductor twisted pair shielded AWG No. 14 stranded meeting IMSA Specification No. 50-2.

730.16 Cable

All signal cable shall conform to applicable IMSA Specification No. 19-1 or 20-1. Use stranded cable color coded AWG No. 14 for all signal and

accessory circuits. Retain the same color identification for the entire length of a circuit run.

730.17 Wiring

1. Terminate all wiring to screw terminals using lugs.
2. Make all splices with solderless connectors, and insulate splices with weatherproof tape applied to a thickness equal to the original insulation.
3. Attach cables to messenger with non-corrosive lashing rods or stainless steel wire lashings.
4. All wiring within enclosed cabinets shall be neatly formed and harnessed and shall have sufficient length for access and servicing.

730.18 Service Connection

Coordinate service connection details and metering with the local utility as directed by the Engineer and in conformance with the City and County requirements. Obtain the necessary service for each installation.

730.19 Sealant

Provide sealant material selected from the Qualified Products List maintained by the Department's Material and Test Division for sealing saw-cuts. The sealant material shall resist the upward movement of loop and lead-in and shall exhibit stable dielectric characteristics, including a low permittivity and high dielectric strength. It shall bond to the roadway paving material, preventing entry of moisture, and shall remain flexible without melting through the anticipated temperature and weather conditions.

730.20 Strand Cable

Span cable for suspending signal heads between pole supports shall be 7-strand, Class A, copper-covered steel wire strand or greater, meeting the requirements of ASTM A460, with a minimum breaking strength as noted on the Plans. An acceptable alternate is 7-strand steel wire with a Class A zinc coating meeting the requirements of ASTM A475, with a minimum breaking strength as shown on the Plans.

730.21

Strand cable for messenger wire (other than span wire as specified above) and pole guy cable use shall be of the diameter(s) shown on the Plans and shall meet the requirements of ASTM A475 for zinc-coated steel wire strand, 7-strand Siemens-Martin Grade with a Class A zinc coating or greater.

A Figure 8 cable combining the messenger cable and conductor cable in an insulated jacket is an acceptable alternate to conductor cable lashed to a messenger cable.

730.21 Bonding and Grounding

Make metallic cable sheaths, conduit, transformer bases, anchor bolts, and metal poles and pedestals mechanically and electrically secure to form a continuous system, and ensure they are effectively grounded. Bonding and grounding jumpers shall be copper wire or copper strap of not less than the same cross-sectional area as No. 6 AWG.

Furnish and install a ground electrode at each service point. Ground electrodes shall be one-piece lengths of copperweld ground rod not less than 8 feet in length and ½ inch in diameter, installed in accordance with the NEC. Ground the conduit and neutral as required under the NEC, except that grounding conductors shall be No. 6 AWG or approved equal, as a minimum. Enclose exposed ground conductors in ½-inch diameter conduit, and bond to the electrode with a copperweld ground clamp.

730.22 Field Test

Prior to completing the work, conduct the following tests on all traffic signal and lighting circuits in the Engineer's presence:

1. Test for ground in circuit.
2. Conduct a megger test on each circuit between the circuit and ground. The insulation resistance shall be not less than the values specified in Section 119 of the NEC.
3. Conduct a functional test to demonstrate that each part of the system functions as specified or intended herein.
4. Test all detector loops and leads before and after they are sealed in the pavement to ensure there are no shorts to ground in the system and to ensure that the loop plus lead-in inductance is within the operating range of the detector.

Replace or repair, in a manner approved by the Engineer, all faults in material or in the installation revealed by these tests. Repeat the applicable testing until no fault appears.

730.23 Inspection

After completion of the installation and before final acceptance of the Project, conduct a full operational check of the system under actual traffic conditions in the presence of the Engineer. The operational check shall cover a minimum time period of 30 calendar days. During this period, perform all necessary adjustments and replace all malfunctioning parts of the equipment required to place the system in an acceptable operational condition at no additional cost to the Department. Perform all work and furnish all materials required under these Specifications subject to the direct supervision, inspection, and approval of the Engineer. Provide the Engineer and authorized representatives free access to the work, and to all plants, yards, shops, mills, and factories where, or in which, articles or materials to be used or furnished in connection with such work are being prepared, fabricated, or manufactured. Provide full and sufficient information to determine that the performance of the work, the character of materials, and the quality of workmanship and materials meets the intent of these Specifications.

Only perform work in the presence of the Engineer or the Inspector appointed by the Engineer, unless permission to do otherwise has first been obtained. The Engineer may reject any work that is performed or constructed in the absence of the Engineer or Inspector, without such permission having been granted, either expressly or by implication.

The inspection of the work shall not relieve the obligation to properly fulfill the Contract as specified. If the Engineer finds a part of the work, or the materials used in the work, to be defective or unsuitable at any time prior to final acceptance, repair or replace such defective or unsuitable work or material.

Request the presence of an Engineer or Inspector in connection with the work under these Specifications at least 24 hours before such services will be required.

730.24

SIGNAL HEADS

730.24 Signal Heads

Signal heads shall meet the latest requirements published in the “Equipment and Materials Standards of the Institute of Transportation Engineers (ITE) for Adjustable Face Vehicle Traffic Control Signal Heads” and the National Electrical Code. The arrangement of traffic signal heads shall be mounted as shown on the Plans or as specified by the Engineer and be in accordance with the latest versions of the MUTCD and the TDOT Traffic Design Manual.

All circular indications shall use 12-inch lenses unless otherwise shown on the Plans. All arrow indications shall use 12-inch lenses. All new vehicle signal heads installed at any one intersection shall be of the same style and from the same manufacturer. All exposed metal signal housings, doors, visors, backplates and framework parts shall be painted with a powder coated finish and be in accordance to the MUTCD specifications. Suspensions for span wire mounting of multi-faced signal heads and signal head clusters (such as a 5-section signal head) shall include an approved swivel type balance adjuster for proper vertical alignment.

Signal head housings shall be cast aluminum and all associated parts/hardware shall be of non-corrosive material. In addition to these requirements, comply with the following:

A. Optical Units

Traffic signal indications shall be LED type and meet the Institute for Transportation Engineers (ITE) latest LED specifications. All LED indications shall have a five year warranty.

B. Signal Head Mounting and Mounting Brackets

Furnish signal heads that either have integral serrations or are equipped with positive lock rings and fittings designed to prevent heads from turning due to external forces. Lock ring and connecting fittings shall have serrated contacts. Provide signals with water-tight fittings.

Support bracket-mounted signal heads, as shown on the Plans, by mounting brackets consisting of assemblies of 1-1/2 inch standard pipe size. Ensure that all members are either plumb or level, symmetrically arranged, and securely assembled. Conceal all conductors within poles and mounting assembly. Secure each slip fitter to the pole.

C. Directional Louvers

Where shown on the Plans, furnish and install louvers in the hoods of the signal head sections designated.

Directional louvers shall have a snug fit in the signal hoods. Construct the outside cylinder and vanes from a non-ferrous metal or galvanized sheet steel. Louvers shall be painted with a powder coated finish.

D. Back Plates

Where shown on the Plans, furnish and attach back plates to the signal heads. All back plates shall be louvered and constructed of 3,003, half-hard, 0.051-inch minimum thickness aluminum sheet. Other materials such as plastic or fiberglass may be used where approved. In fabricating back plates, bend back the inside vertical edges, adjacent to the signal head, to form mounting brackets for attaching to the signal. Form back plates in two or more sections and bolt together, thus allowing for installation after signal heads are in place. Back plates shall have a dull black appearance in the front and back.

E. Wiring

Signal head leads shall be No. 18 AWG stranded with 221 °F thermoplastic insulation. Wire a separate white (common) lead to each socket shell; and wire a colored lead, corresponding to the color code shown on the Plans, to each socket terminal. Provide leads of sufficient length to allow connection to the terminal block specified. Provide each complete signal head with a minimum 4-point terminal block, properly mounted in a signal section. Stud type terminal blocks shall have not less than ¼-inch edge clearance to any portion of the stud. Exterior wiring shall have a 360-degree drip loop in advance of entering the head.

F. Pedestrian Signals

Pedestrian signal heads shall meet the latest requirements published in the "Equipment and Materials Standards of the Institute of Transportation Engineers (ITE) for Adjustable Face Pedestrian Signal Heads", the National Electrical Code and be compatible with NEMA standards. The arrangement of pedestrian signal heads shall be mounted as shown on the Plans or as specified by the Engineer and be in accordance with the latest versions of the MUTCD and the TDOT Traffic Design Manual. The pedestrian indications shall be LED symbols and

730.24

in conformance with the Institute for Transportation Engineers (ITE) latest LED specifications. All LED indications shall have a five year warranty.

In addition, where pedestrian signal heads are provided, they shall:

1. include a pedestrian change interval countdown display where the calculated pedestrian change interval is more than 7 seconds;
2. include Accessible Pedestrian Signals and pedestrian pushbuttons complying with MUTCD Accessible Pedestrian Signals section;
3. incorporate a locator tone meeting the requirements of the MUTCD Accessible Pedestrian Signals; and
4. include a pedestrian pushbutton with tactile vibrating arrow button and audible sound.

The pedestrian countdown display shall conform to the latest FCC regulation on Emission of Electronic Noise.

The manufacturer must supply certification, which includes a copy of the test report by an independent technical laboratory as to the compliance with ITE specifications (where it applies). The report shall also indicate that the tests were performed only after the modules received a thirty (30) minute operational warm-up period immediately preceding the tests.

The housing door, door latch, and hinges shall be of aluminum, or polycarbonate or approved equal. Hinge pins shall be stainless steel. Provide the door with a neoprene gasket capable of making a weather resistant, dust-proof seal when closed.

All pedestrian signal heads, mountings, outside of hoods, and pedestrian push button housings shall have a powder coated finish (if aluminum) or colored resin (if polycarbonate) in accordance to MUTCD specifications.

G. Signal Head Installation

Install signal heads and pedestrian signal heads with the faces completely covered until the entire installation is ready for operation.

CONTROLLERS – GENERAL

730.25 Controllers

Controller equipment shall be permanently marked with the manufacturer's name or trademark, part number, and serial number.

Controllers must meet the following applicable industry standards and amendments:

NEMA TS2 ControllerNEMA TS-2-2016
 ATC Controller.....AASHTO/ITE/NEMA ATC 5.2b

All NEMA TS2 and ATC controllers must provide functionality that meets or exceeds operational characteristics, including NTCIP support, as described in NEMA TS-2-2016.

NEMA TS2 Type 2 controllers shall be used when downward compatibility to existing TS1 cabinets is desired.

Except for replacing controllers in existing systems, all new installations must include controllers that capture high resolution event-based data elements to provide the automated traffic signal performance measures.

The manufacturer must supply certification of the conformance to the above requirements at the time of the bid.

In addition to the above requirements, the controller shall:

1. have all timing values entered via a front panel mounted keyboard. This keyboard shall be an integral part of the controller unit;
2. have an English language menu for programming or reading all controller features;
3. continue to operate the intersection as values are inspected or altered;
4. include the ability to upload and/or download the controller software operating system and user programmed database to or from external media (datakey, usb, sd card etc); and

730.25

5. support Flashing Yellow Arrow for Permissive Left-turn Movements applications.

Surge Protection Devices. The cabinet shall have Surge Protective Devices (SPDs) for the main AC power input, all signal head field wiring terminals, interconnect cable terminals and loop lead-in cable terminals which are located in the cabinet. Furnish SPDs to provide effective defense against high transient voltages caused by lightning discharges or other sources. SPDs must be unobstructed and accessible from the front side of any panel used in the cabinet. The SPD for the main AC power input of the cabinet must be connected on the load side of the cabinet circuit breaker. SPDs must meet the following minimum requirements:

1. AC power SPD:
 - a. Must be UL 1449 4th Edition Listed
 - b. Parallel connected device
 - c. UL Nominal Surge Rating (In): 20kA
 - d. UL Short Circuit Current Rating (SCCR): 150kA minimum
 - e. Surge current rating: 50kA per phase minimum
 - f. Visual status indication
 - g. Remote signalization contacts for monitoring purposes
 - h. 10-year manufacturer's warranty minimum
2. DC power SPD:
 - a. Must be UL 1449 4th Edition recognized
 - b. Parallel connected device
 - c. UL Nominal Surge Rating (In): 10kA minimum
 - d. Must provide protection between all +/-Gnd connections
 - e. Surge current rating: 20kA per phase minimum
 - f. Visual status indication
 - g. Remote signalization contacts for monitoring purposes
 - h. 10-year manufacturer's warranty minimum
3. Data and communication SPD:
 - a. Must be UL 497B listed
 - b. 10-year manufacturer's warranty minimum
4. Signal and interconnect cable field wiring terminal SPD:

- a. Clamp the surge voltage to a level no greater than twice the peak operating voltage of the circuit being protected
 - b. Withstand a surge current of 1000A with an 8 by 20 μ s waveform six times (at 1 second intervals between surges) without damage to the suppressor
 - c. 10-year manufacturer's warranty minimum
5. Loop lead-in cable field wiring terminal SPD:
- a. Protect the detector unit loop inputs against differential (between the loop lead) surges, and against common mode (between loop leads and ground) surges
 - b. Clamp the surge voltage to 25 V or less when subjected to repetitive 300A surges
 - c. Withstand repetitive 400A surges with an 8 by 20 μ s waveform without damage
 - d. 10-year manufacturer's warranty minimum

All SPDs must be installed according to the SPD manufacturer's instructions and not affect the operation of equipment. SPD leads must be kept as short and straight as possible.

CABINETS – GENERAL

730.26 Cabinets

Cabinets must be permanently marked with a label including the manufacturer's name or trademark, model/part number, and the year and month of manufacture. The label should be placed on the inside of the main door using a water resistant method. The label must be visible after installation.

Cabinets shall be provided as a complete unit and have all terminals and facilities necessary for traffic signal control as shown on the plans and shall meet at a minimum, the following requirement:

NEMA TS2 Controller Cabinet.....NEMA TS 2 2016

730.26

The manufacturer must supply certification of the conformance to the above requirements at the time of the bid. Cabinets shall also be in accordance with the latest version of the TDOT Traffic Design Manual.

Two paper copies of the cabinet wiring diagram shall be provided with each cabinet. The nomenclature of signal heads, vehicular movements and pedestrian movements on the wiring diagram must be in accordance with the signal operating plan. Documentation must include a list identifying the termination points of cables used for vehicular and pedestrian signal heads, detector loop lead-ins, and pedestrian pushbutton wires. A heavy duty, resealable plastic bag must be mounted on the backside of main cabinet door for storing cabinet documentation.

House the controller in a rigid, weatherproof cabinet, constructed, finished, and equipped as follows, and as shown on the Standard Details:

1. **Material.** Provide weather-tight cabinets fabricated from aluminum sheet or cast aluminum alloy with a minimum 0.125-inch thickness. All welds on fabricated cabinets shall be internal and continuous; spot welding is not acceptable. Painting of cabinets is only required if the final finish presents an unsightly appearance.
2. **Doors.** Type III, IV, and V cabinets shall have a hinged front opening door that shall include substantially the full area of the front of the cabinet. Equip the door with a positive hold fast device to secure the door in at least two open positions: one position at approximately 90 degrees and the other at 120 degrees or more. The holdfast device shall be easily secured and released without the use of tools. Equip doors for Type II, III, IV, and V cabinets with a switch compartment, and provide the manual switches, specified in **730.26.6.k**, with a hinged front opening auxiliary door. Each door shall have a gasket to provide a weatherproof seal when closed.

Provide the main door with a No. 2 pin-tumbler cylinder lock, and the auxiliary door with a standard police sub-treasury lock. Provide four keys for each lock.

Provide a switch which is to be tied to the cabinet light so that cabinet light will be on when the door is open and off when the door is closed.

3. **Cabinet Mounting.** Mount cabinets as shown on the Plans or Standard Details.

4. **Ventilation.** Unless otherwise specified, provide ventilation as follows:
 - a. On all cabinets housing controllers, mount a screened, rain-tight vent, 1-1/2 inches in diameter or larger, on the cabinet top.
 - b. Provide screened or filtered inlet ventilation openings, equal to or greater in area than top vents, located in the bottom or lower back side of Type I and II cabinets or around the lower 8 inches portion of Type III cabinets.
 - c. Construct the vents so as to project within the cabinet no more than necessary to provide for lock nuts and gaskets to retain the vent.
 - d. Locate vents so as to not interfere with the mounting of controller equipment.
5. **Cabinets with Exhaust Fans.** Exhaust fans shall consist of an electric fan with ball or roller bearings and a capacity of at least 100 cubic feet per minute. Mount the fan in a rain-tight housing attached to the top of the controller cabinet.

The fan shall be controlled by a thermostat having a temperature differential between turn-on and turn-off of 15 °F (-0, +5 °F), adjustable for turn-on through a minimum calibrated range of from 100 °F to 150 °F.

Whenever a fan is to be installed, provide the air inlet filter and filter holder shown in the Standard Details, or approved equal. Internally seal other air inlets. Provide exhaust fans in all cabinets that house controllers, with the exception of flasher controllers.

6. **Auxiliary Equipment.** With the exception of cabinets used in special applications (Type I and II), provide all cabinets with the following:
 - a. Substantial shelves or brackets to support controller and auxiliary equipment.
 - b. Panel for terminals arranged for adequate electrical clearance. Panels should be located in the cabinet as described below:

730.26

- Detectors Lower left wall
- AC power Lower right wall
- Auxiliary/police switches Door
- Load switch bay Back wall

c. The cabinet shall include an LED light and GFI duplex receptacle which can be used when the main circuit breaker is off.

d. Control panel assembly consisting of:

1. Power supply connections made to a 30-ampere circuit breaker mounted on the cabinet separate from the signal terminal panel. The circuit breaker shall be a magnetic trip type, having an interrupting capacity of at least 2,000 amperes at 125 volts AC. The circuit shall trip between 101% and 125% of rated load, with an inverse time delay characteristic provided. Instantaneous tripping shall occur at ten times the nominal rating. All controllers shall be internally fused.
2. Service line surge protection.
3. Electrical service termination point sized to accept No. 4 AWG copper wire.
4. Ground fault receptacle.
5. Porcelain lamp receptacle to accept a standard traffic signal lamp. If LED lenses are utilized, they shall be dimmable and switchable to reduce glare at night time.
6. Circuit breakers in accordance to the National Electric Code for:
 - (a) Main power input to provide all power associated with normal operation.
 - (b) Flasher power input to provide all power associated with flash operation.
 - (c) Service power to provide power for the lamp and duplex receptacle and cabinet light.

7. Copper ground bus (minimum of 12 positions).
 - e. Flasher mechanism independent of controller. The cabinet shall be wired for and include a NEMA flasher mounted on the back panel. All cabinets shall have a two-circuit flasher. The flasher shall have output indicators mounted on the front of the flasher case and shall be rated at a minimum of 15 amperes.
 - f. General purpose relays, where required to perform specified functions. All relays external to the controller or appurtenances shall meet NEMA standards. In addition:
 - Flash transfer relays shall be of heavy-duty type and have a minimum contact rating of 10 amperes. Contacts shall be of silver material to reduce contact pitting.
 - Unless otherwise specified, each cabinet shall include six (6) flash transfer relays.
 - Flash transfer relays shall support Flashing Yellow Arrow for Permissive Left-turn Movements applications.
 - g. Type II, III, IV, and V cabinets, when specified as housing for traffic actuated controllers, with two or more insulated terminal blocks mounted within the housing, one or more for terminating each field wire.
 - h. A minimum of 12 available bare ground positions tied to AC Common Return.
 - i. Earth (driven) ground tie point to terminate a single No. 4 AWG copper ground.
 - j. A tie point to tie all ground systems within the cabinet to a single reference point. All grounds (AC - return, Chassis, and Logic Ground) must be referenced to a single ground point at the electric service.
 - k. A panel (police subpanel) shall contain the following:

730.26

1. A main power switch, which shall be wired to remove all cabinet power when in the Off position
2. An Automatic Flash switch, which shall be wired as follows:
 - (a) The Flash position shall cause the cabinet to provide Flash Operation. The controller shall continue to operate, and Stop Time shall be applied to the controller.
 - (b) Auto/Manual switch to activate Manual Control Enable.
 - (c) Manual control pushbutton switch with self-coiling cord. Cord shall attach to a 2 position terminal strip via fork type connector.
 - (d) Upon return from Flashing to Automatic, the controller shall initialize in the Start-Up Display condition as programmed in the controller, typically major road phases.
3. A panel mounted inside the main door shall contain the following switches:
 - (a) A technician Stop-Time switch to apply Stop Time to each controller ring.
 - (b) An Interval Advance switch, enabled only by the Stop Time switch, to be momentary pushbutton switch to apply Interval advance to the timer.
 - (c) A Signal On-Off switch, which shall remove the AC power applied to the signal heads for normal operation while the controller continues to operate.
 - (d) Individual phase vehicle and pedestrian detector test switches to be miniature toggle of the On-Off Momentary type to place:

- i. No Call - Call provided by detectors
- ii. Locked detector call
- iii. Momentary detector call

Insulate or shield switch terminals on back of main cabinet door so that no live parts are exposed.

Leads from the terminal block to the auxiliary door switches shall be no less than No. 18 AWG stranded, with TW plasticized polyvinyl chloride or nylon insulation enclosed in an insulating loom, and shall be of sufficient length to allow full opening of the main cabinet door.

- l. The cabinet shall be wired with the appropriate number of load switches to accommodate vehicular and pedestrian phasing according to plans. At a minimum, cabinets shall include 16 load switch bases. The load switch wiring shall support Flashing Yellow Arrow for Permissive Left-turn Movement applications.
- m. All cabinet wiring shall be neatly routed and labeled, laced and permanently secured. All cable shall be secured to the panel, where practical. There shall be no holes drilled through the cabinet walls to mount panels or secure cables.
- n. All terminals in the cabinet shall be of the barrier type. The following field connector terminals shall be provided:
 - Four (4) signal output positions per load switch bay (R-Y-G-FL).
 - Ten (10) positions per phase for vehicle loop detector harness.
 - One position per phase for pedestrian detector inputs.
- o. Cabinets shall have SDLC communication between the controller, MMU, Detector Rack, Radar Detector (if applicable) and Video Detection (if applicable).

730.27

- p. Cabinets should have an electrical outlet (Non GFI) that has 120 VAC from the OUTPUT side of the Main Power Surge unit.
- q. Cabinets shall support Flashing Yellow Arrow for Permissive Left-turn Movements applications.
- r. All cabinets shall be supplied with a Malfunction Management Unit (MMU) and shall meet at a minimum, the following requirement:

NEMA TS2 Malfunction
Management Unit.....NEMA TS 2 2016

The manufacturer must supply certification of the conformance to the above requirements at the time of the bid.

According to NEMA TS2 the MMU shall be able to detect the presence of voltage on conflicting field connection terminals, the absence of proper voltages on all the signal field connection terminals of a channel, and shall be capable of monitoring for the presence of satisfactory operating voltages within the Controller Unit (CU) and the MMU itself. The MMU shall be able to operate as a Type 16 with sixteen channels or as a Type 12 with twelve channels (compatible with NEMA TS1 cabinets).

The MMU should have an Ethernet port.

730.27 Auxiliary Equipment for Traffic Signal Controllers

Furnish and install the following auxiliary equipment in each cabinet for traffic actuated controllers.

A. Load Switches

Provide each cabinet complete, with the necessary number of NEMA load switches and Flash Transfer relays necessary to affect the specified signal sequence and phasing. Load switches shall:

- 1. Meet NEMA standards.

2. Have front-face mounted LED indicators to indicate the “On” condition of both the Input and Output circuits.
3. Use replaceable “cube” type circuitry or encapsulated discrete component construction. No unencapsulated discrete component construction are acceptable.

B. Time Clock Switches

Where shown on the Plans, provide time clock switches of solid state circuitry, continuous duty, with a 7-day cycle clock operating from the 120-volt AC service line. Provide switching for a minimum of one independent output and ensure the time of day selection is adjustable to within 1 minute of the desired time. Provide a battery backup system that can maintain time keeping and memory a minimum of 24 hours after power interruption. Furnish an omitting device as an integral part of the time switch to allow the switching operation to be skipped for any preselected day or days of the week. The time clock shall automatically compensate for daylight savings time changes. When the time clock is supplied as an internal component of the controller, supply the clock feature to provide for the selection of Maximum Green II on time of day, day of week, week of year basis. Time clocks shall meet NEMA environmental specifications.

When required in the traffic signal plans, the auxiliary equipment listed below shall meet the following requirements:

1. **Uninterruptable Power Supply (UPS).** An UPS shall power the traffic signal cabinet in the event of a power failure for a minimum of 3 hours.

UPS assemblies should include off-the-shelf deep cycle AGM batteries.

Loss of utility power, transfer from utility power to battery power, and transfer back to utility power must not interfere with normal operation of connected equipment. In the event of UPS failure or battery depletion, connected equipment must be energized automatically upon restoration of utility power.

Removal and replacement of the UPS must not disrupt the operation of the equipment being protected.

730.27

All harnesses necessary to connect and operate the system must be included. All connectors must be keyed to prevent improper connection.

UPS assemblies shall be installed in accordance with the manufacturer's recommendations.

An UPS operation and maintenance manual shall be provided in the cabinet where the UPS is installed with cabinet wiring schematics, electrical interconnection drawings, parts layout and parts lists.

The UPS shall include a manufacturer's warranty covering defects for a minimum of three years (5 years for the external batteries) from the date of final equipment acceptance. The warranty must include provisions for providing a replacement UPS within 10 calendar days of notification for any UPS found to be defective during the warranty period at no cost to the maintaining agency.

2. **Communications – Wireless.** Consist of installing a Wireless Network Communications Link with all necessary hardware in accordance with the plans and standard drawings to provide a data link between field devices (i.e. Traffic Signal Controllers).

Each link shall consist of Master ODU (Out Door Unit, Antenna) connected to a data switch within one of the signal cabinets and a Slave ODU connected to a data switch within the other signal cabinet. Each ODU is aligned to face the opposing ODU. The cable length between the ODU and its associated data switch may not exceed 300 feet.

The Wireless Network Communications Link components at each of the linked traffic signal cabinets shall include an ODU, a LPU (Lightning Protection Unit), power supply mounting hardware, and CAT 5E cabling. The ODU is pole mounted per manufacturer's specifications. The LPU and power supply are mounted within the traffic signal cabinet. CAT 5E cable is installed between the ODU and LPU.

For the applicable frequency spectrum of the radios being deployed, perform a spectrum analysis to ensure no competing equipment in the area. Ensure the radio path site survey test is performed using the supplied brand of radio equipment to be deployed. Typically, if the ODUs can be mounted with clear line of sight between them,

this is sufficient to ensure proper operation. If this is not possible, it may be determined that a repeater station is necessary to complete the intended link. Provide the test results to the Engineer for review and approval. Submit copies of the test results and colored copies of the frequency spectrum scan along with an electronic copy of this information. The Engineer will approve final locations of the ODUs and any necessary repeater stations.

Install each ODU in such a manner that avoids conflicts with other utilities (separation distances in accordance with the guidelines of the NESC) and as specified in the ODU manufacturer's recommendations. Secure the ODU mounting hardware to the pole and route the CAT 5E cable such that no strain is placed on the RJ-45 connectors. Align each antenna/radio to be perpendicular to the ground (using bubble level) and to face the opposing radio.

3. **Fiber optic cables.** Multi-mode type fiber optic cable shall be 50 μm core diameter, with at least 12 fibers per cable unless otherwise specified in the plans. Single-mode type cable shall be between 8-9 μm core diameter, with at least 12 fibers per cable unless otherwise specified. A fiber optic drop cable shall be a minimum of 6 fibers (each type) and be spliced into the trunkline in a splice enclosure either aerially or in a pull box. 50 ft. of slack shall be provided, either lashed to a span aerially, or coiled in a pull box for underground installations. Termination panels shall be provided with sufficient size to provide for a neat installation, and enough panel space to accommodate the specified number of fibers for termination. ST connectors shall be used unless otherwise specified. Any necessary jumpers shall be provided for installed equipment.

730.28 Miscellaneous Traffic Signals

A. Flashing School Signals

When shown on the Plans, provide flashing school signals that conform to the following:

1. The signal shall produce two alternate flashing lights within the marginal limits of a school speed limit sign. Details of the sign construction shall be as shown on the Plans. Sign colors shall conform to the MUTCD and be constructed of materials complying with these specifications.

730.28

2. The two LED lenses shall be yellow in color and a minimum of 8 inches in diameter. The LED lenses shall be part of a weather-proof and water-tight optical unit. The LED lenses shall meet the same requirements for vehicular signal head LED lenses. Mount the lenses in the sign using a molded endless rubber gasket with the sign being mounted to the signal case.
3. Provide a two-circuit type flasher unit to provide alternating equal on-off operation. The flashing mechanism shall produce between 50 and 60 flashes per minute through two 120-volt, 60-cycle AC, 15-ampere circuits. The flasher shall be of solid state construction.
4. Wire the unit for external circuits.
5. The signal shall be actuated by time switch meeting **730.27**. Locate the timing device in a remote mounted control cabinet.
6. Where an illuminated speed limit indication is shown on the Plans, the numeral message shall be illuminated in Portland Orange in a rectangular lens and illuminated only during the period when the signal produces two alternately flashing amber lights.

In addition, the Time Clock Unit/Switch used for Flashing School Signals shall be a programmable module that allows a user to define the time and day that the school speed zone flasher assembly will initiate and terminate flashing operation. The module shall be installed within the pole-mounted signal cabinet provided as part of project. The time clock shall be compatible with the cabinet's wiring relays and termination panels and the battery power supply system. The time clock switch provided shall also have the following features/capabilities outlined below:

1. Daylight Savings Time shall be a user-programmable setting, in addition to having automated compensation per TDOT specifications.
2. The unit shall provide a minimum 12-character, multi-line alphanumeric LCD back-lit display capable of displaying all programming parameters.
3. The unit shall be capable of being programmed manually (using an integral keyboard pad) or programmed externally using an optional software program via a laptop computer and cable connection

(compatible software program is a separate and distinct item from the time switch unit, and if required, will be separately specified and noted in list of estimated project quantities).

4. Unit shall provide automatic Leap Year compensation.
5. The time clock switch shall be capable of up to minimum 24-hours of capacitive back-up operation, 48 hours desirable, in the event of power interruption.
6. Unit shall be compatible with the supplied solar powered power system/battery unit
7. Time clock switch shall be capable of being programmed for one (1) Normal/Main program, and an additional minimum of 12 Exception periods/programs allowing holiday, vacation and custom skip plans. The exception programs will allow for the Normal/Main program to be skipped or allow for flasher operation on alternative schedules (i.e. early release days, summer school, etc).
8. Unit shall conform to **730.27** – Auxiliary Equipment for Traffic Signal Controllers – Time Clock Switches except as superseded herein.
9. Unit shall have non-volatile program memory to allow retention during power loss.

B. Solar Power Flashers

When required, the solar power flasher equipment listed below shall meet the following requirements:

1. Solar panel and mounting equipment shall be installed on cantilever pole shaft as illustrated on layout detail sheet and as directed by manufacturer instructions.
2. Solar power unit assembly shall include all required mounting equipment, wiring/cables, battery supply, battery charging unit and other ancillary equipment necessary to operate the solar panel and properly charge the battery. The photovoltaic array shall include mounting bracket assembly to permit adjustment of the array to optimal sun exposure. The photovoltaic module shall be mounted

730.28

and aligned per manufacturer recommendations to maximize solar exposure.

3. Battery unit shall meet manufacturer specifications required to operate and power L.E.D. signal displays and continuous time clock switch operation. Battery shall be compatible with cabinet equipment, including the time clock switch and the flasher signal displays. Battery unit shall meet minimum environmental and performance specifications required for system operation as recommended by solar panel and time clock switch manufacturers.
4. Solar panel and battery supply shall be of a size and power rating necessary to provide required power to time switch clock and flasher signal displays. Obtain the power load requirements from the solar power equipment manufacturer and provide as required. On a typical school day, it should be expected that the flasher system will operate up to four (4) hours per day with the time clock continuously operating to maintain its clock timer. Provide a solar system sizing report from the manufacturer indicating the power supply requirements of the proposed system required to meet the expected power demand.
5. The photovoltaic modules shall be warranted for a minimum of five (5) years from date of installation.
6. The battery system shall be a gelled-electrolyte type battery with capacity to provide a minimum of five (5) days continuous operation of the flasher assembly without charging. Batteries shall be field replaceable. Batteries shall have prorated warranty of a minimum of five (5) years from date of installation.

C. Portable Traffic Signals

Portable Traffic Signals (PTS) consists of furnishing, installing and configuring a complete PTS system that may be used in construction zones or in other temporary signal locations. The work will be at various sites throughout the state of Tennessee and will consist of providing all labor, materials, equipment and incidentals necessary to make functional the PTS in accordance with these specifications.

The PTS shall be trailer or cart mounted units that provide for easy transportation and quick setup and deployment. There shall be 2 unit options and each unit shall be self-contained.

1. Type 1 units are typically used for long term projects (i.e. projects 5 days or longer in duration) and shall include 2 signal heads per trailer with an upper signal head mounted on an overhead mast arm that can be extended over the travel lane, and a lower signal head mounted on the vertical upright of the trailer.
2. Type 2 units are typically used for short term projects (i.e. projects 4 days or shorter in duration) and shall include 1 signal head that is mounted on the vertical upright of the trailer or cart. Cart-mounted units shall meet the requirements of and be listed on the Department's QPL or Standard Drawings. If the project duration is extended beyond 4 days, then Type 1 units should be substituted in lieu of the Type 2 units for all PTS within the signal system.

The PTS shall be MUTCD Compliant and utilize standard ITE signal heads and adhere to the ITE Specifications and Standards for Vehicle Traffic Control Signal Heads, Light Emitting Diode (LED) Circular Signal Supplement. The unit shall be solar powered and communicate via a wireless or hardwire connection. The unit shall include all the major components listed below or be able to perform the functions of these components. The major components of the unit shall include but are not limited to the trailer or cart, telescoping mast arm (on Type 1 units only), signal head(s) and back plates, traffic signal controller with operating software, solar charging system with batteries, input and output devices, flasher units, conflict monitor, relays, communications system and other equipment required for the safe operation and installation of the unit.

The PTS signal heads and all applicable components of the PTS shall meet the physical display and operational requirements of conventional traffic signals as specific in the MUTCD.

1. For Type 1 units, each unit shall contain 2 signal heads with an upper signal head mounted on an overhead mast arm that can be extended over the travel lane with a minimum clearance of 17 feet measured from the bottom of the signal head unit to the road surface. The lower signal head shall be mounted to the vertical upright of the trailer at a minimum height of 8 feet from the bottom of the signal head unit to the road surface. The signal heads shall also include black back plates that can be easily removed. The signal heads shall have the ability to be rotated 180 degrees to face in the opposite direction and shall have the ability to rotate and lock in

730.28

approximately 10-degree increments to position the signal head for the optimum visibility to motorists.

2. For Type 2 units, the signal head of the unit shall be mounted to the vertical upright at a minimum height of 8 feet from the bottom of the signal head unit to the road surface. The signal head shall also include black back plate that can be easily removed. The PTS shall be easily rotated to position the signal head for optimum visibility to motorists.

The PTS shall include a solid-state controller with operating temperature range of -40°F to +180°F and compliance with NEMA TS-5 Performance Standard. The controller or programming module shall have an easy to read front panel indicator display. The display shall be backlit and have the capability to facilitate programming and display the currently operating program for each vehicular approach. The controller shall be capable of operating the PTS system in a fixed time, traffic actuated, or manual control mode. Each PTS in a connected system shall have the capability to serve as either the master or slave signal. Each PTS shall include a Conflict Monitor Unit (CMU), or Malfunction Management System (MMS) to ensure phase conflicts do not exist during operation.

1. A minimum of 5 automatic time-of-day timing plans within a 24-hour period should be available in fixed time mode. The operating system should have the ability to control a minimum of 4 traffic phases with programmable cycle time adjustments and user adjustable red, amber, minimum green and maximum green times. The operating system shall also have the capability of facilitating standby modes of red, red flash and yellow flash.
2. The system shall have the ability to operate in vehicle actuation mode when vehicle detection detectors are used. The operating system shall have the capability to allow the PTS to be connected to and controlled by a standard NEMA controller.
3. The system shall have the capability to be configured and controlled remotely using a handheld wireless remote control with the capability of being operated at a distance up to 1/4 mile from the master.
4. The system shall have the capability of remote monitoring for reporting, at a minimum, signal location and status, battery voltage

and system defaults. The remote monitoring shall have capability to alert designated individuals if a fault condition occurs.

5. The operating system shall include password protection to prevent unauthorized programming.

The PTS shall communicate with all other PTS within the signal system via license-free wireless 900 MHZ radio link communications. The radio units shall maintain communications at a minimum distance of 1 mile. The radio system shall conform to the applicable Federal Communications Commission (FCC) requirements, including FCC 90.17, and all applicable state and local requirements. The PTS shall be in direct communication at all times either by wireless or hardwire connection to provide for the required conflict monitor.

The system shall have the ability to operate in vehicle actuation mode when vehicle detection detectors are used. For Type 1 units, the PTS detector shall be a high-definition, multi-beam, microwave radar stop bar detector for each vehicular approach. The Type 1 radar detector shall have a minimum range of 140 feet and shall be mounted at a minimum height of 17 feet measured from the top of the road surface. For Type 2 units, the PTS detector shall be a radar detector for each vehicular approach. The Type 2 radar detector shall have a minimum range of 140 feet and shall be mounted and have complete radar detection functionality at a minimum height of 8 feet measured from the top of the road surface.

The PTS shall be equipped with a solar power array, charging unit and battery system. For Type 1 units, the number and size of batteries shall be sufficient to operate the signal for a minimum of 21 days at 70 degrees without additional charging or assist from the solar array. An on-board battery charger shall be compatible with both the solar array and with a 120V AC power source. The solar panel array shall provide for a minimum of 440 watts of solar collection capability. For Type 2 units, the PTS shall have batteries sufficient to operate the signal for a minimum of 5 days at 70 degrees without additional charging or assist from a solar array. All instrumentation for the electrical system and battery compartment shall be mounted in a lockable weatherproof enclosure. Solar panels shall be secured to the mounting brackets for theft prevention. All wiring for the unit shall be protected against weather and damage.

730.28

The trailer or cart, and all mounted components, shall conform to the wind loading requirements (90 mph minimum) as described in the AASHTO Standard Specifications for Highway Signs, Luminaries and Traffic Signals. The wind load calculations shall be completed by an independent third-party contractor and stamped by a U.S. Registered Professional Engineer. The trailer or cart shall be made of structural steel and shall include 4 leveling/stabilizer jacks capable of lifting the trailer or cart a minimum of 6 inches. The trailer or cart shall be equipped with a hydraulic or electric lift system sufficient for 1 person to be able to raise and lower the vertical upright and/or horizontal mast arm to and from the operating position. For Type 1 or 2 units, the trailer or cart shall be equipped to provide legal and safe transport on the public highway system at speeds up to 55 mph. All exterior metal surfaces, except signal heads and back plates, shall be powder-coat painted highway safety orange.

The PTS work shall meet the following general contractor requirements:

1. Be responsible for locating the PTS in the appropriate location based on MUTCD and ITE standards for visibility to motorists and for safe operation.
2. Be responsible for providing all hardware, software, communications equipment and licenses to operate a complete PTS system.
3. Be responsible that all PTS equipment is installed according to the manufacturer's recommendations including wireless or hardwire connections.
4. Be responsible for transport, setup, configuration, operation and monitoring of the PTS throughout the entire project. The Engineer shall approve all timing and settings that are used for operation of the signal.
5. As directed by the Engineer, it may be necessary to relocate the PTS during the project. The cost of the relocation shall be included in the PTS price bid.

DETECTORS

730.29 Detectors

Provide detectors, of the type shown on the Plans, to actuate signal phases of traffic actuated controllers. Provide ample lightning protection to provide effective defense against high transient voltages caused by lightning discharges or from other sources. The lightning protection unit must withstand repeated 400-ampere surges on a 9 x 20 microsecond waveform. Also, the unit must be a two-stage device capable of clamping a minimum of one hundred 300-ampere surges to 25 volts within 40 nanoseconds for surge applied across the two detector leads.

A. Inductive Loop Detection System

Inductive loop detector units (loop amplifiers) shall meet at a minimum, the following requirement:

NEMA TS2 Inductive
Loop Detector Units NEMA TS 2 2016

Loop amplifiers may be single or multi-channel and shall be of the totally self-contained type.

All loop amplifiers shall be of the type to provide both “Extended” and “Delayed” outputs.

The loop detector amplifier shall be full automatic, requiring no adjustments to effect operational ability other than setting of the operating frequency and sensitivity. The amplifier shall:

1. Sense any legal motor vehicle traveling at speeds up to 65 miles per hour.
2. Have both a “Pulse” and “Presence” Output:
 - a. Pulse output shall generate an output of 125 plus or minus 25 millisecond output for each vehicle entry.
 - b. Presence output shall provide a continuous output for up to 60 minutes as long as a vehicle is within the detection zone.
3. Provide at least four user selectable sensitivity ranges.

730.29

4. Be supplied with at least three frequency ranges for crosstalk minimization.
5. Have a front-face mounted indicator to indicate active output of the internal relay. This indicator shall indicate the presence of:
 - a. Normal Output
 - b. Delayed Output
 - c. Extended Output
6. Have a front-panel mounted "Reset" switch that when pressed shall cause the unit to completely re-tune itself.
7. Have Delayed or Extended timing features with the following ranges:
 - a. Delayed output of 0 to 30 seconds in 1-second increments.
 - b. Extended output of 0 to 10 seconds in 1/4-second increments.
8. Have internal diagnostics to determine the operational ability of the loop. These diagnostics shall determine if a loop is opened or shorted and shall provide a visible indication of such condition. Additionally, if such a condition occurs, the amplifier unit shall default to a "constant" output.
9. Provide output by a mechanical relay, which shall be "off" to provide an output.
10. Have all delay functions wired to the associated plan phase green to inhibit that function during controller phase green.
11. Be able to operate with loop lead-in lengths of at least 2,000 feet.

Comply with the details of the detector loop installation as shown on the Plans or Standard Drawings.

B. Video Detection System (VDS)

When specified in the plans, the equipment shall consist of all items necessary to provide a complete functional video detection system that

process images and provide detection outputs to the traffic signal controller.

VDS shall be capable of NEMA TS2 operation.

VDS shall be waterproof and weather resistant.

VDS shall provide user-defined detection zone programming via a graphical user interface (GUI) and any necessary equipment for future programming. The configuration database shall have the ability to be stored on a removable data storage external to the video card.

VDS shall display programmable detection zones and detection activations overlaid on live video inputs. It shall detect vehicles in real time as they travel across each detection zone.

VDS shall have a minimum of 24 programmable detection zones per camera.

VDS shall be capable of:

1. shadow rejection without special hardware;
2. non-impaired operation under light intensity changes;
3. maintained operation during various weather conditions (e.g. rain, fog, snow);
4. anti-vibration, 5% rejection based on image change;
5. ability to select direction of flow parameters;
6. ability to properly detect directionally;
7. ability to configure presence, pulse, extend and delay outputs;
8. ability to set up a minimum of six detection zones per camera view to count the number of vehicles detected and store the information for retrieval;
9. variable focus providing a minimum of 4 to at least 40-degree horizontal field of view; and

730.29

10. store detection zones in non-volatile memory.

VDS shall have no splices between the processors and the cameras.

VDS shall provide LED indicators to show active detection.

VDS camera shall have an internal heater to assure proper operation of the equipment during low temperatures.

VDS shall have surge ratings as set forth in NEMA specifications.

VDS shall have a two-year warranty and updates of all software shall be available without charge during the warranty period.

C. Radar Vehicle Detection System (RVDS)

When specified in the plans, the equipment shall consist of all items necessary to provide a complete functional RVDS that process high-definition, multi-beam radar electromagnetic waves and provide detection outputs to the traffic signal controller.

RVDS shall be capable of NEMA TS2 operation.

An RVDS shall consist of the following components: Radar sensor (1), detector rack interface module (1) power and surge protection panel or module (1) (cabinet interface devices that combine one or more of the above components shall be acceptable as well), and all associated equipment required to setup and operate in a field environment including software, serial and ethernet communication ports, cabling, electrical connectors and mounting hardware.

The RVDS shall be able to operate in all types of weather conditions including: rain, snow, sleet, ice, fog and windblown dust.

Lightning and surge protection will be provided for power connections and communications links to the radar RVDS.

The RVDS shall provide a “fail safe” operation that triggers when communication between the radar vehicle sensor and the interface module is broken. Contact closure from the interface module will occur on all programmed detector channels associated with the affected radar sensor when the fail safe is triggered and will remain in this state until

communication is re-established between the interface module and the radar vehicle sensor.

The RVDS shall comply with all applicable Federal Communications Commission (FCC) requirements. The manufacturer will provide documentation of compliance with FCC specifications.

The RVDS shall maintain frequency stability without the use of manual tuning elements by the user.

The RVDS as a minimum must provide a minimum of 4 separate RF channels selectable by the user to avoid interference with other devices working on the same frequency.

The communication port(s) shall support a communication speed that will not introduce excessive latency between when a vehicle is detected and the contact closure in the traffic signal cabinet.

RVDS interface modules that utilize the detector rack must operate at 12V or 24V DC. Shelf mounted interface modules must operate within a range of 89V to 135V AC, 60 Hz single phase. Power to the RVDS radar sensor must be from the transient protected side of the AC power distribution system in the traffic control cabinet in which the RVDS is installed.

RVDS documentation shall include a comprehensive user guide as well as quick reference guide(s).

RVDS shall have the ability to configure presence, pulse, extend and delay outputs.

D. Wireless Magnetometer Detection System (WMDS)

When specified in the plans, the equipment shall consist of all items necessary to provide a complete functional wireless magnetometer detection system that process changes to earth magnetic field and provide detection outputs to the traffic signal controller.

WMDS shall be capable of NEMA TS2 operation.

The WMDS shall consist of the following components: In-pavement sensors, all wireless communication equipment needed to establish

730.29

communication links to the controller cabinet, interface modules compatible with NEMA TS-2 V2.06b cabinet detector rack, surge protection for the WMDS and system software for set-up and monitoring of the WMDS.

The WMDS must be capable of detecting a variety of vehicle types including motorcycles, automobiles and large trucks. The system must allow the user to select sensitivity levels that adjust the amount of hysteresis to the magnetic field needed to achieve contact closure to the assigned detector channel. Magnetometer sensitivity level adjustments must allow for different levels of vehicle detection.

WMDS shall have the ability to configure presence, pulse, extend and delay outputs.

WMDS equipment failure such as: the sensor, communications link, access point radio, repeater radio (if used) or interface module, shall result in constant vehicle call "fault state" on the affected detector channel to the traffic controller.

WMDS detection accuracy must be comparable to properly operating inductive loops.

The WMDS shall provide real-time vehicle detection (within 150 milliseconds (ms) of vehicle arrival). Once detection is achieved by the sensor, the traffic controller must receive contact closure to the assigned detector channel within the 150 ms time frame.

The WMDS in-pavement sensor must operate on batteries without the need for underground power or communication cable connections to the unit.

The average operating life span of the sensor under battery power must be a minimum of 10 years.

The interface module must provide 2 or 4 detector channels. Sensors must be assignable to the available detector channels on the interface module using software provided with the WMDS.

The front face of the module shall identify detector channel 1 and detector channel 2. Each must use an LED to indicate contact closure on the channel. When vehicle detection is achieved, the LED will be on and contact closure applied to the detector channel. During periods of no

vehicle detection the LEDs will be in an off state and no contact closure will be applied to the detector channel.

The interface module will use an LED indication to indicate a “fault state” with the WMDS. When the fault state is active contact closure will be applied to the appropriate detector channel.

E. Pedestrian Push Buttons

Where shown on the Plans, furnish and install pedestrian push buttons of substantial tamper-proof construction. They shall consist of a direct push type button and single momentary contact switch in a cast metal housing. Operating voltage for pedestrian push buttons shall not exceed 24 volts.

Provide a weatherproof assembly, constructed to prevent electrical shocks under any weather condition.

Where a pedestrian push button is attached to a pole, the housing shall be shaped to fit the curvature of the standard or post to which it is attached to provide a rigid installation.

Unless otherwise specified, install the push button and sign on the crosswalk side of the pole.

Pedestrian push buttons shall have a transient protection that meets NEMA specifications.

730.30 Reserved

730.31 Reserved

TRAFFIC SIGNAL SUPPORTS

730.32 Cantilever Signal Supports

This Subsection applies to the manufacture of steel poles and mast arms for the support of traffic signals. The height of poles, shaft dimensions and wall thickness shall meet the design requirements and mounting height of traffic signals as set forth in these Specifications and shown on the Plans. The Plans indicate bracket arm lengths.

730.32

Furnish poles consisting of a straight or uniformly tapered shaft, cylindrical or octagonal in cross-section, having a base welded to the lower end and complete with anchor bolts. All castings shall be clean and smooth with all details well defined and true to pattern. Steel castings shall conform to ASTM A27, Grade 65-35. Gray iron castings shall conform to ASTM A126, Class A.

All mast arms shall be compatible with the poles in material, strength, shape, and size.

A. Anchor Base

Secure an anchor base of one-piece cast steel or steel plate of adequate strength, shape, and size to the lower end of the shaft. Place the base so as to telescope the shaft, and weld at the top and bottom faces with continuous fillet welds so that the welded connection develops the full strength of the adjacent shaft section to resist bending action. Provide each base with a minimum of four holes to receive the anchor bolts. Provide cast steel bases with removable cast iron covers for anchor bolts and tapped holes for attaching covers with hex head cap screws.

Provide a welded frame handhole, 5 x 8 inches minimum and located with a clear distance above the base of no less than the pole diameter, "D." Weld a 1/2-inch 13 UNC grounding nut to the inside of the pole at a point readily accessible for wiring.

B. Shaft

Fabricate shafts from the best, hot-rolled basic open hearth steel. The shaft shall have only one longitudinal electrically welded joint and may have electrically welded intermediate transverse full penetration circumferential joints, at intervals of not less than 10 feet. The shaft shall be longitudinally cold-rolled to flatten the weld and increase the physical characteristics so that the metal will have a minimum yield strength of 48,000 pounds per square inch. Where transverse full penetration circumferential welds are used, the shaft fabricator shall furnish to the Engineer certification that: (1) all such welds have been radiographed and ultrasonically tested by an independent testing laboratory using a qualified Nondestructive Testing (NDT) technician and (2) the NDT equipment has been calibrated annually.

Fit the shaft with a removable pole cap, a J-hook wire support welded inside near the top, and a flange plate assembly to match that welded to the butt end of the mast arm.

C. Mast Arms

Provide mast arms fabricated and certified in the same manner as the upright shafts and that have the same physical characteristics.

The mast arms shall meet the design requirements necessary to support rigidly mounted traffic signals as shown on the Plans. All arms shall include a removable cap at the tip, grommeted wire outlets, and signal hanger assemblies of the type and number shown on the Plans, and a flange plate welded to the butt end to provide a rigid connection to the mast. The assembly shall be constructed so that all wiring can be concealed internally.

Connect mast arms to the upright pole at a height necessary to provide a minimum clearance of 16 feet 6 inches and a maximum clearance of 19 feet under the traffic signal heads. Install separate signal heads to provide the same clearance.

D. Finish

Galvanize steel poles, mast arms, and hardware in accordance with ASTM A123.

Galvanize all steel and cast iron components, hardware, and threaded fasteners, except anchor bolts, after fabrication in accordance with ASTM A123, or A153 or A385, as applicable.

730.33 Steel Strain Poles

Provide steel strain poles consisting of a uniformly tapered or equivalent upright shaft fitted with a removable pole top, J-hook wire support and 45-degree wire inlet near the top, a span wire clamp, a 5 x 8 inch handhole with reinforced frame and cover, bent anchor bolts, and all other accessories needed to make a complete installation. The pole and all of its component parts shall be designed to support tethered traffic signals of the type and number shown on the Plans, suspended from a span wire assembly. Fabricate and certify the poles as specified for the upright shafts in **730.32**.

730.34

Determine the shaft length required to meet field conditions and vertical clearances of signal heads over the roadway. The signal head clearance shall be a minimum of 16 feet 6 inches and a maximum of 19 feet. Fasten the span wire no closer than 1 foot 6 inches from the top of the pole.

Unless otherwise specified, provide all strain pole traffic signal supports with a one-piece anchor type base, fabricated from drop forged or cast steel of sufficient cross-section to fully develop the ultimate strength of the poles. Fasten the base to the pole with a welded connection that develops the full strength of the pole. Provide the base with a minimum of four holes of sufficient size to accommodate the proper size anchor bolts that are capable of resisting at yield strength stress, the bending moment of the shaft at its yield strength stress. Provide removable cast iron covers for the anchor bolts.

The shaft shall be fabricated from material providing a minimum yield strength of 48,000 pounds per square inch after fabrication.

Galvanize the steel poles and hardware in accordance with ASTM A123.

Galvanize all steel and cast iron components, hardware, and threaded fasteners, except anchor bolts, after fabrication in accordance with ASTM A123, A153, or A385, as applicable.

730.34 Pedestal Support Signal Poles

Provide pedestal poles consisting of one upright pole with suitable base and other accessories or hardware as required to make a complete installation.

All poles shall be made of one continuous piece from top of base connection for the entire height of the pole. The cross-section shall be either cylindrical or octagonal and may or may not be uniformly tapered from butt to tip.

The cross-section at the tip shall have a 4-1/2 inch outside diameter.

A. Type "A" Pedestal (Aluminum)

Pedestals shall be of uniform octagonal or cylindrical cross-section of the tubular tapered type fabricated of one full length sheet.

Bases shall be octagonal or square in shape, of the ornamental type fabricated of cast material. Provide a handhole in each base.

Caps shall be of the nipple or tenon type mounting fabricated of cast material.

Furnish bases with four steel anchor bolts of sufficient size and length to securely anchor the base to the concrete footing. Weld the shaft to the cast metal base. Refer to the AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals (current edition).

Type A pedestal shaft shall be fabricated from aluminum tubing 6063-T4 heat treated to T-6 temper after fabrication, and meeting ASTM B221.

Type A anchor base shall be made of sand-cast aluminum alloy 356-T6 meeting ASTM B26 - SF 70A-T5 specifications.

B. Type "B" Pedestal (Steel)

Pedestals shall be fabricated from a 4-1/2 inch (outside diameter) seamless steel pipe.

Bases shall be octagonal in shape of the ornamental type fabricated of cast or malleable iron and shall have minimum height of 12 inches. The top opening of the base shall be threaded to receive the shaft. Provide a handhole in each base.

Furnish bases with four steel anchor bolts of sufficient length to securely anchor the base to the concrete footing.

730.35 Wooden Pole Signal Supports

A. General

Provide wooden poles of the class and length shown on the Plans and that meet **917.11**. Set poles to the depth shown on the Plans, and fit them with all the necessary hardware to make the installation complete.

The signal head clearance shall be 16 feet 6 inches minimum and 19 feet maximum. Fasten the span wire at least 2 feet below the top of the pole.

730.36

B. Guying Components

Guy clamps shall be steel, 3-bolt type, 6 inches in length, and of the proper strand size to fit the wire used. The clamp bolts shall have upset shoulders fitting into the clamp plate. Substitution of the cable grip is subject to the Engineer's approval.

Attach guy wire to the pole with a 5/8-inch diameter x 12-inch length single strand angle-type eye bolt with 2 x 2 inch square cut washers, lock washer, and square nut.

Instead of the eye bolt specified above, an angle single strand eye of drop forged steel may be used, fastened on threaded end of span wire eye bolt.

Sidewalk guy fittings shall consist of 2-inch inside diameter standard galvanized steel pipe of required length with malleable iron pole plate and guy clamp. Fasten the pole plate to the pole with a 3/8-inch thru bolt and 1/2-inch lag screws.

All guying components and hardware shall be galvanized in accordance with ASTM A123 or A153.

Anchors for guys shall be of the pressed steel four-way expanding fluke type or of the steel or malleable iron sliding plate type. The minimum unexpanded diameter shall be 8 inches, and the minimum expanded area shall be 110 square feet. Coat anchors with a black asphaltic paint.

Guy anchor rods shall be drop-forged steel, 3/4-inch diameter and 7-foot minimum length, threaded, of the single thimble eye type, with a square anchor bolt nut.

730.36 Pole Location

Install all signal support poles at the locations shown on the Plans or where directed by the Engineer.

COMPENSATION

730.37 Method of Measurement

Measurement for traffic signals will be on a per item basis for each item to be furnished and installed, as specified herein and shown on the Plans.

With regard to items for signal head assemblies, each item to be furnished, installed, or both furnished and installed shall be distinguished with a code number as follows:

1. The first digit is the number of faces per assembly.
2. The second digit will indicate the number of 12-inch lenses per assembly (including arrow lenses).
3. The third digit is the quantity of 8-inch lenses per assembly.
4. The letter "A" indicates an arrow lens and the digit following the "A" indicates the number of 12-inch arrow lenses per assembly.
5. The letter "H" or "V" indicates the arrangement of arrow signal lenses to be horizontal or vertical with respect to solid ball indications.

EXAMPLE:

1 5 0 A 2 H

Digits indicate the following:

1 = one face
 5 = five 12-inch lenses
 0 = zero 8-inch lenses
 A2 = two 12-inch arrow lenses
 H = Arrow lenses placed horizontally with respect to circular indications

A. Removal of Signal Equipment

The Department will measure items of equipment or material designated or required for removal on a per each intersection basis. Removal and salvage of all signal heads, poles, control equipment, cabinets, span wire, cable, and similar features to be performed at an intersection shall be included as a unit cost per each intersection. This includes the cost of stockpiling salvable equipment for pick-up by the appropriate agency, as noted in the Plans.

730.37

B. Signal Head Assembly (includes Pedestrian Signal Heads)

The Department will measure signal heads of the type shown on the Plans by the individual assembly complete in place, per each. This item shall include the signal heads, terminals, lamps, attachment hardware, cable connection, and testing.

C. Pull Box

The Department will measure each pull box of the type required as one complete unit, installed, per each. This item includes the pull box, excavation, backfilling, crushed stone base, and other incidental items as called for in the Plans or Standard Drawings.

D. Electrical Service Connection

The Department will measure Electrical Service Connections on a per each signal installation basis. This item includes the electrical service supplied to the weatherhead by the local utility, all necessary materials and labor for connection of the electrical service from the controller to the weatherhead, the wiring of the controller and detectors, and all incidentals necessary to render a complete and operable system.

E. Signal Cable

The Department will measure the length of Signal Cable of each size (number of conductors) installed in linear feet to the nearest foot from point to point along the routing for each cable.

The Department will make horizontal measurements by center to center measurement from:

1. Pole to pole
2. Pole to signal head (when terminating in a signal head)
3. Pull box to pull box
4. Pull box to pole
5. Pull box to pole-mounted or base-mounted controller

For cable inside mastarms, the Department will measure from center of vertical support to signal head where cable terminates.

The Department will make vertical measurement by one of the following:

1. For cable inside poles or conduit risers, the distance from ground level to the point of attachment of the span wire.
2. For cable inside mast arm supports, the distance from ground level to the mast arm connection.
3. For cable to pole-mounted controller,
 - a. From ground level to bottom of controller.
 - b. From bottom of controller to point of attachment of span wire.
4. For cable to pole-mounted signal head or pushbutton,
 - a. From ground level to bottom of signal head or pushbutton
 - b. From bottom of signal head or pushbutton to point of attachment of span wire.

The Department will make no additional allowance for slack length, length inside equipment or supports (except as noted), length for the required 360-degree drip loop, and similar instances requiring additional length of cable.

F. Span Wire

The Department will measure Span Wire Assembly, Tether Wire Assembly, and Messenger Cable by type in linear feet to the nearest foot. The measurement will be made from center to center of poles. These items include attachment hardware, strain insulators, and other hardware shown in the Plans as part of the assembly. The Department will make no additional allowance for slack length and other instances requiring additional length of wire.

G. Steel Conduit Riser Assembly

The Department will measure conduit riser assemblies per each for each size conduit riser installed on the outside of a pole, as shown on the Plans. This item includes conduit, weatherhead, conduit, fittings, nuts, washers, banding, clamps, grounding, and other items necessary for installation.

730.37

H. Conduit

The Department will measure conduit in linear feet to the nearest foot for each size and type of conduit installed.

The Department will measure underground conduit along the conduit by one of the following:

1. From the face of curb to the center of a pull box, pole or controller foundation,
2. From center to center of pull boxes,
3. From center to center of a pull box and a pole or controller foundation, or
4. From center to center of pole foundations or pole foundation and controller foundation.

The Department will add:

1. 1 foot to the above measurements for each entry to a pull box or pole foundation and each exit of a pull box or pole foundation.
2. 3 feet to the measurement for each capped extra entry (conduit stub) or exit to a pull box or pole foundation installed, as shown on the Plans.
3. 3 feet to the measurement for each connection between underground conduit and above ground riser.
4. 3 feet to the measurement for each entry or exit to a foundation for a base-mounted controller.

This item includes trenching, backfilling, sealing, capping, fittings, bushings, banding, grounding, and other accessories and hardware required for installation of the conduit system.

I. Vehicle Loop Detector (Amplifier)

The Department will measure vehicle detector loop amplifier per each unit, including the cable and associated hardware necessary to electrically connect the amplifier to the controller and loop lead in.

The Department will measure two and four channel card rack type amplifiers per each unit, including the cable, card rack(s), and associated hardware necessary to electrically connect the amplifiers to the controller and loop lead-ins.

J. Shielded Detector Cable

The Department will measure the two-conductor shielded detector cable installed between the controller cabinet and the loop detector wires in linear feet to the nearest foot.

The Department will make horizontal measurements (overhead and underground) by one of the following:

1. From center to center of pull boxes,
2. From center to center of pull box and pole,
3. From center to center of poles, or
4. From center to center of pull box or pole and controller foundation.

The Department will make vertical measurements by one of the following:

1. From ground level to the point of attachment of span wire, inside pole or conduit riser,
2. From the bottom of controller cabinet to the point of attachment of span wire, or
3. From ground level to the bottom of controller.

The Department will make no additional allowance for slack length, length inside equipment or supports (except as noted), splices, and similar instances requiring additional length of cable.

730.37

K. Saw Slot

The Department will measure the length of saw slot for installation of detection loop and lead wiring in linear feet to the nearest foot. Measurement for detection loops in the traffic lanes will be made based on the loop size shown on the Plans (the nominal length plus the nominal width) times 2. The Department will make no additional allowance for saw overruns to obtain full depth of saw slot or diagonal cuts to prevent sharp bends in the loop wire. The Department will measure saw slot for detection loop leads from the conduit entry at the face of curb or edge of pavement and along the route of the lead-in to the detection loop.

This item includes backing rods, or polyethylene foam sealant, loop sealant, and all other incidentals necessary to render a complete and operable system.

L. Loop Wire

The Department will measure the length of loop wire for installation of detection loops and lead-ins in linear feet to the nearest foot. Measurement will be made from the pull box or pole to the detection loop, around the loop the required number of turns and back to the pull box, pole, or point of splice. The Department will make no additional allowance for slack length, length inside equipment or supports, splices, and similar instances requiring additional length of wire.

This item includes electrical connections, testing, and all other incidentals necessary to render a complete and operable system.

M. Controller

The Department will measure controllers as one complete unit, installed, per each. This item includes all auxiliary equipment shown the Plans to provide signalization control as shown on the Plans, and all hardware, including the cabinet (and cabinet foundation, if base-mounted), necessary for installation.

N. Wood Pole

The Department will measure Wood Poles, of the type and size shown on the Plans, per each, installed.

O. Guying Device

The Department will measure Guying Devices, of the type shown on the Plans, per each, installed. This item includes the guy wire, anchor, clamps, and all other components shown on the Plans necessary for installation.

P. Steel Strain Pole

The Department will measure Steel Strain Poles of the type and size shown on the Plans, per each, installed. This item includes the pole, foundation, anchor bolts, grounding, and all other hardware shown on the Plans necessary for a complete installation.

Q. Cantilever Signal Support

The Department will measure Cantilever Signal Supports, of the type and size shown on the Plans, per each, installed. This item includes the vertical pole shaft, mast arm, foundation, anchor bolts, grounding, and all other hardware shown on the Plans necessary for a complete installation.

R. Service Cable

The Department will measure two conductor power service cable, of the type and size shown on the Plans, in linear feet to the nearest foot, installed. Horizontal runs will be measured center to center of poles. Vertical runs will be measured from the ground to the weatherhead inside a pole or conduit riser, or from the ground to the bottom of the controller, or from the bottom of the controller to the weatherhead. This item includes all necessary attachment hardware. The Department will make no additional allowance for slack length or other instances requiring additional length of cable.

S. Pedestrian Pushbutton with Sign

The Department will measure Pedestrian Pushbutton with Sign as one complete unit, in place, per each. This item includes the pushbutton, sign, mounting hardware, wiring of pushbutton, testing, and all other incidentals necessary for a complete installation.

730.38

T. Pedestrian Signal Display with Pushbutton and Sign

The Department will measure Pedestrian Signal Display with Pushbutton and Sign as one complete unit, in place, per each. This item includes the signal heads, terminals, lamps, cable connections, pushbutton, sign, all attachment hardware, testing, and other incidentals necessary for a complete installation.

U. Portable Traffic Signal

The Department will measure Portable Traffic Signal, of the type shown on the Plans or as directed by the Engineer, per each, installed. This item includes the all the software and hardware necessary for a complete installation.

730.38 Basis of Payment

The Department will pay for accepted quantities, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Traffic Signal	Lump Sum
Removal of Signal Equipment	Each
Signal Head Assembly (Description)	Each
Install Pull Box (Description)	Each
Electrical Service Connection	Each
Signal Cable – (Description)	Linear Feet
Span Wire Assembly (___ pounds min. break strength)	Linear Feet
Tether Wire Assembly – ___" Diameter	Linear Feet
Messenger Cable – ___" Diameter	Linear Feet
Riser Assembly (Description)	Each
Conduit ___" Diameter (Type)	Linear Feet
Vehicle Detector (Description)	Each
Shielded Detector Cable	Linear Feet
Saw Slot	Linear Feet
Loop Wire	Linear Feet
Controller (Description)	Each
Wood Pole (Description)	Each
Guying Device (Description)	Each
Steel Strain Pole (Description)	Each
Cantilever Signal Support (Description)	Each
Service Cable	Linear Feet
Pedestrian Pushbutton with Sign	Each

730.38

Pedestrian Signal Display with Pushbutton and Sign	Each
Portable Traffic Signal (Type)	Each

The unit price to be paid includes the cost of furnishing and installing, complete in place, each of the various types of equipment required by the Summary of Quantities shown on the Plans. Total payment is full compensation for all materials, labor, equipment, and incidentals necessary to produce a completely operative and finished installation of a traffic signal or traffic signal system as shown on the Plans and as specified herein, including restoration of pavements, sidewalks, and appurtenances damaged or destroyed during construction and tests. All additional materials and labor not specifically shown or called for, which are necessary to complete the traffic signal installation or traffic signal system described, will be considered incidental to the system and no additional allowance will be made.

740.01

SECTION 740 – GEOSYNTHETICS

740.01 Description	866
740.02 Materials	866
740.03 General	866
740.04 Method of Measurement	867
740.05 Basis of Payment.....	867

DESCRIPTION

740.01 Description

This work consists of placing geosynthetics in accordance with these Specifications and the Standard Drawings.

MATERIALS

740.02 Materials

Provide materials meeting the requirements of **921.12** for the type of geosynthetic shown on the Plans.

Furnish a certified laboratory test report from an approved testing laboratory with each shipment of materials. Laboratory test reports shall include the actual numerical test data obtained. Clearly label all rolls as being part of the same production run from which the test data was derived. Protect rolls to prevent damage during transportation, storage, and installation. Cover geosynthetic rolls during storage to protect against UV degradation, and store rolls elevated up off of the ground. Do not install material that is torn, punctured, or otherwise damaged.

CONSTRUCTION REQUIREMENTS

740.03 General

Place geosynthetics as shown on the Plans for the specific application. Compact the surface on which the geosynthetic is to be placed, as directed by the Engineer. Prepare the surface to be as smooth as possible and free from debris, obstructions, and depressions that could result in gaps, tears, or

punctures in the fabric during cover operations. Install the geosynthetic so that placement of cover material will not excessively stretch or tear the geosynthetic. After the geosynthetic is placed, install the initial lift of cover material within five calendar days. Do not operate equipment directly on the geosynthetic. Place cover material so that at least the minimum initial lift thickness, as specified by the Engineer, is between the geosynthetic and equipment tires or tracks at all times. Do not turn equipment and vehicles on the first lift above the geosynthetic.

Repair or replace, as directed by the Engineer and at no cost to the Department, materials that are damaged during or after placement.

COMPENSATION

740.04 Method of Measurement

The Department will measure geosynthetics of the type specified by the square yards, complete in place. No measurement for payment will be made for overlaps, splices, or sewn joints.

740.05 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Geomembrane	Square Yard
Geogrid Reinforcement	Square Yard
Cellular Confinement System (Description)	Square Yard
Geotextile (Type __) (Description)	Square Yard
Geotextile Tube	Linear Feet
Temporary Sediment Tube __" (Description)	Linear Feet

Such payment is full compensation for all labor, equipment, materials, tools, and incidentals necessary to complete the work.

Part 8

PART 8 – ROADSIDE DEVELOPMENT

SECTION 801 – SEEDING.....	869
SECTION 802 – LANDSCAPE PLANTING.....	876
SECTION 803 – SODDING.....	887
SECTION 805 – EROSION CONTROL BLANKETS	893
SECTION 806 – ROADSIDE MAINTENANCE.....	896

SECTION 801 – SEEDING

801.01 Description.....	869
801.02 Materials	869
801.03 Reserved.....	870
801.04 General.....	870
801.05 Preparing the Seedbed.....	870
801.06 Seeding.....	871
801.07 Mulching.....	871
801.08 Care During Construction	872
801.09 Method of Measurement	872
801.10 Basis of Payment.....	874

DESCRIPTION

801.01 Description

This work consists of furnishing and placing seed, commercial fertilizer, agricultural limestone, and mulch material on all newly graded earthen areas that are not to be paved, stabilized, or sodded.

MATERIALS

801.02 Materials

Provide materials as specified in:

Water	802.02.B.5
Mulch Binder: Emulsified Asphalt, Type SS-1 or AE-3	904.03
Grass Seed	918.01
Commercial Fertilizer	918.02
Agricultural Limestone	918.04
Mulch Material	918.05
Inoculant for Legumes	918.06
Liquid Lime	QPL

801.03

801.03 Reserved

CONSTRUCTION REQUIREMENTS

801.04 General

Perform seeding work as specified in **209**.

At the start of permanent seeding operations, prepare, shape, and dress the area to be seeded as specified in **203.08** and **801.05**. Unless otherwise directed by the Engineer, do not sow the seed until after placing the topsoil as specified in **203.06**. Use topsoil with all permanent seeding activities except where its use would be detrimental to effective erosion and siltation control, as determined by the Engineer.

The Contractor may perform Temporary Seeding (with Mulch) or Temporary Seeding (without Mulch) without full preparation of the seedbed as specified in **801.05**, where approved by the Engineer, and application of permanent erosion and siltation control measures is not practicable.

Perform all seeding and related operations as continuous operations.

A unit in relation to seeding area is 1,000 square feet. For purposes of measuring water, a unit is 1 M.G., which equals 1,000 gallons.

801.05 Preparing the Seedbed

When the soil is in a tillable and workable condition, prepare the seedbed in the following manner and sequence:

1. Scarify, disc, harrow, rake, or otherwise work each area to be seeded until it has been loosened and pulverized to a depth as directed by the Engineer.
2. Incorporate fertilizer, at the rate of not less than 20 pounds of Grade 10-10-10, or equivalent, per unit (1,000 square feet), and agricultural limestone, at the rate of not less than 100 pounds per unit, uniformly into the soil for a depth of approximately 1/2 inch.
3. If the soil pH is below 5.5, in addition to the required agricultural lime, apply liquid lime selected from the Department's QPL at a rate of 7.5 gallons per acre (22 ounces per 1,000 square feet).

Incorporating fertilizer into the soil as specified above is not necessary when mixed with seed in water and applied with power sprayer equipment.

801.06 Seeding

The specific seed group will be shown on the Plans or as directed by the Engineer from those specified in **918.01**.

Sow the seed immediately after preparing the seedbed as specified in **801.05**. Sow the seed uniformly using a rotary seeder, hydraulic equipment, or other satisfactory means, at the rate specified in Table 801.06-1, unless otherwise specified or directed.

Table 801.06-1: Seed Application Rates

Seed Group	Application Rate, Pounds per Unit (1,000 square feet)
A, B, and C	2.5
B1	0.6
All other groups specified in 918.01	1.5

Before sowing, inoculate Group C seed and seeds of legumes, when sown alone, in accordance with the recommendations of the inoculant manufacturer and as directed by the Engineer.

Do not perform any seeding during windy weather or when the ground surface is frozen, wet, or otherwise non-tillable. Do not perform seeding during December and January unless otherwise allowed.

801.07 Mulching

When seeding with mulch is specified, use hay, straw, or other approved mulch materials.

When using hay or straw as the mulching material, spread it evenly over the seeded area, immediately following the seeding operations, at an approximate rate of 100 pounds per unit for straw and 150 pounds per unit for hay. The Engineer may vary this rate, depending on the texture and condition of the mulch material and the characteristics of the area seeded.

801.08

To hold hay or straw mulch in place, apply an approved tackifier, listed on the QPL, as recommended by the manufacturer.

When using wood fiber mulching material, apply it at a rate of 28 to 35 pounds per unit, using hydraulic mulching equipment. Spray the material uniformly on the surface of the prepared seedbed. Adjust the application rate as directed by the Engineer.

801.08 Care During Construction

Maintain all seeded areas to the Engineer's satisfaction until acceptance of the Work.

Repair, as directed by the Engineer, all areas previously seeded and mulched in accordance with this Section but that incurred damage or failed to successfully establish an acceptable stand of grasses or legumes. Furnish all material and labor required to repair seeded areas damaged due to Contractor negligence at no cost to the Department. The Department will measure and pay for repairs made to seeded areas, except temporary seeding, required through no fault of the Contractor, in accordance with **801.09** and **801.10**. If the Engineer directs the Contractor to place additional fertilizer on the area to be reseeded, apply additional liquid lime at a rate of 5 gallons per acre (15 ounces per 1,000 square feet) if the pH of the soil is below 5.5.

After an acceptable stand of grass has been attained, top-dress seeded areas with not less than 10 pounds of fertilizer of Grade 10-10-10, or equivalent, per unit at approximately 6-month intervals, unless otherwise specified or directed.

COMPENSATION

801.09 Method of Measurement

A. Seeding

The Department will measure the seeded area for payment by the number of units seeded in accordance with these Specifications and accepted by the Engineer. Each unit shall consist of 1,000 square feet measured along the surface.

B. Mulch

The Department will measure mulch for payment complete and in place, including tackifiers used to hold the mulch in place.

C. Water

The Department will measure water necessary for seedbed preparation and maintenance by the M.G. (1,000 gallons) using calibrated tanks or distributors, or accurate water meters.

The Department will not measure water used in applying seed, fertilizer, and mulch binder.

D. Repairs of Seeded Areas

The Department will measure supplemental items used to repair seeded areas on which a satisfactory stand of grasses or legumes has not been obtained due to causes not attributable to Contractor negligence as provided below. These items will only be used when the reseeding is confined to small areas that would not restrict the Contractor's operation. If the areas to be reseeded are of substantial size, thereby accommodating the Contractor's normal operation, the Contractor shall perform the work in accordance with these Specifications, and the Department will pay for such work under the applicable original seeding item.

1. The Department will not pay for seedbed repair directly but will consider the cost thereof as included in the unit price bid for Seed (Supplemental Application). If additional materials are required to repair the seedbed, the Department will make payment under the appropriate item or items in **203**.
2. The quantity of seed measured for payment to repair seeded areas will be the actual number of pounds of seed used, as determined by bag count of standard weight bags or by weighing the seed on approved scales.
3. The quantity of fertilizer measured for payment will be the actual number of tons of dry fertilizer used as determined by bag count of standard weight bags or by weighing the fertilizer on approved scales. If liquid fertilizer is used, the weight will be converted to its equivalent dry weight in tons.

801.10

E. Fertilizer

The Department will measure fertilizer applied, as specified or directed, to areas with an acceptable stand of grass as specified in **801.09.D.3**.

F. Lime

The Department will measure lime for payment complete and in place by the ton.

The Department will make no direct measurement or payment for agricultural limestone or liquid lime used in repairing seeding areas, but will consider the cost to be included in the unit price bid for Fertilizer.

801.10 Basis of Payment

The Department will pay for accepted quantities, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Seeding (with Mulch)	Unit
Crown Vetch Mixture (with Mulch)	Unit
Temporary Seeding (with Mulch)	Unit
Seeding (without Mulch)	Unit
Crown Vetch Mixture (without Mulch)	Unit
Temporary Seeding (without Mulch)	Unit
Mulch	Unit
Seed (Supplemental Application)	Pound
Fertilizer (Supplemental Application)	Ton

Payment for Seeding, Crown Vetch Mixture, and Temporary Seeding is full compensation for preparing the seed bed, furnishing and placing all materials, including fertilizer, agricultural limestone, seed, mulch materials and mulch binder where mulch is used, and inoculant, if specified.

When the Contract does not provide for a unit bid price for Seeding (without Mulch) and this item is used for temporary or permanent erosion control, the Department will make payment at a rate per unit equal to 0.45 times the unit price bid for Seeding (with Mulch). In addition, if the Contract does not provide a unit bid price for mulch and mulch alone is required, the Department will make payment at a rate per unit equal 0.60 times the unit price bid for Seeding (with Mulch).

801.10

The Department will pay for Water used to prepare the seed bed and for maintenance at the contract unit price per M.G. (1,000 gallons) of water, which payment is full compensation for furnishing and applying the water as specified.

Payment for Seed (Supplemental Application) is full compensation for minor seedbed repair, mulch materials and mulch binder, and inoculant, if specified.

Payment for Fertilizer (Supplemental Application) and fertilizer applied after an acceptable stand of grass has been attained is full compensation for furnishing and applying fertilizer and, where required, liquid lime.

802.01

SECTION 802 – LANDSCAPE PLANTING

802.01	Description	876
802.02	Materials	876
802.03	Reserved.....	880
802.04	Time and Condition of Planting	880
802.05	Staking	880
802.06	Tree Planting.....	880
802.07	Wrapping and Pruning of Trees	881
802.08	Shrub Planting.....	882
802.09	Seedling Planting	882
802.10	Ground Cover Planting	883
802.11	Temporary Storage and Heeling-In.....	883
802.12	Mulching	883
802.13	Final Cleanup	883
802.14	Period of Establishment	884
802.15	Inspection and Replacement of Plants.....	884
802.16	Method of Measurement	885
802.17	Basis of Payment.....	886

DESCRIPTION

802.01 Description

This work consists of furnishing and planting trees, shrubs, seedlings, and ground cover of the kinds and at the locations shown on the Plans or where directed by the Engineer.

MATERIALS

802.02 Materials

A. Planting Material Standards

Before performing any work, furnish proof of having secured a nursery dealer's certificate for each shipment of plants. The certificate shall

indicate the number of plants of each species in the shipment and the project number for which the plants are intended. The certificate shall also include a certification that the plant materials conform to the requirements of the Plans and these Specifications, and that all local, State, and Federal laws pertaining to the inspection, sales, and shipment of plant materials have been complied with.

Consider “collected plant material” to mean plants that are not nursery grown. Do not use collected plant material unless shown on the Plans. Dig collected plant material called for on the Plans with a ball of earth having a minimum diameter at least 25% greater than that specified for nursery grown stock and wrap in burlap. Handle plants to keep their roots protected at all times. During delivery, ensure that the entire load remains suitably covered. Coverings shall not be so tight as to cause heating.

1. Names and Grades. Plant material shall conform to the nomenclature of *Standardized Plant Names*, as adopted by the Joint Committee of Horticulture Nomenclature, latest revision. Size and grading standards shall conform to the latest approved revision of the *American Standard for Nursery Stocks*, Z60.1, published by the American Nursery and Landscape Association. Make no substitutions of size or grade without the Engineer’s written permission. Properly identify each bundle of plants and all separate plants with legible, waterproof tags securely fastened to each plant or bundle of plants.

Ship plants as follows:

- a. Seedlings in bundles of 100.
- b. Bare Root in bundles of 10.
- c. Ball and Burlap individually.

2. Health. Provide plants conforming to the following health requirements:

- a. All plants, including their roots, shall be free of disease, insects, or other injurious qualities.
- b. The trunk bark of all trees shall be sound, trees shall have no large wounds, and small wounds shall have a satisfactory callus roll formed or forming over them.

802.02

- c. Plants shall show good annual growth.
- d. Buds shall be plump and well filled for the species.
- e. Evergreen foliage shall be of good intense color.

3. Quality. All plants shall:

- a. Be true to type;
- b. Have normal, well developed branch systems, and a vigorous fibrous root system;
- c. Be sound, healthy, vigorous plants free from defects, disfiguring knots, sunscald injuries, abrasions of the bark, plant diseases, insect eggs, borers, and all forms of infestation; and
- d. Have been growing in the same climatic conditions as the location of the Project for at least 2 years prior to the date of the Contract.

4. Ball and Burlap/Wire Basket. All balled and burlapped plants shall conform to the *American Standard for Nursery Stock, Z60.1*, latest approved revision. All balls shall be of natural earth in which the plant had been growing. Manufactured or artificially produced or mudded-in balls are not acceptable. Ensure that balls are firm and unbroken. The Engineer may reject balled and burlapped plants if they fail to meet good digging and handling practices.

5. Container Grown Plants. In addition to the requirements of the *American National Standard for Nursery Stock, Z60.1*, container grown plants shall conform to the following:

- 1. The space between the rim or top of the container and the soil line within the container shall not be more than 1-1/2 inches for the 1-gallon and 2-gallon sizes and not more than 2-1/2 inches for the 5-gallon size.
- 2. Encircling roots shall not have grown in such a manner that they will cause girdling of the trunk or stems. If encircling roots do exist, they shall be cut.

3. Roots shall not protrude through drainage holes or over the rim of the container to the extent that they will be damaged while removing the root ball from the container.
4. Plants shall have been acclimated to outside conditions. Container grown plants may be used provided the Engineer approves of their use in writing.

B. Miscellaneous Planting Materials

Obtain the Engineer's approval of the following materials before incorporating them in the work:

1. **Topsoil.** Provide a natural, friable, fertile, fine sandy loam possessing the characteristics of representative topsoils in the vicinity that produce heavy growths of vegetation. The topsoil shall be free from subsoil, noxious weeds, stones larger than 1 inch in diameter, lime, cement, ashes, slag, and other deleterious matter. Topsoil shall be well drained in its original position and free from toxic quantities of acid or alkaline elements.
2. **Mulch.** Unless otherwise specified, provide a standard, commercial quality of aged hardwood bark mulch with a particle size of less than 3 inches and a contamination rate less than 0.5% by volume.
3. **Fertilizer.** Unless otherwise shown on the Plans, do not fertilize trees.
4. **Tree Wrappings.** Avoid using tree wrappings for any purpose other than providing protection during transport.
5. **Water.** For planting work, use water that is free from harmful or objectionable qualities or organisms.
6. **Stakes for Bracing and Anchoring.** Stakes used for guying trees shall be at least 6 feet long, of sound, sturdy material, reasonably capable of withstanding aboveground and underground conditions. Their top and bottom face dimensions shall be at least 2 x 2 inches, a minimum diameter of 2-3/4 inches, or a substitute approved by the Engineer.
7. **Hose.** For staking, use a new fabric-bearing rubber hose with an inside diameter of not less than 1/2 inch.

802.03

8. **Straps.** For staking, use straps consisting of flat, canvas belting with grommets.

802.03 Reserved

CONSTRUCTION REQUIREMENTS

802.04 Time and Condition of Planting

Unless otherwise specified, perform all planting after the growing season, between the dates of November 1 and April 1.

802.05 Staking

The Engineer, or the Contractor when specified, will stake all plant and bed locations in accordance with the plant list and approximate locations shown on the Plans.

Perform the planting at the approved locations. After planting is complete, outline the ground cover areas and seedling areas with painted stakes and twine as directed by the Engineer.

802.06 Tree Planting

A. Planting Pits

Form circular planting pits with vertical sides. Make the diameter of the pits at least 2 feet greater than the diameter of the ball of the tree. The depth of the pit shall be sufficient to accommodate the ball or roots of the tree when the tree is set to the finished grade, allowing for a maximum of 1 inch of tamped spoil below the roots of the plant.

B. Backfill

Backfill for tree planting shall consist of spoil material removed from the hole if suitable. If not, this material may be blended with 50% topsoil. Soil amendments are not recommended.

C. Setting of Trees

Place all plants at a level so that, after settlement, the natural relationship between the original grade at which the plant grew and the present one

shall be the same. The root flare should be level with the soil grade surrounding the tree. Plant trees plumb and orient them for desired effect as directed by the Engineer. Tamp spoil material from the hole around the base of each ball to fill all voids. Place material in 6 to 8-inch thick layers, thoroughly tamping each layer to prevent air pockets.

Cut back burlap and wire baskets and remove a minimum of one-third of the depth of the root ball. Remove all string from the root ball and around the trunk. When planting bare root trees, carefully work soil around the roots and spread them in a natural position before backfilling. Form, around all trees, shallow basins or saucers, which are slightly larger than the diameter of the ball, to hold additional water.

Thoroughly water all plants immediately after planting, fully saturating the backfill in the pits and beds during the same day of planting. Perform planting and watering as one continuous operation. If applying water by hose, use an open end hose at very low pressure to avoid air pockets and injury to the roots.

D. Guying and Staking

Only stake trees when necessary to keep them vertical on a slope or in an area with strong winds. Never stake trees less than 6 feet tall or under 1 inch caliper. When staking is necessary, use biodegradable underground staking, or soft straps or flexible hose without wire. Ensure that staking allows for free movement of the tree trunk.

802.07 Wrapping and Pruning of Trees

A. Wrapping

Wrap tree trunks for transport, and then completely remove all wrapping bandage and string at the time of planting.

B. Pruning

Except for branches damaged during digging and transport, do not prune trees at the time of planting unless otherwise directed.

Do not use tree paint on cuts.

802.08

802.08 Shrub Planting

A. Planting Beds and Pits

Prepare planting beds to a depth of 4 to 6 inches, or as directed by the Engineer. Make plant pits 6 inches deeper and 6 inches greater on all sides than the plant balls.

B. Prepared Topsoil

Backfill for shrub planting shall consist of “prepared topsoil” as specified in **802.06.B**.

C. Setting of Shrubs

Set shrubs as specified in **802.06.C**.

D. Pruning of Shrubs

Except for removing broken or badly bruised branches with a clean cut, do not prune trees at the time of planting unless otherwise directed.

Do not use tree paint on cuts.

802.09 Seedling Planting

This Specification is intended to produce natural appearing wooded areas similar to others in the vicinity. To achieve this effect, mix and plant seedlings specified for a given area as shown on the Plans.

Dig holes to receive these plants of sufficient size and depth to place the roots in a normal position and to allow the plant to be set slightly below grade, leaving a depression to receive and hold water.

After planting the seedlings, provide a thorough watering on the same day. Perform planting and watering as a continuous operation.

After completing the planting, ensure that each plant is solidly in the ground and thoroughly wetted.

802.10 Ground Cover Planting

Ground cover planting shall consist of an overplanting of existing grasses or other growing material. Dig holes to receive these plants of sufficient size and depth to accommodate the roots and to allow the plant to be set slightly below grade, leaving a slight depression to receive and hold water. Place 2 inches of topsoil under the plant and around the roots. Carefully remove containers, except those of organic material, from pot-grown plants to avoid damaging the soil ball.

Perform planting and watering as a continuous operation, thoroughly watering on the same day as planting. This may be done by mechanical means if adequate equipment is available. When watering is complete, ensure that each plant has been thoroughly wetted and that the plant is solidly in the ground.

802.11 Temporary Storage and Heeling-In

Ship plants directly from the nursery. When temporary storage or heeling-in is required, provide and prepare a suitable heeling ground or heeling-in nursery conveniently located near the planting site before shipping the plant material from the growing nursery or other source. Take care in requesting shipment to avoid long periods of temporary storage.

Immediately heel-in, or transport to the planting site and plant, all plant material delivered to the Project. The Engineer will reject material left out of ground overnight, left with its roots bare to the sun and wind, or otherwise left unprotected during transit, unloading, or storage.

802.12 Mulching

Within 2 days of planting trees and shrubs, apply a 4-inch depth of mulch, entirely covering the saucer of individual tree pits and the entire shrub beds. Ensure that mulch does not touch the tree trunk or the stems of shrubs.

802.13 Final Cleanup

Upon completion of all operations described in these Specifications, remove all refuse, brush, including standing dead and rejected plants, sticks, packaging, potting debris, and similar waste, regardless of whether it was directly connected with the Work or previously left by others. Leave the general area in a neat and orderly condition that meets the Engineer's approval.

802.14

802.14 Period of Establishment

Installation of the plant material shall be regarded as partial completion of the horticultural work. The “period of establishment” will be April 1st through November 1st. The Contractor is responsible for all plantings for one full period of establishment.

Keep all plants and plant material installed in a living, healthy condition up to the date for termination of Contractor responsibility for care specified herein. Unless otherwise specified by the Engineer, perform the following work in a continuous manner during the period of establishment

A. Watering

During periods of low rainfall or drought, water all woody plants at weekly intervals unless otherwise directed by the Engineer. Slowly and gradually apply sufficient quantities of water until the root area of the plants is saturated. One inch of water is customary. Apply sufficient quantities of water slowly and gradually until the root area of the plants is saturated. Carefully adjust both the force and volume of water to ensure that no damage occurs to plants, backfill, and mulching material.

B. Cultivating

When shown on the Plans, keep all planting areas free from grass and weeds throughout the entire growing season. Always keep the area clean, open, and properly mulched, unless covered with plastic and mulched. Closely mow areas such as slope bed plantings.

802.15 Inspection and Replacement of Plants

A. Initial Inspection and Replacement of Plants

The Engineer will initially inspect the plants during and before the end of the planting season (April 1st) and will determine the necessity of replacing dead, degenerated, defective, or missing plants. Remove plants fitting into the above categories and plants that are stagnant, whether technically alive or not, and replace them with the specified plants at no cost to the Department. For each plant replaced, perform all necessary work to establish the plant, regardless of already fulfilled obligations regarding other plant material on the site. Based on the findings of the Engineer’s initial inspection as addressed above, replace all plants that are required to be replaced on or before May 1st.

B. Final Inspection: Replacement and Acceptance of Plants

The Engineer will conduct a final inspection of planting during and before the end of the first full growing season and on or about October 1st, after the first full growing season. The Engineer will determine whether to require the Contractor to replace plants as specified in **802.15.A** or if such replacement would be inadvisable due to seasonal or other conditions.

The Contractor's responsibility for care of all plantings that are acceptable on the date of the final inspection mentioned above shall end on that date.

Based on findings of the inspection mentioned above, replace plants that require replacement with plants of the same species, size, and quality at no cost to the Department. Replace non-viable plants before the 15th of February. Upon completion of the work, the Engineer will inspect the replacement plantings and accept or reject the work. If accepted, the Contractor's responsibility for care of the replacement plantings shall end on the date of the Engineer's inspection.

COMPENSATION**802.16 Method of Measurement**

The Department will measure:

1. Living trees, seedlings, and shrubs for payment by the unit (per each).
2. Ground cover by the square yard, in accordance with **109**.
3. Water required for the plant establishment by the M.G. (1,000 gallons).

The Department will only measure for payment those plants in a living, healthy condition at the time the Contractor's responsibility for care of the plants has ended.

The Department will not measure or make payment for water used in plant installation work.

802.17

802.17 Basis of Payment

The Department will pay for accepted quantities, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Trees (Description)	Each
Seedlings (Description)	Each
Cuttings (Description)	Each
Shrubs (Description)	Each
Ground Cover (Description)	Square Yard
Water (Plant Establishment)	M.G. (1,000 gallons)

In making partial payments for planting items, the Department will consider:

1. Approximately one-third of the Contract price to be the value of preparing the holes for planting including placement of prepared mixtures,
2. Approximately one-third as the value of the furnishing and planting of the original plants, and the
3. Remaining one-third as the value of the plant establishment work.

The Department will make partial payments for the plant establishment work as the work progresses, at times to be established by the Engineer at intervals of not less than three months.

SECTION 803 – SODDING

803.01 Description.....	887
803.02 Sod	887
803.03 Fertilizer Grade	889
803.04 Ammonium Nitrate	889
803.05 Agricultural Limestone	889
803.06 Reserved.....	889
803.07 Weather Limitations.....	889
803.08 Removing and Storing Sod for Resetting.....	889
803.09 Sodding	889
803.10 Period of Establishment	890
803.11 Disposal of Surplus Material.....	892
803.12 Method of Measurement	892
803.13 Basis of Payment.....	892

DESCRIPTION

803.01 Description

This work consists of furnishing and placing sod at the locations shown on the Plans or where directed by the Engineer.

Ordinarily, this work will consist of furnishing and placing new sod originating from sources outside the right-of-way. In some cases, however, the work will include removing sod from areas where the requirements of the improvement would destroy existing sod, storing the sod so removed, and resetting it in areas shown on the Plans or designated by the Engineer.

MATERIALS

803.02 Sod

A. General

Provide new sod consisting of live, dense, well-rooted growth of permanent grasses, free from Johnson grass, nut-grass, and other

803.02

undesirable grasses or weeds, that is well-suited for the intended purpose and for the soil in which it is to be planted. Correct installed sod that does not meet these requirements as directed by the Engineer and at no additional cost to the Department.

Cleanly cut all sod in strips having a reasonably uniform soil thickness of not less than 1 inch and a reasonably uniform width of not less than 8 inches and a length of not less than 12 inches.

B. Department of Agriculture Inspection and Authorization

The sale or movement of turf grass or sod for propagation is controlled by Tennessee Plant Pest Act of 1955, TCA 43-515, et. seq. It requires inspection during the growing season and authorization by the Tennessee Department of Agriculture prior to removal. The authorization may be certificates for “Tennessee Certified Premium” sod, or “Tennessee Certified” sod. If the sod offered for use will not meet the requirements for certified sod but will meet the requirements of this Subsection, obtain a “Permit for Movement of Non-certified Turf Grass Sod.”

Request the inspection from the Tennessee Department of Agriculture as early as possible to avoid undue delay. Include the following information in the request for inspection:

1. Project number, county, name and address of the owner or seller,
2. Name and address of purchaser,
3. Kind or variety,
4. Exact location of sod,
5. Location where sod will be used, and
6. Approximate date movement of sod will begin.

Direct the request for inspection to the following address:

Division of Plant Industries
Tennessee Department of Agriculture,
Ellington Agricultural Center
Melrose Station 40627
Nashville, Tennessee 37204
Telephone (615) 360-0130

Furnish a copy of the Department of Agriculture authorization to the Engineer before removing any sod.

803.03 Fertilizer Grade

Provide fertilizer conforming to **918.02** and that is of Grade 10-10-10 or 1-1-1 formula, unless otherwise shown on the Plans or specified in the Special Provisions.

803.04 Ammonium Nitrate

Provide ammonium nitrate conforming to **918.03**.

803.05 Agricultural Limestone

Provide agricultural limestone conforming to **918.04**.

803.06 Reserved**CONSTRUCTION REQUIREMENTS****803.07 Weather Limitations**

Set or reset sod only when the soil is moist and favorable to growth. Do not perform any setting or resetting between December 1 and February 1, unless weather and soil conditions are considered favorable and permission is granted by the Engineer.

803.08 Removing and Storing Sod for Resetting

Cut, handle, and store sod removed from such areas as lawns, yards, and lots so that the sod can be reset in the same locations from which it was removed. Do not substitute sod unless approved by the Engineer. Unless resetting sod immediately after cutting, stack the sod in piles, and keep it moist until reset. Reset sod within 7 days after removal, unless otherwise approved by the Engineer.

803.09 Sodding

Bring the area to be sodded to the lines and grades shown on the Plans. Unless otherwise directed by the Engineer, place topsoil as specified in **203.06** before placing sod. When laying sod adjacent to structures, ditch paving, sidewalks, and similar features, ensure that water will not pond and will flow as designed. Loosen the surface of the ground to be sodded to a depth of not less than 1 inch with a rake or other device. If necessary, sprinkle

803.10

the ground until saturated for a minimum depth of 1 inch, and keep moist until the sod is placed. Immediately before placing the sod, apply fertilizer and lime uniformly to the prepared surface of the ground. Apply fertilizer at the rate of 12 pounds of Grade 10-10-10, or equivalent, per 1,000 square feet. Apply agricultural limestone at the rate of 100 pounds per 1,000 square feet.

Place sod as soon as practicable after removing from the point of origin and keep it in a moist condition during the interim. On urban projects, place the sod on all newly graded cut and fill slopes as work progresses to prevent damage to adjacent facilities and property due to erosion. Take care to retain the soil on the root system during excavating, hauling, and planting. Ensure that all sod is in an acceptable condition upon delivery and placement at the work site. Do not use sod damaged by heat or dry conditions.

Carefully place the sod by hand on the prepared ground surface, with the edges set in close contact and, as far as possible, in a position to break joints. Lay and fit each strip of sod into place, thoroughly wet it, and roll with an approved roller or hand-tamp, as approved by the Engineer. On slopes of 2:1 or steeper, pinning or pegging may be required to hold the sod in place.

803.10 Period of Establishment

A. Watering

Provide all labor and arrange for all watering necessary for rooting of the sod. If rainfall during the first 14 days of the period of establishment is inadequate to maintain a moist soil, perform the necessary watering, as approved by the Engineer. After 14 days, apply ammonium nitrate at the rate of 3.5 pounds per 1,000 square feet and re-water the sod.

B. Department Inspection

An authorized representative of the Department will conduct an inspection to determine the acceptability of the sodding no less than 90 days but not more than 150 days after completion of the sod work or at the acceptance of the entire Project, whichever is later, except that the Engineer may delay the inspection when conditions are such that the acceptability of the sodding cannot be determined at the end of the 150-day period or at the time the entire Project is accepted.

C. Contractor Guarantee

The Contractor shall guarantee, at the time of the Department inspection, a minimum of 95% live sod on the sodded areas and that there are no vacant areas of dead sod larger than 100 square feet. This guarantee shall apply to all permanent sodding performed in conjunction with the Project, regardless of the type protection used or the season in which the sodding is performed.

D. Repairs of Defective Areas

When the sodding does not meet the guarantee requirements at the time of inspection, repair the defective areas. Required repairs may include preparing the sod bed, refertilizing, resodding, and providing any erosion control items that were originally required. Perform such work as soon as favorable working conditions occur after being advised of the repairs required. The Department will not pay for the repair work and materials required to fulfill the guarantee requirements.

E. Care and Maintenance

From the time sodding and protection work begins until the date the entire Project is accepted, keep all sodded areas in good condition at all times.

Do not allow placement of any equipment or material on any planted area, and erect suitable barricades and guards to prevent equipment, labor, or the public from traveling on or over all areas planted with sod.

Promptly repair damage to sodded areas as directed by the Engineer. Perform all work and provide all materials necessary to protect, maintain, and restore sodded areas during the life of the Contract at no additional cost to the Department, except for additional work caused by Department-requested changes. If it becomes necessary to disturb previously sodded areas due to slope changes, addition of paved ditches not previously located by the Engineer, or other changes made at the direction of the Engineer, the Department will make payment for a reasonable amount of additional work, as determined by the Engineer, at the original contract unit prices. The Department will not pay for additional work due to changes made for the benefit of the Contractor, such as slope changes to obtain balance excavation instead of borrow excavation, nor will the Department pay for additional work required because the Contractor failed to properly coordinate its erosion control

803.11

schedule thus causing previously sodded areas to be disturbed by operations that could have been performed before sodding.

F. Contract Time

If, on Contracts involving sodding and other items of construction, the other items have already been completed, the time required for establishment under this item will not be charged against the time stipulated in the Contract for completion of the Project.

803.11 Disposal of Surplus Material

Dispose of all surplus material as directed by the Engineer.

COMPENSATION

803.12 Method of Measurement

The Department will measure:

1. Sod by the square yard in accordance with **109**.
2. Water by the M. G. (1,000 gallons) using calibrated tanks or distributors, or accurate water meters.

Only areas upon which sod has been set or reset will be measured for payment.

803.13 Basis of Payment

The Department will pay for accepted quantities, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Sodding (New Sod)	Square Yard

The Department will pay for water applied during the first 14 days after sodding work is complete, including the water used in the re-watering of the sod after the application of the ammonium nitrate, at the contract unit price for Water per M.G. (1,000 gallons). Water applied after this period will not be paid for and will be considered incidental to other items.

SECTION 805 – EROSION CONTROL BLANKETS

805.01	Description.....	893
805.02	Materials	893
805.03	Reserved.....	893
805.04	Surface Preparation and Blanket Placement	893
805.05	Maintenance.....	894
805.06	Method of Measurement.....	894
805.07	Basis of Payment.....	894

DESCRIPTION

805.01 Description

This work consists of furnishing and placing erosion control blankets, listed on the QPL, over previously prepared and seeded areas as shown on the Plans or as directed by the Engineer.

MATERIALS

805.02 Materials

Provide materials as specified in:

Erosion Control Blankets.....	920.01
Staples.....	920.02

805.03 Reserved

CONSTRUCTION REQUIREMENTS

805.04 Surface Preparation and Blanket Placement

Shape, fertilize, and seed the areas to receive the erosion control blankets as shown on the Plans or as directed by the Engineer. The surface shall be smooth and free of depressions and eroded areas that would allow water to collect or flow under the blanket.

805.05

Place the appropriate type of blanket as specified within 24 hours after the area has been seeded and prior to any rain or watering. If using a jute mesh blanket, after stapling the blanket into place, press it into the ground with a light lawn roller or by other means approved by the Engineer.

Place the blankets as shown on the Plans and Standard Drawings. Drive staples vertically into the ground to anchor the plastic mesh. Space staples as shown on the Plans and Standard Drawings. Where blankets are laid side by side, place the staples so that the staple will anchor mesh from each blanket.

In waterways, ditches, flumes, and channels, unroll the blanket and place in contact with the soil in the direction of the flow of water. The Engineer may specify additional staples or check slots in waterways where slopes are steep or large water volumes or velocities are anticipated.

805.05 Maintenance

Maintain the blanket installation during the life of the Contract. Prior to Project acceptance, if any staples have become loosened or raised, or if the blanket becomes loose, torn, or undermined for any reason, reshape, re-seed, and re-fertilize the damaged areas, and satisfactorily repair or replace the blanket at no additional cost to the Department.

COMPENSATION

805.06 Method of Measurement

The Department will measure blankets of the specified type(s), installed and accepted, by the square yards complete in place. The Department will consider overlaps, over width, and cut anchor slots to be incidental to the work.

805.07 Basis of Payment

The Department will pay for accepted quantities, complete in place, at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Erosion Control Blanket (Type __)	Square Yard
Turf Reinforcement Mat (Class __)	Square Yard
Flexibly Channel Liner (Class __)	Square Yard

805.07

Such payment is full compensation for all materials, equipment, tools, labor, and incidentals, including maintenance.

The Department will pay for the preliminary preparation of the areas on which the blanket is to be placed, including placing topsoil and furnishing and applying all seed, fertilizer, and water, under their specific item numbers.

806.01

SECTION 806 – ROADSIDE MAINTENANCE

806.01 Description	896
806.02 General	896
806.03 Definitions	896
806.04 Time and Frequency	897
806.05 Mowing Operations	897
806.06 Method of Measurement	898
806.07 Basis of Payment	898

DESCRIPTION

806.01 Description

This work consists of litter/debris removal, mowing, and trimming as specified or as directed by the Engineer for the entire highway right-of-way where accessible (fence-to-fence where applicable), including shoulders for the length of the Project.

CONSTRUCTION REQUIREMENTS

806.02 General

Remove litter and debris as directed by the Engineer for the entire construction limits. Dispose of litter and debris in accordance with all applicable permits and state and local ordinances.

Mowing and vegetation removal work shall consist of mowing and trimming of the right-of-way for vegetation control to maintain a neat aesthetic appearance as directed by the Engineer.

806.03 Definitions

A. Litter

Litter refers to any object or group of objects foreign to the right-of-way that has been discarded or abandoned and is or may become visible from the edge of the roadway or shoulder as a result of mowing, vegetation management, construction, maintenance operations, or traffic. Examples

under this definition include but are not limited to paper, plastic, bottles, cans, wood, tires, portions of tire, and metal products.

B. Mowing

Mowing refers to the work associated with cutting or trimming vegetation, primarily consisting of, but not limited to, grasses, invasive weeds, and small trees or shrubs to provide a consistent and aesthetically pleasing standing vegetation height as directed by the Engineer.

C. Trimming

Trimming refers to the work associated with cutting or trimming vegetation in close proximity to objects or in areas not accessible to conventional mowers in an attempt to prevent damage and provide a consistent vegetation height.

806.04 Time and Frequency

Perform litter/debris removal a minimum of twice per year or as directed by the Engineer.

Perform mowing and trimming a minimum of twice per growing season or as directed by the Engineer. The Engineer will issue a notice to begin to the Contractor at least 5 days before the date the mowing cycle is to begin.

Only perform work during the hours of daylight Monday through Saturday, or as directed by the Engineer. Do not perform this work on Sunday.

806.05 Mowing Operations

Perform all mowing to the satisfaction of the Engineer. Cut standing vegetation to a height of 4 inches while maintaining a consistent vegetation profile within the construction limits. Mow only those areas that are designated as mowable areas, including, if present, a minimum of 5 feet up the back slope from the bottom of the ditch, and 5 feet behind all guardrails. To cut vegetation, including small trees, shrubs, and bushes with a stem diameter of up to 1 inch that are inside of and encroaching upon the established mowing limits, use a mower or hand trimming methods as directed by the Engineer. Take care not to damage the trees, plants and shrubs that are designated by the Engineer to remain. Hand trimming may be required as directed by the Engineer for areas of vegetation inside the designated mowing limits that are not accessible to mechanical mowers. As

806.06

work progresses, conduct mowing and trimming to provide a consistent standing vegetation height in all mowing limits adjacent to the roadway. Mow as close as practicable to all fixed objects. Perform hand atop earth berms, within all rip rap areas, and around all fixed objects, including but not limited to earth berms, guardrails, cable rail, utility installations, utility poles, mailboxes, delineators, sign posts, wildflower plots, bridge abutments, and bridge piers. Do not apply chemicals unless authorized by the Engineer. Actual dimensions and mowing limits shall be discussed at the Preconstruction Conference.

Mowing for site distance shall be performed as frequently as necessary to provide adequate visibility and will not be considered as part of a mowing cycle.

COMPENSATION

806.06 Method of Measurement

The Department will not measure litter/debris removal for payment but will consider it incidental to the Work unless otherwise specified in the Contract.

The Department will pay for Mowing and Vegetation Removal by the mowing cycle. A mowing cycle includes the mowing of all areas within Project limits with overgrown vegetation one time.

The Department will not measure mowing for site distance but will consider it incidental to the Work.

806.07 Basis of Payment

The Department will pay for accepted quantities at the contract prices as follows:

<i>Item</i>	<i>Pay Unit</i>
Mowing and Vegetation Removal	Mowing Cycle

All costs associated with mowing and vegetation removal shall be included in the unit bid price for mowing. If the Contract does not contain a pay item for Mowing and Vegetation Removal, it will be incidental to other items of Work.

PART 9 – MATERIALS

SECTION 901 – HYDRAULIC CEMENT	900
SECTION 903 – AGGREGATES	901
SECTION 904 – BITUMINOUS MATERIALS	930
SECTION 905 – JOINT MATERIALS	936
SECTION 906 – DAMPPROOFING AND WATERPROOFING MATERIALS	940
SECTION 907 – CONCRETE REINFORCEMENT	943
SECTION 908 – STRUCTURAL STEEL AND APPURTENANT MATERIALS	946
SECTION 909 – FENCE, GUARD RAIL AND BARRIER.....	956
SECTION 910 – PAINT	966
SECTION 911 – LUMBER, TIMBERS, AND TIMBER PILES.....	971
SECTION 912 – BRICK	974
SECTION 913 – CEMENT CONCRETE CURING MATERIALS	976
SECTION 914 – NON-METALLIC PIPE	977
SECTION 915 – METALLIC PIPE	980
SECTION 916 – HIGHWAY SIGNING MATERIALS	982
SECTION 917 – ROADWAY AND STRUCTURE LIGHTING MATERIALS	991
SECTION 918 – LANDSCAPING MATERIALS.....	1002
SECTION 919 – PAVEMENT MARKING MATERIAL AND MARKERS.....	1006
SECTION 920 – EROSION CONTROL MATERIALS	1014
SECTION 921 – MISCELLANEOUS MATERIALS.....	1015

901.01

SECTION 901 – HYDRAULIC CEMENT

901.01 Hydraulic Cement 900

901.01 Hydraulic Cement

Provide hydraulic cement, selected from the Department’s Producer List, that conforms to the following for the kind and type specified or allowed:

- Portland cement AASHTO M 85
- Portland blast-furnace slag cement (Type IS) AASHTO M 240
- Portland-pozzolan cement (Type IP) AASHTO M 240
- Portland-limestone cement (Type IL) AASHTO M 240

The maximum allowable equivalent alkalis is 0.60% for all cements and blended cements used in concrete riding surfaces with aggregates meeting the requirements of **903.24**. This includes Class CP, A Paving, and DS concrete mixtures.

Use Type I, Type IL, or Type IS cement unless otherwise specified. Do not mix different types of cement.

Provide suitable means for storing and protecting the cement against dampness. The Engineer will reject cement that has become partially set or that contains lumps of caked cement.

Ensure that the temperature of the cement at the time of delivery to the mixer does not exceed 160 °F.

Do not use cement containing air-entraining materials.

SECTION 903 – AGGREGATES

903.01 Fine Aggregate for Concrete.....	901
903.02 Fine Aggregate for Mortar	903
903.03 Coarse Aggregate for Concrete	904
903.04 Reserved.....	906
903.05 Aggregate for Mineral Aggregate Base and Surface Courses.....	906
903.06 Aggregate for Plant Mix Base and Leveling Courses (Hot Mix) .	911
903.07 Reserved.....	915
903.08 Reserved.....	915
903.09 Reserved.....	915
903.10 Aggregate for Bituminous Plant Mix Surface Course (Cold Mix)	915
903.11 Aggregate for Asphaltic Concrete Surface Courses (Hot Mix)....	916
903.12 Aggregate for Slurry Seal and Micro-Surface.....	920
903.13 Aggregate for Bituminous Seal Coat	922
903.14 Aggregate for Double Bituminous Surface Treatment.....	922
903.15 Aggregate for Aggregate-Cement Base Course	923
903.16 Mineral Filler	923
903.17 Aggregate for Underdrains.....	923
903.18 Reserved.....	924
903.19 Lightweight Aggregates for Structural Concrete	924
903.20 Stockpiling Aggregates	924
903.21 Test Methods.....	925
903.22 Sizes of Coarse Aggregate	926
903.23 Reserved.....	927
903.24 Aggregates for Riding Surfaces (Polish-Resistant Aggregates)...	927
903.25 Aggregate Quality Requirements.....	928

903.01 Fine Aggregate for Concrete

For concrete provide aggregate conforming to AASHTO M 6, with the following exceptions and additions:

903.01

1. The option regarding alternate freeze-thaw tests for soundness is waived.
2. The fine aggregate shall be washed in the processing operations.
3. Provide fine aggregate meeting the quality requirements in **903.25**.
4. The amount of deleterious substances shall not exceed the limits specified in Table 903.01-1.

Table 903.01-1: Limits of Deleterious Substances in Fine Aggregate for Concrete

Substance	Maximum Permissible Limits Percent by Weight
Clay Lumps	0.5
Coal and Lignite	0.5
Material Passing the No. 200 Sieve ⁽¹⁾⁽³⁾	3.0
Other deleterious substances (such as shale, alkali, mica, coated/grains, soft and flaky particles) ⁽¹⁾⁽²⁾	3.0

- (1) If the fine aggregate is manufactured from crushed stone and if material finer than the No. 200 sieve consists of the dust of fracture, essentially free from clay or shale, this limit may be increased to 10%.
- (2) Determine other organic impurities according to AASHTO T 267.
- (3) If the fine aggregate is manufactured from crushed gravel and if material finer than the No. 200 sieve consists of the dust of fracture, essentially free from clay or shale, this limit may be increased to 3.5%.

5. Provide fine aggregate that is well graded from coarse to fine within the limits specified in Table 903.01-2.

Table 903.01-2: Gradation Requirements for Fine Aggregate

Sieve Size	Total Percent Passing by Weight
3/8 inch	100
No. 4	95-100
No. 16	50-90
No. 50	5-35
No. 100	0-20
No. 200 ⁽¹⁾	0-3

⁽¹⁾ If the fine aggregate is manufactured from crushed stone and if material finer than the No. 200 sieve consists of the dust of fracture, essentially free from clay or shale, this limit may be increased to 10%.

6. For use in flowable mortar, provide fine aggregate meeting the above requirements, except the gradation shall be as specified in Table 903.01-3.

Table 903.01-3: Gradation Requirements for Fine Aggregate used in Flowable Mortar

Sieve Size	Total Percent Passing by Weight
1/2 inch	100
No. 200	0-20

903.02 Fine Aggregate for Mortar

Provide mortar sand that conforms to AASHTO M 45, meets the quality requirements in **903.25**, and that is uniformly graded from coarse to fine within the limits specified in Table 903.02-1.

903.03

Table 903.02-1: Gradation Requirements for Mortar Sand

Sieve Size	Total Percent Passing by Weight
No. 8	100
No. 50	15-40
No. 100	0-10
No. 200	0-5

903.03 Coarse Aggregate for Concrete

For any type or class of Portland cement concrete, provide coarse aggregate consisting of crushed stone, crushed slag, or crushed or uncrushed gravel, unless otherwise specified.

For Portland cement concrete base and pavement, furnish coarse aggregate in two sizes: Size No. 4 and Size No. 67, graded as specified in **903.22**. Manufacture the two sizes, within the specified limits, to produce Size No. 467, in accordance with **903.22**, when combined in the proper proportions at the batching plant, or a size No. 467, manufactured within the specified limits of **903.22**.

Coarse aggregate in Portland cement concrete pavements for finished riding surfaces of travel lanes including mainline pavements and ramps shall consist of Size No. 467. Ensure that either the Size No. 4 or Size No. 67 fractions meet **903.24**. Ramps using Class A paving concrete or any riding surface travel lane consisting of Size No. 57 shall meet **903.24**.

Coarse aggregate in two-lift composite pavements shall consist of Size No. 467 in the lower lift, graded as specified in **903.22**. Coarse aggregate in the upper lift shall be Size No. 57 or 67 graded as specified in **903.22** and shall meet **903.24** riding surface requirements.

Coarse aggregate in Portland cement concrete bridge decks and overlays on interstates and four or more lane highways consisting of Size No. 57 shall meet **903.24**.

The coarse aggregates for travel lanes and bridge decks shall be crushed and consist of stone, slag, gravel, quartzite, gneiss, or combination thereof with an absorption of plus 4 material not to exceed 5%. Do not use uncrushed gravel, pea gravel, or any other uncrushed particles. Crushed gravel, if used, shall consist of siliceous washed particles after processing, of which at least

70% by count of the material retained on the No. 4 sieve contains a minimum of two fractured faces. One face shall be fractured for the approximate average diameter or thickness of the particle.

For other uses of concrete, provide coarse aggregate of the sizes specified in Table 903.03-1, or as otherwise shown or directed.

Table 903.03-1: Coarse Aggregate Sizes

Application	Coarse Aggregate Size ⁽¹⁾
Structural concrete	No. 57
Self-Consolidating concrete	Maximum-No. 67
Prestressed concrete	No. 57 or 67
Precast concrete	Any size fraction
Concrete for Bridge Repair ⁽²⁾	No. 57 or 67
Concrete curbing placed by machine-extrusion methods	No. 7, 57, 67, or 78
Cement treated permeable base	No. 57

⁽¹⁾ Gradation shall conform to **903.22**.

⁽²⁾ If proposing to use a coarse aggregate size not specified submit a written request to Regional Materials and Tests explaining the necessity for the change.

The coarse aggregates shall otherwise conform to the requirements of AASHTO M 80, with the following exceptions and additions:

A. Deleterious Substances

The amount of deleterious substances shall not exceed the limits specified in Table 903.03-2.

903.04

Table 903.03-2: Limits of Deleterious Substances in Coarse Aggregate for Concrete

Substance	Maximum Percent by Weight
Soft or non-durable fragments (fragments that are structurally weak such as shale, soft sandstone, limonite concretions, gypsum, weathered schist, or cemented gravel), and organic impurities as determined by AASHTO T 267 ⁽¹⁾	3
Coal and lignite ⁽¹⁾	1
Clay lumps ⁽¹⁾	0.25
Material passing the No. 200 sieve ⁽¹⁾⁽²⁾	1.5
Thin or elongated pieces (length greater than 5 times average thickness)	10
Other local deleterious substances ⁽¹⁾	1

⁽¹⁾ The sum of the percentages of these materials (i.e., soft or non-durable fragments, coal and lignite, clay lumps, material passing the No. 200 sieve, and other local deleterious substances) shall not exceed 5.0.

⁽²⁾ For crushed aggregate, if all the material finer than the No. 200 sieve, as determined in accordance with AASHTO T 11, consists of the dust of fracture, essentially free of clay or shale, this limit may be increased to 2.0.

B. Quality Requirements

The coarse aggregate shall meet the quality requirements in **903.25**.

903.04 Reserved

903.05 Aggregate for Mineral Aggregate Base and Surface Courses

Provide crushed stone, crushed slag, crushed or uncrushed gravel, or crushed or uncrushed chert that may be blended with crushed recycled concrete aggregate or screened recycled asphalt pavement (RAP), together with material such as manufactured sand or other fine materials that are either naturally contained or added as needed to conform to these Specifications.

Provide aggregate of Types A and B, as specified below.

A. Type A Aggregate

Provide hard, durable particles or fragments of stone, slag, gravel, or chert, and other finely divided mineral matter.

The Contractor may use recycled concrete aggregate at any percentage and up to full replacement by weight per **903.05.C** or recycled asphalt pavement at a maximum rate of 25% by weight for Type A aggregate, provided the combined aggregate blend meets all the requirements specified below. Crush and screen the recycled concrete and asphalt to produce a uniform stockpile before blending it with the virgin material. Keep the recycled stockpiles free of bricks, steel, wood, and all other deleterious materials.

Provide individual or blended materials meeting the following requirements:

1. **Crushed Stone.** Provide stone free of silt and clay and having a coarse aggregate portion (retained on the No. 4 sieve) that conforms to the requirements specified in **903.25**.
2. **Crushed Slag.** Provide material that:
 - a. Is free of silt and clay,
 - b. Meets the quality requirements in **903.25**,
 - c. Is reasonably uniform in density, and
 - d. Has a dry-rodded weight of at least 70 pounds per cubic foot.
3. **Gravel and Chert.** Screen gravel and chert. All oversize material may be crushed and fed uniformly back over the screen. The coarse aggregate portion shall conform to the quality requirements specified in **903.25**. The portion of the material passing the No. 40 sieve shall be non-plastic or shall have a liquid limit of not greater than 30 and a plasticity index of not more than 8.

If fine aggregate, coarse aggregate, or binder, in addition to that present in the base material, is necessary to meet the gradation or density requirements or to ensure satisfactory bonding of the material, blend such material uniformly with the base course material at the mixing plant by a mechanical feeder to maintain a uniform flow on the belt to the mixer. Do not blend materials on the stockpiles or in the pits using a bulldozer, clamshell, dragline, or similar equipment.

903.05

The composite gradation of Type A aggregate shall be the grading specified in the Contract or shown on the Plans and shall conform to the limits specified in Table 903.05-2.

B. Type B Aggregate

Provide crushed or uncrushed gravel, crushed or uncrushed chert, crushed stone or crushed slag, and other finely divided particles.

The Contractor may use recycled concrete aggregate at any percentage and up to full replacement by weight per **903.05.C** or recycled asphalt pavement at a maximum rate of 30% by weight for Type B aggregate, provided the combined aggregate blend meets all the requirements specified. Crush and screen recycled concrete and asphalt to produce a uniform stockpile before blending it with the virgin material. Keep the recycled stockpiles free of bricks, steel, wood, and all other deleterious materials.

Provide Type B aggregate meeting the same requirements as specified in **903.05.A** for Type A aggregate, with the following exceptions:

1. The aggregate shall meet the quality requirements in **903.25**.
2. Screen Type B aggregate. Oversize materials may be wasted or crushed and returned over the screen and uniformly blended with the other material.
3. Do not use material having a clay content greater than 12%, as determined by hydrometer analysis performed in accordance with AASHTO T 88. Material may be used having a clay content exceeding 12% if a plasticity index-fines product does not exceed 3 when calculated by the following formula:

$$\frac{\% \text{ Passing No. 40 sieve} \times \text{P.I. of Minus No. 40 Material}}{100}$$

If an excess of binder occurs, uniformly incorporate crushed stone, crushed slag, gravel, chert, sand, or other approved granular materials in such proportions, not to exceed 20% of the total mix, as directed by the Engineer.

If the quantity of binder is insufficient to bond the base or surface course properly, uniformly incorporate additional binder of approved quality, in

an amount not to exceed 15% of the total mix, as directed by the Engineer.

Do not use material requiring the addition of coarse aggregate or binder in excess of the above limits, unless otherwise shown on the Plans or specified in the Contract.

The Contractor may blend additional material, if required, at the screening or mixing plant. When blending is done at the plant, use mechanical feeders that will maintain a uniform flow of the materials on the conveyor belt to the mixer or screening plant. Do not blend materials on the stockpile or in the pit using a bulldozer, clamshell, or similar equipment.

The composite gradation of Type B aggregate shall be the grading shown on the Plans or specified in the Contract, and shall conform to the limits specified in Table 903.05-2.

Table 903.05-2: Grading Table for Type A and Type B Aggregate for Mineral Aggregate Base and Surface Courses

Sieve Size	Total Percent by Weight, Passing Sieves				
	Grading A	Grading B	Grading C	Grading D	Grading E
2-1/2 inch	100	--	--	--	--
2 inch	95-100	100	--	--	--
1-1/2 inch	--	95-100	100	100	--
1 inch	--	--	90-100	85-100	100
3/4 inch	--	65-95	--	60-95	90-100
3/8 inch	35-65	--	45-74	50-80	65-100
No. 4	--	35-55	30-55	40-65	--
No. 16	--	15-45	--	20-40 ⁽¹⁾	--
No. 100	0-10	4-15	4-15	9-18 ⁽²⁾	5-15

⁽¹⁾ For gravel and chert bases containing clay, the range is 20-43.

⁽²⁾ For gravel and chert bases containing clay, the range is 7-18.

903.05

C. Recycled Concrete Aggregate

Provide material comprised of concrete reclaimed from the demolition of a concrete structure or pavement. Recycled concrete aggregate may only be used as a mineral aggregate base course, subbase, or shoulder course. The material shall be free of any materials classified as Solid or Hazardous Waste, especially asbestos, lead and mercury, with test results submitted by the contractor to the Project Supervisor. These test results shall be certified and notarized. The aggregate shall meet the quality requirements in **903.25**. Deleterious substances shall be kept to a minimum and may not be higher than the amounts listed on Table 903.05-3.

Table 903.05-3: Deleterious Materials

Material	Maximum Permissible Limits Percent by Weight
Brick	5
Bituminous Concrete Materials	5
Weathered Rock	2
Wood	0.1
Metals	0.1

The gradations of the coarse and fine fractions of aggregate shall be such that, when combined in proper proportions, the resultant mixture will fall within the grading specified in Table 903.05-4.

Table 903.05-4: RCA Grading Tolerances

Sieve Size	Total Percent Passing per Weight
1 ½ inch	100
1 inch	85-100
¾ inch	60-95
3/8 inch	50-80
No. 4	40-65
No. 16	20-40
No. 100	5-18

903.06 Aggregate for Plant Mix Base and Leveling Courses (Hot Mix)

For plant mix base and leveling courses, provide coarse aggregate, fine aggregate, and mineral filler when required.

If at any time the sources of materials are changed, prepare and submit a new mix design as specified in **407.03**.

A. Coarse Aggregate (retained on a No. 4 sieve)

Provide crushed stone, crushed granite, crushed gravel, crushed slag, or a combination of these materials. This material shall conform to the physical properties of ASTM D692 and the quality requirements of **903.25**. The aggregate shall contain no more than 5% soft or nondurable particles.

Crushed gravel shall consist of particles processed from washed material. At least 70% by count of the gravel retained on the No. 4 sieve shall have a minimum of two fractured faces, one of which must be fractured for the approximate average diameter or thickness of the particle. Do not add pea gravel or uncrushed particles.

For virgin coarse aggregate for Grading A, ACRL, and AS mixes, use crushed stone, crushed slag, or a combination of these materials.

B. Fine Aggregate (passing a No. 4 sieve)

Provide limestone fines, natural sand, sand manufactured from stone, gravel, or slag, or combinations of these materials, consisting of hard, tough grains free from injurious amounts of deleterious substances. The fine aggregate shall meet the quality requirements in **903.25**. Fine aggregate containing gypsum (CaSO_4) shall not chemically contain more than 5% sulfur trioxide (SO_3) as determined by analysis of the material passing the No. 8 sieve. In natural sand or sand manufactured from gravel, the percentage of material finer than No. 200 sieve shall not exceed 5%.

For use in Grading A and AS mixes, provide virgin fine aggregate consisting of crushed stone or crushed slag only, and store the material separately from the coarse aggregate.

Ensure that the amount of deleterious substances in natural sand does not exceed the limits specified in Table 903.06-1.

903.06

Table 903.06-1: Maximum Limits for Deleterious Substances in Natural Sand

Substance	Maximum Permissible Limits, Percent by Weight
Clay Lumps	0.5
Coal and Lignite	0.5
Other deleterious substances (such as shale, alkali, mica, coated grains, soft and flaky particles) and organic impurities as determined by AASHTO T 267	3.0

C. Combined Aggregate Grading

Provide the appropriate combination of coarse aggregate and fine aggregate to achieve the combined grading. Use a minimum of three sizes of virgin aggregate for all mix designs except for C, CS, and CW mixes, which shall be designed from a minimum of two sizes of virgin aggregate.

Establish a gradation for each aggregate used in the mix. Table 903.06-2 specifies the stockpile gradation tolerance on each sieve for each virgin aggregate component used in the mix.

Table 903.06-2: Stockpile Gradation Tolerance

Sieve Size	Gradation Tolerance
3/8-inch sieve and larger	± 10%
No. 4 sieve	± 7%
No. 8 sieve	± 5%
No. 30 sieve	± 4%
No. 200 sieve (coarse aggregate)	± 2%
No. 200 sieve (fine aggregate)	± 4%

When the coarse aggregate portion of Grading CW mix is crushed limestone, use no less than 20% and no more than 50% by weight natural sand, or sand manufactured from slag or other approved polish-resistant aggregate. When the coarse aggregate portion is crushed gravel or

crushed slag, between 15% and 40% by weight of the mineral aggregate shall be agricultural limestone or Size No. 10 limestone screenings.

The gradations of the coarse and fine fractions of aggregate shall be such that, when combined in proper proportions, the resultant mixture will meet one of the gradings specified in Tables 903.06-3 and 903.06-4.

**Table 903.06-3: Hot Plant Mix Base Course
Mixture Design Range of Gradations**

Sieve Size	Total Percent Passing, by Weight			
	Grading A	Grading AS	Grading ACRL	Grading B
2 inch	100	100	100	100
1-1/2 inches	81-100	75-100	80-93	95-100
3/4 inch	50-71	55-80	60-75	70-85
3/8 inch	35-50	--	--	49-72
No. 4	24-36	7-11	12-16	34-51
No. 8	13-27	--	--	23-42
No. 30	7-17	--	--	11-22
No. 50	--	--	--	9-14
No. 100	0-10	0-6	0-4	4-10
No. 200	0-4.5	0-4.5	0-3.5	2.5-6.5

903.06

**Table 903.06-4: Hot Plant Mix Leveling Course
Mixture Design Range of Gradations**

Sieve Size	Total Per Cent Passing, by Weight				
	Grading BM	Grading BM2 ⁽¹⁾	Grading C	Grading CW	Grading CS
1-1/4 inch	--	100	--	--	--
1 inch	100	--	--	--	--
3/4 inch	85-100	81-93	100	100	--
3/8 inch	59-79	57-73	70-90	75-100	100
No. 4	42-61	40-56	39-66	--	89-94
No. 8	29-47	28-43	23-47	43-67	53-77
No. 30	13-27	13-25	10-27	23-47	23-42
No. 50	7-20	9-19	8-15	--	--
No. 100	4-10	6-10	4-8	4-10	9-18
No. 200	0-6.5	2.5-6.5	2.5-6.5	2.5-6.5	6-13.5

⁽¹⁾ When using natural sand as the fine aggregate, limit it to a maximum amount of 20% by weight of the mineral aggregate.

For asphalt treated permeable base as specified in **313**, meet the gradation requirements specified in Table 903.06-5.

Table 903.06-5: Gradation Requirements for Asphalt Treated Permeable Base

Sieve Size	Total Percent Passing by Weight
2 inch	100
1-1/2 inch	70-100
3/4 inch	55-80
No. 4	0-11
No. 100	0-4
No. 200	0-3

903.07 Reserved**903.08 Reserved****903.09 Reserved****903.10 Aggregate for Bituminous Plant Mix Surface Course (Cold Mix)**

For cold bituminous plant mix, provide mix aggregate, consisting of crushed stone or crushed slag, meeting the quality requirements of ASTM D692. Crushed slag aggregate retained on the No. 4 sieve shall contain no more than 20% by weight of glassy particles.

The amount of material finer than the No. 200 sieve, as determined in accordance with AASHTO T 11, shall not exceed 1%. If all material finer than the No. 200 sieve consists of the dust of fracture, essentially free from clay or shale, this percentage may be increased to 1.5.

For leveling and surface course mixtures, provide mix aggregate meeting the gradation requirements specified in **903.22** for Size No. 68.

For key or choker aggregate, provide crushed stone, crushed slag, or crushed gravel meeting the gradation requirements specified in **903.22** for Size No. 8 and the same quality requirements as the mix aggregate.

903.11

903.11 Aggregate for Asphaltic Concrete Surface Courses (Hot Mix)

Provide aggregate, consisting of a combination of coarse and fine aggregate, and mineral filler when required or specified. Use a minimum of three sizes of virgin aggregates for all mix designs.

If at any time the sources of materials are changed, provide a new mix design as specified in **407.03.C.2**.

A. Coarse Aggregate (retained on a No. 4 sieve)

Provide aggregate, consisting of crushed stone, crushed slag, crushed gravel, crushed granite, crushed quartzite, crushed gneiss, or natural combinations of these materials. The coarse aggregate shall meet the physical requirements of ASTM D692, with the following exceptions and additions:

1. The aggregate shall meet the quality requirements in **903.25**.
2. Material retained on the No. 4 sieve shall contain a maximum of 10% by weight elongated pieces (length greater than five times the average thickness).
3. Combined aggregate shall consist of siliceous particles processed from washed material, of which at least 70% by count of the material retained on the No. 4 sieve shall have a minimum of two fractured faces, one of which must be fractured for the approximate average diameter or thickness of the particle. Do not add pea gravel or uncrushed particles.
4. Crushed slag coarse aggregate shall contain no more than 20% by weight of glassy particles.

B. Fine Aggregate (passing a No. 4 sieve)

Provide fine aggregate, consisting of natural sand, fines prepared from stone, slag, gravel, granite, quartzite, gneiss, or combinations of these materials. The fine aggregate shall meet the following requirements:

1. Fine aggregate shall consist of hard tough grains free from injurious amounts of clay, loam, or other deleterious substances.

2. Fine aggregate shall meet the quality requirements in **903.25**.
3. Manufactured sand shall have no more than 5% passing the No. 200 sieve when tested in accordance with AASHTO T 11.
4. Fine aggregate containing gypsum (CaSO_4) shall not chemically contain more than 5% sulfur trioxide (SO_3) as determined by analysis of the material passing the No. 8 sieve.
5. Wash and grade natural sand so that not more than 5% will be retained on the No. 4 sieve.
6. For fine aggregate consisting of natural sand, the amount of material finer than a No. 200 sieve, as tested in accordance with AASHTO T 11, shall not exceed 4% by weight.

The amount of deleterious substances in natural sand shall not exceed the limits specified in Table 903.11-1.

Table 903.11-1: Limits of Deleterious Substances in Natural Sand used in Hot Mix

Substance	Maximum Permissible Limits Percent by Weight
Clay Lumps	0.5
Coal and Lignite	0.5
Other deleterious substances (such as shale, alkali, mica, coated grains, soft and flaky particles) and organic impurities as determined by AASHTO T 267	3.0

7. When using agricultural limestone as a portion of the fine aggregate, manufacture it from sound, durable stone that is crushed so that at least 85% will pass the No. 8 sieve and at least 50% will pass the No. 30 sieve.

C. Combined Aggregate Grading

Provide aggregate fractions sized, graded, and combined in proportions that will ensure the resulting composite blend will meet one of the

903.11

gradation requirements specified in Table 903.11-2, together with the additional requirements pertaining to the constituents of the blend specified thereafter.

Establish a single value for each sieve size required in the mix for each virgin aggregate stockpile, with an allowable stockpile tolerance on each sieve as specified in Table 903.06-2.

When using Gradings D or E for the surfacing of shoulders or for other non-traffic lane construction, the Contractor may modify the design with the Engineer's approval.

**Table 903.11-2: Asphalt Concrete Surface Course Mixture Designation
Design Range of Gradations**

Sieve Size	Total Percent Passing by Weight				
	Grading D	Grading E	Grading TL	Grading TLD/TLE	Grading OGFC
3/4 inch	--	--	--	--	100
5/8 inch	100	100	--	--	--
1/2 inch	95-100	95-100	100	100	85-100
3/8 inch	80-93	80-93	100	90-100	55-75
No. 4	54-76	54-76	89-94	54-76	10-25
No. 8	35-57	35-57	53-77	35-57	5-10
No. 30	17-29	17-29	23-42	17-33	--
No. 50	10-18	10-18	--	10-18	--
No. 100	3-10	3-11	9-18	3-10	--
No. 200	0-6.5	0-8	6-14	3-7	2-4

- 1. Grading D and TLD.** Use fine aggregate consisting of natural sand or sand manufactured from gravel, slag, or from crushed stone aggregate meeting the physical and chemical requirements specified in **903.24**. The use of carbonate rocks such as limestone and dolomite or other aggregates that tend to polish under traffic will not be permitted in the coarse aggregate and will be permitted only to the extent specified herein in the fine aggregate.

When using limestone screenings or agricultural limestone, the maximum amount by weight of the mineral aggregate shall be 25% unless the material is shown to meet the same requirements for limestone as specified in Table 903.24-1 for Surface Mixtures. In no case shall the combined aggregate blend consist of less than 75% polish-resistant material. When using natural sand as fine aggregate, limit it to a maximum amount of 25% by weight of the mineral aggregate. The Contractor may substitute a maximum of 5% mineral filler meeting the requirements of **903.16** for an equal quantity of the limestone fines. If the mixture does not comply with the design criteria, provide another source of aggregate.

When using gravel as the coarse aggregate for a 411 Grading D mix, use a minimum of 20% by weight limestone screenings, agricultural limestone, or mineral filler.

Recycled asphalt pavement (RAP) milled from Department or other State Highway Agency projects shall be assumed to contain 75% polish-resistant material.

2. **Grading E and TLE.** When using Grading E as a surface for traffic lanes, 50% to 80% of the mineral aggregate shall be composed of crushed limestone, and the remaining 50% to 20% shall be natural sand, slag sand, sand manufactured from gravel or other approved polish-resistant aggregates, or any combination of these materials, with the following exceptions:
 - a. The sand percentage on the Job Mix Formula (JMF) shall range from 20% to 50%. However, if needed to meet or improve the specified design criteria, the Contractor may alter the limestone and sand percentage by 5% from the percentage shown on the original JMF. If altering the aggregate percentages shown on the original JMF, submit a revision of the original design showing the altered percentages of aggregate.
 - b. When using Grading E for surfacing of shoulders or other non-traffic lane construction, the mineral aggregate may be composed entirely of limestone, including Size No. 10 (screenings) and manufactured sand, but in no case shall the mineral aggregate for this construction consist of less than 50% limestone.

903.12

c. Recycled asphalt pavement (RAP) milled from Department or other State Highway Agency projects shall be assumed to contain 75% polish-resistant material.

3. **Grading OGFC.** A minimum of 75% of the aggregate shall meet the requirements specified in **903.24** for Surface Mixtures (Polish-Resistant Aggregates). The coarse aggregate shall have at least 90% crushed aggregate with two fractured faces and 100% with one fractured face as determined in accordance with ASTM D5821. The coarse aggregate shall have a LA Abrasion value of less than 40% and a maximum absorption of 3.0%.

Recycled asphalt pavement (RAP) milled from Department or other State Highway Agency projects shall be assumed to contain 75% polish-resistant material.

4. **Grading TL.** A minimum of 75% of the aggregate shall meet the requirements specified in **903.24** for Surface Mixtures (Polish-Resistant Aggregates) for the appropriate traffic level. The mixture shall contain a maximum of 15% natural sands.

Recycled asphalt pavement (RAP) milled from Department or other State Highway Agency projects shall be assumed to contain 75% polish-resistant material.

5. **Grading C, CS, CW.** The mixture shall meet all requirements of **903.06**. When using Grading C, CS, or CW as a final riding surface for traffic lanes and the design ADT is greater than 1,000, a minimum of 75% of the aggregate shall meet the requirements specified in **903.24** for Surface Mixtures (Polish-Resistant Aggregate) for the appropriate levels.

Recycled asphalt pavement (RAP) milled from Department or other State Highway Agency projects shall be assumed to contain 75% polish-resistant material.

903.12 Aggregate for Slurry Seal and Micro-Surface

A. Aggregate for Slurry Seal

The aggregate shall be crushed slag, crushed granite, or crushed stone (crushed stone as specified in **903.24**), meeting the requirements of

ASTM D692, except the gradation shall be as specified in Table 903.12-1. The aggregate shall meet the quality requirements in **903.25**. The aggregate shall have a minimum sand equivalent, as determined in accordance with AASHTO T 176, of 45.

Table 903.12-1: Gradation Limits for Aggregate for Slurry Seal Based on Wash Gradation

Sieve	Design Master Range (Total Percent Passing)	Mixture Control Tolerances
3/8 inch	100	
No. 4	90-100	±6.0
No. 8	65-90	±5.0
No. 16	45-70	±5.0
No. 30	30-50	±4.0
No. 50	20-38	±4.0
No. 100	12-28	±3.0
No. 200	8-16	±3.0

B. Aggregate for Micro-Surface

The aggregate shall be crushed slag, crushed granite, or crushed stone (crushed stone as specified in **903.24**) meeting the gradation limits specified in Table 903.12-2 and the physical properties of ASTM D692, except the percent of fractured pieces shall be 100. The aggregate shall meet the quality requirements in **903.25**. The aggregate shall have a minimum sand equivalent, as determined in accordance with AASHTO T 176, of 65. Polish-resistant aggregates will not be required for leveling courses, provided they will be covered with riding surface mixtures.

If blending aggregates from more than one source, use automated proportioning and blending equipment which has individual bins for each aggregate source used to produce a uniform stockpile meeting the job mix formula gradation. Proportion and blending equipment shall be calibrated at the beginning of production. All aggregate sources shall be polish-resistant as specified in **903.24**. The contractor shall provide a Type A laboratory as defined by **106.06** capable of verifying gradation at the location where blending occurs.

903.13

Table 903.12-2: Gradation Limits for Aggregate for Micro-Surfacing Based on Wash Gradation

Sieve	Design Master Range (Total Percent Passing)	Mixture Control Tolerances
3/8 inch	100	
No. 4	70-98	±6.0
No. 8	45-70	±5.0
No. 16	28-50	±5.0
No. 30	19-34	±4.0
No. 50	12-25	±4.0
No. 100	7-18	±2.0
No. 200	4-15	±2.0

903.13 Aggregate for Bituminous Seal Coat

Provide aggregate consisting of crushed stone, crushed slag, or crushed gravel, meeting the physical requirements of ASTM D692, except that at least 50% by count of crushed gravel aggregates shall have at least one fractured face. The aggregate shall meet the quality requirements of **903.25**. Crushed slag aggregate retained on the No. 4 sieve shall contain no more than 20% by weight of glassy particles. Provide aggregates meeting the requirements of **903.24** except, if ADT is less than 1000.

The amount of material finer than the No. 200 sieve shall not exceed 1%. If all material finer than the No. 200 sieve consists of the dust of fracture, essentially free from clay or shale, the percentage may be increased to 1.5.

Use aggregate meeting the gradation requirements in **903.22** for the size identified on the Plans and in accordance with Table 405.06-1.

903.14 Aggregate for Double Bituminous Surface Treatment

Provide aggregate meeting **903.13**. In the mat, use aggregate meeting the gradation requirements specified for Size No. 7 in **903.22**. In the seal, use aggregate meeting the gradation requirements specified for Size No. 8 in **903.22**. Ensure that at least 90% of the aggregate particles retained on the

No. 4 sieve have one or more fractured faces fractured for the approximate average diameter or thickness of the particle.

903.15 Aggregate for Aggregate-Cement Base Course

Provide coarse aggregate, composed of sound, tough, durable fragments of crushed stone, crushed slag, crushed or uncrushed gravel, or crushed or uncrushed chert, which may be blended with crushed recycled concrete or screened recycled asphalt pavement (RAP), and fine aggregate composed of natural or manufactured sand, and silt-clay or other finely divided mineral matter.

Provide gravel or chert aggregate that is screened and of such gradation that 100% will pass a 1-1/2-inch sieve, not more than 75% will pass the No. 4 sieve, and not less than 5% nor more than 15% will pass the No. 200 sieve. The fraction passing the No. 40 sieve shall have liquid limit not greater than 35, and a plasticity index not greater than 10. Provide crushed stone or slag aggregate that is sized and proportioned to meet the gradation requirements specified in **903.05** for Grading D. Blend materials, if required, at the screening plant or at the stationary mixing plant.

Recycled concrete aggregate per **903.05.C** or recycled asphalt pavement (RAP) may be used at a maximum rate of 25% by weight, provided the combined aggregate blend meets all the requirements specified above. If blending, crush and screen the recycled concrete and/or asphalt to produce a uniform stockpile before blending it with the virgin material. Keep the recycled asphalt pavement stockpiles free of bricks, steel, wood, and all other deleterious materials. The virgin aggregate shall meet the quality requirements specified in **903.25**.

Ensure that the combined total of shale, organic material, and other unwanted substances does not exceed 5% by weight.

903.16 Mineral Filler

Provide mineral filler conforming to AASHTO M 17, except that the mineral filler shall be non-plastic.

903.17 Aggregate for Underdrains

Provide crushed stone, crushed slag, or washed gravel meeting the physical requirements of ASTM D692, the quality requirements of **903.25**, and the gradation requirements specified for Size 6, 7, 8, 57, or 78 in **903.22**.

903.18

903.18 Reserved

903.19 Lightweight Aggregates for Structural Concrete

Provide lightweight aggregate conforming to AASHTO M 195, with the following additions:

1. Produce the lightweight aggregate by fusing raw shale, slate, or clay in a rotary kiln.
2. The lightweight coarse aggregate shall conform to the gradation requirements for size 3/4 inch to No. 4, as shown in Table 1 of AASHTO M 195.
3. The aggregate shall meet the quality requirements in **903.25**.
4. Concrete with approximately 6% air content made from the aggregate shall have a minimum durability factor of 90% when tested in accordance with AASHTO T 161.
5. Use material listed on the Department's Producer List.

903.20 Stockpiling Aggregates

Clean and grub sites for aggregate stockpiles before storing aggregates, and ensure the ground is firm, smooth, and well-drained. Maintain a cover of at least 3 inches of aggregate to prevent contamination by soil or foreign material. Build the stockpiles in layers not exceeding 4 feet in height and have each layer completely in place before starting the next layer to prevent segregation. Deposit the material to prevent coning, except in the case of aggregate composed essentially of material finer than the No. 4 sieve and base material.

Do not dump, cast, or push material over the sides of stockpiles, except in the case of aggregate for base material and fine aggregate materials.

Unless otherwise approved, store aggregates from different sources or of different gradings, or that differ in specific gravity by more than 0.03, in separate stockpiles. To prevent the aggregates from mixing, either locate stockpiles of different types or sizes of aggregates far enough apart or separate them with suitable walls or partitions.

When building stockpiles, only operate trucks or other equipment on a stockpile in a manner approved by the Engineer. Use stockpiling methods that will prevent both excessive degradation of the aggregate and contamination of the stockpile with foreign matter. The Engineer will determine excessive degradation by conducting sieve tests of samples taken from any portion of the stockpile over which equipment has operated; failure of such samples to meet all gradation requirements for the aggregate is cause for discontinuing such stockpiling procedure.

903.21 Test Methods

In stating requirements for most materials in **903**, reference has been made to AASHTO and ASTM Standard Specifications for materials. The current AASHTO or ASTM Standard Specification effective at the time of letting for a Contract shall be the governing specification. Those Specifications, in turn, include reference to the respective AASHTO and ASTM methods of sampling and testing. In a few instances, however, properties of materials in **903** have been specified without reference to corresponding AASHTO and ASTM Standard Specifications. In such instances, the methods of sampling and testing specified in Table 903.21-1 will govern.

Table 903.21-1: Aggregate Sampling and Testing Methods

Test	Test Method
Unit Weight	AASHTO T 19
Percentage of Wear	AASHTO T 96
Soundness	AASHTO T 104
Liquid Limit	AASHTO T 89
Plastic Limit and Plasticity Index	AASHTO T 90
Sieve Analysis	AASHTO T 27
Hydrometer Analysis	AASHTO T 88
Material Passing No. 200 Sieve in Aggregate	AASHTO T 11
Ten Minute Boil Test	407.03.E.2
Resistance to Plastic Flow by Marshall Method	AASHTO T 245 ⁽¹⁾

⁽¹⁾ Use a mechanically operated hammer with a rotating base. The compaction hammer shall have a slanted, circular tamping face. The slant on the face shall be 1.6% + 0.0/-0.1.

903.22 Sizes of Coarse Aggregate

Provide coarse aggregate meeting the gradation requirements of AASHTO M 43.

Table 903.22-1: Standard Sizes of Processed Aggregate

Size	Nominal Size, Square Openings	Amounts Finer than Each Laboratory Sieve (Square Openings), Percent by Weight														
		4"	3-1/2"	3"	2-1/2"	2"	1-1/2"	1"	3/4"	1/2"	3/8"	No.4	No.8	No.16	No.50	No.100
1	3-1/2" - 1-1/2"	100	90-100	--	25-60	--	0-15	--	0-5	--	--	--	--	--	--	--
2	2-1/2" - 1-1/2"	--	--	100	90-100	35-70	0-15	--	0-5	--	--	--	--	--	--	--
24	2-1/2" - 3/4"	--	--	100	90-100	--	25-60	--	0-10	0-5	--	--	--	--	--	--
3	2"-1"	--	--	--	100	90-100	35-70	0-15	--	0-5	--	--	--	--	--	--
357	2" - No. 4	--	--	--	100	95-100	--	35-70	--	10-30	--	0-5	--	--	--	--
4	1-1/2" - 3/4"	--	--	--	--	100	90-100	20-55	0-15	--	0-5	--	--	--	--	--
467	1-1/2" - No. 4	--	--	--	--	100	95-100	--	35-70	--	10-30	0-5	--	--	--	--
5	1" - 1/2"	--	--	--	--	--	100	90-100	20-55	0-10	0-5	--	--	--	--	--
56	1" - 3/8"	--	--	--	--	--	100	90-100	40-85	10-40	0-15	0-5	--	--	--	--
57	1" - No. 4	--	--	--	--	--	100	95-100	--	25-60	--	0-10	0-5	--	--	--
6	3/4" - 3/8"	--	--	--	--	--	--	100	90-100	20-55	0-15	0-5	--	--	--	--
67	3/4" - No. 4	--	--	--	--	--	--	100	90-100	--	20-55	0-10	0-5	--	--	--
68	3/4" - No. 8	--	--	--	--	--	--	100	90-100	--	30-65	5-25	0-10	0-5	--	--
7	1/2" - No. 4	--	--	--	--	--	--	--	100	90-100	40-70	0-15	0-5	--	--	--
78	1/2" - No. 8	--	--	--	--	--	--	--	100	90-100	40-75	5-25	0-10	0-5	--	--
8	3/8" - No. 8	--	--	--	--	--	--	--	--	100	85-100	10-30	0-10	0-5	--	--
89	3/8" - No. 16	--	--	--	--	--	--	--	--	100	90-100	20-55	5-30	0-10	0-5	--
9	No. 4 - No. 16	--	--	--	--	--	--	--	--	--	100	85-100	10-40	0-10	0-5	--
10	No. 4 - 0 (1)	--	--	--	--	--	--	--	--	--	100	85-100	--	--	--	10-30

(1) Screenings

903.23 Reserved**903.24 Aggregates for Riding Surfaces (Polish-Resistant Aggregates)**

Provide coarse aggregate consisting of crushed gravel, crushed granite, crushed slag, crushed quartzite, crushed gneiss, or crushed sandstone. Other crushed aggregate may be used provided it has the chemical, physical, and performance characteristics specified in Table 903.24-1.

Table 903.24-1: Quality Requirements for Type I, II, III, and IV Aggregate

Aggregate Property	Test Method	Type I (all roads)	Type II (all roads)	Type III (15,000 ADT max, excluding Interstates)	Type IV (5,000 ADT max)
Silica Dioxide Content, % min	ASTM C25	40%	30%	20%	10%
Calcium Carbonate Content, % max		32%	--	--	--
Acid Insoluble Residue, % min	ASTM D3042	50%	35%	25%	--
British Pendulum Number, ⁽¹⁾ min	AASHTO T 278 AASHTO T 279	30	30	25	22

⁽¹⁾ After 9 hours of accelerated polishing using the British Wheel in accordance with AASHTO T 279

In addition to the requirements specified in Table 903.24-1, Type II, III, and IV aggregates shall have met the preapproval process of the Division of Materials and Tests. All aggregate types must also maintain a satisfactory level of field performance to remain an approved source.

Process and stockpile the material as an independent and separate operation. The Engineer will sample and test each stockpile for approval prior to use.

903.25

903.25 Aggregate Quality Requirements

Table 903.25-1: Fine Aggregate Quality Requirements

Application	Sodium Sulfate Soundness Loss AASHTO T 104, %max	L A Abrasion AASHTO T 96, %max	Absorption AASHTO T 84, %max
Concrete (903.01)	10	40 ⁽¹⁾	N/A
Mortar (903.02)	10	N/A	N/A
Hot Mix Asphalt Mix Base and Leveling Courses (903.06)	12	40 ⁽¹⁾	N/A
Hot Mix Asphalt Surface Courses (903.11)	12	40 ⁽¹⁾	N/A
Slurry Seal (903.12)	12	40 ⁽¹⁾	N/A
Microsurface (903.12)	12	40 ⁽¹⁾	N/A

⁽¹⁾Applicable for fine aggregate manufactured from limestone or dolomite.

Table 903.25-2: Coarse Aggregate Quality Requirements

Application	Sodium Sulfate Soundness Loss AASHTO T 104, %max	L A Abrasion AASHTO T 96, %max	Absorption AASHTO T 85, %max
Concrete (903.03)	9	40	5
Mineral Aggregate Base – Type A (903.05)	15	50	N/A
Mineral Aggregate Base – Type B (903.05)	20	50	N/A
Recycled Concrete Aggregate (903.05)	N/A	50	N/A
Hot Mix Asphalt Mix Base and Leveling Courses (903.06)	9	50	5 ^{(1) (2)}
Hot Mix Asphalt Surface Courses (903.11)	9	40	5 ^{(1) (3)}
Bituminous Seal Coat (903.13)	12	40	N/A
Double Bituminous Surface Treatment (903.14)	12	40	N/A
Aggregate Cement Base Course (903.15)	15	50	N/A
Underdrains (903.17)	12	50	N/A
Lightweight Concrete (903.19)	9	40	10
Machined Riprap (709.02)	12	N/A	N/A
Graded Solid Rock (203.02)	12	N/A	N/A
Solid Rock (203.02)	12	N/A	N/A
Masonry Stone (921.07)	12	N/A	N/A

⁽¹⁾ To be based on the properties of the combined coarse aggregate blend.
⁽²⁾ For Grading CW only.
⁽³⁾ Maximum absorption for OGFC is 3.0%.

904.01

SECTION 904 – BITUMINOUS MATERIALS

904.01 Asphalt Cements	930
904.02 Reserved.....	931
904.03 Emulsified Asphalts	931

904.01 Asphalt Cements

Only obtain asphalt cement for use on Department projects from Certified Asphalt Suppliers that are on the Department’s Producer List.

Asphalt cement shall conform to AASHTO M 320 and Department procedures. Direct Tension testing is not required.

Instead of PG 64-22, the Contractor may use asphalt cement graded to PG 67-22. PG 67-22 shall conform to the requirements of AASHTO M 320 when the applicable tests are conducted at 67 °C and -12 °C, and the dynamic shear of the rolling thin film, pressure aged vessel sample is tested at 26.5 °C.

To modify the asphalt, properly blend one or more modifier(s) consisting styrene butadiene (SB), styrene butadiene styrene (SBS), styrene butadiene rubber (SBR), or Ground Tire Rubber (GTR) to a PG 64-22 or PG 67-22 base asphalt. The use of Re-refined Engine Oil Bottoms (REOB) or Vacuum Tower Asphalt Extender (VTAE) is prohibited.

GTR used to modify asphalt shall meet the requirements of **921.17**. Blending of GTR into asphalt cement shall occur only at the asphalt terminal.

Polyphosphoric acid may be used as a modifier but shall not exceed 0.5% by weight of asphalt binder and may only be used when the primary modifier is one of the styrene-based products listed above.

In addition to the above, asphalt cement modified with GTR shall meet the following requirement. The temperature difference determined by the Separation Test shall not exceed 15 °F. The separation test shall consist of taking the difference in softening point, as determined by the Ring and Ball Test (AASHTO T 53), between the top and bottom thirds of a specimen prepared per ASTM D7173.

In addition to the above requirements, the asphalt cements shall meet the requirements specified in Table 904.01-1.

Table 904.01-1: Requirements for Asphalt Cement

Property*	PG 64-22, PG 67-22	PG 70-22	PG 76-22	PG 82-22
Non-recoverable creep compliance at 3.2 kPa, Jnr(3.2), kPa ⁻¹ at 64°C, Max	4.5	1.0	0.5	0.5
% Difference in non-recoverable creep compliance, Jnr(diff) at 64°C, %, Max	75	75**	N/A	N/A

* Tested in accordance with AASHTO T 350.
** Shall be waived if Jnr(3.2) is equal to or less than 0.5

PG 76-22 and PG 82-22 grade asphalts shall meet the requirements for Indication of Elastic response as defined in AASHTO R 92. PG 70-22 grade asphalts shall have a minimum percent recovery at 3.2 kPa of 29%.

Furnish certifications to the Engineer for all shipments utilized in the work, stating that the asphalt cement provided meets the Department's specification. Ensure that quality control and compliance testing are completed in accordance with the asphalt supplier's approved quality control plan and Department procedures. Identify on the certification, the type(s) of modifier used.

In addition, the asphalt cement supplier shall provide a temperature-viscosity curve for PG 64-22 and PG 67-22 asphalt cements with a recommended mixing temperature range. In order to develop a temperature-viscosity curve, it may be necessary to run the viscosity test at a higher temperature, based on the softening point of the modified asphalt cement.

904.02 Reserved

904.03 Emulsified Asphalts

Provide emulsified asphalts meeting the test requirements specified in Table 904.03-1.

904.03

Table 904.03-1(a): Test Requirements for Emulsified Asphalt

Practices	AASHTO Test Method	CAE-P	CSS-1	CSS-1H	SS-1H	CQS-1H
Saybolt-Furol Viscosity @ 77 °F, seconds	T59	10-50	20-100	20-100	20-100	20-100
Saybolt-Furol Viscosity @ 122 °F, seconds	T59	n/a	n/a	n/a	n/a	n/a
Storage Stability Test, 24-h, %	T59	1 Max	1 Max	1 Max	1 Max	n/a
5-day Settlement, %	T59	n/a	n/a	n/a	n/a	n/a
Particle Charge	T59	Positive	Positive	Positive	n/a	Positive
Sieve Test, %	T59	0.1 Max	0.1 Max	0.1 Max	0.1 Max	0.1 Max
Residue by	T59	Distillation	Distillation	Distillation	Distillation	Distillation
Residue, %	T59	n/a	57 Min	57 Min	57 Min	62 Min
Demulsibility, %	T59	n/a	n/a	n/a	n/a	n/a
Distillate, %	T59	55 Max	n/a	n/a	n/a	n/a
Oil Test, %	T59	12 Max	n/a	n/a	n/a	n/a
Stone Coating	T59	n/a	n/a	n/a	n/a	n/a
Float Test, seconds	T50	n/a	n/a	n/a	n/a	n/a
Penetration	T49	300 Min	100-250	40-90	40-90	40-90
Elastic Recovery, % ⁽¹⁾	T301	n/a	n/a	n/a	n/a	n/a
Ductility @ 77 °F, cm	T51	40 Min	40 Min	40 Min	40 Min	40 Min
Ductility @ 40 °F, cm	T51	n/a	n/a	n/a	n/a	n/a
R&B Softening Point, °F	T53	n/a	n/a	n/a	n/a	n/a
Original G*/sind @ 82 °C	T315	n/a	n/a	n/a	n/a	n/a

⁽¹⁾ Straight-sided mold, 20-cm elongation, 5 min hold, 25 °C

Table 904.03-1(b): Test Requirements for Emulsified Asphalt

Practices	AASHTO Test Method	CQS-1HP	SS-1	AEP	CRS-2	AE3
Saybolt-Furol Viscosity @ 77 °F, seconds	T59	20-100	20-100	10-50	n/a	n/a
Saybolt-Furol Viscosity @ 122 °F, seconds	T59	n/a	n/a	n/a	100-400	50 Min
Storage Stability Test, 24- h, %	T59	n/a	1 Max	n/a	1 Max	n/a
5-day Settlement, %	T59	n/a	n/a	5 Max	n/a	5 Max
Particle Charge	T59	Positive	n/a	n/a	Positive	n/a
Sieve Test, %	T59	0.1 Max	0.1 Max	0.1 Max	0.1 Max	n/a
Residue by	T59	Distillation ⁽¹⁾	Distillation	Distillation	Distillation	Distillation
Residue, %	T59	62 Min	57 Min	n/a	65 Min	n/a
Demulsibility, %	T59	n/a	n/a	n/a	40 Min	n/a
Distillate, %	T59	n/a	n/a	55 Max	n/a	30 Max
Oil Test, %	T59	n/a	n/a	12.0 Max	3.0 Max	6.0 Max
Stone Coating	T59	n/a	n/a	n/a	n/a	90 Min
Float Test, seconds	T50	n/a	n/a	20 Min	n/a	200 Min
Penetration	T49	40-90	100-200	n/a	100-250	n/a
Elastic Recovery, % ⁽²⁾	T301	n/a	n/a	n/a	n/a	n/a
Ductility @ 77 °F, cm	T51	70 Min	40 Min	n/a	40 Min	n/a
Ductility @ 40 °F, cm	T51	n/a	n/a	n/a	n/a	n/a
R&B Softening Point, °F	T53	135 Min	n/a	n/a	n/a	n/a
Original G*/sind @ 82 °C	T315	n/a	n/a	n/a	n/a	n/a

⁽¹⁾ Distill at 350 °F

⁽²⁾ Straight-sided mold, 20-cm elongation, 5 min hold, 25 °C

904.03

Table 904.03-1(c): Test Requirements for Emulsified Asphalt

Practices	AASHTO Test Method	CRS-2P	RS-2	RS-1
Saybolt-Furol Viscosity @ 77 °F, seconds	T59	n/a	n/a	20-100
Saybolt-Furol Viscosity @ 122 °F, seconds	T59	100-400	75-400	n/a
Storage Stability Test, 24- h, %	T59	1 Max	1 Max	1 Max
5-day Settlement, %	T59	n/a	n/a	n/a
Particle Charge	T59	Positive	n/a	n/a
Sieve Test, %	T59	0.1 Max	0.1 Max	0.1 Max
Residue by	T59	Evaporation	Distillation	Distillation
Residue, %	T59	65 Min	63 Min	55 Min
Demulsibility, %	T59	40 Min	60 Min	60 Min
Distillate, %	T59	n/a	n/a	n/a
Oil Test, %	T59	n/a	n/a	n/a
Stone Coating	T59	n/a	n/a	n/a
Float Test, seconds	T50	n/a	n/a	n/a
Penetration	T49	75-175	100-200	100-200
Elastic Recovery, % ⁽¹⁾	T301	50 Min	n/a	n/a
Ductility @ 77 °F, cm	T51	40 Min	40 Min	40 Min
Ductility @ 40 °F, cm	T51	n/a	n/a	n/a
R&B Softening Point, °F	T53	125 Min	n/a	n/a
Original G*/sind @ 82 °C	T315	n/a	n/a	n/a

⁽¹⁾ Straight-sided mold, 20-cm elongation, 5min hold, 25 °C

The producer may conduct a 24-hour (1% Max) storage stability test instead of the 5-day settlement test if the emulsions are to be used within 5 days.

Obtain emulsified asphalts for use on Department projects from Certified Emulsified Asphalt Suppliers that are on the Department's Producer List.

All emulsified asphalts shall be homogeneous and shall adhere firmly to the surface of the mineral aggregate. Failure of the emulsified asphalt to perform satisfactorily on the job is cause for rejection, regardless of its ability to pass laboratory tests.

Use the AE-3 of such stability that it will remain constant and uniform while being mixed with dry or approximately dry aggregate, and that will thoroughly and uniformly coat the entire surface of each fragment while being manipulated and incorporated into the Work. The emulsified asphalt after being incorporated into the Work shall show no signs of re-emulsifying.

Use latex, polymer, and other emulsifiers of styrene butadiene rubber (SBR) or natural latex when manufacturing CQS-1hp. Mill such emulsifiers into the asphalt cement to show no separation after mixing.

When using modified emulsions in micro-surface mixtures, the blended mixture when combined with aggregate and mineral filler shall be:

1. Capable of filling up to 1/2 inch wheel ruts in one pass;
2. Capable of field regulation of the setting time; and
3. Suitable for nighttime placement.

Combine the latex with the asphalt emulsion at the emulsion mill to produce a homogeneous mixture. Latex modified emulsions, upon standing undisturbed for a period of 24 hours, shall have a uniform color throughout, showing no color striations.

905.01

SECTION 905 – JOINT MATERIALS

905.01	Preformed Joint Fillers (Non-Extruding and Resilient Types).....	936
905.02	Joint Mortar.....	936
905.03	Rubber Gaskets	937
905.04	Hemp or Oakum Gaskets	937
905.05	Joint Sealants.....	937

905.01 Preformed Joint Fillers (Non-Extruding and Resilient Types)

Provide preformed joint fillers as shown on the Plans. When designated, punch holes in preformed joint filler to admit the dowels.

Furnish the filler for each joint in a single piece for the full depth and width required for the joint unless otherwise directed by the Engineer. If the Engineer approves the use of more than one piece for a joint, fasten the abutting ends securely, and hold to shape by stapling or using other positive means of fastening satisfactory to the Engineer.

A. Bituminous Type

Provide bituminous type preformed joint fillers conforming to AASHTO M 213.

B. Non-Bituminous Types

Provide non-bituminous types of preformed joint filler conforming to AASHTO M 153, Type I, II, or III, as specified.

C. Polypropylene Foam Type

Provide semi-rigid, closed-cell, polypropylene foam, preformed expansion joint filler conforming to ASTM D8139.

905.02 Joint Mortar

Provide pipe joint mortar consisting of one part Portland cement and two parts sand, adding water as necessary to obtain the required consistency. Use Portland cement conforming to the requirements of **901.01**, Type I, and sand

conforming to the requirements of **903.02**. Obtain the Engineer's approval of the water quality. Use mortar within 30 minutes after its preparation.

905.03 Rubber Gaskets

Provide gaskets conforming to ASTM C443.

905.04 Hemp or Oakum Gaskets

Provide gaskets of hemp or oakum packing for joint filler that are closely twisted, and of the size and type required for the pipe under construction. Gaskets shall be in one piece of sufficient length to pass around the pipe and lap.

905.05 Joint Sealants

A. Sealing Longitudinal Joints between Portland Cement and Asphaltic Concrete

To seal the longitudinal joint between Portland cement and asphaltic concrete, use hot-poured elastic type sealants that comply with the following requirements:

1. Use hot poured elastic type sealants conforming to ASTM D6690, with the following exceptions:
 - a. The joint sealer shall be a mixture of virgin synthetic rubber, reclaimed rubber, or a combination of these materials with asphalt and plasticizers and tackifiers.
 - b. Do not use ground cured rubber scrap.
 - c. The sealer shall be free of foreign material and, when melted, free of lumps.

Furnish the Engineer a certified statement from the manufacturer indicating compliance with the above composition.

2. The flow at 140 °F shall not exceed 0.4 inch in 5 hours. Ductility at 77 °F shall be not less than 16 inches, when tested in accordance with AASHTO T 51.

905.05

3. Furnish the Engineer a certified copy of the test results, showing the batch number and indicating that the material supplied conforms to the requirements of the specifications.

B. Sealing Longitudinal and Transverse Joints and Random Cracks in PCC Pavement

To seal longitudinal and transverse joints and random cracks in Portland cement concrete pavement, use one of the following materials, as shown on the Plans:

1. Hot poured elastic type sealant meeting the requirements of **905.05.A.**
2. Silicone sealant having a low modulus silicone that is specially manufactured to seal Portland cement concrete pavements joints. Furnish silicone sealant in a one part silicone formulation that is non-acid curing and meets the requirements specified in Table 905.05-1.

Table 905.05-1: Requirements for Silicone Sealants

Property	Test Method	Value
Flow	MIL S 8802	5 inches, maximum
Extrusion rate	MIL S 8802	90-250 grams per minute
Tack free time ⁽¹⁾	SAE-AMS-S-8802	35-75 minutes
Specific gravity	ASTM D792, Method A	1.010-1.515
Durometer hardness Shore A ⁽¹⁾	ASTM D2240	10-25
Joint movement and tensile stress at 150% elongation ⁽¹⁾	ASTM D 412, Die C	± 50% joint movement; 75 psi maximum tensile stress
Peel (Adhesion): Unprimed aluminum panel with aluminum screen ⁽¹⁾	MIL S 8802	20 pounds, minimum, with at least 75% cohesive failure
Bond to concrete mortar concrete briquets air cured 7 days at 77 ± 3 °F ⁽²⁾	AASHTO T 132	50 psi, minimum
⁽¹⁾ 7-day cure at 77 ± 3 °F and 45-55% relative humidity ⁽²⁾ Determine the bond to concrete mortar by molding briquets in accordance with AASHTO T 132, sawed in half and bonded with a thin section of sealant. Test the briquets in accordance with AASHTO T 132. Dry briquets to constant weight in an oven at 212 ° ±40 °F.		

If shown on the Plans, provide a backer rod (bond breaker) that is compatible with the sealant and will ensure no bond or reaction will occur between the rod and the sealant.

Use joint fillers and sealants selected from the Department's QPL. Certify that the product meets the applicable specifications and that the material is identical to that previously tested and placed on the QPL.

The Department reserves the right to perform any testing deemed necessary to ensure compliance with these Specifications.

906.01

SECTION 906 – DAMPPROOFING AND WATERPROOFING MATERIALS

906.01 General..... 940
906.02 Class I Dampproofing and Waterproofing 940
906.03 Class II Dampproofing and Waterproofing..... 940
906.04 Bridge Deck Sealants 941

906.01 General

This Section covers materials used in dampproofing and waterproofing concrete surfaces.

Provide the Class of waterproofing shown on the Plans or as otherwise specified or directed.

906.02 Class I Dampproofing and Waterproofing

Provide materials conforming to the following:

- 1. Asphalt seal for use below ground level: ASTM D449, Type I
- 2. Asphalt seal for use above ground level: ASTM D449, Type II or Type III, as specified
- 3. Bituminous fabric: ASTM D173

906.03 Class II Dampproofing and Waterproofing

Provide materials conforming to the following:

- 1. Asphalt seal for use below ground level: ASTM D449, Type I
- 2. Asphalt seal for use above ground level: ASTM D449, Type II or Type III, as specified
- 3. Bituminous fabric: ASTM D173
- 4. Plain asphalt plank: ASTM D517, Type I

906.04 Bridge Deck Sealants**A. System A**

- 1. Membrane.** Provide a membrane laminate formed with suitably plasticized coal tar and reinforced with non-woven synthetic fibers or glass fibers. The membrane shall be a uniformly well-manufactured product, free from blemishes, discontinuities, and other defects. Furnish the membrane in rolls, having a width of 30 or 48 inches or other widths as approved by the Engineer. Ensure that the membrane conforms to the requirements specified in Table 906.04-1.

Table 906.04-1: Requirements for Membrane (System A)

Property	Test Method	Value
Thickness	-	70 ± 5 mils
Pliability 180-degree Bend over 1/4-inch mandrel at -25 °F	ASTM D146	No cracks
Softening Point (minimum)	ASTM D36 (R & B)	230 °F

- 2. Mastic.** Use a cold-applied type mastic, recommended by the membrane manufacturer, that is compatible with the membrane.

B. System B

- 1. Membrane.** Provide a laminate of rubberized asphalt, reinforced with synthetic fibers or mesh. The membrane shall be a uniformly well-manufactured product, free from blemishes, discontinuities, and other defects. Furnish membrane in rolls having a width of 36 inches or other widths as approved by the Engineer. Ensure that the membrane conforms to the requirements specified in Table 906.04-2.

906.04

Table 906.04-2: Requirements for Membrane (System B)

Property	Test Method	Value
Thickness (minimum)	--	65 mils
Tensile strength (minimum)	ASTM D882	300 psi
Elongation at Break (minimum)	ASTM D882	150%
Pliability 180-degree Bend over 1/4-inch mandrel at -25 °F	ASTM D146	No cracks
Peel Adhesion, 7 days at 120 °F +7 days water immersion (minimum)	TT-S-00230 Modified	5 psi

- 2. Mastic.** Use a cold-applied type mastic, recommended by the membrane manufacturer, that is compatible with the membrane.

Provide bridge deck sealants listed on the Department's QPL. Prior to approval and use of the materials for bridge deck sealant, submit to the Materials and Test Engineer a notarized certification by the formulator of these materials, stating that the materials proposed for use, or materials of identical formulation, have been tested and meet all the specified requirements. Include with this notarized certification a certified laboratory test report, containing numerical test data of all the specified requirements, for the materials, or materials of identical formulation, proposed for use, and a sample of the proposed materials for preliminary evaluation. The approval granted based on these certifications will remain in effect until such time that the formulation is changed or the Materials and Tests Engineer requires, at its discretion, requalification of the materials for use, in which event the qualifying procedure shall be repeated.

Submit a certification from the manufacturer of the materials with each subsequent shipment of materials. The certification shall identify the shipment by lot or batch number, state the quantity of material shipped, and state that the material is identical to a lot or batch number (designate) that the Department previously qualified for use.

The Department reserves the right to require samples of all materials to be submitted to the Laboratory for testing.

SECTION 907 – CONCRETE REINFORCEMENT

907.01 Bar Reinforcement for Concrete Structures	943
907.02 Dowel and Tie Bars	943
907.03 Welded Wire Reinforcement	944
907.04 Prestressing Reinforcement Steel and Anchorages	944

907.01 Bar Reinforcement for Concrete Structures

Unless otherwise specified, for all steel reinforcement for concrete, provide billet steel bars conforming to the requirements of ASTM A615, Grade 60. Use standard CRSI hook details unless otherwise shown on the Plans. Provide epoxy-coated reinforcing steel that is listed on the Department's QPL.

Package, in an airtight container, a representative 8-ounce sample of the coating material from each batch, identify it by batch number, and furnish to the Engineer. In addition, for repair of any damage incurred during shipment or installation, the fabricator initially shall furnish to the Project a repair kit containing a touch-up roller and 16 ounces of touch-up coating material with each shipment of epoxy coated reinforcing steel, with additional supplies being furnished as needed.

Provide metal chairs and supports coated with plastic, epoxy, or other approved material that is chemically and electrically inert in concrete. Provide plastic-coated tie wires for use with epoxy-coated reinforcing steel. Obtain the Engineer's approval of such tie wires before use.

907.02 Dowel and Tie Bars

Provide plain dowel bars conforming to ASTM A36 or A615. Use paint meeting the requirements of SSPC Paint Specification No. 15, Type 1 (red oxide paint) or SSPC Paint Specification No. 25. For plastic coated dowels, meet the coating requirements of AASHTO M 254. For epoxy coated dowels, meet the coating requirements of ASTM D3963.

Provide bond breakers, of the type recommended by the coating manufacturer, for all dowel bars except for Type A coated dowels conforming to AASHTO M 254.

907.03

Provide deformed tie bars conforming to ASTM A615.

907.03 Welded Wire Reinforcement

Provide welded wire reinforcement conforming to ASTM A1064. Refer to the Plans for gauges, spacing, and arrangement of wires and coating.

907.04 Prestressing Reinforcement Steel and Anchorages

Assign a lot number to all wire, strand, and bars, and tag them for identification purposes. Likewise, identify anchorage assemblies, and provide certification that the assemblies meet the Post-Tensioning Institute's *Acceptance Standards for Post-Tensioning Systems*.

Furnish a minimum of two samples from each lot or shipment received. Furnish additional samples as directed by the Engineer.

The Engineer will base acceptance of the steel on the results of physical tests conducted by the Department and a manufacturer's certification showing results of the required tests, including stress-strain curves representative of the lot to be used.

Provide wire that is free from injurious defects and that has a workmanlike finish with a smooth surface. The Engineer will reject material that shows injurious defects during or prior to its installation in the Work.

In addition to the above, the prestressing steel and anchorages for post-tensioned tendons shall comply with the following requirements:

A. Seven-Wire Strand for Prestressed Concrete

Provide strand conforming to ASTM A416 for the Grade specified. The strand manufacturer shall certify that the strand has been tested and will bond to concrete of normal strength and consistency in conformance with the prediction equations for transfer and development lengths given in ACI/AASHTO Specifications.

B. Parallel Wire Assemblies for Post-Tensioning

Provide assemblies consisting of parallel wires of the number and size shown on the Plans. Wires shall be high-tensile, hard-drawn, stress-relieved, and uncoated, and shall conform to ASTM A421.

C. Bars for Post-Tensioning

Stress-relieve high tensile strength alloy bars, and then cold-stretch to a minimum of 130,000 pounds per square inch. After cold-stretching, the bars shall meet the physical properties specified in Table 907.04-1.

Table 907.04-1: Physical Properties for Post-Tensioning Bars

Property	Value
Minimum ultimate tensile strength	145,000 psi
Minimum yield strength, measured by the 0.7% extension-under-load method	130,000 psi
Minimum modulus of elasticity	25,000,000 psi
Minimum elongation in 20 bar diameters after rupture	4%
Diameter tolerance	+0.03 inch/-0.01 inch

D. Anchorages for Post-Tensioned Tendons

- 1. For Bars.** Use wedge type anchorages that will develop the minimum ultimate stress specified for the nominal bar area. Wedge type anchorages shall bear against anchorage plates fabricated of hot rolled steel of type and quality approved by the Engineer.
- 2. For Parallel Wire Assemblies.** Unless otherwise specified, use wedge type anchorages of the sandwich plate or conical type, that can develop the ultimate strength of the total number of wires anchored. Embed conical type anchorages within the ends of the concrete members unless otherwise specified. Generally, anchorages shall bear against embedded grids of reinforcing steel approved by the Engineer.
- 3. Alternate Types.** The Contractor may use alternate anchorage types conforming to the general physical requirements specified above for wedge type anchorages if approved by the Engineer.

Before obtaining the Engineer's approval, demonstrate alternate type anchorages are capable of withstanding at least 3,000,000 cycles of twice the maximum live load stress.

908.01

SECTION 908 – STRUCTURAL STEEL AND APPURTENANT MATERIALS

908.01	Structural Steel	946
908.02	Plate for Cold Working	946
908.03	Permanent Steel Bridge Deck Forms	947
908.04	High Strength Structural Bolts	947
908.05	Cast Steel	952
908.06	Steel Forgings	952
908.07	Gray Iron Castings	952
908.08	Malleable Castings	953
908.09	Bronze Bearing Plates, Plain.....	953
908.10	Bronze Bearing Plates, Self-Lubricating.....	953
908.11	Corrosion Resistant Steel	953
908.12	Elastomeric Bearing Pads	953
908.13	Copper Sheet for Flashing.....	954
908.14	Pig Lead	954
908.15	Structural Steel Piles	954
908.16	Steel Shells.....	954
908.17	Steel Pipes.....	954

908.01 Structural Steel

Unless otherwise specified, provide steel plate conforming to ASTM A709, Grade 50 or 50W, and bar stock and rolled shapes conforming to ASTM A709 Grade 50S.

908.02 Plate for Cold Working

Provide plate, that is to be bent or formed cold during fabrication, that conforms to ASTM A283, Grade C.

908.03 Permanent Steel Bridge Deck Forms

Fabricate permanent steel bridge deck forms and supports from steel conforming to ASTM A653 (SS Grades 33 through 80) and having a coating Class G 165 in accordance with ASTM A653.

908.04 High Strength Structural Bolts

Provide bolts, nuts, and washers that are manufactured in the United States, from steel smelted and manufactured in the United States, and that conform to the following requirements:

A. Specifications

Unless otherwise shown on the Plans, all bolts, nuts and washers shall be coated with acceptable coating in accordance with ASTM F3125 for the respective grade. Provide bolts, nuts, and washers that conform to the following requirements:

1. **Bolts.** ASTM F3125, Grade 325 and Grade 490 – High Strength Bolts for Structural Joints.
2. **Nuts.** ASTM A563 - Carbon and Alloy, heat treated Steel Nuts, Grades DH and DH3.
3. **Washers**
 - a. ASTM F436 – Hardened Steel Washers.
 - b. ASTM F959 – Compressible Washer Type Direct Tension Indicators for Use with High Strength Bolts.

B. Manufacturing

1. **Bolts.** Hardness for bolt diameters 1/2 to 1 inch inclusive shall be as specified in Table 908.04-1.

908.04

Table 908.04-1: Hardness Number

Bolt Size	Brinell		Rockwell C	
	Min	Max	Min	Max
1/2 to 1 inch	248	311	24	33

2. **Nuts.** Provide plain nuts of grades DH or DH3, and galvanized nuts of grade DH.
3. **Marking.** Mark all bolts, nuts, and washers in accordance with the appropriate AASHTO/ASTM Specifications.

C. Testing

Only provide high strength bolts, nuts, and washers that have been certified to have met the specified tests identified in their individual ASTM Specification designations, both as individual components, and as assemblies (bolts, nuts, and washers).

1. Bolts

- a. Perform proof load tests, in accordance with ASTM F606 Method 1, at the minimum frequency of testing specified in ASTM A325 paragraph 9.2.4.
- b. Perform wedge tests on full size bolts, in accordance with ASTM F606 paragraph 3.5, at the minimum frequency of testing specified in ASTM A325 paragraph 9.2.4.

2. **Nuts.** Perform proof load tests, in accordance with ASTM F606 paragraph 4.2, at the minimum frequency of testing specified in ASTM A563 paragraph 9.

3. **Assemblies.** The manufacturer or distributor shall perform rotational-capacity tests on all bolt, nut, and washer assemblies prior to shipping as specified in **602.17.E.1** and **602.17.E.2**.

Perform this testing for complete assemblies each day at the site of bolting in accordance with the following:

- a. Except as modified herein, perform the rotational-capacity test in accordance with the requirements of ASTM F3215 Grade A325.
- b. Test each combination of bolt production lot, nut lot, and washer lot as an assembly. Where washers are not required by the installation procedures, do not include them in the lot identification.
- c. Assign a rotational-capacity lot number to each combination of lots tested.
- d. Test a minimum of two assemblies per rotational-capacity lot.
- e. Assemble the bolt, nut, and washer assembly in a Skidmore-Wilhelm Calibrator or an acceptable equivalent device (note - this requirement supersedes the current ASTM F3125 Grade A325 requirement that the test be performed in a steel joint). For short bolts that are too short to be assembled in the Skidmore-Wilhelm Calibrator, see **908.04.C.3.i**.
- f. The minimum rotation, from a snug tight condition (10% of the specified proof load), shall be as specified in Table 908.04-2.

Table 908.04-2: Rotation from Snug Tight Condition

Bolt Length	Minimum Rotation from Snug
Up to and including 4 diameters	240 degrees (2/3 turn)
Over 4 diameters, but not exceeding 8 diameters	360 degrees (1 turn)
Over 8 diameters	480 degrees (1-1/3 turn)

(Note: These values differ from those shown in ASTM F3125.)

908.04

- g. The tension reached at the above rotation shall be equal to or greater than 1.15 times the required installation tension as specified in Table 908.04-3.

Table 908.04-3: Installation Tension and Turn Test Tension

Bolt Diameter (inches)	Required Installation Tension (kips)	Turn Test Tension (kips)
1/2	12	14
5/8	19	22
3/4	28	32
7/8	39	45
1	51	59
1-1/8	56	64
1-1/4	71	82
1-3/8	85	98
1-1/2	103	118

- h. After the required installation tension, as specified in Table 908.04-3 has been exceeded, take and record one reading of tension and torque. The torque value shall conform to the following:

$$\text{Torque} < 0.25 \text{ PD}$$

Where:

Torque = measured torque (foot-pounds)

P = measured bolt tension (pounds)

D = bolt diameter (feet)

- i. Bolts that are too short to test in a Skidmore-Wilhelm Calibrator may be tested in a steel joint. The tension requirement of **908.04.C.3.g** shall not apply. Compute the maximum torque requirement, as specified in **908.04.C.3.h**, using a value of P equal to the turn test tension shown in Table 908.04-3.

D. Documentation**1. Mill Test Report(s) (MTR)**

- a. Furnish MTR for all mill steel used in the manufacture of the bolts, nuts, and washers.
- b. In the MTR, indicate the place where the material was melted and manufactured.

2. Manufacturer Certified Test Report(s) (MCTR)

- a. Provide MCTR from the manufacturer of the bolts, nuts, and washers for the items furnished.
- b. Each MCTR shall show conformance to all applicable test requirements, the sites where tests were performed, and the date of the tests.
- c. In addition to the requirements of **908.04.D.2.a** and **908.04.D.2.b**, the manufacturer performing the rotational-capacity test shall include on the MCTR:
 1. The lot number of each of the items tested.
 2. The rotational-capacity lot number as required in **908.04.C.3.c**.
 3. The results of tests required in **908.04.C.3**.
 4. The location where the bolt assembly components were manufactured.

3. Distributor Certified Test Report(s) (DCTR)

- a. The DCTR shall include the MCTR data required in **908.04.D.2** above for the various bolt assembly components.
- b. The DCTR shall report the rotational-capacity test performed by the distributor or manufacturer.

908.05

E. Shipping

Ship bolts, nuts, and washers from each rotational-capacity lot in the same container. If there is only one production lot number for each size of nut and washer, the nuts and washers may be shipped in separate containers. Permanently mark each container with the rotational-capacity lot number to allow identification at any stage before installation.

908.05 Cast Steel

Provide steel castings conforming to ASTM A27, Grade 65-35.

908.06 Steel Forgings

Provide steel forgings conforming to ASTM A668, Class C1, Annealed. The manufacturer shall furnish the Engineer a record of the annealing charges, showing the forgings in each charge, the melt or melts from which they were secured, the chemical analyses of the respective melts, and the details of the annealing treatment.

908.07 Gray Iron Castings

Provide castings of the type specified and within reasonably close conformity with the dimensions shown on the Plans. The castings shall conform to AASHTO M 105, with the following additions:

1. Unless otherwise specified, all castings shall be Class 30.
2. Cast test bars for tension testing in accordance with AASHTO M 105, Table 2, Test Bar B.
3. Clean all castings of sand and scale by sand blasting or other effective methods to present a smooth, clean, and uniform surface.
4. Cast the date of manufacture into all gray iron castings.
5. The lid and lid seat of the rim of manhole castings shall be machined to form a true bearing.
6. All castings shall weigh at least 95% of the theoretical weight shown on the Plans.

Furnish the Engineer a certification from the manufacturer identifying each heat number and certifying that the requirements from AASHTO M 105 and the above additions have been met.

908.08 Malleable Castings

Provide castings conforming to ASTM A47, Grade 35018.

908.09 Bronze Bearing Plates, Plain

Provide plates conforming to ASTM B22, Alloy UNS No. C 91100, or ASTM B100, Alloy No. 510.

908.10 Bronze Bearing Plates, Self-Lubricating

Prepare plates from metal conforming to **908.09**. Provide plates with trepanned or drilled recesses (not grooves) to the extent of not less than 25% of their surface areas. The recesses shall be filled by pressure to produce dense non-plastic, lubricating inserts consisting of graphite and metallic substances, held together by a lubricating binder. With each lot of plates, the manufacturer shall supply additional lubricating material in stick form for applying to the surfaces of the steel plates that bear on and move over the lubricating bronze plates.

Furnish the plates from standard production stock by approved manufacturers.

908.11 Corrosion Resistant Steel

Provide corrosion resistant steel conforming to ASTM A588.

Furnish the Engineer a certification from the manufacturer that covers each heat number to be used in the Work and that clearly shows that all requirements of this Specification have been met.

908.12 Elastomeric Bearing Pads

For use as bearings for bridge beams, provide elastomeric bearing pads conforming to Section 18 of the AASHTO LRFD Bridge Construction Specifications.

908.13

Unless otherwise specified, provide bearing pads having a shear modulus between 0.080 and 0.175 ksi.

The manufacturer shall provide certified reports on the lot from which each shipment is made, based on tests conducted in its own laboratory or a commercial laboratory designated or approved by the Engineer.

908.13 Copper Sheet for Flashing

Provide sheet copper conforming to ASTM B152 and having a weight per square foot as shown on the Plans.

908.14 Pig Lead

Provide pig lead, conforming to ASTM B29, of common desilverized lead.

908.15 Structural Steel Piles

Provide rolled steel sections of the weight and shape shown on the Plans and that meet the requirements of ASTM A572 or A992, Grade 50 (H-piles) and ASTM A252, Grade 2 or 3 (pipe piles). Do not use steel manufactured by the acid-bessemer process. Ensure that steel piles, when placed in the leads, will not exceed the camber and sweep permitted by the allowable mill tolerance. The Engineer will reject piles that are bent or otherwise damaged.

908.16 Steel Shells

Use steel shells of sufficient strength and rigidity to withstand being driven and to prevent harmful distortion caused by soil pressures or the driving of adjacent piles. Ensure that the shells are sufficiently tight to exclude water during the placing of concrete. The tip and butt diameters shall be as shown on the Plans. Equip shells to be driven without a mandrel with heavy steel driving points. Ensure that the driving points and the connecting welds do not project beyond the perimeter of the pile tips.

908.17 Steel Pipes

Steel pipe to be filled with concrete shall conform to ASTM A252, Grade 2. Closure plates for closed end piles shall conform to ASTM A36.

Provide pipes of the diameter shown on the Plans. The wall thickness shall not be less than that shown on the Plans, but in no case less than 3/16 inch.

908.17

Provide pipe, including end closures, of sufficient strength to be driven by the specified methods without harmful distortion. Ensure that closure plates and connecting welds do not project beyond the perimeter of the pile tips.

909.01

SECTION 909 – FENCE, GUARD RAIL AND BARRIER

909.01 Stock Fence	956
909.02 Chain Link Fence	958
909.03 Fence Gates	962
909.04 Water Gates and Water Crossings.....	964
909.05 Metal Beam Rail	964
909.06 Timber Rail	964
909.07 Guard Rail Posts.....	964
909.08 Guard Rail Hardware	964

909.01 Stock Fence

Unless otherwise specified, the Contractor may choose the type and kind of line post to use, whether wood or steel, and the finish, whether painted or galvanized. Do not change from using one type or kind to the other without the Engineer's written permission. Provide corner posts, end posts, braced line posts, and all fittings and accessories of the same kind and finish as the line post.

A. Fabric

Unless otherwise specified, provide fabric conforming to one of the following:

1. Galvanized steel woven wire meeting ASTM A116 for No. 11 Farm Design No. 1047-6-11, Class III Coating, or
2. Galvanized high tensile strength steel woven wire meeting ASTM A116 for No. 12-1/2 Farm Design, Class III Coating, except that the top and bottom strand shall be 10-1/2 gauge and the yield strength shall be equivalent to No. 11 Farm Design No. 1047-6-11.

B. Steel Posts and Braces

Provide one of the following types of steel line posts, of the lengths shown on the Plans:

1. Studded Tee posts, weighing 1.33 pounds per foot.
2. Lug-U posts, weighing 1.33 pounds per foot.

Furnish each post with a standard anchor plate securely attached to the post.

Provide the following types of end, corner, and braced line posts, of the lengths shown on the Plans:

1. 2-1/2 x 2-1/2 x 1/4 inch angle steel, weighing 4.10 pounds per foot. The braces shall be 2 x 2 x 1/4 inch angle, weighing 3.19 pounds per foot.
2. 2.0-inch (2.375 outside diameter), standard steel black or galvanized pipe, or 2.0 inch (2.375 outside diameter), triple coated steel pipe, with a 0.130-inch minimum wall thickness and coated as specified in **909.02**. Construct the braces of 1.25-inch (1.660 outside diameter) standard steel black or galvanized pipe or 1.25 inch (1.660 outside diameter) triple coated steel pipe with a 0.111-inch minimum wall thickness and coated as specified in **909.02**.

Furnish the round end, corner, and braced line posts complete with ball caps and other necessary fittings. Furnish galvanized round posts and braces that are galvanized inside and outside in accordance with ASTM F1083.

Galvanize, in accordance with ASTM A123, all steel line posts and steel angle for end, corner, and braced line posts, and braces.

Provide round posts at all corners that vary from 90 degrees.

C. Wood Posts and Braces

Provide wood posts, braces, and anchors of southern pine, oak, Douglas fir, or gum. Cut wood from sound and live trees to the dimensions and shapes shown on the Plans or as otherwise designated. Ensure that the wood contains no unsound knots. Sound knots are allowable, provided the diameter of the knot does not exceed one-third of the diameter of the piece at the point where it occurs. Trim all knots smooth with the face of the timber. The posts shall be free of decayed wood, rot, and ring shake.

909.02

The Plans show post and brace sizes in inches. The size refers to the diameter for round pieces and to the edge dimension for square pieces.

The Engineer will allow a tolerance from the dimensions shown on the Plans of 1/4 inch for sawed pieces and 1/2 inch for round pieces. A tolerance of 2% will be allowed in the length of both round and sawed posts. Saw the ends square, unless otherwise specified.

Peel round posts, braces, and anchors to remove all bark and inner skin. Provide timbers having a uniform taper with a slope not greater than 1 1/2 inches in 10 feet. The alignment shall be such that when a line is drawn from the center of the tip to the center of the butt, it shall not fall outside the center of the timber by more than 1% of the length.

Saw sawed posts, braces, and anchors with parallel edges and to not vary more than 1/4 inch from the specified dimensions, except that wane (lack of wood) not exceeding 1/8 of the dimensions of the face and 1/4 of the length of the piece on one corner or the equivalent on two or more corners will be permitted on not more than 10% of the pieces.

Treat posts, braces, and anchors with a preservative treatment, conforming to **911.02**. All preservatives must be registered with the U.S.EPA under FIFRA. Fabricate or frame the timbers before treatment.

D. Barbed Wire

Provide either galvanized or aluminum-coated barbed wire consisting of two No. 12-1/2 gauge twisted steel line wires with No. 14 gauge 4-point barbs spaced not more than 5 inches apart. The galvanized wire shall meet ASTM A121, chain link fence grade.

The Contractor may use high tensile strength wire, meeting the requirements of ASTM A121, chain link fence grade, for the respective wire size, with barb spacings as designated above.

909.02 Chain Link Fence

Unless otherwise specified, provide one of the following kinds of chain link fence fabric:

1. Zinc coated steel,
2. Aluminum coated steel, or
3. Aluminum alloy.

Do not change from using one kind of fabric to another without the Engineer's written permission.

A. Fabric

Provide fabric of the chain link type, conforming to AASHTO M 181. If galvanized, the fabric shall be of Type I, Class D. Manufacture all chain link fabric of No. 9 gauge wire pickets, forming a uniform 2-inch mesh, and to be of the height shown on the Plans or specified in the Contract.

B. Posts and Braces

- 1. Description.** Manufacture the pipe by cold rolling and electric resistance welding of steel strip conforming to ASTM A1011, ASTM A1008 and A1011, or ASTM A653, Grade D.

Provide corrosion protection to all tubing by in-line application of hot-dip galvanizing, followed by a chromate conversion coating and an electrostatically applied clear acrylic or polyester coating on the outside surface. Provide corrosion protection to the inside surface by hot-dip galvanizing or in-line application of a zinc rich paint after fabrication.

2. Protective Coatings

a. External

- i. Apply hot-dipped zinc coating according to ASTM B6 high grade and special high grade. The weight of the hot-dipped zinc coating shall be a minimum of 0.8 ounces per square foot, as determined in accordance with ASTM A90.
- ii. Provide an electrostatically applied clear acrylic or polyester coating thickness of at least 0.1 mils.

- b. Internal.** Hot-dip galvanize the interior surface with a minimum of 0.9 ounce of zinc, or apply a 0.3-mil thickness of zinc rich paint after welding. Use a coating having at least 80% zinc powder by weight and that is capable of providing galvanic protection.

Provide posts and braces conforming to one of the types specified in Table 909.02-1.

909.02

Table 909.02-1: Post and Braces

Application	Material	ASTM Specification	Nominal Diameter (inches)	Outside Diameter (inches)
Line Posts	Galvanized steel pipe	F1083	1.5	1.900
	Aluminum alloy standard (ANSI Schedule 40) pipe	B429, Alloy 6063, Temper T6	1.5	1.900
	Triple coated steel pipe with a 0.120-inch wall thickness	F1043, Group I-C	1.5	1.900
End, Corner, and Pull Posts	Galvanized standard steel pipe	F1083	2.0	2.375
	Aluminum alloy standard (ANSI Schedule 40) pipe	B429, Alloy 6063, Temper T6	2.0	2.375
	Triple coated steel pipe with a 0.130-inch wall thickness	F1043, Group I-C	2.0	2.375
End and Corner Braces	Galvanized standard steel pipe	F1083	1.25	1.660
	Aluminum alloy standard (ANSI Schedule 40) pipe	B429, Alloy 6063, Temper T6 (for corner posts: B241)	1.25	1.660
	Triple coated steel pipe with a 0.111-inch wall thickness	F1043, Group I-C	1.25	1.660

C. Top Rail

Provide top rail conforming to one of the types specified in Table 909.02-2.

Table 909.02-2: Top Rail

Material	Specification	Nominal Diameter (inches)	Outside Diameter (inches)
Galvanized standard steel pipe	ASTM F1083	1.25	1.660
Aluminum alloy standard (ANSI Schedule 40)	ASTM B429, Alloy 6063, Temper T6	1.25	1.660
Triple coated steel pipe with a 0.111-inch minimum wall thickness	ASTM F1043, Group I-C	1.25	1.660

D. Barbed Wire

1. **Steel.** Provide steel barbed wire meeting **909.01.D**.
2. **Aluminum Alloy.** Provide aluminum alloy barbed wire consisting of two twisted strands of 0.110-inch line wire with 0.080-inch diameter 4-point barbs spaced not more than 5 inches apart. Use ASTM B211 alloys of 5052-0 for the wire and 5052-H38 for the barbs.

E. Miscellaneous Fittings and Hardware

1. **Steel.** Provide zinc-coated miscellaneous fittings and hardware of commercial grade steel or better quality, pressed, wrought, or cast as appropriate to the article, and of sufficient strength and other properties to provide a balanced design when used in conjunction with fabric, posts, and wires of the quality specified herein. Galvanize all steel fittings and hardware in accordance with AASHTO M 111.
2. **Aluminum Alloy.** Provide aluminum alloy miscellaneous fittings and hardware of wrought or cast aluminum conforming to AASHTO M 181, Table I.

909.03

F. Wire Ties

Provide No. 9 gauge wire ties of zinc-coated steel, aluminum-coated steel, or aluminum alloy, of sufficient strength and other properties to provide a balanced design when used in conjunction with fabric, posts, and wire of the qualities specified herein.

G. Tension Wire

Provide tension wire meeting AASHTO M 181.

H. Truss Rods and Turnbuckle

Provide truss rods, 5/16 inch in diameter and equipped with a turnbuckle having a take-up of not less than 4 inches. Galvanize rods in accordance with AASHTO M 111.

I. Polyvinyl Chloride Chain Link Fence

Fabricate all posts, fabric and other hardware out of steel meeting the dimensional and material requirements specified herein and coated in accordance with AASHTO M 181, Type IV, Class B.

Fit posts with ornamental tops or extension arms as shown on the Plans. Ornamental tops for tubular posts shall have a base fitting into the post with a flange extending over the top of the posts to protect the post against moisture. Extension arms shall be vertical or extend in or out from the fence line at approximately 45 degrees as shown on the Plans. Provide suitable notches or slots in the extension arms to support and space the barbed wire.

All materials shall be within reasonably close conformity to the sizes, shapes, dimensions, and other factors set out in these Specifications or shown on the Plans, and shall show careful, finished workmanship.

909.03 Fence Gates

Provide swing-type fence gates of the kinds and sizes shown on the Plans, complete with latches, stops, keepers, hinges, and fabric. Provide latches that allow for fastening with a padlock. Cover the gates with fabric matching the fence. Provide hinges of adequate strength to support the gate and to not twist or turn under action of the gate. Provide gates, gate posts, and braces of the

same kind and finish as the adjoining fence. Furnish all gate posts and rails complete with ball caps and rail ends.

A. Stock Fence Gates

Provide the following for stock fence gates:

1. Posts and braces of standard weight steel pipe conforming to ASTM F1083, or triple coated steel pipe meeting **909.02.B**, furnished with all necessary fittings and of the nominal diameter and length shown on the Plans for the particular gate opening.
2. Gate frames of the type and size specified, constructed in accordance with the details and of the materials shown on the Plans.
3. Fabric of the woven wire type meeting ASTM A116, Class II coating, and of the design shown on the Plans.
4. Barbed wire meeting the requirements of **909.01.D**, and attached to the gate frame as shown on the Plans.
5. Fittings of approved design, made of malleable iron or pressed steel.

Galvanize all gate frames, posts, braces, and fittings in accordance with ASTM F1083 or ASTM A123, as applicable.

B. Chain Link Fence Gates

Provide the following for chain link fence gates:

1. Posts, braces, and framing members of standard weight pipe meeting **909.02.B**. The size and length of the posts and braces and the size and dimensions of framing members shall be as shown on the Plans.
2. Fabric of the chain-link type, meeting **909.02.A**. The height of the fabric shall be that shown on the Plans.
3. Barbed wire meeting the requirements of **909.02.D**.

909.04

4. Miscellaneous fittings and accessories meeting the applicable requirements of **909.02.E, F, and G**, including hinges that will allow the gate to swing back 180 degrees, parallel with the fence line.

909.04 Water Gates and Water Crossings

Provide posts, braces, and accessories of the types, kinds, and dimensions shown on the Plans or directed by the Engineer, and that meet the applicable quality requirements of **909.01** or **909.02**.

Provide timber for water gates of the dimensions shown on the Plans or directed by the Engineer, and that meet the requirements of **911.02**.

909.05 Metal Beam Rail

Provide rail elements of corrugated sheet steel beams conforming to AASHTO M 180, with the following exceptions:

1. Galvanize the beams.
2. Provide the class and type of rail shown on the Plans.

909.06 Timber Rail

Provide timber rail having the dimensions shown on the Plans and meeting the requirements of **911.01**.

Provide treated timber, when specified, conforming to **911.02**.

909.07 Guard Rail Posts

Provide railing posts of the section, weight, and length shown on the Plans. The posts may be made of wood, conforming to **911.02**, or steel, conforming to ASTM A36 and galvanized in accordance with ASTM A123.

909.08 Guard Rail Hardware

Provide offset brackets of the resilient and non-resilient types of the type specified.

Provide splices and end connections of the type and design specified and of such strength as to develop the full design strength of the rail elements.

Provide end spring assemblies, when specified, that are positive and of a type and design conforming to the intent, design, and strength of the railing structure, as shown on the Plans.

Provide end anchor rods and accessories as specified and of such size and strength as to develop the full design strength of the rail elements.

Unless otherwise specified, galvanize all steel fittings, bolts, washers, and other accessories in accordance with AASHTO M 111 or ASTM A153, whichever may apply. Perform all galvanizing after fabrication. Mechanically applied zinc coating conforming to ASTM B695 and meeting Class 50 coating thickness is an acceptable alternate for the hot-dipped galvanizing specified in AASHTO M 232.

Provide aluminum alloy fittings, bolts, washers, and other accessories as shown on the Plans.

910.01

SECTION 910 – PAINT

910.01 General Requirements.....	966
910.02 Quick Dry Traffic Marking Paint (White and Yellow)	966
910.03 Structural Steel Coatings.....	970

910.01 General Requirements

Before having any paint manufactured under these Specifications, contact the Department for a sampling, testing, and inspection procedure. Proportion all paint furnished under these Specifications in accordance with the characteristics specified herein. Perform compounding using ingredients or component materials that have been found to conform with the appropriate detailed Specifications as set forth below by reference or otherwise.

Provide paint that will not compact on settling and will readily return to a smooth, uniform consistency for brushing or spraying when stirred vigorously with suitable paddles or when boxed from container to container.

The Contractor may use 55-gallon drums, equipped with efficient mechanical stirring devices, to deliver shop coat paint to fabricating shops that are equipped to handle them. With the Department's written authorization, the Contractor may also use 55-gallon drums equipped with stirring devices to deliver paints to projects requiring large quantities. In all other cases, deliver lots of 5 gallons or more in 5-gallon circular type metal pails constructed of 26 gauge or heavier metal. Equip each container with a full-top removable and replaceable lid and with a bail of sufficient strength to support the pail when completely filled with the specified paint. Label each container with the name and address of the manufacturer, the kind and color of paint, formula, net content of container, date of manufacture, and lot number.

Have paint that has been stored for longer than 6 months re-inspected and approved prior to use.

910.02 Quick Dry Traffic Marking Paint (White and Yellow)

The following requirements apply to quick dry white and yellow traffic paint, also referred to as pigmented binder, for use in marking traffic lanes or barrier lines on bituminous and concrete highways.

A. General Requirements

Provide pigmented binder formulated to allow for application by spray equipment when heated to 130 °F maximum and applied on bituminous or Portland cement concrete pavements.

B. Drop-on Glass Beads

Use glass beads conforming to AASHTO M 247, Type 1.

- 1. General.** For pavement markings, use beads that are clear, transparent, colorless glass, smooth and spherically shaped, free of milkiness, pits, or excessive air bubbles, and that conform to the requirements specified herein.

Glass beads shall not contain more than 200 parts per million of lead or 200 parts per million of arsenic. Certify and ensure that all glass beads meet all Federal requirements. Provide certified test reports demonstrating that all glass beads contain no more than 200 parts per million of arsenic or lead as determined by a certified independent (third party) laboratory, in accordance with Environmental Protection Agency testing methods 3052, 6010B, or 6010C.

Silica content of the glass beads shall be no less than 60%.

- 2. Color and Clarity.** Beads shall be colorless, clear, and free from carbon residues.
- 3. Roundness.** Ensure minimum true spheres overall are 80% when tested in accordance with ASTM D1155; for larger beads use visual inspection.
- 4. Index of Refraction.** Minimum of 1.50, when tested by the liquid emersion method at 77 °F.
- 5. Air Inclusions.** Maximum of 3% overall.

C. Paint

- 1. Characteristic Requirements.** Provide paint meeting the following requirements:

910.02

- a. **Pigment Content.** 58% to 65% by weight. Pigment for white paint shall contain 0.99 pounds per gallon of 94% titanium dioxide. Pigment for yellow paint shall be lead free and contain 0.22 pounds per gallon minimum of 94% titanium dioxide.
- b. **Total Non-Volatile.** 76% by weight, minimum.
- c. **Vehicle Non-Volatile.** 41% by weight, minimum. Vehicle shall be Rohm and Haas E-2706, DOW DT211NA, or an approved equal.
- d. **Minimum Weight.** 13.3 pounds per gallon.
- e. **Paint Viscosity.** 78 to 95 Kneb units when tested at 77 plus or minus 2.0 °F in accordance with ASTM D562.
- f. **Drying Time**
 - (1) Field: The paint shall dry to a no-tracking condition in 3 minutes when applied at 15 plus or minus 1 mil wet film thickness with a bead application rate of 6 pound per gallon of glass spheres per gallon of binder, when the pavement temperature is between 40 and 120 °F and the relative humidity is not exceeding 80%. Apply the pigmented binder with specialized equipment ensuring the binder will have a temperature of 100 to 130 °F at the spray gun. Determine the no-tracking condition by passing over the line as applied above in a simulated passing maneuver with a passenger car travelling 35 miles per hour. Consider a line showing no visual deposition when viewed from a distance of 50 feet as conforming to this drying requirement.
 - (2) Lab: The pigmented binder without glass spheres shall dry to no-pick-up condition in 10 minutes or less when tested in accordance with ASTM D711.
- g. **Volatile Organic Compounds (VOCs).** Meet the current EPA VOC requirements or 150 grams per liter, whichever is lower.
- h. **Paint pH.** 9.6, minimum.

2. **Qualitative Requirements.** Provide finished paint meeting the following quality requirements:
- a. **Condition in Container.** The paint received shall show no livering, skinning, mold growth, corrosion of the container, or hard settling of the pigment. Stirring by hand shall readily disperse any settling, with no persistent foaming.
 - b. **Color.**
 - (1) White: After drying, the color shall be flat white, free from tint, furnishing good opacity and visibility under both daylight and artificial light.
 - (2) Yellow: Color shall closely match chip 33538 of Federal Standard 595B.
 - c. **Flexibility.** No cracking or flaking when tested on a 1/2-inch mandrel in accordance with Federal Specification TT-P-1952B.
 - d. **Dry Opacity (Minimum Contrast Ratio).** 0.95 when drawn with a 0.005 Bird Applicator.
 - e. **Daylight Directional Reflectance.** Not less than 85% for white paint and not less than 50% for yellow (relative to manganese oxide) when measured in accordance with Federal Test Method No. 1416.
 - f. **Bleeding Ratio.** 0.97, minimum, when tested in accordance with Federal Specification TT-P-1952B.
 - g. **Scrub Resistance.** 300 cycles when tested in accordance with ASTM D2484.
 - h. **Freeze-Thaw Stability.** No change in consistency greater than 10% when tested in accordance with Federal Specification TT-P-1952B.
 - i. **Storage Stability.** When stored at 77 plus or minus 4.0 °F in a 3/4-filled can for a period of 30 days, the paint shall be in a homogeneous state with no skinning, curdling, hard settling, or caking that cannot be readily remixed.

910.03

D. Inspection, Testing, Packaging, and Marking

After manufacture, send, to the Division of Materials and Tests, a 0.5-pint sample of paint along with certified laboratory analysis for each batch.

For each batch or lot of glass beads shipped for use on Tennessee projects, send, to the Division of Materials and Tests, a 1-quart sample and a manufacturer's certification that the glass beads meet the requirements of AASHTO M 247 for the type beads.

With each shipment of paint and beads, include a detailed analysis for that particular batch and certification that all ingredients meet the requirements set forth in this Specification.

The Department reserves the right to perform in-plant sampling of ingredients and finished product during manufacturing operations and to sample the packaged product when it is received by the Department. The Department may withhold acceptance of the product until it completes its analysis of the samples.

Ship all paint in new containers that can be properly sealed.

Plainly mark or label all containers to show the following information: name and address of manufacturer, kind and color of paint, formula, net content of container, date of manufacture (month and year), and batch number.

910.03 Structural Steel Coatings

Structural steel coating systems for new and existing structures shall be listed on the Department's QPL for Structural Steel Coatings.

Do not apply any paint, either in the shop or in the field, until the manufacturer has submitted to the Engineer a certification stating that the material supplied has the same formulation as the prequalified material. The Engineer reserves the right to sample and test the materials supplied.

SECTION 911 – LUMBER, TIMBERS, AND TIMBER PILES

911.01	Lumber and Timbers.....	971
911.02	Treated Lumber and Timbers.....	972
911.03	Timber Piles.....	972

911.01 Lumber and Timbers

A. General

Refer to AASHTO M 168 for grading and terminology. This Section primarily addresses bridge and miscellaneous roadway materials.

B. Species of Wood

Use Southern Yellow Pine in accordance with Southern Pine Inspection Bureau (SPIB) Specifications or as otherwise shown on the Plans.

C. Grades of Lumber and Timber

Provide lumber and timbers for permanent use in structures that is grade marked or hammer stamped by a recognized acceptance agency that conforms to the following:

1. **Yard Lumber.** Provide yard lumber with a grade of C Finish, when a choice quality grade for finish purposes and appearance is a requirement, especially when painted.
 - a. **No. 1.** Provide #1 Grade lumber and timbers for general construction and utility purposes where strength is a consideration.
 - b. **No. 2.** Provide #2 Grade lumber and timbers for general construction and utility purposes where strength is not a consideration.
2. **Structural or Stress Rated Lumber and Timber.** As specified or otherwise noted in the plans, provide lumber and timbers of a

911.02

structural grade conforming to the grading rules of the Southern Pine Inspection Bureau (SPIB). Allowable stress shall be in accordance with the current SPIB grading rules.

911.02 Treated Lumber and Timbers

Treated lumber and timbers shall conform to the requirements of **911.01** and are to be treated by a pressure method to retain the minimum retention of preservative per cubic foot of wood for the designated use as outlined in American Wood Protection Association (AWPA) Standard U1, Commodity Specification A: Sawn Products. All preservatives must be registered with the USEPA under FIFRA.

The Engineer will not accept treated structural lumber or timbers for use unless it has been inspected and found satisfactory both before and after treatment. Material that is grade marked and or tagged bearing the mark of an agency accredited under the American Lumber Standards Committee, Inc. (ALSC) shall be acceptable. Alternatively, the manufacturer may furnish a notarized Certificate of Compliance which includes the tally, grade, and preservative retention of material provided.

911.03 Timber Piles

A. General

Provide untreated or treated timber piles in accordance with ASTM D25 Standard Specification for Round Timber Pile.

Fabricate round piles to meet the minimum diameters specified in Table 911.03-1.

Table 911.03-1: Timber Pile Diameters

Length of Pile	Tip Diameter (inches)	Butt End Diameter (inches)
20 feet and under	8	11
Over 20 feet up to 40 feet	8	12
Over 40 feet up to 60 feet	7	12
Over 60 feet	6	13

The diameter of the piles at the butt shall not exceed 18 inches.

Provide piles that have a uniform taper from butt to tip, are straight grained.

B. Preservative Treatment

Pressure preservative treat timber piles with a preservative specified in AASHTO M133 and in accordance with AWPA U1, Commodity Specification E: Round Timber Piling, UC4C. All preservatives must be registered with the USEPA under FIFRA.

912.01

SECTION 912 – BRICK

912.01 Building Brick.....	974
912.02 Sewer Brick.....	974
912.03 Masonry Mortar	974
912.04 Concrete Masonry Units	975
912.05 Brick Paving Units.....	975

912.01 Building Brick

Provide brick of the kind and grade specified.

A. Clay or Shale Brick

Provide brick conforming to ASTM C62.

B. Concrete Brick

Provide brick conforming to ASTM C55.

912.02 Sewer Brick

Provide brick conforming to ASTM C32.

912.03 Masonry Mortar

Compose mortar of one part Portland cement and two parts sand. The Contractor may add hydrated lime to the Portland cement in an amount not to exceed 10%. Add water to the mixture in quantities that will allow a stiff paste to form.

Either hand-mix or machine-mix the mortar. To prepare hand-mixed mortar, thoroughly mix the sand, cement, and hydrated lime together in a clean, tight, mortar box. Once the mixture is of uniform color, add water. Prepare machine-mixed mortar in an approved mixer and mix not less than 1-1/2 minutes.

Use mortar within 30 minutes after mixing. Do not retemper mortar.

Use materials conforming to the following:

Cement.....	901.01
Hydrated Lime.....	ASTM C207
Sand.....	903.02
Water.....	921.01

912.04 Concrete Masonry Units

Provide concrete masonry units conforming to the types, sizes, and dimensions shown on the Plans, and meeting the following requirements, unless otherwise specified:

1. Hollow load-bearing masonry units: ASTM C90, Grade 5, Type II.
2. Hollow non-load-bearing masonry units: ASTM C129, Type II.

Furnish the Department representative samples of the masonry units for testing.

912.05 Brick Paving Units

Provide brick of the kind and grade specified.

A. Masonry Brick

1. Sidewalk: ASTM C902, Class SX, Type 1
2. Crosswalks and Roadway: ASTM C1272, Type R

B. Concrete Brick and Truncated Dome Concrete Brick

Provide brick conforming to ASTM C936

C. Truncated Dome Brick

Provide brick conforming to ASTM C902, Class SX, Type 1

913.01

SECTION 913 – CEMENT CONCRETE CURING MATERIALS

913.01	Water.....	976
913.02	Reserved.....	976
913.03	Reserved.....	976
913.04	Burlap.....	976
913.05	Liquid Membrane-Forming Compounds.....	976
913.06	Sheeting Material for Curing Concrete	976

913.01 Water

For use in curing Portland cement concrete, provide water that is free from all substances that may damage the concrete when applied on the surface as a curing agent.

913.02 Reserved

913.03 Reserved

913.04 Burlap

Provide burlap conforming to AASHTO M 182, Class 3 or Class 4. If Class 1 or Class 2 burlap is allowed, use at least two layers.

913.05 Liquid Membrane-Forming Compounds

Provide compounds listed on the Department's QPL for Coatings for Concrete and conforming to ASTM C309, and use as follows:

1. Where applied texture finish is specified, use a Type 1-D, Class B, membrane that is compatible with the texture finish.
2. Use either a Type 2 membrane or Type 1-D, Class B, membrane on bridge decks when applied in combination with the water method of curing.
3. Use Type 2 membrane in all other applications.

913.06 Sheeting Material for Curing Concrete

Provide material conforming to the water vapor transmission rates specified in ASTM C171.

SECTION 914 – NON-METALLIC PIPE

914.01 Non-reinforced Concrete Pipe.....	977
914.02 Reinforced Concrete Pipe (RCP)	977
914.03 Perforated Concrete Pipe	978
914.04 Drain Tile	978
914.05 Clay Pipe.....	978
914.06 Vitrified Clay Pipe	978
914.07 Plastic and Polyethylene Corrugated Tubing	978
914.08 Precast, Concrete Box Sections.....	978
914.09 Polyvinyl Chloride (PVC) Pipe.....	979
914.10 High Density Polyethylene (HDPE) Pipe	979
914.11 Steel Reinforced Thermoplastic Ribbed Pipe (SRTRP).....	979
914.12 Polypropylene (PP) Pipe	979

914.01 Non-reinforced Concrete Pipe

Provide pipe conforming to ASTM C14 for the specified diameters and strength classes.

Manufacture all non-reinforced concrete pipe to meet the Department's procedure for the Manufacture and Acceptance of Precast Drainage Structures, Noise Wall Panels, and Retaining Wall Panels.

914.02 Reinforced Concrete Pipe (RCP)

Provide pipe conforming to ASTM C76 for the specified diameters and strength classes. Elliptical pipe shall conform to ASTM C507. Arch pipe shall conform to ASTM C506.

Precast reinforced concrete end sections shall conform to the cited Specifications to the extent to which they apply.

Manufacture all reinforced concrete pipe to meet the Departmental procedures.

914.03

914.03 Perforated Concrete Pipe

Provide pipe conforming to AASHTO M 175 or to ASTM C444 for the specified diameters, and, unless otherwise specified, of the standard strength.

914.04 Drain Tile

Provide pipe conforming to AASHTO M 178 for the specified material and diameters, and, unless otherwise specified, of standard quality class. When specified, the pipe spigot shall have integral spacer lugs to provide for an annular opening and self-centering feature.

914.05 Clay Pipe

Provide pipe conforming to ASTM C700 for pipe with full circular cross-section for the specified diameter and strength class. When specified, the bell shall have integral spacer lugs to provide for an annular opening and self-centering feature.

914.06 Vitrified Clay Pipe

Provide pipe conforming to ASTM C700 for the specified diameters and strength classes for circular, unperforated pipe.

914.07 Plastic and Polyethylene Corrugated Tubing

Provide tubing conforming to AASHTO M 252 or ASTM F667 for Heavy Duty Tubing, with the following exception:

Tubing having an elongation greater than 5% but less than 10% is acceptable provided the minimum pipe stiffness requirements in Table 1 are met when tested in accordance with ASTM F667, Section 9.7, using a 12-inch base plate.

914.08 Precast, Concrete Box Sections

For culverts, storm drains, and sewers, provide precast reinforced concrete box sections conforming to ASTM C1577. Manufacture all precast concrete box sections in accordance with the Departmental procedures.

914.09 Polyvinyl Chloride (PVC) Pipe

Provide PVC pipe from the Department's Producer List.

914.10 High Density Polyethylene (HDPE) Pipe

Provide HDPE pipe from the Department's Producer List.

914.11 Steel Reinforced Thermoplastic Ribbed Pipe (SRTRP)

Provide SRTRP for pipe from the Department's Producer List.

914.12 Polypropylene (PP) Pipe

Provide PP pipe for pipe from the Department's Producer List.

915.01

SECTION 915 – METALLIC PIPE

915.01 Ductile Iron or Cast Iron Pipe	980
915.02 Corrugated Metal Pipe (CMP)	980
915.03 Polymer Pre-coated, Corrugated Steel Pipe, Culverts, and Underdrains.....	981

915.01 Ductile Iron or Cast Iron Pipe

Provide ductile iron pipe conforming to ASTM A716 for the specified diameters and strength classes. Unless otherwise specified, either smooth, corrugated, or ribbed pipe may be furnished. For pipe diameters in excess of 48 inches, conform to ANSI Standard for Cast Iron Pipe, or as otherwise specified in the Contract, for the specified diameter and strength class.

Provide cast iron drain pipe conforming to ASTM A74. Unless otherwise specified, provide ductile iron pressure pipe for water lines or sewer construction conforming to the requirements of ASTM A377 for the diameters and working pressures specified.

915.02 Corrugated Metal Pipe (CMP)

A. Corrugated Steel Pipe, Pipe Arches, and Underdrains

Provide corrugated steel pipe from the Department's Producer List, pipe arches, or underdrains, including special sections, such as elbows and flared ends, that conform to AASHTO M 36, aluminum-coated Type 2 meeting AASHTO M 274. Special sections shall be the same thickness as the pipe, arch, or underdrain to which they are joined. Furnish shop-formed elliptical pipe and shop-strutted pipe only where shown on the Plans.

B. Structural Plate Corrugated Steel and Aluminum Structures

Corrugated aluminum alloy structural plate for pipe, pipe arches, and arches shall conform to the requirements of AASHTO M 219.

C. Bituminous Coating

When material supplied for any of the items specified above are to be bituminous-coated, ensure that the metal to be coated is free of grease, dirt, and other contaminants. Bituminous coating and paving shall conform to the requirements of AASHTO M 190. Apply the coating in accordance with the manufacturer's recommended procedures and as directed by the Department.

915.03 Polymer Pre-coated, Corrugated Steel Pipe, Culverts, and Underdrains

Provide polymer pre-coated corrugated steel pipe conforming to AASHTO M 245, Grade 250/250, unless otherwise specified.

916.01

SECTION 916 – HIGHWAY SIGNING MATERIALS

916.01	General Requirements.....	982
916.02	Aluminum and Composite Material Signs	982
916.03	Steel.....	983
916.04	Stainless Steel	984
916.05	Fabrication	984
916.06	Reflective Sheeting	988
916.07	Legends, Borders, and Accessories.....	988
916.08	Flexible Delineator Posts	989

916.01 General Requirements

In constructing highway signs, use all new parts that conform to the requirements of these Specifications, the Plans, and the AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, latest edition. To request any departures from the materials and fabrication shown on the Plans or specified in the Specifications, submit details of such departures, and the reasons they are necessary, to the Engineer for approval. Do not make any such departures without the Engineer's prior written approval.

Furnish the Department notarized certified copies of the chemical and physical properties of all materials incorporated in the structures and accessories that are required for this work.

916.02 Aluminum and Composite Material Signs

Provide aluminum and composite materials conforming to the requirements in Table 916.02-1, unless otherwise specified.

Table 916.02-1: Aluminum and Composite Sign Components

Item	ASTM Specification	Alloy and Temper
Flat sign sheets (sign blanks) and plates (permanent and temporary) ⁽¹⁾	B209	6061-T6 or 5052-H38
Extruded shapes (sign panels), bars, rods	B221	6063-T6
Posts and truss chords	B221	6061-T6
Structural shapes	B308	6061-T6
Delineator sheets	B209	6061-T6
Post and truss bracing members	B221	6063-T6
Bolts other than anchor bolts ⁽²⁾	B211	2024-T4
Nuts, 5/16 inch and larger	B211	6262-T9
Nuts, 1/4 inch and under, tamper-proof type	B211	2024-T4
Washers, Alclad	B209	2024-T4
Flange splicing material	B209	6061-T6
Post caps and chord caps	B26	SG-70A-F
Rivets	B316	6053-T6
Shims	B209	1100-0
Posts clips	B308	6061-T6
Letters, numerals, and symbols	B209	3003-H14

⁽¹⁾ Recycled aluminum flat sheet (sign blanks) meeting ASTM B209, Alloy 6061-T6 or 5052-H38 may be used for temporary signing only. Select composite material sign blanks (temporary signing only) from the Department's QPL. The sign blanks shall be flat and shall contain no visible lateral bow.

⁽²⁾ Apply chromated sealed anodic coating at least 0.0002 inch thick to all finished bolts.

916.03 Steel

Use steel conforming to the requirements in Table 916.03-1, unless otherwise specified:

916.04

Table 916.03-1: Structural Steel and Components

Item	ASTM Specification	Grade
Steel structural shapes ⁽¹⁾	A709	50 S
Steel structural plates ⁽¹⁾	A709	36
Posts, chord, and bracing members, galvanized	A53	B
Post caps and chord caps ⁽¹⁾	A27	--
Bolts, nuts, and washers, galvanized	A307	--

⁽¹⁾ Galvanize in accordance with ASTM A123.

916.04 Stainless Steel

Use stainless steel conforming to the following:

1. Stainless steel bolts, washers and screws: ASTM A193, Austenitic steel.
2. Stainless steel nuts: ASTM A194, Grade 8F, except that the nuts shall be lock nuts with semi-finished hex nuts equivalent to American Standard Heavy Series.

916.05 Fabrication

A. General

Fabricate all signs and supports as shown on the Plans. Submit departures from the Plans in the form of shop drawings, as specified in **916.05.B**. Perform work in a uniform, workmanlike manner.

Complete the fabrication of steel components specified to be galvanized, including the forming of holes or perforations, prior to galvanization.

Fabricate all signs and supports in a plant operated by a fabricator who has the necessary experience to manufacture quality signs and supports meeting these Specifications. Before starting fabrication, provide the Department with the name of the proposed fabricators of the signs and supports, and, if requested by the Department, furnish information as to the fabricator's qualifications and experience.

B. Shop Drawings

For departures from the Plans, submit, for the Engineer's approval, eight copies of shop drawings showing complete detail designs of such departures and all other information necessary to complete the sign assembly.

C. Flat Sheet Signs

Fabricate flat sheet signs of a single piece of sheet aluminum, or composite material (when allowed), without joints and without supporting frame, unless otherwise specified.

D. Multiple Panel Signs

Fabricate multiple panel signs of extruded sections that are 12 inches wide, mounted horizontally, and without vertical joints. Ensure that all panels are flat and straight, and within the commercial tolerances established by the aluminum and composite industry.

E. Overhead Sign Supports

Fabricate overhead sign supports in accordance with the Plans and approved shop drawings. Fabricators must be AISC certified as specified in **602.04.A.4**.

Perform all welding in the shop in accordance with the Plans and the Contract Special Provisions.

Provide brackets for mounting signs (including future signs) of the type to be supported by the structure. They shall be adjustable to allow mounting of the sign faces at any angle between a truly vertical position and 3 degrees from vertical. Obtain this angle by tilting the top of the sign toward traffic. All brackets shall be of a length equal to the heights of the signs being supported.

Thoroughly clean all steel fabricated components other than stainless steel parts, including clamps and brackets, and galvanize by the hot-dip process, meeting the applicable ASTM Specifications specified in **916.03**.

916.05

F. Cutting (Metals)

Saw or mill materials over 1/2 inch thick. Materials 1/2 inch thick or less may be sheared, blanked, sawed, or milled. Ensure that cut edges are true and smooth and free from excessive burrs or ragged breaks.

Fillet re-entrant cuts by drilling prior to cutting.

Do not flame cut aluminum.

G. Bolt Holes (In Metals)

Either drill or blank bolt holes to finished size, provided the diameter of the blanked hole is at least twice the thickness of the metal being blanked.

H. Preparation of Sign Surfaces

Before preparing the surface, complete all fabrication, including cutting, welding, and punching of holes, excluding mounting holes for demountable letters, numerals, symbols, and borders.

Before painting or applying reflective sheeting to the aluminum, treat sign panels in strict accordance with the following procedure:

- 1. Preliminary Cleaning.** Completely submerge the surface in a 6% solution of an inhibited alkaline cleaner at 160 to 180 °F for 3 minutes followed by a cold water rinse.
- 2. Etching.** Follow preliminary cleaning with a surface etch by immersing the sign for three minutes in a 6 to 8% dilute phosphoric acid solution followed by spraying with a cold water rinse and immersing for 1 minute in circulating hot water at 180 °F.
- 3. Handling.** Do not handle any metal, except by device or clean canvas gloves, between cleaning and etching operations and the application of paint or reflective sheeting. Do not allow the metal to come in contact with grease, oils, or other contaminating substances after cleaning and etching and prior to the application of paint or reflective sheeting.

Treat composite material sign panels in accordance with the manufacturer's recommendations.

I. Shop Painting and ReflectORIZATION

All legends, borders and background shall be of the color and placed on the sign as shown on the Plans.

- 1. Application.** Apply reflective sheeting to properly treated base panels with mechanical equipment in the manner specified by the sheeting manufacturer. Type II adhesive coated sheeting shall be pre-perforated.

For sign faces consisting of two or more pieces or panels of reflective sheeting, carefully match pieces for color at the time of sign fabrication to provide uniform appearance and brilliance, both day and night. Apply alternate, successive width sections of either sheeting or panels to be reverse and consecutive to ensure that corresponding edges of reflective sheeting lie adjacent on finished sign. Nonconformance may result in non-uniform shading and an undesirable contrast between adjacent widths of applied sheeting that will not be acceptable. Limit splices. When spliced, overlap Type I adhesive coated sheeting not less than 3/16 inch. Type II adhesive coated sheeting may be spliced with an overlap of not less than 3/16 inch or butted; when butted, ensure that the gaps do not exceed 1/32 inch. Only use butt splices on signs screen processed with transparent color. Extend sheeting applied to extruded sections over top edges and down side legs a minimum of 1/16 inch. Ensure that, after aging 48 hours at 75 °F, adhesion of reflective sheeting to sign surface is strong enough to resist stripping from the panel when tested with a stiff putty knife, and will meet other applicable requirements as specified for Reflective Sheeting in **916.06**.

- 2. Silk Screening.** Apply all legends and borders on signs, except demountable or cut-out legends and borders, by silk screening after the sheeting is attached to the panels, unless otherwise approved by the Engineer. Perform all screening in a workmanlike manner and as recommended by the manufacturer of the reflective sheeting.

The Contractor may apply black legends and borders to signs having silver reflectorized backgrounds by equally effective methods when approved by the Engineer. Use proper size screen mesh in reverse screening to ensure that the finished colors match the prescribed Standard Interstate Colors (AASHTO Manual). Noticeable deviation from the shades is cause for rejection of the sign.

916.06

After silk screening, or reverse silk screening, bake the sign in an approved oven for a period of one hour, at a temperature of 200 °F.

J. Packaging

Package signs in a manner that will prevent damage to any part of the sign, including demountable legends or borders, during shipment and storage. Before packaging, ensure that signs are free of moisture and paints are thoroughly dry. Do not apply adhesive tapes to any sign surfaces. Keep all packaged signs entirely dry.

Securely attach braces to all assembled or partially assembled signs, other than flat sheet signs, to prevent buckling or warping from the time of assembling to attaching on permanent supports.

916.06 Reflective Sheeting

Provide reflective sheeting from the Department's QPL conforming to AASHTO M 268 and the supplementary requirements for fungus resistance of AASHTO M 268. The sheeting material shall have a precoated adhesive backing or a heat and pressure activated adhesive backing protected by a removable liner.

For all signs with a SILVER-WHITE and ORANGE background when used on temporary barricades and channelizing drums, provide reflective sheeting of Type B or better as specified by AASHTO M 268.

For all signs with a SILVER-WHITE, YELLOW, RED, GREEN, BROWN, or BLUE background, provide reflective sheeting of Encapsulated Lens or Micro-prismatic Lens material meeting or exceeding the minimum requirements for Type B or better as specified by AASHTO M 268.

FLOURESCENT ORANGE background material shall meet or exceed the requirements for Type B, as specified by AASHTO M 268.

916.07 Legends, Borders, and Accessories

Provide letters, numerals, symbols, borders, and route markers conforming to the MUTCD.

A. Type "A" Class I (Demountable)

Provide silver-white letters, numerals, symbols, borders, and route markers of a pre-coated pressure sensitive or a tack-free heat-activated adhesive reflective sheeting permanently adhered to the sign panel. The reflective sheeting shall meet the requirements of **916.06** (Type B or better as specified by AASHTO M 268).

Mechanically apply the reflective sheeting to the properly prepared sign panel with the equipment and in a manner prescribed by the sheeting manufacturer. Letters, numerals, symbols, borders, and route markers shall be 0.032 inch thick aluminum sheet of 3003 H14 Alloy or approved composite material. Properly degrease and etch aluminum, or treat with a light, tight, amorphous chromate type coating.

Supply each letter, numeral, symbol, and route marker with mounting holes, and secure to the sign surface with corrosion-resistant screws, bolts, or rivets.

B. Type "A" Class 2 Cut-Out (Direct Applied Reflective Sheeting Copy)

Provide silver-white cut-out letters, numerals, symbols, borders, and route markers of a pre-coated pressure sensitive or a tack-free heat-activated adhesive reflective sheeting. The reflective sheeting shall meet the requirements of **916.06** (Type B or better as specified by AASHTO M 268).

916.08 Flexible Delineator Posts

Provide delineator posts of the height shown on the Plans and of a width that presents a minimum 3-inch wide profile in the direction of approaching traffic. The top 14 inches of the front of the delineator post shall have a smooth surface capable of readily bonding the pressure sensitive reflective sheeting.

Provide delineator posts that are white in color unless otherwise shown on the Plans. Reflecterize the posts with reflective sheeting that conforms to AASHTO M 268, Type B or better retroreflection performance level.

The reflective sheeting strip on the delineators shall be 9 inches long and 3 inches wide profile and facing approaching traffic. Locate the top of the reflective sheeting 1/2 inch from the top of the delineator post.

916.08

For Flexible Type II Object Markers, use reflective sheeting consisting of three yellow squares spaced 4-1/2 inches center to center, each square being 3 inches long with sufficient width to present a 3-inch wide profile when mounted on a post. Locate the top square 1/2 inch from the top of the object marker post.

Select material from the Department's QPL. The manufacturer shall certify that the materials to be supplied are formulated the same as when tested by the National Transportation Products Evaluation Program and will conform to the requirements of this Specification. The Department reserves the right to periodically sample and test delineator posts.

**SECTION 917 – ROADWAY AND STRUCTURE
LIGHTING MATERIALS**

917.01	General Requirements.....	991
917.02	Roadway Lighting Standards	992
917.03	Lighting Assembly Strength Test	998
917.04	Wiring	998
917.05	Metallic Conduit	999
917.06	Metallic Conduit Fittings	999
917.07	Non-metallic Rigid Conduit	999
917.08	Luminaires	999
917.09	Fittings, Pull Boxes, and Bends	1000
917.10	Relays, Switches, Control Cabinets, Etc.	1000
917.11	Service Poles and Wood Standards	1000
917.12	Guying Components	1000
917.13	Grounding Materials	1001
917.14	Splicing Materials	1001
917.15	Drag Wire	1001
917.16	Photoelectric Relay	1001

917.01 General Requirements

Prior to making any purchases, submit for approval a complete list of all proposed materials. Include on the list the manufacturer's name, catalog number, and such other definitive or descriptive data as is necessary to adequately define the item. When requested by the Engineer, furnish samples of the material and notarized certificates by the manufacturer that the material meets the requirements of these Specifications and all industry standards referred to herein.

Obtain all guarantees on mechanical and electrical equipment furnished by the manufacturer and submit them to the Engineer. The Engineer will then transmit these guarantees to the agency responsible for future maintenance of the equipment.

917.02

Provide material and equipment that is designed, manufactured, and tested in accordance with the requirements of at least one of the following societies: ASTM, IPCEA, NEMA, IEEE, ANSI, and AASHTO. Provide material that is UL approved and bears the UL label.

Only furnish new materials and equipment under these Specifications.

917.02 Roadway Lighting Standards

Meet the following requirements for prestressed concrete, aluminum, and steel lighting standards.

Furnish standards of the design and dimensions shown on the Plans, and that conform with AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals. Include calculations for the design of each type of pole and bracket arm length with the shop drawings when submitted for approval.

A. Prestressed Concrete

1. **Scope.** These Specifications apply only to the manufacture of concrete lighting standards used to support lighting units.
2. **Method of Manufacture.** Manufacture all standards by an approved method that will ensure dense and uniform concrete. Place the concrete in one continuous operation. Use a manufacturing method that will produce a smooth cable raceway of 2 inches up to the hand hole, and a 1-inch raceway above the hand hole.
3. **Curing.** Following the casting operation, cure the concrete with low temperature saturated steam. Following the steam curing and while reducing the curing temperature, do not subject the standards to severe temperature changes.
4. **Anchor Base.** Furnish standards with the type of base shown on the Plans. Cast the base as an integral part of the standard.
5. **Foundations.** Where shown on the Plans, furnish the standards with a precast butt foundation that is cast as an integral part of the standard. Provide a conduit entrance slot of not less than 2 x 9 inches in the precast butt base at the location shown on the Plans.

6. **Anchor Bolts.** Use anchor bolts of high strength steel meeting the requirements of ASTM F1554, Grade to be determined by design. Fit each anchor bolt with a hex nut and lock-washer.
7. **Aluminum Bracket Arm.** Fabricate aluminum bracket arms, if specified, from aluminum alloy pipe or tapered tubes. Use pipe conforming to the requirements for nominal 2-inch diameter or larger Schedule 40 pipe of aluminum alloy 6063-T6, ASTM B241. Use tapered tubes conforming to the requirements for aluminum alloy 6063-T6, ASTM B221. Use cast aluminum clamps of Aluminum Alloy No. B-443.
8. **Steel Bracket Arms.** Fabricate steel bracket arms, if specified, from nominal 2-inch diameter or larger Schedule 40 pipe conforming to ASTM A53. Galvanize the steel bracket arm after fabrication in accordance with ASTM A123. Take precautions to obtain high quality galvanized coatings in accordance with ASTM A385.

The design and dimensions of the bracket arm assembly shall be as shown on the Plans. Ensure that the installed bracket will provide a weather-resistant connection with smooth wiring raceway. Use stainless steel bolts and nuts. Hot-dip galvanize all other steel parts and associated hardware in accordance with ASTM A123 or ASTM A153.

B. Aluminum

1. **Scope.** These Specifications apply only to the manufacture of aluminum lighting standards used to support lighting units.
2. **General.** Provide poles consisting of an aluminum shaft having a base attached to the lower end and complete with anchor bolts where required. Use materials conforming to the AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals. Perform welding in accordance with AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals.
3. **Shaft.** Provide a shaft of either spun seamless tubing or formed sheet aluminum. The shaft may have one continuous longitudinal weld. Provide the pole shaft with a uniform taper of approximately

917.02

0.14 inch per foot, or taper in increments as approved by the Engineer.

Furnish shafts in either one or two pieces in accordance with the manufacturer's current practices; however, if the required shaft length exceeds standard shipping limits, furnish the shaft in two pieces.

Assemble the two-piece shafts by telescoping the upper section over the lower section with a firm tapered fit. The telescoping length of the shaft shall be not less than 14 inches. Assemble the shaft in the presence of the Engineer or a qualified representative authorized by the Engineer. Ensure that the sections are correctly plumbed and force fitted. Do not weld the joint.

Provide an opening near the top of the shaft to provide a cable entrance from the shaft into the bracket arm. Design the opening to provide a smooth cable guide for wiring. Equip the top of the shaft with a removable pole top of aluminum alloy held securely in place with set screws. The shaft (excluding transformer base standards) shall have a reinforced handhole, of the size shown on the Plans, with a bolt-on cover. Provide a grounding nut or lug for accommodating a 1/2-inch UNC threaded bolt or stud in the shaft or base.

4. **Anchor Base.** The shaft shall have an anchor base that is strong enough to develop the full strength of the shaft it supports. Provide the base with four holes to receive the anchor bolts and a suitable means for attaching bolt covers. Provide four removable bolt covers with each base.
5. **Breakaway Device.** Provide a breakaway device conforming to the breakaway characteristics as established by Section 12 of the AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals.

To determine if an item meets the breakaway requirements of the AASHTO Standard Specifications, follow testing and reporting procedures comparable to those given in NCHRP Report 153. Acceptance may be based on a single test if the test change in momentum and the analytically inferred changes in momentum over the speed range are less than 750 pound-seconds. If the first dynamic test change in momentum is between 750 and 1,100 pound-

seconds, perform a second dynamic test unless assurance that the test results are representative of what would result from further dynamic tests can be demonstrated analytically and statically. The results of the second test must also meet the specification requirements. Furnish documentation of the breakaway characteristics to the Engineer prior to fabrication.

6. **Bracket Arm Aluminum.** Provide bracket arms for aluminum standards that meet the same requirements as specified in **917.02.A.7** for aluminum bracket arms for concrete standards.
7. **Anchor Bolts.** Provide anchor bolts of high-strength steel, each fitted with a hex nut and lock-washer. Each anchor bolt shall be capable of anchoring the bottom end in the concrete foundation and shall be threaded at the top end. The exposed portion of the threaded end of the anchor bolt, all nuts, washers, couplings, studs, and other fasteners shall be zinc coated, unless otherwise specified, in accordance with ASTM A153. Ensure that the anchor bolts are capable of resisting, at yield strength stress, the bending moment of the shaft at its yield strength stress.
8. **Finish.** All hardware not otherwise specified shall be aluminum or stainless steel. Furnish all materials in natural aluminum color. Furnish pole shafts with either a polished or brush finished surface. Tire-wrap shaft and bracket arm assemblies with a heavy water-resistant paper to provide protection during shipment and installation.

C. Steel

1. **Scope.** These Specifications apply only to the manufacture of steel lighting standards used to support lighting units.
2. **General.** Provide poles consisting of a steel shaft having a base welded to the lower end and complete with anchor bolts. All castings shall be clean, smooth, with details well defined and true to pattern. Provide gray iron castings conforming to ASTM A126, Class A, or ASTM A48, Class 20. Provide steel castings conforming to ASTM A27, Grade 65-35.
3. **Anchor Base.** Secure a one-piece cast steel base, having adequate strength, shape, size, and chamfer, to the lower end of the shaft by two continuous electric arc welds. The base shall telescope the

917.02

shaft. Make one weld on the inside of the base at the end of the shaft; make the other weld on the outside at the top of the base so that the welded connection will develop the full strength of the adjacent shaft section to resist bending action.

Provide four removable anchor bolt covers with each base. Attach each cover to the body of the base using suitable means. Provide a transformer base, if specified, of the design, dimensions, and material shown on the Plans.

4. **Breakaway Device.** Provide breakaway devices conforming to the same requirements as specified in **917.02.B.5** for aluminum poles.
5. **Shaft.** The steel shaft may have only one longitudinal electrically welded joint and shall not have any intermediate horizontal joints or welds. Use only one length of steel sheet and form it into a continuous shaft.

Fabricate the shaft from not less than No. 11 gauge steel conforming to the requirements of ASTM Standards: A242, A595, A606 or A1008, and A1011.

After forming and welding, longitudinally cold-roll the shaft under sufficient pressure to flatten the weld and increase the physical characteristics of the shaft so that the metal will have a minimum guaranteed yield strength of 48,000 pounds per square inch. The shaft (excluding transformer base standards) shall have a reinforced handhole, of the size shown on the Plans, with a bolt-on cover. Provide a ground nut or lug for accommodating a 1/2-inch UNC threaded bolt or stud in the shaft or base. Equip the top of the shaft with a pole cap held securely in place by set screws.

6. **Bracket Arm Steel.** Provide bracket arms for steel standards that meet the same requirements as specified in **917.02.A.8** for steel bracket arms for concrete standards.
7. **Anchor Bolts.** Provide anchor bolts for steel standards that meet the same requirements as specified in **917.02.B.7** for anchor bolts for aluminum standards.
8. **Finish.** Either paint or galvanize steel lighting standards as shown on the Plans and in accordance with the following:

- a. When painting is permitted or specified, thoroughly clean all materials not to be galvanized and shop paint with one coat of zinc chromate primer meeting the requirements of **910.03** before the parts are handled or packaged for shipment.
- b. Galvanize steel standards and bracket arms, and fittings, except hardware and anchor bolts, in accordance with ASTM A123. Galvanize hardware and anchor bolts in accordance with ASTM A153.

D. High Mast

1. **Scope.** These Specifications apply only to the manufacture of steel lighting standards over 55 feet in length used to support head frame, ring assembly, suspension, and power cables and luminaires.
2. **General.** Provide poles consisting of a steel shaft, handhole, anchor base, head frame, suspension cables, power cables, anchor bolts and foundation, and all equipment to complete the installation. Provide standards conforming to the AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals.
3. **Shaft.** Provide shafts tapered from top to bottom, either cylindrical or multi-sided in cross-section, and of either single-piece or slip-fit multi-section construction. Slip-fit design shall consist of tapered sections that telescope each other and are fabricated so that the minimum length of the overlap joint is 1-1/2 times the maximum inside diameter of the overlapping section. Number each section and show minimum and maximum overlap.
 - a. Provide weathering steel shafts conforming to ASTM A595 Grade C; and miscellaneous plates, bars, and structural shapes conforming to ASTM A709 Grade 50 S. Fabricate and weld these poles in accordance with AWS 01.1.
 - b. Provide galvanized steel shafts of high strength steel, cold formed fabricated with one longitudinal weld and having a minimum yield strength of 50,000 pounds per square inch and a maximum specified yield strength of 65,000 pounds per square inch after fabrication. Base the design on the

917.03

yield strength of the material used but not to exceed 60,000 pounds per square inch. Hot-dip galvanize the shaft in accordance with ASTM A123.

917.03 Lighting Assembly Strength Test

Ensure that the complete assembly of all standards, except high mast, when placed upright on a suitable foundation meets the following strength requirements:

1. A vertical load of 100 pounds applied at the point of luminaire attachment shall not produce a deflection in excess of 5% of the horizontal length of the bracket.
2. A vertical load of 250 pounds applied at the same point as in (1) above shall not produce collapse, rupture, or permanent deformation of any portion of the assembly.
3. A horizontal load of 60 pounds applied at the point of luminaire attachment and normal to plans of bracket assembly shall not produce a horizontal deflection in excess of 5% of the horizontal length of the bracket.
4. A horizontal load of 500 pounds applied at the top of the shaft, in any direction, shall not produce a deflection in excess of 8% of the length of the shaft nor shall this load cause failure of any component part of the assembly.

Furnish a signed warranty from the manufacturer stating that the materials used in standard and bracket fabrication fully meet the requirements of these Specifications and will satisfactorily withstand the specified horizontal and vertical loads in the above tests.

917.04 Wiring

Use conductor cable of the size and type shown on the Plans and in strict compliance with the National Electrical Code, the National Electrical Safety Code, and local codes.

Unless otherwise shown on the Plans, for all conductor cable placed in conduits and light standards, use single-conductor AWG copper with UL

rated 600 volt type insulation suitable for wet or dry installation with the conductor temperature not exceeding 167 °F.

Provide direct-burial cable and cable in-duct as shown on the Plans.

917.05 Metallic Conduit

Provide rigid steel conduit conforming to Federal Specifications WW-C-581 or ANSI C 80.1. Galvanize the conduit inside and outside by one of the following processes: hot-dip galvanizing, metallized galvanizing, or electro-galvanizing.

Provide flexible metal conduit conforming to Federal Specification WW-C-566.

Provide aluminum conduit conforming to Federal Specification WW-C-540.

Where welded steel pipe for ordinary use is shown on the Plans, provide pipe that is hot-dip galvanized inside and out and that meets ASTM A53 for Welded Steel Pipe for ordinary uses.

917.06 Metallic Conduit Fittings

Provide galvanized steel conduit fittings conforming to Federal Specifications WW-C-581 or ANSI C-80.4.

917.07 Non-metallic Rigid Conduit

Provide non-metallic rigid conduits and fittings of polyvinyl chloride (PVC), of Schedule 40 or 80 as specified, and conforming to ASTM D1785 for conduit and ASTM D2466 for fittings; or polyethylene conduit meeting the requirements of ASTM D1248 or as specified in the Contract.

917.08 Luminaires

Provide luminaires, complete with power regulated ballast, lamps, insulating transformer (where required), and associated hardware and wiring. Luminaires shall use and include a high intensity discharge lamp of the type shown on the Plans.

Ensure that the luminaires are capable of providing the specified illumination level and uniformity of illumination when installed as shown on the Plans.

917.09

Photometric and electrical requirements shall equal or exceed the requirements shown on the Plans.

917.09 Fittings, Pull Boxes, and Bends

Provide fittings, pull-boxes, bends, and miscellaneous hardware in accordance with the Plans and the National Electrical Code, and that are compatible with the adjacent conduit and materials.

917.10 Relays, Switches, Control Cabinets, Etc.

Provide relays, switches, control cabinets, and miscellaneous electrical equipment in accordance with the applicable codes and as shown on the Plans.

917.11 Service Poles and Wood Standards

Provide wood service poles and standards of the class and length shown on the Plans. Unless otherwise specified, provide poles and standards of treated southern pine, classified according to the latest American Standard Dimensions of Southern Pine Poles, and that meet the requirements of ANSI 05.1. Treat the poles with pentachlorophenol or other approved treatment at the rate recommended by the local power authority, unless otherwise specified. The treatment shall conform to **911.03**.

Provide metal service poles of the kind, design, type, and dimensions shown on the Plans.

917.12 Guying Components

Provide guying components for wood poles consisting of zinc-coated wire strand, zinc-coated anchor rod, four-way expanding anchor, and necessary accessories. Use wire strand conforming to the requirements of ASTM A475 for the particular grade, size, and type specified. Hot-dip galvanize the anchor rod, anchor, and accessories.

All guying components shall be in accordance with the details shown on the Plans.

917.13 Grounding Materials

Provide grounding materials as shown on the Plans. Use clamps that are designed for use with the designated rods.

917.14 Splicing Materials

Use splicing materials as shown on the Plans and of a design and material consistent with the location and type of splice indicated.

917.15 Drag Wire

For drag wire to be installed in the conduit, use nine-gauge galvanized iron wire, unless otherwise specified.

917.16 Photoelectric Relay

For the photoelectric relay for operating the multiple relays in the control center, provide a unit type assembly with a locking type plug that will allow the unit to be easily removed for maintenance purposes.

The photoelectric relay shall operate from 105 to 285 volts, shall have a minimum control range of 0.5 to 5.0 footcandles, and shall have a sensitivity adjustment for both on and off for the total range. The relay contacts shall be able to handle a minimum of 1,000 watts at 250 volts.

918.01

SECTION 918 – LANDSCAPING MATERIALS

918.01 Grass Seed 1002
 918.02 Commercial Fertilizer 1004
 918.03 Ammonium Nitrate 1005
 918.04 Agricultural Limestone 1005
 918.05 Mulch Material 1005
 918.06 Inoculants for Legumes 1005

918.01 Grass Seed

A. General

Provide seed meeting the requirements of the Tennessee Department of Agriculture Chapter 0080-05-06. The Producer must be on the Department’s Producer List.

Pack grass seed in new bags or bags that are sound and not mended.

The vendor shall notify the Department before making shipments to allow the Department to arrange for inspection and testing of stock.

The vendor shall furnish the Department a certified laboratory report from a Society of Commercial Seed Technologists accredited commercial seed laboratory or from a State seed laboratory showing the analysis of the seed to be furnished. The report from an accredited commercial seed laboratory shall be signed by a Registered Member of the Society of Commercial Seed Technologists. The Department may take samples of the seed to check against the certified laboratory report. Sampling and testing will be in accordance with the requirements of the Tennessee Department of Agriculture.

Use commercial grade 10-10-10 fertilizer or equivalent.

B. Seed Groups

When a seed group is used, provide mixtures meeting the requirements specified in Tables 918.01-1 through 918.01-5, unless otherwise specified.

Table 918.01-1: Group A (February 1-July 1)

Kind of Seed	Quantity, Percent by Weight
Kentucky 31 Fescue	80
Korean Lespedeza	15
Annual Rye Grass	5

Table 918.01-2: Group B (June 1-August 15)

Kind of Seed	Quantity, Percent by Weight
Kentucky 31 Fescue	75
Korean Lespedeza	15
German Millet	10

Table 918.01-3: Group B1 (April 15 - August 15)

Kind of Seed	Quantity, Percent by Weight
Bermudagrass (hulled)	70
Annual Lespedeza	30

Table 918.01-4: Group C (August 1-December 1)

Kind of Seed	Quantity, Percent by Weight
Kentucky 31 Fescue	70
Annual Rye Grass	20
White Clover	10

Table 918.01-5: Group C1 (February 1-December 1)

Kind of Seed	Quantity, Percent by Weight
Crown Vetch	25
Kentucky 31 Fescue	70
Annual Rye Grass	5

918.02

Uniformly mix seed when forming Groups. Do not mix Group seed until each type seed that is used to form the Group has been tested separately and meets DOA requirements for purity and germination.

C. Over-Seeding

Groups A, B, and C, when sown on slopes 3:1 and steeper, shall be over seeded with Sericea Lespedeza at the rate of 15 pounds per acre. When over-seeding is performed between February 1 and July 1, use Scarified Sericea Lespedeza with an additional 2 pounds per acre of Weeping Lovegrass. Between July 1 and December, use unhulled Sericea Lespedeza. Only use Group C1 when shown on the Plans.

D. Temporary Seeding

For temporary seeding, use seed groups and approved varieties as specified in Table 918.01-6.

Table 918.01-6: Temporary Seeding

Seed Group (Season)	Kind of Seed	Percent by Weight
Group D (January 1 – May 1)	Annual Rye Grass	33-1/3%
	Korean Lespedeza	33-1/3%
	Spring Oats	33-1/3%
Group E (May 1 – July 15)	Sorghum-Sudan Crosses ⁽¹⁾ or German Millet ⁽²⁾	100%
		100%
Group F July 15 – January 1	Cereal Rye	66-2/3%
	Annual Rye Grass	33-1/3%

⁽¹⁾ Dekalb Sudan SX11, Lindsey 77F, TN Farmer’s Co-op GHS-1 or GHS-2A.

⁽²⁾ German Millet, GaHi-1

918.02 Commercial Fertilizer

Provide a standard commercial fertilizer containing the specified percentages by weight of nitrogen, phosphoric acid, and potash.

Furnish the fertilizer in standard containers, with the name, weight, and guaranteed analysis of the contents clearly marked. Ensure that the containers will adequately protect the fertilizer during handling and transporting.

All commercial fertilizer shall comply with local, State, and Federal fertilizer laws.

918.03 Ammonium Nitrate

For ammonium nitrate, provide a standard commercial product, conforming to the requirements specified in **918.02** for other commercial fertilizers and having a minimum of 33-1/2% nitrogen.

918.04 Agricultural Limestone

Provide agricultural limestone meeting the Department of Agriculture Tennessee Liming Materials Act,

918.05 Mulch Material

Ensure that all hay and straw mulch materials are air dried and reasonably free of noxious weeds and weed seeds or other materials detrimental to plant growth on the highway or on adjacent agricultural lands.

Provide hay derived from stalks of approved grasses, sedges, or legumes seasoned before baling or loading.

Provide straw derived from stalks of rye, oats, wheat, or other approved grain crops.

Both hay and straw shall be suitable for spreading with standard mulch blower equipment.

Provide an approved tackifier, selected from the Department's QPL for Erosion Prevention and Sediment Control, to hold mulch in place.

918.06 Inoculants for Legumes

For treating legume seed, provide inoculants composed of standard cultures of nitrogen-fixing bacteria that are adapted to the particular kind of seed to be treated. Provide the inoculant in convenient containers, of a size sufficient to treat the amount of seed to be planted and that contain labels identifying the specified legume seed to be inoculated and the date period to be used.

919.01

SECTION 919 – PAVEMENT MARKING MATERIAL AND MARKERS

919.01	Thermoplastic Pavement Marking Material.....	1006
919.02	Spray Thermoplastic Pavement Marking Material.....	1010
919.03	Preformed Plastic Pavement Marking Materials.....	1012
919.04	Raised Reflective Pavement Markers.....	1012
919.05	Snowplowable Reflective Pavement Markers.....	1012

919.01 Thermoplastic Pavement Marking Material

Provide material conforming to AASHTO M 249, with the following additions.

A. Materials

Provide retroreflective pavement marking material of an alkyd/maleic based thermoplastic material consisting of homogeneously mixed pigments, filler, resins, and glass beads. Ensure that the pigment, beads, and filler are uniformly dispersed in the resin. The material shall be manufactured from virgin material using no reprocessed components.

Ensure that the material is free from all skins, dirt, and foreign objects, and conforms to the requirements specified in Table 919.01-1.

Table 919.01-1: Thermoplastic Pavement Marking Material

Component	White	Yellow
Binder, % minimum	19	19
TiO ₂ Pigment, % minimum	10	N/A
Intermix Glass Beads, % minimum	35	35
Calcium Carbonate/Fillers, % maximum	36 ⁽¹⁾	46 ⁽¹⁾

⁽¹⁾ The amount of Calcium Carbonate and inert fillers shall be as recommended by the manufacturer, provided all other specifications are met.

Titanium dioxide shall be Rutile Type II, conforming to ASTM D476, with a minimum purity of 93%.

The premixed beads shall constitute the total silica content used in the formulation of the thermoplastic. Uniformly disperse the pigment, beads, and filler in the binder.

The Alkyd/Maleic binder shall consist of a mixture of synthetic resins and high boiling point plasticizers, one of which shall be solid at room temperature. At least one-half of the binder composition, and no less than 15% of the entire material formulation, shall be 100% maleic modified glycerol ester of resin. Do not use a binder containing any petroleum, hydrocarbon resins, tall oil resins, or rosins.

Provide thermoplastic material meeting the following requirements:

1. The thermoplastic material shall be free of contaminants and shall be dry-blended or hot-mixed from 100% virgin stock using no reprocessed materials.
2. The thermoplastic material shall be formulated so that when it is on the roadway surface at any natural temperature, it will exist in a hard, solid state with cold ductility that allows normal movement with the road surface without chipping or cracking.
3. The thermoplastic shall not deteriorate or discolor when held at the application temperature for periods of time up to 4 hours or upon repeated reheating (a minimum of four times).
4. The color, viscosity, and chemical properties versus temperature characteristics of the thermoplastic material shall remain constant for up to 4 hours at the application temperature and shall be the same from batch to batch.
5. The thermoplastic material shall be readily applicable at temperatures between 400 °F and 440 °F from the approved equipment to produce lines and symbols of the specified thickness above the pavement surface.

B. Physical Requirements: After 4 hours @ 425 °F

Ensure that the thermoplastic material meets the physical requirements specified in AASHTO M 249, with the following changes.

919.01

Test the material in accordance with AASHTO T 250 and/or with the appropriate method in Federal Test Method Standard #141 or ASTM Designation.

1. **Bond Strength.** 180 pounds per square inch, minimum, when tested in accordance with ASTM D4796.
2. **Specific Gravity.** Not to exceed 2.30.

C. Glass Beads

Provide glass beads that meet AASHTO M 247.

Provide beads of clear, transparent, colorless glass, smooth and spherically shaped, free of milkiness, pits, or excessive air bubbles and that conform to the following specific requirements.

Use glass beads containing no more than 200 parts per million of lead or 200 parts per million of arsenic. Certify and ensure that all glass beads meet all Federal requirements. Provide an independent test report certifying that all glass beads contain no more than 200 parts per million of arsenic or lead as determined by a certified independent (third party) laboratory, in accordance with Environmental Protection Agency testing methods 3052, 6010B, or 6010C.

1. **Color and Clarity.** Beads shall be colorless, clear and free from carbon residues.
2. **Roundness.** Minimum true spheres overall shall be 80% when tested in accordance with ASTM D1155; for larger beads use visual inspection.
3. **Index of Refraction.** Minimum of 1.50, when tested by the liquid emersion method at 77 °F
4. **Air Inclusions.** Maximum of 3% overall.

D. Intermix Glass Beads

Premix glass beads into the thermoplastic mixture, to amount to 35% of the overall thermoplastic formulation. Use uncoated intermix beads

defined by two distinct gradations and that meet the following requirements:

1. Type 1 Intermix glass beads shall make up at least 50% of 35% of the overall thermoplastic formulation (Intermix Glass Beads) and shall conform to AASHTO M 247, Type 1, with the exception that the minimum true spheres overall shall be 80% as specified in **919.01.C.2**.
2. Type 3 Intermix glass beads shall make up at least 50% of 35% of the overall thermoplastic formulation (Intermix Glass Beads) and shall conform to AASHTO M 247, Type 3 with the exception that the minimum true spheres overall shall be 80% as specified in **919.01.C.2**.

E. Double Drop System

The double drop system shall be capable of applying glass beads at the specified application rates. Apply beads across the entire line width, ensuring uniform application and embedment of the beads to 50 to 60% of the bead diameter.

Use Type 1 drop on beads that are dual-coated for moisture resistance and adhesion and that meet the requirements of AASHTO M 247 Type 1 with the exception that the beads shall be 80% round overall.

Use Type 4 drop on beads that are dual-coated for moisture resistance and adhesion and that meet the requirements of AASHTO M 247 Type 4 with the exception that the beads shall be 80% round overall.

F. Marking Compound. Use material having the following characteristics:

1. In the molten state, the material shall not give off fumes that are toxic or otherwise injurious to persons or property. Obtain material safety data sheets for the product from the manufacturer.
2. The temperature versus viscosity characteristic of the plastic material shall remain constant. In addition, the material shall not deteriorate in any manner during three reheating processes.
3. No obvious change in material color shall occur as a result of up to three reheatings, or in maintaining the material at application

919.02

temperature up to an aggregate time of 4 hours, or from batch to batch.

4. The maximum elapsed time after application at which normal traffic will leave no impression or imprint on the new pavement marking shall be 30 seconds when the air and road surface temperature is approximately 68 °F plus or minus 5 °F.
5. The applied pavement marking shall remain free from tack, and shall not lift from the pavement under normal traffic conditions, within a road temperature range of -20 ° to 150 °F.
6. The pavement marking shall maintain its original dimensions and placement.
7. Cold ductility of the material shall allow for normal dimensional distortion as a result of tall impact within the temperature range specified.
8. The material shall provide a pavement marking that has a uniform thickness throughout its cross-section.

919.02 Spray Thermoplastic Pavement Marking Material

Provide retroreflective pavement marking material that meets the requirements specified in **919.01**, except as noted below.

A. Materials

Spray thermoplastic pavement marking material shall conform to the requirements specified in Table 919.02-1.

Table 919.02-1: Spray Thermoplastic Pavement Marking Material

Component	White	Yellow
Binder, % min	26	26
TiO ₂ Pigment, % min	10	N/A
Intermix Glass Beads, % min	35	35
Calcium Carbonate/Fillers, % max	29 ⁽¹⁾	29 ⁽¹⁾

⁽¹⁾ The amount of Calcium Carbonate and inert fillers shall be as recommended by the manufacturer, provided all other specifications are met.

Requirement **919.01.A.5** does not apply.

B. Physical Requirements: After 4 Hours at 425 °F

Ensure that the thermoplastic material, after being heated for 4 hours plus or minus 5 minutes at 425 plus or minus 3 °F and cooled to 77 plus or minus 3 °F, meets the physical requirements set forth in AASHTO M 249, with the following changes.

Test the material in accordance with AASHTO T 250.

- 1. Specific Gravity.** 2.0 maximum
- 2. Softening Point.** After heating the marking compound for 4 hours plus or minus 5 minutes at 425 plus or minus 3 °F and testing in accordance with ASTM E28, the material shall have a minimum softening point of 180 °F as measured by the ring and ball method.

C. Glass Beads

Use beads conforming to AASHTO M 247, Type 1.

- D. Intermix Glass Beads.** Premix Type 1 glass beads for intermix into the thermoplastic mixture, to amount to 35% of the overall thermoplastic formulation.
- E. Drop on Glass Beads.** Use drop on glass beads that may be applied at the specified application rates and that can flow freely through dispensing equipment in any weather suitable for pavement marking

919.03

application. Apply Type 1 beads at a minimum application rate of 10 pounds per 100 square feet. Apply beads across the entire line width, ensuring uniform application and embedment of the beads to 50 to 60% of the bead diameter. Treat Type I drop-on glass beads with a moisture resistant coating.

F. Marking Compound

Use marking compound conforming to **919.01.F**.

919.03 Preformed Plastic Pavement Marking Materials

Provide preformed plastic pavement marking material selected from the Department's QPL.

919.04 Raised Reflective Pavement Markers

Provide raised reflective pavement markers listed on the Department's QPL and classified as follows:

Type 1	One-Color, Reflective Markers (Two-way Traffic)
Type 2	One-Color, Reflective Markers (One-Way Traffic)
Type 3	Two-Color, Reflective Markers (One-way Traffic)

919.05 Snowplowable Reflective Pavement Markers

Provide reflectors consisting of an acrylic shell filled with tightly adherent potting compound. Select the potting compound based on strength, resilience, and adhesion adequate to pass the necessary physical requirements. The shell shall contain one or two reflective faces. Attach the reflector to an iron casting with an elastomeric pad.

Provide reflectors and castings selected from the Department's QPL and that conform to the following requirements.

A. Reflectors

- 1. Dimensions.** Provide reflectors that are 4 plus or minus 0.5 inches by 2.0 plus or minus 0.25 inches at the base, with a height of 0.40 inch or no higher than 0.50 inch. The slope of the reflector shall be 30 degrees, and the minimum area of the reflective surface shall be 1.87 square inches.

2. **Outer Surface.** Provide the shell with a smooth outer surface, except as needed for identification purposes.
3. **Base Surface.** Ensure that the base of the marker is substantially free from gloss or substances that may reduce its bond to adhesive.

Attach the markers, either mono- or bi-directional as specified, to an iron casting that is shaped to be snow plowable in the two opposing longitudinal directions and designed to allow for removal and replacement when needed to restore reflectivity.

B. Castings

1. **General.** Provide casting that are 10 plus or minus 0.5 inches long by 5.5 plus or minus 0.5 inches wide. Ensure that the maximum projection of the casting above the roadway does not exceed 0.5 inch, and that snowplow blades will ride over the casting without contacting the reflective marker.
2. **Casting Material.** Provide castings of nodular iron conforming to ASTM A536, Grade 72-45-05, hardened to 52-54 RC.
3. **Identification.** Mark each casting with manufacturer's name and model number of marker.

920.01

SECTION 920 – EROSION CONTROL MATERIALS

920.01 Erosion Control Blankets 1014
920.02 Staples 1014

920.01 Erosion Control Blankets

Provide erosion control blankets selected from the Department’s QPL.

920.02 Staples

Use wire not smaller than 11 gauge, formed into a U shape with legs at least 6 inches in length and a crown 1 inch in width. Ensure that staples have sufficient thickness to penetrate the soil without undue distortion.

SECTION 921 – MISCELLANEOUS MATERIALS

921.01 Water.....	1015
921.02 Calcium Chloride.....	1016
921.03 Reserved.....	1017
921.04 Lime.....	1017
921.05 Select Material for Soil-Cement Base.....	1017
921.06 Chemical Admixtures and Additives.....	1017
921.07 Masonry Stone.....	1019
921.08 Waterstops.....	1019
921.09 Grout.....	1022
921.10 Precast Manholes and Catch Basins.....	1022
921.11 Manhole Steps.....	1022
921.12 Geotextile and Geosynthetic Material.....	1022
921.13 Precast Prestressed Bridge Deck Panels.....	1023
921.14 Applied Textured Finish Material.....	1024
921.15 Fly Ash.....	1025
921.16 Slag Cement.....	1026

921.01 Water

For mixing concrete, use water that is reasonably clean and free of oil, salt, acid, alkali, sugar, vegetable matter, and other substances injurious to the finished product. Water provided by a municipal utility may be used without testing.

All other water shall have quality results submitted in accordance with the frequency listed in Table 921.01-01. All water quality results shall adhere to Table 921.01-2.

921.02

Table 921.01-1 Testing Frequency for Mixing Water

Water Source	Testing Frequency⁽¹⁾
Municipal	NA
Non-Municipal	Every 3 months; tested annually after 4 consecutive passing tests

⁽¹⁾ The frequency may vary at the discretion of the Department.

Table 921.01-2 Quality Requirements for Mixing Water

Maximum Concentration in Mixing Water	Limits	ASTM Test Method ⁽¹⁾
Chloride Ion Content, ppm	500	C114
Alkalies as (NaO ₂ + 0.658 K ₂ O), ppm	600	C114
Sulfates as SO ₄ , ppm	3000	C114
Total Solids by mass, ppm	50000	C1603
pH	4.5-8.5	⁽²⁾

⁽¹⁾ Other methods (EPA or those used by water testing companies) are generally acceptable.

⁽²⁾ No ASTM method available.

921.02 Calcium Chloride

A. Solid Form

Provide solid forms of calcium chloride conforming to the requirements of AASHTO M 144, for the type specified, except that the Department will waive requirements for total alkali chlorides and impurities when calcium chloride is to be used in mineral aggregate base or surface courses.

B. Liquid Form

Provide liquid forms of calcium chloride consisting of a clear liquid free from suspended matter and that meets the requirements specified in Table 921.02-1.

Table 921.02-1: Calcium Chloride Liquor

Component	Concentration of Calcium Chloride Liquor	
	32%	38%
Total Calcium Chloride by Weight, min.	32	38
Total Magnesium Chloride by Weight, max.	0.5	0.5

Do not use a calcium chloride solution of less than 32%.

Include with each shipment of calcium chloride liquor a certification from the manufacturer that states the concentration and net weight, and guarantees the percentage of calcium chloride.

921.03 Reserved

921.04 Lime

Provide lime conforming to the requirements of ASTM C977, for the type specified.

921.05 Select Material for Soil-Cement Base

Provide select material for soil-cement base of such general character as to be classified as Group A-1 or A-2, in accordance with AASHTO M 145, and of such size that all will pass the standard 1-1/2 inch sieve.

921.06 Chemical Admixtures and Additives

A. Admixtures

- 1. Portland Cement Concrete Admixtures.** Provide admixtures that are listed on the Department's QPL and conform to AASHTO M 194 for the following seven types of admixtures:

- Type A - Water reducing admixtures
- Type B - Retarding admixtures
- Type C - Accelerating admixtures
- Type D - Water-reducing and retarding admixtures

921.06

- Type E - Water-reducing and accelerating admixtures
- Type F - Water-reducing, high range admixtures
- Type G - Water-reducing, high range admixtures and retarding admixtures
- Type S - Specific performance admixtures

2. **Air-Entraining Admixtures.** Use air-entraining admixtures that are listed on the Department's QPL and conform to AASHTO M 154, except that the tests for bleeding, bond strength, and volume change will not be required.

B. Bituminous Additives

1. **Anti-Stripping Additive.** Use hydrated lime conforming to AASHTO M 303 or other heat-stable asphalt anti-stripping additive containing no ingredient harmful to the bituminous material or the workmen and that does not appreciably alter the specified characteristics of the bituminous material when added in the recommended proportions.

When hydrated lime is the anti-stripping additive, use an amount equal to 1% by weight of the aggregate. Uniformly coat the aggregate with the lime, to the Engineer's satisfaction, before adding the bituminous material to the mixture.

When using an anti-stripping additive other than hydrated lime, use a dosage rate of 0.3%, unless either gravel is used as a coarse aggregate or test results indicate moisture susceptibility, in which case mix at a dosage rate of 0.5%.

The Department's QPL identifies qualified antistripping additives. Do not use any product unless it appears on this list.

2. **Silicone Additives.** The amount of silicone added to asphalt cement shall not exceed 2 oz. of silicone per 5500 gallons asphalt cement.
3. **Warm Mix Asphalt (WMA) Additives.** The Contractor may add qualified WMA additives to bituminous plant mix to reduce placement temperatures as specified in **407.11**. Introduce the WMA additives into the mixture at a constant rate, sufficient to produce the mix temperatures specified in **407.11**, and in a manner approved by the Department. Record all changes to the proportions of the additive used during the course of mix production. The

Department's QPL identifies qualified WMA additives. Only use additives appearing on this list.

921.07 Masonry Stone

Provide sound, dense, and durable masonry stone, free from excessive cracks, pyrite intrusions, and other structural defects. Ensure that stones that will be used with mortar are free from dirt, oil, or other material that might prevent good adhesion with the mortar.

Masonry stone shall meet the quality requirements in **903.25**.

921.08 Waterstops

Provide waterstops of the type, shape, and dimensions shown on the Plans.

A. Metallic

Provide metallic waterstops of sheet copper conforming to the requirements of **908.13**.

B. Nonmetallic

Provide nonmetallic waterstops, manufactured from natural rubber, synthetic rubber, or polyvinyl chloride (PVC), that are dense, homogeneous, and free from holes and other imperfections. The cross-section of the waterstop shall be uniform along its length and transversely symmetrical so that the thickness at any given distance from either edge of the waterstop will be uniform.

Fabricate rubber waterstops from a high-grade thread-type compound, consisting of not less than 70% by volume of the basic polymer, with the remainder composed of reinforcing carbon black, zinc oxide, accelerators, anti-oxidants, vulcanizing agents, and plasticizers. The compound shall contain no factice. As the basic polymer, use natural rubber or a co-polymer of butadiene and styrene, or a blend of both.

Samples taken from the finished waterstop shall meet the requirements specified in Table 921.08-1.

921.08

Table 921.08-1: Requirements for Nonmetallic Waterstops

Property	ASTM Test Method	Value
Tensile Strength (Die "C")	D412	2,500 psi, min
Ultimate Elongation (Die "C")	D412	450%, min
Shore Durometer Hardness	D2240	60-70
Specific Gravity	D297 (Section 17)	1.15 ± 0.03
Water Absorption (% by weight)	D570	5%, max
Tensile strength after accelerated aging, oxygen-pressure method	D572	80%, min

C. Polyvinyl Chloride (PVC) Waterstop

Provide waterstops extruded from an elastomeric plastic compound, the basic resin of which shall be PVC. The compound shall contain additional resins, plasticizers, stabilizers, or other materials needed to ensure that when the material is compounded it will meet the performance requirements specified in Table 921.08-2. Do not use any reclaimed PVC.

Table 921.08-2: Requirements for PVC Waterstops

Property	Test Method	Value
Tensile Strength (Die "C")		
Sheet Material	ASTM D412	2,000 psi, min
Finished Waterstop	ASTM D412	1,700 psi, min
Ultimate Elongation (Die "C")		
Sheet Material	ASTM D412	350%, min
Finished Waterstop	ASTM D412	300%, min
Stiffness in Flexure	ASTM D747	750 psi, min
Accelerated Extraction		
	CRD-C 572	
Tensile Strength (Die "C")	ASTM D412	1,750 psi
Elongation (Die "C")	ASTM D412	300%
Effect of Alkali (after 7 days)		
	CRD-C 572	
Change in Weight		-0.1 to + 0.25%
Change in Hardness, Shore Durometer		± 5%
Low Temperature Brittleness	ASTM D746	-35 °F
Specific Gravity	ASTM D792	1.3

For PVC waterstops, the supplier shall submit a certificate stating that all the performance requirements specified above for the sheet material have been complied with. In addition, the supplier shall submit an affidavit to the effect that the sheet sample is of the same material in all respects as that to be used in the manufacture of the finished waterstop. The supplier shall also specify the value of the specific gravity of the finished waterstop material to within plus or minus 0.02.

Manufacture waterstops with an integral cross-section, uniform within plus or minus 1/8 inch in width, and with the web thickness or bulb diameter within plus 1/16 inch and minus 1/32 inch.

Furnish the Department a certified test report from an approved laboratory covering each lot or unit of finished waterstops and containing the numerical laboratory test data of all required tests.

921.09

921.09 Grout

Mix grout in small quantities as needed, and do not retemper or use grout after it has begun to set. Unless otherwise specified or directed, provide grout consisting of one part Portland cement and two parts sand by volume, mixed with sufficient water to form a grout of proper consistency. Use Portland cement conforming to the requirements of **901.01**, and sand conforming to the requirements of **903.02**. Use water that has been approved by the Engineer.

When non-shrinking or non-shrinking fast-setting grout is specified, either formulate it by incorporating an admixture, or use a pre-mixed grout. Obtain the Engineer's approval of the formulation and the admixture or the premixed grout. Mix and use the grout in accordance with the manufacturer's recommendations. These special grouts will be classified as follows:

- Type I - Non-shrinking Grout
- Type II - Non-shrinking, Fast-setting Grout

921.10 Precast Manholes and Catch Basins

Provide precast manholes and catch basins that conform to ASTM C478 and that are made in accordance with the Departmental procedures.

921.11 Manhole Steps

For use in manholes or catch basins, provide steps meeting ASTM C478, Article 11.2.1, or that are of the design shown on the Plans.

Provide cast iron steps conforming to **908.07**.

Provide aluminum steps fabricated from aluminum Alloy 6061, T6, with a minimum tensile strength of 38,000 pounds per square inch, a minimum yield strength of 35,000 pounds per square inch, and an elongation in 2 inches of not less than 10%.

Alternate manhole steps are listed on the Department's QPL.

921.12 Geotextile and Geosynthetic Material

Provide geotextiles and geosynthetics listed on the Department's QPL and that meet the material requirements shown on the Standard Drawing.

Furnish, with each shipment of materials, a certified laboratory test report from an approved testing laboratory and a certified letter stating the product provided is the same as on the Department's QPL. Laboratory test reports shall include the actual numerical test data obtained. Clearly label all rolls as being part of the same production run from which the test data was derived.

Protect geosynthetics to prevent damage during transportation, storage, and installation. Store geotextile and geosynthetic rolls elevated up off of the ground and covered to protect against UV degradation. Do not install material that is torn, punctured, or otherwise damaged.

921.13 Precast Prestressed Bridge Deck Panels

Construct and inspect the precast prestressed deck panels in accordance with the Plans, approved shop drawings, and the Standard Specifications. Fabricate the panels in a plant certified by the Precast/Prestressed Concrete Institute (PCI) category B-3.

Cast panels on beds that are clean, straight, level, and in good repair. Bulkheads and headers are to be of the size and configuration to adequately hold cables in place during casting operations. Keep forms, headers, cables, reinforcing bars or other steel that comes in contact with freshly placed concrete below 90 °F during casting operations. Cover and cure freshly cast panels as specified in **615.11**.

Provide projecting bars or other hardware for lifting and handling panels at the locations and in accordance with the details shown on the approved Shop Drawings. Protect projecting bars against impact and ensure that they are not bent in the shop, during handling and transporting, or in the field. Protect panels from damage during lifting, storing, and transporting.

Repair small damaged or isolated honeycombed areas that are purely surface in nature and not over 1 inch in depth at the fabrication plant with an approved epoxy grout. Replace panels with more extensive damage or honeycomb.

Inspect the panels at the point of delivery to the jobsite for identification, dimensional tolerances, cracks, and structural damage. Replace panels exhibiting excessive cracking or other structural damage.

Replace panels having any of the following defects:

1. Any crack that comes within 1 inch of a strand.

921.14

2. Corner cracks or breaks that involve one strand.
3. Isolated damage or honeycomb larger than approximately 6 inches in diameter or length and 1 inch in depth that involves one strand.

In evaluating for the above defects, consider a crack as a fissure of any length that extends from the surface of the panel to the mid-depth of the panel or to a strand, in accordance with any of the following conditions:

1. The crack is visible at the ends or edges of the panel.
2. The strand is visible within the crack.
3. The crack can be probed to mid-depth or to the strand.
4. The crack is visible on the top and bottom surface of the panel at approximately the same relative location.

Any new crack that appears in a panel after the deck is poured will be considered to extend to the mid-depth of the panel or to a strand. Replace, or repair to the Engineer's satisfaction, panels exhibiting new cracks after the slab is poured.

Defects not covered by the above will be subject to review by the Engineer.

921.14 Applied Textured Finish Material

The material for applied textured finish shall meet the requirements of Federal Specifications TT-C-00555, Type II, except as modified below:

A. Freeze-Thaw Test

1. Cast and cure three concrete specimens, not less than 4 x 6 x 6 inches, of a mix designed for structures. Moist cure for 14 days with a drying period in room air at 60 to 80 °F for 24 hours before coating with spray finish. Take caution to ensure that no excessive oil forms on specimen. Coat sides of specimens (brush permitted) and cure at room temperature for 48 hours; after which:
2. Immerse the specimen in water at room temperature (60 to 80 °F) for 3 hours; remove and,

3. Place in cold storage at -15 °F for 1 hour; remove and,
4. Thaw at room temperature (60 to 80 °F) for 1 hour.
5. Repeat Steps 3 and 4 to complete a total of 50 cycles.

B. Exposure Test

Subject the material to a 5,000-hour exposure test conforming to ASTM G155, operating a xenon arc light apparatus for non-metallic materials. At the end of the exposure test, the exposed sample shall not show any chipping, flaking, or peeling.

C. Fungus Growth Resistance

Material to be used must pass a fungus resistance test as described by Federal Specification TT-P-29b with a minimum incubation period of 21 days. There shall be no indication of growth after the test.

Submit to the Materials and Tests Engineer a 1-quart sample of the material proposed for use. This material will be tested and placed on the Department's QPL if it meets specifications.

After the material has been initially qualified and placed on the QPL, submit for each project on which the material is used, a certified statement from the formulator stating that the material furnished is identical in all respects to that which was initially qualified.

The Department reserves the right to require samples and to perform any or all the tests specified.

921.15 Fly Ash

Use fly ash meeting AASHTO M 295, Class F or Class C, for the class specified. Do not use fly ash of different classes or sources as a partial replacement for Portland cement in concrete mixes.

Provide fly ash meeting the requirements specified in Table 921.15-1.

921.16

Table 921.15-1: Fly Ash Requirements

Property	Fly Ash Class	
	F	C
A. Chemical Requirements: Uniformity Requirements		
The loss on ignition of individual samples shall not vary from the average established by the 10 preceding tests, or by all preceding tests if the number is less than 10, by more than: Loss on ignition, max variation, percentage points from average	1.0	1.0
B. Physical Requirements: Pozzolanic Activity Index		
With Portland cement, at 7 days, min, % of control	60	60
With Portland cement, at 28 days, min, % of control	75	75

Obtain fly ash from an approved source as shown on the Department's Producer List.

921.16 Slag Cement

Provide slag cement meeting the requirements of AASHTO M 302, Grade 100 or Grade 120. Do not use slag cement of different grades or sources as a partial replacement for Portland cement in concrete mixes.

Obtain slag cement from an approved source as shown on the Department's Producer List.

921.17 Ground Tire Rubber

Provide Class 30-1 Ground Tire Rubber (GTR) as defined by ASTM D5603 except for as noted in Table 921.17-1. The material shall also be certified to meet the requirements of Table 921.17-1. Include certification of the GTR with the Bill of Lading for the modified asphalt cement.

Table 921.17-1: Requirements for Ground Tire Rubber

Property	Specification
Specific Gravity	1.15 ± 0.05
Moisture Content	0.75% Max
Ferrous Metal Content	0.01% Max
Fiber Content	0.5% Max
Ash (ASTM E1131)	10% Max

921.18 Silica Fume

Use silica fume meeting AASHTO M 307.

INDEX

Abbreviations.....	3
Accelerators for concrete	1017
Acceptance	
Final	94
Project	49
Addendum, definition of.....	4
Additives	
Anti-strip for asphalt	1018
Concrete	1017
Silicone for asphalt.....	1018
Warm mix asphalt	1018
Adjusted guardrail.....	703
Admixtures	
Air-entraining.....	1018
Portland Cement Concrete	1017
Advertisement, definition of	4
Aggregate	
Asphalt treated permeable base.....	914
for aggregate-cement base course	923
for asphaltic concrete surface courses (hot mix)	916
for bituminous plant mix surface course (cold mix)	915
for concrete	904
for concrete	901
for double bituminous surface treatment.....	922
for hot bituminous seal coat	922
for lightweight concrete	924
for mineral aggregate base and surface course.....	906
for mortar	903
for plant mix base and leveling courses (hot mix)	911
for Riding Surfaces	927
for sand-asphalt surface course	924
for slurry seal and micro-surface.....	920
for underdrains	923
Mineral aggregate base course	220
mixing	223
Sizes	926

Index

spreading.....	224
Stockpiling.....	924
Test methods.....	925
Aggregate underdrains.....	723
Aggregate-cement base course.....	252
Agricultural limestone.....	1005
Air content.....	502
Air-entraining admixtures.....	1018
Altered Quantities.....	106
Aluminum for signs.....	982
Amendment, definition of.....	4
Ammonium nitrate.....	1005
Anchor bolts	
Sign support.....	751
Traffic signal.....	814
Anchorage	
Post-tensioned steel.....	637
Post-tensioned Tendons.....	944
Post-Tensioned Tendons.....	945
Angles, connections.....	462
Annealing.....	465
Anti-Strip Additive.....	248
Application temperature, bituminous seal coat.....	288
Applied textured finish for concrete.....	1024
Arch rings, stone masonry.....	610
Artifacts.....	142
Asphalt	
Acceptance of asphalt mix.....	342
Aggregate feed.....	320
Batch plants.....	316
Continuous mix plants.....	319
Contractor Quality Control.....	302
Hauling equipment.....	323
Heating.....	312
Material transfer device.....	323
Mixer.....	318, 320
Mixing time.....	318
Pavement samples.....	338
Pavers.....	323
Preparation of aggregate.....	330
Preparation of asphalt cement.....	328
Rollers.....	325
Silos or surge bins.....	322

Index

Storage	312
Storage bins or silos	330
Surge system	330
Testing	309
Thermometer	321
Warm mix	329
Asphalt cement.....	930
Asphalt Concrete Surface.....	352
Asphalt curb machine.....	781
Asphalt or Cement Treated Permeable Base.....	272
Asphalt Paving	
Mixing.....	330
Surface preparation	328
Surface requirements.....	339
Temperature limitations	326
Asphalt Plant	
Aggregate bins	313
Aggregate control.....	321
Aggregate feed	321
Bituminous control.....	313, 317
Dryer	313
Dryer drum.....	321
Dryer feeder	312
Dust collector	314
Field Laboratory.....	315
Plant requirements.....	312
Safety requirements.....	314
Scales	316
Screens	313
Storage system requirements.....	315
Surge system requirements	315
Thermometer.....	314, 319
Warm mix modifications	316
Weigh box or hopper.....	317
Asphaltic concrete curb (hot mix).....	780
Authority	
of Inspectors.....	46
of the Engineer.....	33
Automatic controls, asphalt screed	332
Award	
Cancellation of.....	20
Contract Award.....	20
Definition of.....	4

Index

Back walls	
Brick masonry.....	615
Stone masonry.....	611
Backfill	
Flowable fill.....	156, 165
Major structures	164
Material.....	155
Pipe Culverts.....	165
Backfilling	127
Barbed wire.....	961
Barricades	732
Bars for posttensioning	945
Bars, lacing	462
Base Course	
Aggregate-Cement	252
Definition of.....	4
Mineral aggregate	220
Batching concrete	394
Bearing pads, elastomeric	953
Bearing plates, bronze.....	953
Bents, timber structures	422
Bid opening.....	15
Bid Schedule.....	13
Bidder, definition of.....	4
bituminous asphalt plant mix pavements	296
Bituminous cold mix.....	348
Bituminous material.....	930
Bituminous mixing plant.....	312
Bituminous mixture	298
Bituminous plant mix base.....	242
design properties	244
mixtures	243
Bituminous plant mix surface (cold mix).....	348
Bituminous seal coat.....	288
application rates	291
Blasting	132, 143
Bolt holes	
for signs	986
for steel structures	435
Bolts	
Connections for steel structures	441
High strength.....	947
High strength connections.....	442

Index

Ribbed	441
Testing	948
Timber structures	424
Turned.....	441
Unfinished.....	441
Bond, contract definition of	5
Borrow Excavation	139
Borrow material	144
borrow pits	<i>See</i> Clearing and Grubbing
Borrow Pits	144
Box Bridge, definition of	4
Box Culverts	
Backfilling.....	164
Excavation.....	158
Foundation preparation	161
Box section, precast concrete.....	978
Braces, stock fence.....	956
Bracket arms for light standards	767
Brick laying.....	614
Brick masonry	613
Bricks	974
Clay or shale	974
Concrete	974
Sewer	974
Bridge deck sealant	646, 941
Application.....	647
Weather limitations	647
Bridge Excavation.....	154
Bridge expansion joint systems.....	671
Bridge railing	659
Bridge seats	
Brick masonry.....	615
Stone masonry.....	611
Bridge, definition of.....	4
Bridges	
Backfilling.....	164
Foundation preparation	161
Removal	131
Building brick	974
Buildings removal	130
Buried ground wire	764
Burlap.....	976
Cabinets	827

Index

Cable	818
Identification	765
Markers	770
Underground	763
Calcium chloride	1016
Calendar Day	4, 91
Calibration, asphalt aggregate	320
Camber	523
Care of sod	890
Cast iron pipe	980
Cast steel	952
Castings	
Gray iron	952
Malleable	953
Castings and fittings	602
Cast-in-place concrete piles	564
Catchbasins	600, 1022
Cement	900
Bulk	528
Hydraulic	900
Portland	900
Storage	900
Cement Application	
Aggregate cement	254
Soil cement	232
Cement concrete ditch paving	692
Cement concrete sidewalks, driveways and median pavement	681
Cement Treated Permeable Base	272
Chain link fence	958
Fittings and hardware	961
Gates	963
Top rail	960
Change Directive, definition of	5
Change Order, definition of	5
Changes	21
Differing Site Conditions	21
Eliminated Items	23
Extra Work	23, 106
Notification by Contractor	23
Significant Changes in the Character of Work	22
Suspensions	22
Channel Excavation	140
Chemical additives	1017

Index

Claims	49, 121
Against the Department	77
Appeal Process.....	54
Claim Certification.....	52
Department Decision.....	54
Informal Claim Meeting.....	50
Submission of.....	51
Classification	
Riprap.....	716
Stone masonry.....	605
Clay or shale bricks.....	974
Clay pipe.....	978
Cleanup, final.....	29
Clearing and Grubbing.....	124
5 feet outside the construction lines	125
Borrow Pits	126
Method of Measurement	128
Preparation	125
Right-of-Way	125
Swampy areas	126
Coal, rights to.....	28
Coarse aggregate	
for asphalt surface (hot mix)	916
for concrete	904
for plant mix base and leveling course.....	911
Codes, electrical.....	758, 808
Cofferdams.....	160
Cold mix (bituminous).....	348
Column supports, cantilever signs	751
Combined aggregate grading	912
Combined grading, for asphalt surface (hot mix).....	917
Commissioner, definition of.....	5
Compaction	
Aggregate cement base	255
Aggregate-Lime-Fly Ash Base Course	267
Asphalt paving	333
Cold mix.....	350
Conditioning aggregate base	260
Mineral aggregate base	225
Mineral aggregate surface.....	277
Soil cement.....	233
Compensable Delay Costs	115
Competency of Bidders.....	12

Index

Completion Time	91
Composition	
Asphalt curb	780
Asphalt surface	353
Cold mix	349
Concrete	
Classification	501
Compressive strength.....	<i>See</i>
Curing	547
Defective.....	541
Drum mixing speed.....	531
Finishing	542
Forms	516
Heated	530
Joints.....	399, 538
Mixing.....	394
Mixing limitations.....	395
Mixing time.....	531
Placement.....	395, 534
Proportioning	501, 623
Protection.....	549
Quality Assurance.....	501
Reinforcement.....	943
Reinforcement placement	524
Retempering.....	531
Slip forming	396
temperature	530
Temperature	530
Test specimens.....	398
Trucks	531
Under water.....	539
Concrete Base Deficiency.....	241
Concrete curing compound	976
Concrete masonry units.....	975
Concrete median barrier.....	728
Concrete parapet	660
Concrete Pavement	
Acceptance testing	509
Batching plant	389, 511
Concrete batching	394
Conditioning base	394
Consolidation of concrete	403
Construction joints.....	402

Index

Construction of base.....	393
Curing	409
Final concrete finish.....	405
Final strike-off	403
Finishing	403
Floating	404
Forms	390
Hand finishing.....	403
Joints	399
Machine finishing	403
Materials handling.....	394
Mixers	389, 512
Proportioning	387
Quality control	389
Setting forms	393
Spreading and finishing equipment.....	391
Subgrade preparation	393
Surface testing.....	406
Thickness	414
Vibrators	391
Concrete pipe	
Non-reinforced.....	977
Reinforced.....	977
Concrete Plant	
Bins	511
Hoppers	511
Scales	511
Concrete Structures	499
Conditioning mineral aggregate base.....	259
Conductors	818
Conduit.....	750, 759, 816
Backfilling.....	761
Direct burial	761
Encased	761
Metallic	999
Non-metallic rigid.....	999
On structures	762
Steel fittings	999
Testing	762
Trenches.....	759
Conformity with Plans and Specifications	36
Connection angles	462
Construction change, definition of.....	5

Index

Construction Joints	402, 539
Contract	
Award	<i>See</i> Award
Change Order	107
Default	95
Definition of	5
Execution	20
Failure to Execute	20
Intent of	21
Negotiations	107
Payment and Performance Bond	20
Subletting	79
Termination	95
Contract Change	<i>See</i> Changes
Contractor	
Definition of	6
Duties of	38
Legal Responsibilities	75
Responsibilities for Work	76
Control cabinets	1000
Control center	770
Control strips, asphalt paving	334
Controllers	825
Controlling Activity of Work, definition of	6
Cooperation	
Between Contractors	42
with Utilities, Railroads, and Pipelines	40
Coordination of Plans and Specifications	37
Copings	
Brick masonry	615
Stone masonry	611
Copper sheet for flashing	954
Corner posts, stock fence	956
Countersinking timber structures	424
Cribs	160
Critical Path Method	84
Critical Path Method, definition of	6
Critical Path, definition of	6
Cultivating, landscape	884
Culvert	
Excavation	154
Removal	131
Curb	

Index

Concrete base	239
Removal	133
Curb and gutter	687
Curb machine, asphalt.....	781
Curing	409
Aggregate cement base	256
Aggregate-Lime-Fly Ash Base Course	268
Asphalt curb	783
Concrete	547, 626
Concrete curb and gutter	690
Ditch paving.....	694
Polymer modified concrete	656
Sidewalk, median pavement, and driveways.....	684
Soil cement.....	234
Steam method.....	626
Curing compound, concrete	976
Current test.....	771
Curving steel beams and girders	432
Cut Slopes	179
Cutting metal for signs.....	986
Dampproofing materials	940
Date, completion definition of	5
Day, calendar definition of.....	4
Defective concrete.....	541
Defective Material.....	63
Definitions.....	4
Delays	91
Compensable Delay Costs.....	115
Concurrent.....	94
Excusable, Compensable	93
Excusable, Non-Compensable	92
Liquidated Damages	95
Delineators	749
Density	
Aggregate cement base	255
Asphalt pavement.....	335
Conditioning mineral aggregate base	260
Embankment	176
Soil cement.....	233
Department, definition of.....	6
Detectors, traffic signal	845
Detour, definition of.....	6
Differing Site Conditions	21

Index

Disadvantaged Business Enterprise, definition of.....	6
Disposal of debris	127
Disputes	<i>See Claims</i>
Distributor, bituminous material	280
Ditches	188
Dowels	400, 943
Drag wire	1001
Drain tile	978
Drainage Structures, removal.....	131
Dressing	182
Driveways, concrete.....	681
Driving Piles	569
Drum speed, concrete mixer	531
Drums, temporary traffic control	733
Ducts	638
Dust Control.....	28
Early entry sawing	401
Edging at forms and concrete joints.....	406
Elastomeric bearing pads	953
Electrical codes	758, 808
Eliminated Items	23
Embankment	174
Compaction	176
Formation of	176
Moisture	176
Preparation for	174
Stability of.....	179
Emulsified Asphalt	931
End walls, pipe.....	600
Engineer	
Authority of.....	33
Definition of.....	6
Environmental Protection	68
Equipment.....	89
Alternative Equipment.....	55
Definition of.....	7
Movement of.....	27
Operation of	27
Erection	
Fence.....	707
Guardrail	699
Monuments and markers	711
Steel	470

Index

Erosion Control	191
Preconstruction Conference	192
Requirements	193
Structures	196
Erosion control blanket	893, 1014
Establishment of plants	884
Establishment of sod	890
Examination of the Site	13
Excavation	138
Borrow	139
Box Culvert	158
Bridges	154, 158
Channel	140
Classification	138
Dry excavation (bridges)	154
Major structures	158
Pipe	581
Pipe Culvert	159
Protection of	160
Requirements	141
Road and drainage	139
Rock excavation (bridges)	154
Sewer	588
Shaping and dressing	147
Slides	151
Structure	153
Undercutting	141
Unsuitable material	146
Use of excavated material	160
Wet excavation (bridges)	154
Excess Material	146
Expansion joints	402
Driveways	683
Median pavement	683
Sidewalks	683
Explosives	74
Extra work	23
Eyebars	464
Fabric for stock fence	956
Fabrication of signs	984
Fabrication, steel structures	463
Falsework	522
Falsework Removal	541

Index

Federal Aid Provisions.....	67
Fence.....	705
Chain link.....	958
Erection.....	707
Gates.....	962
Posts.....	706
Stock.....	956
Fertilizer.....	879, 1004
Field connections	
Structural Steel.....	436
Field laboratory.....	60
Asphalt plant.....	303, 315
Field Offices.....	801
Filter cloth.....	1022
Filter cloth underdrains.....	722
Final Acceptance.....	94
Final Payment.....	121
Fine aggregate	
for asphalt surface (hot mix).....	916
for concrete.....	901
for mortar.....	903
for plant mix base and leveling course (hot mix).....	911
Finishing	
Aggregate cement base.....	256
Aggregate-Lime-Fly Ash Base Course.....	267
Asphalt mixes.....	331
Concrete base.....	239
Concrete median barrier.....	729
Concrete, curb and gutter.....	689
Ditch paving.....	694
Driveways.....	683
Median pavement.....	683
Sidewalk.....	683
Soil cement.....	234
Fittings, chain link fence.....	961
Flaggers.....	735
Flashing Arrow Board.....	736
Flashing school signals.....	837
Flashing, copper sheet.....	954
Flexible Delineator Posts.....	989
Flocculants.....	197
Flowable Fill.....	156, 165
fly ash.....	262

Index

Fly ash.....	1025
Fog Sealing	286
Force Account.....	108
Force account, definition of	7
Force, working for cast in place prestress concrete.....	640
Forgings, steel.....	952
Forms	390
Concrete	516
Ditch paving.....	693
Driveways	682
Median pavement.....	682
Metal concrete forms	517
Permanent bridge deck forms.....	517
Removal	411, 541, 626
Sidewalks	682
Surface treatment	517
Foundation fill material.....	155
Foundation preparation	161
Monuments and markers	711
Pipe	581
Riprap.....	717
Sewer	588
Foundations	
Light standards.....	765
Sign supports.....	750
Gates	
Fence.....	962
Water.....	964
Geosynthetics.....	866, 1022
Geotextile.....	1022
Grade control, automatic.....	324
Grading	138
Grass seed	1002
Gray iron castings	952
Ground cover planting	883
Ground Granulated Blast Furnace Slag.....	1026
Grounding material	1001
Grounding resistance test.....	772
Grout.....	1022
Grouting	
Cast in place tendon duct	641
Precast prestressed concrete.....	631
Guardrail	696

Index

Adjusted.....	701
Adjustment.....	703
Dismantling.....	702
Hardware.....	964
Metal.....	964
Post installation.....	697
Posts.....	964
Removal.....	701
Reset.....	701
Timber.....	964
Guy wires for light standards.....	1000
Guying trees.....	881
Hammers	
Calibration tests.....	568
Diesel.....	560
for concrete piles.....	562
for steel piles.....	561
for steel shells.....	562
for timber piles.....	560
Gravity.....	560
Hardware, guardrail.....	964
Hazardous/Toxic Waste.....	71
Heated concrete.....	530
Hemp gaskets.....	937
High early strength concrete.....	504
High mast light standards.....	997
High Strength Bolts.....	442, 947
Highmast light standards.....	767
Highway signing.....	748
Highway, definition of.....	7
Holes	
Accuracy of punched and drilled holes, steel structures.....	437
Accuracy of Reamed and Drilled Holes.....	437
Drifting, steel structures.....	440
Drilled for steel structures.....	436
Punched for steel structures.....	436
Reamed or drilled.....	436
Holidays, definition of.....	7
Hydrated lime.....	1017
Hydraulic cement.....	900
Hydro-Demolition-Blasting.....	655
Inlet pipes.....	602
Inoculants for legumes.....	1005

Index

Inspection.....	47, 59
Reinspection.....	63
Source or Plant.....	60
Inspection of plants.....	884
Inspector, definition of.....	7
Inspectors	
Authority and Duties of.....	46
Duties of.....	47
Instructions to bidders, definition of.....	7
Inverts.....	602
Joining pipe.....	581, 597
Joint fillers, preformed.....	936
Joint materials.....	936
Joint mortar.....	936
Joint sealants.....	937
Joints	
Abutting steel structures.....	462
Aggregate cement base.....	256
Aggregate-Lime-Fly Ash Base Course.....	268
Asphalt paving.....	338
Concrete.....	538
Concrete median barrier.....	729
Concrete pavement.....	399
Construction.....	402
Ditch paving.....	694
Expansion.....	400, 402
Finishing.....	403
Inserts.....	402
longitudinal.....	399
Sawed.....	400
Sealing.....	412
Sewer.....	589
Soil cement.....	234
Transverse.....	400, 401, 402
Jute mesh application.....	894
Laboratory, definition of.....	8
Lacing bars.....	462
Lamps.....	770
Landscape planting.....	876
Landscape planting season.....	880
Lane closure restrictions.....	25
Laws.....	64
Laying brick.....	614

Index

Laying pipe	581
Lead, pig	954
Legal Rights, Waiver of.....	77
Letter of Credit, definition of.....	8
Leveling concrete.....	554
Liability Insurance	76
Liability of Public Officials	77
Licenses	66
Light standards.....	765, 992
Wood.....	1000
Lighting.....	756
Lighting assembly strength test.....	998
Lighting materials	991
Lime Stabilization	
Application of lime	213
Compaction and finishing	215
Curing	216
Drilling.....	218
extra depth.....	217
Extra depth stabilization	213
Final mixing.....	214
Mixing and mellowing.....	214
Preparation of existing surface.....	212
Tolerances and Reconstruction	216
Lime Treatment.....	210
Lime, hydrated	1017
Liquidated Damages	95
Litter	896
Load Restrictions	65
Longitudinal Joints	399
Loss on ignition test, mineral aggregate in asphalt paving mixture.....	311
Luminaires	767, 999
Machined riprap.....	716, 720
Maintenance	
Traffic	25
Maintenance	
During Construction.....	27
Maintenance	
Mineral aggregate base	227
Maintenance	
Soil cement	235
Maintenance	
Aggregate cement base	256

Index

Maintenance	
Prime coat	281
Maintenance	
Bituminous seal coat	294
Maintenance	
Cold mix.....	350
Major and Minor Items, definition of.....	8
Major Structures	
Backfilling.....	164
Excavation.....	158
Foundation preparation	161
Malleable castings.....	953
Manhole steps	1022
Manholes.....	1022
Manholes, catchbasins, inlets and pipe endwalls	600
Markers	710
Markers, cable.....	770
Marking steel	468
Masonry mortar.....	974
Masonry stone.....	1019
Masonry units, concrete	975
Match marking steel structures	440
Material	
Defective	63
Quality of	58
Material Guaranty	19
Material Transfer Devices (MTD)	323
Materials	
Certification	59
Handling.....	62
Information	58
Local Sources.....	58
Notice of Arrival	62
Notice of Source.....	62
Right to Materials Found on the Project	28
Sampling, Testing, and Inspection	59
Storage	62
Materials, Definition of.....	8
Measurement of Quantities	100
Mechanical mixer, aggregate cement base.....	253
Median barrier concrete	728
Median pavement.....	681
Metal beam rail	964

Index

Metallic conduit	999
Metallic pipe	980
Micro-Surfacing.....	366
Migratory Birds.....	72
Mineral Aggregate Base	220
Conditioning	259
Mineral Aggregate Base	906
Mineral aggregate surface.....	276
construction methods	277
Mineral filler.....	923
Miscellaneous materials.....	1015
Mix Design Requirements	305
Mixer	
Asphalt.....	318, 320
Mineral aggregate base	221
Polymer modified concrete	652
Mixing	
Aggregate cement base	254
Asphalt paving	330
Asphalt surface	361
Cold mix	350
Concrete	394
Concrete, curb and gutter.....	689
Lime – Fly Ash – Aggregate Mix	264, 266
Mineral aggregate base	223
Paint	486
Polymer modified concrete	655
Soil cement	232
Mixing plant	
Aggregate cement base	253
Mixing time (concrete)	531
Mobilization of forces, supplies and equipment	799
Modified asphalt cement volumetric testing	306
Modified Class A concrete.....	389
Moisture, embankment	176
Monuments	710
Mortar, masonry.....	974
Mowing.....	897
Mulch.....	879, 1005
Mulching.....	871, 883
Night Work Lighting	739
Non-metallic pipe	977
Non-metallic rigid conduit.....	999

Index

Non-reinforced concrete pipe.....	977
Notice to contractors, definition of	8
Nut rotation, steel structures	447
Oakum gaskets	937
Obstruction removal.....	129
Opening to traffic.....	48
Concrete pavement.....	413
Concrete structures.....	552
Outlet pipes	602
Overhead sign supports.....	985
Overhead wire installation	770
Packaging signs.....	988
Paint	966
Application.....	486
for pavement marking	966
for steel structures	966
Mixing.....	486
Storage	486
Paint system for steel structures.....	970
Painting	480
Application of paint	489, 490
Field painting	490
Metal	549
Pipe drains.....	598
Protection of traffic from paint	495
Repainting existing steel structures.....	491
Shop painting	489
Steel piles.....	574
Steel shells	574
Structural Steel.....	474
Surface preparation	482
Timber structures	425
Parapet, concrete.....	659
Partial Completion	48
Partial Payment	118
Patents.....	66
Pavement	
Removal.....	133
Restoration	66
Pavement markers.....	790
Pavement markers (material)	1006, 1012
Pavement marking.....	784
Removal.....	742, 795

Index

Temporary.....	743
Thermoplastic	785
Pavement markings	
Painted	793
Pavement structure, definition of.....	8
Pavers (asphalt mix).....	323
Pay item, definition of.....	8
Payment	
Altered Quantities	106
Compensable Delay Costs	115
Eliminated, Altered, or Terminated Work	114
Extra Work.....	106
Final Payment	121
Non-Recoverable Costs	118
Partial Payment.....	118
Scope of	105
Stockpiled Materials	119
Payment and Performance Bond.....	20
Payrolls	78
Perforated concrete pipe	978
Performance tests, (lighting).....	772
Performance, promptness of	74
Period of establishment, landscape	884
Permits	66
Navigable Waters.....	68
Pest Control	78
Photoelectric relay	1001
Pig lead	954
Pile drivers	559
Piles	
Bearing value	571
Cast-in-place	564, 573
Conditioning treated timber piles.....	574
Cutoffs	574
Driving.....	569
Extensions.....	573
Handling	569
Load tests	565
Order list	568
Penetration	571
Precast.....	562
splices	573
Storage.....	569

Index

Structural steel	954
Test piles	565
Timber.....	972
Piling.....	558
Classification.....	559
Pin Clearances.....	466
Pin connections	473
Pin Holes.....	466
Pins and Rollers	465
Pipe	
Bedding material	155
Bridge railing	659
Cast iron.....	980
Clay.....	978
Metallic	980
Non-metallic	977
Removal	133
Removed and relaid	592
Steel	954
Vitrified clay	978
Pipe connections, sewer	589
Pipe culvert support	155
Pipe Culverts	
Backfilling.....	165
Excavation.....	159
Foundation preparation	163
Pipe culverts and storm sewers	578
Pipe drains.....	596
Pipe end walls	600
Pipe laying	
Culverts and Storm Sewers	581
Sewer	588
Pipe removal	592
Pipe underdrains.....	723
Placing	
Asphalt curb	782
Concrete, curb and gutter	689
Plans.....	34
Conformity with.....	36
Coordination	37
Definition of.....	8
Plant Establishment.....	884
Planting season.....	880

Plants	
Ball and burlap.....	878
Container grown	878
Final acceptance.....	885
Grades	877
Health.....	877
Inspection.....	884
Names	877
Quality	878
Replacement.....	884
Storage and heeling-in	883
Plastic pavement marking (cold applied).....	1012
Plastic tubing.....	978
Plate cut edges	460
Plates	
Bent.....	463
Web.....	463
Pointing stone masonry.....	609
Polish-Resistant Aggregates	927
Pollution Control	
Air.....	72
SWPPP.....	69
Water.....	68
Polymer modified concrete	650
Curing	656
Placing, Consolidating, Finishing	656
Reconstruction	657
Texturing.....	656
Portable Barrier Rail	732
Portable Impact Attenuators	733
Portland cement concrete base.....	238
Portland Cement Concrete Pavement	387, <i>See</i> Concrete Pavement
Post installation, guardrail	697
Posts	
Guardrail	964
Signs	749
Stock fence.....	956
Post-tensioned, prestressed, cast in place concrete	634
Post-tensioning, precast concrete.....	628
Precast concrete box sections.....	978
Precast concrete piles.....	562
Precast-prestressed concrete	618
Precoated galvanized pipe.....	981

Index

Preconstruction Conference	39
Preformed joint fillers	936
Preformed plastic pavement markers	792
Prequalification Questionnaire.....	12
Prequalification, definition of	9
Presplitting	143
Prestressing methods.....	619
Prestressing, cast in place concrete	639
Pretensioning, precast concrete	622
Primavera Project Management	84
Prime coat	279
Application.....	281
Cover material.....	281
Protection	281
Surface preparation	280
Project Sign	805
Project, acceptance of	49
Project, definition of	9
Proportioning	
Concrete pavement.....	387
Lime-Fly Ash-Aggregate Mix.....	263
Polymer modified concrete	651
Portland cement concrete base	239
Precast concrete.....	623
Proposal	
Consideration of.....	19
Delivery of	15
Preparation of.....	14
Public opening	15
Rejection of.....	16
Withdrawal of	15
Proposal form, definition of.....	9
Proposal Forms	12
Proposal guaranties, Return	19
Proposal guaranty, definition of.....	9
Proposal, definition of.....	9
Protection	
Lakes	68
Protection	
Reservoirs	68
Protection	
Streams.....	68
Protection	

Index

Forest	71
Protection	
Hazardous/Toxic Waste	71
Protection	
Prime coat	281
Protection	
Bituminous seal coat	294
Protection	
Concrete pavement.....	412
Protection	
of traffic from paint.....	495
Protection	
Concrete	549
Protection	
Prestressing steel.....	635
Protection	
Sidewalk, median pavement, and driveways	684
Protection	
Concrete curb and gutter	690
Protection	
Ditch paving.....	694
Protection	
Asphalt curb	783
Protection	
Seeding	872
Pruning shrubs	882
Pruning trees	881
Public Convenience	73
Pugmill.....	221
Pull boxes.....	762, 814, 1000
Pulverizing (soil cement)	232
Punched holes	436
QPL, definition of	9
Quantities	13
Railroads, cooperation with	40
Raised pavement markers	790
Reamed Holes	436
Reconstruction, soil cement	235
Recycled Asphalt Pavement	244, 356
Recycled Asphalt Shingles	246, 358
Reflective pavement markers.....	790
Reflective sheeting	
Application.....	987

Index

for signs.....	988
ReflectORIZATION of signs	987, 988
Reinforced concrete pipe	977
Reinforcement for prestressing	944
Reinforcing bar	524
for concrete structures.....	943
Splicing	525
Substitution	524
Relaying pipe	594
Relays.....	1000
Removal of guardrail	701
Removal of pavement marking	742
Repainting steel structures	491
Reset guardrail	701
Restoration	66
Retarder for concrete.....	1017
Rideability.....	550
Right-of-Way	76
Right-of-Way, definition of	9
Riprap	
Classification.....	716
Machined.....	720
Riprap and slope pavement	714
Road, definition of	7
Roadbed, definition of.....	9
Roadside development, definition of	9
Roadside Maintenance	896
Roadside, definition of.....	9
Roadway and structure lighting	756
Roadway, definition of.....	9
Rock Cuts.....	143
Rock Drilling (bridges)	155
Rollers, asphalt.....	325
Rolling	
Bituminous seal coat	293
double bituminous seal coat	294
Rubber gaskets	937
Rust inhibitor, prestressing steel	635
Safety	73
Employee Health and Safety Program	73
Public	73
Sampling	59
Asphalt mix.....	322

Index

Resampling	63
Sandbag Berms and Channel Plugs	196
Sanitary Provisions	73
Sanitary sewers	587
Sawed joints.....	399
Scales	
Asphalt.....	316, 320
Schedule.....	81
Critical Path Method.....	84
Sealants	
Bridge deck.....	941
Joint.....	937
Sealing joints.....	412
Seed, grass	1002
Seedbed.....	870
Seeding	869
Seeding repair	872
Seedling planting	882
Select material for soil-cement	1017
Service connection.....	819
Service poles.....	1000
Sewer brick	974
Sewer joints	589
Shaping	147
Mineral aggregate base	225
Shells, steel	954
Shipping steel.....	468
Shop assembling, steel structures.....	438
Shop Drawings.....	11, 34
Shop inspection.....	429
Shop painting signs.....	987
Shotcrete	664
Preconstruction Test Panels	667
Production Test Panels.....	668
Proportioning	664
Quality Control and Acceptance	667
Test Panel Curing and Testing.....	668
Shoulder.....	188, 413
Shoulder, definition of	10
Shrub	
Planting.....	882
Pruning.....	882
Setting.....	882

Index

Sidewalk	
Concrete	681
Removal	133
Sign posts	749
Sign support foundation	750
Signing	748
Signing materials	748
Signs.....	752
Accessories	988
Borders.....	988
Fabrication	984
Flat sheet signs.....	985
Legends.....	988
Multiple panel signs.....	985
Silicone additive.....	331
Silk screening signs.....	987
Silting.....	68
Slope pavement.....	714
Slope paving.....	719
Slump.....	389, 508
Slurry Seal.....	364
Snowplowable reflective pavement markers.....	791, 1012
Sod	
Care	890
Establishment.....	890
Material	887
Placement.....	889
Removing and storing for resetting.....	889
Repair.....	773
Weather limitations	889
Sodium chloride	1017
Soil Cement Base.....	230
Special provisions, definition of	10
Specialty Item, definition of.....	10
Specifications	
Conformity with.....	36
Coordination	37
Definition of.....	10
Spiking, timber structures	424
Splices, electrical conductor.....	764
Splicing material for light wire	1001
Spread footings	522
Spreading	

Index

Aggregate, bituminous seal coat	293
Aggregate-Lime-Fly Ash Base Course	267
Asphalt mixes	331
Cement, aggregate-cement base.....	254
Cement, soil cement base.....	232
Mineral aggregate base	224
Stability, embankments.....	179
Stakes.....	879
Stakes, Lines, and Grades	42
Standard Gradation for mix design	247
Standard Specifications, definition of.....	10
Staples.....	1014
State, definition of.....	10
Station	101
Stationary mixing plant	
Aggregate cement base	255
Steam curing concrete.....	626
Steel	
Cast	952
Corrosion resistant	953
for signs	983
Forgings	952
Pipes.....	954
Shells.....	954
Stainless for signs	984
Steel plate for cold working	946
Steel Structures	428
Assembling	472
Erection.....	470
Fabrication	463
Full size test of steel members	467
Identification.....	466
Misfits.....	472
Shop assembling	438
Steps, manhole	1022
Stiffeners.....	464
Stock fence.....	956
Stockpiled Materials	119
Stockpiling aggregate.....	924
Stone Masonry	605
Arch rings	610
Back walls.....	611
Bridge seats.....	611

Index

Classification.....	605
Copings	611
Pointing.....	609
Stone laying	607
Top walls.....	611
Storm sewers.....	578
Straightedge Testing	
Concrete pavement.....	405
Strand cable.....	819
Street, definition of	7
Stress Relieving	465
Stress transfer.....	629
Stressing requirements, precast-prestressed concrete.....	621
Stringers, timber structures	422
Stripping test, bituminous material	310
Structural removal.....	130
Structural steel	946
Structural steel bridge railing	659
Structural steel piles	954
Structural timber	971
Structure Excavation.....	153
Structure excavation for pipes.....	581
Structures	
Concrete	499
Steel	428
Stumps	125
Subcontractor, definition of	10
Subgrade	
Bituminous Material	211
Checking	185
Compaction.....	184
construction and preparation	183
Drainage and protection	184
Equipment.....	211
Preparation (soil cement)	232
Treatment (lime)	210
Subgrade preparation	
Curb and gutter	689
Ditch paving.....	693
Driveways	682
Median pavement.....	682
Sidewalks	682
Subgrade, definition of.....	10

Index

Substructure, definition of	10
Superintendent, definition of	10
Superstructure, definition of	10
Supplemental Specification, definition of.....	11
Supports	
Overhead signs.....	752, 985
Traffic signal.....	851
Surety, definition of.....	11
Surface preparation	
Asphalt concrete	361
for paint.....	482
Prime coat	280
Signs	986
Slurry seal and micro-surfacing	373
Tack coat.....	285
Surface requirements	
Asphalt base.....	249
Asphalt paving	339
Asphalt surface	361
Cold mix	350
Mineral aggregate base	227
Surface Requirements for treated permeable base	273
Surface tolerance	
Aggregate cement base	256
Concrete base.....	239
Survey	42
Suspending pipe drains	597
Suspension, temporary.....	90
Suspensions.....	22
swampy areas.....	<i>See Clearing and Grubbing</i>
Switches	1000
Tack coat.....	284
Application.....	285
application temperatures	285
bituminous materials.....	284
Surface preparation	285
Taxes.....	66
Temperature	
Asphalt.....	301, 314, 328
Tack coat.....	284
Temporary pavement marking.....	743
Temporary structures	661
Temporary supports for structural steel	471

Index

Temporary traffic control.....	731
Temporary traffic control plan	744
Tendons, prestressing.....	639
Tension wire, chain link fence	962
Termination.....	95
Convenience.....	97
Default	95
Without Fault	97
Terms	<i>See Definitions</i>
Test piles	565
Testing	59
Field Laboratory.....	60
Retesting	63
Texture coat for concrete	1024
Thermoplastic pavement marking.....	785
Thickness	
Aggregate cement base	256
Aggregate-Lime-Fly Ash Base Course	268
Asphalt base	250
Concrete base	240
Mineral aggregate surface	278
Soil cement.....	234
Threads for bolts and pins.....	466
Tie bars	943
Tile, drain.....	978
Timber.....	971
Grades	971
Piles.....	972
Rail.....	964
Timber protection.....	421
Timber Structures	
Concrete pedestals.....	421
Erection	424
Flooring.....	423
Framing.....	422
Mud sills.....	421
Painting	425
Posts for bents	422
Sills	422
Stringers	422
Time, contract definition of.....	6
Time, project completion	91
Tolerance	

Index

Concrete base	240
Concrete pavement thickness.....	414
Precast-prestressed bridge units	631
Soil cement	234
Top rail, chain link fence	960
Tops of walls	
Brick masonry.....	615
Stone masonry.....	611
Topsoil	882
for landscape plants.....	879
Stripping, stockpiling, and placing	146
Traffic	
Aggregate cement base	256
On soil cement	235
Opening Sections of a Project to	48
Traffic cones	732
Traffic signal coordination.....	851
Traffic signal supports	851
Traffic signals	808
Transfer of stress.....	629
Transformer base	815
Transverse Joints.....	400, 401, 402
Treated Permeable Base.....	270
Tree	
Planting	880
Pruning.....	881
Setting	880
Staking	881
Wrapping	881
Trees, removed.....	125
Tremie.....	540
Trimming	897
Truss rods, chain link fence	962
Turnbuckle, chain link fence.....	962
Unacceptable Work.....	48
Unauthorized Work.....	48
Undercutting	141, 145
Underdrains.....	722
Aggregate.....	723
Aggregate with pipe.....	723
Filtercloth.....	724
Underground cable.....	763
Underground Storage Tanks	133

Index

Underwater concrete	539
unit of payment	101
Unsuitable Material.....	146
Unsuitable Soil.....	144
Utilities, cooperation with.....	40
Value Engineering Change Proposal.....	29
Vibrating concrete.....	538
Vitrified clay pipe	978
Voltage test	771
Warm Mix Asphalt.....	329
Process Equipment.....	316
Washers	
for timber structures	424
Water.....	879
for concrete	1015
Water crossings	964
Water for curing concrete	976
Water gates.....	964
Water reducer	
(high range) for concrete.....	1018
accelerator for concrete.....	1018
for concrete	1017
retarder for concrete	1017
Water Well Abandonment	134
Watering, landscape	884
Waterproofing.....	549, 940
Waterstops.....	549
Waterstops.....	1019
Watertightness, sanitary sewers	590
Weather limitations, sod	889
Web plates.....	463
Weep holes.....	527
Weighing of steel members.....	467
Welded wire reinforcement.....	944
Welds	460
Wheel Guards.....	423
Wire assemblies for posttensioning	944
Wire installation, overhead	770
Wire strand, seven wire for prestressed concrete	944
Wire ties, chain link fence.....	962
Wire, Barbed.....	958, 961
Wiring	819, 998
Wood light poles	766, 767

Index

Work Methods 89
Work Order 11, 81
Work, definition of 11
Work, extra, definition of 7
Workers 89
Working days 91
Working Days 11
Working drawing, definition of 11
Working Drawings 34
Wrapping trees 881
Yard lumber 971
Zinc, inorganic paint system 970

STATE

(Rev. 9-7-21)

(Rev. 12-15-21)

OF

TENNESSEE

January 1, 2021

Supplemental Specifications – 100SS

of the

Standard Specifications for Road and Bridge Construction

January 1, 2021

Subsection 104.03.B & C (pg. 23-24), 9-7-21; **Contract Change Notification; B & C**; Revise subsections:

B. Written Acknowledgement by Engineer

The Engineer will provide written acknowledgement of the Contractor's written notice within ten (10) calendar days.

C. Written Response by Engineer

The Engineer will provide a written response within the specified number of calendar days based on the requested contract change:

1. For requested changes to the contract time in excess of one hundred eighty (180) days or requested changes that alter the original contract amount by more than \$200,000, the Engineer will respond within thirty (30) days of receiving the Contractor's written notice.
2. For requested changes to the contract time in excess of ninety (90) days but less than or equal to one hundred eighty (180) days, or requested changes that alter the original contract amount by more than \$100,000 but less than or equal to \$200,000, or by more than ten percent (10%) of the original contract, whichever is less, the Engineer will respond within twenty-one (21) days of receiving the Contractor's written notice.
3. For all other requested changes to the contract, the Engineer will respond within fourteen (14) calendar days of receiving the Contractor's written notice.

The written response to the Contractor's written notice will include one of the following:

1. Confirmation that a change is necessary in accordance with **104.02**, and direction on how the Work will proceed.
2. A denial of the request for a change, which will include references to the Contract as to why the condition does not represent a change.
3. A request for additional information stating the specific information needed and the date by which it must be received. The Engineer will respond to the additional information provided within fourteen (14) calendar days.

When a change is necessary, the Engineer will make appropriate adjustments to the Contract price and time, if warranted, in accordance with **108.07**, **109.04**, **109.05.A**, and **109.06**. If the Contractor disagrees with the Engineer's decision or does not agree with the Contract adjustments, the Contractor may pursue the issue as a claim in accordance with **105.16**.

Subsection 106.06.A.1 (pg. 61), 12-15-21; **Field Laboratory, Type A**; Revise No. 1:

1. Scales of appropriate capacity and design to weigh the required samples. Scales are to be sensitive to within 0.1% of the sample to be weighed. Provide standard weights for scale calibration. Scale calibration shall ~~be~~ completed annually every six months, by an independent source ~~with no calibration exceeding 6 months to the day in~~.

Subsection 108.01 (pg. 79, 80), 12-15-21; **Subletting of Contract**; Revise Item list:

Item 105-01 – Construction Stakes, Lines and Grades
 Item 202-01.~~02~~ – Removal of Asbestos
~~Item 203-40 – Rock Anchors, Anchor Blocks, Tie Back Anchors~~
 Item 209 – ~~Project~~ EPSC
 Item 411-12 – ~~** Shoulder~~ Scoring
~~Item 411-33 – Stamped Asphalt~~
 Item 501-03.~~12~~ – Concrete Shoulder Rumble Strip
~~Item 503-01 – Grinding Concrete Pavement~~
 Item 602-03 – Steel Structures
 Item 602-04 – Steel Structures
~~Item 602-10.13 / .14 – Navigational Lighting~~
 Item 602-10.81 – Heat Straightening
 Item 603-02 – Repainting Steel Structures
 Item 603-05 – Containment and Disposal of Waste
 Item 604-04.01 – Applied Texture Finish (New Structures),
 Item 604-04.02 – Applied Texture Finish (Existing Structures)
~~Item 604-04.10 – Graffiti Protection~~
~~Item 604-04.20&.21 – Painting or Staining Concrete Surfaces~~
 Item 604-04.62 – Clean and Texture Finish Median Barrier
 Item 604-05.31 – Bridge Deck Grooving (Mechanical)

- Item 604.07 – Retaining Wall
- Item 604-42.01 – Underwater Divers
- Item 606-26.05 – Core Drilling for Piles (Abandoned)
- Item 617 – Bridge Deck Sealant
- Item 619 – Polymer Modified Concrete Overlay
- Item 624 – Retaining Wall ~~Items~~
- Item 625-01.08,10,11 – Inclinator, Camera Drilled Shaft Inspections
- ~~Item 640 – Weigh Station Items~~
- Item 705 – Guardrail, ~~Anchors, etc.~~
- Item 706 – Guardrail Adjusted, Removed and Reset~~Items~~
- Item 707 – Fence ing ~~Items~~
- Item 712 – Temporary Traffic Control ~~Items~~
- Item 713 – Highway Signing ~~Items~~
- Item 714 – Roadway and Structure Lighting ~~Items~~
- Item 716 – Pavement Markings ~~Items~~
- ~~Item 720-03, 720-04, 720-05, 720-06, 720-07, 720-08, 720-09 – Railroad Highway Crossing~~
- ~~Item 721-01.06 – Irrigation System Repair~~
- Item 721-10, 721-11.20, 721-11.30, 721-12 – Landscape and Irrigation
- Item 724 – Landscape Lighting
- Item 725 – ITS items
- Item 730 – Traffic Signals ~~Items~~
- Item 740 – Geosynthetics
- Item 79* – Utilities ~~Items~~
- ~~Item 750.01 – Mitigation Site~~
- Item 801 – Seeding
- Item 802 – Landscaping ~~Items~~ Plantings
- Item 803-01 – Sodding
- Item 805 – Erosion Control
- Item 806 – Project Mowing

Subsection 108.03.A, B, & C (pg. 81,82,85,87,88), 9-7-21; **Contract Change Notification; A & B;** Revise Heading,
C.1.c; Add new No.vi, **C.3;** Revise last paragraph, **C.4;** Revise last paragraph & add sentence:

A. Project Durations Less Than 9 Months

B. Project Durations 9 Months to 24 Months

C.1.c Narrative report in PDF file format fit to 8.5x11 inch paper and including:...

- vi. The quantity and estimated daily production rate for controlling activities;
- vii. Description of the calendars including identification of workdays per week, holidays, number of shifts per day, and number of hours per shift;
- viii. Description of how the schedule accommodates adverse weather days for each month; and

- ix. Description of execution plan, including number and type of crews, a list of subcontractors’ crews, and expected equipment, but not limited to large equipment transport and delivery, transportation permits for oversized/overweight loads, and availability.

3. Baseline CPM Schedule.

The Engineer and Contractor will review the draft baseline CPM schedule at a meeting specific for the review of the schedule. The Engineer will accept the draft baseline CPM schedule, provide review comments, or request additional information. Make appropriate adjustments or provide additional information within 14 calendar days. The Engineer’s acceptance is based solely on whether the baseline schedule meets the requirements of **108.03**. Review comments made by the Engineer on the initial schedule will not relieve the Contractor from compliance with the Contract. The Contractor is responsible for scheduling, sequencing, and prosecuting the Work to comply with the Contract requirements.

4. Schedule Updates.

Submit the updated schedule electronically to the Engineer in accordance with the requirements of this subsection. The Engineer reserves the right to reject any schedule updates because of changes in relationships between activities on the critical path, inadequate or inaccurate narrative updates, or other deficiencies in the schedule updates as required in this subsection.

The Department will measure and pay for CPM Project Schedule in accordance with **108.11** and **108.12** respectively.

Subsection 108.11 (pg. 99), 9-7-21; **Method of Measurement**; Add subsection **108.11**:

108.11 Method of Measurement

The Department will measure construction CPM Project Schedule as a percentage of the lump sum price bid for the completion of the work specified in **108.03.C** and partial payment will be made according to the schedule in Table 108.11-1.

Table 108.11-1: Payment Schedule for CPM Project Schedule

Estimate Number or Percent of Total Contract Amount of Previous Estimate	Total Percent of CPM Project Schedule Lump Sum Bid Item
Estimate # 1	20%
Estimate # 3	40%
20%	50%
40%	60%
60%	70%
80%	80%
95%	100%

Subsection 108.12 (pg. 99), 9-7-21; **Method of Measurement**; Add subsection **108.12**:

108.12 Basis of Payment

The Department will make partial payments for CPM Project Schedule on the basis of a percentage of the lump sum price bid in accordance with the schedule shown in Table 108.11-1.

If the Contractor fails to provide monthly schedule updates, or address the Engineer's comments regarding the monthly schedule update, within 10 calendar days following the progress estimate pay period cutoff date, the Engineer will withhold payment for CPM Project Schedule and may withhold up to an additional 5% of the monthly estimate payment, until such time as an acceptable update has been provided.

No additional payments will be made for schedule revisions as requested per **108.03.D**.

Such payment is full compensation for meeting all requirements of **108.03.C** and **D**.

STATE

OF

TENNESSEE

(Rev. 12-15-21)

January 1, 2021

Supplemental Specifications – 400SS

of the

Standard Specifications for Road and Bridge Construction

January 1, 2021

Subsection 403.04 (pg. 286), 12-15-21; **Preparing Surface**; Revise Paragraph:

Prepare the designated surface as specified in **4054.05**. Ensure that the surface is dry when applying tack coat.

Subsection 403.05.C (pg. 286), 12-15-21; **Fog Sealing**; Revise 1st Paragraph:

When the Contract requires bituminous material for fog sealing of shoulders, provide emulsified asphalt meeting **403.02** or an item from QPL 40A. Apply diluted emulsified asphalt at a rate of 0.10 to 0.15 gallons per square yard based on a dilution rate of one part emulsified asphalt to one part water. This application may require two equal increments if run-off occurs. Apply fog seal when the ambient air temperature or the surface temperature is a minimum of 50°F.

Subsection 407.09 (pg. 326-327), 12-15-21; **Weather Limitations**; Revise No. 2 & 3:

2. The bituminous plant mix is placed according to the temperature limitations specified in Table 407.09-1 and when weather conditions otherwise allow the pavement to be properly placed, compacted, and finished. Placement may proceed if either the air or surface temperature is met except for 411-TL, 411-TLD, 411-TLE, and 411-OGFC mixtures.

Measurement of the surface temperature shall be done on pavement that is shaded from direct sunlight unless no shaded location exists. If paving based on the air temperature, stop work once the air temperature falls below the minimum threshold. Do not start paving if the surface temperature does not meet the requirements and the air temperature is forecast to fall below the minimum temperature within 4 hours of starting work.

Table 407.09-1: Temperature Limitations

Compacted Thickness	Minimum Air or Surface Temperature (°F)	
	Unmodified mixes (PG 64, 67)	Modified mixes (PG 70, 76, 82)
≤ 1.5 inches	45	55
> 1.5 inches to < 3.0 inches	40	50
≥ 3.0 inches	35	45

3. For 411-TL, 411-TLD, 411-TLE, and 411-OGFC mixtures, placement shall proceed only when the pavement surface temperature and the air temperature are a minimum of 55° F and rising. Stop paving if the air temperature falls below 55°F immediately. Placement of these mixtures is restricted to the period between April 1 and October 31.

For all other mixtures, Do not place bituminous plant mix, with a compacted thickness of 1.5 inches or less, between November 30 and April 1. Do not place bituminous plant mix, with a compacted thickness greater than 1.5 inches, between December 15 and March 16. Only place 411-TL, 411-TLD, 411-TLE, and 411-OGFC mixtures when the pavement surface temperature and the ambient air temperature are a minimum of 55°F and rising; limit placement to the period from April 1 to November 1. If the temperature meets the above requirements, outside of normal paving season, a request for a seasonal limitation waiver may be submitted for Departmental consideration. Requests shall be submitted in writing at least one week before the anticipated need.

Subsection 407.15.C (pg. 336-337), 12-15-21; **Test Strips**; Revise 1st Paragraph:

Construct test strips for all A, B, BM, BM-2, C, CW, D, and E mixtures that require density testing to establish rolling patterns, to accommodate the Department to calibrate nuclear gauges, to verify that the base course or surface course mixture meets the density requirements of the specifications, and for mix design and production verification as required. A test strip is not required for mixes AS, A-CRL, CS, TL, TLD, and TLE, but a adjustments to the roller pattern may be made at the direction of the Engineer for mixtures that do not require density testing.

Subsection 407.20.C.3 (pg. 346-347), 12-15-21; **Loss on Ignition (LOI)**; Revise 2nd & Remove 4th Paragraph:

If the percent of LOI in the aggregate differs by plus or minus 2% from the LOI indicated in the JMF, the Department will make a payment deduction in the price bid for the mix applied to the entire days production, not as a penalty but as liquidated damages. The percent of total payment to be deducted will be 5 times the percent that the LOI exceeds the JMF tolerance of plus or minus 2%.

To determine the deduction, the Department will use lots of approximately 5,000 square yards. The Department inspector will perform sampling and testing to establish the LOI according to the Department's sampling and testing procedures. If the initial tests indicate a variation in the LOI of plus or minus 2% than the value shown on the mix design, the Contractor shall perform the additional sampling necessary to establish the LOI of the aggregate in each lot, with the cost of the sampling being included in the contract unit prices bid for the paving items.

Subsection 411.03.B (pg. 353), 12-15-21; **Proportioning**; Revise Table 411.03-01:

Table 411.03-1: Proportions of Total Mixture, Percent by Weight

Surface Course	Effective Combined Mineral Aggregate	Asphalt Cement
Grading D	93.0 – 94.3	5.7 – 7.0 ⁽¹⁾
Grading E ⁽²⁾	93.0 – 94.3	5.7 – 7.0 ⁽¹⁾
Grading E (shoulders)	93.5 – 94.0	6.0 – 6.5 ⁽¹⁾
Grading TL	92.5 – 94.3	5.7 – 7.5 ⁽¹⁾
Grading TLD	93.0 – 94.3	5.7 – 7.0 ⁽¹⁾
Grading TLE	93.0 – 94.3	5.7 – 7.0 ⁽¹⁾
<u>Grading TLE (shoulders)</u>	<u>93.5 – 94.0</u>	<u>6.0 – 6.5 ⁽¹⁾</u>
Grading OGFC	92.0 – 94.0	6.0 – 8.0 ⁽¹⁾

⁽¹⁾ If the effective combined specific gravity of the aggregate exceeds 2.80, the above proportions may be adjusted as directed by the Engineer. The upper limit for flow values shall not apply to mixes with modified asphalt liquids.

⁽²⁾ The minimum allowable asphalt cement content for 411E low volume mixtures is 5.3%.

Subsection 411.03.C.1 (pg. 358), 12-15-21; **Recycled Asphalt Pavement**; Revise 2nd Paragraph:

All mixes shall contain at least 80% virgin asphalt, except for 411E Shoulder and 411TLE Shoulder Mixtures, which shall have at least 65% virgin asphalt.

STATE

OF

TENNESSEE

(Rev. 12-15-21)

January 1, 2021

Supplemental Specifications – 600SS

of the

Standard Specifications for Road and Bridge Construction

January 1, 2021

Subsection 602.04.A (pg. 429), 12-15-21; **Shop Inspection**; Revise A:

Fabricators of steel bridges shall hold the following certifications in accordance with the AISC Certification Program ~~– Bridge QMS Certification for Structural Steel Fabricators – Standard for Steel Bridges~~:

1. As a minimum, all fabricators shall be certified in the category of ~~intermediate bridges~~ Certified Bridge Fabricator – Intermediate Bridge (IBR) with applicable supplemental requirements.
2. Fabricators of advanced type bridges, as defined in the AISC Standard for Steel Bridges, shall be certified in the category of ~~advanced bridges~~ Certified Bridge Fabricator – Advanced (ABR) with applicable supplemental requirements.
3. Fabricators of diaphragms, cross-frames, floor beams, stringers (rolled beams) and laterals shall be certified in the category of Certified Bridge Fabricator – Intermediate Bridge (IBR) ~~Intermediate bridges~~, as a minimum.
4. Fabricators of bridge bearings, expansion joints, sign structures and other metal highway components as listed in the AISC standard shall hold certification ~~under the AISC Certification Program – Standard for Bridge and Highway Metal Component Manufacturers. As an alternative, fabricators of bridge bearing or expansion joints may hold certification in the category of Intermediate bridges under the Standard for Steel Bridges.~~ under the AISC Certification Program – Bridge Component QMS Certification (CPT). As an alternative, fabricators of bridge bearing or expansion joints may hold certification under the Bridge QMS Certification in the category of Certified Bridge Fabricator – Intermediate Bridge (IBR).

Subsection 607.02.B (pg. 579), 12-15-21; **Materials, Pipe Culverts, Cross Drains, Side Drains, & Storm Drains**; Remove 1st Sentence:

B. Pipe Culverts, Cross Drains, Side Drains, & Storm Drains

~~Where Pipe Culverts (Cross Drains & Median Drains) are specified, provide them in accordance with the following:~~

Subsection 607.07 (pg. 582), 12-15-21; **Joining Pipe:** Revise 5th paragraph.

HDPE, PP, SRTRP, and PVC pipe shall be joined in accordance with ASTM D3212 and meet the performance requirements for ~~soil tightness, unless~~ water-tightness is specified. Install joints so that the connection of pipe sections, for a continuous line, will be free from irregularities in the flow line.

Subsection 619.04.A (pg. 652-653), 12-15-21; **Volumetric Continuous Mixers;** Revise No. 3 & Ticket List:

3. The volumetric mixing plant shall be operated and calibrated by a Volumetric Mixer Operator ~~certified by VMMB and holds~~ with a TDOT Concrete Field Testing Technician Certification or equivalent. In the presence of the Engineer, perform the calibration of gate settings according to the manufacturer's recommendations for the mix design to be used before starting work. The calibration procedure shall account for the moisture content of the aggregates. The yield shall be maintained within a tolerance of plus or minus 1% and verified using a minimum 2 cubic feet container every 50 cubic yards. Recalibrations will be necessary when indicated by the yield checks, and at any other times the Engineer deems necessary to ensure proper proportioning of the materials.

Each load of concrete produced by a volumetric continuous mixing plant shall be accompanied by a Concrete Delivery Ticket. The ticket shall include as a minimum the following:

- a. Date
- b. Contract number
- c. County
- d. Class of concrete
- e. Concrete design number
- f. Number of cubic yards
- g. Load number
- h. Truck number
- i. Maximum water allowed by design
- j. Total water added
- k. Water-cementitious materials ratio
- l. Time loaded
- m. Time discharged
- n. Signature of producer's ~~VMMB-Certified~~ Volumetric Mixer Operator

Subsection 623.02.C.1 (pg. 673), 12-15-21; **Modular Roadway Expansion Joints, Fabrication and Construction;** Revise No. 1:

1. Construct the expansion joint systems as shown on the shop drawings. Meet the tolerance requirements included in AASHTO specifications. Perform all welding according to AWS specifications and by certified welders only. Ensure that fabricators are certified ~~under the AISC Quality Certification, Category I, Simple Steel Bridges, SBR-1B, under the AISC Certification Program – Bridge Component QMS Certification (CPT). As an alternative, fabricators of bridge bearing or expansion joints may hold certification under the Bridge QMS Certification in the category of Certified Bridge Fabricator - Intermediate Bridge (IBR).~~

Subsection 623.03.C.2 (pg. 676, 677), 12-15-21; **Strip Seal Expansion Joints, Fabrication and Construction**; Revise No. 2:

2. Shop drawings shall also supply information regarding material specifications, geometry, a table of variable temperature and dimensions, and a bill of material. The maximum joint opening shall be 4 inches. Construct the expansion joint systems in accordance with the details shown on the shop drawings. Tolerance requirements shall be in accordance with AASHTO Specifications. Perform all welding in accordance with AWS specifications and by certified welders only. Ensure that fabricators are certified ~~under the AISC Quality Certification, Category I, Conventional Steel Structures.~~ under the AISC Certification Program – Bridge Component QMS Certification (CPT). As an alternative, fabricators of bridge bearing or expansion joints may hold certification under the Bridge QMS Certification in the category of Certified Bridge Fabricator - Intermediate Bridge (IBR).

STATE

OF

TENNESSEE

(Rev. 12-15-21)

January 1, 2021

Supplemental Specifications – 700SS

of the

Standard Specifications for Road and Bridge Construction

January 1, 2021

Subsection 705.06 (pg. 698), 12-15-21; Installation of Posts; Add new 7th Paragraph:

When an underground structure or utility prevents proper post installation for a run of guardrail, posts may be omitted along the run of guardrail only as detailed in the Department's Standard Drawings. A post will not be omitted from any end terminal or transition. If the conditions noted for omitting posts cannot be used, then the use of a guardrail footing or weak post attachment to culvert may be used as detailed in the Department's Standard Drawings

Subsection 705.10 (pg. 700), 12-15-21; Basis of Payment; Add new 7th Paragraph:

When posts are omitted from a run of guardrail, payment shall be as noted in the Standard Drawings.

- a. For 1 post being omitted, the Department will pay the contract unit price for W Beam Guardrail (Type 2) MASH TL-3.
- b. For 2 or 3 posts being omitted, the Department will pay for the linear feet of nested W Beam rail as detailed in the Standard Drawings at a rate equal of 1.5 times the contract unit price for W Beam Guardrail (Type 2) MASH TL-3.
- c. If a guardrail footing or attachment to culvert was used, the Department will pay for work as noted in the Standard Drawings.

Subsection 712.02 (pg. 731-732), 12-15-21; **Materials; Revise List:**

Aluminum.....	916.02
Reflective Sheeting.....	916.06
Paint.....	910.026.09
Cold Rolled Carbon Steel -16 gauge	ASTM A1008
Non-metallic Drums and Barricades	QPL
Reflective Sheeting.....	916.06

Subsection 712.02.B (pg. 732), 12-15-21; **Temporary Pavement Marking Material; Revise 1st Paragraph:**

Unless otherwise specified, the material for pavement marking ~~line~~ shall be either temporary pavement marking tape listed on the Department’s QPL, or reflectorized paint with raised reflective pavement markers placed as shown on the Plans

Subsection 712.02.E (pg. 733), 12-15-21; **Portable Impact Attenuators; Revise Heading & 1st Paragraph:**

E. ~~Portable Impact Attenuators~~ Temporary Work Zone Crash Cushions

~~Portable impact attenuators~~ Temporary work zone crash cushions shall be in accordance with the Plans and Specifications, meet the requirements for the appropriate test level, and meet the requirements of and be listed on the Department’s QPL or Standard Drawings.

Subsection 712.04.B (pg. 735-736), 12-15-21; **THP Troopers and Uniformed Law Enforcement Officers; Revise 2nd Paragraph:**

When a THP Trooper is not available, the Contractor may provide a Uniformed Law Enforcement Officer if approved by the Engineer and the Regional Safety Coordinator or Regional Operations Office. All Uniformed Law Enforcement Officers shall provide a marked Federal, State, County, City, or Metropolitan government law enforcement vehicle equipped with blue lights and have the authority to write traffic tickets and make arrests within the project site. The Uniformed Law Enforcement Officer shall maintain a detailed written log of enforcement activities and shall submit the log to the Engineer for verification each month.

Subsection 712.06 (pg. 743), 12-15-21; **Temporary Marking; Revise Heading, Add No. 2, & Revise No. 1 & 3:**

712.06 Temporary Pavement Centerline and Lane Marking

Unless otherwise specified, install temporary pavement marking as follows:

1. Provide 4-inch wide pavement marking (line) for center, edge, lane and barrier lines as shown on the Plans for projects that will have traffic maintained overnight. For temporary pavement ~~line~~ markings (line) on intermediate layers of pavement, use reflective tape, reflectorized paint, and raised pavement markers, or a combination thereof as shown on the Plans or as required by the Engineer, and install meeting 716, 910.02, 919.04, or Department's QPL at the end of each day's work to permanent standards before dark hours. Short, unmarked sections will not be allowed. ~~The Department will measure and pay for these markings as Painted Pavement Marking (Line) in accordance with 716.08 and 716.09.~~ Preserve established no-passing zones, if any, on the existing pavement; if no-passing zones have not previously been established, establish them before beginning the work. Mark two-lane, two-way highways with 10-foot long center lines applied on 40-foot centers and appropriate no-passing barrier lines.
2. When required, provide temporary pavement markings at intersections for temporary pavement markings on intermediate layers of pavement. The Department will require temporary intersection pavement markings to be reflectorized paint, or removable pavement marking meeting 716, 910.02, 919.04, and or Department's QPL.
3. Where required on the completed permanent pavement surface, for 10-foot lane lines, no-passing barrier line, and edge line, use reflectorized paint applied as specified in 716 meet 716.03.

Subsection 712.09 (pg. 744, 745), 12-15-21; **Method of Measurement; Revise No. 5, 7, 8 & Add 9:**

5. Warning Lights and Flashing Arrow Boards by the unit, Changeable Message Signs per each for the type designated. Payment will be based on the maximum number in place at one time.
7. ~~Portable Impact Attenuators~~ Temporary Work Zone Crash Cushion based on the initial installation of each ~~portable impact attenuator~~. No additional payment will be made for removal, moving, and reinstalling ~~impact attenuators~~ at other locations on the Project as directed by the Engineer. Payment will be based on the maximum number ~~of portable impact attenuators~~ in place at one time.
8. Temporary pavement marking (line) for edge, center, lane and barrier lines will be measured as listed in the plans, as described for complete in place and accepted, as Painted Pavement Marking (Line) in 716.07 regardless of whether the lines are painted, taped markings, or raised pavement markers, or a combination of the above as shown on the Plans or as required by the Engineer, ~~except that Removable Pavement Marking (Line) will be measured by the linear foot of installed line. Only the marked line will be measured for payment.~~
9. Temporary pavement markings at intersections will be measured as listed in the plans complete in place and accepted as Painted Pavement Marking (Description) or Removable Pavement Marking (Description)

Subsection 712.10 (pg. 746, 747), 12-15-21; **Basis of Payment; Revise Item List & Paragraphs 4, 5, 9, Remove Paragraph 8:**

<i>Item</i>	<i>Pay Unit</i>
Traffic Control	Lump Sum
Portable Barrier Rail	Linear Feet
Portable Impact Attenuator <u>Temporary Work Zone Crash Cushion</u>	Each
Signs	Square Feet
Vertical Panels	Square Feet
Flexible Drums	Each
Temporary Barricades (Type)	Linear Feet
Removable Pavement Marking (Description)	Linear Feet
Changeable Message Sign Unit	Each
Arrow Board (Type C)	Each
Barrier Rail Delineator	Each
Temporary Flexible Tubular Delineator	Each

Payment for ~~Portable Energy Absorbing Terminals~~ Temporary Work Zone Crash Cushion will be made at the contract price ~~per Portable Energy Absorbing terminal~~, complete in place, with total payment based on the maximum number ~~of portable energy absorbing terminals~~ in place at one time as specified in **712.09**.

Payment for Signs (Construction) ~~and Vertical Panels~~ is full compensation for providing sign panels with proper sheeting and legend, erecting on proper supports, furnishing all mounting hardware, covering when not in use, relocating, handling, and maintaining until Project completion. Vertical Panels will be paid as Signs (Construction).

~~The Department will pay for 10-foot lane line/center line and solid barrier line as Painted Pavement Marking (Line) in accordance with 716.08.~~

Payment for Removable Pavement Marking ~~items Line, 8-inch Barrier Line, Channelization Striping or Stop Line, is shall be~~ full compensation for the installation, maintenance, and removal of the marking line when it is no longer required.

Subsection 716.03.B (pg. 790), 12-15-21; **Application; Revise No. 3 & Add No. 4:**

3. **Temporary Pavement Marking (Line).** When thermoplastic is used on the final pavement surface, the Contractor may use reflectorized paint for the center, edge, lane and barrier lines installed meeting 716.07 and 910~~to permanent standards~~ at the end of each day's work and then install the permanent pavement marking after the paving operation is completed. Short, unmarked sections are not allowed. The Department will not directly measure and pay for temporary markings for the final surface, and will consider the costs thereof to be incidental to the item for the permanent thermoplastic pavement markings (line).
4. **Temporary Pavement Markings at Intersections.** When required, temporary pavement markings at intersections are to be installed with reflectorized paint meeting 716.07 and 910. The Department will measure and pay as noted in 712.09 and 712.10,

Subsection 716.07.A (pg. 793), 12-15-21; **Application; Revise 11th Paragraph:**

When reflectorized paint is required for temporary or final marking, install the paint meeting 910.02~~to permanent standards~~ at the end of each day's work. Do not leave any short, unmarked sections.

STATEOFTENNESSEE

(Rev. 12-15-21)

January 1, 2021

Supplemental Specifications – 900SS
of the
Standard Specifications for Road and Bridge Construction
January 1, 2021

Subsection 904.03 (pg. 931-934), 12-15-21; **Emulsified Asphalt**; Revise Table 904.03-1(c):

Table 904.03-1(c): Test Requirements for Emulsified Asphalt

Practices	AASHTO Test Method	CRS-2P	RS-2	RS-1	CRS-1
Saybolt-Furol Viscosity @ 77 °F, seconds	T59	n/a	n/a	20-100	<u>n/a</u>
Saybolt-Furol Viscosity @ 122 °F, seconds	T59	100-400	75-400	n/a	<u>20-100</u>
Storage Stability Test, 24- h, %	T59	1 Max	1 Max	1 Max	<u>1 Max</u>
5-day Settlement, %	T59	n/a	n/a	n/a	<u>n/a</u>
Particle Charge	T59	Positive	n/a	n/a	<u>Positive</u>
Sieve Test, %	T59	0.1 Max	0.1 Max	0.1 Max	<u>0.1 Max</u>
Residue by	T59	Evaporation	Distillation	Distillation	<u>Distillation</u>
Residue, %	T59	65 Min	63 Min	55 Min	<u>60 Min</u>
Demulsibility, %	T59	40 Min	60 Min	60 Min	<u>40 Min</u>
Distillate, %	T59	n/a	n/a	n/a	<u>n/a</u>
Oil Test, %	T59	n/a	n/a	n/a	<u>3.0 Max</u>
Stone Coating	T59	n/a	n/a	n/a	<u>n/a</u>
Float Test, seconds	T50	n/a	n/a	n/a	<u>n/a</u>
Penetration	T49	75-175	100-200	100-200	<u>100-250</u>
Elastic Recovery, % ⁽¹⁾	T301	50 Min	n/a	n/a	<u>n/a</u>
Ductility @ 77 °F, cm	T51	40 Min	40 Min	40 Min	<u>40 Min</u>
Ductility @ 40 °F, cm	T51	n/a	n/a	n/a	<u>n/a</u>
R&B Softening Point, °F	T53	125 Min	n/a	n/a	<u>n/a</u>
Original G*/sind @ 82 °C	T315	n/a	n/a	n/a	<u>n/a</u>

⁽¹⁾ Straight-sided mold, 20-cm elongation, 5min hold, 25 °C

Subsection 916.06 (pg. 988), 12-15-21; **Reflective Sheeting**; Revise Subsection:

Provide reflective sheeting from the Department's QPL conforming to AASHTO M 268 and the supplementary requirements for fungus resistance of AASHTO M 268. The sheeting material shall have a precoated adhesive backing or a heat and pressure activated adhesive backing protected by a removable liner.

For all signs with a SILVER-WHITE and ORANGE background when used on temporary barricades and channelizing drums, provide reflective sheeting ~~of that meets or exceeds AASHTO M 268, Type B. or better as specified by AASHTO M 268.~~

For all permanent panel signs with a SILVER-WHITE, YELLOW, RED, GREEN, BROWN, or BLUE background, provide reflective sheeting ~~of Encapsulated Lens or Microprismatic Lens material that meets or exceeding the minimum requirements for AASHTO M 268, Type- DB, or better as specified by AASHTO M 268.~~

For overhead permanent signs attached to sign structures which overhang travel lanes and are not illuminated with sign lighting, provide reflective sheeting that meets AASHTO M 268, Type D.

For all other sign types, provide reflective sheeting that meets or exceeds AASHTO M 268, Type B.

For FLOURESCENT ORANGE background, material provide reflective sheeting that shall meet or exceeds the requirements for AASHTO M 268, Type B, as specified by AASHTO M 268.

Subsection 916.07 (pg. 988,989), 12-15-21; **Legends, Borders, and Accessories**; Revise Subsection:

Provide letters, numerals, symbols, borders, and route markers conforming to the MUTCD.

A. Type "A" Class I (Demountable)

Provide silver-white letters, numerals, symbols, borders, and route markers of a pre-coated pressure sensitive or a tack-free heat-activated adhesive reflective sheeting permanently adhered to the sign panel. ~~The reflective sheeting shall meet the requirements of 916.06 (Type B or better as specified by AASHTO M 268).~~

For all permanent panel signs, provide reflective sheeting that meets AASHTO M 268, Type D.

Mechanically apply the reflective sheeting to the properly prepared sign panel with the equipment and in a manner prescribed by the sheeting manufacturer. Letters, numerals, symbols, borders, and route markers shall be 0.032 inch thick aluminum sheet of 3003 H14 Alloy or approved composite material. Properly degrease and etch aluminum, or treat with a light, tight, amorphous chromate type coating.

Supply each letter, numeral, symbol, and route marker with mounting holes, and secure to the sign surface with corrosion-resistant screws, bolts, or rivets.

B. Type "A" Class 2 Cut-Out (Direct Applied Reflective Sheeting Copy)

Provide silver-white cut-out letters, numerals, symbols, borders, and route markers of a pre-coated pressure sensitive or a tack-free heat-activated adhesive reflective sheeting. ~~The reflective sheeting shall meet the requirements of 916.06 (Type B or better as specified by AASHTO M 268).~~

For all permanent panel signs, provide reflective sheeting that meets AASHTO M 268, Type D.

For all other sign types, provide reflective sheeting that meets or exceeds AASHTO M 268, Type B.