



Stark Metropolitan Housing Authority

Insured: Linwood Acres
Property: 3331 14th St. SW
Canton, OH 44710

Estimator: Chuck Samsa
Company: Stark Metro Housing Authority

Claim Number:

Policy Number:

Type of Loss:

Date of Loss:
Date Inspected:

Date Received:
Date Entered: 3/25/2024 9:20 AM

Price List: OHCA8X_MAR24
Restoration/Service/Remodel
Estimate: LINWOODROOFSIDING

Contractor is responsible for any permits or inspections.
Contractor to verify all measurements.
Site to be free and clear of any debris upon completion of the job.
All Address numbers on front and back of unit to be removed and reattached after installation of new siding.
All satellite dishes on roofs or building to be removed and NOT reinstalled.



LINWOODROOFSIDING

Doors/Hardware

DESCRIPTION	QTY
1. R&R Steel door, 3' x 7'	216.00 EA
All exterior doors to be replaced. All doors should be 36" but contractor will have to verify. The shop has 4 doors and all other units have 2 doors except for the 4 1 bedroom duplexes which only have one. All doors to be steel door/steel frame/smooth panel. Doors to be equivalent to what is currently installed. Doors to have 2 3/4 backset.	
2. R&R Door lockset & deadbolt - exterior	216.00 EA
Lock set MUST be Falcon brand to accommodate our current "core system".	
3. R&R Screen door - metal - 36"	216.00 EA
Screen door handle and latch to be included.	
4. R&R Door closer - pneumatic	216.00 EA
5. Paint door trim & jamb - 2 coats (per side)	432.00 EA
6. Paint door slab only - 2 coats (per side)	432.00 EA

NOTES:

Roof/Siding 3337 14th St.

DESCRIPTION	QTY
7. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
8. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ
9. Ice & water barrier	372.00 SF
10. R&R Drip edge	130.00 LF
11. Continuous ridge vent - shingle-over style	31.00 LF
12. Remove Roof vent - turtle type - Plastic	7.00 EA
13. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
14. R&R Flashing - pipe jack	2.00 EA
15. R&R Siding - vinyl	1350.00 SF
16. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	



CONTINUED - Roof/Siding 3337 14th St.

DESCRIPTION	QTY
17. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
18. R&R Fascia - metal - 6"	130.00 LF
19. R&R Soffit - vinyl	130.00 LF
20. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
21. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
22. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	
23. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 3315 14th St.

DESCRIPTION	QTY
24. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
25. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ
26. Ice & water barrier	372.00 SF
27. R&R Drip edge	130.00 LF
28. Continuous ridge vent - shingle-over style	31.00 LF
29. Remove Roof vent - turtle type - Plastic	7.00 EA
30. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
31. R&R Flashing - pipe jack	2.00 EA
32. R&R Siding - vinyl	1350.00 SF



CONTINUED - Roof/Siding 3315 14th St.

DESCRIPTION	QTY
33. Sheathing - OSB - 1/2" Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	1350.00 SF
34. House wrap (air/moisture barrier) Tape all seams and overlapped areas to ensure a watertight seal.	1350.00 SF
35. R&R Fascia - metal - 6"	130.00 LF
36. R&R Soffit - vinyl	130.00 LF
37. Metal Z flashing / drip cap Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	18.00 LF
38. R&R vent cover Replace exhaust/dryer vents by front and rear doors.	4.00 EA
39. Electrician - per hour Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	1.00 HR
40. R&R Gutter / downspout - aluminum - up to 5" Replace all gutters and down spouts.	142.00 LF

NOTES:

Roof/Siding 3319 14th St.

DESCRIPTION	QTY
41. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
42. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ
43. Ice & water barrier	372.00 SF
44. R&R Drip edge	130.00 LF
45. Continuous ridge vent - shingle-over style	31.00 LF
46. Remove Roof vent - turtle type - Plastic	7.00 EA
47. R&R Underlayment - 7/16" OSB Replace bad roof decking as needed	0.00 SF



CONTINUED - Roof/Siding 3319 14th St.

DESCRIPTION	QTY
48. R&R Flashing - pipe jack	2.00 EA
49. R&R Siding - vinyl	1350.00 SF
50. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
51. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
52. R&R Fascia - metal - 6"	130.00 LF
53. R&R Soffit - vinyl	130.00 LF
54. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
55. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
56. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	
57. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	

NOTES:

Roof/Siding 3323 14th St.

DESCRIPTION	QTY
58. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
59. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ
60. Ice & water barrier	372.00 SF
61. R&R Drip edge	130.00 LF
62. Continuous ridge vent - shingle-over style	31.00 LF
63. Remove Roof vent - turtle type - Plastic	7.00 EA



CONTINUED - Roof/Siding 3323 14th St.

DESCRIPTION	QTY
64. R&R Underlayment - 7/16" OSB Replace bad roof decking as needed	0.00 SF
65. R&R Flashing - pipe jack	2.00 EA
66. R&R Siding - vinyl	1350.00 SF
67. Sheathing - OSB - 1/2" Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	1350.00 SF
68. House wrap (air/moisture barrier) Tape all seams and overlapped areas to ensure a watertight seal.	1350.00 SF
69. R&R Fascia - metal - 6"	130.00 LF
70. R&R Soffit - vinyl	130.00 LF
71. Metal Z flashing / drip cap Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	18.00 LF
72. R&R vent cover Replace exhaust/dryer vents by front and rear doors.	4.00 EA
73. Electrician - per hour Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	1.00 HR
74. R&R Gutter / downspout - aluminum - up to 5" Replace all gutters and down spouts.	142.00 LF

NOTES:

Roof/Siding 3335 14th St.

DESCRIPTION	QTY
75. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
76. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ
77. Ice & water barrier	372.00 SF
78. R&R Drip edge	130.00 LF



CONTINUED - Roof/Siding 3335 14th St.

DESCRIPTION	QTY
79. Continuous ridge vent - shingle-over style	31.00 LF
80. Remove Roof vent - turtle type - Plastic	7.00 EA
81. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
82. R&R Flashing - pipe jack	2.00 EA
83. R&R Siding - vinyl	1350.00 SF
84. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
85. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
86. R&R Fascia - metal - 6"	130.00 LF
87. R&R Soffit - vinyl	130.00 LF
88. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
89. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
90. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	
91. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	

NOTES:

Roof/Siding 3418 14th St.

DESCRIPTION	QTY
92. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
93. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ



CONTINUED - Roof/Siding 3418 14th St.

DESCRIPTION	QTY
94. Ice & water barrier	372.00 SF
95. R&R Drip edge	130.00 LF
96. Continuous ridge vent - shingle-over style	31.00 LF
97. Remove Roof vent - turtle type - Plastic	7.00 EA
98. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
99. R&R Flashing - pipe jack	2.00 EA
100. R&R Siding - vinyl	1350.00 SF
101. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
102. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
103. R&R Fascia - metal - 6"	130.00 LF
104. R&R Soffit - vinyl	130.00 LF
105. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
106. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
107. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	
108. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 1356 Linwood Ave.

DESCRIPTION	QTY
-------------	-----



CONTINUED - Roof/Siding 1356 Linwood Ave.

DESCRIPTION	QTY
109. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
110. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ
111. Ice & water barrier	372.00 SF
112. R&R Drip edge	130.00 LF
113. Continuous ridge vent - shingle-over style	31.00 LF
114. Remove Roof vent - turtle type - Plastic	7.00 EA
115. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
116. R&R Flashing - pipe jack	2.00 EA
117. R&R Siding - vinyl	1350.00 SF
118. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
119. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
120. R&R Fascia - metal - 6"	130.00 LF
121. R&R Soffit - vinyl	130.00 LF
122. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
123. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
124. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	
125. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 1354 Linwood Ave.



DESCRIPTION	QTY
126. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
127. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ
128. Ice & water barrier	372.00 SF
129. R&R Drip edge	130.00 LF
130. Continuous ridge vent - shingle-over style	31.00 LF
131. Remove Roof vent - turtle type - Plastic	7.00 EA
132. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
133. R&R Flashing - pipe jack	2.00 EA
134. R&R Siding - vinyl	1350.00 SF
135. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
136. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
137. R&R Fascia - metal - 6"	130.00 LF
138. R&R Soffit - vinyl	130.00 LF
139. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
140. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
141. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	
142. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 1350 Linwood Ave.

DESCRIPTION	QTY
143. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
144. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ
145. Ice & water barrier	372.00 SF
146. R&R Drip edge	130.00 LF



CONTINUED - Roof/Siding 1350 Linwood Ave.

DESCRIPTION	QTY
147. Continuous ridge vent - shingle-over style	31.00 LF
148. Remove Roof vent - turtle type - Plastic	7.00 EA
149. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
150. R&R Flashing - pipe jack	2.00 EA
151. R&R Siding - vinyl	1350.00 SF
152. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
153. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
154. R&R Fascia - metal - 6"	130.00 LF
155. R&R Soffit - vinyl	130.00 LF
156. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
157. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
158. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	
159. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 1360 Linwood Ave.

DESCRIPTION	QTY
160. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
161. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ



CONTINUED - Roof/Siding 1360 Linwood Ave.

DESCRIPTION	QTY
162. Ice & water barrier	372.00 SF
163. R&R Drip edge	130.00 LF
164. Continuous ridge vent - shingle-over style	31.00 LF
165. Remove Roof vent - turtle type - Plastic	7.00 EA
166. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
167. R&R Flashing - pipe jack	2.00 EA
168. R&R Siding - vinyl	1350.00 SF
169. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
170. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
171. R&R Fascia - metal - 6"	130.00 LF
172. R&R Soffit - vinyl	130.00 LF
173. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
174. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
175. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	
176. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 1366 Linwood Ave.

DESCRIPTION	QTY
-------------	-----



CONTINUED - Roof/Siding 1366 Linwood Ave.

DESCRIPTION	QTY
177. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
178. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ
179. Ice & water barrier	372.00 SF
180. R&R Drip edge	130.00 LF
181. Continuous ridge vent - shingle-over style	31.00 LF
182. Remove Roof vent - turtle type - Plastic	7.00 EA
183. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
184. R&R Flashing - pipe jack	2.00 EA
185. R&R Siding - vinyl	1350.00 SF
186. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
187. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
188. R&R Fascia - metal - 6"	130.00 LF
189. R&R Soffit - vinyl	130.00 LF
190. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
191. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
192. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	
193. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 1368 Linwood Ave.



DESCRIPTION	QTY
194. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
195. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ
196. Ice & water barrier	372.00 SF
197. R&R Drip edge	130.00 LF
198. Continuous ridge vent - shingle-over style	31.00 LF
199. Remove Roof vent - turtle type - Plastic	7.00 EA
200. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
201. R&R Flashing - pipe jack	2.00 EA
202. R&R Siding - vinyl	1350.00 SF
203. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
204. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
205. R&R Fascia - metal - 6"	130.00 LF
206. R&R Soffit - vinyl	130.00 LF
207. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
208. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
209. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	
210. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 1372 Linwood Ave.

DESCRIPTION	QTY
211. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
212. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ
213. Ice & water barrier	372.00 SF
214. R&R Drip edge	130.00 LF



CONTINUED - Roof/Siding 1372 Linwood Ave.

DESCRIPTION	QTY
215. Continuous ridge vent - shingle-over style	31.00 LF
216. Remove Roof vent - turtle type - Plastic	7.00 EA
217. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
218. R&R Flashing - pipe jack	2.00 EA
219. R&R Siding - vinyl	1350.00 SF
220. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
221. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
222. R&R Fascia - metal - 6"	130.00 LF
223. R&R Soffit - vinyl	130.00 LF
224. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
225. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
226. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	
227. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 1378 Linwood Ave.

DESCRIPTION	QTY
228. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
229. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ



CONTINUED - Roof/Siding 1378 Linwood Ave.

DESCRIPTION	QTY
230. Ice & water barrier	372.00 SF
231. R&R Drip edge	130.00 LF
232. Continuous ridge vent - shingle-over style	31.00 LF
233. Remove Roof vent - turtle type - Plastic	7.00 EA
234. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
235. R&R Flashing - pipe jack	2.00 EA
236. R&R Siding - vinyl	1350.00 SF
237. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
238. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
239. R&R Fascia - metal - 6"	130.00 LF
240. R&R Soffit - vinyl	130.00 LF
241. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
242. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
243. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	
244. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 1380 Linwood Ave.

DESCRIPTION	QTY
-------------	-----



CONTINUED - Roof/Siding 1380 Linwood Ave.

DESCRIPTION	QTY
245. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
246. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ
247. Ice & water barrier	372.00 SF
248. R&R Drip edge	130.00 LF
249. Continuous ridge vent - shingle-over style	31.00 LF
250. Remove Roof vent - turtle type - Plastic	7.00 EA
251. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
252. R&R Flashing - pipe jack	2.00 EA
253. R&R Siding - vinyl	1350.00 SF
254. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
255. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
256. R&R Fascia - metal - 6"	130.00 LF
257. R&R Soffit - vinyl	130.00 LF
258. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
259. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
260. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	
261. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 1384 Linwood Ave.



DESCRIPTION	QTY
262. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
263. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ
264. Ice & water barrier	372.00 SF
265. R&R Drip edge	130.00 LF
266. Continuous ridge vent - shingle-over style	31.00 LF
267. Remove Roof vent - turtle type - Plastic	7.00 EA
268. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
269. R&R Flashing - pipe jack	2.00 EA
270. R&R Siding - vinyl	1350.00 SF
271. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
272. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
273. R&R Fascia - metal - 6"	130.00 LF
274. R&R Soffit - vinyl	130.00 LF
275. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
276. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
277. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	
278. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 1388 Linwood Ave.

DESCRIPTION	QTY
279. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
280. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ
281. Ice & water barrier	372.00 SF
282. R&R Drip edge	130.00 LF



CONTINUED - Roof/Siding 1388 Linwood Ave.

DESCRIPTION	QTY
283. Continuous ridge vent - shingle-over style	31.00 LF
284. Remove Roof vent - turtle type - Plastic	7.00 EA
285. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
286. R&R Flashing - pipe jack	2.00 EA
287. R&R Siding - vinyl	1350.00 SF
288. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
289. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
290. R&R Fascia - metal - 6"	130.00 LF
291. R&R Soffit - vinyl	130.00 LF
292. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
293. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
294. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	
295. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 1394 Linwood Ave.

DESCRIPTION	QTY
296. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
297. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ



CONTINUED - Roof/Siding 1394 Linwood Ave.

DESCRIPTION	QTY
298. Ice & water barrier	372.00 SF
299. R&R Drip edge	130.00 LF
300. Continuous ridge vent - shingle-over style	31.00 LF
301. Remove Roof vent - turtle type - Plastic	7.00 EA
302. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
303. R&R Flashing - pipe jack	2.00 EA
304. R&R Siding - vinyl	1350.00 SF
305. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
306. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
307. R&R Fascia - metal - 6"	130.00 LF
308. R&R Soffit - vinyl	130.00 LF
309. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
310. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
311. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	
312. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 3312 Windsor Pl.

DESCRIPTION	QTY
-------------	-----



CONTINUED - Roof/Siding 3312 Windsor Pl.

DESCRIPTION	QTY
313. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
314. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ
315. Ice & water barrier	372.00 SF
316. R&R Drip edge	130.00 LF
317. Continuous ridge vent - shingle-over style	31.00 LF
318. Remove Roof vent - turtle type - Plastic	7.00 EA
319. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
320. R&R Flashing - pipe jack	2.00 EA
321. R&R Siding - vinyl	1350.00 SF
322. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
323. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
324. R&R Fascia - metal - 6"	130.00 LF
325. R&R Soffit - vinyl	130.00 LF
326. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
327. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
328. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	
329. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 3318 Windsor Pl.



DESCRIPTION	QTY
330. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
331. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ
332. Ice & water barrier	372.00 SF
333. R&R Drip edge	130.00 LF
334. Continuous ridge vent - shingle-over style	31.00 LF
335. Remove Roof vent - turtle type - Plastic	7.00 EA
336. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
337. R&R Flashing - pipe jack	2.00 EA
338. R&R Siding - vinyl	1350.00 SF
339. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
340. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
341. R&R Fascia - metal - 6"	130.00 LF
342. R&R Soffit - vinyl	130.00 LF
343. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
344. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
345. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	
346. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 3328 Windsor Pl.

DESCRIPTION	QTY
347. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
348. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ
349. Ice & water barrier	372.00 SF
350. R&R Drip edge	130.00 LF



CONTINUED - Roof/Siding 3328 Windsor Pl.

DESCRIPTION	QTY
351. Continuous ridge vent - shingle-over style	31.00 LF
352. Remove Roof vent - turtle type - Plastic	7.00 EA
353. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
354. R&R Flashing - pipe jack	2.00 EA
355. R&R Siding - vinyl	1350.00 SF
356. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
357. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
358. R&R Fascia - metal - 6"	130.00 LF
359. R&R Soffit - vinyl	130.00 LF
360. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
361. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
362. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	
363. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 3332 Windsor Pl.

DESCRIPTION	QTY
364. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
365. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ



CONTINUED - Roof/Siding 3332 Windsor Pl.

DESCRIPTION	QTY
366. Ice & water barrier	372.00 SF
367. R&R Drip edge	130.00 LF
368. Continuous ridge vent - shingle-over style	31.00 LF
369. Remove Roof vent - turtle type - Plastic	7.00 EA
370. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
371. R&R Flashing - pipe jack	2.00 EA
372. R&R Siding - vinyl	1350.00 SF
373. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
374. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
375. R&R Fascia - metal - 6"	130.00 LF
376. R&R Soffit - vinyl	130.00 LF
377. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
378. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
379. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	
380. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 3334 Windsor Pl.

DESCRIPTION	QTY
-------------	-----



CONTINUED - Roof/Siding 3334 Windsor Pl.

DESCRIPTION	QTY
381. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
382. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ
383. Ice & water barrier	372.00 SF
384. R&R Drip edge	130.00 LF
385. Continuous ridge vent - shingle-over style	31.00 LF
386. Remove Roof vent - turtle type - Plastic	7.00 EA
387. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
388. R&R Flashing - pipe jack	2.00 EA
389. R&R Siding - vinyl	1350.00 SF
390. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
391. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
392. R&R Fascia - metal - 6"	130.00 LF
393. R&R Soffit - vinyl	130.00 LF
394. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
395. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
396. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	
397. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 3340 Windsor Pl.



DESCRIPTION	QTY
398. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
399. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ
400. Ice & water barrier	372.00 SF
401. R&R Drip edge	130.00 LF
402. Continuous ridge vent - shingle-over style	31.00 LF
403. Remove Roof vent - turtle type - Plastic	7.00 EA
404. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
405. R&R Flashing - pipe jack	2.00 EA
406. R&R Siding - vinyl	1350.00 SF
407. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
408. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
409. R&R Fascia - metal - 6"	130.00 LF
410. R&R Soffit - vinyl	130.00 LF
411. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
412. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
413. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	
414. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 3342 Windsor Pl.

DESCRIPTION	QTY
415. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
416. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ
417. Ice & water barrier	372.00 SF
418. R&R Drip edge	130.00 LF



CONTINUED - Roof/Siding 3342 Windsor Pl.

DESCRIPTION	QTY
419. Continuous ridge vent - shingle-over style	31.00 LF
420. Remove Roof vent - turtle type - Plastic	7.00 EA
421. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
422. R&R Flashing - pipe jack	2.00 EA
423. R&R Siding - vinyl	1350.00 SF
424. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
425. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
426. R&R Fascia - metal - 6"	130.00 LF
427. R&R Soffit - vinyl	130.00 LF
428. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
429. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
430. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	
431. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 3346 Windsor Pl.

DESCRIPTION	QTY
432. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
433. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ



CONTINUED - Roof/Siding 3346 Windsor Pl.

DESCRIPTION	QTY
434. Ice & water barrier	372.00 SF
435. R&R Drip edge	130.00 LF
436. Continuous ridge vent - shingle-over style	31.00 LF
437. Remove Roof vent - turtle type - Plastic	7.00 EA
438. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
439. R&R Flashing - pipe jack	2.00 EA
440. R&R Siding - vinyl	1350.00 SF
441. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
442. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
443. R&R Fascia - metal - 6"	130.00 LF
444. R&R Soffit - vinyl	130.00 LF
445. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
446. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
447. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	
448. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 3348 Windsor Pl.

DESCRIPTION	QTY
-------------	-----

CONTINUED - Roof/Siding 3348 Windsor Pl.

DESCRIPTION	QTY
449. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
450. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ
451. Ice & water barrier	372.00 SF
452. R&R Drip edge	130.00 LF
453. Continuous ridge vent - shingle-over style	31.00 LF
454. Remove Roof vent - turtle type - Plastic	7.00 EA
455. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
456. R&R Flashing - pipe jack	2.00 EA
457. R&R Siding - vinyl	1350.00 SF
458. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
459. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
460. R&R Fascia - metal - 6"	130.00 LF
461. R&R Soffit - vinyl	130.00 LF
462. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
463. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
464. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	
465. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 3352 Windsor Pl.



DESCRIPTION	QTY
466. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	10.90 SQ
467. 3 tab - 25 yr. - composition shingle roofing - incl. felt	11.00 SQ
468. Ice & water barrier	372.00 SF
469. R&R Drip edge	130.00 LF
470. Continuous ridge vent - shingle-over style	31.00 LF
471. Remove Roof vent - turtle type - Plastic	7.00 EA
472. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
473. R&R Flashing - pipe jack	2.00 EA
474. R&R Siding - vinyl	1350.00 SF
475. Sheathing - OSB - 1/2"	1350.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
476. House wrap (air/moisture barrier)	1350.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
477. R&R Fascia - metal - 6"	130.00 LF
478. R&R Soffit - vinyl	130.00 LF
479. Metal Z flashing / drip cap	18.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
480. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
481. R&R Gutter / downspout - aluminum - up to 5"	142.00 LF
Replace all gutters and down spouts.	
482. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 3333 14th St.

DESCRIPTION	QTY
483. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	14.40 SQ
484. 3 tab - 25 yr. - composition shingle roofing - incl. felt	14.67 SQ
485. Ice & water barrier	152.00 SF
486. R&R Drip edge	152.00 LF



CONTINUED - Roof/Siding 3333 14th St.

DESCRIPTION	QTY
487. Continuous ridge vent - shingle-over style	37.00 LF
488. Remove Roof vent - turtle type - Plastic	10.00 EA
489. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
490. R&R Flashing - pipe jack	2.00 EA
491. R&R Siding - vinyl	264.00 SF
492. Sheathing - OSB - 1/2"	264.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
493. House wrap (air/moisture barrier)	264.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
494. R&R Fascia - metal - 6"	152.00 LF
495. R&R Soffit - vinyl	152.00 LF
496. R&R Gutter / downspout - aluminum - up to 5"	94.00 LF
Replace all gutters and down spouts.	
497. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 3310 14th St.

DESCRIPTION	QTY
498. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	14.40 SQ
499. 3 tab - 25 yr. - composition shingle roofing - incl. felt	14.67 SQ
500. Ice & water barrier	152.00 SF
501. R&R Drip edge	152.00 LF
502. Continuous ridge vent - shingle-over style	37.00 LF
503. Remove Roof vent - turtle type - Plastic	10.00 EA



CONTINUED - Roof/Siding 3310 14th St.

DESCRIPTION	QTY
504. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
505. R&R Flashing - pipe jack	2.00 EA
506. R&R Siding - vinyl	264.00 SF
507. Sheathing - OSB - 1/2"	264.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
508. House wrap (air/moisture barrier)	264.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
509. R&R Fascia - metal - 6"	152.00 LF
510. R&R Soffit - vinyl	152.00 LF
511. R&R Gutter / downspout - aluminum - up to 5"	94.00 LF
Replace all gutters and down spouts.	
512. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 3312 14th St.

DESCRIPTION	QTY
513. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	14.40 SQ
514. 3 tab - 25 yr. - composition shingle roofing - incl. felt	14.67 SQ
515. Ice & water barrier	152.00 SF
516. R&R Drip edge	152.00 LF
517. Continuous ridge vent - shingle-over style	37.00 LF
518. Remove Roof vent - turtle type - Plastic	10.00 EA
519. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	



CONTINUED - Roof/Siding 3312 14th St.

DESCRIPTION	QTY
520. R&R Flashing - pipe jack	2.00 EA
521. R&R Siding - vinyl	264.00 SF
522. Sheathing - OSB - 1/2"	264.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
523. House wrap (air/moisture barrier)	264.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
524. R&R Fascia - metal - 6"	152.00 LF
525. R&R Soffit - vinyl	152.00 LF
526. R&R Gutter / downspout - aluminum - up to 5"	94.00 LF
Replace all gutters and down spouts.	
527. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 3404 14th St.

DESCRIPTION	QTY
528. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	14.40 SQ
529. 3 tab - 25 yr. - composition shingle roofing - incl. felt	14.67 SQ
530. Ice & water barrier	152.00 SF
531. R&R Drip edge	152.00 LF
532. Continuous ridge vent - shingle-over style	37.00 LF
533. Remove Roof vent - turtle type - Plastic	10.00 EA
534. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
535. R&R Flashing - pipe jack	2.00 EA
536. R&R Siding - vinyl	264.00 SF



CONTINUED - Roof/Siding 3404 14th St.

DESCRIPTION	QTY
537. Sheathing - OSB - 1/2"	264.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
538. House wrap (air/moisture barrier)	264.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
539. R&R Fascia - metal - 6"	152.00 LF
540. R&R Soffit - vinyl	152.00 LF
541. R&R Gutter / downspout - aluminum - up to 5"	94.00 LF
Replace all gutters and down spouts.	
542. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 1392 Linwood Ave.

DESCRIPTION	QTY
543. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	19.80 SQ
544. 3 tab - 25 yr. - composition shingle roofing - incl. felt	20.00 SQ
545. Ice & water barrier	274.00 SF
546. R&R Drip edge	237.00 LF
547. Step flashing	37.00 LF
548. Continuous ridge vent - shingle-over style	64.00 LF
549. Remove Roof vent - turtle type - Plastic	10.00 EA
550. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
551. R&R Flashing - pipe jack	2.00 EA
552. R&R Siding - vinyl	1590.00 SF
553. Sheathing - OSB - 1/2"	1590.00 SF



CONTINUED - Roof/Siding 1392 Linwood Ave.

DESCRIPTION	QTY
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
554. House wrap (air/moisture barrier)	1590.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
555. R&R Fascia - metal - 6"	237.00 LF
556. R&R Soffit - vinyl	400.00 SF
557. Metal Z flashing / drip cap	30.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
558. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
559. R&R Gutter / downspout - aluminum - up to 5"	210.00 LF
Replace all gutters and down spouts.	
560. Range - electric - Remove & reset	1.00 EA
561. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 3316 Windsor Pl.

DESCRIPTION	QTY
562. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	19.80 SQ
563. 3 tab - 25 yr. - composition shingle roofing - incl. felt	20.00 SQ
564. Ice & water barrier	274.00 SF
565. R&R Drip edge	237.00 LF
566. Step flashing	37.00 LF
567. Continuous ridge vent - shingle-over style	64.00 LF
568. Remove Roof vent - turtle type - Plastic	10.00 EA
569. R&R Underlayment - 7/16" OSB	0.00 SF



CONTINUED - Roof/Siding 3316 Windsor Pl.

DESCRIPTION	QTY
Replace bad roof decking as needed	
570. R&R Flashing - pipe jack	2.00 EA
571. R&R Siding - vinyl	1590.00 SF
572. Sheathing - OSB - 1/2"	1590.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
573. House wrap (air/moisture barrier)	1590.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
574. R&R Fascia - metal - 6"	237.00 LF
575. R&R Soffit - vinyl	400.00 SF
576. Metal Z flashing / drip cap	30.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
577. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
578. R&R Gutter / downspout - aluminum - up to 5"	210.00 LF
Replace all gutters and down spouts.	
579. Range - electric - Remove & reset	1.00 EA
580. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 3330 Windsor Pl.

DESCRIPTION	QTY
581. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	16.00 SQ
582. 3 tab - 25 yr. - composition shingle roofing - incl. felt	16.00 SQ
583. Ice & water barrier	168.00 SF
584. R&R Drip edge	168.00 LF



CONTINUED - Roof/Siding 3330 Windsor Pl.

DESCRIPTION	QTY
585. Continuous ridge vent - shingle-over style	45.00 LF
586. Remove Roof vent - turtle type - Plastic	10.00 EA
587. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
588. R&R Flashing - pipe jack	2.00 EA
589. R&R Siding - vinyl	1642.00 SF
590. Sheathing - OSB - 1/2"	1642.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
591. House wrap (air/moisture barrier)	1642.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
592. R&R Fascia - metal - 6"	208.00 LF
593. R&R Soffit - vinyl	130.00 SF
594. Metal Z flashing / drip cap	100.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
Install flashing/drip edge anywhere where vinyl siding meets the offset brick. Tape to ensure no water penetration.	
595. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
596. R&R Gutter / downspout - aluminum - up to 5"	140.00 LF
Replace all gutters and down spouts.	
597. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 1370 Linwood Ave.

DESCRIPTION	QTY
598. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	16.00 SQ
599. 3 tab - 25 yr. - composition shingle roofing - incl. felt	16.00 SQ



CONTINUED - Roof/Siding 1370 Linwood Ave.

DESCRIPTION	QTY
600. Ice & water barrier	168.00 SF
601. R&R Drip edge	168.00 LF
602. Continuous ridge vent - shingle-over style	45.00 LF
603. Remove Roof vent - turtle type - Plastic	10.00 EA
604. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
605. R&R Flashing - pipe jack	2.00 EA
606. R&R Siding - vinyl	1642.00 SF
607. Sheathing - OSB - 1/2"	1642.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
608. House wrap (air/moisture barrier)	1642.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
609. R&R Fascia - metal - 6"	208.00 LF
610. R&R Soffit - vinyl	130.00 SF
611. Metal Z flashing / drip cap	100.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
Install flashing/drip edge anywhere where vinyl siding meets the offset brick. Tape to ensure no water penetration.	
612. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
613. R&R Gutter / downspout - aluminum - up to 5"	140.00 LF
Replace all gutters and down spouts.	
614. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 3317 14th St.

DESCRIPTION	QTY
-------------	-----

CONTINUED - Roof/Siding 3317 14th St.

DESCRIPTION	QTY
615. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	16.00 SQ
616. 3 tab - 25 yr. - composition shingle roofing - incl. felt	16.00 SQ
617. Ice & water barrier	168.00 SF
618. R&R Drip edge	168.00 LF
619. Continuous ridge vent - shingle-over style	45.00 LF
620. Remove Roof vent - turtle type - Plastic	10.00 EA
621. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
622. R&R Flashing - pipe jack	2.00 EA
623. R&R Siding - vinyl	1642.00 SF
624. Sheathing - OSB - 1/2"	1642.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
625. House wrap (air/moisture barrier)	1642.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
626. R&R Fascia - metal - 6"	208.00 LF
627. R&R Soffit - vinyl	130.00 SF
628. Metal Z flashing / drip cap	100.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
Install flashing/drip edge anywhere where vinyl siding meets the offset brick. Tape to ensure no water penetration.	
629. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
630. R&R Gutter / downspout - aluminum - up to 5"	140.00 LF
Replace all gutters and down spouts.	
631. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:



Roof/Siding 1398 Linwood Ave.

DESCRIPTION	QTY
632. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	16.00 SQ
633. 3 tab - 25 yr. - composition shingle roofing - incl. felt	16.00 SQ
634. Ice & water barrier	168.00 SF
635. R&R Drip edge	168.00 LF
636. Continuous ridge vent - shingle-over style	45.00 LF
637. Remove Roof vent - turtle type - Plastic	10.00 EA
638. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
639. R&R Flashing - pipe jack	2.00 EA
640. R&R Siding - vinyl	1642.00 SF
641. Sheathing - OSB - 1/2"	1642.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
642. House wrap (air/moisture barrier)	1642.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
643. R&R Fascia - metal - 6"	208.00 LF
644. R&R Soffit - vinyl	130.00 SF
645. Metal Z flashing / drip cap	100.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
Install flashing/drip edge anywhere where vinyl siding meets the offset brick. Tape to ensure no water penetration.	
646. R&R vent cover	4.00 EA
Replace exhaust/dryer vents by front and rear doors.	
647. R&R Gutter / downspout - aluminum - up to 5"	140.00 LF
Replace all gutters and down spouts.	
648. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 1352 Linwood Ave.

DESCRIPTION	QTY
--------------------	------------

CONTINUED - Roof/Siding 1352 Linwood Ave.

DESCRIPTION	QTY
649. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
650. 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
651. Ice & water barrier	148.00 SF
652. R&R Drip edge	148.00 LF
653. Continuous ridge vent - shingle-over style	41.00 LF
654. Remove Roof vent - turtle type - Plastic	8.00 EA
655. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
656. R&R Flashing - pipe jack	2.00 EA
657. R&R Siding - vinyl	1336.00 SF
658. Sheathing - OSB - 1/2"	1336.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
659. House wrap (air/moisture barrier)	1336.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
660. R&R Fascia - metal - 6"	168.00 LF
661. R&R Soffit - vinyl	280.00 SF
662. Metal Z flashing / drip cap	130.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
Install flashing/drip edge anywhere where vinyl siding meets the offset brick. Tape to ensure no water penetration.	
663. R&R vent cover	2.00 EA
Replace exhaust/dryer vents by front and rear doors.	
664. R&R Gutter / downspout - aluminum - up to 5"	110.00 LF
Replace all gutters and down spouts.	
665. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:



Roof/Siding 1358 Linwood Ave.

DESCRIPTION	QTY
666. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
667. 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
668. Ice & water barrier	148.00 SF
669. R&R Drip edge	148.00 LF
670. Continuous ridge vent - shingle-over style	41.00 LF
671. Remove Roof vent - turtle type - Plastic	8.00 EA
672. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
673. R&R Flashing - pipe jack	2.00 EA
674. R&R Siding - vinyl	1336.00 SF
675. Sheathing - OSB - 1/2"	1336.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
676. House wrap (air/moisture barrier)	1336.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
677. R&R Fascia - metal - 6"	168.00 LF
678. R&R Soffit - vinyl	280.00 SF
679. Metal Z flashing / drip cap	130.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
Install flashing/drip edge anywhere where vinyl siding meets the offset brick. Tape to ensure no water penetration.	
680. R&R vent cover	2.00 EA
Replace exhaust/dryer vents by front and rear doors.	
681. R&R Gutter / downspout - aluminum - up to 5"	110.00 LF
Replace all gutters and down spouts.	
682. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 1364 Linwood Ave.

DESCRIPTION	QTY
--------------------	------------

CONTINUED - Roof/Siding 1364 Linwood Ave.

DESCRIPTION	QTY
683. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
684. 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
685. Ice & water barrier	148.00 SF
686. R&R Drip edge	148.00 LF
687. Continuous ridge vent - shingle-over style	41.00 LF
688. Remove Roof vent - turtle type - Plastic	8.00 EA
689. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
690. R&R Flashing - pipe jack	2.00 EA
691. R&R Siding - vinyl	1336.00 SF
692. Sheathing - OSB - 1/2"	1336.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
693. House wrap (air/moisture barrier)	1336.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
694. R&R Fascia - metal - 6"	168.00 LF
695. R&R Soffit - vinyl	280.00 SF
696. Metal Z flashing / drip cap	130.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
Install flashing/drip edge anywhere where vinyl siding meets the offset brick. Tape to ensure no water penetration.	
697. R&R vent cover	2.00 EA
Replace exhaust/dryer vents by front and rear doors.	
698. R&R Gutter / downspout - aluminum - up to 5"	110.00 LF
Replace all gutters and down spouts.	
699. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:



Roof/Siding 1376 Linwood Ave.

DESCRIPTION	QTY
700. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
701. 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
702. Ice & water barrier	148.00 SF
703. R&R Drip edge	148.00 LF
704. Continuous ridge vent - shingle-over style	41.00 LF
705. Remove Roof vent - turtle type - Plastic	8.00 EA
706. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
707. R&R Flashing - pipe jack	2.00 EA
708. R&R Siding - vinyl	1336.00 SF
709. Sheathing - OSB - 1/2"	1336.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
710. House wrap (air/moisture barrier)	1336.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
711. R&R Fascia - metal - 6"	168.00 LF
712. R&R Soffit - vinyl	280.00 SF
713. Metal Z flashing / drip cap	130.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
Install flashing/drip edge anywhere where vinyl siding meets the offset brick. Tape to ensure no water penetration.	
714. R&R vent cover	2.00 EA
Replace exhaust/dryer vents by front and rear doors.	
715. R&R Gutter / downspout - aluminum - up to 5"	110.00 LF
Replace all gutters and down spouts.	
716. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 1382 Linwood Ave.

DESCRIPTION	QTY
--------------------	------------



CONTINUED - Roof/Siding 1382 Linwood Ave.

DESCRIPTION	QTY
717. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
718. 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
719. Ice & water barrier	148.00 SF
720. R&R Drip edge	148.00 LF
721. Continuous ridge vent - shingle-over style	41.00 LF
722. Remove Roof vent - turtle type - Plastic	8.00 EA
723. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
724. R&R Flashing - pipe jack	2.00 EA
725. R&R Siding - vinyl	1336.00 SF
726. Sheathing - OSB - 1/2"	1336.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
727. House wrap (air/moisture barrier)	1336.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
728. R&R Fascia - metal - 6"	168.00 LF
729. R&R Soffit - vinyl	280.00 SF
730. Metal Z flashing / drip cap	130.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
Install flashing/drip edge anywhere where vinyl siding meets the offset brick. Tape to ensure no water penetration.	
731. R&R vent cover	2.00 EA
Replace exhaust/dryer vents by front and rear doors.	
732. R&R Gutter / downspout - aluminum - up to 5"	110.00 LF
Replace all gutters and down spouts.	
733. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:



Roof/Siding 1390 Linwood Ave.

DESCRIPTION	QTY
734. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
735. 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
736. Ice & water barrier	148.00 SF
737. R&R Drip edge	148.00 LF
738. Continuous ridge vent - shingle-over style	41.00 LF
739. Remove Roof vent - turtle type - Plastic	8.00 EA
740. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
741. R&R Flashing - pipe jack	2.00 EA
742. R&R Siding - vinyl	1336.00 SF
743. Sheathing - OSB - 1/2"	1336.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
744. House wrap (air/moisture barrier)	1336.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
745. R&R Fascia - metal - 6"	168.00 LF
746. R&R Soffit - vinyl	280.00 SF
747. Metal Z flashing / drip cap	130.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
Install flashing/drip edge anywhere where vinyl siding meets the offset brick. Tape to ensure no water penetration.	
748. R&R vent cover	2.00 EA
Replace exhaust/dryer vents by front and rear doors.	
749. R&R Gutter / downspout - aluminum - up to 5"	110.00 LF
Replace all gutters and down spouts.	
750. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 1396 Linwood Ave.

DESCRIPTION	QTY
-------------	-----

CONTINUED - Roof/Siding 1396 Linwood Ave.

DESCRIPTION	QTY
751. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
752. 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
753. Ice & water barrier	148.00 SF
754. R&R Drip edge	148.00 LF
755. Continuous ridge vent - shingle-over style	41.00 LF
756. Remove Roof vent - turtle type - Plastic	8.00 EA
757. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
758. R&R Flashing - pipe jack	2.00 EA
759. R&R Siding - vinyl	1336.00 SF
760. Sheathing - OSB - 1/2"	1336.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
761. House wrap (air/moisture barrier)	1336.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
762. R&R Fascia - metal - 6"	168.00 LF
763. R&R Soffit - vinyl	280.00 SF
764. Metal Z flashing / drip cap	130.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
Install flashing/drip edge anywhere where vinyl siding meets the offset brick. Tape to ensure no water penetration.	
765. R&R vent cover	2.00 EA
Replace exhaust/dryer vents by front and rear doors.	
766. R&R Gutter / downspout - aluminum - up to 5"	110.00 LF
Replace all gutters and down spouts.	
767. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:



Roof/Siding 3314 Windsor Pl.

DESCRIPTION	QTY
768. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
769. 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
770. Ice & water barrier	148.00 SF
771. R&R Drip edge	148.00 LF
772. Continuous ridge vent - shingle-over style	41.00 LF
773. Remove Roof vent - turtle type - Plastic	8.00 EA
774. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
775. R&R Flashing - pipe jack	2.00 EA
776. R&R Siding - vinyl	1336.00 SF
777. Sheathing - OSB - 1/2"	1336.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
778. House wrap (air/moisture barrier)	1336.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
779. R&R Fascia - metal - 6"	168.00 LF
780. R&R Soffit - vinyl	280.00 SF
781. Metal Z flashing / drip cap	130.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
Install flashing/drip edge anywhere where vinyl siding meets the offset brick. Tape to ensure no water penetration.	
782. R&R vent cover	2.00 EA
Replace exhaust/dryer vents by front and rear doors.	
783. R&R Gutter / downspout - aluminum - up to 5"	110.00 LF
Replace all gutters and down spouts.	
784. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 3320 Windsor Pl.

DESCRIPTION	QTY
--------------------	------------

CONTINUED - Roof/Siding 3320 Windsor Pl.

DESCRIPTION	QTY
785. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
786. 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
787. Ice & water barrier	148.00 SF
788. R&R Drip edge	148.00 LF
789. Continuous ridge vent - shingle-over style	41.00 LF
790. Remove Roof vent - turtle type - Plastic	8.00 EA
791. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
792. R&R Flashing - pipe jack	2.00 EA
793. R&R Siding - vinyl	1336.00 SF
794. Sheathing - OSB - 1/2"	1336.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
795. House wrap (air/moisture barrier)	1336.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
796. R&R Fascia - metal - 6"	168.00 LF
797. R&R Soffit - vinyl	280.00 SF
798. Metal Z flashing / drip cap	130.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
Install flashing/drip edge anywhere where vinyl siding meets the offset brick. Tape to ensure no water penetration.	
799. R&R vent cover	2.00 EA
Replace exhaust/dryer vents by front and rear doors.	
800. R&R Gutter / downspout - aluminum - up to 5"	110.00 LF
Replace all gutters and down spouts.	
801. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:



Roof/Siding 3326 Windsor Pl.

DESCRIPTION	QTY
802. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
803. 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
804. Ice & water barrier	148.00 SF
805. R&R Drip edge	148.00 LF
806. Continuous ridge vent - shingle-over style	41.00 LF
807. Remove Roof vent - turtle type - Plastic	8.00 EA
808. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
809. R&R Flashing - pipe jack	2.00 EA
810. R&R Siding - vinyl	1336.00 SF
811. Sheathing - OSB - 1/2"	1336.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
812. House wrap (air/moisture barrier)	1336.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
813. R&R Fascia - metal - 6"	168.00 LF
814. R&R Soffit - vinyl	280.00 SF
815. Metal Z flashing / drip cap	130.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
Install flashing/drip edge anywhere where vinyl siding meets the offset brick. Tape to ensure no water penetration.	
816. R&R vent cover	2.00 EA
Replace exhaust/dryer vents by front and rear doors.	
817. R&R Gutter / downspout - aluminum - up to 5"	110.00 LF
Replace all gutters and down spouts.	
818. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 3344 Windsor Pl.

DESCRIPTION	QTY
-------------	-----

CONTINUED - Roof/Siding 3344 Windsor Pl.

DESCRIPTION	QTY
819. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
820. 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
821. Ice & water barrier	148.00 SF
822. R&R Drip edge	148.00 LF
823. Continuous ridge vent - shingle-over style	41.00 LF
824. Remove Roof vent - turtle type - Plastic	8.00 EA
825. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
826. R&R Flashing - pipe jack	2.00 EA
827. R&R Siding - vinyl	1336.00 SF
828. Sheathing - OSB - 1/2"	1336.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
829. House wrap (air/moisture barrier)	1336.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
830. R&R Fascia - metal - 6"	168.00 LF
831. R&R Soffit - vinyl	280.00 SF
832. Metal Z flashing / drip cap	130.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
Install flashing/drip edge anywhere where vinyl siding meets the offset brick. Tape to ensure no water penetration.	
833. R&R vent cover	2.00 EA
Replace exhaust/dryer vents by front and rear doors.	
834. R&R Gutter / downspout - aluminum - up to 5"	110.00 LF
Replace all gutters and down spouts.	
835. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:



Roof/Siding 3350 Windsor Pl.

DESCRIPTION	QTY
836. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
837. 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
838. Ice & water barrier	148.00 SF
839. R&R Drip edge	148.00 LF
840. Continuous ridge vent - shingle-over style	41.00 LF
841. Remove Roof vent - turtle type - Plastic	8.00 EA
842. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
843. R&R Flashing - pipe jack	2.00 EA
844. R&R Siding - vinyl	1336.00 SF
845. Sheathing - OSB - 1/2"	1336.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
846. House wrap (air/moisture barrier)	1336.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
847. R&R Fascia - metal - 6"	168.00 LF
848. R&R Soffit - vinyl	280.00 SF
849. Metal Z flashing / drip cap	130.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
Install flashing/drip edge anywhere where vinyl siding meets the offset brick. Tape to ensure no water penetration.	
850. R&R vent cover	2.00 EA
Replace exhaust/dryer vents by front and rear doors.	
851. R&R Gutter / downspout - aluminum - up to 5"	110.00 LF
Replace all gutters and down spouts.	
852. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 3311 14th St.

DESCRIPTION	QTY
-------------	-----

CONTINUED - Roof/Siding 3311 14th St.

DESCRIPTION	QTY
853. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
854. 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
855. Ice & water barrier	148.00 SF
856. R&R Drip edge	148.00 LF
857. Continuous ridge vent - shingle-over style	41.00 LF
858. Remove Roof vent - turtle type - Plastic	8.00 EA
859. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
860. R&R Flashing - pipe jack	2.00 EA
861. R&R Siding - vinyl	1336.00 SF
862. Sheathing - OSB - 1/2"	1336.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
863. House wrap (air/moisture barrier)	1336.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
864. R&R Fascia - metal - 6"	168.00 LF
865. R&R Soffit - vinyl	280.00 SF
866. Metal Z flashing / drip cap	130.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
Install flashing/drip edge anywhere where vinyl siding meets the offset brick. Tape to ensure no water penetration.	
867. R&R vent cover	2.00 EA
Replace exhaust/dryer vents by front and rear doors.	
868. R&R Gutter / downspout - aluminum - up to 5"	110.00 LF
Replace all gutters and down spouts.	
869. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:



Roof/Siding 3313 14th St.

DESCRIPTION	QTY
870. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
871. 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
872. Ice & water barrier	148.00 SF
873. R&R Drip edge	148.00 LF
874. Continuous ridge vent - shingle-over style	41.00 LF
875. Remove Roof vent - turtle type - Plastic	8.00 EA
876. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
877. R&R Flashing - pipe jack	2.00 EA
878. R&R Siding - vinyl	1336.00 SF
879. Sheathing - OSB - 1/2"	1336.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
880. House wrap (air/moisture barrier)	1336.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
881. R&R Fascia - metal - 6"	168.00 LF
882. R&R Soffit - vinyl	280.00 SF
883. Metal Z flashing / drip cap	130.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
Install flashing/drip edge anywhere where vinyl siding meets the offset brick. Tape to ensure no water penetration.	
884. R&R vent cover	2.00 EA
Replace exhaust/dryer vents by front and rear doors.	
885. R&R Gutter / downspout - aluminum - up to 5"	110.00 LF
Replace all gutters and down spouts.	
886. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 3321 14th St.

DESCRIPTION	QTY
--------------------	------------



CONTINUED - Roof/Siding 3321 14th St.

DESCRIPTION	QTY
887. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
888. 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
889. Ice & water barrier	148.00 SF
890. R&R Drip edge	148.00 LF
891. Continuous ridge vent - shingle-over style	41.00 LF
892. Remove Roof vent - turtle type - Plastic	8.00 EA
893. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
894. R&R Flashing - pipe jack	2.00 EA
895. R&R Siding - vinyl	1336.00 SF
896. Sheathing - OSB - 1/2"	1336.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
897. House wrap (air/moisture barrier)	1336.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
898. R&R Fascia - metal - 6"	168.00 LF
899. R&R Soffit - vinyl	280.00 SF
900. Metal Z flashing / drip cap	130.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
Install flashing/drip edge anywhere where vinyl siding meets the offset brick. Tape to ensure no water penetration.	
901. R&R vent cover	2.00 EA
Replace exhaust/dryer vents by front and rear doors.	
902. R&R Gutter / downspout - aluminum - up to 5"	110.00 LF
Replace all gutters and down spouts.	
903. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:



Roof/Siding 3339 14th St.

DESCRIPTION	QTY
904. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
905. 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
906. Ice & water barrier	148.00 SF
907. R&R Drip edge	148.00 LF
908. Continuous ridge vent - shingle-over style	41.00 LF
909. Remove Roof vent - turtle type - Plastic	8.00 EA
910. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
911. R&R Flashing - pipe jack	2.00 EA
912. R&R Siding - vinyl	1336.00 SF
913. Sheathing - OSB - 1/2"	1336.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
914. House wrap (air/moisture barrier)	1336.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
915. R&R Fascia - metal - 6"	168.00 LF
916. R&R Soffit - vinyl	280.00 SF
917. Metal Z flashing / drip cap	130.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
Install flashing/drip edge anywhere where vinyl siding meets the offset brick. Tape to ensure no water penetration.	
918. R&R vent cover	2.00 EA
Replace exhaust/dryer vents by front and rear doors.	
919. R&R Gutter / downspout - aluminum - up to 5"	110.00 LF
Replace all gutters and down spouts.	
920. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 3416 14th St.

DESCRIPTION	QTY
--------------------	------------



CONTINUED - Roof/Siding 3416 14th St.

DESCRIPTION	QTY
921. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
922. 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
923. Ice & water barrier	148.00 SF
924. R&R Drip edge	148.00 LF
925. Continuous ridge vent - shingle-over style	41.00 LF
926. Remove Roof vent - turtle type - Plastic	8.00 EA
927. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
928. R&R Flashing - pipe jack	2.00 EA
929. R&R Siding - vinyl	1336.00 SF
930. Sheathing - OSB - 1/2"	1336.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
931. House wrap (air/moisture barrier)	1336.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
932. R&R Fascia - metal - 6"	168.00 LF
933. R&R Soffit - vinyl	280.00 SF
934. Metal Z flashing / drip cap	130.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
Install flashing/drip edge anywhere where vinyl siding meets the offset brick. Tape to ensure no water penetration.	
935. R&R vent cover	2.00 EA
Replace exhaust/dryer vents by front and rear doors.	
936. R&R Gutter / downspout - aluminum - up to 5"	110.00 LF
Replace all gutters and down spouts.	
937. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:



Roof/Siding 3420 14th St.

DESCRIPTION	QTY
938. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
939. 3 tab - 25 yr. - composition shingle roofing - incl. felt	13.00 SQ
940. Ice & water barrier	148.00 SF
941. R&R Drip edge	148.00 LF
942. Continuous ridge vent - shingle-over style	41.00 LF
943. Remove Roof vent - turtle type - Plastic	8.00 EA
944. R&R Underlayment - 7/16" OSB	0.00 SF
Replace bad roof decking as needed	
945. R&R Flashing - pipe jack	2.00 EA
946. R&R Siding - vinyl	1336.00 SF
947. Sheathing - OSB - 1/2"	1336.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
948. House wrap (air/moisture barrier)	1336.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
949. R&R Fascia - metal - 6"	168.00 LF
950. R&R Soffit - vinyl	280.00 SF
951. Metal Z flashing / drip cap	130.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
Install flashing/drip edge anywhere where vinyl siding meets the offset brick. Tape to ensure no water penetration.	
952. R&R vent cover	2.00 EA
Replace exhaust/dryer vents by front and rear doors.	
953. R&R Gutter / downspout - aluminum - up to 5"	110.00 LF
Replace all gutters and down spouts.	
954. Electrician - per hour	1.00 HR
Detach and reset the electrical line/clips from the weather head to the meter in order to install the siding.	

NOTES:

Roof/Siding 3331 14th St. - Shop

DESCRIPTION	QTY
--------------------	------------

CONTINUED - Roof/Siding 3331 14th St. - Shop

DESCRIPTION	QTY
955. Remove 3 tab - 25 yr. - composition shingle roofing - incl. felt	54.30 SQ
956. 3 tab - 25 yr. - composition shingle roofing - incl. felt	54.33 SQ
957. Ice & water barrier	482.00 SF
958. R&R Drip edge	329.00 LF
959. Continuous ridge vent - shingle-over style	162.00 LF
960. Remove Roof vent - turtle type - Plastic	8.00 EA
961. R&R Flashing - pipe jack	3.00 EA
962. R&R Siding - vinyl	480.00 SF
963. Sheathing - OSB - 1/2"	480.00 SF
Install OSB sheathing over existing Celotex on the entirety of areas to be sided.	
964. House wrap (air/moisture barrier)	480.00 SF
Tape all seams and overlapped areas to ensure a watertight seal.	
965. R&R Fascia - metal - 6"	340.00 LF
966. Metal Z flashing / drip cap	24.00 LF
Install drip cap over the windows in the areas that will be sided. Tape the top to ensure no water penetration behind the drip cap.	
967. R&R Gutter / downspout - aluminum - up to 5"	370.00 LF
Replace all gutters and down spouts.	
968. Aluminum break work	300.00 LF
Exposed wood beneath fascia area to be wrapped in aluminum.	
969. R&R Light/outlet J-block - vinyl	2.00 EA
970. Light fixture - Detach & reset	2.00 EA

NOTES:



1 1-20240321_154211

Date Taken: 3/21/2024



2

2-20240321_154138

Date Taken: 3/21/2024



3

3-20240321_154112

Date Taken: 3/21/2024



4

4-20240321_154053

Date Taken: 3/21/2024



5

5-20240321_154033

Date Taken: 3/21/2024



6

6-20240321_154029

Date Taken: 3/21/2024



7

7-20240321_154020

Date Taken: 3/21/2024