| | | | | |
|---|---|---|---|---|
| 3 | 615 ARNO N.E. | 1/6 | 11/13/80 | 1 BEDROOM DUPLEX |
| CLASS OF WORK | ADDRESS | NUMBER OF CARDS | DATE | DESCRIPTION |




5/20/76

5/28/76

CITY OF ALBUQUERQUE

This microimage of this document is certified to be a complete and accurate copy of the original document as it appears in the files of the BUILDING AND INSPECTION DIVISION

City Clerk/Recorder

CITY OF ALBUQUERQUE

This microimage is certified to be a complete and accurate copy of the original document as it appears in the files of the BUILDING INSPECTION DIVISION, and was microfilmed in the regular course of business. The photographic processes used meet the Basic Microfilm Standards of the National Micrographics Association (MS115-1977).

City Clerk/Recorder

CITY OF ALBUQUERQUE

THIS MICROIMAGE IS THE BEST POSSIBLE REPRODUCTION DUE TO THE POOR QUALITY OF THE ORIGINAL DOCUMENT

CITY CLERK/RECORDER

ADDITIONS & ALTERATIONS TO THE PAN AMERICAN BUILDING - EAST

2340 MENAUL NE ALBUQUERQUE, NEW MEXICO

2nd FLOOR - OPPORTUNITY PARTITION LOCATIONS

LABOR & INDUSTRIAL COMMISSION

CONSULTANT

RUPLEY & ASSOCIATES
ARCHITECT · PLANNER · LANDSCAPE ARCHITECT
(505) 266 2777
305 SAN PEDRO NE
ALBUQUERQUE, NEW MEXICO 87108

STATE OF NEW MEXICO
JOHN D. RUPLEY
NO. 1981
REGISTERED ARCHITECT

COMMISSION NUMBER
7605

SHEET NUMBER
7
OF 8

CITY OF ALBUQUERQUE

| | | | | |
|---|---|---|---|---|
| 3 | 615 ARNO N.E. | 2/6 | 11/13/80 | 1 BEDROOM DUPLEX |
| CLASS OF WORK | ADDRESS | NUMBER OF CARDS | DATE | DESCRIPTION |




UNIT 'A' 1/4"=1'-0"




UNIT 'B' 1/4"=1'-0"

**Provide Ground Fault Protection on all Bathroom and Exterior Electrical Outlets**

EXHAUST FANS AND/OR VENTS TO BE CONNECTED DIRECTLY TO THE OUTSIDE



CITY OF ALBUQUERQUE
The microimage of this document is certified to be an accurate copy of the original document as it appears in the files of the BUILDING AND INSPECTION DIVISION
Mary Lou Cooper
Mary Lou Cooper, City Clerk/Recorder

CITY OF ALBUQUERQUE
This microimage is certified to be a complete and accurate copy of the original document as it appears in the files of the BUILDING INSPECTION DIVISION, and was microfilmed in the regular course of business. The photographic processes used meet the Eastman Standards of the National Micrographics Association (MS116-1977).
Mary Lou Cooper
City Clerk/Recorder

CITY OF ALBUQUERQUE
THIS MICROIMAGE IS THE BEST POSSIBLE REPRODUCTION DUE TO THE POOR QUALITY OF THE ORIGINAL DOCUMENT
Mary Lou Cooper
MARY LOU COOPER
CITY CLERK/RECORDER

STATE OF NEW MEXICO
DONALD S. FOWLER
2332
REGISTERED
PROFESSIONAL ENGINEER

FIXTURE SCHEDULE

| MARK | DESCRIPTION | LAMPS | REMARKS |
|---|---|---|---|
| A | LIGHTCRAFT 224-30-76 | 2/60WINC | CEILING SURFACE |
| B | LIGHTCRAFT 258-70-76 | 2/60WINC | WALL SURFACE, CTR ABOVE OR BESIDE MIRROR, OR 7' UP. |
| C | STERLING P610/AH610 | 1/60WINC | CEILING RECESSED. |
| D | LIGHTCRAFT 136-41-76 | 1/100WINC | CEILING PENDANT |
| ~~EC~~ N/C | ~~PRESCOLITE 73132~~ | ~~2/26P5~~ | ~~CEILING SURFACE~~ |
| ~~EW~~ N/C | ~~PRESCOLITE 73232~~ | ~~2/26P5~~ | ~~WALL SURFACE~~ |
| F | STERLING FP-248 | 2/40WRS/WW | CEILING SURFACE |
| G | STERLING 4340LP | 3/60WINC | CEILING SURFACE |
| H | STERLING P211/ZH211 | 1/100WINC | CEILING RECESSED |
| K | PORCELAIN LAMPHOLDER | 1/100WINC | SURFACE. PC = PULLCHAIN. |
| L | LIGHTCRAFT 606-20-43 | 1/60WINC | WALL SURF-UP 7' |
| M | MARCO NMP48L | 1/50WMV/DX | CEILING SURFACE. |
| ~~N~~ | ~~GUTH F61-X414F-1AIM1~~ | ~~1/40WRS/WW~~ | ~~CEILING RECESSED~~ |
| P N.I.C. | 2 LAMP X 4' HPF STRIP | 2/40WRS/WW | CEILING SURFACE |
| Q | PRESCOLITE 1224-362 | 1/100WINC | CEILING RECESSED |
| R | PRESCOLITE 1225-462 | 1/140WINC | CEILING RECESSED |
| ~~T~~ | ~~PRESCOLITE 90H4W-71~~ | ~~1/100WMV~~ | ~~CEILING RECESSED~~ |
| U | MCGRAW-EDISON CH14031-120WK | 1/100WMV | WALL SURFACE |
| V | MCGRAW-EDISON CH14031-120BK ON POLE #5002 | 1/100WMV | POLE MOUNTED AREA LIGHT |
| W | STERLING SL-60 | 1/25WINC | NIGHTLIGHT- 18" UP TO CENTER |

PLAN NOTES

1. 3 POLE TOGGLE SWITCH, SQUARE "D" #2510-K02, WITH WEATHER PROOF COVER PLATE, FOR COOLER DISCONNECT.
2. CONNECT 2-SPEED FAN AND PUMP. PROVIDE FUSETRONS FOR RUNNING PROTECTION. SEE UTILITIES SITE PLAN FOR LOCATION.
3. CONNECT HEATER AND CONTROLS.
4. INSTALL COOLER CONTROL SWITCH. FAN-ON-OFF, FAN-HI-LO, PUMP-ON-OFF TYPE.
5. COORDINATE RECESSED FIXTURE WITH DUCT WORK TO AVOID CONFLICT.
6. CONNECT RANGE HOOD.
7. 3 #6 CONDUCTORS.
8. 
9. 
10. INSTALL EMERG. CALL BELL APPROX. 6" BELOW CLG.
11. INSTALL EMERG. CALL SWITCH APPROX. 54" UP. SWITCH WITH EYELET AND 32" INCH PULL CORD.
12. 4" SQ. BOX, COVER & BLANK PLATE FOR FUTURE TV. STUB OUT & CAP 3/4" PVC 12" U.G., & 3/4" PVC 4" ABOVE ROOF.

GENERAL REQUIREMENTS - SEE SPECIFICATIONS FOR DETAILS

1. WIRING TYPES: APARTMENTS - NM CABLE.
   EXTERIOR LIGHTING - DIRECT BURIAL CABLE.
2. WIRING DEVICES TYPE: APARTMENTS - INTERMEDIATE GR. IVORY COLOR.
3. DEVICE PLATES: SMOOTH WHITE IVORY PLASTIC, 0.10" INCH THICK.
4. SAFETY SWITCHES & FUSES - AS SHOWN
6. PANELS - AS SHOWN; G.E., SQUARE D, ITE, FEDERAL PAC.
7. SPARES - THE 10% FIGURE SPECIFIED APPLIES TO 100W INCANDESCENTS.
8. RECEPTACLES IN ELDERLY UNITS TO BE 24" ABOVE FLOOR, EXCEPT AT COUNTERS. RECEPTACLES 8" ABOVE COUNTERTOPS
9. LOCATE SMOKE DETECTOR APPROXIMATELY WHERE SHOWN - ADJUST ACTUAL LOCATION TO BE OUT OF PATH OF AIRFLOW FROM REGISTERS.

MAY 28 1976
BUILDING SECTION

REVISED DATE: 4/12/76
JOB NO. 74-05
DATE: 6-26-74
PARKER, BOLE & ASSOCIATES
LOOKOUT
POWER & LIGHTING PLANS, RISERS
TURKEY HOUSING
ROOF

CITY OF ALBUQUERQUE

| | | | | |
|---|---|---|---|---|
| 3 | 615 ARNO N.E. | 3/6 | 11/13/80 | 1 BEDROOM DUPLEX |
| CLASS OF WORK | ADDRESS | NUMBER OF CARDS | DATE | DESCRIPTION |




FOUNDATION PLAN GROUP TYPE I (AA) 1/8"=1'-0"




NOTE:
SEE SITE PLAN FOR FLOOR SLAB & SIDEWALK ELEVATIONS & FOR ENTRY SLAB & SIDEWALK SLOPES — SLOPE PATIO SLABS 1" AWAY FROM BLDG.

NOTE:
SEE SITE PLAN FOR SPECIFIC ENTRY SLAB LOCATIONS

FOUNDATION PLAN GROUP TYPE II (BB) 1/8"=1'-0"




ROOF FRAMING PLAN GROUP TYPE I (AA) 1/8"=1'-0"




ROOF FRAMING PLAN GROUP TYPE II (BB) 1/8"=1'-0"

## GENERAL FRAMING NOTES

1. PROVIDE: 1/2" x 4' x 8' PLYWOOD SHEETS FOR CORNER BRACING OR EQUAL AS REQUIRED BY UNIFORM BUILDING CODE OR HUD.
2. LINTEL SCHEDULE: (LOAD BEARING WALLS)
   2 - 2x8 OPENINGS TO 4'
   2 - 2x10 OPENINGS 5' TO 8'
   2 - 2x12 OPENINGS 8' TO 12'

   OTHER OPENINGS NOTED ON PLAN. THESE LINTELS ARE FOR OPENINGS IN BEARING WALLS & WALLS PERPENDICULAR TO JOISTS.
3. FIB. = FLUSH BEAM HANG JOISTS WITH STEEL JOIST HANGERS
4. WOOD STRESS VALUES:
   JOISTS: 1300
   BEAMS: 1500
5. ROOF VENTS: SEE DETAIL RV SHEET 4
   2 VENTS PER UNIT

CITY OF ALBUQUERQUE
This microimage is certified to be a complete and accurate copy of the original document as it exists in the files of the BUILDING INSPECTION DIVISION, and was microfilmed in the regular course of business. The photographic process used meets the Basic Microfilming Standards of the National Micrographics Association (MS110-1977).
City Clerk/Recorder

CITY OF ALBUQUERQUE
THIS MICROIMAGE IS THE BEST POSSIBLE REPRODUCTION DUE TO THE POOR QUALITY OF THE ORIGINAL DOCUMENT
MARY ANN DOUBER
CITY CLERK/RECORDER

MAY 25 1978
BUILDING INSPECTION

CITY OF ALBUQUERQUE

| | | | | |
|---|---|---|---|---|
| 3 | 615 ARNO N.E. | 4/6 | 11/13/80 | 1 BEDROOM DUPLEX |
| CLASS OF WORK | ADDRESS | NUMBER OF CARDS | DATE | DESCRIPTION |

## SCHEDULE OF GAUGES FOR RECTANGULAR DUCT CONSTRUCTION - ALL SITES

| Steel U.S. Std. Gauge | Maximum Side, Inches | Type of Transverse Joint Connections | Bracing |
|---|---|---|---|
| 26 | Up to 12 | S, drive, pocket or bar slips, on 7'-0" center. | None. |
| 24 | 13 to 18 | S, drive, pocket or bar slips, on 7'-0" center. | None. |
| 24 | 19 to 30 | S, drive, 1" pocket or 1" bar slips on 7'-0" center. | 1 x 1 x 1/8" angles 4' from joint. |


CITY OF ALBUQUERQUE

This microimage is certified to be a complete and accurate copy of the original document as it appears in the files of the BUILDING INSPECTION DIVISION, and was microfilmed in the regular course of business. The photographic processes used meet the Basic Microfilm Standards of the National Micrographics Association (AIIM)(1-1977)

Mary Lou Cooper
CITY CLERK/RECORDER

CITY OF ALBUQUERQUE
THIS MICROIMAGE IS THE BEST POSSIBLE REPRODUCTION DUE TO THE POOR QUALITY OF THE ORIGINAL DOCUMENT

Mary Lou Cooper
MARY LOU COOPER
CITY CLERK/RECORDER


## PLUMBING FIXTURES SCHEDULE

| SYMBOL | DESCRIPTION |
|---|---|
| P-1 | WATER CLOSET: AMERICAN STANDARD "Cadet" Model 2122.059, siphon jet, close-coupled tank, standard Tank and Fittings, with CHURCH No. 5330.022 seat. 3" waste, 2" vent, ½" cw. |
| P-2 | LAVATORY: AMERICAN STANDARD "Declyn" Model No.0321.024 19" x 17", with Aquarian faucet, pop-up drain. Furnish speed riser supplies with stops, state app'd. trap (1¼" x 1½"). 1¼" p-trap, 1½" waste, 1½" vent, ½" cw & ½" hw. Furnish with mounting frame. |
| P-3 | LAVATORY: AMERICAN STANDARD "Scotion" Model 0360.024 with Aquarian faucet, pop-up drain, 20" x 18". Furnish speed riser supplies with stops, State Approved trap (1¼" x 1½"). 1¼" p-trap, 1½" waste, 1½" vent, ½" cw, ½" hw. Wall hanger, enameled cast iron. |
| P-4 | BATH TUB: ROBINSON & LAMY "Classic" - Integral Bath & Shower Unit with wall surround. 5 ft. length, reinforced fiberglass, plastic, no clg. Right or left outlet as required. Furnish with Symmons D-1-210-XK non-scald Tub & Shower safety mix unit, concealed mixing valve with integral stops, volume control S.B., Tub Spout & Shower head. Color to be white. ½" cw, ½" hw, 1½" vent, 1½" p-trap, 1½" waste, 14" APRON. |
| P-5 | KITCHEN SINK: AMERICAN STANDARD Model No. 7018.013 flat rim countertop sink, enameled cast iron, 4179.016 single lever faucet, 4331.013 crumb cup strainers. Furnish speed riser supplies with stops. State approved trap (1½" x 2"). ½" cw, ½" hw, 1½" vent, 2" waste. |

NOTE: This Contractor shall furnish and install all fixtures indicated on the drawings, with all required connections. Each fixture branch riser shall be taken off from the top of branch main, and an air-chamber 12" long (minimum) shall be located above each fixture branch, undiminished thus.




All branches shall be valved and all valves shall be accessible with access provided by this Contractor. All valves shall have unions adjacent.

## GRILLE & REGISTER SCHEDULE

| SYMBOL | DESCRIPTION |
|---|---|
| RG | RETURN GRILLE: ANEMOSTAT No. 53HD, steel construction, fixed horizontal fins spaced 3/4". Furnish with baked enamel prime coat finish. Actual sizes as noted on the drawings. |
| D-2 | SIDEWALL REGISTER: KRUEGER Series 800 , with vertical face bars individually adjustable & rear horizontal gang operated. . Actual sizes shall be as noted on the drawings. Furnish with opposed blade damper with slotted adjustment. |

## MISCELLANEOUS PLUMBING EQUIP. SCHEDULE

| SYMBOL | DESCRIPTION |
|---|---|
| CO | CLEANOUT: SMITH No. 4223, cast iron top, vandalproof screws, galvanized. (for outside installation). |
| WCO | WALL CLEAN-OUT: SMITH #4170, EXTRA HEAVY BRONZE PLUG |
| HWH-1 | WATER HEATER: Natural gas fired, orificed for operation at 5200 ft. elev., glass-lined tank. Furnish ASME combination T&P relief valve with full size type "K" copper relief drain. 100% safety pilot METALBESTOS type "B" flue. Furnish 5 year warranty. Nos. are NATIONAL. |

| SYMBOL | MODEL | S/L INPUT | STORAGE CA. | FLUE |
|---|---|---|---|---|
| HWH-1 | N30S-5R | 42,000 | 30 | 3"ϕ |

| | |
|---|---|
| WRB | WASHER ROUGH-IN BOX: CARUTH recessed water connector box with drain fitting and hose bibbs. Steel case with white finish, Model "A". |
| WH-1 | WALL HYDRANT: SMITH 5510, freezeproof bronze construction. |

## MECHANICAL EQUIPMENT SCHEDULE

| SYMBOL | DESCRIPTION |
|---|---|
| 1 | FURNACE: AGA approved, orificed for operation at 5300 ft. elevation, direct drive, forced air furnace, natural gas fired. Furnish with replaceable air filters and standard safety controls, including a 100% pilot safety, wall thermostat. LENNOX Model G1202-55, 55,000 BTUH SL furnace input, 750 cfm at .3" TSP, 120V-1ϕ-60~, 1/5 HP, ½" acoustic liner in fan compartment. |
| 2 | EVAPORATIVE COOLER: Side discharge, drip type unit, adjustable V-belt drive, pads, float valve, 120V-1ϕ pump, 20 ga. galv. sheet metal covers to close inlet louvers during winter, complete package unit, 2-speed, 2-winding fan motor. Models are ARCTIC CIRCLE. |

| SYMBOL | MODEL | CFM AT 3/8" SP (Hi SPD) | HP | MOTOR |
|---|---|---|---|---|
| 2 | 3023B-2 | 2500 | 1/4 | 120V-1ϕ-60~ |

| | |
|---|---|
| 3 | EXHAUST FAN: Recessed ceiling, installation, complete with inlet grille, backdraft damper, roofjack with birdscreen. DRUAN Model No. 555, 80 cfm, 120V-1ϕ-60~. |


CITY OF ALBUQUERQUE

This microimage of this document is certified to be an accurate copy of the original document as it appears in the files of the BUILDING AND INSPECTION DIVISION

Mary Lou Cooper, City Clerk/Recorder



CITY OF ALBUQUERQUE

| CLASS OF WORK | ADDRESS | NUMBER OF CARDS | DATE | DESCRIPTION |
|---|---|---|---|---|
| 3 | 615 ARNO N.E. | 5/6 | 11/13/80 | 1 BEDROOM DUPLEX |



ELECTRICAL SITE PLAN - ARNO SITE SCALE 1"=20'

ELECTRICAL SITE PLAN - ARNO SITE SCALE 1"=20'

PLAN NOTES

PLAN NOTES

(1) 2-UNIT METER/FUSE SERVICE EQPT. SEE RISER SCHEMATIC.
(1) 2-UNIT METER/FUSE SERVICE EQPT. SEE RISER SCHEMATIC.
2-APTS.
(2) 4-UNIT METER/FUSE SERVICE EQPT. SEE RISER SCHEMATIC.
(2) 4-UNIT METER/FUSE SERVICE EQPT. SEE RISER SCHEMATIC.
4 APTS. LOCATE OFF-CENTER TO AVOID CANALE.
(3) 5-UNIT METER/FUSE SERVICE EQPT. SEE RISER SCHEMATIC.
(3) 5-UNIT METER/FUSE SERVICE EQPT. SEE RISER SCHEMATIC.
ROOF TOP 100 AMPS LIGHTING PANEL. FUSE SITE LTG. SERVICE EQPT. @ 30 AMPS.
(4) INSTALL "U" FIXTURES ON FASCIA AT ROOF LINE.
(4) INSTALL "U" FIXTURES ON FASCIA AT ROOF LINE.
(5) RUN CONDUIT EXPOSED ON SHELTER FRAMING. ATTACH
(5) RUN CONDUIT WITH EACH 3/8" [illegible] FRAMING WASHER
FOR ATTACHMENT TO BOLT [illegible] BOLTS & LONDER WASHERS
IN ADDITION TO BOX MOUNTING SCREWS.
(6) 3-UNIT METER/FUSE SERVICE EQPT. SEE RISER SCHEMATIC.
(6) 3-UNIT METER/FUSE SERVICE EQPT. SEE RISER SCHEMATIC.
& 100 AMPS LIGHTING PANEL. FUSE SITE LTG. SERVICE
EQPT @ 30 AMPS.
(7) TELEPHONE TERMINAL BY TEL. CO. CONTRACTOR RUN TEL.
(7) TELEPHONE TERMINAL BY TEL. CO. CONTRACTOR RUN TEL.
TO SERVICE TERMINAL. TERMINAL BY TEL. CO.
(8) PROVIDE [illegible] TERMINAL. TELEPHONE COMPANY
(8) PROVIDE [illegible] UNDERGROUND DISTRIBUTION BY
(9) PROVIDE [illegible] FORMER & UNDERGROUND DISTRIBUTION BY
PUBLIC SERVICE CO.
(9) CONNECT LIGHT IN MAIL KIOSK.
(9) CONNECT LIGHT IN MAIL KIOSK.

CITY OF ALBUQUERQUE
CITY OF ALBUQUERQUE
This microimage is approximately a complete and usable reproduction of the original document. Unauthorized reproduction or distribution of this microimage is prohibited. If you have questions about this microimage, please contact the City Clerk's Office, Vital Records, 505-768-3000. National Microfilm Association Standards.
CITY CLERK'S OFFICE

ELECTRICAL SITE PLAN - COMANCHE SITE SCALE 1"=20'

ELECTRICAL SITE PLAN - COMANCHE SITE SCALE 1"=20'

CITY OF ALBUQUERQUE

| CLASS OF WORK | ADDRESS | NUMBER OF CARDS | DATE | DESCRIPTION |
|---|---|---|---|---|
| 3 | 615 ARNO N.E. | 6/6 | 11/13/80 | 1 BEDROOM DUPLEX |

CITY OF ALBUQUERQUE

615 ARNO

BUILDING & INSPECTION DIVISION

Address 615 ARNO NE
Owner BRADBURY & STAMM/C. OK SP/ALBUQ.
Contractor BRADBURY & STAMM Phone 765-1100
Architect or Engineer BARKER/FEL
Type Bldg. ☐ Comm. ☒ Res. ☐ New
Addition SCOTT TEMPLEHOF SCH Lot ROW Block SEE C3 OF PLANS
Type of Construction I, II, III, IV O ☐ 1-Hour, H.T.
Occupancy Group A, B, C, D, E, F, G, H, I O
Division 1, 2, 3, 4, 5 Fire Zone 1, 2, 0
Description of Bldg. 1 BR DUPLEX UNIT A - 4 BLDGS
House or Bldg. 1224 ~~1224~~ Sq. Ft. Garage ~~70~~ Sq. Ft.
Basement Sq. Ft. Porch Sq. Ft.
Remodel Cost 25,200 EA Construction Cost Sq. Ft.
Structural Mechanical
NOTE: These plans are not approved unless stamped and this permit is initialed by plan checker
PERMITTEE OR APPLICANTS PLANS TO BE ON JOB SITE AT ALL TIMES

2-BLDGS: 78.84
PERMIT FEE $39.42 EA
1314 EA.

APPROVED
Attn: Sign
Date
DEPT. TRAFFIC ENGINEERING
Albuquerque, New Mexico

NOV 14 1980

NOTICE TO CONTRACTOR
CONSTRUCTION HAZARDS SHALL BE PLACED AT LEAST 20 FEET AWAY FROM WORKING AREA

BE ADVISED
SANITARY FACILITIES MUST BE PROVIDED ON EACH CONSTRUCTION JOB.
C.O. ORDINANCE 7-10-5.

APPROVED FOR DRAINAGE
7 MAY 76
K.H. Lewis ACE Hyd

CONDITIONS

2-BLDGS: 80.40
PERMIT FEE $40.20
1340 EA

METER IS ESTIMATED

ADDRESS ISSUED FROM CITY ENGINEER'S OFFICE
ISSUED BY
DATE 5/4/76
BY

OFFICE of CITY ENGINEER
Set To
S. Lewis
In accordance with
COMMISSION ORDINANCE
#219-1977
Date 5/4/76 By

ALBUQUERQUE ENVIRONMENTAL SERVICES DEPARTMENT
TYPE OF FACILITY Apts.
NOT APPLICABLE APPROVED DISAPPROVED INITIAL/DATE
6-1-76 CONS. SAN.
WATER
COMMENTS: Control dust & debris during clearing & construction. Recommend that pebbles not be used on final surfaces as they get kicked out & cause many safety hazards in neighborhood.

ALBUQUERQUE COMPREHENSIVE ZONING ORDINANCE
Proposed Construction Complies With
Martineztown N.D.P.
OR in zone
ATLAS J-14
Z.A. Dorothy Nunnley
PLANNING DEPT.

REJECT
STRUCTURAL MECHANICAL
1. Specify int. beam hangers - Sht. A11 See note
2. 11 ste. rated party walls. "see note
3. 6/12 & extra. Unit A indecisive OK as is
4. Dig Bm too small, 70" min. Unit A OK as is
Rejected B Date 5/28
Approved Date 6/1
5. Ext. Bm Unit B window too small OK as is
6. D/Mat window Unit B too small OK as is
7. 2' min. Dia. f/ftg. clg. Unit B Sht. A2-12 OK as is
8. Clg. Lites Not To Code See note

REJECT - ZONING
Does Zoning Permit Use on Counter
Fill Out Reverse Side
Date 5/17
Approved Date 6/1/76

two Apts only
6-3-76

ALBUQUERQUE FIRE DEPARTMENT
FIRE INSPECTION BUREAU
724 SILVER, S.W. TEL. 843-9700
☐ APPROVED WITH THE FOLLOWING CONDITIONS
☒ CALL OUTSIDE FIRE PROTECTION EQUIPMENT
☐ DENIED
☒ DISAPPROVED
SIGNATURE CF
DATE 5-17-76

CITY OF ALBUQUERQUE
BUILDING & INSPECTION DIVISION
Address
Owner Phone
Contractor Phone
Architect or Engineer
Type Bldg. ☐ Comm. ☐ Res. ☐ New
Addition Lot Block
Type of Construction I, II, III, IV O ☐ 1-Hour, H.T.
Occupancy Group A, B, C, D, E, F, G, H, I O
Division 1, 2, 3, 4, 5 Fire Zone 1, 2, 0
Description of Bldg. 1 BR DUPLEX UNIT B - 2 BLDGS
House or Bldg. 1234 Sq. Ft. Porch 106 Sq. Ft.
Basement Sq. Ft. Garage Sq. Ft.
Remodel Cost 25,228 Construction Cost
Structural Mechanical
NOTE: These plans are not approved unless stamped and this permit is initialed by plan checker
PERMITTEE OR APPLICANTS PLANS TO BE ON JOB SITE AT ALL TIMES

CITY OF ALBUQUERQUE
The microimage of this document is certified to be an accurate copy of current as it appears in the files of the BUILDING AND INSPECTION DIVISION
MARY LOU COOPER
CITY CLERK/RECORDER

CITY OF ALBUQUERQUE
THIS MICROIMAGE IS THE BEST POSSIBLE REPRODUCTION DUE TO THE POOR QUALITY OF THE ORIGINAL DOCUMENT
MARY LOU COOPER
CITY CLERK/RECORDER

CITY OF ALBUQUERQUE
THIS MICROIMAGE IS THE BEST POSSIBLE REPRODUCTION DUE TO THE POOR QUALITY OF THE ORIGINAL DOCUMENT
MARY LOU COOPER
CITY CLERK/RECORDER

CITY OF ALBUQUERQUE
This microimage is certified to be a complete and accurate copy of the original document as it appears in the files of the BUILDING INSPECTION DIVISION, and was microfilmed in the regular course of business. The photographic processes used meet the Basic Requirements Standards of the National Micrographics Association (MS115-1977).
City Clerk/Recorder

ALBUQ. REFUSE SERVICE
REFUSE STORAGE FACILITIES
PLAN CHECKING SECTION
APPROVED ☐
APPROVED WITH BELOW LISTED CONDITIONS ☑
REJECTED AS PER BELOW LISTED CONDITIONS ☐
BY: DATE 6/2/76
REMARKS: As per attached letters

THE ACTUAL PRODUCER OF THE REFUSE WILL ASSUME THE PRINCIPLE RESPONSIBILITY FOR FURNISHING ADEQUATE FACILITIES AND ACCESS TO SAME AT ALL TIMES.

REFUSE STORAGE FACILITIES MUST HAVE UNOBSTRUCTED TRUCK DRIVE UP ACCESS AT ALL TIMES DUE TO POSSIBILITY OF NIGHT COLLECTION SERVICE.

## CITY OF ALBUQUERQUE

ALBUQUERQUE, NEW MEXICO

June 2, 1976

INTER-OFFICE CORRESPONDENCE

REF. NO.

TO: Don Peterson, Zoning Administrator

FROM: Gene Mares, Planner

SUBJECT: Martineztown Housing Project Parking Lot

The parking lot, containing 10 parking spaces, as shown on the revised site plan for the Public Housing Project, on the west side of Arno Street between Roma Avenue and Fruit Avenue, N.E., is acceptable. It is in compliance with the adopted Martineztown Neighborhood Development Plan.

GM:bg