CLASS OF WORK	ADDRESS	NUMBER OF CARDS	DATE	DESCRIPTION
2	615 ARNO NE	20/21	2/78	ELEC SITE



ELECTRICAL SITE PLAN - ARNO SITE SC: 1"=20'



ELECTRICAL SITE PLAN - COMANCHE SITE SCALE: 1"=20'

PLAN NOTES

1. 2-UNIT METER/FUSE SERVICE EQPT. SEE RISER SCHEMATIC. 2- APTS.
2. 4-UNIT METER/FUSE SERVICE EQPT. SEE RISER SCHEMATIC. 4 APTS. LOCATE OFFCENTER TO AVOID CANALE.
3. 5-UNIT METER/FUSE SERVICE EQPT. SEE RISER SCHEMATIC. 4 APTS PLUS SITE LIGHTING PANEL. FUSE SITE LTG SERVICE EQPT @ 30 AMPS.
4. INSTALL "U" FIXTURES ON FASCIA AT ROOF LINE.
5. RUN CONDUIT EXPOSED ON SHELTER FRAMING. ATTACH FIXT "M" WITH 2- 1/4" X 1 1/2" LAG BOLTS & FENDER WASHERS IN ADDITION TO BOX MOUNTING SCREWS.
6. 3-UNIT METER/FUSE SERVICE EQPT. SEE RISER SCHEMATIC. 2 APTS PLUS SITE LIGHTING PANEL. FUSE SITE LTG SERVICE EQPT @ 30 AMPS.
7. TELEPHONE TERMINAL BY TEL. CO. CONTRACTOR RUN TEL CONDUITS TO POINT TOWARD THIS TERMINAL. TELEPHONE COMPANY TO PREWIRE DWELLING UNITS FROM POINT (7)
8. PADMOUNT TRANSFORMER & UNDERGROUND DISTRIBUTION BY PUBLIC SERVICE CO.
9. CONNECT LIGHT IN MAIL KIOSK.

REVISED DATE: 4/12/76

DONALD S. FOWLER 2512 REGISTERED PROFESSIONAL ENGINEER

CITY OF ALBUQUERQUE

The attached document is certified to be an exact copy of the original on file in the Plans Examiner's Office, Building and Inspection Division

Donald S. Fowler, City Electrical Engineer

MAY 28 1976 BUILDING SECTION

BARKER·BOL & ASSOCIATES
ARCHITECTS
8308 B COMANCHE ROAD NE ALBUQUERQUE N MEX 87109

JOB NO. 7403
DATE: 2-16-76

LOCKWOOD MODERN CONSTRUCTION COMPANY

ELECTRICAL SITE PLAN
ARNO ST. & COMANCHE RD SITES

TURKEY HOUSING
PROJECT N.M. 1-11-4

E 4