CLASS OF WORK	ADDRESS	NUMBER OF CARDS	DATE	DESCRIPTION
2	615 ARNO NE	10/21	2/78	DOOR DET



WOOD TRIM: EXT. DOORS - A GRADE OR BETTER PINE OR HEMLOCK
INT. DOORS - D SELECT OR BETTER PINE

DOOR & WINDOW DETAILS SCALE - 3" = 1'-0"



SKYLITE 1½" = 1'-0" 12

ROOM FINISH SCHEDULE UNITS A° & B°

ROOM	FLOORS: CARPET	FLOORS: VINYL ASB.	FLOORS: EXP. CONC.	BASE: WOOD	BASE: VINYL	BASE: NONE	WALLS: ½ GYP. BD.	WALLS: ½ GYP. BD. 1/8" FIBERGLAS SHOWER	CLOS.: ½ GYP. BD.	CLOS.: ½ GYP. BD. 1/8" FIBERGLAS WITH 1/4" GYP. BD.	REMARKS
LIVING	●				●		●			●	
DINING		●			●		●			●	
KITCHEN		●			●		●			●	
HALL	●				●		●			●	
BEDROOM	●*				●		●			●	* CARPET @ CLOSET
BATH		●			●		●			●	
FURN & WH			●			●		●			
CLOSETS	* ●				●				●	●	* CARPET AT COAT CLOSET & DOOR #4
STORAGE		●			●		●			●	

ROOM FINISH SCHEDULE 2 & 3 BEDROOM TOWNHOUSE *

LIVING		●			●		●	●		
KITCHEN		●			●		●	●		
DINING		●			●		●	●		
OUTSIDE STOR.			●			●			●	
STORAGE *		●			●		●		●	* STORAGE UNDER STAIRS IN 2 BR. 3 HOUSE
STAIRS	●				●		●	●		
BEDROOMS	●				●		●	●		
CLOSETS	●				●		●	●		
BATH	●				●		●	●		
FURN & WH	●			●			●			

● GENERAL NOTE FOR UNITS A & B : USE 5/8" FIRECODE TYPE 'X' GYP. BD. ON ALL PARTY WALLS & BEARING PARTITIONS

* GENERAL NOTE FOR 2 & 3 BEDROOM TOWNHOUSES : 5/8" FIRECODE TYPE 'X' GYP. BD. ON ALL PARTY WALLS

DOOR SCHEDULE UNIT A

DOOR	SIZE	TYPE	TRESH.	REMARKS
1	3'-0" x 6'-8" x 1¾"	S.C. WOOD FLUSH PANEL	●	
2	2'-4" x 6'-8" x 1⅜"	H.C. WD. F.P.		
3	2'-8" x 6'-8" x 1¾"	S.C. WD. F.P.	●	
4	2'-8" x 6'-8" x 1⅛"	FULL SCREEN WOOD STILE		OFF SET HDWR.
5	6'-0" x 6'-8" x 1⅛"	H.C. WD. F.P. BI-FOLD		NO WOOD JAMBS
6	1'-6" x 6'-8" x 1⅜"	H.C. WD. F.P.		
7	2-3'-0" x 6'-8" x 1⅜"	H.C. WD. F.P.		BIPASS
8	2'-8" x 6'-8" x 1⅜"	H.C. WD. F.P.		
9	3'-0" x 5'-4" x 1⅜"	H.C. WD. F.P.		*FOR RA PLATFORM
10	2'-8" x 6'-8" x 1⅜"	H.C. WD. F.P.		

DOOR SCHEDULE UNITS B

1	3'-0" x 6'-8" x 1¾"	S.C. WOOD FLUSH PANEL	●	
2	2'-8" x 6'-8" x 1¾"	S.C. WD. F.P.	●	
3	2'-8" x 6'-8" x 1⅜"	FULL SCREEN WOOD STILE		OFF SET HDWR.
4	2'-4" x 6'-8" x 1⅜"	H.C. WD. F.P.		
5	1'-6" x 6'-8" x 1⅜"	H.C. WD. F.P.		
6	2'-0" x 6'-8" x 1⅜"	H.C. WD. F.P.		
7	2'-0" x 5'-4" x 1⅜"	H.C. WD. F.P.		
8	2'-8" x 6'-8" x 1⅜"	H.C. WD. F.P.		
9	2'-0" x 5'-4" x 1⅜"	H.C. WD. F.P.		
10	2'-8" x 6'-8" x 1⅜"	H.C. WD. F.P.		
11	2-2'-0" x 6'-8" x 1⅜"	H.C. WD. F.P.		BI-PASS
12 & 13	3'-0" x 6'-8" x 1⅛"	WD. FP. BI FOLD		NO WOOD TRIM

DOOR SCHEDULE TWO BEDROOM TOWNHOUSE

1	3'-0" x 6'-8" x 1¾"	S.C. WOOD FLUSH PANEL	●	W/ SCREEN DOOR
2	2'-0" x 6'-8" x 1⅜"	H.C. WD. F.P.		
3	2'-0" x 6'-8" x 1⅜"	H.C. WD. F.P.		CUT DOOR DOWN
4	6'-0" x 6'-8"	ALUM SLIDER W/ SCREEN		TEMP GLASS
5	3'-0" x 6'-0" x 1¾"	S.C. WD F.P.	●	
6	4'-0" x 6'-8" x 1⅜"	WD. F.P. BIFOLD		NO WOOD TRIM
7	2'-8" x 6'-8" x 1⅜"	H.C. WD. F.P.		
8	2'-8" x 6'-0" x 1⅜"	H.C. WD. F.P.		BI-PASS
9	1'-6" x 6'-8" x 1⅜"	H.C. WD. F.P.		
10	2'-0" x 6'-8" x 1⅜"	H.C. WD. F.P.		
11	2'-0" x 6'-8" x 1⅜"	H.C. WD. F.P.		W/GRILLE SEE MECH
12	2'-0" x 6'-8" x 1⅜"	H.C. WD. F.P.		W/GRILLE SEE MECH
13	2'-0" x 6'-8" x 1⅜"	H.C. WD. F.P.		W/GRILLE SEE MECH
14	2'-0" x 6'-8" x 1⅜"	H.C. WD. F.P.		CUT DOWN

DOOR SCHEDULE THREE BEDROOM TOWNHOUSE

DOOR	SIZE	TYPE	TRESH.	REMARKS
1	3'-0" x 6'-8" x 1¾"	S.C. WOOD F.P.	●	W/ SCREEN DOOR
2	2'-0" x 6'-8" x 1⅜"	H.C. WOOD F.P.		
3	2'-0" x 6'-8" x 1⅜"	H.C. WOOD F.P.		
4	8'-0" x 6'-8"	ALUM. SLIDER W/ SCREEN		
5	3'-0" x 6'-8" x 1⅜"	H.C. WOOD F.P.		
6	2'-0" x 6'-0" x 1¾"	S.C. WOOD F.P.	●	CUT DOWN
7	2'-0" x 6'-8" x 1⅜"	H.C. WOOD F.P.		
8	2'-8" x 6'-8" x 1⅜"	H.C. WOOD F.P.		BI-PASS
9	2'-6" x 6'-8" x 1⅜"	H.C. WOOD F.P.		
10	2'-6" x 6'-8" x 1⅜"	H.C. WOOD F.P.		
11	2-2'-0" x 6'-8" x 1⅜"	H.C. WOOD F.P.		BI-PASS
12	2'-0" x 6'-8" x 1⅜"	H.C. WOOD F.P.		
13	2'-0" x 6'-8" x 1⅜"	H.C. WOOD F.P.		
14	1'-6" x 6'-8" x 1⅜"	H.C. WOOD F.P.		
15	2'-6" x 6'-8" x 1⅜"	H.C. WOOD F.P.		
16	2'-6" x 6'-8" x 1⅜"	H.C. WOOD F.P.		W/GRILLE SEE MECH

NOTE: FOR DOOR HARDWARE SEE SPECIFICATIONS



GRAB-BAR @ ELDERLY UNITS (A&B) 1½" = 1'-0"



CABINET, BATH & INTERIOR ELEVATIONS SCALE 1'-0" = 3/8"
UNITS A & B

CITY OF ALBUQUERQUE
The microfilm of this document is certified to be an accurate copy of the original document as it appears in the records of the BUILDING AND INSPECTION DIVISION
City Microfilm Recorder
MAY 08 1978
BUILDING SECTION

REVISED DATE: 4/12/76

JOB NO. 74-05
DATE: 2-6-76

BARKER·BOL & ASSOCIATES
ARCHITECTS
[illegible] BERNALILLO COUNTY, NEW MEXICO [illegible]

LOCKWOOD MODERN CONSTRUCTION COMPANY

DOOR & WINDOW DTLS, DR & FINISH SCHED. - ALL UNITS: INT. ELEV. - A&B UNITS

TURKEY HOUSING
PROJECT N.M. 1-11-4

A 12