CLASS OF WORK	ADDRESS	NUMBER OF CARDS	DATE	DESCRIPTION
2	615 ARNO NE	6/21	2/78	FOUND & FRAME



FOUNDATION PLAN GROUP TYPE I (AA) 1/8"=1'-0"



FOUNDATION PLAN GROUP TYPE II (BB) 1/8"=1'-0"

NOTE:
SEE SITE PLANS FOR FLOOR SLAB & SIDEWALK ELEVATIONS & FOR ENTRY SLAB & SIDEWALK SLOPES —
SLOPE PATIO SLABS 1" AWAY FROM BLDG.

NOTE:
SEE SITE PLAN FOR SPECIFIC ENTRY SLAB LOCATIONS

CITY OF ALBUQUERQUE

ALBUQUERQUE, NEW MEXICO

June 2, 1976

REF. NO.

INTER-OFFICE CORRESPONDENCE

TO: Don Peterson, Zoning Administrator

FROM: Gene Mares, Planner

SUBJECT: Martineztown Housing Project Parking Lot

The parking lot, containing 10 parking spaces, as shown on the revised site plan for the Public Housing Project, on the west side of Arno Street between Roma Avenue and Fruit Avenue, N.E., is acceptable. It is in compliance with the adopted Martineztown Neighborhood Development Plan.

GM:bg



ROOF FRAMING PLAN GROUP TYPE I (AA) 1/8"=1'-0"



ROOF FRAMING PLAN GROUP TYPE II (BB) 1/8"=1'-0"

GENERAL FRAMING NOTES

1. PROVIDE: 1/2" x 4' x 8' PLYWOOD SHEETS FOR CORNER BRACING OR EQUAL AS REQUIRED BY UNIFORM BUILDING CODE OR M.P.S.
2. LINTEL SCHEDULE: (LOAD BEARING WALLS)
   2 - 2x8 OPENINGS TO 5'
   2 - 2x10 OPENINGS 5' TO 8'
   2 - 2x12 OPENINGS 8' TO 12'

   OTHER OPENINGS NOTED ON PLAN. THESE LINTELS ARE FOR OPENINGS IN BEARING WALLS & WALLS PERPENDICULAR TO JOISTS.
3. F.B. = FLUSH BEAM, HANG JOISTS WITH STEEL JOIST HANGERS
4. WOOD STRESS VALUES:
   JOISTS: 1300
   BEAMS: 1500
5. ROOF VENTS: SEE DETAIL RV SHEET 4
   2 VENTS PER UNIT

MAY 28 1976
BUILDING DIVISION

REVISED DATE: 4/12/76

JOB NO. 74-05
DATE: 2-16-76

BARKER·BOL & ASSOCIATES
ARCHITECTS

LOCKWOOD MODERN CONSTRUCTION COMPANY

FOUNDATION & FRAMING PLANS
ARNO STREET SITE

TURNKEY HOUSING
PROJECT N.M. 1-11-A

A 5