2	615 ARNO NE	15/21	2/78	PLUMB
CLASS OF WORK	ADDRESS	NUMBER OF CARDS	DATE	DESCRIPTION



SOIL, WASTE, & VENT & GAS - TYPICAL AA & BB UNITS

SCALE: 1/4" = 1'-0"



SOIL, WASTE, & VENT & GAS - TYPICAL BB UNITS

SCALE: 1/4" = 1'-0"

NOTES:

1. See Vent Thru Roof Detail, in specifications.
2. Vent Line in wall. Support from wall studs.
3. Washer rough-in box - washer installation by Owner.
4. Drop down in wall with waste line.
5. Rise up in wall with vent line.
6. See Utilities Plans for continuation.
7. Install Gas Regulator and meter sized for 300 cfh (for duplex) or 600 cfh (for 4 plex.) with 6 ounce, leaving and 2 psig ± entering pressure. Regulator shall contain auto shutoff and internal relief. Install gas cock and union on entering side of regulator and 1" capped inspection tee on leaving side. Complete the above per Southern Union Gas Co. requirements and Local Code.
8. Route Gas Piping on roof. Support from 4" x 4" x 6" long redwood blocks on roof. Spaced 10'-0" on center.
9. Drop down into Furnace Room with ¾" gas line.
10. Connect Furnace with ¾" line. Install gas cock and union at each unit.
11. Install bath tub piping access door 20" x 20" min.
12. Connect hot water heater with ½" line. Install gas cock & union at unit.



NOTE: The units are arranged with varying common walls. See Utilities Plans for unit arrangements. Some units are arranged for opposite-hand piping, see Utilities Site Plans.

SOIL, WASTE, & VENT RISER - TYPICAL AA-BB UNITS

NOT TO SCALE



SOIL, WASTE, & VENT RISER - TYPICAL BB UNITS

NOT TO SCALE

The reproduction of this document is restricted to be an accurate copy of the original document as it appears in the files of the CITY OF ALBUQUERQUE BUILDING AND INSPECTION DIVISION

Mary Kay Cooper, City Clerk/Recorder

MAY 28 1976 BUILDING SECTION

PROFESSIONAL ENGINEER NEW MEXICO 3845

REVISED DATE: 4/13/76

JOB NO. 74-09

DATE: 2-6-76

BARKER·BOL & ASSOCIATES
ARCHITECTS ENGINEERS CITIES
2404 EAST MATTED 18 N.E. ALBUQUERQUE, N.M. 87106 Tele. 266-5

LOCKWOOD MODERN CONSTRUCTION COMPANY

PLUMBING PLANS & RISERS
ARNO ST. & COMANCHE RD SITES

TURNKEY HOUSING
PROJECT N.M. 1-11-A

M 7

8.5" 11" 17" 22"