

ADDENDUM # 2

Date: October 9, 2017
To: Construction Documents, Dated 09.27.17
Project: NLRHA Silver City & Eastgate Demolition Package
North Little Rock, Arkansas

Attachments: Cover Sheet (1 page), Addendum #1 Description (1 pages), Section 004000 BID FORM (4 pages) **(6 pages total)**

Drawings: None at this time

This addendum and the attachments listed above, issued prior to bidding, alters, amends, corrects, or clarifies the Proposal Documents to the extent stated herein and does thereby become a part of the Proposal Documents and will become part of the Contract Documents of the successful bidder(s).

1. GENERAL CLARIFICATION:

- a. General Contractor can use a concrete and rock crusher for the demolition work to reduce off-site hauling and demolition backfill if determined will save overall cost for the project.
- b. Just to clarify: The sewer lines can be capped off at the utility easement (not at each individual building).

2. Project Manual:

- a. **DELETE** Section 004000 BID FORM from the project manual. **ADD** attached revised Section 004000 BID FORM to the project manual.
- b. Refer to Project Manual Section 024116 STRUCTURE DEMOLITION 3.5 BACKFILLING OPERATION B & C. , **CHANGE** and **REVISE** as follows:
 - B. The final one foot (1') below finish grade shall have the following fill replacement (where buildings/foundation walls were removed): Clayey sand or silty sand, sandy clay, or clayey gravel. Contractor shall furnish additional gravel material should adequate on-site approved material not be available.
 - C. Contractor shall cover only the disturbed areas on both sites (Silver City/Eastgate) with a min. 2" of approved topsoil. Site shall be seeded and mulched with an "anchored" type mulch. Contractor shall be responsible for watering until turf is established.

END OF ADDENDUM NUMBER TWO