FINISH SCHEDULE

ROOM FINISHES

ROOM NO.	ROOM NAME	CEILING HEIGHT	FLOOR: F-1 VINYL ASBESTOS TILE	F-2 VINYL ASBESTOS TILE	F-3 CERAMIC TILE	F-4 CERAMIC TILE	F-5 CERAMIC MOSAIC TILE	F-6 QUARRY TILE	F-7 CARPET /CARPET @ STAIRWAYS	F-8 SHEET VINYL	BASE: B-1 VINYL COVE BASE, 4"	B-2 RUBBER BASE - TOP SET	B-3 RUBBER BASE, CARPET NOTE 1.	B-4 WOOD BASE	B-5 RED OAK BASE	B-6 CERAMIC TILE BASE	B-7 CERAMIC TILE BASE	B-8 QUARRY TILE	WALL: P-1 PAINT	P-2 "	P-3 "	P-4 "	P-5 "	WP-1 WALL PANELING	WP-2 "	WP-3 "	WP-4 "	WP-5 "	WP-6 "	WP-7 "	VC-1 VINYL WALL COVERING	VC-2 "	VC-3 "	VC-4 "	CEILING: CT-1 CERAMIC TILE NOTE 15	CT-2 CERAMIC TILE	CT-3 CERAMIC MOSAIC TILE	2'x4' LAY IN, ARMSTRONG TILE (NOTE 2)	GYP. BD. W/ TEXTURED FIN.	GYP. BD. " 4" PANEL'G.	GYP. BD. w/ STUCCO FIN. TO MARCH EXT.	GYP. BD. TAPE ONLY	MISC.: PL-1 PLASTIC LAMINATE	PL-2 "	PL-3 "	H-1 HARDBOARD NOTE 4	D-1 1" MINI BLINDS	DRAPE BLIND: NO JOB FINISH.
101	LOBBY	VAR.							●	●									●																●	●									●	
102	MED. CONFERENCE	9'-0"							●	●				●																				●	●									●	
103 +	RESTROOM	8'-0"						●								●			●																●										●	
104	PRIVATE OFF.	9'-0"							●	●				●																				●	●									●	
105	"	"							●	●				●																				●	●									●	
106	"	"							●	●				●																				●	●									●	
107	"	"							●	●				●																				●	●									●	
108	"	"							●	●				●																				●	●									●	
109	"	"							●	●				●																				●	●									●	
110	"	"							●	●				●																				●	●									●	
111	"	"							●	●				●																				●	●									●	
112 +	PARA LEGAL	"										●																						●	●										
113	LOUNGE	VAR.	●									●																						●	●									●	
114	KITCHEN	8'-6"	●									●																						●	●									●	
115	ELEC./TELE.	9'-0"																																												
116	STORAGE	9'-0"	●									●																						●	●										
117	STORAGE	8'-0"																																											
118 +	STAIRS	VAR.							●	●		●																						●	●									●	
119 +	PRIVATE OFF.	9'-0"							●	●		●																						●	●									●	
120	"	"							●	●		●																						●	●									●	
121	"	"							●	●		●																						●	●									●	
122	"	"							●	●		●																						●	●									●	
123	G.M. PARK	"							●	●		●																						●	●									●	
124	M. WILHELM	"							●	●		●																						●	●									●	
125	"	"							●	●		●																						●	●									●	
126	S.R. RAU	"							●	●		●																						●	●									●	
127	PRIVATE OFF.	"							●	●		●																						●	●									●	
128	SM. CONFERENCE	"							●	●		●																						●	●									●	
129	RECEPTION	"							●	●		●																						●	●									●	
130 +	SECRETARIAL	"							●	●		●																						●	●									●	
131 +	"	"							●	●		●																						●	●									●	
132 +	MENS' RESTROOM	8'-0"		●												●			●																●										●	
133 +	JANITOR	8'-0"						●											●																●										●	
134 +	WOMENS' R.R.	8'-0"		●												●			●																●										●	
135 +	SECRETARIAL	9'-0"							●	●		●																						●	●									●	
136 +	"	9'-0"							●	●		●																						●	●									●	
137 +	STAIRS	VAR.							●	●		●																						●	●									●	
138	EQUIPMNT.	8'-0"																																												
139	STORAGE	8'-0"	●																																											
140 +	WORD PROCESS.	9'-0"							●	●		●																						●	●									●	

FINISH LIST

FLOOR COVERINGS

F-1 VINYL ASBESTOS TILE
KENTILE, MARBELIZED
#T951, 3/32" TH
BUCKSKIN

F-2 VINYL ASBESTOS TILE
KENTILE, HALOVER GLATE
#1053, 1/8" TH
HANOVER BLUE

F-3 CERAMIC TILE 6"x6"
FRANCICAN, TERRA GRANDE
#63
BUFF

F-4 CERAMIC TILE, 3"x6"
FRANCICAN, TERRA GRANDE
#60
DUSK

F-5 CERAMIC MOSAIC, 2"x2"
AMERICAN OLEAN
BEACH TAN.

F-6 QUARRY TILE, 4"x8"
GAIL CERAMICS
UNGLAZED PAVERS
4"x8", FAWN.

F-7 CARPET
PHILADELPHIA CARPETS
"TOP BRASS" #
COLOR TO FOLLOW

F-8 SHEET VINYL
ARMSTRONG, VINYL CORLON
"SANDOVAL"
#B6662.

F-7A CARPET @ STAIRWAYS
STRATTON "MERIT" SERIES
VALIANT
COLOR TO FOLLOW.

BASE

B-1 VINYL COVE BASE, 4"
ARMSTRONG, VINYL CORLON
"SANDOVAL"
#B6662.

B-2 RUBBER BASE
ROPPE
4" H, TOPSET
#70, WHITE

B-3 RUBBER BASE
ROPPE
4" H, CARPET BASE
#70, WHITE.

B-4 WOOD BASE
1/2" x 3 1/4" BIRCH
PRE-FINISHED
SEE NOTE 9.

B-5 WOOD BASE
9/16" x 5 1/4" RED OAK
W.M.# G18
STAIN TO MATCH PANELS

B-6 CERAMIC TILE, 3"x6"
FRANCICAN, TERRA GRANDE
TO MATCH WALLS
#60 OR #63, (2) COURSES

B-7 CERAMIC MOSAIC, 2"x2"
AMERICAN, OLEAN
BEACHTAN
6", (3) COURSES.

B-8 QUARRY TILE
GAIL CERAMICS
UNGLAZED PAVER
4"x8", FAWN.

WALL COVERINGS

P-1 PAINT
PRATT & LAMBERT
#V 358 W
SNOFLAKE

P-2 PAINT
AMERITONE
#2880
FAWN

P-3 PAINT
AMERITONE
#291 H WISTFUL BEIGE
WISTFUL BEIGE

P-4 PAINT
AMERITONE
#287 C
COPPER BROWN.

P-5 PAINT
PRATT & LAMBERT
#B754A
SYMPHONY BLUE

WP-1 WALL PANELING
WEYERHAUSER, PRE FIN
"FORESTGLO" SERIES
GREEN BRIAR HICKORY

WP-2 WALL PANELING
WEYERHAUSER, PRE FIN
"FORESTGLO" SERIES
DEL MONTE OAK

WP-3 WALL PANELING
WEYERHAUSER, PRE FIN
"FORESTGLO" SERIES
KASHMIR CHERRY

WP-4 WALL PANELING
GEORGIA-PACIFIC, PRE FIN.
"FIRELIGHT" SERIES
CORDAL WALNUT

WP-5 WALL PANELING
GEORGIA-PACIFIC, PRE FIN.
"FIRELIGHT" SERIES
FORUM OAK

WP-6 WALL PANELING
GEORGIA PACIFIC, PRE FIN.
"RENAISSANCE" SERIES
BARCELONA

WP-7 WALL-PANELING
1/4" PLYWOOD
VENEER: RED OAK.

VC-1 VINYL WALL COVERING
GUARD
"EL PRADO", TYPE I
#61361, MISTY CREAM

VC-2 VINYL WALL COVERING
GUARD
"BALIKARTA" TYPE I
#G1601,

VC-3 VINYL WALL COVERING
GUARD
"GUNNY" TYPE I
G1521, CHAMPAGNE

VC-4 VINYL WALL COVERING
GENON
"LEGEND" TYPE I
#CC 0205, STRING

CT-1 CERAMIC TILE
CERAMIC TILE
CERAMIC MOSAIC TILE
2'x4' LAY IN, ARMSTRONG TILE (NOTE 2)
GYP. BD. W/ TEXTURED FIN.
GYP. BD. " 4" PANEL'G.
GYP. BD. w/ STUCCO FIN. TO MARCH EXT.
GYP. BD. TAPE ONLY

CT-1 CERAMIC TILE, 3"x6"
FRANCICAN, TERRA GRANDE
#63
BUFF

CT-2 CERAMIC TILE, 3"x6"
FRANCICAN, TERRA GRANDE
#60
DUSK

CT-3 CERAMIC MOSAIC 2"x2"
AMERICAN OLEAN
BEACH TAN.

CEILING

C-1 CEILING TILES
ARMSTRONG, 2'x4'
GEOLOGIC LOOK III
WHITE

MISC. FINISHES

D-1 BLINDS, 1" MINI
LEVELOR "RIVIERA"
#8813, SATIN FIN.
DK. BRONZE.

PL-1 PLASTIC LAMINATE
FORMICA
#-913
INDIAN SMOKE

PL-2 PLASTIC LAMINATE
FORMICA #
#-919
DESERT BEIGE

PL-3 PLASTIC LAMINATE
WILSON ART
#1972
ANTIQUE WHITE

H-1 HARDBOARD
MARLITE
(1/8") H.P.L. FINISH
WHITE ONYX

* - SEE NOTE 7.) and 12.)



GENERAL NOTES

1) SEE FINISH LIST (THIS SHT.) FOR SPECIFIC COLORS, MATERIALS and MANUFACTURER OF INT. FINISH
2) SEE SHTS A-6, 17, 18 FOR SPECIFIC LOCATION OF EACH FINISH
3) T BAR SYSTEM TO BE FACTORY FINISHED LOW TEXTURE WHITE, LAY-IN CLG SYSTEM. SEE REFLECTED CLG. PLAN FOR GRID PATTERN.
4) USE 4'-0" H. PRE-FINISHED HRDBD WAINSCOT AT JANITOR. RM. EA. FLR. (SEE FINISH PLAN FOR SPECIFIC LOCATION.) TRIM EDGE W/ SATIN ALUM. BINDING EDGE (9' W.P. GYP.)
5) CERAMIC TILE WAINSCOT HEIGHT AS INDICATED ON INTERIOR ELEVATIONS SHT A-22. ALL TILE 9' W.P. GYP.
6) INTERIOR WALLS W/ ONE COAT LATEX W/ THE EXCEPTION OF ALL RESTRMS, JANITOR RMS, COFFEE BARS (2 EA. FLR.) AND KITCHEN, WHICH RECEIVE TWO COATS SEMI-GLOSS & P.V.A. SEALER.
*7) (T) WHEN FINISH SYMBOL ACCOMPANIED W/ THE LETTER "T" CONTRACTOR TO ADD 1x4 BIRCH TRIM @ CLG. SEE DTL 13, SHT A-23. WHEN TRIM OCCURS W/ VINYL W.C. OR PAINT, STAIN TO MATCH PRE FINISH INT. DOOR. IF TRIM OCCURS W/ PRE FIN. PANELING STAIN TO MATCH PANEL'G.
8) WHEN PRE FINISHED PANEL'G INSTALLED CONTRACTOR TO INSTALL 1x4 BIRCH TRIM, CHAIR RAIL (SEE DTL'S FOR HGT.) TRIM TO BE STAINED TO MATCH PANEL'G
9) ALL WOOD BASES TO BE STAINED TO MATCH PANELS IT OCCURS W/ IF INDICATED W/ VINYL OR PAINT STAIN TO MATCH PRE FIN. INT DOORS, W/ THE EXCEPTION OF THE LOUNGE, KITCH WILL HAVE A WOOD BASE PAINTED TO MATCH WALLS.
10) ALL CARPET TO BE INSTALLED W/ PADDING (SEE SPECIFICATIONS) W/ THE EXCEPTION OF THE STAIRWAYS AND LANDINGS WHICH WILL BE DIRECTLY GLUE-DOWN. WRAP STAIRS.
11) CARPET @ STAIR TREADS TO BE EDGE BOUND ON BOTH SIDES TO COVER and PROTECT EXPOSED EDGE.
* 12) (W) WHEN FINISH SYMBOL ACCOMPANIED W/ THE LETTER "W" THAT FINISH IS TO BE INSTALLED AS WAINSCOT W/ 1x4 BIRCH CHAIR RAIL. RAIL STAINED TO MATCH PANEL'G OR IF OCCURS W/ VINYL OR PAINT STAINED TO MATCH PRE FINISH DOOR.
13) FINISH MAT. SUPPLIED and INSTALLED BY OCCUPANT. REQUIRE CONTRACTOR TO PROVIDE WALLS PREPARED TO RECIEVE WALL COVERING and FLRS. PREPARED TO RECIEVE WOOD FLOORING. (PARQUET OR PLANK.)

FINISH LEGEND

- ▭ : RM. NO.
- ▢ : FLOOR COVERING; CARPET, V.A.T., TILE, ETC.
- ⬡ : WALL COVERING; VINYL, PAINT, PANELS, TILE, ETC.
- (T) : WALL COVERING W/ TRIM @ CLG. SEE NOTE 7.)
- ◯ : MISCELLANEOUS FINISHES, PLAS. LAM., BLINDS, HARDBOARD, ETC.
- – – – : UNLESS NOTED OTHERWISE INDICATES FLOOR FINISH CHG.
  : AT WINDOWS INDICATES BLINDS.
- (W) : WALL COVERING TO BE INSTALL AS WAINSCOTT, W/ 1x4 BIRCH CHAIR RAIL.
- \+ : RM. FINISH REMAINS THE SAME ON 1ST, 2ND and 3RD FLR. SEE FIRST FLR. FINISH PLAN FOR DESIGNATION.

FINISH FLOOR PLAN
FIRST FLOOR PLAN THE LAW CENTER

Thompson Architectural Group, Inc.
1177 W Shaw Avenue Fresno, California 93711 (209) 225-3232

Karren Douglas, Trainee A.I.A.
California 05242

No. Issue Rev. Date

Project Coordinator CBN
Project No. 81099
Date 4.28.82
Scale 1/8" = 1'-0"

Sheet No. 17
A-16
of 49

#81099