

ADDENDUM # 2

Date: July 15, 2020
To: Construction Documents, Dated 06.16.20
Project: NLRHA Silver City Demolition Package
North Little Rock, Arkansas

Attachments: Addendum #2 Description (1 pages) **(1 pages total)**

Drawings: S3 Silver City Survey (24 x 36) **(1 sheet total)**

This addendum and the attachments listed above, issued prior to bidding, alters, amends, corrects, or clarifies the Proposal Documents to the extent stated herein and does thereby become a part of the Proposal Documents and will become part of the Contract Documents of the successful bidder(s).

1. GENERAL CLARIFICATION:

- a. See attached sheet S3 Silver City Survey sheet for reference:
 1. Additional sewer line removal clarification: The sewer lines running off 20th street does not need to be disturb since it's connecting to surrounding neighborhood.
 2. Water lines from existing buildings to be capped off at street.
 3. Demolition Contractor to coordinate capping off the Gas lines from existing buildings with Centerpoint Entergy.
 4. Demolition Contactor to coordinate capping off the Electricity from existing buildings with North Little Rock Electric Department.
- b. Backfill to be compacted at 95% of Modified Proctor Dry Density (ASTM 1557) for all compacted fill that will be filling in the holes at the existing buildings.

2. PROJECT MANUAL:

- a. Refer to Project Manual Section 024116 STRUCTURE DEMOLITION 3.5 BACKFILLING OPERATION B & C. , **CHANGE** and **REVISE** as follows:
 - B. The final one foot (1') below finish grade shall have the following fill replacement (where buildings/foundation walls were removed): Clayey sand or silty sand, sandy clay, or clayey gravel. Contractor shall furnish additional compacted fill dirt material should adequate on-site approved material not be available. Regrade to drain properly.
 - C. Contractor shall cover only the **disturbed areas** at Silver City with a min. 2" of approved compactable fill dirt. Site **"SHALL NOT"** be seeded and mulched with an "anchored" type mulch.

END OF ADDENDUM NUMBER TWO