



CLARIFICATION LETTER #1

DATE: 5/05/21

ISSUED BY: Miguel A. Hernandez, CFP Coordinator

QSP - SECURITY SYSTEM INSTALLATION AT PATTERSON PAVILION

Please acknowledge the following clarifications by signing this form and send by email or fax: vrodriguez@hialeahhousing.org or by fax 305-887-0997:

- 1. Should the contractor do patching?
 - Yes, the contractor it is responsible to put a patch panel and do the patching of the devices.

Contractor IT Hardware Requirements

- 2. Re-Terminate Cat5e to 48 port Cat5e patch panel where applicable (How many?)
 - If there are existing Cat5e that are in perfect condition to be re-used, they need to be re-terminated and patched as many as the number of cameras are going to be used.
- 3. The new system should be Capable of future integration of Central Management System (Central Management System Brand ? Will handle Access Control and CCTV?)
 - No prefer brand. We are open to suggestions and options as per your experience in the area.
- 4. The Housing Authority some prior systems install Hikvision's and older ExacqVision
 - 1. HikVision does not comply with Made in America, and it's banned from some government institutions. Will you accept Solutions under HikVision?
 - We are open for different solutions as your experience with the System Management software.
 - 2. Cameras preferred brand? e.g Axis, Pelco etc.
 - There is no prefer brand. We need outdoor cameras with a minimum resolution of 5mp, indoor with a minimum resolution of 2mp, vandal proof, IR for night/dark vision, motion detector. Video compression H.264 or better
 - 3. Management Software preferred brand: e.g Milestone Sys , Axis etc.
 - No preferred brand. We are open to your experience on the field.
- 5. Purchase, install and configure XX (# of cameras to be determined at site meeting) cameras of power over Ethernet (PoE) fixed network cameras selected at the site walkthrough.
 - 1. All cameras have to be POE. Do you have this number already? The number of NVR´s are closely attached to the XX number.
 - Building A – Total of 22 Cameras (8 Exterior & 14 Interior)
 - Building B – Total of 25 Cameras (8 Exterior & 17 Interior)

EXCEPT AS PROVIDED HEREIN, ALL TERMS AND CONDITIONS OF THE SOLICITATION REMAIN UNCHANGED AND IN FULL FORCE AND EFFECT.

ACKNOWLEDGEMENT OF RECEIPT
DATE:

COMPANY NAME:

NAME:

TITLE: