



CATCH BASIN DETAIL
EXISTING TO BE REUSED N.T.S.



SILT FENCE DETAIL
N.T.S.

- 1- FABRIC SHALL CONSIST OF WOVEN POLYPROPYLENE, 36" IN WIDTH AND FASTENED TO HARDWOOD POSTS WITH THREE, ONE INCH WIDE CROWN STAPLES.
- 2- POST SHALL BE OF SOUND HARDWOOD, 48" IN LENGTH WITH MINIMUM CROSS SECTION OS 1.125 sq-in. .SOFTWOOD POST SHALL BE USED.
- 3- POST SHALL BE POSITIONED VERTICALLY AT A DISTANCE NOT TO EXCEED 10'-0" ON CENTER FOR THE ENTIRE LENGTH OF THE SILT FENCE.
- 4- SOIL SHALL BE TRENCHED TO 6" OF THE SILT FENCE FABRIC TO FALL BELOW GRADE. POSTS SHALL BE DRIVE A MINIMUM OF 18" BELOW NATURAL GRADE TO ALLOW 6" OF MATERIAL TO EXTEND INTO TRENCH. TRENCH SHALL BE BACKFILLED TO ORIGINAL GRADE, LEAVING A MINIMUM OF 6" OF FABRIC BELOW FINISH GRADE. IF THE SILT FENCE IS INSTALLED ON A SLOPE, THE POSTS SHALL BE POSITIONED ON THE DOWNWARD SIDE. IF THE SILT FENCE IS INSTALLED ON A LEVEL SITE, THE POSTS SHALL BE INSTALLED TO THE OUTSIDE OF THE EXCAVATED AREA.
- 5- CONNECTION/JOINING OF SILT FENCES SHALL BE COMPLETED BY TIGHTLY OVERLAPPING THE ENDS OF THE ROLLS A MINIMUM OF 12" OR BY OVERLAPPING THE END POSTS AND SECURING THE THE TWO POSTS TOGETHER TIGHTLY WITH PLASTIC WIRE TIES AND/OR STEEL BAILING WIRE.




Copyright 2019 V3 Architectural Group, Inc.
All rights reserved. These drawings and specifications are instruments of service and shall remain the property of V3 Architectural Group, Inc. whether the product for which they were prepared is installed or not. They are not to be used for any other project or extension to the project except by agreement in writing and with appropriate compensation to V3 Architectural Group, Inc. Reproduction or distribution of these drawings without the written consent of V3 Architectural Group, Inc. is prohibited.

**HIALEAH HOUSING AUTHORITY
STORAGE BLDG. ADDITION AND ALTERATIONS
815 WEST 75TH ST
HIALEAH, FLORIDA 33014**

DATE:	01.08.21
DESIGNED BY:	DLC
DRAWN BY:	DLC
REVIEWED BY:	MDF
PROJECT NO.:	20-0032
REVISIONS	

B.D.C. (DERM) 05-03-21



CMBeng
Consulting • Design
CMB eng llc.
14850 SW 26 St. #215 • Miami, Florida 33185
O. 786.375.5348 • CMB@CMBeng.com

SITE DRAINAGE PLAN

SD 1.0
CONSTRUCTION DOCUMENT

Project No.: 21_0044